DOE/EIA-0208(2013-50)
Distribution Category UC-98

Data for Week Ended:
December 13, 2013

Weekly Petroleum Status Report



www.eia.doe.gov
Energy Information Administration

EIA DATA ARE AVAILABLE IN ELECTRONIC FORM

The tables in the *Weekly Petroleum Status Report* (WPSR) are posted to the web site after 10:30 a.m. Eastern Standard Time (EST) on Wednesdays in CSV and XLS formats. PDF files are posted to the web site after 1:00 p.m. on Wednesdays. For some weeks that include holidays, posting is delayed by one day.

WPSR customers may also want to take a look at EIA's This Week in Petroleum (TWIP) web site (http://www.eia.gov/oog/info/twip/twip.asp) which provides current market analysis and data for crude oil and major petroleum products. It is generally available at 1:00 p.m. EST on Wednesdays.

All current EIA publications are available on the EIA web site. Users can view and download selected pages or entire reports, search for information, download EIA data and analysis applications, and find out about new EIA information products and services:

World Wide Web: http://www.eia.gov/
FTP: ftp://ftp.eia.doe.gov

EIA also offers a listserv service for EIA press releases and other short documents. This service is also used to notify customers of new data and analysis products, changes to current products, and other news of interest. Sign up for one or more listservs by doing the following:

Logon to www.eia.gov
On the left sidebar click on "Sign up for email Updates"
Simply follow the prompts

For further information, and for answers to questions on energy statistics, please contact EIA's National Energy Information Center at:

National Energy Information Center (NEIC)
EI-30, Forrestal Building
Washington, DC 20585
(202) 586-8800 (phone)
(202) 586-0727 (fax)
9:00 a.m. to 4:00 p.m., Eastern Time, M-F
E-mail: infoctr@eia.doe.gov

Release Date: December 18, 2013

This report was prepared by the Energy Information Administration, the independent statistical and analytical agency within the U.S. Department of Energy. The information contained herein should be attributed to the Energy Information Administration and should not be construed as advocating or reflecting any policy position of the Department of Energy or any other organization.

Preface

The Weekly Petroleum Status Report (WPSR) provides timely information on supply and selected prices of crude oil and principal petroleum products. It provides the industry, press, planners, policymakers, consumers, analysts, and State and local governments with a ready, reliable source of current information.

Petroleum supply data presented in the *WPSR* describe supply and disposition of crude oil and petroleum products in the United States and major U.S. regions called Petroleum Administration for Defense (PAD) Districts. Geographic coverage in the *WPSR* includes the 50 States and District of Columbia. U.S. territories are treated as import sources but are otherwise excluded from weekly petroleum supply statistics. Petroleum supply data include field production, imports and exports, inputs and production at refineries and blending terminals, production from gas processing plants and fractionators, and inventories at refineries, terminals, pipelines, and fractionators. Crude oil inventories include Alaskan crude oil in transit by water. Aggregated weekly petroleum supply statistics are used for calculation of products supplied, which is an approximation of U.S. petroleum demand.

The supply data contained in this report are based primarily on company submissions for the week ending 7:00 a.m. the preceding Friday. Selected data are released electronically after 10:30 a.m. Eastern Standard Time (EST) each Wednesday.

Price data presented in the *WPSR* include world crude oil contract prices, spot prices of crude oil and major products in major U.S. and world markets, futures prices of crude oil and major products on the New York Mercantile Exchange (NYMEX), and retail prices of gasoline and on-highway diesel fuel. During the heating season, wholesale and retail prices of propane and residential heating oil are also provided. Collectively, these price series provide a comprehensive and timely view of current U.S. and world prices of crude oil and major petroleum products.

Weekly price data are collected as of 8:00 a.m. every Monday. Weekly retail gasoline and on-highway diesel prices are first available around 5:00 p.m. EST on Monday (Tuesday when Monday is a Federal holiday). Wholesale and retail propane and residential heating oil prices are released electronically after 10:30 a.m. EST each Wednesday during the heating season (October through mid-March). The daily spot and futures prices are provided by Reuters, Inc.

This report is available on the World Wide Web at:

http://www.eia.gov/petroleum/supply/weekly/

Contents

Highlights v

Tables
1. U.S. Petroleum Balance Sheet, Week Ending 12/13/13 1
2. U.S. Inputs and Production by PAD District 2
3. Refiner and Blender Net Production 3
4. Stocks of Crude Oil by PAD District, and Stocks of Petroleum Products, U.S. Totals 4
5. Stocks of Total Motor Gasoline and Fuel Ethanol by PAD District 6
6. Stocks of Distillate, Kerosene-Type Jet Fuel, Residual Fuel Oil, and Propane/Propylene by PAD District 8
7. Imports of Crude Oil and Total Products by PAD District 13
8. Preliminary Crude Imports by Country of Origin 14
9. U.S. and PAD District Weekly Estimates 15
10. U.S. World Crude Oil Prices - **Discontinued** 22
11. Spot Prices of Crude Oil, Motor Gasoline, and Heating Oils, January 2012 to Present 23
12. Spot Prices of Ultra-Low Sulfur Diesel, Kerosene-Type Jet, Residual Fuels, and Propane, January 2012 to Present 25
13. NYMEX Futures Prices of Crude Oil, Motor Gasoline, No. 2 Heating Oil 26
14. U.S. Retail Motor Gasoline and On-Highway Diesel Fuel Prices, January 2012 to Present 27

Figures
1. Stocks of Crude Oil, June 2012 to Present 5
2. Stocks of Total Motor Gasoline by PAD District, June 2012 to Present 7
3. Stocks of Distillate Fuel Oil by PAD District, June 2012 to Present 9
4. Stocks of Kerosene-Type Jet Fuel, June 2012 to Present 10
5. Stocks of Residual Fuel Oil by PAD District, June 2012 to Present 11
6. Stocks of Propane/Propylene by PAD District, June 2012 to Present 12
7. Daily Crude Oil and Petroleum Product Spot Prices. 24
8. Daily Trans-Atlantic Spot Product Price Differentials: New York Harbor less Rotterdam (ARA) 24
9. Daily Futures Price Differentials: First Delivery Month Less Second Delivery Month 26
10. U.S. Average Retail Regular Motor Gasoline and On-Highway Diesel Fuel Prices 28

Sources 29

Appendices
A. Petroleum Supply Summary Table 31
B. Explanatory Notes 32
C. Northeast Home Heating Oil Reserve 46
D. Winter Fuels Explanatory Notes 53

Glossary 55

Highlights

U.S. crude oil refinery inputs averaged 16.0 million barrels per day during the week ending December 13, 2013, 200 thousand barrels per day lower than the previous week's average. Refineries operated at 91.5% of their operable capacity last week. Gasoline production increased last week, averaging 9.3 million barrels per day. Distillate fuel production decreased last week, averaging 5.0 million barrels per day.

U.S. crude oil imports averaged over 7.7 million barrels per day last week, up by 870 thousand barrels per day from the previous week. Over the last four weeks, crude oil imports averaged over 7.5 million barrels per day, 9.4% below the same four-week period last year. Total motor gasoline imports (including both finished gasoline and gasoline blending components) last week averaged 599 thousand barrels per day. Distillate fuel imports averaged 226 thousand barrels per day last week.

U.S. commercial crude oil inventories (excluding those in the Strategic Petroleum Reserve) decreased by 2.9 million barrels from the previous week. At 372.3 million barrels, U.S. crude oil inventories are above the upper limit of the average range for this time of year. Total motor gasoline inventories increased by 1.3 million barrels last week, and are above the upper limit of the average range. Finished gasoline inventories decreased while blending components inventories increased last week. Distillate fuel inventories decreased by 2.1 million barrels last week and are below the lower limit of the average range for this time of year. Propane/propylene inventories fell 2.7 million barrels last week and are well below the lower limit of the average range. Total commercial petroleum inventories decreased by 12.6 million barrels last week.

Total products supplied over the last four-week period averaged 19.8 million barrels per day, up by 4.0% from the same period last year. Over the last four weeks, motor gasoline product supplied averaged 8.8 million barrels per day, up by 3.7% from the same period last year. Distillate fuel product supplied averaged over 3.7 million barrels per day over the last four weeks, down by 0.8% from the same period last year. Jet fuel product supplied is up 1.6% compared to the same four-week period last year.

The WTI price was $96.27 per barrel on December 13, 2013, $1.21 under last week's price but $9.95 above a year ago. The spot price for conventional gasoline in the New York Harbor was $2.639 per gallon, $0.101 less than last week's price and $0.051 under a year ago. The spot price for No. 2 heating oil in the New York Harbor was $2.956 per gallon, $0.087 less than last week's price and $0.020 under a year ago.

The national average retail regular gasoline price decreased to $3.239 per gallon on December 16, 2013, $0.030 per gallon less than last week and $0.015 under a year ago. The national average retail diesel fuel price decreased to $3.871 per gallon, $0.008 per gallon less than last week and $0.074 under a year ago.

Refinery Activity (Thousand Barrels per Day)

	Four Weeks Ending		
	12/13/13	12/6/13	12/14/12
Crude Oil Input to Refineries	15,930	15,809	15,391
Refinery Capacity Utilization (Percent)	91.5	90.7	90.3
Motor Gasoline Production	9,173	9,162	8,931
Distillate Fuel Oil Production	5,088	5,076	4,762

See Table 2.

Products Supplied (Thousand Barrels per Day)

	Four Weeks Ending		
	12/13/13	12/6/13	12/14/12
Motor Gasoline	8,787	8,764	8,472
Distillate Fuel Oil	3,742	3,803	3,774
All Other Products	7,261	7,084	6,776
Total	19,790	19,650	19,022

See Table 1.

Stocks (Million Barrels)

	12/13/13	12/6/13	12/14/12
Crude Oil (Excluding SPR)	372.3	375.2	371.6
Motor Gasoline	220.5	219.1	219.3
Distillate Fuel Oil[1]	116.0	118.1	117.0
All Other Oils	364.4	373.3	388.6
Crude Oil in SPR	696.0	696.0	695.0
Total	1,769.2	1,781.7	1,791.5

See Table 1.

Prices (Dollars per Gallon except as noted)

	12/13/13	12/6/13	12/14/12
World Crude Oil (Dollars per Barrel)	–	–	–
Spot Prices			
WTI Crude Oil - Cushing (Dollars per Barrel)	96.27	97.48	86.32
Conv. Regular Gasoline - NYH	2.639	2.740	2.690
No. 2 Heating Oil - NYH	2.956	3.043	2.976
Ultra-Low Sulfur Diesel Fuel - NYH	2.974	3.053	3.061
Propane - Mont Belvieu	1.306	1.269	0.762

Net Imports (Thousand Barrels per Day)

	Four Weeks Ending		
	12/13/13	12/6/13	12/14/12
Crude Oil	7,473	7,506	8,269
Petroleum Products	-1,558	-1,649	-597
Total	5,916	5,857	7,672

See Table 1.

	Retail Prices		
	12/16/13	12/9/13	12/17/12
Motor Gasoline - Regular	3.239	3.269	3.254
Motor Gasoline - Midgrade	3.423	3.453	3.409
Motor Gasoline - Premium	3.605	3.632	3.571
On-Highway Diesel Fuel	3.871	3.879	3.945

See Table 10,11,12,14.

Data for the week ending December 6 reflect benchmarking to the September *Petroleum Supply Monthly* values.

– = Data Not Available.

[1] Distillate fuel oil stocks located in the "Northeast Heating Oil Reserve" are not included.

Note: Data may not add to total due to independent rounding.

Table 1. U.S. Petroleum Balance Sheet, Week Ending 12/13/2013

Petroleum Stocks (Million Barrels)	Current Week	Week Ago			Year Ago		
	12/13/13	12/6/13	Difference	Percent Change	12/14/12	Difference	Percent Change
Crude Oil	1,068.3	1,071.2	-2.9	-0.3	1,066.6	1.7	0.2
Commercial (Excluding SPR)[1]	372.3	375.2	-2.9	-0.8	371.6	0.7	0.2
Strategic Petroleum Reserve (SPR)[2]	696.0	696.0	0.0	0.0	695.0	1.0	0.1
Total Motor Gasoline	220.5	219.1	1.3	0.6	219.3	1.2	0.5
Reformulated	0.0	0.0	0.0	2.3	0.0	0.0	25.7
Conventional	41.4	41.5	-0.1	-0.2	55.6	-14.2	-25.5
Blending Components	179.0	177.6	1.4	0.8	163.7	15.3	9.4
Fuel Ethanol	15.6	15.4	0.2	1.1	20.8	-5.2	-25.0
Kerosene-Type Jet Fuel	37.0	36.6	0.4	1.2	39.3	-2.3	-5.8
Distillate Fuel Oil[3]	116.0	118.1	-2.1	-1.8	117.0	-1.0	-0.9
15 ppm sulfur and Under	94.9	95.1	-0.2	-0.2	85.1	9.8	11.5
> 15 ppm to 500 ppm sulfur	3.9	3.8	0.1	2.6	6.4	-2.5	-38.9
> 500 ppm sulfur[3]	17.1	19.2	-2.0	-10.6	25.5	-8.3	-32.7
Residual Fuel Oil	35.2	34.8	0.4	1.1	37.1	-1.9	-5.0
Propane/Propylene	50.0	52.6	-2.7	-5.1	69.2	-19.3	-27.8
Other Oils[4]	226.6	233.8	-7.2	-3.1	222.1	4.5	2.0
Unfinished Oils	82.9	85.5	-2.6	-3.0	82.5	0.4	0.5
Total Stocks (Including SPR)[2,3]	1,769.2	1,781.7	-12.6	-0.7	1,791.5	-22.3	-1.2
Total Stocks (Excluding SPR)[3]	1,073.2	1,085.8	-12.6	-1.2	1,096.5	-23.3	-2.1

Petroleum Supply (Thousand Barrels per Day)	Current Week	Week Ago		Year Ago		Four-Week Averages Week Ending			Cumulative Daily Average		
	12/13/13	12/6/13	Difference	12/14/12	Difference	12/13/13	12/14/12	Percent Change	12/13/13	12/14/12	Percent Change
Crude Oil Supply											
(1) **Domestic Production**[5]	8,058	8,075	-17	6,863	1,195	8,041	6,838	17.6	7,453	6,205	20.1
(2) Alaska	539	532	7	563	-24	535	559	-4.2	511	524	-2.5
(3) Lower 48	7,519	7,543	-24	6,300	1,219	7,506	6,279	19.5	6,942	5,681	22.2
(4) **Net Imports (Including SPR)**	7,675	6,805	870	8,356	-681	7,473	8,269	-9.6	7,752	8,649	-10.4
(5) Imports	7,732	6,862	870	8,399	-667	7,530	8,312	-9.4	7,802	8,689	-10.2
(6) Commercial Crude Oil	7,732	6,862	870	8,399	-667	7,530	8,312	-9.4	7,802	8,689	-10.2
(7) Imports by SPR	0	0	0	0	0	0	0	–	0	0	–
(8) Imports into SPR by Others	0	0	0	0	0	0	0	–	0	0	–
(9) Exports	57	57	0	43	14	57	42	34.9	50	39	27.5
(10) **Stock Change (+/build; -/draw)**	-420	-1,512	1,092	-138	-282	-577	-101	– –	37	114	– –
(11) Commercial Stock Change	-420	-1,512	1,092	-138	-282	-577	-101	– –	34	116	– –
(12) SPR Stock Change	0	0	0	0	0	0	0	– –	3	-3	– –
(13) **Adjustment**[6]	-222	-261	39	237	-459	-161	183	– –	87	225	– –
(14) **Crude Oil Input to Refineries**	15,931	16,131	-200	15,594	337	15,930	15,391	3.5	15,255	14,965	1.9
Other Supply											
(15) **Production**	4,865	4,895	-30	4,506	359	4,861	4,438	9.5	4,525	4,385	3.2
(16) Natural Gas Plant Liquids[7]	2,707	2,707	0	2,458	249	2,682	2,413	11.2	2,498	2,359	5.9
(17) Renewable Fuels/Oxygenate Plant	1,011	1,027	-16	921	90	1,034	911	13.6	934	933	0.1
(18) Fuel Ethanol	928	944	-16	822	107	928	821	13.1	852	861	-0.9
(19) Other[8]	83	83	0	99	-16	106	90	18.4	81	72	12.3
(20) Refinery Processing Gain	1,147	1,161	-14	1,127	20	1,145	1,115	2.6	1,094	1,093	0.1
(21) **Net Imports**[9]	-1,379	-1,835	456	-481	-898	-1,558	-597	– –	-1,072	-812	– –
(22) Imports[9]	2,007	1,551	456	2,420	-413	1,828	2,211	-17.3	1,976	2,028	-2.6
(23) Exports[9]	3,386	3,386	0	2,901	485	3,386	2,808	20.6	3,047	2,840	7.3
(24) **Stock Change (+/build; -/draw)**[3,10]	-1,379	837	-2,216	-140	-1,239	-353	404	– –	-99	26	– –
(25) **Adjustment**[11]	200	200	0	195	5	204	193	– –	194	180	– –
Products Supplied											
(26) **Total**[12]	20,996	18,554	2,442	19,955	1,042	19,790	19,022	4.0	19,002	18,692	1.7
(27) Finished Motor Gasoline[13]	9,016	8,348	668	8,618	398	8,787	8,472	3.7	8,759	8,648	1.3
(28) Kerosene-Type Jet Fuel	1,469	1,480	-11	1,486	-17	1,510	1,487	1.6	1,447	1,429	1.3
(29) Distillate Fuel Oil	4,089	3,304	785	4,214	-125	3,742	3,774	-0.8	3,806	3,667	3.8
(30) Residual Fuel Oil	265	205	60	433	-168	274	322	-14.9	277	363	-23.6
(31) Propane/Propylene	1,618	1,561	57	1,583	35	1,593	1,520	4.8	1,307	1,195	9.3
(32) Other Oils[14]	4,539	3,657	883	3,621	918	3,885	3,448	12.7	3,406	3,390	0.5
Net Imports of Crude and Petroleum Products											
(33) Total	6,296	4,970	1,326	7,875	-1,579	5,916	7,672	-22.9	6,680	7,837	-14.8

– – = Not Applicable.
– = Data Not Available.
1 Includes those domestic and Customs-cleared foreign crude oil stocks held at refineries, in pipelines, in lease tanks, and in transit to refineries.
2 Includes non-U.S. stocks held under foreign or commercial storage agreements.
3 Excludes stocks located in the "Northeast Heating Oil Reserve." For details see Appendix C.
4 Includes weekly data for NGPLs and LRGs (except propane/propylene), kerosene, and asphalt and road oil; and estimated stocks of minor products based on monthly data.
5 Domestic crude oil production includes lease condensate and is estimated using a combination of short-term forecasts for the lower 48 states and the latest available production estimates from Alaska. For more details see Appendix B, under "Data Obtained Through Models."
6 Formerly known as Unaccounted-for Crude Oil, this is a balancing item. See Glossary for further explanation.
7 Formerly known as Natural Gas Liquids Production, prior to June 4, 2010, this included adjustments for fuel ethanol and motor gasoline blending components.
8 Includes denaturants (e.g. Pentanes Plus), other oxygenates (e.g. ETBE and MTBE), and other renewables (e.g. biodiesel).
9 Includes finished petroleum products, unfinished oils, gasoline blending components, fuel ethanol, and NGPLs and LRGs.
10 Includes an estimate of minor product stock change based on monthly data.
11 Includes monthly adjustments for hydrogen and other hydrocarbon production.
12 Total Product Supplied = Crude Oil Input to Refineries (line 14) + Other Supply Production (line 15) + Net Product Imports (line 21) – Stock Change (line 24) + Adjustment (line 25).
13 See Table 2, footnote #3.
14 Other Oil Product Supplied = Total Product Supplied (line 26) less the product supplied of Finished Motor Gasoline (line 27), Kerosene-Type Jet Fuel (line 28), Distillate Fuel Oil (line 29), Residual Fuel Oil (line 30), and Propane/Propylene (line 31).
Notes: Some data estimated (see Sources for clarification). Data may not add to total due to independent rounding. Differences and percent changes are calculated using unrounded numbers.
Source: See page 29.

Table 2. U.S. Inputs and Production by PAD District
(Thousand Barrels per Day, Except Where Noted)

Product / Region	Current Week	Last Week		Year Ago		2 Years Ago		Four-Week Averages		
	12/13/13	12/6/13	Difference	12/14/12	Percent Change	12/16/11	Percent Change	12/13/13	12/14/12	Percent Change
Refiner Inputs and Utilization										
Crude Oil Inputs	15,931	16,131	-200	15,594	2.2	14,604	9.1	15,930	15,391	3.5
East Coast (PADD 1)	1,021	1,099	-78	954	7.0	938	8.8	1,023	944	8.3
Midwest (PADD 2)	3,563	3,693	-130	3,486	2.2	3,497	1.9	3,607	3,420	5.4
Gulf Coast (PADD 3)	8,363	8,286	77	8,277	1.0	7,214	15.9	8,307	8,148	1.9
Rocky Mountain (PADD 4)	573	570	3	592	-3.3	559	2.4	581	583	-0.5
West Coast (PADD 5)	2,412	2,484	-72	2,285	5.5	2,396	0.6	2,413	2,295	5.1
Gross Inputs	16,310	16,501	-192	15,918	2.5	15,063	8.3	16,295	15,694	3.8
East Coast (PADD 1)	1,113	1,106	7	1,040	7.0	939	18.5	1,074	979	9.6
Midwest (PADD 2)	3,565	3,691	-126	3,442	3.6	3,522	1.2	3,609	3,381	6.7
Gulf Coast (PADD 3)	8,458	8,448	10	8,419	0.5	7,499	12.8	8,417	8,320	1.2
Rocky Mountain (PADD 4)	574	573	2	599	-4.0	561	2.4	584	587	-0.6
West Coast (PADD 5)	2,599	2,683	-85	2,419	7.5	2,542	2.2	2,612	2,425	7.7
Operable Capacity[1]	17,818	17,818	0	17,395	2.4	17,736	0.5	17,817	17,388	2.5
East Coast (PADD 1)	1,297	1,297	0	1,293	0.3	1,618	-19.8	1,296	1,293	0.2
Midwest (PADD 2)	3,769	3,769	0	3,720	1.3	3,721	1.3	3,769	3,715	1.5
Gulf Coast (PADD 3)	9,093	9,093	0	8,725	4.2	8,646	5.2	9,093	8,725	4.2
Rocky Mountain (PADD 4)	630	630	0	624	1.0	624	1.0	630	624	1.0
West Coast (PADD 5)	3,029	3,029	0	3,032	-0.1	3,128	-3.2	3,029	3,030	0.0
Percent Utilization[2]	91.5	92.6	-1.1	91.5	– –	84.9	– –	91.5	90.3	– –
East Coast (PADD 1)	85.8	85.3	0.5	80.4	– –	58.0	– –	82.9	75.8	– –
Midwest (PADD 2)	94.6	97.9	-3.4	92.5	– –	94.6	– –	95.7	91.0	– –
Gulf Coast (PADD 3)	93.0	92.9	0.1	96.5	– –	86.7	– –	92.6	95.4	– –
Rocky Mountain (PADD 4)	91.2	90.9	0.3	95.9	– –	89.9	– –	92.6	94.1	– –
West Coast (PADD 5)	85.8	88.6	-2.8	79.8	– –	81.3	– –	86.2	80.0	– –
Refiner and Blender Net Production										
Finished Motor Gasoline[3]	9,311	8,982	329	8,888	4.8	9,390	-0.8	9,173	8,931	2.7
Finished Motor Gasoline (less Adjustment)[4]	9,376	9,428	-52	9,149	2.5	9,247	1.4	9,403	9,029	4.1
East Coast (PADD 1)	2,871	2,839	32	2,825	1.6	2,916	-1.6	2,862	2,846	0.6
Midwest (PADD 2)	2,546	2,573	-27	2,283	11.5	2,380	7.0	2,529	2,209	14.5
Gulf Coast (PADD 3)	2,087	2,110	-23	2,145	-2.7	2,165	-3.6	2,114	2,143	-1.4
Rocky Mountain (PADD 4)	311	357	-46	299	3.9	275	13.1	324	294	10.2
West Coast (PADD 5)	1,562	1,550	12	1,597	-2.2	1,511	3.4	1,575	1,537	2.4
Reformulated[4]	2,983	2,891	92	2,985	-0.1	3,094	-3.6	2,958	2,923	1.2
Conventional[4]	6,393	6,537	-144	6,165	3.7	6,153	3.9	6,445	6,106	5.6
Adjustment[5]	-65	-446	381	-261	– –	143	– –	-231	-98	– –
Kerosene-Type Jet Fuel	1,595	1,619	-24	1,488	7.2	1,420	12.3	1,570	1,442	8.9
East Coast (PADD 1)	65	66	-2	66	-2.2	52	24.5	65	62	4.6
Midwest (PADD 2)	225	240	-15	206	9.2	210	7.3	226	198	13.8
Gulf Coast (PADD 3)	780	840	-60	822	-5.2	675	15.4	800	777	3.0
Rocky Mountain (PADD 4)	26	27	-1	23	13.7	30	-11.6	26	25	3.6
West Coast (PADD 5)	500	445	54	370	34.9	454	10.2	454	380	19.5
Distillate Fuel Oil	4,956	5,262	-306	4,880	1.6	5,008	-1.0	5,088	4,762	6.8
East Coast (PADD 1)	344	332	12	387	-11.0	375	-8.3	324	332	-2.5
Midwest (PADD 2)	1,143	1,168	-25	1,042	9.7	1,136	0.7	1,134	1,026	10.5
Gulf Coast (PADD 3)	2,780	2,965	-186	2,688	3.4	2,688	3.4	2,873	2,655	8.2
Rocky Mountain (PADD 4)	171	195	-24	204	-16.5	203	-15.8	187	204	-8.5
West Coast (PADD 5)	518	601	-84	558	-7.3	607	-14.7	571	545	4.7
15 ppm sulfur and Under	4,482	4,824	-342	4,289	4.5	4,132	8.5	4,624	4,269	8.3
> 15 ppm to 500 ppm sulfur	150	171	-22	121	23.8	225	-33.5	146	146	0.4
> 500 ppm sulfur	324	267	57	470	-31.0	651	-50.2	318	348	-8.6
Residual Fuel Oil	448	442	6	372	20.5	493	-9.1	435	398	9.0
East Coast (PADD 1)	35	38	-3	54	-35.7	54	-35.5	38	53	-27.5
Midwest (PADD 2)	70	60	10	42	64.7	58	19.5	61	42	47.3
Gulf Coast (PADD 3)	226	219	7	179	26.1	268	-15.9	202	198	1.9
Rocky Mountain (PADD 4)	14	15	-1	13	2.6	11	30.3	14	12	14.0
West Coast (PADD 5)	104	111	-7	83	25.6	102	2.4	120	94	27.0
Propane/Propylene[6]	1,405	1,479	-74	1,261	11.5	1,187	18.4	1,452	1,339	8.4
East Coast (PADD 1)	140	142	-2	72	95.1	66	112.1	130	67	95.2
Midwest (PADD 2)	246	285	-39	268	-8.2	255	-3.5	271	275	-1.3
Gulf Coast (PADD 3)	878	886	-8	787	11.6	757	15.9	898	823	9.2
PADDs 4 and 5	141	167	-26	134	5.2	109	30.0	152	175	-13.0
Ethanol Plant Production										
Fuel Ethanol	928	944	-16	822	13.0	943	-1.6	928	821	13.1
East Coast (PADD 1)	W	W	W	W	W	W	W	W	W	W
Midwest (PADD 2)	859	874	-14	770	11.6	878	-2.1	858	768	11.8
Gulf Coast (PADD 3)	W	W	W	W	W	W	W	W	W	W
Rocky Mountain (PADD 4)	W	W	W	W	W	W	W	W	W	W
West Coast (PADD 5)	W	W	W	W	W	W	W	W	W	W

– – = Not Applicable.
– = Data Not Available.
W = Data Withheld.
[1] Based on the latest reported monthly operable capacity.
[2] Calculated as gross inputs divided by the latest reported monthly operable capacity. See Glossary. Percentages are calculated using unrounded numbers.
[3] Finished motor gasoline production and product supplied include a weekly adjustment applied only to the U.S. total to correct for the imbalance created by blending of fuel ethanol and motor gasoline blending components. From 1993 to June 4, 2010, this adjustment was estimated from the latest monthly data and allocated to formulation and PAD District production data.
[4] Excludes adjustments for fuel ethanol and motor gasoline blending components. Historical data prior to June 4, 2010 includes the adjustment allocated by PAD District and formulation.
[5] Adjustment to correct for the imbalance created by the blending of fuel ethanol and motor gasoline blending components. For details see Appendix B.
[6] Includes propane/propylene production from natural gas plants.
Notes: Data may not add to total due to independent rounding. Differences and percent changes are calculated using unrounded numbers.
Source: See page 29.

Table 3. Refiner and Blender Net Production
(Thousand Barrels per Day)

Product / Region	Current Week	Last Week		Year Ago		2 Years Ago		Four-Week Averages		
	12/13/13	12/6/13	Difference	12/14/12	Percent Change	12/16/11	Percent Change	12/13/13	12/14/12	Percent Change
Refiner Net Production										
Finished Motor Gasoline[1]	2,368	2,462	-94	2,662	-11.0	2,703	-12.4	2,381	2,612	-8.8
East Coast (PADD 1)	67	71	-4	168	-60.1	174	-61.6	64	154	-58.3
Midwest (PADD 2)	790	798	-8	843	-6.3	904	-12.6	755	815	-7.4
Gulf Coast (PADD 3)	1,021	1,011	9	1,111	-8.1	1,158	-11.9	1,024	1,111	-7.8
Rocky Mountain (PADD 4)	235	279	-44	227	3.5	229	2.8	248	230	7.9
West Coast (PADD 5)	255	302	-48	312	-18.3	237	7.6	290	302	-3.9
Reformulated	49	48	1	83	-40.0	93	-47.0	49	78	-37.4
Blended with Ethanol	49	48	1	83	-40.0	93	-47.0	49	78	-37.4
Other	0	0	0	0	–	0	–	0	0	–
Conventional	2,319	2,414	-95	2,579	-10.1	2,609	-11.1	2,333	2,534	-8.0
Blended with Ethanol	374	384	-10	382	-2.1	390	-3.9	384	372	3.1
Ed55 and Lower	374	384	-10	382	-2.1	390	-4.0	384	372	3.1
Greater than Ed55	0	0	0	0	50.9	0	–	0	0	252.1
Other	1,944	2,030	-85	2,197	-11.5	2,220	-12.4	1,949	2,162	-9.9
Distillate Fuel Oil	4,969	5,276	-308	4,838	2.7	4,988	-0.4	5,079	4,731	7.4
15 ppm sulfur and Under	4,457	4,794	-338	4,281	4.1	4,189	6.4	4,593	4,264	7.7
> 15 ppm to 500 ppm sulfur	144	169	-25	113	27.1	241	-40.3	141	134	5.0
> 500 ppm sulfur	368	313	55	445	-17.2	558	-34.0	345	333	3.6
Kerosene	75	121	-46	3	2,644.2	26	191.8	82	29	184.0
Kerosene-Type Jet Fuel	1,595	1,619	-24	1,488	7.2	1,420	12.3	1,570	1,442	8.9
Residual Fuel Oil	448	442	6	372	20.5	493	-9.1	435	398	9.0
Blender Net Production										
Finished Motor Gasoline[1]	7,008	6,966	42	6,488	8.0	6,544	7.1	7,022	6,417	9.4
East Coast (PADD 1)	2,804	2,767	36	2,657	5.5	2,741	2.3	2,798	2,691	4.0
Midwest (PADD 2)	1,755	1,775	-19	1,440	21.9	1,475	19.0	1,774	1,394	27.2
Gulf Coast (PADD 3)	1,066	1,098	-32	1,034	3.1	1,007	5.9	1,090	1,032	5.6
Rocky Mountain (PADD 4)	75	78	-3	72	5.3	46	64.2	76	64	18.7
West Coast (PADD 5)	1,308	1,248	60	1,285	1.7	1,275	2.6	1,284	1,235	4.0
Reformulated	2,934	2,843	91	2,902	1.1	3,000	-2.2	2,909	2,845	2.2
Blended with Ethanol	2,934	2,843	91	2,902	1.1	3,000	-2.2	2,909	2,845	2.2
Other	0	0	0	0	–	0	–	0	0	–
Conventional	4,074	4,123	-49	3,585	13.6	3,543	15.0	4,112	3,571	15.1
Blended with Ethanol	4,926	5,022	-96	4,856	1.4	4,872	1.1	4,991	4,802	4.0
Ed55 and Lower	4,925	5,020	-96	4,855	1.4	4,871	1.1	4,990	4,801	3.9
Greater than Ed55	1	1	0	1	26.5	2	-12.2	2	1	56.8
Other	-852	-899	47	-1,271	-33.0	-1,329	-35.9	-879	-1,230	-28.5
Distillate Fuel Oil	-13	-14	1	41	-131.4	20	-164.8	9	32	-72.3
15 ppm sulfur and Under	26	29	-4	8	206.4	-57	-144.6	30	5	485.6
> 15 ppm to 500 ppm sulfur	6	3	3	8	-24.8	-16	-135.5	5	11	-52.8
> 500 ppm sulfur	-44	-46	2	25	-274.2	93	-147.4	-27	15	-280.5
Kerosene	1	2	-2	1	-16.7	2	-64.0	0	0	-47.6
Kerosene-Type Jet Fuel	0	0	0	0	–	0	–	0	0	–

– – = Not Applicable.
– = Data Not Available.
[1] Does not include adjustments for fuel ethanol and motor gasoline blending components.
Notes: Data may not add to total due to independent rounding. Differences and percent changes are calculated using unrounded numbers.
Source: See page 29.

Table 4. Stocks of Crude Oil by PAD District, and Stocks of Petroleum Products,[1] U.S. Totals
(Million Barrels)

Product / Region	Current Week	Last Week		Year Ago		2 Years Ago	
	12/13/13	12/6/13	Difference	12/14/12	Percent Change	12/16/11	Percent Change
Crude Oil	1,068.3	1,071.2	-2.9	1,066.6	0.2	1,019.5	4.8
Commercial (Excluding SPR)[2]	372.3	375.2	-2.9	371.6	0.2	323.6	15.1
East Coast (PADD 1)	10.0	10.2	-0.2	10.5	-4.8	9.7	2.9
Midwest (PADD 2)	110.0	110.3	-0.3	111.1	-1.0	94.1	16.9
Cushing[3]	40.6	41.2	-0.6	47.0	-13.5	30.2	34.5
Gulf Coast (PADD 3)	181.4	184.4	-3.0	176.7	2.7	149.0	21.7
Rocky Mountain (PADD 4)	19.7	19.8	-0.1	18.0	9.5	16.0	23.4
West Coast (PADD 5)	51.2	50.6	0.6	55.4	-7.5	54.7	-6.4
Alaska In-Transit[4]	6.0	4.9	1.1	3.4	78.0	3.1	94.8
SPR[5]	696.0	696.0	0.0	695.0	0.1	696.0	0.0
Total Motor Gasoline	220.5	219.1	1.3	219.3	0.5	218.4	1.0
Reformulated	0.0	0.0	0.0	0.0	25.7	0.3	-85.8
Conventional	41.4	41.5	-0.1	55.6	-25.5	60.3	-31.3
Blending Components	179.0	177.6	1.4	163.7	9.4	157.8	13.4
Fuel Ethanol	15.6	15.4	0.2	20.8	-25.0	17.7	-11.5
Kerosene-Type Jet Fuel	37.0	36.6	0.4	39.3	-5.8	41.5	-10.7
Distillate Fuel Oil[6]	116.0	118.1	-2.1	117.0	-0.9	139.1	-16.7
15 ppm sulfur and Under	94.9	95.1	-0.2	85.1	11.5	89.8	5.7
> 15 ppm to 500 ppm sulfur	3.9	3.8	0.1	6.4	-38.9	10.2	-61.8
> 500 ppm sulfur[6]	17.1	19.2	-2.0	25.5	-32.7	39.1	-56.2
Residual Fuel Oil	35.2	34.8	0.4	37.1	-5.0	38.7	-8.9
Propane/Propylene	50.0	52.6	-2.7	69.2	-27.8	56.9	-12.2
Other Oils [7]	226.6	233.8	-7.2	222.1	2.0	202.0	12.2
Unfinished Oils	82.9	85.5	-2.6	82.5	0.5	79.0	5.0
Total Stocks (Including SPR)[3,6]	1,769.2	1,781.7	-12.6	1,791.5	-1.2	1,733.8	2.0
Total Stocks (Excluding SPR)[6]	1,073.2	1,085.8	-12.6	1,096.5	-2.1	1,037.8	3.4

-- = Not Applicable.
[1] Includes those domestic and Customs-cleared foreign stocks held at, or in transit to, refineries, ethanol plants, and bulk terminals, as well as stocks in pipelines. Stocks (excluding propane) held at natural gas processing plants are included in "Other Oils." All stock levels are as of the end of the period.
[2] Includes those domestic and Customs-cleared foreign crude oil stocks held at refineries, in pipelines, in lease tanks, and in transit to refineries.
[3] Includes domestic and foreign crude oil stocks held in tank farms in Lincoln, Payne, and Creek counties in Oklahoma. Cushing, Oklahoma, is the designated delivery point for NYMEX crude oil futures contracts.
[4] Includes crude oil stocks in transit by water between Alaska and the other States, the District of Columbia, Puerto Rico, and the Virgin Islands, as well as stocks held at transshipment terminals.
[5] Includes non-U.S. stocks held under foreign or commercial storage agreements.
[6] Excludes stocks located in the "Northeast Heating Oil Reserve." For details see Appendix C.
[7] Includes weekly data for NGPLs and LRGs (except propane/propylene), kerosene, and asphalt and road oil; and estimated stocks of minor products based on monthly data.
Notes: Some data estimated (see Sources for clarification). Data may not add to total due to independent rounding. Differences and percent changes are calculated using unrounded numbers.
Source: See page 29.

Figure 1. Stocks of Crude Oil by PAD District, June 2012 to Present



Table 5. Stocks of Total Motor Gasoline and Fuel Ethanol by PAD District
(Million Barrels)

Product / Region	Current Week	Last Week		Year Ago		2 Years Ago	
	12/13/13	12/6/13	Difference	12/14/12	Percent Change	12/16/11	Percent Change
Motor Gasoline							
Total Motor Gasoline	220.5	219.1	1.3	219.3	0.5	218.4	1.0
East Coast (PADD 1)	56.5	57.3	-0.8	49.1	15.1	57.8	-2.1
Midwest (PADD 2)	50.3	49.0	1.3	49.9	0.9	49.9	0.8
Gulf Coast (PADD 3)	76.3	74.9	1.4	80.6	-5.3	75.1	1.6
Rocky Mountain (PADD 4)	7.5	7.9	-0.4	7.1	5.4	7.2	3.9
West Coast (PADD 5)	29.9	30.1	-0.2	32.6	-8.5	28.4	5.0
Finished Motor Gasoline	41.5	41.6	-0.1	55.7	-25.4	60.6	-31.6
East Coast (PADD 1)	7.8	7.5	0.4	8.1	-2.7	11.0	-28.7
Midwest (PADD 2)	13.3	13.4	-0.1	21.9	-39.0	24.6	-45.9
Gulf Coast (PADD 3)	12.5	12.3	0.2	17.2	-27.3	16.3	-22.9
Rocky Mountain (PADD 4)	4.1	4.4	-0.3	4.2	-3.0	4.7	-13.5
West Coast (PADD 5)	3.7	4.0	-0.3	4.3	-13.3	4.0	-7.7
Reformulated	0.0	0.0	0.0	0.0	25.7	0.3	-85.8
East Coast (PADD 1)	0.0	0.0	0.0	0.0	28.6	0.3	-90.1
Midwest (PADD 2)	0.0	0.0	0.0	0.0	–	0.0	–
Gulf Coast (PADD 3)	0.0	0.0	0.0	0.0	–	0.0	–
Rocky Mountain (PADD 4)	0.0	0.0	0.0	0.0	–	0.0	–
West Coast (PADD 5)	0.0	0.0	0.0	0.0	21.4	0.0	-55.3
Conventional	41.4	41.5	-0.1	55.6	-25.5	60.3	-31.3
East Coast (PADD 1)	7.8	7.4	0.4	8.0	-2.8	10.7	-27.1
Midwest (PADD 2)	13.3	13.4	-0.1	21.9	-39.0	24.6	-45.9
Gulf Coast (PADD 3)	12.5	12.3	0.2	17.2	-27.3	16.3	-22.9
Rocky Mountain (PADD 4)	4.1	4.4	-0.3	4.2	-3.0	4.7	-13.5
West Coast (PADD 5)	3.7	4.0	-0.3	4.3	-13.4	4.0	-7.2
Blending Components	179.0	177.6	1.4	163.7	9.4	157.8	13.4
East Coast (PADD 1)	48.7	49.8	-1.1	41.1	18.6	46.8	4.1
Midwest (PADD 2)	37.0	35.6	1.4	28.0	32.1	25.3	46.4
Gulf Coast (PADD 3)	63.8	62.6	1.2	63.3	0.7	58.8	8.4
Rocky Mountain (PADD 4)	3.4	3.5	-0.1	2.9	17.5	2.5	36.4
West Coast (PADD 5)	26.1	26.0	0.1	28.3	-7.8	24.4	7.1
Fuel Ethanol							
Fuel Ethanol	15.6	15.4	0.2	20.8	-25.0	17.7	-11.5
East Coast (PADD 1)	5.1	4.9	0.2	7.0	-27.4	6.7	-23.9
Midwest (PADD 2)	5.5	5.4	0.1	6.9	-20.3	5.5	0.2
Gulf Coast (PADD 3)	2.8	2.8	0.0	4.0	-29.8	3.0	-8.1
Rocky Mountain (PADD 4)	0.3	0.3	0.0	0.3	-4.7	0.3	15.9
West Coast (PADD 5)	1.9	1.9	0.0	2.6	-26.2	2.2	-11.3

– – = Not Applicable.
– = Data Not Available.
Notes: Data may not add to total due to independent rounding. Differences and percent changes are calculated using unrounded numbers.
Source: See page 29.

Figure 2. Stocks of Total Motor Gasoline by PAD District, June 2012 to Present













Table 6. Stocks of Distillate, Kerosene-Type Jet Fuel, Residual Fuel Oil, and Propane/Propylene by PAD District
(Million Barrels)

Product / Region	Current Week	Last Week		Year Ago		2 Years Ago	
	12/13/13	12/6/13	Difference	12/14/12	Percent Change	12/16/11	Percent Change
Distillate Fuel Oil[1]	116.0	118.1	-2.1	117.0	-0.9	139.1	-16.7
East Coast (PADD 1)	36.5	37.7	-1.2	39.2	-7.1	54.4	-33.0
New England (PADD 1A)	6.1	6.6	-0.4	5.8	6.5	11.6	-46.9
Central Atlantic (PADD 1B)	19.0	19.5	-0.5	23.5	-19.2	32.1	-40.9
Lower Atlantic (PADD 1C)	11.3	11.6	-0.3	10.0	13.4	10.7	5.7
Midwest (PADD 2)	25.9	26.0	-0.1	25.4	1.9	28.4	-8.7
Gulf Coast (PADD 3)	36.9	37.3	-0.4	34.0	8.3	40.1	-8.0
Rocky Mountain (PADD 4)	3.8	3.7	0.1	4.0	-6.2	3.8	-0.1
West Coast (PADD 5)	12.9	13.4	-0.4	14.2	-9.1	12.5	3.3
15 ppm sulfur and Under	94.9	95.1	-0.2	85.1	11.5	89.8	5.7
East Coast (PADD 1)	24.9	24.3	0.6	20.1	23.9	20.2	23.6
New England (PADD 1A)	1.9	1.7	0.1	1.6	18.7	2.0	-7.5
Central Atlantic (PADD 1B)	12.7	12.5	0.2	10.2	23.7	10.0	26.7
Lower Atlantic (PADD 1C)	10.4	10.1	0.3	8.3	25.2	8.1	27.5
Midwest (PADD 2)	24.7	24.7	0.0	23.7	4.1	26.1	-5.6
Gulf Coast (PADD 3)	30.3	30.7	-0.4	25.6	18.0	30.0	0.9
Rocky Mountain (PADD 4)	3.4	3.4	0.0	3.7	-8.0	3.4	1.0
West Coast (PADD 5)	11.6	11.9	-0.3	12.0	-2.7	10.1	14.7
> 15 ppm to 500 ppm sulfur	3.9	3.8	0.1	6.4	-38.9	10.2	-61.8
East Coast (PADD 1)	1.1	1.2	0.0	0.8	34.9	3.5	-67.0
New England (PADD 1A)	0.0	0.0	0.0	0.0	157.1	0.1	-57.1
Central Atlantic (PADD 1B)	0.8	0.7	0.0	0.4	73.0	2.4	-67.1
Lower Atlantic (PADD 1C)	0.3	0.4	0.0	0.4	-14.1	1.0	-67.6
Midwest (PADD 2)	0.6	0.7	-0.1	1.0	-42.7	1.4	-55.5
Gulf Coast (PADD 3)	1.7	1.6	0.1	3.4	-50.9	4.0	-57.8
Rocky Mountain (PADD 4)	0.2	0.2	0.0	0.2	7.9	0.2	-17.6
West Coast (PADD 5)	0.3	0.2	0.1	0.9	-67.3	1.2	-75.8
> 500 ppm sulfur[1]	17.1	19.2	-2.0	25.5	-32.7	39.1	-56.2
East Coast (PADD 1)	10.4	12.2	-1.8	18.3	-43.2	30.8	-66.3
New England (PADD 1A)	4.2	4.8	-0.6	4.2	1.3	9.5	-55.3
Central Atlantic (PADD 1B)	5.6	6.3	-0.7	12.8	-56.6	19.8	-71.9
Lower Atlantic (PADD 1C)	0.6	1.1	-0.6	1.3	-54.4	1.5	-61.5
Midwest (PADD 2)	0.6	0.6	0.0	0.7	-4.5	0.9	-28.5
Gulf Coast (PADD 3)	4.9	5.0	-0.1	5.0	-0.8	6.1	-19.1
Rocky Mountain (PADD 4)	0.2	0.2	0.0	0.1	26.9	0.2	2.5
West Coast (PADD 5)	1.0	1.2	-0.2	1.4	-26.9	1.2	-14.1
Kerosene-Type Jet Fuel	37.0	36.6	0.4	39.3	-5.8	41.5	-10.7
East Coast (PADD 1)	7.7	8.2	-0.5	8.8	-12.6	9.6	-20.1
Midwest (PADD 2)	7.1	6.6	0.6	6.9	2.9	8.4	-15.6
Gulf Coast (PADD 3)	12.6	12.8	-0.2	13.2	-4.7	14.0	-9.6
Rocky Mountain (PADD 4)	0.5	0.6	-0.1	0.6	-11.7	0.6	-13.8
West Coast (PADD 5)	9.1	8.4	0.7	9.8	-7.0	8.9	2.8
Residual Fuel Oil	35.2	34.8	0.4	37.1	-5.0	38.7	-8.9
East Coast (PADD 1)	8.7	8.9	-0.2	10.4	-16.3	11.0	-20.4
New England (PADD 1A)	0.4	0.5	0.0	0.4	12.7	0.6	-22.3
Central Atlantic (PADD 1B)	5.8	5.9	-0.2	7.3	-20.9	8.4	-31.0
Lower Atlantic (PADD 1C)	2.5	2.5	0.0	2.7	-8.3	2.0	23.8
Midwest (PADD 2)	1.4	1.3	0.0	1.5	-5.0	1.6	-10.4
Gulf Coast (PADD 3)	19.6	19.3	0.3	20.3	-3.2	21.1	-7.1
Rocky Mountain (PADD 4)	0.2	0.2	0.0	0.2	-2.4	0.2	-3.3
West Coast (PADD 5)	5.3	5.1	0.2	4.7	12.1	4.8	9.3
Propane/Propylene	50.0	52.6	-2.7	69.2	-27.8	56.9	-12.2
East Coast (PADD 1)	4.2	4.5	-0.3	5.1	-17.4	6.0	-30.1
New England (PADD 1A)	0.2	0.3	0.0	0.7	-70.6	0.6	-63.2
Central Atlantic (PADD 1B)	2.6	2.8	-0.2	2.4	10.0	3.2	-17.6
Lower Atlantic (PADD 1C)	1.4	1.4	0.0	2.0	-31.4	2.3	-39.4
Midwest (PADD 2)	16.0	16.9	-1.0	24.3	-34.4	24.1	-33.7
Gulf Coast (PADD 3)	27.1	28.3	-1.2	37.1	-27.0	24.9	8.6
PADDs 4 and 5	2.7	2.9	-0.2	2.7	0.9	1.9	45.3
Propylene (Total U.S. Nonfuel Use)[2]	3.3	3.1	0.2	3.7	-12.3	5.1	-35.8

-- = Not Applicable.
[1] Excludes stocks located in the "Northeast Heating Oil Reserve." For details see Appendix C.
[2] Nonfuel use propylene data collected from bulk terminal facilities only.
Notes: Data may not add to total due to independent rounding. Differences and percent changes are calculated using unrounded numbers.
Source: See page 29.
R = Revised Data.

Figure 3. Stocks of Distillate Fuel Oil by PAD District, June 2012 to Present



Figure 4. Stocks of Kerosene-Type Jet Fuel by PAD District, June 2012 to Present



Figure 5. Stocks of Residual Fuel Oil by PAD District, June 2012 to Present



Figure 6. Stocks of Propane/Propylene by PAD District, June 2012 to Present



Table 7. Imports of Crude Oil and Total Products by PAD District
(Thousand Barrels per Day)

Product / Region	Current Week	Last Week		Year Ago		2 Years Ago		Four-Week Averages		
	12/13/13	12/6/13	Difference	12/14/12	Percent Change	12/16/11	Percent Change	12/13/13	12/14/12	Percent Change
Net Imports (Incl. SPR)	6,296	4,970	1,326	7,875	-20.1	6,803	-7.5	5,916	7,672	-22.9
Imports (Incl. SPR)	9,739	8,413	1,326	10,819	-10.0	9,683	0.6	9,358	10,480	-10.7
Exports[1]	3,443	3,443	0	2,944	16.9	2,880	19.5	3,443	2,850	20.8
Crude Oil Net Imports (Incl. SPR)	7,675	6,805	870	8,356	-8.1	7,545	1.7	7,473	8,269	-9.6
Commercial[2]	7,732	6,862	870	8,399	-7.9	7,581	2.0	7,530	8,312	-9.4
East Coast (PADD 1)	507	549	-42	1,041	-51.3	973	-47.9	564	903	-37.6
Midwest (PADD 2)	1,932	1,868	65	1,671	15.7	1,569	23.1	1,959	1,580	24.0
Gulf Coast (PADD 3)	3,842	3,246	597	4,372	-12.1	3,730	3.0	3,700	4,433	-16.5
Rocky Mountain (PADD 4)	395	228	167	304	30.1	309	28.0	314	278	13.1
West Coast (PADD 5)	1,055	971	84	1,011	4.3	1,000	5.4	994	1,118	-11.2
Imports by SPR	0	0	0	0	–	0	–	0	0	–
Imports into SPR by Others	0	0	0	0	–	0	–	0	0	–
Exports[3]	57	57	0	43	32.6	36	58.3	57	42	34.9
Total Products Net Imports	-1,379	-1,835	456	-481	– –	-742	– –	-1,558	-597	– –
Imports	2,007	1,551	456	2,420	-17.1	2,102	-4.5	1,828	2,211	-17.3
East Coast (PADD 1)	1,162	898	265	1,263	-8.0	999	16.3	1,069	1,117	-4.4
Midwest (PADD 2)	76	80	-4	181	-58.0	102	-25.9	84	209	-60.1
Gulf Coast (PADD 3)	603	528	75	824	-26.9	904	-33.3	550	687	-19.9
Rocky Mountain (PADD 4)	14	11	3	15	-6.3	13	6.8	13	18	-27.5
West Coast (PADD 5)	152	34	119	137	11.4	83	83.9	113	179	-37.0
Motor Gasoline	599	671	-72	521	15.0	601	-0.3	670	528	26.9
Reformulated	0	0	0	0	–	0	–	0	0	–
Conventional	55	57	-2	102	-46.2	81	-32.4	48	62	-22.7
Blending Components	544	614	-70	418	30.1	519	4.7	622	467	33.4
Fuel Ethanol	0	0	0	37	-100.0	26	-100.0	0	42	-100.0
Kerosene-Type Jet Fuel	63	25	38	25	148.3	9	574.2	57	32	77.7
Distillate Fuel Oil	226	85	141	242	-6.5	128	77.3	170	194	-12.3
15 ppm sulfur and Under	112	84	28	167	-33.0	87	27.8	133	111	19.6
> 15 ppm to 500 ppm sulfur	0	0	0	0	–	0	–	0	4	-100.0
> 500 ppm to 2000 ppm sulfur	115	1	113	75	52.1	40	184.8	37	68	-45.3
> 2000 ppm sulfur	0	0	0	0	–	0	–	0	11	-100.0
Residual Fuel Oil	233	127	106	368	-36.7	221	5.7	181	325	-44.2
Propane/Propylene	121	133	-13	174	-30.4	132	-8.7	129	175	-26.5
Other Oils	765	509	256	1,053	-27.4	985	-22.4	620	914	-32.1
Exports	3,386	3,386	0	2,901	16.7	2,844	19.1	3,386	2,808	20.6

– – = Not Applicable.
– = Data Not Available.
1 Includes estimated exports of crude oil, refined petroleum products, and fuel ethanol.
2 Prior to June 4, 2010, included "Imports into SPR by Others."
3 Crude oil exports are restricted to: (1) crude oil derived from fields under the State waters of Alaska's Cook Inlet; (2) Alaskan North Slope crude oil; (3) certain domestically produced crude oil destined for Canada; (4) shipments to U.S. territories; and (5) California crude oil to Pacific Rim countries.
Notes: Data may not add to total due to independent rounding. Differences and percent changes are calculated using unrounded numbers.
Source: See page 29.

Table 8. Preliminary Crude Imports by Country of Origin (For the Top 10 Importing Countries of 2012)[1]
(Thousand Barrels per Day)

Countries[2]	2012 Percentage [3]	Current Week	Last Week		Year Ago		2 Years Ago		Four-Week Averages		
		12/13/13	12/6/13	Difference	12/14/12	Percent Change	12/16/11	Percent Change	12/13/13	12/14/12	Percent Change
Crude Imports By Country of Origin											
Canada	28.4	2,786	2,316	470	2,333	19.4	2,133	30.6	2,577	2,100	22.7
Saudi Arabia	16.0	1,905	1,295	610	1,504	26.7	1,251	52.3	1,516	1,420	6.8
Mexico	11.4	947	1,161	-214	1,111	-14.8	603	57.0	1,065	1,072	-0.6
Venezuela	10.7	779	783	-4	1,097	-29.0	656	18.8	719	1,033	-30.4
Iraq	5.6	143	120	23	380	-62.4	71	101.4	209	507	-58.9
Nigeria	4.8	0	136	-136	512	-100.0	505	-100.0	102	519	-80.3
Colombia	4.7	127	114	13	346	-63.3	421	-69.8	168	451	-62.8
Kuwait	3.6	237	127	110	254	-6.7	173	37.0	353	261	35.2
Angola	2.6	128	223	-95	49	161.2	443	-71.1	107	74	44.4
Brazil	2.2	134	64	70	71	88.7	198	-32.3	140	95	47.5

– = Data Not Available.
[1] Preliminary data collected weekly. See the Petroleum Supply Monthly for updated data or the Petroleum Supply Annual for final data.
[2] Countries reported represent the top 10 countries based on annual import volumes from the PSM data as published on 2/27/13 from the prior year full year. Some data estimated.
[3] Calculated from annualized import data of each country as a percentage of the total imports from the last full calendar year of the Petroleum Supply Monthly as published on 2/27/13.
Notes: Data may not add to total due to independent rounding. Differences and percent changes are calculated using unrounded numbers.
Source: See page 29.

Table 9. U.S. and PAD District Weekly Estimates
(Thousand Barrels per Day Except Where Noted)

Product/Region	Current Week	Last Week	Year Ago	2 Years Ago	Four-Week Averages	
	12/13/13	12/6/13	12/14/12	12/16/11	12/13/13	12/14/12
Crude Oil Production						
Domestic Production[1]	8,058	8,075	6,863	5,862	8,041	6,838
Alaska	539	532	563	605	535	559
Lower 48	7,519	7,543	6,300	5,257	7,506	6,279
Refiner Inputs and Utilization						
Crude Oil Inputs	15,931	16,131	15,594	14,604	15,930	15,391
East Coast (PADD 1)	1,021	1,099	954	938	1,023	944
Midwest (PADD 2)	3,563	3,693	3,486	3,497	3,607	3,420
Gulf Coast (PADD 3)	8,363	8,286	8,277	7,214	8,307	8,148
Rocky Mountain (PADD 4)	573	570	592	559	581	583
West Coast (PADD 5)	2,412	2,484	2,285	2,396	2,413	2,295
Gross Inputs	16,310	16,501	15,918	15,063	16,295	15,694
East Coast (PADD 1)	1,113	1,106	1,040	939	1,074	979
Midwest (PADD 2)	3,565	3,691	3,442	3,522	3,609	3,381
Gulf Coast (PADD 3)	8,458	8,448	8,419	7,499	8,417	8,320
Rocky Mountain (PADD 4)	574	573	599	561	584	587
West Coast (PADD 5)	2,599	2,683	2,419	2,542	2,612	2,425
Operable Capacity[2]	17,818	17,818	17,395	17,736	17,817	17,388
East Coast (PADD 1)	1,297	1,297	1,293	1,618	1,296	1,293
Midwest (PADD 2)	3,769	3,769	3,720	3,721	3,769	3,715
Gulf Coast (PADD 3)	9,093	9,093	8,725	8,646	9,093	8,725
Rocky Mountain (PADD 4)	630	630	624	624	630	624
West Coast (PADD 5)	3,029	3,029	3,032	3,128	3,029	3,030
Percent Utilization[3]	91.5	92.6	91.5	84.9	91.5	90.3
East Coast (PADD 1)	85.8	85.3	80.4	58.0	82.9	75.8
Midwest (PADD 2)	94.6	97.9	92.5	94.6	95.7	91.0
Gulf Coast (PADD 3)	93.0	92.9	96.5	86.7	92.6	95.4
Rocky Mountain (PADD 4)	91.2	90.9	95.9	89.9	92.6	94.1
West Coast (PADD 5)	85.8	88.6	79.8	81.3	86.2	80.0
Refiner and Blender Net Inputs						
Motor Gasoline Blending Components	408	426	122	514	511	-47
East Coast (PADD 1)	2,003	2,072	1,911	2,107	2,060	1,947
Midwest (PADD 2)	287	252	119	107	309	66
Gulf Coast (PADD 3)	-2,029	-2,047	-2,135	-1,802	-2,024	-2,132
Rocky Mountain (PADD 4)	8	16	-26	-11	3	-29
West Coast (PADD 5)	140	134	252	113	163	102
RBOB	414	301	293	436	424	306
East Coast (PADD 1)	552	519	476	510	597	548
Midwest (PADD 2)	29	-1	31	41	4	24
Gulf Coast (PADD 3)	-252	-261	-266	-214	-248	-270
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	85	43	52	99	71	3
CBOB	35	-90	-161	24	-26	-332
East Coast (PADD 1)	1,390	1,322	1,311	1,308	1,300	1,268
Midwest (PADD 2)	136	131	5	108	186	11
Gulf Coast (PADD 3)	-1,554	-1,657	-1,558	-1,473	-1,605	-1,694
Rocky Mountain (PADD 4)	-8	-14	-24	-11	-11	-28
West Coast (PADD 5)	72	129	105	91	104	111
GTAB	22	58	-30	122	52	36
East Coast (PADD 1)	22	58	-30	122	52	36
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
All Other Blending Components	-63	157	20	-68	62	-57
East Coast (PADD 1)	40	172	154	166	111	94
Midwest (PADD 2)	122	122	83	-42	119	31
Gulf Coast (PADD 3)	-223	-129	-311	-115	-170	-168
Rocky Mountain (PADD 4)	16	30	-2	0	15	-2
West Coast (PADD 5)	-17	-38	95	-78	-13	-13
Fuel Ethanol	827	826	823	835	832	810
East Coast (PADD 1)	303	303	301	317	304	301
Midwest (PADD 2)	228	233	229	225	231	223
Gulf Coast (PADD 3)	122	129	126	126	127	124
Rocky Mountain (PADD 4)	25	24	24	23	24	23
West Coast (PADD 5)	149	138	144	144	144	139
Refiner and Blender Net Production						
Finished Motor Gasoline[4]	9,311	8,982	8,888	9,390	9,173	8,931
Finished Motor Gasoline (less Adjustment)[5]	9,376	9,428	9,149	9,247	9,403	9,029
East Coast (PADD 1)	2,871	2,839	2,825	2,916	2,862	2,846
Midwest (PADD 2)	2,546	2,573	2,283	2,380	2,529	2,209
Gulf Coast (PADD 3)	2,087	2,110	2,145	2,165	2,114	2,143
Rocky Mountain (PADD 4)	311	357	299	275	324	294
West Coast (PADD 5)	1,562	1,550	1,597	1,511	1,575	1,537
Adjustment[6]	-65	-446	-261	143	-231	-98
Reformulated[5]	2,983	2,891	2,985	3,094	2,958	2,923
East Coast (PADD 1)	1,178	1,155	1,156	1,256	1,174	1,158
Midwest (PADD 2)	372	354	371	378	358	357
Gulf Coast (PADD 3)	352	369	395	392	374	387
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	1,081	1,013	1,063	1,069	1,052	1,020

See footnotes at end of table.

Table 9. U.S. and PAD District Weekly Estimates
(Thousand Barrels per Day Except Where Noted) — Continued

Product/Region	Current Week	Last Week	Year Ago	2 Years Ago	Four-Week Averages	
	12/13/13	12/6/13	12/14/12	12/16/11	12/13/13	12/14/12
Refiner and Blender Net Production						
Blended with Fuel Ethanol[5]	2,983	2,891	2,985	3,094	2,958	2,923
East Coast (PADD 1)	1,178	1,155	1,156	1,256	1,174	1,158
Midwest (PADD 2)	372	354	371	378	358	357
Gulf Coast (PADD 3)	352	369	395	392	374	387
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	1,081	1,013	1,063	1,069	1,052	1,020
Other[5]	0	0	0	0	0	0
East Coast (PADD 1)	0	0	0	0	0	0
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
Conventional[5]	6,393	6,537	6,165	6,153	6,445	6,106
East Coast (PADD 1)	1,693	1,684	1,669	1,660	1,688	1,687
Midwest (PADD 2)	2,173	2,219	1,912	2,002	2,171	1,852
Gulf Coast (PADD 3)	1,734	1,740	1,750	1,773	1,740	1,756
Rocky Mountain (PADD 4)	311	357	299	275	324	294
West Coast (PADD 5)	481	537	535	442	523	517
Blended with Fuel Ethanol[5]	5,300	5,406	5,238	5,262	5,375	5,174
East Coast (PADD 1)	1,874	1,877	1,842	1,902	1,885	1,850
Midwest (PADD 2)	1,914	1,984	1,905	1,881	1,956	1,866
Gulf Coast (PADD 3)	879	917	880	877	904	863
Rocky Mountain (PADD 4)	246	238	238	228	242	229
West Coast (PADD 5)	387	389	373	374	387	366
Ed55 and Lower	5,299	5,404	5,237	5,260	5,374	5,173
East Coast (PADD 1)	1,874	1,877	1,842	1,902	1,885	1,850
Midwest (PADD 2)	1,913	1,983	1,905	1,880	1,955	1,866
Gulf Coast (PADD 3)	879	917	880	876	904	863
Rocky Mountain (PADD 4)	246	238	238	228	242	229
West Coast (PADD 5)	387	389	373	374	387	366
Greater than Ed55	2	2	1	2	2	1
East Coast (PADD 1)	0	0	0	0	0	0
Midwest (PADD 2)	1	1	0	1	1	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
Other[5]	1,093	1,131	926	891	1,070	932
East Coast (PADD 1)	-181	-193	-173	-241	-198	-163
Midwest (PADD 2)	259	234	7	121	214	-14
Gulf Coast (PADD 3)	855	823	870	897	836	893
Rocky Mountain (PADD 4)	64	119	61	47	82	65
West Coast (PADD 5)	95	148	162	68	135	151
Kerosene-Type Jet Fuel	1,595	1,619	1,488	1,420	1,570	1,442
East Coast (PADD 1)	65	66	66	52	65	62
Midwest (PADD 2)	225	240	206	210	226	198
Gulf Coast (PADD 3)	780	840	822	675	800	777
Rocky Mountain (PADD 4)	26	27	23	30	26	25
West Coast (PADD 5)	500	445	370	454	454	380
Commercial[7]	1,513	1,515	1,348	1,303	1,475	1,308
East Coast (PADD 1)	65	66	66	52	65	62
Midwest (PADD 2)	207	226	190	202	211	181
Gulf Coast (PADD 3)	729	733	742	624	735	685
Rocky Mountain (PADD 4)	24	26	18	27	24	22
West Coast (PADD 5)	488	463	331	397	440	358
Military[7]	82	105	140	118	96	134
East Coast (PADD 1)	0	0	0	0	0	0
Midwest (PADD 2)	18	14	16	8	15	17
Gulf Coast (PADD 3)	51	107	80	51	65	92
Rocky Mountain (PADD 4)	2	1	5	2	2	3
West Coast (PADD 5)	12	-18	40	57	14	21
Distillate Fuel Oil	4,956	5,262	4,880	5,008	5,088	4,762
East Coast (PADD 1)	344	332	387	375	324	332
Midwest (PADD 2)	1,143	1,168	1,042	1,136	1,134	1,026
Gulf Coast (PADD 3)	2,780	2,965	2,688	2,688	2,873	2,655
Rocky Mountain (PADD 4)	171	195	204	203	187	204
West Coast (PADD 5)	518	601	558	607	571	545
15 ppm sulfur and Under	4,482	4,824	4,289	4,132	4,624	4,269
East Coast (PADD 1)	254	222	262	194	234	222
Midwest (PADD 2)	1,135	1,169	1,037	1,043	1,130	1,035
Gulf Coast (PADD 3)	2,431	2,663	2,303	2,186	2,543	2,302
Rocky Mountain (PADD 4)	163	190	197	186	179	197
West Coast (PADD 5)	500	579	489	522	537	512
> 15 ppm to 500 ppm sulfur	150	171	121	225	146	146
East Coast (PADD 1)	34	15	16	-5	13	11
Midwest (PADD 2)	-3	14	5	92	7	2
Gulf Coast (PADD 3)	100	126	82	93	109	113
Rocky Mountain (PADD 4)	11	7	5	15	8	6
West Coast (PADD 5)	8	10	13	30	8	13
> 500 ppm sulfur	324	267	470	651	318	348
East Coast (PADD 1)	56	95	109	186	77	99
Midwest (PADD 2)	11	-15	-1	0	-4	-12
Gulf Coast (PADD 3)	249	176	304	408	220	239
Rocky Mountain (PADD 4)	-3	-1	2	1	-1	0
West Coast (PADD 5)	11	12	56	54	26	20

See footnotes at end of table.

Table 9. U.S. and PAD District Weekly Estimates
(Thousand Barrels per Day Except Where Noted) — Continued

Product/Region	Current Week	Last Week	Year Ago	2 Years Ago	Four-Week Averages	
	12/13/13	12/6/13	12/14/12	12/16/11	12/13/13	12/14/12
Refiner and Blender Net Production						
Residual Fuel Oil	448	442	372	493	435	398
East Coast (PADD 1)	35	38	54	54	38	53
Midwest (PADD 2)	70	60	42	58	61	42
Gulf Coast (PADD 3)	226	219	179	268	202	198
Rocky Mountain (PADD 4)	14	15	13	11	14	12
West Coast (PADD 5)	104	111	83	102	120	94
Propane/Propylene[8]	1,405	1,479	1,261	1,187	1,452	1,339
East Coast (PADD 1)	140	142	72	66	130	67
Midwest (PADD 2)	246	285	268	255	271	275
Gulf Coast (PADD 3)	878	886	787	757	898	823
PADDs 4 and 5	141	167	134	109	152	175
Ethanol Plant Production						
Fuel Ethanol	928	944	822	943	928	821
East Coast (PADD 1)	W	W	W	W	W	W
Midwest (PADD 2)	859	874	770	878	858	768
Gulf Coast (PADD 3)	W	W	W	W	W	W
Rocky Mountain (PADD 4)	W	W	W	W	W	W
West Coast (PADD 5)	W	W	W	W	W	W
Stocks (Million Barrels)[9]						
Crude Oil (including SPR)[10]	1,068.3	1,071.2	1,066.6	1,019.5	– –	– –
Commercial	372.3	375.2	371.6	323.6	– –	– –
East Coast (PADD 1)	10.0	10.2	10.5	9.7	– –	– –
Midwest (PADD 2)	110.0	110.3	111.1	94.1	– –	– –
Cushing, Oklahoma[11]	40.6	41.2	47.0	30.2	– –	– –
Gulf Coast (PADD 3)	181.4	184.4	176.7	149.0	– –	– –
Rocky Mountain (PADD 4)	19.7	19.8	18.0	16.0	– –	– –
West Coast (PADD 5)	51.2	50.6	55.4	54.7	– –	– –
Alaska In-Transit[12]	6.0	4.9	3.4	3.1	– –	– –
SPR[13]	696.0	696.0	695.0	696.0	– –	– –
Total Motor Gasoline	220.5	219.1	219.3	218.4	– –	– –
East Coast (PADD 1)	56.5	57.3	49.1	57.8	– –	– –
Midwest (PADD 2)	50.3	49.0	49.9	49.9	– –	– –
Gulf Coast (PADD 3)	76.3	74.9	80.6	75.1	– –	– –
Rocky Mountain (PADD 4)	7.5	7.9	7.1	7.2	– –	– –
West Coast (PADD 5)	29.9	30.1	32.6	28.4	– –	– –
Finished Motor Gasoline	41.5	41.6	55.7	60.6	– –	– –
Reformulated	0.0	0.0	0.0	0.3	– –	– –
East Coast (PADD 1)	0.0	0.0	0.0	0.3	– –	– –
Midwest (PADD 2)	0.0	0.0	0.0	0.0	– –	– –
Gulf Coast (PADD 3)	0.0	0.0	0.0	0.0	– –	– –
Rocky Mountain (PADD 4)	0.0	0.0	0.0	0.0	– –	– –
West Coast (PADD 5)	0.0	0.0	0.0	0.0	– –	– –
Blended with Fuel Ethanol	0.0	0.0	0.0	0.3	– –	– –
East Coast (PADD 1)	0.0	0.0	0.0	0.3	– –	– –
Midwest (PADD 2)	0.0	0.0	0.0	0.0	– –	– –
Gulf Coast (PADD 3)	0.0	0.0	0.0	0.0	– –	– –
Rocky Mountain (PADD 4)	0.0	0.0	0.0	0.0	– –	– –
West Coast (PADD 5)	0.0	0.0	0.0	0.0	– –	– –
Other	0.0	0.0	0.0	0.0	– –	– –
East Coast (PADD 1)	0.0	0.0	0.0	0.0	– –	– –
Midwest (PADD 2)	0.0	0.0	0.0	0.0	– –	– –
Gulf Coast (PADD 3)	0.0	0.0	0.0	0.0	– –	– –
Rocky Mountain (PADD 4)	0.0	0.0	0.0	0.0	– –	– –
West Coast (PADD 5)	0.0	0.0	0.0	0.0	– –	– –
Conventional	41.4	41.5	55.6	60.3	– –	– –
East Coast (PADD 1)	7.8	7.4	8.0	10.7	– –	– –
Midwest (PADD 2)	13.3	13.4	21.9	24.6	– –	– –
Gulf Coast (PADD 3)	12.5	12.3	17.2	16.3	– –	– –
Rocky Mountain (PADD 4)	4.1	4.4	4.2	4.7	– –	– –
West Coast (PADD 5)	3.7	4.0	4.3	4.0	– –	– –
Blended with Fuel Ethanol	0.3	0.3	0.3	0.3	– –	– –
East Coast (PADD 1)	0.0	0.0	0.0	0.0	– –	– –
Midwest (PADD 2)	0.1	0.1	0.2	0.2	– –	– –
Gulf Coast (PADD 3)	0.1	0.1	0.1	0.1	– –	– –
Rocky Mountain (PADD 4)	0.0	0.0	0.1	0.0	– –	– –
West Coast (PADD 5)	0.0	0.0	0.0	0.0	– –	– –
Ed55 and Lower	0.3	0.3	0.3	0.3	– –	– –
East Coast (PADD 1)	0.0	0.0	0.0	0.0	– –	– –
Midwest (PADD 2)	0.1	0.1	0.2	0.2	– –	– –
Gulf Coast (PADD 3)	0.1	0.1	0.1	0.1	– –	– –
Rocky Mountain (PADD 4)	0.0	0.0	0.1	0.0	– –	– –
West Coast (PADD 5)	0.0	0.0	0.0	0.0	– –	– –
Greater than Ed55	0.0	0.0	0.0	0.0	– –	– –
East Coast (PADD 1)	0.0	0.0	0.0	0.0	– –	– –
Midwest (PADD 2)	0.0	0.0	0.0	0.0	– –	– –
Gulf Coast (PADD 3)	0.0	0.0	0.0	0.0	– –	– –
Rocky Mountain (PADD 4)	0.0	0.0	0.0	0.0	– –	– –
West Coast (PADD 5)	0.0	0.0	0.0	0.0	– –	– –
Other	41.2	41.3	55.3	60.0	– –	– –
East Coast (PADD 1)	7.8	7.4	8.0	10.7	– –	– –
Midwest (PADD 2)	13.2	13.2	21.7	24.5	– –	– –
Gulf Coast (PADD 3)	12.5	12.3	17.2	16.2	– –	– –
Rocky Mountain (PADD 4)	4.0	4.3	4.1	4.7	– –	– –
West Coast (PADD 5)	3.7	4.0	4.3	4.0	– –	– –

See footnotes at end of table.

Table 9. U.S. and PAD District Weekly Estimates
(Thousand Barrels per Day Except Where Noted) — Continued

Product/Region	Current Week	Last Week	Year Ago	2 Years Ago	Four-Week Averages	
	12/13/13	12/6/13	12/14/12	12/16/11	12/13/13	12/14/12
	Stocks (Million Barrels)[9]					
Motor Gasoline Blending Components	179.0	177.6	163.7	157.8	– –	– –
East Coast (PADD 1)	48.7	49.8	41.1	46.8	– –	– –
Midwest (PADD 2)	37.0	35.6	28.0	25.3	– –	– –
Gulf Coast (PADD 3)	63.8	62.6	63.3	58.8	– –	– –
Rocky Mountain (PADD 4)	3.4	3.5	2.9	2.5	– –	– –
West Coast (PADD 5)	26.1	26.0	28.3	24.4	– –	– –
RBOB	46.0	47.2	48.0	45.6	– –	– –
East Coast (PADD 1)	16.2	17.4	14.8	16.5	– –	– –
Midwest (PADD 2)	5.8	6.0	6.2	5.5	– –	– –
Gulf Coast (PADD 3)	10.4	9.9	10.7	11.0	– –	– –
Rocky Mountain (PADD 4)	0.0	0.0	0.0	0.0	– –	– –
West Coast (PADD 5)	13.7	13.9	16.3	12.6	– –	– –
CBOB	83.1	80.4	66.3	61.8	– –	– –
East Coast (PADD 1)	23.5	23.8	19.5	21.2	– –	– –
Midwest (PADD 2)	24.3	22.4	13.9	12.0	– –	– –
Gulf Coast (PADD 3)	29.2	28.1	27.6	23.8	– –	– –
Rocky Mountain (PADD 4)	1.4	1.6	1.2	0.7	– –	– –
West Coast (PADD 5)	4.6	4.5	4.1	4.2	– –	– –
GTAB	0.4	0.5	0.6	0.9	– –	– –
East Coast (PADD 1)	0.4	0.5	0.6	0.9	– –	– –
Midwest (PADD 2)	0.0	0.0	0.0	0.0	– –	– –
Gulf Coast (PADD 3)	0.0	0.0	0.0	0.0	– –	– –
Rocky Mountain (PADD 4)	0.0	0.0	0.0	0.0	– –	– –
West Coast (PADD 5)	0.0	0.0	0.0	0.0	– –	– –
All Other Blending Components	49.5	49.5	48.8	49.6	– –	– –
East Coast (PADD 1)	8.6	8.1	6.2	8.3	– –	– –
Midwest (PADD 2)	6.9	7.2	7.9	7.8	– –	– –
Gulf Coast (PADD 3)	24.2	24.6	25.1	24.1	– –	– –
Rocky Mountain (PADD 4)	2.0	1.9	1.7	1.8	– –	– –
West Coast (PADD 5)	7.9	7.7	8.0	7.7	– –	– –
Fuel Ethanol	15.6	15.4	20.8	17.7	– –	– –
East Coast (PADD 1)	5.1	4.9	7.0	6.7	– –	– –
Midwest (PADD 2)	5.5	5.4	6.9	5.5	– –	– –
Gulf Coast (PADD 3)	2.8	2.8	4.0	3.0	– –	– –
Rocky Mountain (PADD 4)	0.3	0.3	0.3	0.3	– –	– –
West Coast (PADD 5)	1.9	1.9	2.6	2.2	– –	– –
Kerosene-Type Jet Fuel	37.0	36.6	39.3	41.5	– –	– –
East Coast (PADD 1)	7.7	8.2	8.8	9.6	– –	– –
Midwest (PADD 2)	7.1	6.6	6.9	8.4	– –	– –
Gulf Coast (PADD 3)	12.6	12.8	13.2	14.0	– –	– –
Rocky Mountain (PADD 4)	0.5	0.6	0.6	0.6	– –	– –
West Coast (PADD 5)	9.1	8.4	9.8	8.9	– –	– –
Distillate Fuel Oil[14]	116.0	118.1	117.0	139.1	– –	– –
East Coast (PADD 1)	36.5	37.7	39.2	54.4	– –	– –
New England (PADD 1A)	6.1	6.6	5.8	11.6	– –	– –
Central Atlantic (PADD 1B)	19.0	19.5	23.5	32.1	– –	– –
Lower Atlantic (PADD 1C)	11.3	11.6	10.0	10.7	– –	– –
Midwest (PADD 2)	25.9	26.0	25.4	28.4	– –	– –
Gulf Coast (PADD 3)	36.9	37.3	34.0	40.1	– –	– –
Rocky Mountain (PADD 4)	3.8	3.7	4.0	3.8	– –	– –
West Coast (PADD 5)	12.9	13.4	14.2	12.5	– –	– –
15 ppm sulfur and Under	94.9	95.1	85.1	89.8	– –	– –
East Coast (PADD 1)	24.9	24.3	20.1	20.2	– –	– –
New England (PADD 1A)	1.9	1.7	1.6	2.0	– –	– –
Central Atlantic (PADD 1B)	12.7	12.5	10.2	10.0	– –	– –
Lower Atlantic (PADD 1C)	10.4	10.1	8.3	8.1	– –	– –
Midwest (PADD 2)	24.7	24.7	23.7	26.1	– –	– –
Gulf Coast (PADD 3)	30.3	30.7	25.6	30.0	– –	– –
Rocky Mountain (PADD 4)	3.4	3.4	3.7	3.4	– –	– –
West Coast (PADD 5)	11.6	11.9	12.0	10.1	– –	– –
> 15 ppm to 500 ppm sulfur	3.9	3.8	6.4	10.2	– –	– –
East Coast (PADD 1)	1.1	1.2	0.8	3.5	– –	– –
New England (PADD 1A)	0.0	0.0	0.0	0.1	– –	– –
Central Atlantic (PADD 1B)	0.8	0.7	0.4	2.4	– –	– –
Lower Atlantic (PADD 1C)	0.3	0.4	0.4	1.0	– –	– –
Midwest (PADD 2)	0.6	0.7	1.0	1.4	– –	– –
Gulf Coast (PADD 3)	1.7	1.6	3.4	4.0	– –	– –
Rocky Mountain (PADD 4)	0.2	0.2	0.2	0.2	– –	– –
West Coast (PADD 5)	0.3	0.2	0.9	1.2	– –	– –
> 500 ppm sulfur[14]	17.1	19.2	25.5	39.1	– –	– –
East Coast (PADD 1)	10.4	12.2	18.3	30.8	– –	– –
New England (PADD 1A)	4.2	4.8	4.2	9.5	– –	– –
Central Atlantic (PADD 1B)	5.6	6.3	12.8	19.8	– –	– –
Lower Atlantic (PADD 1C)	0.6	1.1	1.3	1.5	– –	– –
Midwest (PADD 2)	0.6	0.6	0.7	0.9	– –	– –
Gulf Coast (PADD 3)	4.9	5.0	5.0	6.1	– –	– –
Rocky Mountain (PADD 4)	0.2	0.2	0.1	0.2	– –	– –
West Coast (PADD 5)	1.0	1.2	1.4	1.2	– –	– –
Residual Fuel Oil	35.2	34.8	37.1	38.7	– –	– –
East Coast (PADD 1)	8.7	8.9	10.4	11.0	– –	– –
New England (PADD 1A)	0.4	0.5	0.4	0.6	– –	– –
Central Atlantic (PADD 1B)	5.8	5.9	7.3	8.4	– –	– –
Lower Atlantic (PADD 1C)	2.5	2.5	2.7	2.0	– –	– –
Midwest (PADD 2)	1.4	1.3	1.5	1.6	– –	– –
Gulf Coast (PADD 3)	19.6	19.3	20.3	21.1	– –	– –
Rocky Mountain (PADD 4)	0.2	0.2	0.2	0.2	– –	– –
West Coast (PADD 5)	5.3	5.1	4.7	4.8	– –	– –

See footnotes at end of table.

Table 9. U.S. and PAD District Weekly Estimates
(Thousand Barrels per Day Except Where Noted) — Continued

Product/Region	Current Week	Last Week	Year Ago	2 Years Ago	Four-Week Averages	
	12/13/13	12/6/13	12/14/12	12/16/11	12/13/13	12/14/12
Stocks (Million Barrels)[9]						
Propane/Propylene	50.0	52.6	69.2	56.9	– –	– –
East Coast (PADD 1)	4.2	4.5	5.1	6.0	– –	– –
New England (PADD 1A)	0.2	0.3	0.7	0.6	– –	– –
Central Atlantic (PADD 1B)	2.6	2.8	2.4	3.2	– –	– –
Lower Atlantic (PADD 1C)	1.4	1.4	2.0	2.3	– –	– –
Midwest (PADD 2)	16.0	16.9	24.3	24.1	– –	– –
Gulf Coast (PADD 3)	27.1	28.3	37.1	24.9	– –	– –
PADD's 4 & 5	2.7	2.9	2.7	1.9	– –	– –
Propylene (Total U.S. Nonfuel Use)[15]	3.3	3.1	3.7	5.1	– –	– –
Other Oils[16]	226.6	233.8	222.1	202.0	– –	– –
Unfinished Oils	82.9	85.5	82.5	79.0	– –	– –
Kerosene	1.8	1.9	2.0	2.6	– –	– –
Asphalt and Road Oil	19.6	19.1	18.7	17.2	– –	– –
NGPLs/LRGs (Excluding Propane/Propylene)	92.3	97.6	91.8	77.8	– –	– –
Total Stocks (Excluding SPR)[14]	1,073.2	1,085.8	1,096.5	1,037.8	– –	– –
Total Stocks (Including SPR)[13,14]	1,769.2	1,781.7	1,791.5	1,733.8	– –	– –
Imports						
Total Crude Oil Incl SPR	7,732	6,862	8,399	7,581	7,530	8,312
Commercial[17]	7,732	6,862	8,399	7,581	7,530	8,312
East Coast (PADD 1)	507	549	1,041	973	564	903
Midwest (PADD 2)	1,932	1,868	1,671	1,569	1,959	1,580
Gulf Coast (PADD 3)	3,842	3,246	4,372	3,730	3,700	4,433
Rocky Mountain (PADD 4)	395	228	304	309	314	278
West Coast (PADD 5)	1,055	971	1,011	1,000	994	1,118
Imports by SPR	0	0	0	0	0	0
Imports into SPR by Others	0	0	0	0	0	0
Total Motor Gasoline	599	671	521	601	670	528
East Coast (PADD 1)	568	669	453	536	650	484
Midwest (PADD 2)	6	2	5	3	3	3
Gulf Coast (PADD 3)	14	0	43	62	11	30
Rocky Mountain (PADD 4)	0	0	0	0	0	1
West Coast (PADD 5)	11	0	19	0	7	10
Finished Motor Gasoline	55	57	102	81	48	62
East Coast (PADD 1)	49	56	90	19	42	40
Midwest (PADD 2)	3	2	2	0	2	2
Gulf Coast (PADD 3)	0	0	0	62	0	11
Rocky Mountain (PADD 4)	0	0	0	0	0	1
West Coast (PADD 5)	3	0	11	0	4	8
Reformulated	0	0	0	0	0	0
East Coast (PADD 1)	0	0	0	0	0	0
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
Blended with Fuel Ethanol	0	0	0	0	0	0
East Coast (PADD 1)	0	0	0	0	0	0
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
Other	0	0	0	0	0	0
East Coast (PADD 1)	0	0	0	0	0	0
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
Conventional	55	57	102	81	48	62
East Coast (PADD 1)	49	56	90	19	42	40
Midwest (PADD 2)	3	2	2	0	2	2
Gulf Coast (PADD 3)	0	0	0	62	0	11
Rocky Mountain (PADD 4)	0	0	0	0	0	1
West Coast (PADD 5)	3	0	11	0	4	8
Blended with Fuel Ethanol	0	0	1	0	1	1
East Coast (PADD 1)	0	0	0	0	0	0
Midwest (PADD 2)	0	0	1	0	1	1
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
Ed55 and Lower	0	0	1	0	1	1
East Coast (PADD 1)	0	0	0	0	0	0
Midwest (PADD 2)	0	0	1	0	1	1
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
Greater than Ed55	0	0	0	0	0	0
East Coast (PADD 1)	0	0	0	0	0	0
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
Other	55	57	101	81	47	61
East Coast (PADD 1)	49	56	90	19	42	40
Midwest (PADD 2)	3	1	1	0	1	1
Gulf Coast (PADD 3)	0	0	0	62	0	11
Rocky Mountain (PADD 4)	0	0	0	0	0	1
West Coast (PADD 5)	3	0	11	0	4	8

See footnotes at end of table.

Table 9. U.S. and PAD District Weekly Estimates
(Thousand Barrels per Day Except Where Noted) — Continued

Product/Region	Current Week 12/13/13	Last Week 12/6/13	Year Ago 12/14/12	2 Years Ago 12/16/11	Four-Week Averages 12/13/13	Four-Week Averages 12/14/12
Imports						
Motor Gasoline Blending Components	544	614	418	519	622	467
East Coast (PADD 1)	518	613	363	517	608	443
Midwest (PADD 2)	3	0	3	3	1	2
Gulf Coast (PADD 3)	14	0	43	0	11	19
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	9	0	9	0	3	2
RBOB	255	133	96	94	227	110
East Coast (PADD 1)	255	133	96	94	227	110
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
CBOB	41	20	34	36	46	59
East Coast (PADD 1)	32	20	25	36	43	57
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	9	0	9	0	3	2
GTAB	28	120	0	93	74	60
East Coast (PADD 1)	28	120	0	93	74	60
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
All Other Blending Components	220	341	289	297	276	237
East Coast (PADD 1)	203	340	242	295	264	216
Midwest (PADD 2)	3	0	3	3	1	2
Gulf Coast (PADD 3)	14	0	43	0	11	19
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
Fuel Ethanol	0	0	37	26	0	42
East Coast (PADD 1)	0	0	37	12	0	29
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	1
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	13	0	12
Kerosene-Type Jet Fuel	63	25	25	9	57	32
East Coast (PADD 1)	62	25	18	0	37	16
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	7	0	0	5
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	1	0	1	9	21	11
Distillate Fuel Oil	226	85	242	128	170	194
East Coast (PADD 1)	220	75	237	126	164	171
Midwest (PADD 2)	2	1	4	1	1	3
Gulf Coast (PADD 3)	0	0	0	0	0	4
Rocky Mountain (PADD 4)	0	0	1	1	0	0
West Coast (PADD 5)	4	9	1	0	5	15
15 ppm sulfur and Under	112	84	167	87	133	111
East Coast (PADD 1)	108	75	161	85	129	106
Midwest (PADD 2)	0	0	4	1	0	3
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	1	1	0	0
West Coast (PADD 5)	4	9	1	0	4	1
> 15 ppm to 500 ppm sulfur	0	0	0	0	0	4
East Coast (PADD 1)	0	0	0	0	0	0
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	4
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
> 500 ppm to 2000 ppm sulfur	115	1	75	40	37	68
East Coast (PADD 1)	112	0	75	40	35	54
Midwest (PADD 2)	2	1	0	0	1	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	1	0	0	1	14
> 2000 ppm sulfur	0	0	0	0	0	11
East Coast (PADD 1)	0	0	0	0	0	11
Midwest (PADD 2)	0	0	0	0	0	0
Gulf Coast (PADD 3)	0	0	0	0	0	0
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	0	0	0	0	0	0
Residual Fuel Oil	233	127	368	221	181	325
East Coast (PADD 1)	112	53	153	207	84	200
Midwest (PADD 2)	2	3	8	4	3	5
Gulf Coast (PADD 3)	68	62	107	9	78	74
Rocky Mountain (PADD 4)	0	0	0	0	0	0
West Coast (PADD 5)	51	9	100	0	17	47
Propane/Propylene	121	133	174	132	129	175
East Coast (PADD 1)	70	59	69	32	62	71
Midwest (PADD 2)	34	51	79	81	51	79
Gulf Coast (PADD 3)	0	0	0	0	0	0
PADDs 4 and 5	16	23	26	20	15	25
Other Oils	765	509	1,053	985	620	914
East Coast (PADD 1)	131	17	297	86	73	147
Midwest (PADD 2)	31	23	84	14	26	118
Gulf Coast (PADD 3)	520	466	667	833	462	573
Rocky Mountain (PADD 4)	2	1	2	0	4	8
West Coast (PADD 5)	81	2	2	53	56	68

See footnotes at end of table.

Table 9. U.S. and PAD District Weekly Estimates
(Thousand Barrels per Day Except Where Noted) — Continued

Product/Region	Current Week	Last Week	Year Ago	2 Years Ago	Four-Week Averages	
	12/13/13	12/6/13	12/14/12	12/16/11	12/13/13	12/14/12
Imports						
Kerosene	0	0	0	0	0	0
NGPLs/LRGs (Excluding Propane/Propylene)	21	18	84	84	31	136
Total Product Imports	2,007	1,551	2,420	2,102	1,828	2,211
East Coast (PADD 1)	1,162	898	1,263	999	1,069	1,117
Midwest (PADD 2)	76	80	181	102	84	209
Gulf Coast (PADD 3)	603	528	824	904	550	687
Rocky Mountain (PADD 4)	14	11	15	13	13	18
West Coast (PADD 5)	152	34	137	83	113	179
Total Imports (Incl SPR)	9,739	8,413	10,819	9,683	9,358	10,480
East Coast (PADD 1)	1,669	1,447	2,267	1,960	1,633	1,992
Midwest (PADD 2)	2,008	1,948	1,851	1,672	2,043	1,789
Gulf Coast (PADD 3)	4,445	3,774	5,196	4,634	4,250	5,119
Rocky Mountain (PADD 4)	409	239	319	322	327	295
West Coast (PADD 5)	1,207	1,005	1,148	1,070	1,106	1,285
Exports[18]						
Total	3,443	3,443	2,944	2,880	3,443	2,850
Crude Oil[19]	57	57	43	36	57	42
Products	3,386	3,386	2,901	2,844	3,386	2,808
Finished Motor Gasoline	363	363	462	523	363	369
Kerosene-Type Jet Fuel	126	126	109	73	126	101
Distillate Fuel Oil	1,394	1,394	1,063	1,072	1,394	1,035
Residual Fuel Oil	361	361	364	380	361	358
Propane/Propylene	288	288	132	67	288	118
Other Oils[20]	854	854	771	729	854	827
Net Imports (Incl SPR)						
Total	6,296	4,970	7,875	6,803	5,916	7,672
Crude Oil	7,675	6,805	8,356	7,545	7,473	8,269
Products	-1,379	-1,835	-481	-742	-1,558	-597
Product Supplied						
Total Product Supplied	20,996	18,554	19,955	19,324	19,790	19,022
Finished Motor Gasoline[4]	9,016	8,348	8,618	8,879	8,787	8,472
Kerosene-Type Jet Fuel	1,469	1,480	1,486	1,426	1,510	1,487
Distillate Fuel Oil	4,089	3,304	4,214	4,400	3,742	3,774
Residual Fuel Oil	265	205	433	534	274	322
Propane/Propylene	1,618	1,561	1,583	1,580	1,593	1,520
Other Oils[21]	4,539	3,657	3,621	2,505	3,885	3,448
Ultra Low Sulfur Distillate Reclassification						
< 15 ppm Distillate, Downgraded to 15 to 500 ppm	–	–	–	–	–	–

-- = Not Applicable.
W = Data Withheld.
1 Domestic crude oil production includes lease condensate and is estimated using a combination of short-term forecasts for the lower 48 states and the latest available production estimates from Alaska. For more details see Appendix B, under "Data Obtained Through Models."
2 Based on the latest reported monthly operable capacity.
3 Calculated as gross inputs divided by the latest reported monthly operable capacity. See Glossary. Percentages are calculated using unrounded numbers.
4 Finished motor gasoline production and product supplied include a weekly adjustment applied only to the U.S. total to correct for the imbalance created by blending of fuel ethanol and motor gasoline blending components. From 1993 to June 4, 2010, this adjustment was estimated from the latest monthly data and allocated to formulation and PAD District production data.
5 Excludes adjustments for fuel ethanol and motor gasoline blending components. Historical data prior to June 4, 2010 includes the adjustment allocated by PAD District and formulation.
6 Adjustment to correct for the imbalance created by the blending of fuel ethanol and motor gasoline blending components. For details see Appendix B.
7 Commercial and military kerosene jet fuel production is only collected from refiners and may not total to total kerosene jet fuel production.
8 Includes propane/propylene production from natural gas plants.
9 Includes those domestic and Customs-cleared foreign stocks held at, or in transit to, refineries, ethanol plants, and bulk terminals, as well as stocks in pipelines. Stocks (excluding propane) held at natural gas processing plants are included in "Other Oils." All stock levels are as of the end of the period.
10 Includes those domestic and Customs-cleared foreign crude oil stocks held at refineries, in pipelines, in lease tanks, and in transit to refineries.
11 Includes domestic and foreign crude oil stocks held in tank farms in Lincoln, Payne, and Creek counties in Oklahoma. Cushing, Oklahoma, is the designated delivery point for NYMEX crude oil futures contracts.
12 Includes crude oil stocks in transit by water between Alaska and the other States, the District of Columbia, Puerto Rico, and the Virgin Islands, as well as stocks held at transshipment terminals.
13 Includes non-U.S. stocks held under foreign or commercial storage agreements.
14 Excludes stocks located in the "Northeast Heating Oil Reserve." For details see Appendix C.
15 Nonfuel use propylene data collected from bulk terminal facilities only.
16 Includes weekly data for NGPLs and LRGs (except propane/propylene), kerosene, and asphalt and road oil; and estimated stocks of minor products based on monthly data.
17 Prior to June 4, 2010, included "Imports into SPR by Others."
18 Exports are estimated.
19 Crude oil exports are restricted to: (1) crude oil derived from fields under the State waters of Alaska's Cook Inlet; (2) Alaskan North Slope crude oil; (3) certain domestically produced crude oil destined for Canada; (4) shipments to U.S. territories; and (5) California crude oil to Pacific Rim countries.
20 Other Oil Exports = Total Exports less the exports of Finished Motor Gasoline, Kerosene-Type Jet Fuel, Distillate Fuel Oil, Residual Fuel Oil, and Propane/Propylene.
21 Other Oil Product Supplied = Total Product Supplied less the product supplied of Finished Motor Gasoline, Kerosene-Type Jet Fuel, Distillate Fuel Oil, Residual Fuel Oil, and Propane/Propylene.
Notes: Some data estimated (see Sources for clarification). Data may not add to total due to independent rounding. Differences and percent changes are calculated using unrounded numbers.
Source: See page 29.
R = Revised Data.

Table 10. U.S. World Crude Oil Prices
(Dollars per Barrel)

The data on this page are no longer available.

Table 11. Spot Prices of Crude Oil, Motor Gasoline, and Heating Oil, 2012 to Present
(Crude Oil in Dollars per Barrel, Products in Dollars per Gallon)

Year / Product	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
2012												
Crude Oil												
WTI - Cushing	100.27	102.20	106.16	103.32	94.66	82.30	87.90	94.13	94.51	89.49	86.53	87.86
Brent	110.69	119.33	125.45	119.75	110.34	95.16	102.62	113.36	112.86	111.71	109.06	109.49
Motor Gasoline												
Conventional												
New York Harbor	2.822	3.044	3.167	3.206	2.877	2.602	2.747	3.022	3.270	2.975	2.817	2.727
U.S. Gulf Coast	2.777	2.999	3.169	3.101	2.780	2.516	2.645	2.968	3.034	2.778	2.522	2.475
RBOB Regular												
Los Angeles	2.920	3.302	3.383	3.250	3.234	2.626	2.819	3.129	3.162	3.135	2.792	2.615
Heating Oils												
No. 2 Heating Oil												
New York Harbor	3.054	3.196	3.217	3.150	2.913	2.619	2.813	3.045	3.134	3.140	3.009	2.995
2013												
Crude Oil												
WTI - Cushing	94.76	95.31	92.94	92.02	94.51	95.77	104.67	106.57	106.29	100.54	93.86	–
Brent	112.96	116.05	108.47	102.25	102.56	102.92	107.93	111.28	111.60	109.08	107.79	–
Motor Gasoline												
Conventional												
New York Harbor	2.852	3.053	2.914	2.706	2.742	2.740	2.924	2.933	2.797	2.685	2.673	–
U.S. Gulf Coast	2.669	2.922	2.901	2.685	2.708	2.688	2.853	2.861	2.604	2.490	2.451	–
RBOB Regular												
Los Angeles	2.900	3.332	3.029	2.906	2.999	3.021	3.047	2.825	2.907	2.761	2.651	–
Heating Oils												
No. 2 Heating Oil												
New York Harbor	3.068	3.168	2.943	2.742	2.739	2.752	2.885	2.958	2.961	2.940	2.923	–

2013	Average for Week Ending:		Daily Prices:									
	Fri 11/22	Fri 11/29	Mon 12/2	Tue 12/3	Wed 12/4	Thu 12/5	Fri 12/6	Mon 12/9	Tue 12/10	Wed 12/11	Thu 12/12	Fri 12/13
Crude Oil												
WTI - Cushing	93.92	92.97	93.61	95.83	96.97	97.14	97.48	97.10	98.32	97.25	97.21	96.27
Brent	109.32	111.32	111.49	113.06	113.27	112.07	111.50	110.07	108.91	109.47	108.99	108.08
Motor Gasoline												
Conventional												
New York Harbor	2.725	2.707	2.698	2.746	2.725	2.727	2.740	2.677	2.698	2.670	2.643	2.639
U.S. Gulf Coast	2.583	2.509	2.470	2.503	2.485	2.480	2.492	2.459	2.481	2.429	2.398	2.377
RBOB Regular												
Los Angeles	2.636	2.666	2.655	2.708	2.690	2.650	2.722	2.639	2.661	2.569	2.543	2.514
Heating Oils												
No. 2 Heating Oil												
New York Harbor	2.952	3.027	3.042	3.055	3.043	3.037	3.043	2.998	3.012	3.003	2.963	2.956

– = Data Not Available.
Notes: Monthly and weekly prices are calculated by EIA from daily data. See Glossary for definitions of abbreviations.
See Appendix B, Technical Note 1, for more information about the data in this table.
Source: See page 29.

Figure 7. Daily Crude Oil and Petroleum Product Spot Prices, January 2012 to Present



Note: See Glossary for definitions of abbreviations.
Source: See page 29.

Figure 8. Daily Trans-Atlantic Spot Product Price Differentials: New York Harbor less Rotterdam (ARA), January 2012 to Present



Notes: See Glossary for definitions of abbreviations. See Appendix B, Technical Note 3, for more information about the data in this graph.
Source: See page 29.

Table 12. Spot Prices of Ultra-Low Sulfur Diesel Fuel, Kerosene-Type Jet Fuel, and Propane, 2012 to Present
(Dollars per Gallon)

Year / Product	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
2012												
No. 2 Distillate												
Ultra-Low Sulfur Diesel Fuel												
New York Harbor	3.080	3.223	3.302	3.242	2.987	2.710	2.921	3.179	3.229	3.236	3.180	3.070
U.S. Gulf Coast	3.034	3.178	3.270	3.217	2.947	2.667	2.879	3.143	3.186	3.157	2.997	2.960
Los Angeles	3.088	3.242	3.384	3.252	3.007	2.654	2.854	3.225	3.299	3.226	3.071	2.971
Kerosene-Type Jet Fuel												
U.S. Gulf Coast	3.087	3.207	3.256	3.226	2.974	2.678	2.892	3.156	3.191	3.111	2.960	2.940
Propane												
Mont Belvieu	1.294	1.220	1.261	1.196	0.954	0.788	0.874	0.901	0.910	0.962	0.890	0.797
2013												
No. 2 Distillate												
Ultra-Low Sulfur Diesel Fuel												
New York Harbor	3.103	3.237	3.037	2.900	2.888	2.891	3.018	3.068	3.048	2.995	2.938	–
U.S. Gulf Coast	3.044	3.200	3.007	2.879	2.843	2.861	2.981	3.040	3.014	2.935	2.857	–
Los Angeles	3.114	3.259	3.020	2.908	2.846	2.914	3.043	3.103	3.062	2.972	2.910	–
Kerosene-Type Jet Fuel												
U.S. Gulf Coast	3.091	3.218	2.969	2.808	2.725	2.769	2.894	3.003	2.934	2.885	2.830	–
Propane												
Mont Belvieu	0.838	0.862	0.895	0.939	0.932	0.863	0.920	1.061	1.107	1.136	1.181	–

2013	Average for Week Ending:		Daily Prices:									
	Fri 11/22	Fri 11/29	Mon 12/2	Tue 12/3	Wed 12/4	Thu 12/5	Fri 12/6	Mon 12/9	Tue 12/10	Wed 12/11	Thu 12/12	Fri 12/13
No. 2 Distillate												
Ultra-Low Sulfur Diesel Fuel												
New York Harbor	2.968	3.042	3.050	3.060	3.050	3.049	3.053	3.011	3.027	3.020	2.978	2.974
U.S. Gulf Coast	2.881	2.956	2.961	2.970	2.968	2.967	2.971	2.921	2.935	2.935	2.893	2.888
Los Angeles	2.920	3.026	3.056	3.068	3.035	3.007	3.016	2.953	2.967	2.965	2.923	2.933
Kerosene-Type Jet Fuel												
U.S. Gulf Coast	2.859	2.942	2.956	2.955	2.955	2.944	2.948	2.913	2.927	2.935	2.893	2.878
Propane												
Mont Belvieu	1.193	1.165	1.200	1.234	1.265	1.263	1.269	1.301	1.314	1.311	1.314	1.306

– = Data Not Available.
Notes: Monthly and weekly prices are calculated by EIA from daily data. See Glossary for definitions of abbreviations.
See Appendix B, Technical Note 2, for more information about the data in this table.
Source: See page 30.

Table 13. NYMEX Futures Prices of Crude Oil, Motor Gasoline, and No. 2 Heating Oil
(Crude Oil in Dollars per Barrel, all others in Dollars per Gallon)

	Mon 12/2	Tue 12/3	Wed 12/4	Thu 12/5	Fri 12/6	Mon 12/9	Tue 12/10	Wed 12/11	Thu 12/12	Fri 12/13
Crude Oil (WTI, Cushing, Oklahoma)										
January-2014	93.82	96.04	97.20	97.38	97.65	97.34	98.51	97.44	97.50	96.60
February-2014	94.10	96.27	97.43	97.61	97.90	97.56	98.66	97.72	97.82	96.93
March-2014	94.28	96.31	97.45	97.64	97.94	97.58	98.58	97.72	97.77	96.91
April-2014	94.27	96.07	97.18	97.36	97.66	97.29	98.19	97.39	97.42	96.55
Regular Reformulated Blendstock for Oxygenate Blending (RBOB) (New York Harbor)										
January-2014	2.678	2.724	2.719	2.713	2.727	2.675	2.683	2.661	2.635	2.629
February-2014	2.694	2.738	2.734	2.727	2.741	2.690	2.696	2.677	2.649	2.644
March-2014	2.716	2.759	2.753	2.745	2.758	2.708	2.713	2.696	2.668	2.662
April-2014	2.893	2.936	2.930	2.921	2.934	2.886	2.890	2.879	2.854	2.845
No. 2 Heating Oil (New York Harbor)										
January-2014	3.050	3.065	3.059	3.050	3.057	3.014	3.017	3.021	2.980	2.976
February-2014	3.048	3.065	3.060	3.050	3.057	3.015	3.017	3.022	2.981	2.975
March-2014	3.043	3.061	3.056	3.047	3.054	3.012	3.015	3.020	2.980	2.973
April-2014	3.033	3.052	3.047	3.038	3.045	3.004	3.007	3.013	2.974	2.966

Note: See Appendix B, Technical Note 3, for more information about the data in this table.
Source: See page 30.

Figure 9. Daily Futures Price Differentials: First Delivery Month Less Second Delivery Month, January 2011 to Present



Note: See Appendix B, Technical Note 4, for more information about the data in this graph.
Source: See page 30.

Table 14. U.S. Retail Motor Gasoline and On-Highway Diesel Fuel Prices, 2012 to Present
(Dollars per Gallon, Including Taxes)

Year / Product	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
2012												
Motor Gasoline	3.440	3.640	3.907	3.958	3.791	3.596	3.498	3.780	3.910	3.812	3.521	3.381
Conventional Areas	3.388	3.576	3.827	3.893	3.698	3.515	3.433	3.724	3.859	3.714	3.444	3.322
RFG Areas	3.546	3.770	4.071	4.090	3.982	3.760	3.630	3.895	4.013	4.011	3.678	3.500
Regular	3.380	3.579	3.852	3.900	3.732	3.539	3.439	3.722	3.849	3.746	3.452	3.310
East Coast (PADD 1)	3.429	3.639	3.805	3.900	3.667	3.428	3.408	3.684	3.836	3.736	3.497	3.396
New England (PADD 1A)	3.481	3.675	3.830	3.949	3.805	3.588	3.551	3.777	3.928	3.883	3.667	3.525
Central Atlantic (PADD 1B)	3.458	3.654	3.821	3.931	3.736	3.508	3.487	3.723	3.886	3.832	3.658	3.519
Lower Atlantic (PADD 1C)	3.391	3.616	3.787	3.862	3.574	3.321	3.306	3.626	3.773	3.621	3.326	3.266
Midwest (PADD 2)	3.328	3.476	3.823	3.828	3.645	3.513	3.436	3.775	3.860	3.624	3.346	3.228
Gulf Coast (PADD 3)	3.205	3.454	3.677	3.771	3.523	3.286	3.218	3.507	3.635	3.484	3.204	3.097
Rocky Mountain (PADD 4)	3.018	3.108	3.530	3.785	3.755	3.690	3.519	3.518	3.721	3.720	3.538	3.211
West Coast (PADD 5)	3.606	3.854	4.223	4.174	4.215	4.016	3.697	3.937	4.074	4.234	3.764	3.500
Midgrade	3.512	3.714	3.977	4.028	3.868	3.671	3.569	3.849	3.984	3.901	3.605	3.466
Premium	3.651	3.851	4.101	4.162	3.995	3.793	3.705	3.989	4.124	4.041	3.764	3.627
On-Highway Diesel Fuel	3.833	3.953	4.127	4.115	3.979	3.759	3.721	3.983	4.120	4.094	4.000	3.961
East Coast (PADD 1)	3.916	4.041	4.178	4.167	4.025	3.797	3.768	3.975	4.109	4.090	4.054	4.041
New England (PADD 1A)	4.049	4.158	4.256	4.267	4.157	3.952	3.876	4.044	4.202	4.220	4.202	4.172
Central Atlantic (PADD 1B)	4.006	4.131	4.260	4.261	4.108	3.891	3.851	4.034	4.174	4.183	4.174	4.145
Lower Atlantic (PADD 1C)	3.824	3.951	4.102	4.079	3.940	3.699	3.686	3.918	4.043	3.997	3.937	3.938
Midwest (PADD 2)	3.723	3.843	4.019	4.013	3.877	3.676	3.682	3.971	4.062	4.058	3.950	3.937
Gulf Coast (PADD 3)	3.757	3.878	4.041	4.025	3.885	3.678	3.639	3.875	4.018	3.993	3.891	3.857
Rocky Mountain (PADD 4)	3.827	3.859	4.078	4.109	3.997	3.851	3.697	3.996	4.236	4.221	4.095	3.866
West Coast (PADD 5)	4.022	4.162	4.414	4.379	4.247	3.958	3.837	4.180	4.392	4.290	4.123	4.023
California	4.103	4.251	4.474	4.419	4.316	4.027	3.917	4.240	4.456	4.376	4.170	4.076
2013												
Motor Gasoline	3.391	3.736	3.779	3.638	3.675	3.689	3.661	3.645	3.604	3.420	3.322	–
Conventional Areas	3.324	3.668	3.713	3.566	3.621	3.634	3.582	3.583	3.542	3.358	3.263	–
RFG Areas	3.527	3.874	3.913	3.784	3.786	3.799	3.821	3.771	3.731	3.547	3.441	–
Regular	3.319	3.670	3.711	3.570	3.615	3.626	3.591	3.574	3.532	3.344	3.243	–
East Coast (PADD 1)	3.439	3.697	3.710	3.537	3.482	3.496	3.562	3.576	3.518	3.346	3.300	–
New England (PADD 1A)	3.515	3.758	3.759	3.600	3.560	3.591	3.697	3.753	3.702	3.512	3.418	–
Central Atlantic (PADD 1B)	3.512	3.744	3.731	3.579	3.527	3.540	3.629	3.650	3.596	3.393	3.349	–
Lower Atlantic (PADD 1C)	3.362	3.643	3.679	3.487	3.424	3.434	3.472	3.468	3.405	3.260	3.228	–
Midwest (PADD 2)	3.203	3.648	3.657	3.541	3.733	3.748	3.535	3.523	3.500	3.271	3.145	–
Gulf Coast (PADD 3)	3.162	3.468	3.536	3.379	3.355	3.359	3.407	3.397	3.298	3.109	3.038	–
Rocky Mountain (PADD 4)	2.916	3.325	3.471	3.500	3.612	3.702	3.623	3.636	3.601	3.440	3.216	–
West Coast (PADD 5)	3.507	3.908	4.022	3.879	3.909	3.901	3.915	3.813	3.823	3.671	3.499	–
Midgrade	3.479	3.816	3.863	3.723	3.750	3.763	3.746	3.729	3.692	3.517	3.423	–
Premium	3.644	3.969	4.016	3.876	3.888	3.909	3.904	3.896	3.855	3.684	3.597	–
On-Highway Diesel Fuel	3.909	4.111	4.068	3.930	3.870	3.849	3.866	3.905	3.961	3.885	3.839	–
East Coast (PADD 1)	4.008	4.160	4.105	3.964	3.866	3.841	3.875	3.916	3.969	3.902	3.861	–
New England (PADD 1A)	4.165	4.295	4.229	4.081	3.991	3.982	4.010	4.045	4.077	4.031	3.996	–
Central Atlantic (PADD 1B)	4.099	4.224	4.164	4.019	3.919	3.910	3.938	3.976	4.033	3.961	3.913	–
Lower Atlantic (PADD 1C)	3.910	4.087	4.037	3.902	3.803	3.764	3.802	3.847	3.902	3.833	3.797	–
Midwest (PADD 2)	3.854	4.078	4.031	3.911	3.907	3.871	3.850	3.873	3.942	3.855	3.812	–
Gulf Coast (PADD 3)	3.834	4.024	4.006	3.843	3.756	3.750	3.794	3.829	3.875	3.796	3.755	–
Rocky Mountain (PADD 4)	3.691	3.974	3.991	3.872	3.834	3.854	3.848	3.927	3.936	3.886	3.842	–
West Coast (PADD 5)	4.007	4.258	4.193	4.048	3.972	3.958	3.997	4.057	4.119	4.046	3.975	–
California	4.083	4.325	4.245	4.134	4.040	4.023	4.068	4.138	4.209	4.134	4.048	–

2013	9/30	10/7	10/14	10/21	10/28	11/4	11/11	11/18	11/25	12/2	12/9	12/16
Motor Gasoline	3.499	3.441	3.430	3.435	3.372	3.343	3.274	3.298	3.372	3.353	3.350	3.321
Conventional Areas	3.425	3.369	3.368	3.382	3.311	3.284	3.210	3.239	3.320	3.290	3.287	3.245
RFG Areas	3.651	3.589	3.557	3.542	3.498	3.463	3.405	3.419	3.478	3.482	3.478	3.475
Regular	3.425	3.367	3.354	3.360	3.294	3.265	3.194	3.219	3.293	3.272	3.269	3.239
East Coast (PADD 1)	3.409	3.363	3.348	3.353	3.318	3.289	3.243	3.282	3.386	3.389	3.382	3.373
New England (PADD 1A)	3.617	3.573	3.525	3.492	3.459	3.430	3.393	3.396	3.453	3.475	3.494	3.508
Central Atlantic (PADD 1B)	3.483	3.429	3.398	3.382	3.362	3.336	3.295	3.341	3.423	3.441	3.447	3.457
Lower Atlantic (PADD 1C)	3.291	3.250	3.257	3.290	3.243	3.212	3.159	3.203	3.338	3.325	3.300	3.270
Midwest (PADD 2)	3.348	3.275	3.295	3.314	3.198	3.188	3.074	3.126	3.191	3.121	3.132	3.079
Gulf Coast (PADD 3)	3.176	3.127	3.107	3.129	3.072	3.030	2.978	3.004	3.140	3.124	3.104	3.047
Rocky Mountain (PADD 4)	3.549	3.507	3.459	3.426	3.368	3.307	3.227	3.183	3.145	3.113	3.077	3.055
West Coast (PADD 5)	3.802	3.737	3.684	3.655	3.609	3.564	3.507	3.467	3.457	3.475	3.477	3.472
Midgrade	3.596	3.535	3.527	3.531	3.475	3.441	3.380	3.401	3.470	3.457	3.453	3.423
Premium	3.758	3.701	3.694	3.696	3.644	3.614	3.552	3.573	3.649	3.635	3.632	3.605
On-Highway Diesel Fuel	3.919	3.897	3.886	3.886	3.870	3.857	3.832	3.822	3.844	3.883	3.879	3.871
East Coast (PADD 1)	3.931	3.908	3.904	3.905	3.889	3.878	3.855	3.841	3.870	3.906	3.912	3.915
New England (PADD 1A)	4.046	4.040	4.032	4.032	4.020	4.008	3.991	3.981	4.003	4.040	4.066	4.064
Central Atlantic (PADD 1B)	3.997	3.967	3.963	3.961	3.951	3.938	3.903	3.890	3.919	3.949	3.972	3.977
Lower Atlantic (PADD 1C)	3.861	3.838	3.837	3.840	3.818	3.808	3.793	3.779	3.808	3.848	3.837	3.840
Midwest (PADD 2)	3.894	3.876	3.854	3.853	3.837	3.826	3.798	3.794	3.829	3.879	3.870	3.852
Gulf Coast (PADD 3)	3.831	3.805	3.797	3.800	3.783	3.769	3.752	3.745	3.753	3.780	3.773	3.766
Rocky Mountain (PADD 4)	3.927	3.915	3.889	3.875	3.865	3.857	3.836	3.836	3.837	3.858	3.851	3.852
West Coast (PADD 5)	4.075	4.052	4.047	4.049	4.036	4.015	3.976	3.954	3.954	3.998	3.993	3.982
California	4.172	4.150	4.139	4.129	4.117	4.092	4.055	4.022	4.023	4.056	4.066	4.066

– = Data Not Available.
Note: See Glossary for definitions of abbreviations. See Appendix B, Technical Note 5, for more information about data in this table.
Source: See page 30.

Figure 10. U.S. Average Retail Regular Motor Gasoline and On-Highway Diesel Fuel Prices, January 2012 to Present (Dollars per Gallon, Including Taxes)



Note: See Appendix B, Weekly Petroleum Price Surveys, page 40 for more information about the data in this graph.
Source: See page 30.

Sources

Table 1

• Current Week Data: Estimates for most series based on data collected on Forms EIA-800, -801, -802, -803, -804, -805, and -809. Other Oils Stocks, Other Supply Stock Change, Other Supply Adjustment, and Total Product Supplied are estimates based on both current weekly data and data published in the most recent month of the *Petroleum Supply Monthly*. Natural Gas Plant Liquids Production, Other Renewable Fuels and Oxygenate Plant Production, and Refinery Processing Gain are estimates based on data published in the most recent month of the *Petroleum Supply Monthly*. Estimates for Other Oils Stocks, Crude Oil Production, Exports, and Other Supply Adjustment are explained in Appendix B.

• Previous Week Data, Previous Year Data, and Four-Week Averages: Estimates based on data published by EIA in the *Weekly Petroleum Status Report* for the respective periods.

Table 2

• Current Week Data: Estimates of Refinery Inputs and Utilization based on weekly data collected on Form EIA-800. Operable Capacity and Percent Utilization are based on data published in the most recent month of the *Petroleum Supply Monthly*. Estimates of Refiner and Blender Net Production based on weekly data collected on Forms EIA-800 and -805. Gasoline Adjustment estimate is based on estimation methodology described in Appendix B. Estimates for Fuel Ethanol Production are based on weekly data collected on Form EIA-809.

• Previous Week Data, Previous Year Data, 2-Year Ago Data, and Four-Week Averages: Estimates based on data published by EIA in the *Weekly Petroleum Status Report* for the respective periods.

Table 3

• Current Week Data: Estimates of Refinery Net Production based on weekly data collected on Form EIA-800. Estimates of Blender Net Production based on weekly data collected on Form EIA-805.

• Previous Week Data, Previous Year Data, 2-Year Ago Data, and Four-Week Averages: Estimates based on data published by EIA in the *Weekly Petroleum Status Report* for the respective periods.

Table 4

• Current Week Data: Estimates based on weekly data collected on Forms EIA-800, -801, -802, -803, and -809. Other Oils estimate is based on both current weekly data and data published in the most recent month of the *Petroleum Supply Monthly* as explained in Appendix B.

• Previous Week Data, Previous Year Data, 2-Year Ago Data, and Four-Week Averages: Estimates based on data published by EIA in the *Weekly Petroleum Status Report* for the respective periods.

Figure 1

• Data for Ranges: 2012-2014, EIA, *Weekly Petroleum Status Report*

• Week-Ending Stocks: Estimates based on weekly data collected on Forms EIA-800, -801, -802 and -803.

Table 5

• Current Week Data: Estimates based on weekly data collected on Forms EIA-800, -801, -802, and -809.

• Previous Week Data, Previous Year Data, 2-Year Ago Data, and Four-Week Averages: Estimates based on data published by EIA in the *Weekly Petroleum Status Report* for the respective periods.

Figure 2

• Data for Ranges: 2012-2014, EIA, *Weekly Petroleum Status Report*

• Week-Ending Stocks: Estimates based on weekly data collected on Forms EIA-800, -801, and -802.

Table 6

• Current Week Data: Estimates based on weekly data collected on Forms EIA-800, -801, and -802.

• Previous Week Data, Previous Year Data, 2-Year Ago Data, and Four-Week Averages: Estimates based on data published by EIA in the *Weekly Petroleum Status Report* for the respective periods.

Figure 3 and Figure 4 and Figure 5 and Figure 6

• Data for Ranges: 2012-2014, EIA, *Weekly Petroleum Status Report*

• Week-Ending Stocks: Estimates based on weekly data collected on Forms EIA-800, -801, and -802.

Table 7

• Current Week Data: Estimates based on weekly data collected on Form EIA-804. Estimate for Exports is explained in Appendix B.

• Previous Week Data, Previous Year Data, 2-Year Ago Data, and Four-Week Averages: Estimates based on data published by EIA in the Weekly Petroleum Status Report for the respective periods.

Table 8

• Current Week Data: Estimates based on weekly data collected on Form EIA-804. Crude Import Percentage by Country is calculated from data published by EIA in the *Petroleum Supply Monthly* and is explained in Appendix B.

• Previous Week Data, Previous Year Data, 2-Year Ago Data, and Four-Week Averages: Estimates based on data published by EIA in the *Weekly Petroleum Status Report* for the respective periods.

Table 9

• Current Week Data: Estimates for most series based on data collected on Forms EIA-800, -801, -802, -803, -804, -805, and -809. Operable Capacity and Percent Utilization are based on data published in the most recent month of the *Petroleum Supply Monthly*. Gasoline Adjustment estimate is based on estimation methodology described in Appendix B. Other Oils Stocks and Total Product Supplied based on both current weekly data and data published in the most recent month of the *Petroleum Supply Monthly*. The methodology for calculating Product Supplied is explained in Appendix B. Estimate for Exports is explained in Appendix B.

• Previous Week Data, Previous Year Data, 2-Year Ago Data, and Four-Week Averages: Estimates based on data published by EIA in the *Weekly Petroleum Status Report* for the respective periods.

Table 10

• EIA/OEA, Office of Integrated and International Energy Analysis.
• Platt's Oilgram Price Report.
• Petroleum Intelligence Weekly.
• Oil and Gas Journal.
• Wall Street Journal.
• Oil Market Intelligence.
• Natural Resources Canada
• Petroleum Place (www.petroleumplace.com)

Table 11 and Figures 7 and 8

• THOMSON REUTERS

Table 12

• THOMSON REUTERS

Table 13 and Figure 9

• Crude Oil Futures: New York Mercantile Exchange (NYMEX), and Products: THOMSON REUTERS

Table 14 and Figure 10

• Motor Gasoline Form EIA-878, "Motor Gasoline Price Survey," and On-Highway Diesel: Form EIA-888, "On-Highway Diesel Fuel Price Survey."

Appendix A

Table A1. Petroleum Supply Summary, November 2013 (derived from weekly data)

Category	November 2013	October 2013	Difference	November 2012	Percent Change	WPSR to PSM Comparison		
						September 2013	PSM September 2013	Difference
Stocks (Million Barrels)								
Total Stocks (Including SPR)[1]	1,785.1	1,812.9	-27.7	1,788.3	-0.2	1,822.7	1,831.6	-8.9
Crude Oil	1,078.8	1,081.4	-2.6	1,066.8	1.1	1,063.6	1,067.1	-3.6
SPR[2]	696.0	696.0	0.0	695.0	0.2	696.0	696.0	0.0
Commercial	382.8	385.4	-2.6	371.9	2.9	367.6	371.2	-3.6
Products	706.3	731.4	-25.1	721.5	-2.1	759.1	764.5	-5.3
Total Motor Gasoline	214.4	210.0	4.3	212.8	0.7	219.8	219.3	0.6
Finished Motor Gasoline	39.9	38.8	1.2	55.4	-27.9	47.9	40.4	7.4
Reformulated	0.0	0.0	0.0	0.0	-18.9	0.0	0.0	0.0
Conventional	39.9	38.8	1.2	55.4	-28.0	47.9	40.4	7.5
Blending Components	174.4	171.3	3.2	157.4	10.8	171.9	178.8	-6.9
Fuel Ethanol	15.2	15.2	0.1	19.4	-21.7	15.4	16.0	-0.6
Kerosene-Type Jet Fuel	36.4	39.5	-3.1	40.1	-9.3	40.4	41.1	-0.7
Distillate Fuel Oil[1]	114.8	117.8	-3.0	115.5	-0.6	127.4	128.6	-1.2
15 ppm sulfur and Under	91.6	94.6	-3.0	83.0	10.3	104.5	105.5	-0.9
> 15 ppm sulfur to 500 ppm	3.7	3.9	-0.2	6.4	-42.0	4.6	4.6	0.0
> 500 ppm sulfur[1]	19.5	19.3	0.2	26.1	-25.2	18.3	18.5	-0.3
Residual Fuel Oil	34.8	34.3	0.5	38.3	-9.1	34.3	35.7	-1.4
Propane/Propylene	53.8	62.1	-8.3	72.3	-25.6	66.7	67.8	-1.1
Other Oils[3]	236.9	252.6	-15.6	223.0	6.3	255.1	256.0	-0.9
Unfinished Oils	86.4	87.9	-1.5	80.6	7.2	83.1	82.8	0.3
Products Supplied (Thousand Barrels per Day)								
Total Products Supplied	19,984	19,370	614	18,994	5.2	19,077	19,116	-39
Finished Motor Gasoline	8,895	9,035	-140	8,630	3.1	8,774	8,918	-144
Kerosene-Type Jet Fuel	1,535	1,386	149	1,430	7.3	1,436	1,419	17
Distillate Fuel Oil	3,883	3,922	-39	3,897	-0.4	3,772	3,713	59
Residual Fuel Oil	239	169	70	362	-34.0	231	349	-118
Propane/Propylene	1,594	1,468	126	1,388	14.8	1,213	1,093	120
Other Oils[4]	3,838	3,389	449	3,288	16.7	3,651	3,625	26
Inputs and Utilization (Thousand Barrels per Day)								
Crude Oil Inputs	15,662	14,951	711	15,025	4.2	15,635	15,628	7
Operable Utilization Rate (%)	90.0	86.5	3.5	88.2	– –	90.3	90.7	-0.4
Imports (Thousand Barrels per Day)								
Total Net Imports	6,137	6,238	-101	7,296	-15.9	6,499	6,349	150
Crude Oil	7,689	7,574	115	7,972	-3.6	7,922	7,812	110
Products	-1,552	-1,336	-216	-675	– –	-1,423	-1,464	41
Imports	9,551	9,644	-93	10,114	-5.6	9,853	9,979	-126
Crude Oil	7,745	7,630	115	8,014	-3.4	7,977	7,911	66
SPR	0	0	0	0	0.0	0	–	0
Commercial	7,745	7,630	115	8,014	-3.4	7,977	7,911	66
Products	1,805	2,014	-209	2,100	-14.1	1,876	2,068	-192
Total Motor Gasoline	583	514	69	547	6.6	496	539	-43
Finished Motor Gasoline	50	36	14	63	-20.6	22	40	-18
Reformulated	0	0	0	0	0.0	0	–	0
Conventional	50	36	14	63	-20.6	22	40	-18
Blending Components	533	478	55	484	10.1	474	499	-25
Fuel Ethanol	0	0	0	45	-100.0	18	23	-5
Kerosene-Type Jet Fuel	65	57	8	27	140.7	75	68	7
Distillate Fuel Oil	145	137	8	176	-17.6	108	132	-24
15 ppm sulfur and Under	118	107	11	104	13.5	100	84	16
> 15 ppm sulfur to 500 ppm	0	0	0	13	-100.0	0	1	-1
> 500 ppm sulfur	27	30	-3	59	-54.2	8	47	-38
Residual Fuel Oil	187	174	13	284	-34.2	158	229	-71
Propane/Propylene	133	127	6	147	-9.5	84	87	-3
Other Oils[3]	691	1,003	-312	874	-20.9	937	989	-52
Exports	3,413	3,406	7	2,818	21.1	3,355	3,631	-276
Crude Oil	57	56	1	42	35.7	56	99	-43
Products	3,357	3,350	7	2,776	20.9	3,299	3,532	-233
Stock Change (Thousand Barrels per Day)								
Total[5]	-924	-318	-606	-183	– –	145	370	-225
Crude Oil[5]	-88	575	-663	-90	– –	249	256	-7
Products[5]	-836	-893	57	-93	– –	-105	113	-218

– – = Not Applicable.
– = Data Not Available.
[1] Distillate fuel oil stocks located in the "Northeast Heating Oil Reserve" are not included.
[2] Crude oil stocks in the PSR include non-U.S. stocks held under foreign or commercial storage agrements.
[3] Includes natural gas plant liquids (NGPLs) and liquefied refinery gases (LRGs) (except propane/propylene). Prior to June 2010, "Other Oils" included Fuel Ethanol and Motor Gasoline Blending Components.
[4] Includes NGPLs and LRGs, other liquids, and all other finished petroleum products except finished motor gasoline, kerosene-type jet fuel, distillate fuel oil, residual fuel oil, and propane/propylene.
[5] A negative number indicates a decrease in stocks and a positive number indicates an increase.
Note: Totals may not equal sum of components due to independent rounding.
Source: Energy Information Administration, appropriate issues of the Weekly Petroleum Status Report and the Petroleum Supply Monthly.

Appendix B

Explanatory Notes and Detailed Methods Report

1. Overview 34
   A. The Energy Information Administration's Quality Guidelines 34
   B. Concepts of Product Supply and Demand 34
2. Weekly Petroleum Supply Surveys 34
   A. Weekly Petroleum Supply Reporting System 34
   B. Weekly Supply Survey Methodology 35
      (1.) Sampling Frame 35
      (2.) Sample Design 35
      (3.) Collection 36
      (4.) Processing 36
      (5.) Imputation and Estimation 36
      (6.) Macro Editing 37
      (7.) Dissemination 37
   C. Additional Sources of Data 37
      (1.) Data Obtained Through Models 38
         a. Domestic Crude Oil Production (Tables 1 and 9) 38
         b. Exports (Tables 1, 7, 9) 38
         c. Stocks of Other Oils (Tables 1, 4, 9) 38
         d. Refinery Processing Gain (Tables 1, Line 20) 38
         e. Stocks of Crude Oil (Tables 1, 4, and 9) 38
      (2.) Data Obtained from Supplemental Sources 39
         a. Natural Gas Liquids Production (Table 1, Line 16) 39
         b. Other Renewable Fuels/Oxygenate Plant Production (Table 1, Line 19) 39
         c. Other Supply Adjustment (Table 1, Line 25) 39
         d. Production of Finished Motor Gasoline Adjustment (Tables 2 and 9) 39
   D. Quality 39
      (1.) Response Rates 39
      (2.) Timing Issues 39
      (3.) Non-sampling Errors 39
      (4.) Resubmissions 39
      (5.) Revision Policy 40
   E. Petroleum Historic Stock Ranges 40
   F. Data Assessment 40
   G. Confidentiality—Data protection and disclosure - Weekly Supply Surveys 40
3. Weekly Petroleum Price Surveys 40
   A. Weekly Price Survey Methodology 40
      (1.) Sampling Frame 40
         a. EIA-878, "Motor Gasoline Price Survey" 40
         b. EIA-888 "On-Highway Diesel Fuel Price Survey" 41
      (2.) Sampling Design 41
         a. EIA-878, "Motor Gasoline Price Survey" 41
         b. EIA-888 "On-Highway Diesel Fuel Price Survey" 41
      (3.) Collection 41
      (4.) Processing and Micro Editing 42
      (5.) Imputation and Estimation 42
         a. EIA-878, "Motor Gasoline Price Survey" 42
         b. EIA-888 "On-Highway Diesel Fuel Price Survey" 42
      (6.) Macro Editing and Validation 42
         a. EIA-878, "Motor Gasoline Price Survey" 42
         b. EIA-888 "On-Highway Diesel Fuel Price Survey" 42
      (7.) Dissemination 42

B. Quality 43
(1.) Response Rates 43
(2.) Sampling and Non-sampling Errors 43
a. Sampling Errors 43
b. Non-sampling Errors 43
(3.) Revision Policy 43
C. Confidentiality—Data protection and disclosure for Weekly Price Surveys 43
4. Notes 43

Weekly Petroleum Status Report Explanatory Notes

Overview

The Energy Information Administration's Quality Guidelines

The data contained in the *Weekly Petroleum Status Report (WPSR)* are subject to separate information quality guidelines issued by the Office of Management and Budget (OMB), the Department of Energy (DOE), and Energy Information Administration (EIA). With available resources, EIA continually works to improve its systems in order to provide high quality information needed by public and private policymakers and decision makers. EIA has performance standards to ensure the quality (i.e., objectivity, utility, and integrity) of information it disseminates to the public. Quality is ensured and maximized at levels appropriate to the nature and timeliness of the disseminated information. Information about EIA's quality program is available at http://www.eia.doe.gov/smg/EIA-IQ-Guidelines.html.

Concepts of Product Supply and Demand

Petroleum supply estimates contained in the *WPSR* are often interpreted as an approximation of petroleum demand measured as product supplied. Product supplied is often called "implied" demand because it is a measure of demand that is implied by disappearance of petroleum products from facilities and activities in the "primary" supply chain. Facilities and activities in the primary supply chain include refineries and blending terminals, gas processing plants and fractionators, oxygenate producers, importers, exporters, bulk storage terminals, and pipelines. Total product supplied in the *WPSR* may be calculated from petroleum balances reported in Table 1. Total product supplied for crude oil and petroleum products is equal to crude oil input to refineries (line 14) + Other Supply Production (line 15) + net imports(line 21) - Stock Change (line 24) + Adjustment (line 25). Product supplied for individual products equals production plus imports minus stock change minus exports. "Crude Oil Supply Adjustment" (line 13) (formerly called "Unaccounted-for Crude Oil") is the balancing item between crude oil supply and disposition.

The secondary supply chain system is that portion of the overall distribution network that falls between producers and end-users. Product typically flows in bulk from the primary supply system into the secondary system before delivery in small quantities to consumers (the tertiary system). The secondary system includes storage at bulk plants; at retail motor fuel outlets, such as service stations, truck stops, and convenience stores; and at retail fuel oil dealers. Bulk plants are wholesale storage facilities that have less than 50,000 barrels of storage capacity and, by definition, receive product only by tank car or truck, not by barge, tanker, or pipeline. Tertiary inventories are held by end users and include fuel in vehicle tanks, heating oil in residential tanks, fuel oil held by utilities, jet fuel stored in facilities operated by end users, and certain proprietary storage of raw materials for the chemical industry (ethylene, propylene, etc.).

Data users sometimes consider demand as sales to the ultimate consumer or as the actual consumption of the product. Since there may be time delays between the movement of product into the primary market and its ultimate purchase or consumption, these definitions of demand require data on changes in secondary and/or tertiary stocks or the assumption that these values either remain constant or are small compared to primary supply. The most recent study of secondary stocks was done by the National Petroleum Council in 1989. This study revealed that secondary distillate stocks were equal to about 6.9 percent of distillate stocks and 6.7 percent of distillate storage capacity. The study also noted that secondary storage capacity was decreasing due to EPA regulations.

Weekly Petroleum Supply Surveys

The data presented in the *WPSR* include data collected by the EIA on seven weekly petroleum supply and two weekly petroleum price surveys and data released by Reuters Ltd. During the heating months (October through mid-March), data from a 3rd weekly price survey are included in Appendix D, "Winter Fuels Heating Prices."

Weekly Petroleum Supply Reporting System

The seven weekly petroleum supply surveys are part of the Petroleum Supply Reporting System (PSRS). The PSRS tracks the supply and disposition of crude oil, petroleum products, and natural gas liquids in the United States. The PSRS is organized into two data collection subsystems, the Weekly Petroleum Supply Reporting System (WPSRS) and the Monthly Petroleum Supply Reporting System (MPSRS). The WPSRS processes the data from the seven weekly surveys. The MPSRS includes eight monthly surveys and one annual survey. The survey forms that comprise the PSRS are:

1. EIA-800, "Weekly Refinery and Fractionator Report,"
2. EIA-801, "Weekly Bulk Terminal Report,"
3. EIA-802, "Weekly Product Pipeline Report,"
4. EIA-803, "Weekly Crude Oil Stocks Report,"
5. EIA-804, "Weekly Imports Report,"
6. EIA-805, "Weekly Bulk Terminal and Blender Report,"
7. EIA-809, "Weekly Oxygenate Report,"
8. EIA-810, "Monthly Refinery Report,"
9. EIA-812, "Monthly Product Pipeline Report,"
10. EIA-813, "Monthly Crude Oil Report,"
11. EIA-814, "Monthly Imports Report,"
12. EIA-815, "Monthly Bulk Terminal and Blender Report."
13. EIA-816, "Monthly Natural Gas Liquids Report"
14. EIA-817, "Monthly Tanker and Barge Movement Report"
15. EIA-819, "Monthly Oxygenate Report"
16. EIA-820, "Annual Refinery Report."

A copy of the forms and instructions is available at:
http://www.eia.gov/survey/

Weekly supply surveys are administered at seven key points along the petroleum production and supply chain: (1) refineries, fractionators, and gas processing plants, (2) bulk terminals, (3) product pipelines, (4) crude oil stock holders, (5) importers, (6) blenders and (7) fuel ethanol production facilities Monthly surveys also include inter-PAD District movements by pipelines, tankers, and barges. Weekly surveys do not capture petroleum movements. Data collected weekly

using Forms EIA-800 through EIA-805 and EIA-809 are similar to, though less detailed than, the data collected monthly using Forms EIA-810, EIA-812 through EIA-815 and EIA-819. Respondents reporting to the weekly surveys constitute a sample of those reporting on the monthly surveys.

Annual U.S. refinery capacity data are collected on the Form EIA-820, "Annual Refinery Report." These data are published in the *Refinery Capacity Report*.

Weekly Supply Survey Methodology

Sampling Frame

The EIA weekly reporting system, as part of the Petroleum Supply Reporting System (PSRS), was designed to collect data similar to those collected monthly. The sample of companies that report weekly in the WPSRS are selected from the universe of companies that report on the corresponding monthly forms with the exception of the EIA-801 in 2010.

The sampling frame for Form EIA-800 "Weekly Refinery Report" includes refineries reporting on Form EIA-810 "Monthly Refinery Report" as well as fractionators reporting on Form EIA-816 "Monthly Natural Gas Liquids Report." Monthly reports on Form EIA-810 are required from operators of every operating and idle refinery located in the 50 States, District of Columbia, Virgin Islands, Puerto Rico, and other U.S. territories. Monthly reports on Form EIA-816 are required from operators of every operating and idle gas processing plant, fractionator, and butane isomerization plant located in the 50 States and the District of Columbia.

The EIA-801 sampling frame consists of all companies reporting ending stocks on the EIA-815, "Monthly Bulk Terminal and Blender Report." This includes every bulk terminal and blending facility operating company located in the 50 States, the District of Columbia, Puerto Rico, and the Virgin Islands. A bulk terminal is primarily used for storage and/or marketing of petroleum products and has a total bulk storage capacity of 50,000 barrels or more, and/or receives petroleum products by tanker, barge, or pipeline. Bulk terminal facilities associated with a product pipeline are included.

The EIA-802 sampling frame consists of all companies reporting on the EIA-812, "Monthly Product Pipeline Report." This includes all petroleum product pipeline companies that transport refined petroleum products (including interstate, intrastate, and intracompany pipeline movements) in the 50 States and the District of Columbia. Bulk terminal facilities associated with a product pipeline are excluded.

The EIA-803 sampling frame consists of all companies reporting on the EIA-813, "Monthly Crude Oil Report." This includes all companies that carry or store 1,000 barrels or more of crude oil. Included are gathering and trunk pipeline companies (including interstate, intrastate, and intracompany pipelines), crude oil producers, terminal operators, storers of crude oil (except refineries), and companies transporting Alaskan crude oil by water in the 50 States and the District of Columbia.

The EIA-804 sampling frame consists of all companies reporting on the EIA-814, "Monthly Imports Report." This includes each Importer of Record (or Ultimate Consignee in some situations regarding Canadian imports) that import crude oil or petroleum products (1) into the 50 States and the District of Columbia, (2) into Puerto Rico, the Virgin Islands, Guam and other U.S. possessions (Midway Islands, Wake Island, American Samoa, and Northern Mariana Islands), (3) Foreign Trade Zones located in the 50 States and the District of Columbia and (4) from Puerto Rico, the Virgin Islands and other U.S. possessions into the 50 States and the District of Columbia.

The EIA-805 sampling frame consists of all companies reporting inputs and production on the EIA-815, "Monthly Bulk Terminal and Blender Report." This includes all storage terminals which produce finished motor gasoline through the blending of various motor gasoline blending components, natural gas liquids, and oxygenates in the 50 States, the District of Columbia, Puerto Rico, the Virgin Islands, Guam and other U.S. possessions.

The EIA-809 sampling frame consists of all operators of facilities reporting fuel ethanol production on the EIA-819, "Monthly Oxygenate Report." This includes fuel ethanol production facilities in the 50 States and the District of Columbia.

Sample Design

The sampling procedure used for the weekly surveys is the cut-off method. In the cut-off method, companies are ranked from largest to smallest on the basis of quantities reported during some previous period. Companies are chosen for the sample beginning with the largest and adding companies until the total sample covers approximately 90 percent of the total volumes for each item and each geographic region for which data may be published. For example, for distillate fuel oil stocks, the weekly sample includes those respondents whose combined volumes of stocks for distillate fuel oil from refineries, bulk terminals, and pipelines constitute at least 90 percent of the total volume of distillate fuel oil stocks as reported in the corresponding monthly surveys.

To assure 90-percent coverage of the total for each item collected and each geographic region for each weekly survey, the sample is reviewed each month. This review focuses on changes in the current monthly data as it relates to the weekly surveys, changes in the weekly surveys that impact the monthly surveys, and changes in respondent reporting patterns. Companies are added or removed from the surveys based on the changes. Refer to Table B1 for sample size of weekly surveys.

For the weekly surveys, better coverage will most likely reduce any sampling error. As shown in Table B2, 2012 coverage was comparable to 2011. Of the 21 product and supply type combinations, all except one had coverage above 90 percent in 2012. For 3 of the 21 combinations, 2012 coverage increased slightly over 2011. The largest percentage increase from 2011 to 2012 was for jet fuel oil imports, an increase of 0.4 percent. Bulk Terminals distillate fuel oil stocks and residual fuel oil production had the largest percentage decrease from 2011 to 2012, a decline of 6 percent each. Tabulations were done before rounding of the coverage values. Total motor gasoline production percentages include production from refineries, terminals and blenders.

Table B1. Frame and Sample Size for Weekly Supply Surveys

	Weekly Form	September 2013 Frame Size	Weekly Sample Size
Refiners (Refineries)	EIA-800	144	127
Bulk Terminals	EIA-801	*	713
Product Pipelines	EIA-802	82	43
Crude Oil Stock Holders	EIA-803	221	56
Importers	EIA-804	401	106
Terminal Blenders	EIA-805	1,480	713
Ethanol Producers	EIA-809	197	145

* The sample for the EIA-801 comes from the same frame as the EIA-805.

Table B2. Average Coverage for Weekly Surveys, 2011 and 2012
(Percent of Final Monthly Volumes Included in Monthly-From-Weekly Sample)

Product	Stocks (%)						Production (%)		Imports (%)	
	Refinery		Bulk Terminals		Pipeline					
	2012	2011	2012	2011	2012	2011	2012	2011	2012	2011
Total Motor Gasoline	99	100	89	93	98	99	98	99	97	97
Jet Fuel	99	100	92	94	99	100	100	100	100	99
Distillate Fuel Oil	99	100	86	91	98	98	98	99	96	96
Residual Fuel Oil	99	100	89	93	-	-	99	100	96	99
Crude Oil	99	99	-	-	-	-	-	-	98	99

Collection

Survey data for the WPSR are collected by facsimile, Internet using secure file transfer, and electronic transmission on a weekly basis. All respondents must submit their data by 5:00 p.m. on the Monday following the end of the report period. The weekly report period begins at 7:01 a.m. on Friday and ends at 7:00 a.m. on the following Friday.

Processing

Data collected through the WPSRS are received, logged into an automated Survey Control File, keyed, and processed through an edit program. Cell values determined to be unusual or inconsistent with other cell values are flagged either by automated process or analyst review. The validity of the value of each flagged cell is investigated. From the investigation, some flagged values are either verified or corrected by the respondent. Any remaining flagged values are referred to as unresolved. Imputation is performed for nonrespondents and unresolved data items. The cleansed data are further reviewed at the aggregate level to determine if other data issues exist (see Macro Editing).

A clean data file is available by the close of business Tuesday. Corrections to previous periods, late submissions, or resubmissions for the current period received after publication are used in editing and imputation for the following periods (see Revision Policy).

Imputation and Estimation

After company reports have been checked and entered into the weekly database, values are imputed for companies that have not responded, reported incomplete data, or reported data that failed editing and could not be confirmed. The imputed values are calculated using exponentially smoothed means of recent weekly reported values for this specific company.

The equation for the exponential smoothing is:

$$Y_t = \alpha * y_t + (1 - \alpha) * Y_{t-1}$$

where

Y_t is the prediction for week t+1 (using data through week t),

y_t is week t's reported value,

Y_{t-1} is the prediction for week t (using data through week t-1),

α is a number between 0 and 1, chosen by survey/product/type

In the equation for exponential smoothing, the size of α controls the importance of last week's value relative to the aggregate of all weeks before that as represented by the prediction for last week. For example, if $\alpha = 0.8$, then last week's value is much more important in predicting this week's value than all the previous week's values are

since the weight of last week is 0.8 and the weight of the previous weeks collectively is 0.2. In general, the α values for the expected means of the non-zero responses are low for imports (last week is much less important than history) and much higher for production, inputs and stocks.

The imputed values are treated like reported values in the estimation procedure, which calculates ratio estimates of the weekly totals. First, the current week's data for a given product reported by companies in a geographic region are summed (weekly sum, W_s.) Next, the most recent month's data for the product reported by those same companies are summed (monthly sum, M_s.) Finally, the most recent month's data for the product as reported by all companies, including adjustments made in the monthly process, is summed (M_t). The current week's ratio estimate for that product for all companies, W_t, is given by:

$$W_t = (M_t / M_s) * W_s$$

The ratio (M_t / M_s) may be adjusted to account for very unusual events or industry changes not yet reflected in the lagged monthly data. For example, the hurricanes in September 2005 rendered the September data unrepresentative for purposes of applying the ratio to the *WPSR* in December 2005. Note, however, the gasoline and ethanol fuel adjustment is not included in M_t and is treated explicitly.

This procedure is used directly to estimate total weekly inputs to refineries and production. When refineries are closed or inoperable, the lagged monthly data impacts the estimate of operable capacity and percent utilization in the WPSR. Operable capacity is the latest reported monthly operable capacity. The percent utilization is calculated as gross weekly inputs divided by operable capacity. The use of monthly capacity data may result in an overestimate of operable capacity and an underestimate of percent utilization until the shutdown is shown in the monthly data.

To estimate stocks of finished products, the preceding procedure is followed separately for refineries, bulk terminals, and pipelines. Total estimates are performed by summing over establishment types.

Published values of gasoline production include a fuel adjustment to account for the imbalance between supply and disposition of motor gasoline blending components and fuel ethanol. For further detail, refer to Additional Sources of Data, Data Obtained from Supplemental Sources (below).

Weekly imports data are highly variable on a company-by-company basis or a week-to-week basis. Therefore, an exponentially smoothed ratio has been developed for weekly imports. The estimate of total weekly imports is the product of the smoothed ratio and the sum of the weekly reported values and imputed values.

For imports, the ratio is smoothed as follows:

$$R_t = \alpha * r_t + (1 - \alpha) * R_{t-1}$$

where

R_t is the smoothed ratio for week t+1 (using ratios through week t),

r_t is week t's ratio of the most recent monthly total for all respondents to the monthly total of respondents from the weekly sample,

R_{t-1} is the smoothed ratio for week t (using ratios through week t-1),

α is a number between 0 and 1, chosen by product but not by PADD/Respondent ID.

When $M_s = 0$, then r_t is not defined for the week and the smoothed ratio is not updated, that is, the previous smoothed ratio is used as the multiplier.

Macro Editing

After the respondent-level data have been collected and processed. The WPSR processing system is "locked down" to all staff except a select group of industry analysts and statisticians, referred to as the WPSR Review Team. Aggregate-level estimates are generated by product and geographic region for the current week, three prior weeks, year ago data for the same week, along with 4-week averages. The WPSR Review Team has the responsibility for reviewing the aggregated data for all products and resolving inconsistencies with these estimates.

Once the WPSR Review Team have completed their review, preliminary WPSR tables are generated and provided to the Petroleum Division Director (PDD) for review. At 4 p.m., the team meets with the PDD for a final review and discussion of the estimates. Discrepancies in the data are discussed and, if necessary, adjustments are made and the final published statistics are generated for release on Wednesday morning at 10:30 a.m.

Dissemination

The data are published in the *WPSR* and the *TWIP* every Wednesday for the report period ending on the previous Friday. The WPSR tables are released to the EIA Web site at 10:30 a.m. (Eastern Standard Time) in CSV and XLS formats. The weekly highlights are released in PDF format at 10:30 am. The entire *WPSR* is released at 1:00 p.m. in PDF and HTML format. For weeks which include holidays (or have other disruptions to normal operations), releases are delayed by one day. The *WPSR* tables can be accessed at: http://www.eia.gov/petroleum/supply/weekly/.

Selected data from the weekly supply surveys are also published in the *This Week in Petroleum (TWIP)* generally available at 1:00 p.m. Eastern Time on Wednesdays. The *TWIP* can be accessed at: http://www.eia.gov/oog/info/twip/twip.asp.

Additional Sources of Data

Due to the tight time constraints in publishing weekly petroleum supply statistics and the desire to reduce industry response burden, some of the statistics published in the *WPSR* are obtained from sources other than the 7 weekly supply surveys. These other sources include models to data and data from supplemental sources such as the *PSM* or the Bureau of the Census.

Data Obtained Through Models

Domestic Crude Oil Production (Tables 1 and 9)

EIA estimates weekly domestic crude oil production using a combination of short-term forecasts and the latest available production estimates from Alaska. The four data elements contributing to the estimate are:

- the most recent Short-Term Energy Outlook (STEO) model estimate (including interim estimates) for average daily production for the lower 48 States and the Federal Gulf of Mexico (GOM) (STEO Table 4a: http://www.eia.gov/forecasts/steo/data.cfm?type=tables);
- daily production volumes delivered from the North Slope of Alaska to the Trans-Alaska Pipeline System (TAPS) (reported to EIA by the Alyeska Pipeline Service Company);
- daily volumes of natural gas plant liquids produced on the North Slope delivered to TAPS (reported to EIA by BP); and
- daily production for South Alaska estimated from monthly production reports (lagged by two months) from the Alaska Oil and Gas Conservation Commission (AOGCC).

Most of the uncertainty in the weekly estimate is associated with the STEO forecast for lower 48 and GOM production. For example, when lower 48 crude oil production is either increasing or decreasing rapidly, the accuracy of the estimate for any particular month is likely to be reduced. During tropical storms or hurricanes that affect Gulf of Mexico oil production, near real-time daily shut-in volumes reported by the Bureau of Safety and Environmental Enforcement (BSEE) are subtracted from the daily lower 48 estimate. See Previous STEO Forecasts at http://www.eia.gov/forecasts/steo/data.cfm?type=tables for comparisons of current and previous monthly STEO forecasts for lower 48 oil production and percent changes for STEO quarterly forecasts.

Exports (Tables 1, 7, and 9)

Official U.S. exports statistics for crude oil and petroleum products are compiled by the U.S. Bureau of the Census and are published in the *PSM*. The EIA obtains these data on a monthly basis approximately 6 weeks after the close of the reporting month. Weekly, per day estimates of exports for crude oil and petroleum products except motor gasoline are forecast using an autoregressive integrated moving-average (ARIMA) procedure. The weekly estimate is updated when a new monthly estimate is calculated for the *PSM*. The ARIMA procedure models a value as a linear combination of its own past values and present and past values of other related time series. The most recent 5 years of past data are used to obtain the exports forecast. In addition, for residual fuel oil, 5 years of related price data are used. The price data include some U.S. and some foreign series. The weekly estimate is replaced when a new monthly estimate is calculated for the *PSM*. The export estimate for motor gasoline relies on the most recently available Census data to estimate current weekly exports of motor gasoline.

Since the inputs to the model are based on export volumes that are 2 months old, analysts review the estimate to determine if current factors such as hurricanes or other severe weather require an adjustment to the weekly exports estimate.

Stocks of Other Oils (Tables 1, 4, 9)

Stocks of minor products (referred to as "other oils") are not collected on the weekly survey forms (Forms 800 through 805 and 809). Minor products include aviation gasoline, other hydrocarbons and oxygenates, aviation gasoline blending components, naphtha and other oils for petrochemical feedstock use, special naphtha, lube oils, waxes, coke, and miscellaneous oils. An estimate of weekly stocks of minor products is derived by first computing an average daily rate of stock change for the minor products for each month based on monthly data for the past 6 years (Table 1 of the *PSM*). The daily stock change for a month is estimated by subtracting the prior month's end of month other oils stocks from the current month's end of month other oils stocks and dividing by the number of days in the current month. This average daily rate and the minor stock levels from the most recent *PSM* are then used to estimate the minor product stock level for the current week.

Since some of the components of the stocks of other oils are based on values from past monthly data, analysts review the estimate to determine if factors such as recent increases or decreases in crude runs or reported outlier data require an adjustment to the estimate of stocks of minor products.

Refinery Processing Gain (Table 1, Line 20)

Processing gain is the volumetric amount by which total output is greater than input for a given period of time. This difference is due to the processing of crude oil into products which, in total, have a lower specific gravity than the crude oil processed.

Processing gain in the *WPSR* is calculated by dividing processing gain from Table 29 of the *PSM* by Refinery and Blender Net Inputs of Crude Oil in thousands of barrels per day from Table 3 of *PSM* for each of the latest 12 months of the *PSM*. The 12 values are added and divided by 12. The result is then multiplied by this week's crude oil input to refineries value in Table 1 of the *WPSR* to obtain the processing gain value for the week.

Stocks of Crude Oil (Tables 1, 4, and 9)

The EIA-803 collects end of week crude oil stocks by PADD which is a combination of stocks in pipelines and tank farms, terminals, and on leases operated by the reporting company. Small, independent producers of crude oil on federal leases are not required to report on the EIA-803. An adjustment is made to the PADD 3 and PADD 4 stocks to correct for the understatement of lease crude oil stocks. Values added for the adjustment are 10,300 thousand barrels in PAD District 3 and 330 thousand barrels in PAD District 4. These adjustments are reflected in total U.S. crude oil stocks in Tables 1, 4, and 9 and in PAD District crude oil stocks in Tables 4 and 9.

Data Obtained from Supplemental Sources

Natural Gas Plant Liquids Production (Table 1, Line 16)

Natural Gas Plant Liquids Production is not collected on the weekly surveys. The volume shown for "Natural Gas Plant Liquids Production" is "Field Production" of "Natural Gas Plant Liquids and Liquefied Refinery Gases" from Table 3, "U.S. Daily Average Supply and Disposition of Crude Oil and Petroleum Products" of the latest *PSM*. For further information see the Explanatory Notes in the appendix of the *PSM* available at: http://www.eia.gov/petroleum/supply/monthly/

Other Renewable Fuels/Oxygenate Plant Production (Table 1, Line 19)

"Other Renewable Fuels/Oxygenate Plant Production" is derived from data on Table 3 of the latest PSM. It is derived by adding Total "Renewable Fuels and Oxygenate Plant Net Production," less Renewable Fuels and Oxygenate Plant "Fuel Ethanol" production, plus the adjustments to "Oxygenates (excluding fuel ethanol) and adjustments to "Renewable Fuels Except Fuel Ethanol." Other Renewable Fuels/Oxygenate Plant Production includes production of "Oxygenates (excluding fuel ethanol)" and "Renewable Fuels Except Fuel Ethanol." "Oxygenates (excluding fuel ethanol)" include ETBE, MTBE, and E85 as well as input of denaturants for fuel ethanol at fuel ethanol plants. For further information see the explanatory notes in the appendix of the *PSM* available at: http://www.eia.gov/petroleum/supply/monthly/

Other Supply Adjustment (Table 1, Line 25)

Other Supply Adjustment is equal to the sum of the "Adjustment" for Refiner and Blender Net Production of Finished Motor Gasoline from Table 2 of the *WPSR* and the adjustments to the supply for "Hydrogen" and "Other Hydrocarbons" from Table 3 of the *PSM*.

Production of Finished Motor Gasoline Adjustment (Tables 2 and 9)

Production of finished motor gasoline reported in Tables 2 and 9 of the *WPSR* includes refinery production, blender production, and adjustments to account for imbalances between supply and disposition of motor gasoline blending components and fuel ethanol. An adjustment is needed to finished motor gasoline production because there typically is more supply than disposition reported for motor gasoline blending components and fuel ethanol. Since there is no end-user demand for motor gasoline blending components or fuel ethanol, the imbalance is typically interpreted as unreported gasoline production at blenders. Gasoline production adjustments are included in Total US finished gasoline production reported in the *WPSR*. The adjustment is the sum of the values required to balance the supply and disposition of motor gasoline blending components and fuel ethanol. Supply is production plus imports minus stock change. Disposition is refinery and blender net production plus exports.

For motor gasoline blending components, production equals the motor gasoline blending component adjustment value from Table 3 of the *PSM*. Imports, stock change, and refinery and blender net inputs are current weekly data; and exports are from the Petroleum Export Model. For fuel ethanol, production equals ethanol plant production, imports, stock change, and refinery and blender net inputs are current weekly data and exports are from the Petroleum Export Model.

Additional details concerning gasoline adjustments are available in Appendix B, "Detailed Statistics Explanatory Notes" of the *PSM*.

Quality

Response Rates

The response rate for the weekly supply surveys is generally 95 to 100 percent. Chronic nonrespondents and late filing respondents are contacted by telephone and reminded of their requirement to report. Nearly all of the major companies report on time. The nonresponse rate for the published estimate is usually between 1 percent and 2 percent.

Timing Issues

Timing of reported data can impact published results. For example, the calculation of product supplied includes imports and change in stock levels. Normally imports would result in a stock increase. However, respondents recording inventories are frequently different than the respondents reporting imports. The accounting system of one respondent may lag that of another, resulting in the imports and associated stocks being reported in different weeks. These timing differences result in weekly variations in product supplied.

Non-sampling Errors

The weekly supply data are closely watched by market analysts and are sometimes attributed to movements in both spot and futures prices on the day the data are released. When petroleum markets are particularly tight or when the data are not what the market is expecting, (e.g. a build in inventories occurs when a decline is expected), the weekly data take on a more significant role in the assessment of petroleum markets, where such assessments affect billions of dollars in the financial markets.

Non-sampling errors may arise in the survey estimates from a number of sources including: (1) the inability to obtain data from all companies in the frame or sample (non-response and the method used to account for non-response), (2) response errors, (3) differences in the interpretation of questions or definitions, (4) mistakes in recording or coding of the data obtained from respondents, (5) data timing, and (6) other errors of collection, response, coverage, and estimation.

Resubmissions

Resubmissions are required whenever an error greater than 5 percent of the true value is discovered or if requested by EIA. Late submissions or resubmissions received after the publication date are used for editing and imputation for future periods. In rare instances, the data are used to publish a revised estimate. See Revision Policy below.

Revision Policy

EIA will disseminate revised weekly data only if the revision is expected to substantively affect understanding of U.S. petroleum supplies. The decision to disseminate a revision to weekly data will be based on EIA's judgment of the revision's expected effect. If a revision is necessary, it will be disseminated in the next regularly scheduled release of the weekly products.

Petroleum Historic Stock Ranges

The 5-year high/low stock ranges displayed in Figures 1 through 6 are provided to help WPSR users compare current petroleum inventories to recent historic levels on a U.S. total and regional basis.

The 5-year ranges provide the reader with the highest and lowest weekly stock levels for a given product by region over the equivalent week during the prior five years. Current weekly stock estimates published in the WPSR (labeled Weekly) are plotted in relation to these 5-year stock levels (shaded area on the charts) for crude oil, total motor gasoline, distillate fuel oil, kerosene-type jet fuel, residual fuel oil, and propane inventories. The charts show two years of data, covering periods either from December through December or June to June.

Data Assessment

The principal objective of the PSRS is to provide an accurate picture of petroleum industry activities and of the availability of petroleum products nationwide from primary distribution channels. The weekly data, which are based on sample estimates stemming largely from preliminary company data, serve as leading indicators of the monthly data. The weekly data are not expected to have the same level of accuracy as the preliminary monthly data when compared with final monthly data. However, the weekly data are expected to exhibit like trends and product flow characteristic of the preliminary and final monthly data.

To assess the accuracy of weekly statistics, monthly estimates derived from weekly estimates are compared with the final monthly aggregates published in the Petroleum Supply Annual *(PSA)*. Although final monthly data published in the *PSA* are still subject to error, they have been thoroughly reviewed and edited, they reflect all revisions made during the year, and they are considered to be the most accurate data available. The mean absolute percent error provides a measure of the average revisions relative to the aggregates being measured for a variable. The mean absolute percent error for 2007 weekly data was less than 2 percent for 22 of the 62 major petroleum variables analyzed. As a group, stocks continued to have the most accurate monthly from weekly estimates. The detailed analysis is available in a feature article entitled "Accuracy of Petroleum Supply Data" available at: http://www.eia.doe.gov/petroleum/supply/monthly/archive/2009/2009_02/pdf/art0902.pdf

Confidentiality—Data protection and disclosure - Weekly Supply Surveys

The information reported on Forms EIA-800 through EIA-805 and EIA-809 is kept confidential and not disclosed to the public to the extent that it satisfies the criteria for exemption under the Freedom of Information Act (FOIA), 5 U.S.C. §552, the DOE regulations, 10 C.F.R. §1004.11, implementing the FOIA, and the Trade Secrets Act, 18 U.S.C §1905. The Energy Information Administration (EIA) protects this information in accordance with its confidentiality and security policies and procedures.

The Federal Energy Administration Act requires the EIA to provide company-specific data to other Federal agencies when requested for official use. The information reported on these forms may also be made available, upon request, to another component of the Department of Energy (DOE); to any Committee of Congress, the General Accounting Office, or other Federal agencies authorized by law to receive such information. A court of competent jurisdiction may obtain this information in response to an order. The information may be used for any nonstatistical purposes such as administrative, regulatory, law enforcement, or adjudicatory purposes.

Disclosure limitation procedures are not applied to the statistical data published from these surveys' information. Thus, there may be some statistics from forms EIA-800 through EIA-805 and EIA-809 that are based on data from fewer than three respondents, or that are dominated by data from one or two large respondents. In these cases, it may be possible for a knowledgeable person to estimate the information reported by a specific respondent.

Company specific data are also provided to other DOE offices for the purpose of examining specific petroleum operations in the context of emergency response planning and actual emergencies.

Weekly Petroleum Price Surveys

Weekly Price Survey Methodology

EIA survey price data contained in this report are derived from two weekly telephone surveys, the EIA-878, "Motor Gasoline Price Survey," and the EIA-888, "On-Highway Diesel Fuel Price Survey." These surveys provide timely information on national and regional retail prices of gasoline and on-highway diesel fuel.

Sampling Frame

EIA-878, "Motor Gasoline Price Survey"

The EIA-878 sample was drawn from a frame of approximately 115,000 retail gasoline outlets. The gasoline outlet frame was constructed by combining outlet information purchased from a private commercial source with company-level information contained on existing EIA petroleum product frames and surveys. Outlet names and codes were obtained from the private commercial data source. Company-level retail gasoline sales volumes by State were obtained from EIA surveys. Additional information was obtained directly

from companies selling retail gasoline to supplement information on the frame. The individual frame outlets were mapped to counties using their codes. The outlets were then assigned to the published geographic areas using their county assignment. Each outlet is designated as either in an area requiring reformulated gasoline (RFG) based on Environmental Protection Agency (EPA) program requirements or in an area designated as a conventional gasoline area. Reformulated gasoline is required by the EPA in any area that is designated as an ozone nonattainment area. A conventional area is defined as any area that does not require the sale of reformulated gasoline. All formulations of finished motor gasoline may be sold in conventional areas.

EIA-888 "On-Highway Diesel Fuel Price Survey"

The EIA-888 frame was constructed using commercially available lists from several sources. These sources were used to provide a comprehensive coverage of truck stops and service stations that sell on-highway diesel fuel in the contiguous United States. Due to statistical and operational considerations, outlets in the States of Alaska and Hawaii were excluded from the target population. The frame includes around 62,000 service stations and 4,000 truck stops. Based on information from other EIA survey data the four largest on-highway diesel sellers in the nation were identified. This allowed for classifying the outlets into three categories; service stations, mid-sized truck stops, and the top four.

Sample Design

EIA-878, "Motor Gasoline Price Survey"

The design is based on the definitions of publication cells and sampling cells. A publication cell is defined by geography (PADD, State, and city) and attainment status (reformulated or conventional gasoline). Hence, New York State reformulated gasoline is a publication cell. New York City, conventional gasoline in PADD 1A (New England), and all of the United States are also publication cells. A sampling cell is defined as the smallest basic geographical unit formed by the boundaries of the geographic and formulation areas for which average prices are published. Thus, the part of New York State where reformulated gasoline is required, but is not in New York City, would be a sampling cell. Every county in the U.S. was assigned to a sampling cell. Sampling cells are mutually exclusive and collectively exhaustive.

The gasoline outlet sample is an area sample consisting of a sample of outlets from the previous EIA-878 sample and an augmentation sample of outlets from the new outlet frame described above. The previous sample employed an entirely different sample design and frame using a selection of companies within a State and then a selection of outlets within the selected companies for that State. The new sample includes approximately 50 percent of the noncertainty sample from the previous sample to insure continuity in the historical data series. The augmentation outlets were obtained by first sampling counties and then sampling the outlets from the gasoline outlet frame within those counties. After the counties were assigned to a sample cell, the standard deviations of gasoline prices for these sampling cells were estimated using the prices from the previous sample of the gasoline survey. These standard deviations and the number of stations from the Census Bureau's County Business Patterns (CBP) were used to determine the required number of outlets to be sampled. The statistical technique used was the Chromy allocation algorithm, an iterative procedure to determine the number of units required for each sampling cell. A Goodman-Kish PPS sampling method was used to select counties, ordering counties within sampling cells by number of stations. The required number of stations was randomly selected from the outlet frame file within each selected county. Once this augmentation portion of the sample was obtained, standard deviations were re-estimated, combining the previous gasoline sample outlets and newly sampled outlets. The Chromy algorithm was applied again to determine the revised sample cell requirements. The previous sample's outlets were then sub-sampled to insure a self-weighting sample within each stratum, and allocations satisfied by sampling half from each of the self-weighting sub-sample and the old sample.

In determining the required sample size, the target coefficient of variation for publication cells was set for 0.4 cents for the United States, 0.55 for PADDs and U.S. formulations, 0.70 for sub-PADDS and the PADD formulations, 0.85 for cities and states, and 1.0 for the remaining published cells (i.e. state and sub-PADD formulations). The sample size is approximately 800 outlets.

EIA-888 "On-Highway Diesel Fuel Price Survey"

The primary publication cells of the survey include Petroleum Administration for Defense Districts (PADDs) 2, 3, 4, three sub-PADDs within PADD 1, and the two subparts of PADD 5 (the State of California and the West Coast region excluding California). The U.S., the East Coast (PADD 1), and the West Coast (PADD 5) are considered secondary publication cells since their prices are aggregated based on the prices from their primary publication cell components. To select the sample, allocations were first assigned to all primary publication cells through a simulation of coefficients of variation of average prices using historical price data. The target coefficient of variation for each primary publication cell was capped at 1%. Allocations were further assigned to the States covered by each primary publication cell. The distribution of allocations was proportional to the annual State total volume of retail on-highway diesel fuel sales. This allocation procedure yielded a total target sample size of 403 retail outlets. The States were treated as sampling strata in the sample design.

Based on information from other survey data and industry sources the proportions of total diesel volumes sold by outlets in the three categories (service stations, mid-sized truck stops, and top four) were assumed to be 20%, 55%, and 25%, respectively. These volume proportions, along with the outlet counts for the three categories on the frame, were used to calculate relative size measures for the outlets in each of the three categories. Pareto Sampling, which is a PPS procedure, and the size measures for each outlet were then used to select sampling units from each State.

Collection

Each Monday, the individual gasoline and diesel outlets are called and asked to report the pump price of their products as of 8:00 a.m. local time. If Monday is a holiday, the calls are made on the next business day; however, the Monday price is still recorded. The collection takes place using a computer assisted telephone interview (CATI) with built in editing. Companies who prefer to report through their headquarters on behalf of their selected outlets are allowed to do so. Companies preferring to report by fax or email are also permitted to report by that method. Data obtained through non-phone methods are entered

into the CATI system and treated the same as phone collected prices. Nonrespondent firms are telephoned up to three times. The data are collected more frequently during emergency situations.

In 2007, on-highway diesel prices were collected for two types of diesel fuel, ultra low sulfur and low sulfur. This dual collection was in response to the industry's implementation of EPA requirements phasing out the use of low sulfur diesel fuel. Publication of Low Sulfur On-Highway Diesel (LSD) prices at the U.S. level was discontinued on December 8, 2008 due to a diminishing number of stations selling LSD as a result of EPA diesel fuel regulations. EIA continued to collect LSD prices from retail outlets and included them in the Diesel Average All Types price until July 26, 2010, when no more outlets reported LSD sales. Beginning July 26, 2010 publication of the Ultra Low Sulfur Diesel (ULSD) price became fully represented by the Diesel Average All Types price. As of December 1, 2010 (September 1, 2006 in California), any on-highway diesel fuel sold is ULSD as mandated by EPA on-highway diesel fuel regulations.

Processing and Micro Editing

The data are edited when they are entered into the CATI system, normally during the phone interview. Respondents are asked to verify prices that fail edits. If prices are outside a certain range or fail other criteria (e.g. the price of a station's fuel grade is the same or cheaper than the price of a lower grade), respondents are also asked to explain the reason for the extreme deviation in price. Data obtained through non-phone methods are also entered into the CATI system. If the data fail the edits, the respondents are called and asked to verify their reported price(s). Imputation is used for outliers and nonrespondents.

A set of models that use the latest weighted average motor gasoline spot prices to predict the direction and amount of change in the U.S., 5 PADDs, 3 sub-PADDs and the State of California retail prices are run on both Fridays and Mondays. If the survey results differ significantly from the model results, additional verification of the reported prices is done.

In addition, in the middle of the weekly data collection, interviewing stops in order to run a pre-check report on data which has already been collected. This is done to test the integrity of the current data, check for severe fuel price changes (i.e. bogus records), and re-set any records which have been resolved. Bogus records discovered during the pre-check are re-called to recheck or correct these prices. Any edits introduced to the data by this process will be applied when another pre-check or final processing is run.

Final processing takes place once all records in the CATI system have been resolved. Many of the same tasks of the pre- check process are repeated and final price estimates are created.

Imputation and Estimation

EIA-878, "Motor Gasoline Price Survey"

To estimate average prices, sample weights were constructed based on the sampled outlet's number of pumps as a proxy for sales volume. These weights are applied each week to the reported outlet gasoline prices to obtain averages for the specific formulations, grades and geographic areas. Weights used in aggregating across grades, formulations, and geographic areas were derived using volume data from the EIA-782C "Monthly Report of Prime Supplier Sales of Petroleum Products Sold for Local Consumption," and demographic data from the Bureau of the Census and Department of Transportation on population, number of gasoline stations, and number of vehicles. A "Coefficient of Variation of Price Report" is published weekly at: http://www.eia.gov/petroleum/gasdiesel/sampling_error_report.cfm

EIA-888 "On-Highway Diesel Fuel Price Survey"

The reported and imputed prices each week are aggregated in multiple steps to obtain price estimates for publication cells. First, State average prices are calculated as simple unweighted averages of reported and imputed prices. Volumes of on-highway diesel sold in the States in 2010, as published by the Federal Highway Administration, are then used to weight the State average prices and obtain average prices for primary publication cells. Average prices for secondary publication cells are weighted averages of primary publication cell prices based on the proportion of diesel volumes attributable to their component primary publication cells. A "Coefficient of Variation of Price Report" is published weekly at: http://www.eia.gov/petroleum/gasdiesel/sampling_error.cfm

Macro Editing and Validation

EIA-878, "Motor Gasoline Price Survey"

Once the motor gasoline price data have been processed, the data are checked through a validation program. The program identifies the outliers in price changes from a week ago and in actual prices by grade and region. Significant outliers are investigated and verified by calling the respondent(s) and/or checking the fax or email from the respondent.

EIA-888 "On-Highway Diesel Fuel Price Survey"

After processing, the outlet prices are checked by a diesel validation program. The program identifies outliers and allows the analyst to further examine the data. Significant outliers are investigated and verified by calling the respondent(s) and/or checking the fax or email from the respondent for explanations. Also, credit card transaction prices are obtained from a private source and used to estimate a U.S. and PADD level price for on-highway diesel fuel. If the survey results differ significantly from these sources, additional verification of the reported prices is done.

Dissemination

The retail gasoline and diesel prices are processed and released around 5 p.m. each Monday, except on Federal holidays, in which case the data are released on Tuesday (but still represent Monday's price). Retail gasoline and on-highway diesel fuel prices are released on EIA's website: http://www.eia.gov/petroleum/gasdiesel/.

The data are also available through email notification to those customers who sign up for that service. The U.S., PADD, and sub-PADD level regular gasoline and diesel fuel average prices are available on EIA's prerecorded telephone hotline at (202) 586-6966 and in this publication, the *Weekly Petroleum Status Report*.

Quality

Response Rates

The response rates on Forms EIA-878 and EIA-888 are usually 98 to 100 percent.

Sampling and Non-sampling Errors

Sampling Errors

Sampling errors are those errors that occur when survey estimates are based on a sample rather than being derived from a complete census of the frame. Tables showing data from the EIA-878 and EIA-888 surveys utilize a sample of resellers and retailers and, therefore, have sampling error. The particular sample used for each of the EIA-878 and EIA-888 surveys is one of a large number of all possible samples that could have been selected using the same design. Estimates derived from the different possible samples would differ from each other. The average of these estimates would be close to the estimate derived from a complete enumeration of the population (a census), assuming that a complete enumeration has the same nonsampling errors as the sample survey. The sampling error, or standard error of the estimate, is a measure of the variability among the estimates from all possible samples of the same size and design and, thus, is a measure of the precision with which an estimate from a particular sample approximates the results of a complete enumeration.

Estimates of the sampling error for the EIA-878 can be found at:
http://www.eia.gov/petroleum/gasdiesel/sampling_error_report.cfm

Estimates of the sampling error for the EIA-888 can be found at:
http://www.eia.gov/petroleum/gasdiesel/sampling_error.cfm

Non-sampling Errors

Non-sampling errors may arise from a number of sources including: (1) the inability to obtain data from all companies in the frame or sample (non-response and the method used to account for non-response), (2) response errors, (3) differences in the interpretation of questions or definitions, (4) mistakes in recording or coding of the data obtained from respondents, and (5) other errors of collection, response, coverage, and estimation.

Revision Policy

EIA disseminates revised weekly data only if the revision is expected to substantively affect users understanding of U.S. petroleum prices. The decision to disseminate a revision to weekly data will be based on EIA's judgment of the revision's expected effect. If a revision is necessary, it will be disseminated in the next regularly scheduled release of the weekly products.

Confidentiality—Data protection and disclosure for Weekly Price Surveys

The information reported on the weekly price survey Forms EIA-878 and EIA-888 is considered confidential in accordance with the Confidential Information Protection and Statistical Efficiency Act of 2002 (P.L. 107-347) and the information will be used solely for statistical purposes. Instructions to the forms include the following:

"The information you provide will be used for statistical purposes only. In accordance with the Confidential Information Protection provisions of Title 5, Subtitle A, Public Law 107-347 and other applicable Federal laws, your responses will be kept confidential and will not be disclosed in identifiable form to anyone other than employees or agents without your consent. By law, every EIA employee, as well as every agent has taken an oath and is subject to a jail term, a fine of up to $250,000, or both if he or she discloses ANY identifiable information about you."

Notes

Note 1

Calculation of World Oil Price

The weighted average international price of oil, shown in the Highlights and in Table 10, is an average calculated using specific crude oil prices weighted by the estimated crude oil export volume for each oil-producing country. To develop Table 10, a list of major oil producing/exporting countries was chosen. For each country, the contract selling price of one or more representative crude oils was determined by investigating a number of industry publications (i.e., Platt's Oilgram Price Report, Wall Street Journal, and Canadian Ministry of Natural Resources) and by contacting oil market analysts. Then, the appropriate crude oil exporting volumes to be used as weighting factors for each country were determined. These volumes are estimates based on a number of sources which provide data on production, consumption, and petroleum product exports for these countries. Export volumes for a number of smaller producing/exporting countries, not listed in the table, are included in the weighting factors. After the export volumes had been determined, simple mathematical weighted averages were calculated to arrive at the Total OPEC, Total Non-OPEC, and Total World prices. The average United States (FOB) import price is derived by the same basic procedure as the world oil price that is, taking the representative contract crude oil price of a specific crude oil from a particular country and weighting this price by a certain volume of crude oil. In this case, the weighting factors are the volumes of crude oil imported into the U.S. from pertinent countries. Import volumes from a number of smaller producing/exporting countries, not listed in the table, are included in the weighting factors.

Note 2

The spot prices that are shown in Tables 11 and 12 are calculated by taking an unweighted average of the daily closing spot prices for a given product over a specified time period, such as a week or month.

Note 3

The futures prices shown in Table 13 are the official daily closing prices at 2:30 p.m. from the trading floor of the New York Mercantile Exchange (NYMEX) for a specific delivery month for each product listed.

Note 4

The futures price differentials shown in Figure 9 show the market premium for the first NYMEX delivery month contract over the second. For example, the data for September show the difference between October and November futures contract prices for crude oil and petroleum products, indicating the relative values placed by markets on commodities to be delivered during those two months. This differential, if negative and large enough, provides incentive for refiners and traders to hold product in storage, and if positive, to defer purchases until some future point in time.

Note 5

The retail gasoline prices shown in Table 14 reflect sales of reformulated gasoline (RFG) in those areas where required by Federal or State law and conventional gasoline elsewhere (see Figure B1). Areas requiring RFG may change over time due to the ozone non-attainment status of an area being re-designated by the Environmental Protection Agency (EPA), a State opting in or out of an EPA clean fuel program, or a State adopting its own specific clean fuel program. EIA reclassifies the outlets reporting retail gasoline prices each time an area shifts in or out of a reformulated gasoline program. Conventional areas include areas where oxygenated gasoline may be required for all or part of the year.

Figure B1. Gasoline Formulation Required by Area as of June 1, 2004

Source: U.S. Environmental Protection Agency and State environmental offices.

Appendix C

Northeast Home Heating Oil Reserve

Information on the Northeast Home Heating Oil Reserve is available from the U.S. Department of Energy (DOE) Office of Petroleum Reserves web site at http://www.fossil.energy.gov/programs/reserves/heatingoil/.

Northeast Home Heating Oil Reserve (NEHHOR) inventories now classified as ultra-low sulfur distillate (15 parts per million) are not considered to be in the commercial sector and therefore are excluded from distillate fuel oil supply and disposition statistics in Energy Information Administration publications, such as the *Weekly Petroleum Status Report*, *Petroleum Supply Monthly*, and *This Week In Petroleum*.

Northeast Home Heating Oil Reserve

Terminal Operator	Location	Thousands of Barrels
Hess Corp.	Groton, CT	500*
Global Companies LLC	Revere, MA	500*

* DOE has completed converting the NEHHOR from high sulfur heating oil to ultra-low sulfur distillate (15 parts per million). In 2011, two companies were awarded with contracts for storage of 500 thousand barrels each. Shipments to refill the reserve were completed in February 2012.

Source: Energy Information Administration

Appendix D

Table D1. Residential Heating Oil Prices by Region and State
(Dollars per Gallon, Excluding Taxes)

Region/State	2012 - 2013 Heating Season Monthly					
	October	November	December	January	February	March
Average	4.014	4.012	3.986	4.017	4.145	4.055
East Coast (PADD 1)	4.021	4.018	3.994	4.027	4.154	4.063
New England (PADD 1A)	3.960	3.924	3.915	3.973	4.104	4.017
Central Atlantic (PADD 1B)	4.071	4.091	4.056	4.072	4.196	4.102
Lower Atlantic (PADD 1C)	3.751	3.770	3.762	3.748	3.839	3.836
Midwest (PADD 2)	3.714	3.748	3.672	3.553	3.776	3.687

Region/State	2013 - 2014 Heating Season Monthly					
	October	November	December	January	February	March
Average	3.832	3.837	–	–	–	–
East Coast (PADD 1)	3.835	3.840	–	–	–	–
New England (PADD 1A)	3.763	3.787	–	–	–	–
Central Atlantic (PADD 1B)	3.893	3.884	–	–	–	–
Lower Atlantic (PADD 1C)	3.637	3.631	–	–	–	–
Midwest (PADD 2)	3.526	3.498	–	–	–	–

Region/State	2013 - 2014 Heating Season Weekly											
	9/30	10/7	10/14	10/21	10/28	11/4	11/11	11/18	11/25	12/2	12/9	12/16
Average	–	3.813	3.842	3.855	3.819	3.824	3.815	3.822	3.888	3.917	3.956	3.952
East Coast (PADD 1)	–	3.815	3.845	3.857	3.821	3.827	3.817	3.825	3.891	3.920	3.960	3.956
New England (PADD 1A)	–	3.744	3.767	3.785	3.757	3.768	3.766	3.773	3.840	3.865	3.918	3.921
Connecticut	–	3.913	3.952	3.967	3.925	3.945	3.943	3.943	4.038	4.064	4.119	4.104
Maine	–	3.565	3.569	3.575	3.559	3.561	3.559	3.558	3.584	3.626	3.658	3.688
Massachusetts	–	3.791	3.807	3.829	3.802	3.813	3.813	3.822	3.896	3.897	3.963	3.971
New Hampshire	–	3.571	3.593	3.613	3.600	3.623	3.619	3.621	3.671	3.718	3.787	3.793
Rhode Island	–	3.791	3.840	3.869	3.835	3.839	3.835	3.875	3.925	3.949	4.000	3.992
Vermont	–	3.590	3.582	3.615	3.588	3.580	3.575	3.575	3.682	3.710	3.734	3.716
Central Atlantic (PADD 1B)	–	3.873	3.908	3.916	3.873	3.875	3.859	3.867	3.933	3.965	3.996	3.987
Delaware	–	3.743	3.677	3.662	3.665	3.675	3.668	3.667	3.728	3.774	3.786	3.802
Dist Columbia	–	4.279	4.278	4.437	4.437	4.408	4.402	4.426	4.461	4.580	4.581	4.573
Maryland	–	3.799	3.799	3.863	3.867	3.828	3.825	3.800	3.853	3.885	3.926	3.942
New Jersey	–	3.858	3.880	3.918	3.876	3.912	3.887	3.900	3.966	4.026	4.060	4.054
New York	–	4.103	4.121	4.119	4.089	4.077	4.050	4.060	4.113	4.141	4.171	4.165
Pennsylvania	–	3.545	3.623	3.621	3.547	3.560	3.563	3.571	3.661	3.683	3.712	3.692
Lower Atlantic (PADD 1C)	–	3.637	3.643	3.632	3.634	3.623	3.633	3.627	3.641	3.677	3.683	3.663
North Carolina	–	3.652	3.652	3.647	3.639	3.636	3.612	3.614	3.616	3.637	3.637	3.636
Virginia	–	3.635	3.642	3.630	3.633	3.622	3.635	3.629	3.644	3.682	3.689	3.666
Midwest (PADD 2)	–	3.531	3.539	3.533	3.501	3.517	3.489	3.465	3.522	3.533	3.501	3.452
Indiana	–	3.577	3.600	3.590	3.584	3.622	3.576	3.550	3.574	3.581	3.532	3.472
Iowa	–	3.452	3.439	3.423	3.344	3.356	3.332	3.351	3.496	3.480	3.431	3.384
Kentucky	–	3.542	3.540	3.536	3.515	3.532	3.545	3.481	3.482	3.522	3.487	3.458
Michigan	–	3.564	3.588	3.577	3.582	3.572	3.532	3.510	3.620	3.611	3.596	3.508
Minnesota	–	3.586	3.592	3.579	3.514	3.491	3.481	3.479	3.550	3.578	3.566	3.544
Nebraska	–	3.451	3.450	3.445	3.354	3.331	3.291	3.281	3.358	3.373	3.383	3.377
Ohio	–	3.543	3.568	3.580	3.576	3.616	3.558	3.550	3.568	3.588	3.544	3.500
Wisconsin	–	3.527	3.518	3.537	3.500	3.549	3.508	3.501	3.588	3.581	3.535	3.451

– = Data Not Available.
Source: Based on data collected by State Energy Offices.

Table D2. Wholesale Heating Oil Prices by Region and State
(Dollars per Gallon, Excluding Taxes)

Region/State	2013 - 2014 Heating Season Monthly					
	October	November	December	January	February	March
Average	3.075	3.046	–	–	–	–
East Coast (PADD 1)	3.071	3.039	–	–	–	–
New England (PADD 1A)	3.105	3.077	–	–	–	–
Central Atlantic (PADD 1B)	3.054	3.024	–	–	–	–
Lower Atlantic (PADD 1C)	3.037	2.973	–	–	–	–
Midwest (PADD 2)	3.098	3.084	–	–	–	–

Region/State	2013 - 2014 Heating Season Weekly											
	9/30	10/7	10/14	10/21	10/28	11/4	11/11	11/18	11/25	12/2	12/9	12/16
Average	–	3.073	3.106	3.106	3.016	3.003	2.990	3.042	3.150	3.152	3.137	3.074
East Coast (PADD 1)	–	3.069	3.102	3.105	3.006	2.983	2.977	3.044	3.151	3.159	3.168	3.107
New England (PADD 1A)	–	3.106	3.136	3.137	3.040	3.019	3.012	3.084	3.194	3.205	3.222	3.166
Connecticut	–	3.084	3.116	3.111	3.021	2.996	3.001	3.074	3.187	3.198	3.207	3.143
Maine	–	3.111	3.139	3.149	3.026	3.012	3.006	3.074	3.179	3.181	3.202	3.158
Massachusetts	–	3.110	3.142	3.143	3.046	3.024	3.018	3.092	3.200	3.215	3.229	3.161
New Hampshire	–	3.118	3.142	3.142	3.071	3.052	3.003	3.076	3.200	3.216	3.247	3.238
Rhode Island	–	3.070	3.102	3.104	2.998	2.975	2.970	3.038	3.147	3.150	3.171	3.113
Vermont	–	3.190	3.223	3.229	3.129	3.114	3.115	3.190	3.301	3.309	3.334	3.274
Central Atlantic (PADD 1B)	–	3.050	3.084	3.089	2.991	2.968	2.964	3.030	3.135	3.144	3.149	3.084
Delaware	–	3.022	3.048	3.056	2.944	2.906	2.916	3.101	3.207	3.087	3.103	3.130
Maryland	–	3.011	3.045	3.054	2.956	2.937	2.920	2.992	3.109	3.099	3.111	3.047
New Jersey	–	3.029	3.061	3.062	2.971	2.940	2.939	3.002	3.106	3.114	3.122	3.065
New York	–	3.087	3.121	3.128	3.023	2.995	2.992	3.057	3.164	3.184	3.189	3.121
Pennsylvania	–	3.040	3.078	3.083	2.986	2.975	2.971	3.035	3.135	3.143	3.141	3.069
Lower Atlantic (PADD 1C)	–	3.038	3.069	3.073	2.968	2.935	2.916	2.966	3.074	3.069	3.075	3.010
North Carolina	–	3.000	3.035	3.037	2.941	2.913	2.894	2.939	3.045	3.046	3.043	2.982
Virginia	–	3.062	3.091	3.096	2.985	2.949	2.930	2.984	3.092	3.084	3.096	3.028
Midwest (PADD 2)	–	3.090	3.125	3.111	3.064	3.099	3.054	3.034	3.147	3.118	2.987	2.915
Illinois	–	3.027	3.036	3.025	3.001	3.062	2.984	2.978	3.135	3.092	2.947	2.865
Indiana	–	3.046	3.079	3.098	3.086	3.109	3.056	3.065	3.166	3.137	3.006	2.898
Iowa	–	3.095	3.123	3.075	2.966	2.943	2.975	2.990	3.180	3.147	3.036	3.030
Kansas	–	3.056	3.085	3.047	2.934	2.905	2.934	2.941	3.138	3.102	3.004	2.990
Kentucky	–	3.141	3.190	3.181	3.127	3.165	3.067	3.011	3.089	3.095	3.017	2.931
Michigan	–	3.045	3.093	3.064	3.001	3.064	3.015	3.009	3.154	3.114	2.966	2.861
Minnesota	–	3.140	3.160	3.108	2.984	2.979	3.004	3.025	3.219	3.170	3.056	3.046
Missouri	–	3.033	3.073	3.070	2.974	2.967	2.953	2.969	3.144	3.102	3.004	2.943
Nebraska	–	3.080	3.104	3.063	2.956	2.932	2.955	2.970	3.165	3.132	3.034	3.026
North Dakota	–	3.153	3.200	3.185	3.075	3.075	3.106	3.123	3.311	3.263	3.177	3.116
Ohio	–	3.117	3.152	3.139	3.108	3.151	3.133	3.097	3.165	3.130	2.959	2.900
South Dakota	–	3.177	3.199	3.152	3.059	3.032	3.047	3.037	3.201	3.167	3.094	3.084
Wisconsin	–	3.040	3.076	3.080	3.023	3.054	3.014	3.018	3.171	3.106	2.976	2.910

– = Data Not Available.
Source: Based on terminal quotes collected by the Oil Price Information Service (OPIS).

Figure D1. Residential Heating Oil Prices by PAD District (Dollars per Gallon, Excluding Taxes)



Source: Based on data collected by State Energy Offices.

Figure D2. Wholesale Heating Oil Prices by PAD District (Dollars per Gallon, Excluding Taxes)



Source: Based on data collected by Oil Price Information Service.

Table D3. Residential Propane Prices by Region and State
(Dollars per Gallon, Excluding Taxes)

Region/State	2012 - 2013 Heating Season Monthly					
	October	November	December	January	February	March
Average	2.205	2.241	2.249	2.279	2.312	2.315
East Coast (PADD 1)	2.909	2.936	2.937	2.963	3.001	3.002
New England (PADD 1A)	3.037	3.055	3.079	3.132	3.188	3.185
Central Atlantic (PADD 1B)	2.953	2.978	2.959	2.983	3.011	3.015
Lower Atlantic (PADD 1C)	2.698	2.737	2.758	2.762	2.801	2.801
Midwest (PADD 2)	1.662	1.704	1.717	1.750	1.780	1.785

Region/State	2013 - 2014 Heating Season Monthly					
	October	November	December	January	February	March
Average	2.370	2.495	–	–	–	–
East Coast (PADD 1)	2.995	3.087	–	–	–	–
New England (PADD 1A)	3.024	3.066	–	–	–	–
Central Atlantic (PADD 1B)	3.019	3.142	–	–	–	–
Lower Atlantic (PADD 1C)	2.918	2.995	–	–	–	–
Midwest (PADD 2)	1.860	2.012	–	–	–	–

Region/State	2013 - 2014 Heating Season Weekly											
	9/30	10/7	10/14	10/21	10/28	11/4	11/11	11/18	11/25	12/2	12/9	12/16
Average	–	2.358	2.337	2.377	2.406	2.450	2.482	2.506	2.542	2.566	2.621	2.712
East Coast (PADD 1)	–	2.999	2.965	3.003	3.013	3.044	3.073	3.090	3.141	3.165	3.246	3.315
New England (PADD 1A)	–	3.032	3.028	3.024	3.012	3.033	3.047	3.064	3.121	3.172	3.257	3.314
Connecticut	–	2.961	2.878	2.937	2.960	2.994	3.038	3.034	3.083	3.110	3.189	3.260
Maine	–	2.678	2.675	2.694	2.693	2.729	2.752	2.786	2.804	2.837	2.922	2.997
Massachusetts	–	3.137	3.088	3.138	3.114	3.129	3.163	3.137	3.219	3.233	3.331	3.368
New Hampshire	–	3.027	3.016	3.005	2.979	2.987	2.983	2.984	3.054	3.136	3.212	3.256
Rhode Island	–	3.547	3.493	3.570	3.577	3.574	3.565	3.600	3.678	3.709	3.773	3.831
Vermont	–	3.227	3.331	3.204	3.185	3.218	3.235	3.299	3.357	3.418	3.523	3.590
Central Atlantic (PADD 1B)	–	2.997	2.981	3.038	3.059	3.095	3.122	3.145	3.204	3.213	3.307	3.383
Delaware	–	2.985	3.048	3.020	3.043	3.086	3.069	3.088	3.114	3.158	3.210	3.209
Maryland	–	3.164	3.215	3.277	3.250	3.293	3.327	3.306	3.337	3.363	3.455	3.505
New Jersey	–	3.474	3.467	3.586	3.606	3.616	3.603	3.591	3.642	3.653	3.783	3.853
New York	–	2.864	2.840	2.855	2.912	2.933	3.008	3.049	3.121	3.154	3.237	3.335
Pennsylvania	–	2.931	2.893	2.980	2.979	3.035	3.033	3.061	3.124	3.101	3.199	3.274
Lower Atlantic (PADD 1C)	–	2.971	2.871	2.908	2.920	2.948	2.999	3.001	3.031	3.059	3.109	3.177
North Carolina	–	2.937	2.897	2.869	2.882	2.912	2.967	2.955	2.975	2.998	3.051	3.116
Virginia	–	3.068	2.796	3.018	3.029	3.051	3.088	3.129	3.188	3.233	3.273	3.351
Midwest (PADD 2)	–	1.835	1.826	1.867	1.911	1.966	2.000	2.030	2.053	2.077	2.111	2.221
Indiana	–	2.057	2.063	2.136	2.176	2.256	2.305	2.341	2.420	2.455	2.518	2.662
Iowa	–	1.527	1.525	1.556	1.586	1.621	1.651	1.658	1.683	1.689	1.749	1.877
Kentucky	–	2.119	2.056	2.119	2.147	2.207	2.207	2.272	2.237	2.256	2.300	2.376
Michigan	–	2.062	2.024	2.101	2.127	2.150	2.163	2.196	2.213	2.216	2.263	2.359
Minnesota	–	1.675	1.671	1.692	1.774	1.846	1.894	1.945	1.973	1.980	2.001	2.130
Missouri	–	1.796	1.743	1.829	1.842	1.901	1.901	1.915	1.932	1.948	2.014	2.126
Nebraska	–	1.540	1.543	1.537	1.567	1.596	1.646	1.662	1.670	1.682	1.727	1.844
North Dakota	–	1.563	1.583	1.593	1.710	1.843	1.947	1.957	1.961	1.955	1.974	2.084
Ohio	–	2.344	2.364	2.391	2.441	2.512	2.549	2.581	2.628	2.762	2.705	2.754
South Dakota	–	1.582	1.577	1.606	1.677	1.720	1.792	1.796	1.803	1.801	1.857	1.955
Wisconsin	–	1.675	1.687	1.697	1.738	1.761	1.797	1.835	1.845	1.857	1.894	2.025

– = Data Not Available.
Source: Based on data collected by State Energy Offices.

Table D4. Wholesale Propane Prices by Region and State
(Dollars per Gallon, Excluding Taxes)

Region/State	2013 - 2014 Heating Season Monthly					
	October	November	December	January	February	March
Average	1.259	1.396	–	–	–	–
East Coast (PADD 1)	1.362	1.482	–	–	–	–
Central Atlantic (PADD 1B)	1.398	1.520	–	–	–	–
Lower Atlantic (PADD 1C)	1.307	1.426	–	–	–	–
Midwest (PADD 2)	1.224	1.362	–	–	–	–

Region/State	2013 - 2014 Heating Season Weekly											
	9/30	10/7	10/14	10/21	10/28	11/4	11/11	11/18	11/25	12/2	12/9	12/16
Average	–	1.202	1.251	1.273	1.311	1.365	1.381	1.412	1.427	1.406	1.524	1.637
East Coast (PADD 1)	–	1.324	1.351	1.378	1.394	1.427	1.442	1.509	1.551	1.548	1.660	1.712
Central Atlantic (PADD 1B)	–	1.349	1.389	1.418	1.437	1.473	1.493	1.530	1.584	1.587	1.702	1.751
Delaware	–	–	–	–	–	–	–	–	–	–	–	–
New Jersey	–	1.423	1.485	1.511	1.559	1.554	1.575	1.583	1.596	1.624	1.672	1.672
New York	–	1.331	1.374	1.409	1.423	1.494	1.516	1.562	1.637	1.642	1.792	1.864
Pennsylvania	–	1.293	1.345	1.371	1.378	1.414	1.432	1.478	1.541	1.529	1.659	1.720
Lower Atlantic (PADD 1C)	–	1.286	1.295	1.318	1.330	1.357	1.366	1.479	1.503	1.489	1.596	1.653
North Carolina	–	1.242	1.276	1.292	1.289	1.312	1.327	1.440	1.468	1.428	1.540	1.596
Virginia	–	1.330	1.345	1.385	1.435	1.472	1.468	1.578	1.592	1.645	1.740	1.800
Midwest (PADD 2)	–	1.174	1.211	1.231	1.278	1.341	1.356	1.373	1.379	1.351	1.471	1.607
Illinois	–	1.188	1.227	1.240	1.306	1.370	1.358	1.388	1.375	1.332	1.473	1.644
Indiana	–	1.242	1.286	1.308	1.383	1.475	1.436	1.484	1.509	1.484	1.636	1.772
Iowa	–	1.162	1.199	1.208	1.252	1.308	1.330	1.338	1.331	1.305	1.416	1.549
Kansas	–	1.128	1.154	1.171	1.207	1.260	1.281	1.288	1.279	1.254	1.375	1.518
Minnesota	–	1.176	1.205	1.229	1.296	1.369	1.410	1.416	1.409	1.384	1.481	1.623
Missouri	–	1.182	1.215	1.234	1.263	1.298	1.324	1.333	1.363	1.343	1.460	1.597
Nebraska	–	1.140	1.175	1.186	1.225	1.271	1.292	1.298	1.289	1.264	1.383	1.514
North Dakota	–	1.062	1.107	1.174	1.271	1.357	1.395	1.424	1.391	1.371	1.452	1.625
Ohio	–	1.258	1.289	1.327	1.347	1.413	1.433	1.476	1.537	1.516	1.635	1.703
South Dakota	–	1.155	1.190	1.197	1.239	1.285	1.302	1.307	1.302	1.278	1.398	1.528
Wisconsin	–	1.217	1.256	1.276	1.331	1.418	1.441	1.443	1.453	1.410	1.525	1.662

– = Data Not Available.
Source: Based on terminal quotes collected by the Oil Price Information Service (OPIS).

Figure D3. Residential Propane Prices by PAD District (Dollars per Gallon, Excluding Taxes)



Source: Based on data collected by State Energy Offices.

Figure D4. Wholesale Propane Prices by PAD District (Dollars per Gallon, Excluding Taxes)



Source: Based on data collected by Oil Price Information Service.

Appendix D

Winter Fuels Explanatory Notes

Prices

The residential No. 2 heating oil and propane prices (excluding taxes) for a given State are based on the results of two independent telephone surveys of marketers and refiners, one for each of the two products. Data are collected by State Energy Offices under the Energy Information Administration (EIA) State Heating Oil and Propane Program (SHOPP).

Sampling Methodology and Estimation Procedures for Residential No. 2 Heating Oil

The No.2 heating oil price data are reported by a statistical sample. According to the requirement of the SHOPP program, 21 States and the District of Columbia (DC) in the East Coast and Midwest regions participate in the No.2 heating oil price survey. The sampling frame used was a list of all Company State Units (CSUs) in those 21 States and DC that reported residential No. 2 heating oil sales on the 2006 Form EIA-863, "Petroleum Product Sales Survey." CSUs that sold at least 5% of the residential No.2 heating oil in a State, as reported in the frame survey EIA-863, were automatically included in the sample and are referred to as certainty units. The remaining CSUs, referred to as non-certainty units, were stratified into three groups by their residential No.2 heating oil sales volumes in each State. Strata boundaries were determined using the Dalenius-Hodges procedure. The sample allocations were designed generally to yield average price coefficients of variation (CV) of 1%, but, due to budget constraints, individual State sample sizes were capped at 35 even if the target CV was not met. In addition, a minimum size of 15 was required for each of the 21 States. The sample of CSUs within each stratum was a simple random sample. The residential No.2 heating oil sample size inclusive of certainty and non-certainty units is 527 CSUs.

To estimate the average residential No. 2 heating oil price data for a State, the sample and volume weights are applied to the reported price, summed and divided by the sum of the weighted volume:

$$\sum_{j=1}^{s}\sum_{i=1}^{n_j} w_{ij} v_{ij} p_{ij} \Big/ \sum_{j=1}^{s}\sum_{i=1}^{n_j} w_{ij} v_{ij}$$

where w_{ij} = sample weight, v_{ij} = volume weight, p_{ij} = price, i = respondent, n_j = sample size of stratum j, and s = number of strata. The sample weights w_{ij} were calculated as ratios of population number of CSUs to the sampled number of CSUs in each stratum. Volume weights v_{ij} were assigned using the data reported in the frame survey.

State level residential No. 2 heating oil average prices are then aggregated into regional and overall averages with State level total prime supplier volumes as weights.

These fixed volume weights indicate the relative importance of the individual companies according to the size of their sales at the time of the frame. Therefore, changes in the average price across time reflect only the change in the price being offered by the company, and not changes in the amounts sold. Price indexes constructed using fixed volumes, such as these annual sales, are known as Laspeyres Indexes. One alternative method of weighting, used in Paasche Indexes, uses current weights. This method would require each company to report the number of gallons sold at the reported price each pricing period and would be more burdensome on the companies. Both methods of weighting are correct but provide different averages particularly when volumes are changing. It has been argued in the literature that during periods of change, the Laspeyres method has a tendency to overestimate price changes, while the Paasche method tends to underestimate price changes.

In this survey, it is expected that the change in volumes weekly during the heating season is small. Residential sales are not bulk in nature and do not tend to reflect discounts on price for large volume purchases. Absolute changes in volume within a year's time would more likely reflect demand and be consistent across companies within a geographical area. Therefore, even though the volume weights used in the calculation of average prices in the SHOPP tend to lag behind the actual volumes sold in the reference period, fixed volumes are used to reduce company burden and enable timely release of average prices.

Sampling Methodology and Estimation Procedures for Residential Propane

The propane price data are reported by a statistical sample. According to the requirement of the SHOPP program, 24 States in the East Coast and Midwest regions participate in the propane price survey. The sampling frame used was a list of all Company State Units (CSUs) in those 24 States that reported residential propane sales on the 2006 Form EIA-863, "Petroleum Product Sales Survey." The population of the survey was first stratified by State which is the publication cell. Due to high residential propane price variation and budget constraints, sample sizes of all strata were limited to 30 even though the target CV of 1% was not met in many States. To select the sample, the CSUs in each State were ordered by zip code in order to control for the geographic location of the companies. A Probability Proportional to Size (PPS) Systematic Sample with Probability Minimum Replacement, using the propane volumes reported in the frame survey EIA-863 as a measure of sampling unit size, was then selected from this ordering. With the targeted maximum sample size of 30 CSUs in each State, any CSU that sold more than 3.3% (1/30) of the residential propane in a State was selected at least once. Within each sampled CSU, a simple random sample of residential propane outlets was drawn by using an outlet address listing EIA developed with information provided by the industry and State energy officials. The number of outlets selected from each CSU was the same as the number of times that CSU was selected in the PPS sample. The resulting total number of outlets selected to report on the propane sample was 720.

In cases where there were fewer outlets in a sampled CSU than the number of times that CSU was sampled in the PPS sample, all outlets for that CSU were selected and their weights were adjusted to $n_i^{'}/n_i$, where $n_i^{'}$ is the number of times that CSU was sampled and n_i is

the number of outlets sampled. (This was also the practice if a CSU preferred to report on the survey by providing the average of all its outlets in a given State.). Therefore, the actual number responding each month may deviate from the 720 outlets sampled.

To estimate the average residential propane price data for a State, a simple average of the prices from each sampled outlet yields a valid estimate as a result of the cancellation of sample weights of the PPS sample design and volume weights in the estimate:

$$\frac{1}{n}\sum_{i=1}^{n}\frac{n_i'}{n_i}p_i$$

where p_i = price, i = outlet respondent, n = sample size, and n_i'/n_i = weight adjustment as described in previous paragraph.

Regional and overall averages are calculated as averages of the State level residential propane prices with State level total prime supplier volumes as weights.

Revision Error

Numbers may be revised in the publication based on data received late or receipt of revised data. Numbers are published as preliminary and final. The difference between preliminary and final data is called the revision error.

Response Rate

Response rates are generally 95 to 100 percent.

Note 3. Confidentiality of Information

The information contained on Form EIA-877 will be kept confidential and not disclosed to the public to the extent that it satisfies the criteria for exemption under the Freedom of Information Act (FOIA), 5 U.S.C. Sec. 552, the DOE regulations, 10 C.F.R. Sec. 1004.11, implementing the FOIA, and the Trade Secrets Act, 18 U.S.C. Sec. 1905. The EIA will protect individual respondent's information in accordance with its confidentiality and security policies and procedures.

The Federal Energy Administration Act requires the EIA to provide company-specific data to other Federal agencies when requested for official use. The information reported on the Form EIA-877 may also be made available, upon request, to another component of the Department of Energy (DOE); to any Committee of Congress, the General Accounting Office, or other Federal agencies authorized by law to receive such information. A court of competent jurisdiction may obtain this information in response to an order.

Definitions of Petroleum Products and Other Terms

(Revised May 2010)

Alcohol. The family name of a group of organic chemical compounds composed of carbon, hydrogen, and oxygen. The series of molecules vary in chain length and are composed of a hydrocarbon plus a hydroxyl group; CH3-(CH2)n-OH (e.g., methanol, ethanol, and tertiary butyl alcohol).

Alkylate. The product of an alkylation reaction. It usually refers to the high octane product from alkylation units. This alkylate is used in blending high octane gasoline.

Alkylation. A refining process for chemically combining isobutane with olefin hydrocarbons (e.g., propylene, butylene) through the control of temperature and pressure in the presence of an acid catalyst, usually sulfuric acid or hydrofluoric acid. The product, alkylate, an isoparaffin, has high octane value and is blended with motor and aviation gasoline to improve the antiknock value of the fuel.

All Other Motor Gasoline Blending Components. See Motor Gasoline Blending Components.

API Gravity. An arbitrary scale expressing the gravity or density of liquid petroleum products. The measuring scale is calibrated in terms of degrees API; it may be calculated in terms of the following formula:

$$Degrees\ API = \frac{141.5}{sp.\ gr.\ @\ 60^{o}F} - 131.5$$

The higher the API gravity, the lighter the compound. Light crudes generally exceed 38 degrees API and heavy crudes are commonly labeled as all crudes with an API gravity of 22 degrees or below. Intermediate crudes fall in the range of 22 degrees to 38 degrees API gravity.

Aromatics. Hydrocarbons characterized by unsaturated ring structures of carbon atoms. Commercial petroleum aromatics are benzene, toluene, and xylene (BTX).

Asphalt. A dark-brown-to-black cement-like material containing bitumens as the predominant constituent obtained by petroleum processing; used primarily for road construction. It includes crude asphalt as well as the following finished products: cements, fluxes, the asphalt content of emulsions (exclusive of water), and petroleum distillates blended with asphalt to make cutback asphalts. Note: The conversion factor for asphalt is 5.5 barrels per short ton.

ASTM. The acronym for the American Society for Testing and Materials.

Atmospheric Crude Oil Distillation. The refining process of separating crude oil components at atmospheric pressure by heating to temperatures of about 600 degrees Fahrenheit to 750 degrees Fahrenheit (depending on the nature of the crude oil and desired products) and subsequent condensing of the fractions by cooling.

Aviation Gasoline (Finished). A complex mixture of relatively volatile hydrocarbons with or without small quantities of additives, blended to form a fuel suitable for use in aviation reciprocating engines. Fuel specifications are provided in ASTM Specification D 910 and Military Specification MIL-G-5572. Note: Data on blending components are not counted in data on finished aviation gasoline.

Aviation Gasoline Blending Components. Naphthas which will be used for blending or compounding into finished aviation gasoline (e.g., straight-run gasoline, alkylate, reformate, benzene, toluene, and xylene). Excludes oxygenates (alcohols, ethers), butane, and pentanes plus. Oxygenates are reported as other hydrocarbons, hydrogen, and oxygenates.

Barrel. A unit of volume equal to 42 U.S. gallons.

Barrels Per Calendar Day. The amount of input that a distillation facility can process under usual operating conditions. The amount is expressed in terms of capacity during a 24-hour period and reduces the maximum processing capability of all units at the facility under continuous operation (see **Barrels per Stream Day**) to account for the following limitations that may delay, interrupt, or slow down production:

- the capability of downstream facilities to absorb the output of crude oil processing facilities of a given refinery. No reduction is made when a planned distribution of intermediate streams through other than downstream facilities is part of a refinery's normal operation;
- the types and grades of inputs to be processed;
- the types and grades of products expected to be manufactured;
- the environmental constraints associated with refinery operations;
- the reduction of capacity for scheduled downtime due to such conditions as routine inspection, maintenance, repairs, and turnaround; and
- the reduction of capacity for unscheduled downtime due to such conditions as mechanical problems, repairs, and slowdowns.

Barrels Per Stream Day. The maximum number of barrels of input that a distillation facility can process within a 24-hour period when running at full capacity under optimal crude and product slate conditions with no allowance for downtime.

Benzene (C_6H_6). An aromatic hydrocarbon present in small proportion in some crude oils and made commercially from petroleum by the catalytic reforming of naphthenes in petroleum naphtha. Also made from coal in the manufacture of coke. Used as a solvent, in manufacturing detergents, synthetic fibers, and petrochemicals and as a component of high-octane gasoline.

Biomass-Based Diesel Fuel. Biodiesel and other renewable diesel fuel or diesel fuel blending components derived from biomass, but excluding renewable diesel fuel coprocessed with petroleum

feedstocks.

Blending Components. See Motor or Aviation Gasoline Blending Components.

Blending Plant. A facility which has no refining capability but is either capable of producing finished motor gasoline through mechanical blending or blends oxygenates with motor gasoline.

Bonded Petroleum Imports. Petroleum imported and entered into Customs bonded storage. These imports are not included in the import statistics until they are: (1) withdrawn from storage free of duty for use as fuel for vessels and aircraft engaged in international trade; or (2) withdrawn from storage with duty paid for domestic use.

BTX. The acronym for the commercial petroleum aromatics benzene, toluene, and xylene. See individual categories for definitions.

Bulk Station. A facility used primarily for the storage and/or marketing of petroleum products which has a total bulk storage capacity of less than 50,000 barrels and receives its petroleum products by tank car or truck.

Bulk Terminal. A facility used primarily for the storage and/or marketing of petroleum products which has a total bulk storage capacity of 50,000 barrels or more and/or receives petroleum products by tanker, barge, or pipeline.

Butane (C_4H_{10}). A normally gaseous straight-chain or branch-chain hydrocarbon extracted from natural gas or refinery gas streams. It includes normal butane and refinery-grade butane and is designated in ASTM Specification D1835 and Gas Processors Association Specifications for commercial butane.

> ***Normal Butane (C_4H_{10}).*** A normally gaseous straight-chain hydrocarbon that is a colorless paraffinic gas which boils at a temperature of 31.1 degrees Fahrenheit and is extracted from natural gas or refinery gas streams.
>
> ***Refinery-Grade Butane (C_4H_{10}).*** A refinery-produced stream that is composed predominantly of normal butane and/or isobutane and may also contain propane and/or natural gasoline. These streams may also contain significant levels of olefins and/or fluorides contamination.

Butylene (C_4H_8). An olefinic hydrocarbon recovered from refinery processes.

Captive Refinery Oxygenate Plants. Oxygenate production facilities located within or adjacent to a refinery complex.

Catalytic Cracking. The refining process of breaking down the larger, heavier, and more complex hydrocarbon molecules into simpler and lighter molecules. Catalytic cracking is accomplished by the use of a catalytic agent and is an effective process for increasing the yield of gasoline from crude oil. Catalytic cracking processes fresh feeds and recycled feeds.

> ***Fresh Feeds.*** Crude oil or petroleum distillates which are being fed to processing units for the first time.
> ***Recycled Feeds.*** Feeds that are continuously fed back for additional processing.

Catalytic Hydrocracking. A refining process that uses hydrogen and catalysts with relatively low temperatures and high pressures for converting middle boiling or residual material to high-octane gasoline, reformer charge stock, jet fuel, and/or high grade fuel oil. The process uses one or more catalysts, depending upon product output, and can handle high sulfur feedstocks without prior desulfurization.

Catalytic Hydrotreating. A refining process for treating petroleum fractions from atmospheric or vacuum distillation units (e.g., naphthas, middle distillates, reformer feeds, residual fuel oil, and heavy gas oil) and other petroleum (e.g., cat cracked naphtha, coker naphtha, gas oil, etc.) in the presence of catalysts and substantial quantities of hydrogen. Hydrotreating includes desulfurization, removal of substances (e.g., nitrogen compounds) that deactivate catalysts, conversion of olefins to paraffins to reduce gum formation in gasoline, and other processes to upgrade the quality of the fractions.

Catalytic Reforming. A refining process using controlled heat and pressure with catalysts to rearrange certain hydrocarbon molecules, thereby converting paraffinic and naphthenic type hydrocarbons (e.g., low-octane gasoline boiling range fractions) into petrochemical feedstocks and higher octane stocks suitable for blending into finished gasoline. Catalytic reforming is reported in two categories. They are:

> ***Low Pressure.*** A processing unit operating at less than 225 pounds per square inch gauge (PSIG) measured at the outlet separator.
>
> ***High Pressure.*** A processing unit operating at either equal to or greater than 225 pounds per square inch gauge (PSIG) measured at the outlet separator.

Charge Capacity. The input (feed) capacity of the refinery processing facilities.

Coal. A readily combustible black or brownish-black rock whose composition, including inherent moisture, consists of more than 50 percent by weight and more than 70 percent by volume of carbonaceous material. It is formed from plant remains that have been compacted, hardened, chemically altered, and metamorphosed by heat and pressure over geologic time.

Commercial Kerosene-Type Jet Fuel. See ***Kerosene-Type Jet Fuel.***

Conventional Blendstock for Oxygenate Blending (CBOB). See ***Motor Gasoline Blending Components.***

Conventional Gasoline. See ***Motor Gasoline (Finished).***

Crude Oil. A mixture of hydrocarbons that exists in liquid phase in natural underground reservoirs and remains liquid at atmospheric pressure after passing through surface separating facilities. Depending upon the characteristics of the crude stream, it may also include:

> Small amounts of hydrocarbons that exist in gaseous phase in natural underground reservoirs but are liquid at atmospheric pressure after being recovered from oil well (casinghead) gas in lease separators and are subsequently commingled with the crude stream without being separately measured.

Lease condensate recovered as a liquid from natural gas wells in lease or field separation facilities and later mixed into the crude stream is also included;

Small amounts of nonhydrocarbons produced from oil, such as sulfur and various metals;

Drip gases, and liquid hydrocarbons produced from tar sands, oil sands, gilsonite, and oil shale.

Liquids produced at natural gas processing plants are excluded. Crude oil is refined to produce a wide array of petroleum products, including heating oils; gasoline, diesel and jet fuels; lubricants; asphalt; ethane, propane, and butane; and many other products used for their energy or chemical content.

Crude oil is considered as either domestic or foreign, according to the following:

Domestic. Crude oil produced in the United States or from its Aouter continental shelf' as defined in 43 USC 1331.

Foreign. Crude oil produced outside the United States. Imported Athabasca hydrocarbons (tar sands from Canada) are included.

Crude Oil, Refinery Receipts. Receipts of domestic and foreign crude oil at a refinery. Includes all crude oil in transit except crude oil in transit by pipeline. Foreign crude oil is reported as a receipt only after entry through customs. Crude oil of foreign origin held in bonded storage is excluded.

Crude Oil Losses. Represents the volume of crude oil reported by petroleum refineries as being lost in their operations. These losses are due to spills, contamination, fires, etc. as opposed to refinery processing losses.

Crude Oil Production. The volume of crude oil produced from oil reservoirs during given periods of time. The amount of such production for a given period is measured as volumes delivered from lease storage tanks (i.e., the point of custody transfer) to pipelines, trucks, or other media for transport to refineries or terminals with adjustments for (1) net differences between opening and closing lease inventories, and (2) basic sediment and water (BS&W).

Crude Oil Qualities. Refers to two properties of crude oil, the sulfur content and API gravity, which affect processing complexity and product characteristics.

Delayed Coking. A process by which heavier crude oil fractions can be thermally decomposed under conditions of elevated temperatures and pressure to produce a mixture of lighter oils and petroleum coke. The light oils can be processed further in other refinery units to meet product specifications. The coke can be used either as a fuel or in other applications such as the manufacturing of steel or aluminum.

Desulfurization. The removal of sulfur, as from molten metals, petroleum oil, or flue gases. Petroleum desulfurization is a process that removes sulfur and its compounds from various streams during the refining process. Desulfurization processes include catalytic hydrotreating and other chemical/physical processes such as adsorption. Desulfurization processes vary based on the type of stream treated (e.g., naphtha, distillate, heavy gas oil, etc.) and the amount of sulfur removed (e.g., sulfur reduction to 10 ppm). See ***Catalytic Hydrotreating.***

Disposition. The components of petroleum disposition are stock change, crude oil losses, refinery inputs, exports, and products supplied for domestic consumption.

Distillate Fuel Oil. A general classification for one of the petroleum fractions produced in conventional distillation operations. It includes diesel fuels and fuel oils. Products known as No. 1, No. 2, and No. 4 diesel fuel are used in on-highway diesel engines, such as those in trucks and automobiles, as well as off-highway engines, such as those in railroad locomotives and agricultural machinery. Products known as No. 1, No. 2, and No. 4 fuel oils are used primarily for space heating and electric power generation.

No. 1 Distillate. A light petroleum distillate that can be used as either a diesel fuel or a fuel oil.

No. 1 Diesel Fuel. A light distillate fuel oil that has a distillation temperature of 550 degrees Fahrenheit at the 90-percent recovery point and meets the specifications defined in ASTM Specification D 975. It is used in high speed diesel engines generally operated under frequent speed and load changes, such as those in city buses and similar vehicles. See ***No. 1 Distillate.***

No. 1 Fuel Oil. A light distillate fuel oil that has distillation temperatures of 400 degrees Fahrenheit at the 10-percent recovery point and 550 degrees Fahrenheit at the 90-percent recovery point and meets the specifications defined in ASTM Specification D 396. It is used primarily as fuel for portable outdoor stoves and portable outdoor heaters. See ***No. 1 Distillate.***

No. 2 Distillate. A petroleum distillate that can be used as either a diesel fuel or a fuel oil.

No. 2 Diesel Fuel. A distillate fuel oil that has a distillation temperature of 640 degrees Fahrenheit at the 90-percent recovery point and meets the specifications defined in ASTM Specification D 975. It is used in high-speed diesel engines that are generally operated under uniform speed and load conditions, such as those in railroad locomotives, trucks, and automobiles. See ***No. 2 Distillate.***

Ultra-Low Sulfur No. 2 Diesel Fuel. Diesel fuel oil having sulfur content of 15 ppm or lower. Ultra-low sulfur diesel fuel oil that will be shipped by pipeline must satisfy the sulfur specification of the shipping pipeline if the pipeline specification is below 15 ppm. Diesel fuel oil intended for pipeline shipment that fails to meet a pipeline sulfur specification that is below 15 ppm will be classified as low-sulfur diesel fuel oil.

Low Sulfur No. 2 Diesel Fuel. No. 2 diesel fuel that has a sulfur level no higher than 0.05 percent by weight. It is used primarily in motor vehicle diesel engines for on-highway use.

High Sulfur No. 2 Diesel Fuel. No. 2 diesel fuel that has a sulfur level above 0.05 percent by weight.

No. 2 Fuel Oil (Heating Oil). A distillate fuel oil that has a distillation temperature of 640 degrees Fahrenheit at the 90-percent recovery point and meets the specifications defined in ASTM Specification D 396. It is used in atomizing type burners for domestic heating or for moderate capacity commercial/industrial burner units. See ***No. 2 Distillate***.

No. 4 Fuel. A distillate fuel oil made by blending distillate fuel oil and residual fuel oil stocks. It conforms to ASTM Specification D 396 or Federal Specification VV-F-815C and is used extensively in industrial plants and in commercial burner installations that are not equipped with preheating facilities. It also includes No. 4 diesel fuel used for low- and medium-speed diesel engines and conforms to ASTM Specification D 975.

No. 4 Diesel Fuel. See ***No. 4 Fuel.***

No. 4 Fuel Oil. See ***No. 4 Fuel.***

Electricity (Purchased). Electricity purchased for refinery operations that is not produced within the refinery complex.

Ending Stocks. Primary stocks of crude oil and petroleum products held in storage as of 12 midnight on the last day of the month. Primary stocks include crude oil or petroleum products held in storage at (or in) leases, refineries, natural gas processing plants, pipelines, tank farms, and bulk terminals that can store at least 50,000 barrels of petroleum products or that can receive petroleum products by tanker, barge, or pipeline. Crude oil that is in-transit by water from Alaska, or that is stored on Federal leases or in the Strategic Petroleum Reserve is included. Primary Stocks exclude stocks of foreign origin that are held in bonded warehouse storage.

ETBE (Ethyl tertiary butyl ether) $(CH_3)_3COC_2H_5$. An oxygenate blend stock formed by the catalytic etherification of isobutylene with ethanol.

Ethane (C_2H_6). A normally gaseous straight-chain hydrocarbon. It is a colorless paraffinic gas that boils at a temperature of - 127.48 degrees Fahrenheit. It is extracted from natural gas and refinery gas streams.

Ether. A generic term applied to a group of organic chemical compounds composed of carbon, hydrogen, and oxygen, characterized by an oxygen atom attached to two carbon atoms (e.g., methyl tertiary butyl ether).

Ethylene (C_2H_4). An olefinic hydrocarbon recovered from refinery processes or petrochemical processes. Ethylene is used as a petrochemical feedstock for numerous chemical applications and the production of consumer goods.

Exports. Shipments of crude oil and petroleum products from the 50 States and the District of Columbia to foreign countries, Puerto Rico, the Virgin Islands, and other U.S. possessions and territories.

Field Production. Represents crude oil production on leases, natural gas liquids production at natural gas processing plants, new supply of other hydrocarbons/oxygenates and motor gasoline blending components, and fuel ethanol blended into finished motor gasoline.

Flexicoking. A thermal cracking process which converts heavy hydrocarbons such as crude oil, tar sands bitumen, and distillation residues into light hydrocarbons. Feedstocks can be any pumpable hydrocarbons including those containing high concentrations of sulfur and metals.

Fluid Coking. A thermal cracking process utilizing the fluidized-solids technique to remove carbon (coke) for continuous conversion of heavy, low-grade oils into lighter products.

Fresh Feed Input. Represents input of material (crude oil, unfinished oils, natural gas liquids, other hydrocarbons and oxygenates or finished products) to processing units at a refinery that is being processed (input) into a particular unit for the first time.

Examples:

(1.) Unfinished oils coming out of a crude oil distillation unit which are input into a catalytic cracking unit are considered fresh feed to the catalytic cracking unit.

(2.) Unfinished oils coming out of a catalytic cracking unit being looped back into the same catalytic cracking unit to be reprocessed are not considered fresh feed.

Fuel Ethanol (C_2H_5OH). An anhydrous alcohol (ethanol with less than 1% water) intended for gasoline blending as described in Oxygenates definition.

Fuels Solvent Deasphalting. A refining process for removing asphalt compounds from petroleum fractions, such as reduced crude oil. The recovered stream from this process is used to produce fuel products.

Gas Oil. A liquid petroleum distillate having a viscosity intermediate between that of kerosene and lubricating oil. It derives its name from having originally been used in the manufacture of illuminating gas. It is now used to produce distillate fuel oils and gasoline.

Gasohol. A blend of finished motor gasoline containing alcohol (generally ethanol but sometimes methanol) at a concentration of 10 percent or less by volume. Data on gasohol that has at least 2.7 percent oxygen, by weight, and is intended for sale inside carbon monoxide nonattainment areas are included in data on oxygenated gasoline. See ***Oxygenates***.

Gasoline Blending Components. Naphthas which will be used for blending or compounding into finished aviation or motor gasoline (e.g., straight-run gasoline, alkylate, reformate, benzene, toluene, and xylene). Excludes oxygenates (alcohols, ethers), butane, and pentanes plus.

Gasoline Treated as Blendstock (GTAB). See ***Motor Gasoline Blending Components.***

Gross Input to Atmospheric Crude Oil Distillation Units. Total input to atmospheric crude oil distillation units. Includes all crude oil, lease condensate, natural gas plant liquids, unfinished oils, liquefied refinery gases, slop oils, and other liquid hydrocarbons produced from tar sands, gilsonite, and oil shale.

Heavy Gas Oil. Petroleum distillates with an approximate boiling range from 651 degrees Fahrenheit to 1000 degrees Fahrenheit.

High-Sulfur Distillate Fuel Oil. Distillate fuel oil having sulfur content greater than 500 ppm.

Hydrogen. The lightest of all gases, occurring chiefly in combination with oxygen in water; exists also in acids, bases, alcohols, petroleum, and other hydrocarbons.

Idle Capacity. The component of operable capacity that is not in operation and not under active repair, but capable of being placed in operation within 30 days; and capacity not in operation but under active repair that can be completed within 90 days.

Imported Crude Oil Burned As Fuel. The amount of foreign crude oil burned as a fuel oil, usually as residual fuel oil, without being processed as such. Imported crude oil burned as fuel includes lease condensate and liquid hydrocarbons produced from tar sands, gilsonite, and oil shale.

Imports. Receipts of crude oil and petroleum products into the 50 States and the District of Columbia from foreign countries, Puerto Rico, the Virgin Islands, and other U.S. possessions and territories.

Isobutane (C_4H_{10}). A normally gaseous branch-chain hydrocarbon. It is a colorless paraffinic gas that boils at a temperature of 10.9 degrees Fahrenheit. It is extracted from natural gas or refinery gas streams.

Isobutylene (C_4H_8). An olefinic hydrocarbon recovered from refinery processes or petrochemical processes.

Isohexane (C_6H_{14}). A saturated branch-chain hydrocarbon. It is a colorless liquid that boils at a temperature of 156.2 degrees Fahrenheit.

Isomerization. A refining process which alters the fundamental arrangement of atoms in the molecule without adding or removing anything from the original material. Used to convert normal butane into isobutane (C_4), an alkylation process feedstock, and normal pentane and hexane into isopentane (C_5) and isohexane (C_6), high-octane gasoline components.

Isopentane. See ***Natural Gasoline and Isopentane.***

Kerosene. A light petroleum distillate that is used in space heaters, cook stoves, and water heaters and is suitable for use as a light source when burned in wick-fed lamps. Kerosene has a maximum distillation temperature of 400 degrees Fahrenheit at the 10-percent recovery point, a final boiling point of 572 degrees Fahrenheit, and a minimum flash point of 100 degrees Fahrenheit. Included are No. 1-K and No. 2-K, the two grades recognized by ASTM Specification D 3699 as well as all other grades of kerosene called range or stove oil, which have properties similar to those of No. 1 fuel oil. See ***Kerosene-Type Jet Fuel.***

Kerosene-Type Jet Fuel. A kerosene-based product having a maximum distillation temperature of 400 degrees Fahrenheit at the 10-percent recovery point and a final maximum boiling point of 572 degrees Fahrenheit and meeting ASTM Specification D 1655 and Military Specifications MIL-T-5624P and MIL-T-83133D (Grades JP-5 and JP-8). It is used for commercial and military turbojet and turboprop aircraft engines.

> ***Commercial.*** Kerosene-type jet fuel intended for use in commercial aircraft.
>
> ***Military.*** Kerosene-type jet fuel intended for use in military aircraft.

Lease Condensate. A mixture consisting primarily of pentanes and heavier hydrocarbons which is recovered as a liquid from natural gas in lease separation facilities. This category excludes natural gas liquids, such as butane and propane, which are recovered at downstream natural gas processing plants or facilities. See ***Natural Gas Liquids.***

Light Gas Oils. Liquid Petroleum distillates heavier than naphtha, with an approximate boiling range from 401 degrees Fahrenheit to 650 degrees Fahrenheit.

Liquefied Petroleum Gases (LPG). A group of hydrocarbon-based gases derived from crude oil refining or natural gas fractionation. They include: ethane, ethylene, propane, propylene, normal butane, butylene, isobutane, and isobutylene. For convenience of transportation, these gases are liquefied through pressurization.

Liquefied Refinery Gases (LRG). Liquefied petroleum gases fractionated from refinery or still gases. Through compression and/or refrigeration, they are retained in the liquid state. The reported categories are ethane/ethylene, propane/propylene, normal butane/butylene, and isobutane/isobutylene. Excludes still gas.

Low-Sulfur Distillate Fuel Oil. Distillate fuel oil having sulfur content greater than 15 ppm to 500 ppm. Low sulfur distillate fuel oil also includes product with sulfur content equal to or less than 15 ppm if the product is intended for pipeline shipment and the pipeline has a sulfur specification below 15 ppm.

Lubricants. Substances used to reduce friction between bearing surfaces or as process materials either incorporated into other materials used as processing aids in the manufacture of other products, or used as carriers of other materials. Petroleum lubricants may be produced either from distillates or residues. Lubricants include all grades of lubricating oils from spindle oil to cylinder oil and those used in greases.

Merchant Oxygenate Plants. Oxygenate production facilities that are not associated with a petroleum refinery. Production from these facilities is sold under contract or on the spot market to refiners or other gasoline blenders.

Methanol (CH_3OH). A light, volatile alcohol intended for gasoline blending as described in Oxygenate definition.

Middle Distillates. A general classification of refined petroleum products that includes distillate fuel oil and kerosene.

Military Kerosene-Type Jet Fuel. See ***Kerosene-Type Jet Fuel.***

Miscellaneous Products. Includes all finished products not classified elsewhere (e.g., petrolatum, lube refining byproducts (aromatic extracts and tars), absorption oils, ram-jet fuel, petroleum rocket fuels, synthetic natural gas feedstocks, and specialty oils). Note: Beginning with January 2004 data, naphtha-type jet fuel is included in Miscellaneous Products.

Motor Gasoline (Finished). A complex mixture of relatively volatile hydrocarbons with or without small quantities of additives, blended to form a fuel suitable for use in spark-ignition engines. Motor gasoline, as defined in ASTM Specification D 4814 or Federal Specification VV-G-1690C, is characterized as having a boiling range of 122 to 158 degrees Fahrenheit at the 10 percent recovery point to 365 to 374 degrees Fahrenheit at the 90 percent recovery point. "Motor Gasoline" includes conventional gasoline; all types of oxygenated gasoline, including gasohol; and reformulated gasoline, but excludes aviation gasoline. Volumetric data on blending components, such as oxygenates, are not counted in data on finished motor gasoline until the blending components are blended into the gasoline. Note: E85 is included only in volumetric data on finished motor gasoline production and other components of product supplied.

Conventional Gasoline. Finished motor gasoline not included in the oxygenated or reformulated gasoline categories. Note: This category excludes reformulated gasoline blendstock for oxygenate blending (RBOB) as well as other blendstock.

Ed 55 and Lower. Finished conventional motor gasoline blended with a maximum of 55 volume percent denatured fuel ethanol.

Greater than Ed55. Finished conventional motor gasoline blended with denatured fuel ethanol where the volume percent of denatured fuel ethanol exceeds 55%.

OPRG. "Oxygenated Fuels Program Reformulated Gasoline" is reformulated gasoline which is intended for use in an oxygenated fuels program control area.

Oxygenated Gasoline (Including Gasohol). Oxygenated gasoline includes all finished motor gasoline, other than reformulated gasoline, having oxygen content of 2.0 percent or higher by weight. Gasohol containing a minimum 5.7 percent ethanol by volume is included in oxygenated gasoline. Oxygenated gasoline was reported as a separate product from January 1993 until December 2003 inclusive. Beginning with monthly data for January 2004, oxygenated gasoline is included in conventional gasoline. Historical data for oxygenated gasoline excluded Federal Oxygenated Program Reformulated Gasoline (OPRG). Historical oxygenated gasoline data also excluded other reformulated gasoline with a seasonal oxygen requirement regardless of season.

Reformulated Gasoline. Finished gasoline formulated for use in motor vehicles, the composition and properties of which meet the requirements of the reformulated gasoline regulations promulgated by the U.S. Environmental Protection Agency under Section 211(k) of the Clean Air Act. It includes gasoline produced to meet or exceed emissions performance and benzene content standards of federal-program reformulated gasoline even though the gasoline may not meet all of the composition requirements (e.g., oxygen content) of federal-program reformulated gasoline. Note: This category includes Oxygenated Fuels Program Reformulated Gasoline (OPRG). Reformulated gasoline excludes Reformulated Blendstock for Oxygenate Blending (RBOB) and Gasoline Treated as Blendstock (GTAB).

Reformulated (Blended with Alcohol). Reformulated gasoline blended with an alcohol component (e.g., fuel ethanol) at a terminal or refinery to raise the oxygen content.

Reformulated (Blended with Ether). Reformulated gasoline blended with an ether component (e.g., methyl tertiary butyl ether) at a terminal or refinery to raise the oxygen content.

Reformulated (Non-Oxygenated). Reformulated gasoline without added ether or alcohol components.

Motor Gasoline Blending. Mechanical mixing of motor gasoline blending components, and oxygenates when required, to produce finished motor gasoline. Finished motor gasoline may be further mixed with other motor gasoline blending components or oxygenates, resulting in increased volumes of finished motor gasoline and/or changes in the formulation of finished motor gasoline (e.g., conventional motor gasoline mixed with MTBE to produce oxygenated motor gasoline).

Motor Gasoline Blending Components. Naphthas (e.g., straight-run gasoline, alkylate, reformate, benzene, toluene, xylene) used for blending or compounding into finished motor gasoline. These components include reformulated gasoline blendstock for oxygenate blending (RBOB) but exclude oxygenates (alcohols, ethers), butane, and pentanes plus. Note: Oxygenates are reported as individual components and are included in the total for other hydrocarbons, hydrogens, and oxygenates.

Conventional Blendstock for Oxygenate Blending (CBOB). Conventional gasoline blendstock intended for blending with oxygenates downstream of the refinery where it was produced. CBOB must become conventional gasoline after blending with oxygenates. Motor gasoline blending components that require blending other than with oxygenates to become finished conventional gasoline are reported as All Other Motor Gasoline Blending Components. Excludes reformulated blendstock for oxygenate blending (RBOB).

Gasoline Treated as Blendstock (GTAB). Non-certified Foreign Refinery gasoline classified by an importer as blendstock to be either blended or reclassified with respect to

reformulated or conventional gasoline. GTAB was classified on EIA surveys as either reformulated or conventional based on emissions performance and the intended end use in data through the end of December 2009. Designation of GTAB as reformulated or conventional was discontinued beginning with data for January 2010. GTAB was reported as a single product beginning with data for January 2010. GTAB data for January 2010 and later months is presented as conventional motor gasoline blending components when reported as a subset of motor gasoline blending components.

Reformulated Blendstock for Oxygenate Blending (RBOB). Specially produced reformulated gasoline blendstock intended for blending with oxygenates downstream of the refinery where it was produced. Includes RBOB used to meet requirements of the Federal reformulated gasoline program and other blendstock intended for blending with oxygenates to produce finished gasoline that meets or exceeds emissions performance requirements of Federal reformulated gasoline (e.g., California RBOB and Arizona RBOB). Excludes conventional gasoline blendstocks for oxygenate blending (CBOB).

RBOB for Blending with Alcohol. Motor gasoline blending components intended to be blended with an alcohol component (e.g., fuel ethanol) at a terminal or refinery to raise the oxygen content. RBOB product detail by type of oxygenate was discontinued effective with data for January 2010. Beginning with data for January 2010, RBOB was reported as a single product.

RBOB for Blending with Ether. Motor gasoline blending components intended to be blended with an ether component (e.g., methyl tertiary butyl ether) at a terminal or refinery to raise the oxygen content. RBOB product detail by type of oxygenate was discontinued effective with data for January 2010. Beginning with data for January 2010, RBOB was reported as a single product.

All Other Motor Gasoline Blending Components. Naphthas (e.g., straight-run gasoline, alkylate, reformate, benzene, toluene, xylene) used for blending or compounding into finished motor gasoline. Includes receipts and inputs of Gasoline Treated as Blendstock (GTAB). Excludes conventional blendstock for oxygenate blending (CBOB), reformulated blendstock for oxygenate blending, oxygenates (e.g. fuel ethanol and methyl tertiary butyl ether), butane, and pentanes plus.

MTBE (Methyl tertiary butyl ether) $(CH_3)_3COCH_3$. An ether intended for gasoline blending as described in Oxygenate definition.

Naphtha. A generic term applied to a petroleum fraction with an approximate boiling range between 122 degrees Fahrenheit and 400 degrees Fahrenheit.

Naphtha Less Than 401° F. See ***Petrochemical Feedstocks.***

Naphtha-Type Jet Fuel. A fuel in the heavy naphtha boiling range having an average gravity of 52.8 degrees API, 20 to 90 percent distillation temperatures of 290 degrees to 470 degrees Fahrenheit, and meeting Military Specification MIL-T-5624L (Grade JP-4). It is used primarily for military turbojet and turboprop aircraft engines because it has a lower freeze point than other aviation fuels and meets engine requirements at high altitudes and speeds. Note: Beginning with January 2004 data, naphtha-type jet fuel is included in ***Miscellaneous Products.***

Natural Gas. A gaseous mixture of hydrocarbon compounds, the primary one being **methane**.

Natural Gas Field Facility. A field facility designed to process natural gas produced from more than one lease for the purpose of recovering condensate from a stream of natural gas; however, some field facilities are designed to recover propane, normal butane, pentanes plus, etc., and to control the quality of natural gas to be marketed.

Natural Gas Liquids. Those hydrocarbons in natural gas that are separated from the gas as liquids through the process of absorption, condensation, adsorption, or other methods in gas processing or cycling plants. Generally such liquids consist of propane and heavier hydrocarbons and are commonly referred to as lease condensate, natural gasoline, and liquefied petroleum gases. Natural gas liquids include natural gas plant liquids (primarily ethane, propane, butane, and isobutane; see ***Natural Gas Plant Liquids***) and lease condensate (primarily pentanes produced from natural gas at lease separators and field facilities; see ***Lease Condensate***).

Natural Gas Plant Liquids. Those hydrocarbons in natural gas that are separated as liquids at natural gas processing plants, fractionating and cycling plants, and, in some instances, field facilities. Lease condensate is excluded. Products obtained include ethane; liquefied petroleum gases (propane, butanes, propane-butane mixtures, ethane-propane mixtures); isopentane; and other small quantities of finished products, such as motor gasoline, special naphthas, jet fuel, kerosene, and distillate fuel oil.

Natural Gas Processing Plant. Facilities designed to recover natural gas liquids from a stream of natural gas that may or may not have passed through lease separators and/or field separation facilities. These facilities control the quality of the natural gas to be marketed. Cycling plants are classified as gas processing plants.

Natural Gasoline and Isopentane. A mixture of hydrocarbons, mostly pentanes and heavier, extracted from natural gas, that meets vapor pressure, end-point, and other specifications for natural gasoline set by the Gas Processors Association. Includes isopentane which is a saturated branch-chain hydrocarbon, (C_5H_{12}), obtained by fractionation of natural gasoline or isomerization of normal pentane.

Net Receipts. The difference between total movements into and total movements out of each PAD District by pipeline, tanker, and barge.

Normal Butane. See ***Butane***.

OPEC. An intergovernmental organization whose stated objective is to coordinate and unify petroleum policies of member countries. It was created at the Baghdad Conference on September 10–14, 1960. Current members (with years of membership) include Algeria

(1969-present), Angola (2007-present), Ecuador (1973-1992 and 2007-present), Iran (1960-present), Iraq (1960-present), Kuwait (1960-present), Libya (1962-present), Nigeria (1971-present), Qatar (1961-present), Saudi Arabia (1960-present), United Arab Emirates (1967-present), and Venezuela (1960-present). Countries no longer members of OPEC include Gabon (1975-1994) and Indonesia (1962-2008).

Operable Capacity. The amount of capacity that, at the beginning of the period, is in operation; not in operation and not under active repair, but capable of being placed in operation within 30 days; or not in operation but under active repair that can be completed within 90 days. Operable capacity is the sum of the operating and idle capacity and is measured in barrels per calendar day or barrels per stream day.

Operable Utilization Rate. Represents the utilization of the atmospheric crude oil distillation units. The rate is calculated by dividing the gross input to these units by the *operable* refining capacity of the units.

Operating Capacity. The component of operable capacity that is in operation at the beginning of the period.

Operating Utilization Rate. Represents the utilization of the atmospheric crude oil distillation units. The rate is calculated by dividing the gross input to these units by the *operating* refining capacity of the units.

Other Hydrocarbons. Materials received by a refinery and consumed as a raw material. Includes hydrogen, coal tar derivatives, gilsonite, and natural gas received by the refinery for reforming into hydrogen. Natural gas to be used as fuel is excluded.

Other Oils Equal To or Greater Than 401º F. See ***Petrochemical Feedstocks.***

Other Oxygenates. Other aliphatic alcohols and aliphatic ethers intended for motor gasoline blending (e.g., isopropyl ether (IPE) or n-propanol).

Oxygenated Gasoline. See ***Motor Gasoline (Finished).***

Oxygenates. Substances which, when added to gasoline, increase the amount of oxygen in that gasoline blend. Fuel Ethanol, Methyl Tertiary Butyl Ether (MTBE), Ethyl Tertiary Butyl Ether (ETBE), and methanol are common oxygenates.

> ***Fuel Ethanol.*** Blends of up to 10 percent by volume anhydrous ethanol (200 proof) (commonly referred to as the "gasohol waiver").
>
> ***Methanol.*** Blends of methanol and gasoline-grade tertiary butyl alcohol (GTBA) such that the total oxygen content does not exceed 3.5 percent by weight and the ratio of methanol to GTBA is less than or equal to 1. It is also specified that this blended fuel must meet ASTM volatility specifications (commonly referred to as the "ARCO" waiver).
>
> Blends of up to 5.0 percent by volume methanol with a minimum of 2.5 percent by volume cosolvent alcohols having a carbon number of 4 or less (i.e., ethanol, propanol, butanol, and/or GTBA). The total oxygen must not exceed 3.7 percent by weight, and the blend must meet ASTM volatility specifications as well as phase separation and alcohol purity specifications (commonly referred to as the "DuPont" waiver).
>
> ***MTBE (Methyl tertiary butyl ether).*** Blends up to 15.0 percent by volume MTBE which must meet the ASTM D4814 specifications. Blenders must take precautions that the blends are not used as base gasolines for other oxygenated blends (commonly referred to as the "Sun" waiver).

Pentanes Plus. A mixture of hydrocarbons, mostly pentanes and heavier, extracted from natural gas. Includes isopentane, natural gasoline, and plant condensate.

Persian Gulf. The countries that comprise the Persian Gulf are: Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, and the United Arab Emirates.

Petrochemical Feedstocks. Chemical feedstocks derived from petroleum principally for the manufacture of chemicals, synthetic rubber, and a variety of plastics. The categories reported are "Naphtha Less Than 401º F" and "Other Oils Equal To or Greater Than 401º F."

> ***Naphtha Less Than 401º F.*** A naphtha with a boiling range of less than 401 degrees Fahrenheit that is intended for use as a petrochemical feedstock.
>
> ***Other Oils Equal To or Greater Than 401º F.*** Oils with a boiling range equal to or greater than 401 degrees Fahrenheit that are intended for use as a petrochemical feedstock.

Petroleum Administration for Defense (PAD) Districts. Geographic aggregations of the 50 States and the District of Columbia into five districts by the Petroleum Administration for Defense in 1950. These districts were originally defined during World War II for purposes of administering oil allocation.

Petroleum Coke. A residue high in carbon content and low in hydrogen that is the final product of thermal decomposition in the condensation process in cracking. This product is reported as marketable coke or catalyst coke. The conversion is 5 barrels (of 42 U.S. gallons each) per short ton. Coke from petroleum has a heating value of 6.024 million Btu per barrel.

> ***Catalyst Coke.*** In many catalytic operations (e.g., catalytic cracking) carbon is deposited on the catalyst, thus deactivating the catalyst. The catalyst is reactivated by burning off the carbon, which is used as a fuel in the refining process. This carbon or coke is not recoverable in a concentrated form.
>
> ***Marketable Coke.*** Those grades of coke produced in delayed or fluid cokers which may be recovered as relatively pure carbon. This "green" coke may be sold as is or further purified by calcining.

Petroleum Products. Petroleum products are obtained from the processing of crude oil (including lease condensate), natural gas, and other hydrocarbon compounds. Petroleum products include unfinished oils, liquefied petroleum gases, pentanes plus, aviation

gasoline, motor gasoline, naphtha-type jet fuel, kerosene-type jet fuel, kerosene, distillate fuel oil, residual fuel oil, petrochemical feedstocks, special naphthas, lubricants, waxes, petroleum coke, asphalt, road oil, still gas, and miscellaneous products.

Pipeline (Petroleum). Crude oil and product pipelines used to transport crude oil and petroleum products respectively, (including interstate, intrastate, and intracompany pipelines) within the 50 States and the District of Columbia.

Plant Condensate. One of the natural gas liquids, mostly pentanes and heavier hydrocarbons, recovered and separated as liquids at gas inlet separators or scrubbers in processing plants.

Processing Gain. The volumetric amount by which total output is greater than input for a given period of time. This difference is due to the processing of crude oil into products which, in total, have a lower specific gravity than the crude oil processed.

Processing Loss. The volumetric amount by which total refinery output is less than input for a given period of time. This difference is due to the processing of crude oil into products which, in total, have a higher specific gravity than the crude oil processed.

Product Supplied, Crude Oil. Crude oil burned on leases and by pipelines as fuel.

Production Capacity. The maximum amount of product that can be produced from processing facilities.

Products Supplied. Approximately represents consumption of petroleum products because it measures the disappearance of these products from primary sources, i.e., refineries, natural gas processing plants, blending plants, pipelines, and bulk terminals. In general, product supplied of each product in any given period is computed as follows: field production, plus refinery production, plus imports, plus unaccounted for crude oil, (plus net receipts when calculated on a PAD District basis), minus stock change, minus crude oil losses, minus refinery inputs, minus exports.

Propane (C_3H_8). A normally gaseous straight-chain hydrocarbon. It is a colorless paraffinic gas that boils at a temperature of - 43.67 degrees Fahrenheit. It is extracted from natural gas or refinery gas streams. It includes all products designated in ASTM Specification D1835 and Gas Processors Association Specifications for commercial propane and HD-5 propane.

Propylene (C_3H_6). An olefinic hydrocarbon recovered from refinery processes or petrochemical processes.

> ***Propylene (C_3H_6) (nonfuel use).*** Propylene that is intended for use in nonfuel applications such as petrochemical manufacturing. Nonfuel use propylene includes chemical-grade propylene, polymer-grade propylene, and trace amounts of propane. Nonfuel use propylene also includes the propylene component of propane/propylene mixes where the propylene will be separated from the mix in a propane/propylene splitting process. Excluded is the propylene component of propane/propylene mixes where the propylene component of the mix is intended for sale into the fuel market.

Refinery. An installation that manufactures finished petroleum products from crude oil, unfinished oils, natural gas liquids, other hydrocarbons, and oxygenates.

Refinery-Grade Butane. See ***Butane.***

Refinery Input, Crude Oil. Total crude oil (domestic plus foreign) input to crude oil distillation units and other refinery processing units (cokers, etc.).

Refinery Input, Total. The raw materials and intermediate materials processed at refineries to produce finished petroleum products. They include crude oil, products of natural gas processing plants, unfinished oils, other hydrocarbons and oxygenates, motor gasoline and aviation gasoline blending components and finished petroleum products.

Refinery Production. Petroleum products produced at a refinery or blending plant. Published production of these products equals refinery production minus refinery input. Negative production will occur when the amount of a product produced during the month is less than the amount of that same product that is reprocessed (input) or reclassified to become another product during the same month. Refinery production of unfinished oils, and motor and aviation gasoline blending components appear on a net basis under refinery input.

Refinery Yield. Refinery yield (expressed as a percentage) represents the percent of finished product produced from input of crude oil and net input of unfinished oils. It is calculated by dividing the sum of crude oil and net unfinished input into the individual net production of finished products. Before calculating the yield for finished motor gasoline, the input of natural gas liquids, other hydrocarbons and oxygenates, and net input of motor gasoline blending components must be subtracted from the net production of finished motor gasoline. Before calculating the yield for finished aviation gasoline, input of aviation gasoline blending components must be subtracted from the net production of finished aviation gasoline.

Reformulated Blendstock for Oxygenate Blending (RBOB). See ***Motor Gasoline Blending Components.***

Reformulated Gasoline. See ***Motor Gasoline (Finished).***

Renewable Diesel Fuel (Other). Diesel fuel and diesel fuel blending components produced from renewable sources that are coprocessed with petroleum feedstocks and meet requirements of advanced biofuels.

Renewable Fuels (Other). Fuels and fuel blending components, except biomass-based diesel fuel, renewable diesel fuel, and fuel ethanol, produced from renewable biomass.

Residual Fuel Oil. A general classification for the heavier oils, known as No. 5 and No. 6 fuel oils, that remain after the distillate fuel oils and lighter hydrocarbons are distilled away in refinery operations. It conforms to ASTM Specifications D 396 and D 975 and Federal Specification VV-F-815C. No. 5, a residual fuel oil of medium viscosity, is also known as Navy Special and is defined in Military Specification MIL-F-859E, including Amendment 2 (NATO Symbol F-770). It is used in steam-powered vessels in government service

and inshore power plants. No. 6 fuel oil includes Bunker C fuel oil and is used for the production of electric power, space heating, vessel bunkering, and various industrial purposes.

Residuum. Residue from crude oil after distilling off all but the heaviest components, with a boiling range greater than 1000 degrees Fahrenheit.

Road Oil. Any heavy petroleum oil, including residual asphaltic oil used as a dust palliative and surface treatment on roads and highways. It is generally produced in six grades from 0, the most liquid, to 5, the most viscous.

Shell Storage Capacity. The design capacity of a petroleum storage tank which is always greater than or equal to working storage capacity.

Special Naphthas. All finished products within the naphtha boiling range that are used as paint thinners, cleaners, or solvents. These products are refined to a specified flash point. Special naphthas include all commercial hexane and cleaning solvents conforming to ASTM Specification D1836 and D484, respectively. Naphthas to be blended or marketed as motor gasoline or aviation gasoline, or that are to be used as petrochemical and synthetic natural gas (SNG) feedstocks are excluded.

Steam (Purchased). Steam, purchased for use by a refinery, that was not generated from within the refinery complex.

Still Gas (Refinery Gas). Any form or mixture of gases produced in refineries by distillation, cracking, reforming, and other processes. The principal constituents are methane, ethane, ethylene, normal butane, butylene, propane, propylene, etc. Still gas is used as a refinery fuel and a petrochemical feedstock. The conversion factor is 6 million BTU's per fuel oil equivalent barrel.

Stock Change. The difference between stocks at the beginning of the reporting period and stocks at the end of the reporting period. Note: A negative number indicates a decrease (i.e., a drawdown) in stocks and a positive number indicates an increase (i.e., a buildup) in stocks during the reporting period.

Strategic Petroleum Reserve (SPR). Petroleum stocks maintained by the Federal Government for use during periods of major supply interruption.

Sulfur. A yellowish nonmetallic element, sometimes known as "brimstone." It is present at various levels of concentration in many fossil fuels whose combustion releases sulfur compounds that are considered harmful to the environment. Some of the most commonly used fossil fuels are categorized according to their sulfur content, with lower sulfur fuels usually selling at a higher price. Note: No. 2 Distillate fuel is currently reported as having either a 0.05 percent or lower sulfur level for on-highway vehicle use or a greater than 0.05 percent sulfur level for off- highway use, home heating oil, and commercial and industrial uses. Residual fuel, regardless of use, is classified as having either no more than 1 percent sulfur or greater than 1 percent sulfur. Coal is also classified as being low-sulfur at concentrations of 1 percent or less or high-sulfur at concentrations greater than 1 percent.

Supply. The components of petroleum supply are field production, refinery production, imports, and net receipts when calculated on a PAD District basis.

TAME (Tertiary amyl methyl ether) $(CH_3)_2(C_2H_5)COCH_3$. An oxygenate blend stock formed by the catalytic etherification of isoamylene with methanol.

Tank Farm. An installation used by gathering and trunk pipeline companies, crude oil producers, and terminal operators (except refineries) to store crude oil.

Tanker and Barge. Vessels that transport crude oil or petroleum products. Data are reported for movements between PAD Districts; from a PAD District to the Panama Canal; or from the Panama Canal to a PAD District.

TBA (Tertiary butyl alcohol) $(CH_3)_3COH$. An alcohol primarily used as a chemical feedstock, a solvent or feedstock for isobutylene production for MTBE; produced as a co-product of propylene oxide production or by direct hydration of isobutylene.

Thermal Cracking. A refining process in which heat and pressure are used to break down, rearrange, or combine hydrocarbon molecules. Thermal cracking includes gas oil, visbreaking, fluid coking, delayed coking, and other thermal cracking processes (e.g., flexicoking). See individual categories for definition.

Toluene ($C_6H_5CH_3$). Colorless liquid of the aromatic group of petroleum hydrocarbons, made by the catalytic reforming of petroleum naphthas containing methyl cyclohexane. A high-octane gasoline-blending agent, solvent, and chemical intermediate, base for TNT.

Unaccounted for Crude Oil. Represents the arithmetic difference between the calculated supply and the calculated disposition of crude oil. The calculated supply is the sum of crude oil production plus imports minus changes in crude oil stocks. The calculated disposition of crude oil is the sum of crude oil input to refineries, crude oil exports, crude oil burned as fuel, and crude oil losses.

Unfinished Oils. All oils requiring further processing, except those requiring only mechanical blending. Unfinished oils are produced by partial refining of crude oil and include naphthas and lighter oils, kerosene and light gas oils, heavy gas oils, and residuum.

Unfractionated Streams. Mixtures of unsegregated natural gas liquid components excluding, those in plant condensate. This product is extracted from natural gas.

United States. The United States is defined as the 50 States and the District of Columbia.

Vacuum Distillation. Distillation under reduced pressure (less the atmospheric) which lowers the boiling temperature of the liquid being distilled. This technique with its relatively low temperatures prevents cracking or decomposition of the charge stock.

Visbreaking. A thermal cracking process in which heavy atmospheric or vacuum-still bottoms are cracked at moderate temperatures to increase production of distillate products and reduce viscosity of the

distillation residues.

Wax. A solid or semi-solid material at 77 degrees Fahrenheit consisting of a mixture of hydrocarbons obtained or derived from petroleum fractions, or through a Fischer-Tropsch type process, in which the straight-chained paraffin series predominates. This includes all marketable wax, whether crude or refined, with a congealing point (ASTM D 938) between 80 (or 85) and 240 degrees Fahrenheit and a maximum oil content (ASTM D 3235) of 50 weight percent.

Working Storage Capacity. The difference in volume between the maximum safe fill capacity and the quantity below which pump suction is ineffective (bottoms).

Xylene ($C_6H_4(CH_3)_2$). Colorless liquid of the aromatic group of hydrocarbons made the catalytic reforming of certain naphthenic petroleum fractions. Used as high-octane motor and aviation gasoline blending agents, solvents, chemical intermediates. Isomers are metaxylene, orthoxylene, paraxylene.