


# February 2021

# Monthly Energy Review



*Independent Statistics & Analysis*  
U.S. Energy Information  
Administration

[www.eia.gov/mer](http://www.eia.gov/mer)

# Monthly Energy Review

---

The *Monthly Energy Review* (MER) is the U.S. Energy Information Administration's (EIA) primary report of recent and historical energy statistics. Included are statistics on total energy production, consumption, stocks, trade, and energy prices; overviews of petroleum, natural gas, coal, electricity, nuclear energy, and renewable energy; carbon dioxide emissions; and data unit conversions.

Release of the MER is in keeping with responsibilities given to EIA in Public Law 95–91 (Department of Energy Organization Act), which states, in part, in Section 205(a)(2):

*“The Administrator shall be responsible for carrying out a central, comprehensive, and unified energy data and information program which will collect, evaluate, assemble, analyze, and disseminate data and information...”*

The MER is intended for use by members of Congress, federal and state agencies, energy analysts, and the general public. EIA welcomes suggestions from readers regarding MER content and other EIA publications.

**Related monthly publications:** Other monthly EIA reports are Petroleum Supply Monthly, Petroleum Marketing Monthly, Natural Gas Monthly, and Electric Power Monthly. For more information, contact EIA's Office of Communications via email at [infoctr@eia.gov](mailto:infoctr@eia.gov).

## Important notes about the data

**Data displayed:** For tables beginning in 1949, annual data are usually displayed only in 5-year increments between 1950 and 2000 in the tables in Portable Document Format (PDF) files; however, all annual data are shown in the Excel files, comma-separated values (CSV) files, application programming interface (API) files, and in the data browser. Also, only two to three years of monthly data are displayed in the PDF files; however, for many series, monthly data beginning with January 1973 are available in the Excel files, CSV files, API files, and in the data browser.

**Comprehensive changes:** Each month, most MER tables and figures present data for a new month. These data are usually preliminary (and sometimes estimated or forecasted) and likely to be revised the following month. The first dissemination of most annual data is also preliminary. It is often based on monthly estimates and is likely to be revised later that year after final data are published from sources, according to source data revision policies and publication schedules. In addition, EIA may revise historical data when a major revision in a source publication is needed, when new data sources become available, or when estimation methodologies are improved. A record of current and historical changes to MER data is available at <https://www.eia.gov/totalenergy/data/monthly/whatsnew.php>.

**Annual data from 1949:** In 2013, EIA expanded the MER to incorporate annual data as far back as 1949 in those data tables that were previously published in both the Annual Energy Review and MER.

## Electronic access

The MER is available on EIA's website in various formats at <http://www.eia.gov/totalenergy/data/monthly>.

- Full report and report tables: PDF files
- Table data (unrounded): Excel files, CSV files, API files, and data browser
- Graphs: PDF files and data browser

Note: PDF files display selected annual and monthly data; Excel files, CSV files, API files, and data browser display all available annual and monthly data, often with greater precision than the PDF files.

**Timing of release:** The MER is posted at <http://www.eia.gov/totalenergy/data/monthly> no later than the last work day of the month.

**Released:** February 23, 2021

# Monthly Energy Review

## February 2021

**U.S. Energy Information Administration**  
Office of Energy Statistics  
U.S. Department of Energy  
Washington, DC 20585

This report was prepared by the U.S. Energy Information Administration (EIA), the statistical and analytical agency within the U.S. Department of Energy. By law, EIA's data, analyses, and forecasts are independent of approval by any other officer or employee of the United States Government. The views in this report therefore should not be construed as representing those of the Department of Energy or other federal agencies.

# Contacts

The *Monthly Energy Review* is prepared by the U.S. Energy Information Administration, Office of Energy Statistics, Office of Energy Demand and Integrated Statistics, Integrated Statistics Team, under the direction of Ryan Repice, 202-586-5828 (ryan.repice@eia.gov). Questions and comments specifically related to the *Monthly Energy Review* may be addressed to Alexander Sun, 202-287-5948 (alexander.sun@eia.gov).

For assistance in acquiring data, please contact EIA's Office of Communications at 202-586-8800 (infoctr@eia.gov). Questions about the collection, processing, or interpretation of the information may be directed to the following subject specialists:

<b>Section</b>	<b>1. Energy Overview</b> . . . . .	Dianne R. Dunn	202-586-2792 dianne.dunn@eia.gov
<b>Section</b>	<b>2. Energy Consumption by Sector</b> . . . . .	Dianne R. Dunn	202-586-2792 dianne.dunn@eia.gov
<b>Section</b>	<b>3. Petroleum</b> . . . . .	Javed Zaidi	202-586-1155 javed.zaidi@doe.gov
<b>Section</b>	<b>4. Natural Gas</b> . . . . .	Michael Kopalek	202-586-4001 michael.kopalek@eia.gov
<b>Section</b>	<b>5. Crude Oil and Natural Gas Resource Development</b> . . .	Gary Long	202-586-3467 gary.long@eia.gov
<b>Section</b>	<b>6. Coal</b> . . . . .	Rosalyn Berry	202-586-6393 rosalyn.berry@eia.gov
<b>Section</b>	<b>7. Electricity</b> . . . . .	Glenn McGrath	202-586-4325 glenn.mcgrath@eia.gov
<b>Section</b>	<b>8. Nuclear Energy</b> . . . . .	Tim Shear	202-586-0403 tim.shear@eia.gov
<b>Section</b>	<b>9. Energy Prices</b>		
	Petroleum . . . . .	Maureen Klein	202-586-8013 maureen.klein@eia.gov
	Natural Gas . . . . .	Michael Kopalek	202-586-4001 michael.kopalek@eia.gov
	Average Retail Prices of Electricity . . . . .	Peter Wong	202-586-7574 peter.wong@eia.gov
	Cost of Fuel at Electric Generating Plants . . . . .	Eric Harrison	202-586-1158 eric.harrison@eia.gov
<b>Section</b>	<b>10. Renewable Energy</b> . . . . .	Lolita Jamison	202-586-9567 lolita.jamison@eia.gov
<b>Section</b>	<b>11. Environment</b> . . . . .	Perry Lindstrom	202-586-0934 perry.lindstrom@eia.gov

# Contents

	Page
Section 1. Energy Overview .....	1
Section 2. Energy Consumption by Sector .....	35
Section 3. Petroleum.....	57
Section 4. Natural Gas .....	99
Section 5. Crude Oil and Natural Gas Resource Development .....	109
Section 6. Coal .....	115
Section 7. Electricity .....	125
Section 8. Nuclear Energy .....	149
Section 9. Energy Prices.....	155
Section 10. Renewable Energy .....	175
Section 11. Environment .....	195
Appendix A. British Thermal Unit Conversion Factors.....	209
Appendix B. Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors.....	225
Appendix C. Population, U.S. Gross Domestic Product, and U.S. Gross Output.....	229
Appendix D. Estimated Primary Energy Consumption in the United States, Selected Years, 1635–1945 .....	231
Appendix E. Alternative Approaches for Deriving Energy Contents of Noncombustible Renewables.....	235
Glossary.....	241

# Tables

Page

<b>Section 1.</b>	<b>Energy Overview</b>	
1.1	Primary Energy Overview.....	3
1.2	Primary Energy Production by Source.....	5
1.3	Primary Energy Consumption by Source.....	7
1.4a	Primary Energy Imports by Source Overview.....	9
1.4b	Primary Energy Exports by Source.....	11
1.4c	Primary Energy Net Imports by Source.....	13
1.5	Merchandise Trade Value.....	15
1.6	Cost of Fuels to End Users in Real (1982–1984) Dollars.....	17
1.7	Primary Energy Consumption, Energy Expenditures, and Carbon Dioxide Emissions Indicators.....	19
1.8	Motor Vehicle Mileage, Fuel Consumption, and Fuel Economy.....	21
1.9	Heating Degree Days by Census Division.....	22
1.10	Cooling Degree Days by Census Division.....	23
1.11a	Non-Combustion Use of Fossil Fuels in Physical Units.....	24
1.11b	Heat Content of Non-Combustion Use of Fossil Fuels.....	25
<b>Section 2.</b>	<b>Energy Consumption by Sector</b>	
2.1	Energy Consumption by Sector.....	37
2.2	Residential Sector Energy Consumption.....	39
2.3	Commercial Sector Energy Consumption.....	41
2.4	Industrial Sector Energy Consumption.....	43
2.5	Transportation Sector Energy Consumption.....	45
2.6	Electric Power Sector Energy Consumption.....	47
2.7	U.S. Government Energy Consumption by Agency, Fiscal Years.....	48
2.8	U.S. Government Energy Consumption by Source, Fiscal Years.....	49
<b>Section 3.</b>	<b>Petroleum</b>	
3.1	Petroleum Overview.....	59
3.2	Refinery and Blender Net Inputs and Net Production.....	61
3.3	Petroleum Trade	
3.3a	Overview.....	63
3.3b	Imports by Type.....	65
3.3c	Imports From OPEC Countries.....	66
3.3d	Imports From Non-OPEC Countries.....	67
3.3e	Exports by Type.....	68
3.3f	Exports by Country of Destination.....	69
3.4	Petroleum Stocks.....	71
3.5	Petroleum Products Supplied by Type.....	73
3.6	Heat Content of Petroleum Products Supplied by Type.....	75
3.7	Petroleum Consumption	
3.7a	Residential and Commercial Sectors.....	77
3.7b	Industrial Sector.....	78
3.7c	Transportation and Electric Power Sectors.....	79
3.8	Heat Content of Petroleum Consumption	
3.8a	Residential and Commercial Sectors.....	82
3.8b	Industrial Sector.....	83
3.8c	Transportation and Electric Power Sectors.....	84
<b>Section 4.</b>	<b>Natural Gas</b>	
4.1	Natural Gas Overview.....	101
4.2	Natural Gas Trade by Country.....	102
4.3	Natural Gas Consumption by Sector.....	103
4.4	Natural Gas in Underground Storage.....	104

# Tables

Page

<b>Section 5.</b>	<b>Crude Oil and Natural Gas Resource Development</b>	
5.1	Crude Oil and Natural Gas Drilling Activity Measurements .....	111
5.2	Crude Oil and Natural Gas Exploratory and Development Wells.....	112
<b>Section 6.</b>	<b>Coal</b>	
6.1	Coal Overview .....	117
6.2	Coal Consumption by Sector.....	118
6.3	Coal Stocks by Sector .....	119
<b>Section 7.</b>	<b>Electricity</b>	
7.1	Electricity Overview .....	127
7.2	Electricity Net Generation	
7.2a	Total (All Sectors) .....	129
7.2b	Electric Power Sector.....	130
7.2c	Commercial and Industrial Sectors.....	131
7.3	Consumption of Combustible Fuels for Electricity Generation	
7.3a	Total (All Sectors) .....	133
7.3b	Electric Power Sector.....	134
7.3c	Commercial and Industrial Sectors (Selected Fuels) .....	135
7.4	Consumption of Combustible Fuels for Electricity Generation and Useful Thermal Output	
7.4a	Total (All Sectors) .....	137
7.4b	Electric Power Sector.....	138
7.4c	Commercial and Industrial Sectors (Selected Fuels) .....	139
7.5	Stocks of Coal and Petroleum: Electric Power Sector .....	141
7.6	Electricity End Use .....	143
<b>Section 8.</b>	<b>Nuclear Energy</b>	
8.1	Nuclear Energy Overview.....	151
8.2	Uranium Overview.....	153
<b>Section 9.</b>	<b>Energy Prices</b>	
9.1	Crude Oil Price Summary .....	157
9.2	F.O.B. Costs of Crude Oil Imports From Selected Countries .....	158
9.3	Landed Costs of Crude Oil Imports From Selected Countries.....	159
9.4	Retail Motor Gasoline and On-Highway Diesel Fuel Prices.....	160
9.5	Refiner Prices of Residual Fuel Oil.....	161
9.6	Refiner Prices of Petroleum Products for Resale .....	162
9.7	Refiner Prices of Petroleum Products to End Users.....	163
9.8	Average Retail Prices of Electricity .....	165
9.9	Cost of Fossil-Fuel Receipts at Electric Generating Plants.....	167
9.10	Natural Gas Prices.....	169
<b>Section 10.</b>	<b>Renewable Energy</b>	
10.1	Renewable Energy Production and Consumption by Source.....	177
10.2	Renewable Energy Consumption	
10.2a	Residential and Commercial Sectors .....	178
10.2b	Industrial and Transportation Sectors .....	179
10.2c	Electric Power Sector .....	180
10.3	Fuel Ethanol Overview .....	181
10.4	Biodiesel and Other Renewable Fuels Overview.....	182
10.5	Solar Energy Consumption .....	183
10.6	Solar Electricity Net Generation .....	184

# Tables

Page

## Section 11. Environment

11.1	Carbon Dioxide Emissions From Energy Consumption by Source .....	197
11.2	Carbon Dioxide Emissions From Energy Consumption: Residential Sector .....	199
11.3	Carbon Dioxide Emissions From Energy Consumption: Commercial Sector .....	200
11.4	Carbon Dioxide Emissions From Energy Consumption: Industrial Sector.....	201
11.5	Carbon Dioxide Emissions From Energy Consumption: Transportation Sector.....	202
11.6	Carbon Dioxide Emissions From Energy Consumption: Electric Power Sector .....	203
11.7	Carbon Dioxide Emissions From Biomass Energy Consumption.....	204

## Appendix A. British Thermal Unit Conversion Factors

A1	Approximate Heat Content of Petroleum and Other Liquids .....	210
A2	Approximate Heat Content of Petroleum Production, Imports, and Exports .....	211
A3	Approximate Heat Content of Petroleum Consumption and Fuel Ethanol .....	212
A4	Approximate Heat Content of Natural Gas .....	213
A5	Approximate Heat Content of Coal and Coal Coke .....	214
A6	Approximate Heat Rates for Electricity, and Heat Content of Electricity .....	215

## Appendix B. Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors

B1	Metric Conversion Factors .....	227
B2	Metric Prefixes .....	228
B3	Other Physical Conversion Factors .....	228

## Appendix C. Population, U.S. Gross Domestic Product, and U.S. Gross Output

C1	Population, U.S. Gross Domestic Product, and U.S. Gross Output .....	230
----	--	-----

## Appendix D. Estimated Primary Energy Consumption in the United States, Selected Years, 1635–1945

D1	Estimated Primary Energy Consumption in the United States, Selected Years, 1635–1945 .....	232
----	--	-----

## Appendix E. Alternative Approaches for Deriving Energy Contents of Noncombustible Renewables

E1	Noncombustible Renewable Primary Energy Consumption:	
E.1a	Conventional Hydroelectric Power, Geothermal, and Wind.....	238
E.1b	Solar and Total.....	239



# Figures

## Page

<b>Section 1. Energy Overview</b>	
1.1 Primary Energy Overview .....	2
1.2 Primary Energy Production .....	4
1.3 Primary Energy Consumption .....	6
1.4a Primary Energy Imports .....	8
1.4b Primary Energy Exports .....	10
1.4c Primary Energy Net Imports .....	12
1.5 Merchandise Trade Value .....	14
1.6 Cost of Fuels to End Users in Real (1982–1984) Dollars .....	16
1.7 Primary Energy Consumption and Energy Expenditures Indicators .....	18
1.8 Motor Vehicle Mileage, Fuel Consumption, and Fuel Economy, 1949–2019 .....	20
<b>Section 2. Energy Consumption by Sector</b>	
2.1 Energy Consumption by Sector .....	36
2.2 Residential Sector Energy Consumption .....	38
2.3 Commercial Sector Energy Consumption .....	40
2.4 Industrial Sector Energy Consumption .....	42
2.5 Transportation Sector Energy Consumption .....	44
2.6 Electric Power Sector Energy Consumption .....	46
<b>Section 3. Petroleum</b>	
3.1 Petroleum Overview .....	58
3.2 Refinery and Blender Net Inputs and Net Production .....	60
3.3 Petroleum Trade	
3.3a Overview .....	62
3.3b Imports and Exports by Type .....	64
3.4 Petroleum Stocks .....	70
3.5 Petroleum Products Supplied by Type .....	72
3.6 Heat Content of Petroleum Products Supplied by Type .....	74
3.7 Petroleum Consumption by Sector .....	76
3.8a Heat Content of Petroleum Consumption by End-User Sector, 1949–2018 .....	80
3.8b Heat Content of Petroleum Consumption by End-User Sector, Monthly .....	81
<b>Section 4. Natural Gas</b>	
4.1 Natural Gas .....	100
<b>Section 5. Crude Oil and Natural Gas Resource Development</b>	
5.1 Crude Oil and Natural Gas Resource Development Indicators .....	110
<b>Section 6. Coal</b>	
6.1 Coal .....	116
<b>Section 7. Electricity</b>	
7.1 Electricity Overview .....	126
7.2 Electricity Net Generation .....	128
7.3 Consumption of Selected Combustible Fuels for Electricity Generation .....	132
7.4 Consumption of Selected Combustible Fuels for Electricity Generation and Useful Thermal Output .....	136
7.5 Stocks of Coal and Petroleum: Electric Power Sector .....	140
7.6 Electricity End Use .....	142

# Figures

## Page

### Section 8. Nuclear Energy

8.1	Nuclear Energy Overview .....	150
8.2	Uranium Overview .....	152

### Section 9. Energy Prices

9.1	Petroleum Prices .....	156
9.2	Average Retail Prices of Electricity .....	164
9.3	Cost of Fossil-Fuel Receipts at Electric Generating Plants .....	166
9.4	Natural Gas Prices .....	168

### Section 10. Renewable Energy

10.1	Renewable Energy Consumption .....	176
------	------------------------------------	-----

### Section 11. Environment

11.1	Carbon Dioxide Emissions From Energy Consumption by Source .....	196
11.2	Carbon Dioxide Emissions From Energy Consumption by Sector .....	198


# 1. Energy Overview

---


**Figure 1.1 Primary Energy Overview**

(Quadrillion Btu)


Overview, 1949–2019




Overview, Monthly



Overview, November 2020



Net Imports, January–November



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.1.

**Table 1.1 Primary Energy Overview**  
(Quadrillion Btu)

	Production				Trade			Stock Change and Other <sup>d</sup>	Consumption			
	Fossil Fuels <sup>a</sup>	Nuclear Electric Power	Renewable Energy <sup>b</sup>	Total	Imports	Exports	Net Imports <sup>c</sup>		Fossil Fuels <sup>e</sup>	Nuclear Electric Power	Renewable Energy <sup>b</sup>	Total <sup>f</sup>
1950 Total .....	32.553	0.000	2.978	35.531	1.913	1.465	0.448	-1.380	31.615	0.000	2.978	34.599
1955 Total .....	37.347	.000	2.784	40.131	2.790	2.286	.504	-.457	37.380	.000	2.784	40.178
1960 Total .....	39.855	.006	2.928	42.789	4.188	1.477	2.710	-.458	42.091	.006	2.928	45.041
1965 Total .....	47.205	.043	3.396	50.644	5.892	1.829	4.063	-.754	50.515	.043	3.396	53.953
1970 Total .....	59.152	.239	4.070	63.462	8.342	2.632	5.709	-1.354	63.501	.239	4.070	67.817
1975 Total .....	54.697	1.900	4.687	61.284	14.032	2.323	11.709	-1.062	65.323	1.900	4.687	71.931
1980 Total .....	58.979	2.739	5.428	67.147	15.796	3.695	12.101	-1.227	69.782	2.739	5.428	78.021
1985 Total .....	57.502	4.076	6.084	67.661	11.781	4.196	7.584	1.088	66.035	4.076	6.084	76.334
1990 Total .....	58.523	6.104	6.040	70.668	18.817	4.752	14.065	-.299	72.281	6.104	6.040	84.433
1995 Total .....	57.496	7.075	6.557	71.129	22.180	4.496	17.684	2.118	77.162	7.075	6.559	90.931
2000 Total .....	57.307	7.862	6.102	71.271	28.865	3.962	24.904	2.528	84.620	7.862	6.104	98.702
2001 Total .....	58.485	8.029	5.162	71.675	30.052	3.731	26.321	-1.933	82.800	8.029	5.160	96.064
2002 Total .....	56.777	8.145	5.731	70.653	29.331	3.608	25.722	1.160	83.592	8.145	5.726	97.535
2003 Total .....	55.983	7.960	5.942	69.885	31.007	4.013	26.994	.956	83.909	7.960	5.944	97.835
2004 Total .....	55.884	8.223	6.063	70.169	33.492	4.351	29.141	.692	85.666	8.223	6.075	100.002
2005 Total .....	54.995	8.161	6.221	69.377	34.659	4.462	30.197	.527	85.623	8.161	6.234	100.102
2006 Total .....	55.877	8.215	6.586	70.678	34.649	4.727	29.921	-1.207	84.477	8.215	6.637	99.392
2007 Total .....	56.369	8.459	6.510	71.338	34.679	5.338	29.341	.215	85.805	8.459	6.523	100.893
2008 Total .....	57.527	8.426	7.192	73.145	32.970	6.949	26.021	-.412	83.041	8.426	7.175	98.754
2009 Total .....	56.612	8.355	7.625	72.592	29.690	6.920	22.770	-1.420	77.862	8.355	7.608	93.942
2010 Total .....	58.159	8.434	8.314	74.907	29.866	8.176	21.690	.916	80.723	8.434	8.267	97.513
2011 Total .....	60.515	8.269	9.300	78.083	28.748	10.373	18.375	.404	79.263	8.269	9.204	96.863
2012 Total .....	62.291	8.062	8.886	79.239	27.068	11.267	15.801	-.666	77.304	8.062	8.847	94.374
2013 Total .....	64.177	8.244	9.418	81.839	24.623	11.788	12.835	2.443	79.224	8.244	9.451	97.117
2014 Total .....	69.616	8.338	9.767	87.720	23.241	12.270	10.971	-.415	80.017	8.338	9.740	98.276
2015 Total .....	70.201	8.337	9.729	88.267	23.794	12.902	10.892	-1.783	79.090	8.337	9.721	97.375
2016 Total .....	65.445	8.427	R 10.425	R 84.297	25.378	14.119	11.259	1.781	78.319	8.427	R 10.365	R 97.338
2017 Total .....	68.478	8.419	R 11.200	R 88.096	25.458	17.946	7.512	1.990	77.907	8.419	R 11.081	R 97.599
<b>2018 January .....</b>	<b>5.988</b>	<b>.780</b>	R .973	R 7.742	<b>2.228</b>	<b>1.572</b>	<b>.655</b>	<b>1.263</b>	<b>7.911</b>	<b>.780</b>	R .954	R 9.660
February .....	5.605	.677	.918	R 7.201	1.861	1.525	.336	.521	6.476	.677	R .893	R 8.058
March .....	6.267	.701	R 1.012	7.979	2.114	1.742	.372	.351	6.990	.701	.996	R 8.702
April .....	5.960	.618	R 1.019	7.597	2.125	1.792	.333	-.049	6.251	.618	R 1.002	7.881
May .....	6.212	.704	R 1.050	7.966	2.142	1.775	.367	-.356	6.219	.704	R 1.041	7.977
June .....	6.098	.729	1.030	7.857	2.176	1.762	.414	-.134	6.380	.729	1.015	R 8.138
July .....	6.408	.758	R .946	R 8.111	2.161	1.863	.298	.195	6.903	.758	R .929	8.604
August .....	6.692	.756	.949	R 8.398	2.192	1.737	.454	-.169	6.976	.756	R .935	8.683
September .....	6.443	.677	R .866	R 7.986	1.999	1.723	.275	-.406	6.322	.677	R .846	7.855
October .....	6.743	.621	.902	8.266	1.982	1.894	.088	-.275	6.564	.621	R .884	8.079
November .....	6.603	.669	R .906	8.177	1.896	1.884	.012	.319	6.943	.669	R .888	8.509
December .....	6.787	.749	R .944	8.480	1.958	1.955	.003	.539	7.336	.749	R .926	8.902
<b>Total .....</b>	<b>75.807</b>	<b>8.438</b>	R <b>11.515</b>	R <b>95.761</b>	<b>24.833</b>	<b>21.224</b>	<b>3.610</b>	<b>1.798</b>	<b>81.271</b>	<b>8.438</b>	R <b>11.308</b>	R <b>101.169</b>
<b>2019 January .....</b>	<b>6.814</b>	<b>.770</b>	R .945	R 8.529	<b>2.122</b>	<b>1.910</b>	<b>.212</b>	<b>.791</b>	<b>7.830</b>	<b>.770</b>	R .921	R 9.532
February .....	6.134	.676	R .875	R 7.684	1.700	1.725	-.024	.717	6.828	.676	R .862	R 8.377
March .....	6.679	.680	R .992	R 8.350	1.925	1.912	.013	.329	7.025	.680	R .980	8.692
April .....	6.660	.633	R 1.032	R 8.324	1.925	1.893	.032	-.694	6.007	.633	R 1.015	7.662
May .....	6.888	.701	R 1.065	R 8.654	2.046	1.954	.092	-.809	6.171	.701	R 1.054	7.937
June .....	6.597	.718	R 1.002	R 8.317	1.889	1.940	-.051	-.360	6.186	.718	R .989	7.906
July .....	6.783	.754	R .989	R 8.526	2.021	1.889	.132	-.109	6.807	.754	R .975	8.548
August .....	7.064	.751	R .946	R 8.761	1.975	1.969	.006	-.215	6.857	.751	R .930	8.552
September .....	6.804	.690	R .904	R 8.398	1.789	1.977	-.188	-.357	6.260	.690	R .891	7.853
October .....	7.052	.648	R .932	R 8.632	1.816	2.088	-.272	-.432	6.351	.648	R .922	7.928
November .....	6.849	.670	R .903	R 8.421	1.688	2.028	-.340	.296	6.807	.670	R .888	8.377
December .....	7.015	.763	R .941	R 8.719	1.969	2.190	-.221	.427	7.227	.763	R .921	8.925
<b>Total .....</b>	<b>81.339</b>	<b>8.452</b>	R <b>11.524</b>	R <b>101.315</b>	<b>22.865</b>	<b>23.474</b>	<b>-.609</b>	<b>-.417</b>	<b>80.357</b>	<b>8.452</b>	R <b>11.348</b>	R <b>100.289</b>
<b>2020 January .....</b>	<b>7.011</b>	<b>.774</b>	R .992	R 8.778	<b>1.866</b>	<b>2.180</b>	<b>-.314</b>	<b>.495</b>	<b>7.206</b>	<b>.774</b>	R .968	R 8.959
February .....	6.434	.689	R .992	R 8.115	1.719	2.169	-.450	.643	6.639	.689	R .971	8.308
March .....	6.810	.668	R .991	R 8.469	1.779	2.261	-.482	-.148	6.198	.668	R .960	7.839
April .....	6.269	.618	R .915	R 7.802	1.507	1.911	-.404	-.885	4.978	.618	R .906	6.513
May .....	5.872	.672	R 1.033	R 7.577	1.649	1.653	-.004	-.719	5.136	.672	R 1.034	6.854
June .....	5.892	.702	R 1.047	R 7.641	1.704	1.684	.020	-.383	5.523	.702	R 1.040	7.278
July .....	6.300	.725	R 1.003	R 8.028	1.689	1.875	-.186	.259	6.364	.725	R .994	8.101
August .....	R 6.329	.720	R .962	R 8.012	1.614	1.879	-.265	R .272	6.329	.720	R .949	8.019
September .....	R 6.131	.686	R .892	R 7.709	1.539	1.874	-.335	R -.054	5.741	.686	R .880	7.320
October .....	R 6.241	.620	R .947	R 7.808	R 1.575	R 1.987	R -.413	R .109	5.947	.620	R .926	7.504
November .....	6.270	.645	1.003	7.918	1.598	1.953	-.354	.040	5.964	.645	.982	7.603
<b>11-Month Total ...</b>	<b>69.559</b>	<b>7.519</b>	<b>10.777</b>	<b>87.855</b>	<b>18.241</b>	<b>21.426</b>	<b>-3.185</b>	<b>-.371</b>	<b>66.024</b>	<b>7.519</b>	<b>10.611</b>	<b>84.299</b>
<b>2019 11-Month Total ...</b>	<b>74.323</b>	<b>7.689</b>	<b>10.583</b>	<b>92.596</b>	<b>20.896</b>	<b>21.285</b>	<b>-.388</b>	<b>-.843</b>	<b>73.129</b>	<b>7.689</b>	<b>10.427</b>	<b>91.364</b>
<b>2018 11-Month Total ...</b>	<b>69.020</b>	<b>7.689</b>	<b>10.572</b>	<b>87.281</b>	<b>22.876</b>	<b>19.269</b>	<b>3.607</b>	<b>1.260</b>	<b>73.935</b>	<b>7.689</b>	<b>10.382</b>	<b>92.147</b>

<sup>a</sup> Coal, natural gas (dry), crude oil, and natural gas plant liquids.  
<sup>b</sup> See Tables 10.1–10.2c for notes on series components and estimation; and see Note, "Renewable Energy Production and Consumption," at end of Section 10.  
<sup>c</sup> Net imports equal imports minus exports.  
<sup>d</sup> Includes petroleum stock change and adjustments; natural gas net storage withdrawals and balancing item; coal stock change, losses, and unaccounted for; fuel ethanol stock change; and biodiesel stock change and balancing item.  
<sup>e</sup> Coal, coal coke net imports, natural gas, and petroleum.  
<sup>f</sup> Also includes electricity net imports.  
R=Revised.


Notes: • See "Primary Energy," "Primary Energy Production," and "Primary Energy Consumption," in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: • **Production:** Table 1.2. • **Trade:** Tables 1.4a and 1.4b. • **Stock Change and Other:** Calculated as consumption minus production and net imports. • **Consumption:** Table 1.3.

**Figure 1.2 Primary Energy Production**  
(Quadrillion Btu)


By Source, 1949–2019




By Source, Monthly



Total, January–November



By Source, November 2020



[a] National gas plant liquids.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.2.

**Table 1.2 Primary Energy Production by Source**  
(Quadrillion Btu)

	Fossil Fuels					Nuclear Electric Power	Renewable Energy <sup>a</sup>							Total
	Coal <sup>b</sup>	Natural Gas (Dry)	Crude Oil <sup>c</sup>	NGPL <sup>d</sup>	Total		Hydro- electric Power <sup>e</sup>	Geo- thermal	Solar	Wind	Bio- mass	Total		
1950 Total .....	14.060	6.233	11.447	0.813	32.553	0.000	1.415	NA	NA	NA	1.562	2.978	35.531	
1955 Total .....	12.370	9.345	14.410	1.223	37.347	.000	1.360	NA	NA	NA	1.424	2.784	40.131	
1960 Total .....	10.817	12.656	14.935	1.447	39.855	.006	1.608	(s)	NA	NA	1.320	2.928	42.789	
1965 Total .....	13.055	15.775	16.521	1.853	47.205	.043	2.059	.002	NA	NA	1.335	3.396	50.644	
1970 Total .....	14.607	21.666	20.401	2.478	59.152	.239	2.634	.006	NA	NA	1.431	4.070	63.462	
1975 Total .....	14.989	19.640	17.729	2.338	54.697	1.900	3.155	.034	NA	NA	1.499	4.687	61.284	
1980 Total .....	18.598	19.908	18.249	2.225	58.979	2.739	2.900	.053	NA	NA	2.475	5.428	67.147	
1985 Total .....	19.325	16.980	18.992	2.204	57.502	4.076	2.970	.097	(s)	(s)	3.016	6.084	67.661	
1990 Total .....	22.488	18.326	15.571	2.138	58.523	6.104	3.046	.171	.059	.029	2.735	6.040	70.668	
1995 Total .....	22.130	19.082	13.887	2.398	57.496	7.075	3.205	.152	.068	.033	3.099	6.557	71.129	
2000 Total .....	22.735	19.662	12.358	2.551	57.307	7.862	2.811	.164	.063	.057	3.006	6.102	71.271	
2001 Total .....	23.547	20.166	12.282	2.491	58.485	8.029	2.242	.164	.062	.070	2.624	5.162	71.675	
2002 Total .....	22.732	19.382	12.160	2.502	56.777	8.145	2.689	.171	.060	.105	2.705	5.731	70.653	
2003 Total .....	22.094	19.633	11.960	2.296	55.983	7.960	2.793	.173	.058	.113	2.805	5.942	69.885	
2004 Total .....	22.852	19.074	11.550	2.408	55.884	8.223	2.688	.178	.058	.142	2.996	6.063	70.169	
2005 Total .....	23.185	18.556	10.974	2.280	54.995	8.161	2.703	.181	.058	.178	3.101	6.221	69.377	
2006 Total .....	23.790	19.022	10.767	2.299	55.877	8.215	2.869	.181	.061	.264	3.212	6.586	70.678	
2007 Total .....	23.493	19.786	10.741	2.349	56.369	8.459	2.446	.186	.066	.341	3.472	6.510	71.338	
2008 Total .....	23.851	20.703	10.613	2.359	57.527	8.426	2.511	.192	.074	.546	3.868	7.192	73.145	
2009 Total .....	21.624	21.139	11.340	2.508	56.612	8.355	2.669	.200	.078	.721	3.957	7.625	72.592	
2010 Total .....	22.038	21.806	11.610	2.705	58.159	8.434	2.539	.208	.091	.923	4.553	8.314	74.907	
2011 Total .....	22.221	23.406	11.998	2.890	60.515	8.269	3.103	.212	.112	1.168	4.704	9.300	78.083	
2012 Total .....	20.677	24.610	13.842	3.162	62.291	8.062	2.629	.212	.159	1.340	4.547	8.886	79.239	
2013 Total .....	20.001	24.859	15.865	3.451	64.177	8.244	2.562	.214	.225	1.601	4.816	9.418	81.839	
2014 Total .....	20.286	26.718	18.607	4.005	69.616	8.338	2.467	.214	.338	1.728	5.020	9.767	87.720	
2015 Total .....	17.946	28.067	19.712	4.476	70.201	8.337	2.321	.212	.427	1.777	4.992	9.729	88.267	
2016 Total .....	14.667	27.576	18.537	4.665	65.445	8.427	2.472	.210	.570	2.096	5.077	10.425	84.297	
2017 Total .....	15.625	28.289	19.576	4.987	68.478	8.419	2.767	.210	.777	2.343	5.103	11.200	88.096	
2018 January .....	1.262	2.529	1.769	.429	5.988	.780	.228	.018	.049	.233	1.446	1.973	7.742	
February .....	1.225	2.332	1.639	.408	5.605	.677	.227	.016	.055	.211	.408	.918	7.201	
March .....	1.332	2.612	1.855	.468	6.267	.701	.235	.018	.074	.241	1.444	1.012	7.979	
April .....	1.178	2.523	1.797	.462	5.960	.618	.256	.016	.086	.241	.420	1.019	7.597	
May .....	1.241	2.637	1.850	.484	6.212	.704	.277	.018	.096	.218	.440	1.050	7.966	
June .....	1.251	2.565	1.815	.467	6.098	.729	.251	.017	.102	.225	.435	1.030	7.857	
July .....	1.280	2.704	1.929	.496	6.408	.758	.229	.018	.097	.150	.452	1.046	8.111	
August .....	1.408	2.758	2.014	.512	6.692	.756	.200	.018	.095	.181	.455	.949	8.398	
September .....	1.268	2.713	1.962	.500	6.443	.677	.174	.017	.085	.169	.421	1.066	7.986	
October .....	1.350	2.839	2.044	.511	6.743	.621	.178	.017	.072	.193	.442	.902	8.266	
November .....	1.278	2.795	2.038	.492	6.603	.669	.199	.017	.056	.200	.433	.906	8.177	
December .....	1.291	2.874	2.123	.499	6.787	.749	.208	.019	.048	.221	.448	.944	8.480	
Total .....	15.363	31.882	22.835	5.727	75.807	8.438	2.663	.209	.916	2.482	5.245	11.515	95.761	
2019 January .....	1.331	2.878	2.096	.509	6.814	.770	.221	.018	.052	.216	1.438	1.945	8.529	
February .....	1.179	2.616	1.863	.476	6.134	.676	.204	.016	.056	.201	.397	.875	7.684	
March .....	1.126	2.915	2.109	.529	6.679	.680	.234	.018	.084	.229	.427	.992	8.350	
April .....	1.234	2.833	2.074	.518	6.660	.633	.248	.016	.095	.257	.415	1.032	8.324	
May .....	1.248	2.950	2.148	.541	6.888	.701	.285	.017	.102	.229	.432	1.065	8.654	
June .....	1.145	2.866	2.066	.519	6.597	.718	.250	.017	.110	.199	.425	1.002	8.317	
July .....	1.191	2.978	2.088	.526	6.783	.754	.221	.018	.113	.196	.441	.989	8.526	
August .....	1.286	3.051	2.195	.533	7.064	.751	.201	.018	.109	.178	.440	.946	8.761	
September .....	1.180	2.949	2.136	.540	6.804	.690	.165	.017	.095	.218	.409	.904	8.398	
October .....	1.162	3.090	2.238	.562	7.052	.648	.163	.016	.085	.245	.423	.932	8.632	
November .....	1.098	3.012	2.198	.540	6.849	.670	.180	.014	.063	.223	.423	.903	8.421	
December .....	1.075	3.121	2.261	.558	7.015	.763	.191	.016	.053	.236	.445	.941	8.719	
Total .....	14.256	35.258	25.473	6.352	81.339	8.452	2.563	.201	1.018	2.626	5.116	11.524	101.315	
2020 January .....	1.123	E 3.060	E 2.253	.575	7.011	.774	.226	.017	.066	.251	1.432	1.992	8.778	
February .....	.958	E 2.851	E 2.106	.519	6.434	.689	.235	.016	.078	.259	1.404	.992	8.115	
March .....	.930	E 3.043	E 2.250	.587	6.810	.668	.209	.019	.093	.260	1.410	.991	8.469	
April .....	.788	E 2.894	E 2.053	.534	6.269	.618	.196	.018	.112	.261	.328	.915	7.802	
May .....	.746	E 2.825	E 1.770	.531	5.872	.672	.272	.018	.131	.251	.360	1.033	7.577	
June .....	.793	E 2.751	E 1.785	.562	5.892	.702	.259	.017	.130	.266	.375	1.047	7.641	
July .....	.874	E 2.888	E 1.938	.600	6.300	.725	.247	.018	.139	.201	.398	1.003	8.028	
August .....	.960	RE 2.904	E 1.870	.595	R 6.329	.720	.216	.018	.128	.201	.400	.962	8.012	
September .....	.912	E 2.786	RE 1.858	.574	R 6.131	.686	.171	.018	.109	.206	.388	.892	7.709	
October .....	.943	E 2.863	RE 1.843	.593	R 6.241	.620	.163	.018	.101	.262	.403	.947	7.808	
November .....	.930	E 2.862	E 1.902	.576	6.270	.645	.197	.018	.081	.301	.405	1.003	7.918	
11-Month Total .....	9.958	E 31.726	E 21.627	6.248	69.559	7.519	2.391	.196	1.169	2.719	4.303	10.777	87.855	
2019 11-Month Total .....	13.181	32.137	23.212	5.794	74.323	7.689	2.372	.185	.965	2.390	4.671	10.583	92.596	
2018 11-Month Total .....	14.073	29.008	20.712	5.228	69.020	7.689	2.456	.190	.867	2.261	4.798	10.572	87.281	

<sup>a</sup> Most data are estimates. See Tables 10.1–10.2c for notes on series components and estimation; and see Note, "Renewable Energy Production and Consumption," at end of Section 10.

<sup>b</sup> Beginning in 1989, includes waste coal supplied. Beginning in 2001, also includes a small amount of refuse recovery. See Table 6.1.

<sup>c</sup> Includes lease condensate.

<sup>d</sup> Natural gas processing plant production of natural gas liquids (ethane, propane, normal butane, isobutane, and natural gasoline). Through 1980, also includes natural gas processing plant production of finished petroleum products (aviation gasoline, distillate fuel oil, jet fuel, kerosene, motor gasoline, special

naphthas, and miscellaneous products).

<sup>e</sup> Conventional hydroelectric power.

R=Revised. E=Estimate. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy Production" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 1.3 Primary Energy Consumption**

(Quadrillion Btu)


By Source, [a] 1949–2020




By Source, [a] Monthly



Total, January–November



By Source, [a] November 2020



[a] Small quantities of net imports of coal coke and electricity are not shown.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.3.



**Table 1.3 Primary Energy Consumption by Source**  
(Quadrillion Btu)

	Fossil Fuels <sup>a</sup>				Nuclear Electric Power	Renewable Energy <sup>b</sup>						Total <sup>g</sup>
	Coal	Natural Gas <sup>c</sup>	Petro- leum <sup>d</sup>	Total <sup>e</sup>		Hydro- electric Power <sup>f</sup>	Geo- thermal	Solar	Wind	Bio- mass	Total	
1950 Total .....	12.347	5.968	13.298	31.615	0.000	1.415	NA	NA	NA	1.562	2.978	34.599
1955 Total .....	11.167	8.998	17.225	37.380	.000	1.360	NA	NA	NA	1.424	2.784	40.178
1960 Total .....	9.838	12.385	19.874	42.091	.006	1.608	(s)	NA	NA	1.320	2.928	45.041
1965 Total .....	11.581	15.769	23.184	50.515	.043	2.059	.002	NA	NA	1.335	3.396	53.953
1970 Total .....	12.265	21.795	29.499	63.501	.239	2.634	.006	NA	NA	1.431	4.070	67.817
1975 Total .....	12.663	19.948	32.699	65.323	1.900	3.155	.034	NA	NA	1.499	4.687	71.931
1980 Total .....	15.423	20.235	34.159	69.782	2.739	2.900	.053	NA	NA	2.475	5.428	78.021
1985 Total .....	17.478	17.703	30.866	66.035	4.076	2.970	.097	(s)	(s)	3.016	6.084	76.334
1990 Total .....	19.173	19.603	33.500	72.281	6.104	3.046	.171	.059	.029	2.735	6.040	84.433
1995 Total .....	20.089	22.671	34.341	77.162	7.075	3.205	.152	.068	.033	3.101	6.559	90.931
2000 Total .....	22.580	23.824	38.152	84.620	7.862	2.811	.164	.063	.057	3.008	6.104	98.702
2001 Total .....	21.914	22.773	38.084	82.800	8.029	2.242	.164	.062	.070	2.622	5.160	96.064
2002 Total .....	21.904	23.510	38.117	83.592	8.145	2.689	.171	.060	.105	2.701	5.726	97.535
2003 Total .....	22.321	22.831	38.707	83.909	7.960	2.793	.173	.058	.113	2.806	5.944	97.835
2004 Total .....	22.466	22.923	40.139	85.666	8.223	2.688	.178	.058	.142	3.008	6.075	100.002
2005 Total .....	22.797	22.565	40.217	85.623	8.161	2.703	.181	.058	.178	3.114	6.234	100.102
2006 Total .....	22.447	22.239	39.731	84.477	8.215	2.869	.181	.061	.264	3.262	6.637	99.392
2007 Total .....	22.749	23.663	39.368	85.805	8.459	2.446	.186	.066	.341	3.485	6.523	100.893
2008 Total .....	22.387	23.843	36.769	83.041	8.426	2.511	.192	.074	.546	3.851	7.175	98.754
2009 Total .....	19.691	23.416	34.779	77.862	8.355	2.669	.200	.078	.721	3.940	7.608	93.942
2010 Total .....	20.834	24.575	35.321	80.723	8.434	2.539	.208	.091	.923	4.506	8.267	97.513
2011 Total .....	19.658	24.955	34.639	79.263	8.269	3.103	.212	.112	1.168	4.609	9.204	96.863
2012 Total .....	17.378	26.089	33.833	77.304	8.062	2.629	.212	.159	1.340	4.508	8.847	94.374
2013 Total .....	18.039	26.805	34.398	79.224	8.244	2.562	.214	.225	1.601	4.848	9.451	97.117
2014 Total .....	17.998	27.383	34.658	80.017	8.338	2.467	.214	.338	1.728	4.994	9.740	98.276
2015 Total .....	15.549	28.191	35.368	79.090	8.337	2.321	.212	.427	1.777	4.983	9.721	97.375
2016 Total .....	14.226	28.400	35.712	78.319	8.427	2.472	.210	.570	2.096	R 5.017	R 10.365	R 97.338
2017 Total .....	13.837	28.055	36.043	77.907	8.419	2.767	.210	.777	2.343	R 4.983	R 11.081	R 97.599
2018 January .....	1.334	3.456	3.126	7.911	.780	.228	.018	.049	.233	R .427	R .954	R 9.660
February .....	.963	2.803	2.711	6.476	.677	.227	.016	.055	.211	R .383	R .893	R 8.058
March .....	.941	2.892	3.159	6.990	.701	.235	.018	.074	.241	R .429	R .996	R 8.702
April .....	.863	2.429	2.962	6.251	.618	.256	.016	.086	.241	R .403	R 1.002	R 7.881
May .....	.993	2.123	3.104	6.219	.704	.277	.018	.096	.218	R .431	R 1.041	R 7.977
June .....	1.160	2.132	3.089	6.380	.729	.251	.017	.102	.225	R .420	R 1.015	R 8.138
July .....	1.311	2.429	3.165	6.903	.758	.229	.018	.097	.150	R .436	R .929	R 8.604
August .....	1.309	2.391	3.277	6.976	.756	.200	.018	.095	.181	R .441	R .935	R 8.683
September .....	1.120	2.228	2.975	6.322	.677	.174	.017	.085	.169	R .401	R .846	R 7.855
October .....	1.017	2.362	3.187	6.564	.621	.178	.017	.072	.193	R .424	R .884	R 8.079
November .....	1.082	2.808	3.057	6.943	.669	.199	.017	.056	.200	R .415	R .888	R 8.509
December .....	1.158	3.101	3.080	7.336	.749	.208	.019	.048	.221	R .430	R .926	R 9.022
Total .....	13.252	31.153	36.892	81.271	8.438	2.663	.209	.916	2.482	R 5.038	R 11.308	R 101.169
2019 January .....	1.161	3.542	3.130	7.830	.770	.221	.018	.052	.216	R .414	R .921	R 9.532
February .....	.949	3.123	2.757	6.828	.676	.204	.016	.056	.201	R .384	R .862	R 8.377
March .....	.933	3.028	3.065	7.025	.680	.234	.018	.084	.229	R .414	R .980	R 8.692
April .....	.719	2.288	3.001	6.007	.633	.248	.016	.095	.257	R .399	R 1.015	R 7.662
May .....	.850	2.207	3.116	6.171	.701	.285	.017	.102	.229	R .421	R 1.054	R 7.937
June .....	.931	2.192	3.065	6.186	.718	.250	.017	.110	.199	R .413	R .989	R 7.906
July .....	1.154	2.476	3.179	6.807	.754	.221	.018	.113	.196	R .426	R .975	R 8.548
August .....	1.086	2.517	3.255	6.857	.751	.201	.018	.109	.178	R .425	R .930	R 8.552
September .....	.986	2.282	2.995	6.260	.690	.165	.017	.095	.218	R .396	R .891	R 7.853
October .....	.801	2.387	3.165	6.351	.648	.163	.016	.085	.245	R .414	R .922	R 7.928
November .....	.885	2.878	3.046	6.807	.670	.180	.014	.063	.223	R .408	R .888	R 8.377
December .....	.860	3.277	3.093	7.227	.763	.191	.016	.053	.236	R .425	R .921	R 8.925
Total .....	11.316	32.196	36.866	80.357	8.452	2.563	.201	1.018	2.626	R 4.939	R 11.348	R 100.289
2020 January .....	.785	3.415	3.007	7.206	.774	.226	.017	.066	.251	R .408	R .968	R 8.959
February .....	.694	3.141	2.805	6.639	.689	.235	.016	.078	.259	R .382	R .971	R 8.308
March .....	.633	2.805	2.761	6.198	.668	.209	.019	.093	.260	R .379	R .960	R 7.839
April .....	.515	2.324	2.140	4.978	.618	.196	.018	.112	.261	R .319	R .906	R 6.513
May .....	.575	2.144	2.416	5.136	.672	.272	.018	.131	.251	R .362	R 1.034	R 6.854
June .....	.769	2.211	2.544	5.523	.702	.259	.017	.130	.266	R .368	R 1.040	R 7.278
July .....	1.021	2.583	2.759	6.364	.725	.247	.018	.139	.201	R .389	R .994	R 8.101
August .....	1.035	2.494	2.801	6.329	.720	.216	.018	.128	.201	R .386	R .949	R 8.019
September .....	.807	2.252	2.683	5.741	.686	.171	.018	.109	.206	R .377	R .880	R 7.320
October .....	.725	2.412	2.811	5.947	.620	.163	.018	.101	.262	R .382	R .926	R 7.504
November .....	.725	2.533	2.708	5.964	.645	.197	.018	.081	.301	R .384	R .982	R 7.603
11-Month Total ...	8.285	28.316	29.434	66.024	7.519	2.391	.196	1.169	2.719	4.137	10.611	84.299
2019 11-Month Total ...	10.456	28.918	33.774	73.129	7.689	2.372	.185	.965	2.390	4.514	10.427	91.364
2018 11-Month Total ...	12.093	28.052	33.812	73.935	7.689	2.456	.190	.867	2.261	4.608	10.382	92.147


<sup>a</sup> Includes non-combustion use of fossil fuels.  
<sup>b</sup> Most data are estimates. See Tables 10.1–10.2c for notes on series components and estimation; and see Note, "Renewable Energy Production and Consumption," at end of Section 10.  
<sup>c</sup> Natural gas only; excludes supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.  
<sup>d</sup> Petroleum products supplied; excludes biofuels that have been blended with petroleum—biofuels are included in "Biomass."  
<sup>e</sup> Includes coal coke net imports. See Tables 1.4c.  
<sup>f</sup> Conventional hydroelectric power.  
<sup>g</sup> Includes coal coke net imports and electricity net imports, which are not

separately displayed. See Tables 1.4c.  
R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.  
Notes: • See "Primary Energy Consumption" in Glossary.  
• See Table D1 for estimated energy consumption for 1635–1945. • Totals may not equal sum of components due to independent rounding.  
• Geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
Sources: See end of section.


**Figure 1.4a Primary Energy Imports**

(Quadrillion Btu)


By Source, 1949–2019




By Source, Monthly



Total, January–November



Total, Monthly



[a] Crude oil and lease condensate, includes imports into the Strategic Petroleum Reserve, which began in 1977.

[b] Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

[c] Coal, coal coke, biomass, and electricity.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.4a.

**Table 1.4a Primary Energy Imports by Source**  
(Quadrillion Btu)

	Imports								
	Coal	Coal Coke	Natural Gas	Petroleum			Biomass <sup>c</sup>	Electricity	Total
				Crude Oil <sup>a</sup>	Petroleum Products <sup>b</sup>	Total			
1950 Total .....	0.009	0.011	0.000	1.056	0.830	1.886	NA	0.007	1.913
1955 Total .....	.008	.003	.011	1.691	1.061	2.752	NA	.016	2.790
1960 Total .....	.007	.003	.161	2.196	1.802	3.999	NA	.018	4.188
1965 Total .....	.005	.002	.471	2.654	2.748	5.402	NA	.012	5.892
1970 Total .....	.001	.004	.846	2.814	4.656	7.470	NA	.021	8.342
1975 Total .....	.024	.045	.978	8.721	4.227	12.948	NA	.038	14.032
1980 Total .....	.030	.016	1.006	11.195	3.463	14.658	NA	.085	15.796
1985 Total .....	.049	.014	.952	6.814	3.796	10.609	NA	.157	11.781
1990 Total .....	.067	.019	1.551	12.766	4.351	17.117	NA	.063	18.817
1995 Total .....	.237	.095	2.901	15.669	3.131	18.800	.001	.146	22.180
2000 Total .....	.313	.094	3.869	19.783	4.641	24.424	(s)	.166	28.865
2001 Total .....	.495	.063	4.068	20.348	4.946	25.294	.002	.131	30.052
2002 Total .....	.422	.080	4.104	19.920	4.677	24.597	.002	.125	29.331
2003 Total .....	.626	.068	4.042	21.060	5.105	26.165	.002	.104	31.007
2004 Total .....	.682	.170	4.365	22.082	6.063	28.145	.013	.117	33.492
2005 Total .....	.762	.088	4.450	22.091	7.108	29.198	.012	.150	34.659
2006 Total .....	.906	.101	4.291	22.085	7.054	29.139	.066	.146	34.649
2007 Total .....	.909	.061	4.723	21.914	6.842	28.756	.055	.175	34.679
2008 Total .....	.855	.089	4.084	21.448	6.214	27.662	.085	.195	32.970
2009 Total .....	.566	.009	3.845	19.699	5.367	25.066	.027	.178	29.690
2010 Total .....	.484	.030	3.834	20.140	5.219	25.359	.004	.154	29.866
2011 Total .....	.327	.035	3.555	19.595	5.038	24.633	.019	.178	28.748
2012 Total .....	.212	.028	3.216	19.239	4.122	23.361	.049	.202	27.068
2013 Total .....	.199	.003	2.955	16.957	4.169	21.126	.102	.236	24.623
2014 Total .....	.252	.002	2.763	16.178	3.773	19.951	.046	.227	23.241
2015 Total .....	.256	.003	2.786	16.299	4.111	20.410	.079	.259	23.794
2016 Total .....	.220	.006	3.082	17.392	4.309	21.700	.123	.248	25.378
2017 Total .....	.168	.001	3.109	17.597	4.277	21.874	.081	.224	25.458
2018 January .....	.010	(s)	.307	1.507	.381	1.888	.004	.018	2.228
February .....	.007	(s)	.243	1.273	.318	1.591	.003	.016	1.861
March .....	.011	(s)	.278	1.432	.371	1.803	.004	.019	2.114
April .....	.010	.001	.248	1.501	.345	1.847	.004	.015	2.125
May .....	.011	.001	.233	1.472	.404	1.876	.004	.018	2.142
June .....	.010	(s)	.234	1.544	.365	1.909	.004	.019	2.176
July .....	.014	(s)	.253	1.492	.382	1.873	.002	.018	2.161
August .....	.010	(s)	.243	1.502	.411	1.913	.005	.021	2.192
September .....	.005	(s)	.219	1.381	.375	1.756	.003	.015	1.999
October .....	.006	.001	.221	1.382	.354	1.736	.006	.013	1.982
November .....	.008	(s)	.218	1.372	.280	1.652	.005	.013	1.896
December .....	.018	(s)	.264	1.334	.323	1.657	.004	.014	1.958
Total .....	.122	.003	2.961	17.192	4.309	21.501	.048	.199	24.833
2019 January .....	.013	(s)	.298	1.420	.370	1.790	.005	.016	2.122
February .....	.007	(s)	.239	1.132	.303	1.435	.003	.016	1.700
March .....	.015	(s)	.259	1.274	.353	1.628	.006	.017	1.925
April .....	.011	.001	.212	1.273	.409	1.681	.006	.015	1.925
May .....	.008	(s)	.213	1.344	.459	1.803	.005	.016	2.046
June .....	.014	(s)	.206	1.300	.345	1.645	.007	.018	1.889
July .....	.011	(s)	.236	1.304	.444	1.748	.007	.019	2.021
August .....	.011	.001	.226	1.305	.408	1.713	.006	.020	1.975
September .....	.013	(s)	.213	1.179	.358	1.537	.007	.018	1.789
October .....	.015	(s)	.216	1.173	.392	1.565	.007	.012	1.816
November .....	.010	.001	.229	1.058	.368	1.426	.006	.017	1.688
December .....	.011	(s)	.262	1.284	.387	1.671	.007	.018	1.969
Total .....	.138	.003	2.810	15.045	4.596	19.641	.072	.201	22.865
2020 January .....	.011	(s)	.269	1.204	.361	1.565	.006	.016	1.866
February .....	.007	(s)	.244	1.146	.302	1.448	.005	.015	1.719
March .....	.009	(s)	.223	1.183	.342	1.525	.005	.017	1.779
April .....	.007	(s)	.198	1.004	.274	1.278	.007	.016	1.507
May .....	.010	.001	.194	1.144	.278	1.421	.005	.018	1.649
June .....	.006	(s)	.195	1.163	.317	1.480	.006	.018	1.704
July .....	.010	(s)	.218	1.110	.324	1.434	.005	.023	1.689
August .....	.006	(s)	.219	1.021	.338	1.358	.007	.023	1.614
September .....	.010	.001	.179	.981	.345	1.327	.006	.016	1.539
October .....	.005	.002	.207	.995	.345	1.339	.007	.014	1.575
November .....	.013	(s)	.221	1.013	.328	1.341	.007	.016	1.598
11-Month Total .....	.096	.004	2.366	11.963	3.554	15.516	.066	.192	18.241
2019 11-Month Total .....	.127	.003	2.548	13.761	4.209	17.970	.065	.184	20.896
2018 11-Month Total .....	.103	.003	2.697	15.858	3.986	19.844	.044	.185	22.876

<sup>a</sup> Crude oil and lease condensate. Includes imports into the Strategic Petroleum Reserve, which began in 1977.

<sup>b</sup> Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

<sup>c</sup> Fuel ethanol (minus denaturant) and biodiesel.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy" in Glossary. • Totals may not equal sum of

components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 1.4b Primary Energy Exports**

(Quadrillion Btu)


By Source, 1949-2019




By Source, Monthly



Total, January–November



Total, Monthly



[a] Crude oil and lease condensate.

[b] Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

[c] Includes coal coke.

[d] Biomass and electricity

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.4b.

**Table 1.4b Primary Energy Exports by Source**  
(Quadrillion Btu)

	Exports								
	Coal	Coal Coke	Natural Gas	Petroleum			Biomass <sup>c</sup>	Electricity	Total
				Crude Oil <sup>a</sup>	Petroleum Products <sup>b</sup>	Total			
1950 Total .....	0.786	0.010	0.027	0.202	0.440	0.642	NA	0.001	1.465
1955 Total .....	1.465	.013	.032	.067	.707	.774	NA	.002	2.286
1960 Total .....	1.023	.009	.012	.018	.413	.431	NA	.003	1.477
1965 Total .....	1.376	.021	.027	.006	.386	.392	NA	.013	1.829
1970 Total .....	1.936	.061	.072	.029	.520	.549	NA	.014	2.632
1975 Total .....	1.761	.032	.074	.012	.427	.439	NA	.017	2.323
1980 Total .....	2.421	.051	.049	.609	.551	1.160	NA	.014	3.695
1985 Total .....	2.438	.028	.056	.432	1.225	1.657	NA	.017	4.196
1990 Total .....	2.772	.014	.087	.230	1.594	1.824	NA	.055	4.752
1995 Total .....	2.318	.034	.156	.200	1.776	1.976	NA	.012	4.496
2000 Total .....	1.528	.028	.245	.106	2.003	2.110	NA	.051	3.962
2001 Total .....	1.265	.033	.377	.043	1.956	1.999	(s)	.056	3.731
2002 Total .....	1.032	.020	.520	.019	1.963	1.982	(s)	.054	3.608
2003 Total .....	1.117	.018	.686	.026	2.083	2.110	.001	.082	4.013
2004 Total .....	1.253	.033	.862	.057	2.068	2.125	.001	.078	4.351
2005 Total .....	1.273	.043	.735	.067	2.276	2.344	.001	.065	4.462
2006 Total .....	1.264	.040	.730	.052	2.554	2.606	.005	.083	4.727
2007 Total .....	1.507	.036	.830	.058	2.803	2.861	.036	.069	5.338
2008 Total .....	2.071	.049	.972	.061	3.626	3.686	.089	.083	6.949
2009 Total .....	1.515	.032	1.082	.093	4.101	4.194	.035	.062	6.920
2010 Total .....	2.101	.036	1.147	.088	4.691	4.780	.047	.065	8.176
2011 Total .....	2.751	.024	1.519	.100	5.820	5.919	.108	.051	10.373
2012 Total .....	3.087	.024	1.633	.143	6.261	6.404	.078	.041	11.267
2013 Total .....	2.895	.021	1.587	.284	6.886	7.170	.076	.039	11.788
2014 Total .....	2.435	.023	1.528	.744	7.414	8.158	.081	.045	12.270
2015 Total .....	1.852	.021	1.800	.964	8.153	9.118	.080	.031	12.902
2016 Total .....	1.546	.025	2.356	1.238	8.752	9.990	.181	.021	14.119
2017 Total .....	2.388	.030	3.182	2.424	9.684	12.108	.206	.032	17.946
2018 January .....	.210	.004	.303	.242	.795	1.037	.015	.004	1.572
February .....	.218	.001	.278	.278	.719	.997	.025	.004	1.525
March .....	.240	.002	.294	.349	.826	1.175	.026	.004	1.742
April .....	.268	.003	.281	.329	.883	1.213	.021	.006	1.792
May .....	.228	.002	.275	.367	.881	1.248	.018	.004	1.775
June .....	.246	.002	.264	.391	.832	1.224	.023	.004	1.762
July .....	.241	.002	.309	.409	.882	1.291	.017	.003	1.863
August .....	.243	.001	.314	.330	.826	1.155	.019	.004	1.737
September .....	.235	.001	.304	.346	.815	1.161	.018	.004	1.723
October .....	.262	.002	.309	.400	.892	1.293	.025	.003	1.894
November .....	.217	.003	.341	.412	.885	1.297	.022	.004	1.884
December .....	.216	.003	.367	.424	.921	1.345	.021	.003	1.955
Total .....	2.824	.029	3.640	4.277	10.158	14.434	.249	.047	21.224
2019 January .....	.229	.003	.368	.468	.820	1.287	.018	.005	1.910
February .....	.166	.001	.333	.466	.737	1.203	.017	.005	1.725
March .....	.225	.001	.377	.473	.806	1.279	.022	.009	1.912
April .....	.212	.002	.341	.498	.810	1.309	.022	.007	1.893
May .....	.221	.002	.372	.524	.811	1.335	.019	.006	1.954
June .....	.204	.002	.363	.531	.813	1.344	.021	.005	1.940
July .....	.159	.002	.397	.479	.825	1.304	.020	.007	1.889
August .....	.190	.002	.388	.487	.873	1.360	.022	.006	1.969
September .....	.190	.003	.398	.530	.831	1.360	.019	.006	1.977
October .....	.162	.003	.430	.604	.866	1.470	.018	.005	2.088
November .....	.186	.002	.445	.527	.844	1.372	.018	.004	2.028
December .....	.160	.003	.485	.626	.889	1.515	.023	.004	2.190
Total .....	2.305	.024	4.698	6.212	9.926	16.139	.240	.068	23.474
2020 January .....	.153	.002	.515	.575	.910	1.485	.020	.005	2.180
February .....	.168	.002	.458	.614	.897	1.511	.025	.006	2.169
March .....	.170	.001	.502	.629	.931	1.561	.023	.004	2.261
April .....	.135	.001	.425	.527	.798	1.325	.020	.005	1.911
May .....	.116	.001	.399	.518	.597	1.115	.016	.005	1.653
June .....	.113	(s)	R .342	.471	.735	1.206	.019	.004	1.684
July .....	.132	.001	.352	.578	.793	1.371	.015	.004	1.875
August .....	.111	.001	.362	.584	.798	1.382	.020	.003	1.879
September .....	.132	.001	.398	.555	.765	1.320	.019	.003	1.874
October .....	.124	.003	R .485	.519	.833	1.352	.020	.003	R 1.987
November .....	.173	.002	.531	.467	.758	1.225	.019	.003	1.953
11-Month Total .....	1.526	.016	4.769	6.037	8.817	14.854	.214	.046	21.426
2019 11-Month Total .....	2.146	.021	4.213	5.586	9.037	14.624	.217	.064	21.285
2018 11-Month Total .....	2.608	.025	3.273	3.853	9.237	13.090	.229	.044	19.269

<sup>a</sup> Crude oil and lease condensate.

<sup>b</sup> Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

<sup>c</sup> Beginning in 2001, includes biodiesel. Beginning in 2010, also includes fuel ethanol (minus denaturant). Beginning in 2016, also includes wood and wood-derived fuels.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 1.4c Primary Energy Net Imports**

(Quadrillion Btu)


Total, 1949–2019




By Major Source, 1949–2019



Total, Monthly



By Major Source, Monthly



[a] Crude oil and lease condensate. Includes imports into the Strategic Petroleum Reserve, which began in 1977.

[b] Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

[c] Includes coal coke.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.4c.

**Table 1.4c Primary Energy Net Imports by Source**  
(Quadrillion Btu)

	Net Imports <sup>a</sup>								
	Coal	Coal Coke	Natural Gas	Petroleum			Biomass <sup>d</sup>	Electricity	Total
				Crude Oil <sup>b</sup>	Petroleum Products <sup>c</sup>	Total			
1950 Total .....	-0.777	0.001	-0.027	0.854	0.390	1.244	NA	0.006	0.448
1955 Total .....	-1.456	-.010	-.021	1.624	.354	1.978	NA	.014	.504
1960 Total .....	-1.017	-.006	.149	2.178	1.389	3.568	NA	.015	2.710
1965 Total .....	-1.372	-.018	.444	2.648	2.362	5.010	NA	(s)	4.063
1970 Total .....	-1.935	-.058	.774	2.785	4.136	6.921	NA	.007	5.709
1975 Total .....	-1.738	.014	.904	8.708	3.800	12.508	NA	.021	11.709
1980 Total .....	-2.391	-.035	.957	10.586	2.912	13.499	NA	.071	12.101
1985 Total .....	-2.389	-.013	.896	6.381	2.570	8.952	NA	.140	7.584
1990 Total .....	-2.705	.005	1.464	12.536	2.757	15.293	NA	.008	14.065
1995 Total .....	-2.081	.061	2.745	15.469	1.355	16.824	.001	.134	17.684
2000 Total .....	-1.215	.065	3.623	19.676	2.638	22.314	(s)	.115	24.904
2001 Total .....	-.771	.029	3.691	20.305	2.990	23.294	.001	.075	26.321
2002 Total .....	-.610	.061	3.583	19.901	2.714	22.615	.002	.072	25.722
2003 Total .....	-.491	.051	3.356	21.034	3.021	24.055	.001	.022	26.994
2004 Total .....	-.571	.138	3.503	22.025	3.995	26.020	.012	.039	29.141
2005 Total .....	-.512	.044	3.714	22.023	4.831	26.855	.011	.085	30.197
2006 Total .....	-.358	.061	3.560	22.032	4.501	26.533	.062	.063	29.921
2007 Total .....	-.598	.025	3.893	21.855	4.040	25.895	.019	.107	29.341
2008 Total .....	-1.215	.041	3.112	21.388	2.588	23.976	-.004	.112	26.021
2009 Total .....	-.949	-.024	2.763	19.606	1.266	20.872	-.009	.116	22.770
2010 Total .....	-1.617	-.006	2.687	20.052	.528	20.580	-.042	.089	21.690
2011 Total .....	-2.423	.011	2.036	19.495	-.781	18.714	-.089	.127	18.375
2012 Total .....	-2.875	.004	1.583	19.096	-2.139	16.957	-.029	.161	15.801
2013 Total .....	-2.696	-.017	1.369	16.673	-2.717	13.956	.026	.197	12.835
2014 Total .....	-2.183	-.022	1.235	15.434	-3.641	11.793	-.034	.182	10.971
2015 Total .....	-1.596	-.018	.986	15.335	-4.042	11.292	-.001	.227	10.892
2016 Total .....	-1.326	-.019	.725	16.154	-4.443	11.710	-.058	.227	11.259
2017 Total .....	-2.220	-.029	-.073	15.173	-5.407	9.766	-.124	.192	7.512
2018 January .....	-.200	-.004	.004	1.265	-.414	.851	-.011	.014	.655
February .....	-.211	-.001	-.035	.995	-.401	.594	-.023	.012	.336
March .....	-.230	-.002	-.017	1.083	-.455	.628	-.022	.015	.372
April .....	-.258	-.002	-.033	1.172	-.538	.634	-.017	.010	.333
May .....	-.217	-.002	-.042	1.106	-.477	.628	-.014	.014	.367
June .....	-.235	-.001	-.030	1.153	-.467	.685	-.019	.015	.414
July .....	-.227	-.002	-.056	1.082	-.500	.582	-.014	.015	.298
August .....	-.233	-.001	-.071	1.172	-.414	.758	-.015	.017	.454
September .....	-.230	-.001	-.085	1.035	-.440	.595	-.014	.011	.275
October .....	-.255	-.002	-.089	.982	-.539	.444	-.019	.010	.088
November .....	-.209	-.003	-.123	.960	-.605	.355	-.016	.009	.012
December .....	-.198	-.003	-.104	.910	-.598	.312	-.016	.011	.003
Total .....	-2.702	-.026	-.679	12.915	-5.849	7.066	-.201	.152	3.610
2019 January .....	-.217	-.003	-.070	.952	-.450	.503	-.013	.011	.212
February .....	-.159	-.001	-.094	.666	-.434	.232	-.014	.011	-.024
March .....	-.210	-.001	-.118	.801	-.453	.349	-.016	.008	.013
April .....	-.201	-.001	-.130	.774	-.402	.373	-.017	.008	.032
May .....	-.212	-.002	-.159	.821	-.352	.468	-.013	.010	.092
June .....	-.191	-.002	-.157	.770	-.469	.301	-.014	.012	-.051
July .....	-.149	-.002	-.161	.825	-.381	.444	-.014	.013	.132
August .....	-.180	-.001	-.163	.817	-.465	.353	-.017	.014	.006
September .....	-.177	-.002	-.185	.649	-.473	.176	-.012	.012	-.188
October .....	-.147	-.002	-.214	.569	-.474	.095	-.011	.007	-.272
November .....	-.177	-.002	-.216	.530	-.476	.055	-.012	.012	-.340
December .....	-.149	-.003	-.223	.658	-.502	.156	-.016	.014	-.221
Total .....	-2.167	-.021	-1.888	8.833	-5.331	3.502	-.168	.133	-.609
2020 January .....	-.142	-.001	-.246	.629	-.549	.080	-.014	.011	-.314
February .....	-.161	-.002	-.214	.532	-.595	-.063	-.020	.010	-.450
March .....	-.160	-.001	-.279	.554	-.589	-.036	-.018	.013	-.482
April .....	-.127	-.001	-.226	.477	-.524	-.047	-.013	.011	-.404
May .....	-.106	(s)	-.205	.625	-.320	.306	-.011	.012	-.004
June .....	-.107	(s)	-.147	.692	-.418	.274	-.013	.013	.020
July .....	-.122	(s)	-.134	.532	-.469	.063	-.011	.019	-.186
August .....	-.105	-.001	-.143	.437	-.461	-.023	-.013	.020	-.265
September .....	-.122	-.001	-.220	.427	-.420	.007	-.013	.013	-.335
October .....	-.119	-.001	R, -.279	.475	-.488	-.013	-.012	.011	R, -.413
November .....	-.159	-.002	-.310	.546	-.430	.116	-.011	.013	-.354
11-Month Total .....	-1.430	-.012	-2.403	5.926	-5.263	.662	-.148	.146	-3.185
2019 11-Month Total .....	-2.018	-.018	-1.665	8.175	-4.828	3.347	-.152	.119	-.388
2018 11-Month Total .....	-2.505	-.023	-.576	12.005	-5.251	6.754	-.184	.141	3.607

<sup>a</sup> Net imports equal imports minus exports.

<sup>b</sup> Crude oil and lease condensate. Includes imports into the Strategic Petroleum Reserve, which began in 1977.

<sup>c</sup> Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

<sup>d</sup> Beginning in 2001, includes biodiesel. Beginning in 2010, also includes fuel ethanol (minus denaturant). Beginning in 2016, also includes wood and wood-derived fuels.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: Tables 1.4a and 1.4b.


**Figure 1.5 Merchandise Trade Value**

(Billion Dollars[a])


Imports and Exports, 1974–2020




Imports and Exports, Monthly



Trade Balance, 1974–2020



Trade Balance, Monthly



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.5.



**Table 1.5 Merchandise Trade Value**  
(Million Dollars<sup>a</sup>)

	Petroleum <sup>b</sup>			Energy <sup>c</sup>			Non-Energy Balance	Total Merchandise		
	Exports	Imports	Balance	Exports	Imports	Balance		Exports	Imports	Balance
1974 Total .....	792	24,668	-23,876	3,444	25,454	-22,010	18,126	99,437	103,321	-3,884
1975 Total .....	907	25,197	-24,289	4,470	26,476	-22,006	31,557	108,856	99,305	9,551
1980 Total .....	2,833	78,637	-75,803	7,982	82,924	-74,942	55,246	225,566	245,262	-19,696
1985 Total .....	4,707	50,475	-45,768	9,971	53,917	-43,946	-73,765	218,815	336,526	-117,712
1990 Total .....	6,901	61,583	-54,682	12,233	64,661	-52,428	-50,068	393,592	496,088	-102,496
1995 Total .....	6,321	54,368	-48,047	10,358	59,109	-48,751	-110,050	584,742	743,543	-158,801
2000 Total .....	10,192	119,251	-109,059	13,179	135,367	-122,188	-313,916	781,918	1,218,022	-436,104
2001 Total .....	8,868	102,747	-93,879	12,494	121,923	-109,429	-302,470	729,100	1,140,999	-411,899
2002 Total .....	8,569	102,663	-94,094	11,541	115,748	-104,207	-364,056	693,103	1,161,366	-468,263
2003 Total .....	10,209	132,433	-122,224	13,768	153,298	-139,530	-392,820	724,771	1,257,121	-532,350
2004 Total .....	13,130	179,266	-166,136	18,642	206,660	-188,018	-462,912	818,775	1,469,704	-650,930
2005 Total .....	19,155	250,068	-230,913	26,488	289,723	-263,235	-504,242	905,978	1,673,455	-767,477
2006 Total .....	28,171	299,714	-271,543	34,711	332,500	-297,789	-519,515	1,036,635	1,853,938	-817,304
2007 Total .....	33,293	327,620	-294,327	41,725	364,987	-323,262	-485,501	1,148,199	1,956,962	-808,763
2008 Total .....	61,695	449,847	-388,152	76,075	491,885	-415,810	-400,389	1,287,442	2,103,641	-816,199
2009 Total .....	44,509	251,833	-207,324	54,536	271,739	-217,203	-286,379	1,056,043	1,559,625	-503,582
2010 Total .....	64,753	333,472	-268,719	80,625	354,982	-274,357	-361,005	1,278,495	1,913,857	-635,362
2011 Total .....	<sup>b</sup> 102,180	<sup>b</sup> 431,866	<sup>b</sup> -329,686	128,989	453,839	-324,850	-400,597	1,482,508	2,207,954	-725,447
2012 Total .....	111,949	408,509	-296,560	136,054	423,860	-287,806	-442,640	1,545,821	2,276,267	-730,446
2013 Total .....	123,244	363,141	-239,897	147,572	379,758	-232,186	-457,284	1,578,517	2,267,987	-689,470
2014 Total .....	127,818	326,709	-198,891	154,498	347,474	-192,976	-541,506	1,621,874	2,356,356	-734,482
2015 Total .....	85,890	177,455	-91,565	103,612	190,501	-86,889	-658,594	1,503,328	2,248,811	-745,483
2016 Total .....	74,921	142,920	-67,999	92,971	153,800	-60,829	-674,497	1,451,460	2,186,786	-735,326
2017 Total .....	104,975	181,672	-76,697	137,920	194,790	-56,870	-735,526	1,547,195	2,339,591	-792,396
2018 January .....	10,015	18,086	-8,071	13,086	19,870	-6,784	-71,369	125,034	203,187	-78,153
February .....	9,786	14,623	-4,837	12,859	15,746	-2,887	-55,844	128,235	186,966	-58,731
March .....	11,571	16,733	-5,162	14,880	17,788	-2,908	-55,534	149,547	207,989	-58,442
April .....	12,710	18,028	-5,318	15,953	18,898	-2,945	-63,956	138,235	205,136	-66,901
May .....	13,118	19,738	-6,620	16,587	20,544	-3,957	-66,696	145,513	216,167	-70,653
June .....	13,477	20,295	-6,818	16,609	21,082	-4,473	-61,415	145,503	211,391	-65,888
July .....	13,777	21,605	-7,828	17,476	22,624	-5,148	-78,139	133,740	217,027	-83,287
August .....	12,248	21,597	-9,349	15,870	22,621	-6,751	-75,119	140,118	221,988	-81,870
September .....	12,708	19,282	-6,574	16,088	20,123	-4,035	-68,044	139,331	211,410	-72,079
October .....	14,637	19,760	-5,123	18,362	20,760	-2,398	-86,564	147,077	236,040	-88,962
November .....	13,193	15,809	-2,616	16,794	17,113	-319	-74,071	139,337	213,727	-74,390
December .....	12,420	13,932	-1,512	16,280	15,574	706	-73,391	134,018	206,702	-72,685
Total .....	149,661	219,489	-69,828	190,843	232,741	-41,898	-830,143	1,665,688	2,537,729	-872,041
2019 January .....	11,965	14,077	-2,112	15,609	15,674	-65	-74,915	129,608	204,587	-74,980
February .....	11,642	12,273	-631	14,555	13,581	974	-56,750	129,919	185,694	-55,776
March .....	12,896	15,335	-2,439	16,389	16,707	-318	-59,179	148,472	207,969	-59,497
April .....	12,953	17,808	-4,855	16,746	18,631	-1,885	-72,450	134,838	209,174	-74,335
May .....	13,369	20,087	-6,718	16,948	20,860	-3,912	-74,442	142,237	220,591	-78,354
June .....	12,771	16,978	-4,207	16,142	17,657	-1,515	-67,782	137,870	207,167	-69,297
July .....	12,669	18,265	-5,596	16,000	19,036	-3,036	-82,634	133,129	218,799	-85,670
August .....	13,196	16,240	-3,044	16,122	17,009	-887	-76,449	138,310	215,647	-77,336
September .....	12,912	14,396	-1,484	16,289	15,131	1,158	-73,721	134,162	206,725	-72,563
October .....	13,925	15,027	-1,102	17,376	15,804	1,572	-78,569	142,418	219,414	-76,997
November .....	13,187	13,281	-94	16,798	14,279	2,519	-65,055	136,940	199,476	-62,536
December .....	15,069	15,307	-238	18,863	16,531	2,332	-69,364	135,258	202,289	-67,032
Total .....	156,553	189,075	-32,522	197,836	200,900	-3,064	-851,307	1,643,161	2,497,531	-854,371
2020 January .....	14,000	14,873	-873	17,912	15,914	1,998	-69,402	128,993	196,397	-67,404
February .....	14,074	12,543	1,531	17,509	13,286	4,223	-50,326	132,182	178,285	-46,103
March .....	12,407	11,023	1,384	15,863	11,628	4,235	-64,057	134,560	194,382	-59,822
April .....	7,904	5,966	1,938	10,749	6,485	4,264	-73,916	95,799	165,452	-69,652
May .....	4,960	5,907	-947	7,559	6,518	1,041	-74,423	90,549	163,931	-73,382
June .....	6,722	7,555	-833	9,275	8,108	1,167	-75,820	105,056	179,709	-74,653
July .....	8,712	8,644	68	11,391	9,348	2,043	-90,055	112,827	200,839	-88,012
August .....	9,177	9,445	-268	11,946	10,230	1,716	-87,131	118,044	203,459	-85,415
September .....	8,878	9,156	-278	11,836	9,833	2,003	-86,929	121,469	206,395	-84,926
October .....	8,603	8,927	-324	12,197	9,715	2,482	-89,413	132,571	219,502	-86,931
November .....	8,027	8,716	-689	12,294	9,717	2,577	<sup>R</sup> -88,299	<sup>R</sup> 127,024	<sup>R</sup> 212,746	<sup>R</sup> -85,722
December .....	10,246	9,981	265	14,966	11,254	3,712	-86,630	132,565	215,483	-82,918
Total .....	113,711	112,736	975	153,497	122,036	31,461	-936,401	1,431,638	2,336,579	-904,940

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> Through 2010, data are for crude oil, petroleum preparations, liquefied propane and butane, and other mineral fuels. Beginning in 2011, data are for petroleum products and preparations.

<sup>c</sup> Petroleum, coal, natural gas, and electricity.

<sup>R</sup>=Revised.

Notes: • Monthly data are not adjusted for seasonal variations. • See Note 1, "Merchandise Trade Value," at end of section. • Totals may not equal sum of


components due to independent rounding. • The U.S. import statistics reflect both government and nongovernment imports of merchandise from foreign countries into the U.S. customs territory, which comprises the 50 states, the District of Columbia, Puerto Rico, and the Virgin Islands.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual and monthly data beginning in 1974.


Sources: See end of section.

**Figure 1.6 Cost of Fuels to End Users In Real (1982-1984) Dollars**


Costs, 1960–2020




Costs, November 2020




Residential Electricity, [a] Monthly



Motor Gasoline, [a] Monthly



Residential Natural Gas, [a] Monthly



[a] Includes Taxes.

[b] Excludes Taxes.

Note: See "Real Dollars" in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Tables 1.6.

**Table 1.6 Cost of Fuels to End Users in Real (1982–1984) Dollars**

	Consumer Price Index, All Urban Consumers <sup>a</sup>	Motor Gasoline <sup>b</sup>		Residential Heating Oil <sup>c</sup>		Residential Natural Gas <sup>b</sup>		Residential Electricity <sup>b</sup>	
	Index 1982–1984=100	Dollars per Gallon	Dollars per Million Btu	Dollars per Gallon	Dollars per Million Btu	Dollars per Thousand Cubic Feet	Dollars per Million Btu	Cents per Kilowatthour	Dollars per Million Btu
<b>1960 Average</b> .....	29.6	NA	NA	NA	NA	NA	NA	8.8	25.74
<b>1965 Average</b> .....	31.5	NA	NA	NA	NA	NA	NA	7.6	22.33
<b>1970 Average</b> .....	38.8	NA	NA	NA	NA	2.81	2.72	5.7	16.62
<b>1975 Average</b> .....	53.8	NA	NA	NA	NA	3.18	3.12	6.5	19.07
<b>1980 Average</b> .....	82.4	1.482	11.85	1.182	8.52	4.47	4.36	6.6	19.21
<b>1985 Average</b> .....	107.6	1.112	8.89	0.979	7.06	5.69	5.52	6.87	20.13
<b>1990 Average</b> .....	130.7	0.931	7.44	0.813	5.86	4.44	4.31	5.99	17.56
<b>1995 Average</b> .....	152.4	0.791	6.38	0.569	4.10	3.98	3.87	5.51	16.15
<b>2000 Average</b> .....	172.2	0.908	7.33	0.761	5.49	4.51	4.39	4.79	14.02
<b>2001 Average</b> .....	177.1	0.864	6.98	0.706	5.09	5.44	5.28	4.84	14.20
<b>2002 Average</b> .....	179.9	0.801	6.47	0.628	4.52	4.39	4.28	4.69	13.75
<b>2003 Average</b> .....	184.0	0.890	7.19	0.736	5.31	5.23	5.09	4.74	13.89
<b>2004 Average</b> .....	188.9	1.018	8.23	0.819	5.91	5.69	5.55	4.74	13.89
<b>2005 Average</b> .....	195.3	1.197	9.68	1.051	7.58	6.50	6.33	4.84	14.18
<b>2006 Average</b> .....	201.6	1.307	10.59	1.173	8.46	6.81	6.63	5.16	15.12
<b>2007 Average</b> .....	207.342	1.374	11.22	1.250	9.01	6.31	6.14	5.14	15.05
<b>2008 Average</b> .....	215.303	1.541	12.67	1.495	10.78	6.45	6.28	5.23	15.33
<b>2009 Average</b> .....	214.537	1.119	9.23	1.112	8.02	5.66	5.52	5.37	15.72
<b>2010 Average</b> .....	218.056	1.301	10.78	1.283	9.25	5.22	5.11	5.29	15.51
<b>2011 Average</b> .....	224.939	1.590	13.19	NA	NA	4.90	4.80	5.21	15.27
<b>2012 Average</b> .....	229.594	1.609	13.35	NA	NA	4.64	4.53	5.17	15.17
<b>2013 Average</b> .....	232.957	1.538	12.77	NA	NA	4.43	4.31	5.21	15.26
<b>2014 Average</b> .....	236.736	1.447	12.01	NA	NA	4.63	4.49	5.29	15.50
<b>2015 Average</b> .....	237.017	1.059	8.80	NA	NA	4.38	4.22	5.34	15.64
<b>2016 Average</b> .....	240.007	0.918	7.63	NA	NA	4.19	4.03	5.23	15.33
<b>2017 Average</b> .....	245.120	1.007	8.37	NA	NA	4.45	4.29	5.26	15.41
<b>2018 January</b> .....	247.867	1.047	8.70	NA	NA	3.59	3.46	4.93	14.45
February .....	248.991	1.057	8.78	NA	NA	3.87	3.73	5.07	14.87
March .....	249.554	1.054	8.76	NA	NA	3.91	3.77	5.20	15.23
April .....	250.546	1.116	9.27	NA	NA	4.01	3.86	5.14	15.07
May .....	251.588	1.178	9.79	NA	NA	5.37	5.18	5.21	15.28
June .....	251.989	1.179	9.79	NA	NA	6.54	6.30	5.17	15.15
July .....	252.006	1.163	9.66	NA	NA	7.08	6.82	5.21	15.27
August .....	252.146	1.158	9.62	NA	NA	7.36	7.09	5.26	15.41
September .....	252.439	1.161	9.65	NA	NA	6.83	6.58	5.15	15.10
October .....	252.885	1.165	9.68	NA	NA	4.83	4.66	5.08	14.89
November .....	252.038	1.084	9.01	NA	NA	3.74	3.60	5.12	15.00
December .....	251.233	0.987	8.20	NA	NA	3.83	3.69	4.95	14.50
<b>Average</b> .....	<b>251.107</b>	<b>1.113</b>	<b>9.25</b>	<b>NA</b>	<b>NA</b>	<b>4.18</b>	<b>4.03</b>	<b>5.13</b>	<b>15.02</b>
<b>2019 January</b> .....	251.712	0.934	7.77	NA	NA	3.72	3.58	4.95	14.52
February .....	252.776	0.954	7.93	NA	NA	3.72	3.58	5.03	14.75
March .....	254.202	1.031	8.57	NA	NA	3.71	3.56	5.05	14.80
April .....	255.548	1.132	9.41	NA	NA	4.25	4.08	5.18	15.20
May .....	256.092	1.157	9.62	NA	NA	4.98	4.79	5.20	15.23
June .....	256.143	1.099	9.13	NA	NA	6.07	5.84	5.20	15.24
July .....	256.571	1.105	9.19	NA	NA	6.91	6.65	5.17	15.15
August .....	256.558	1.059	8.80	NA	NA	7.16	6.89	5.18	15.19
September .....	256.759	1.049	8.72	NA	NA	6.86	6.59	5.13	15.02
October .....	257.346	1.065	8.85	NA	NA	4.86	4.67	4.98	14.59
November .....	257.208	1.045	8.68	NA	NA	3.63	3.49	5.07	14.85
December .....	256.974	1.032	8.58	NA	NA	3.62	3.48	4.93	14.46
<b>Average</b> .....	<b>255.657</b>	<b>1.055</b>	<b>8.77</b>	<b>NA</b>	<b>NA</b>	<b>4.11</b>	<b>3.95</b>	<b>5.09</b>	<b>14.91</b>
<b>2020 January</b> .....	257.971	1.020	8.48	NA	NA	3.69	3.54	4.96	14.53
February .....	258.678	0.978	8.13	NA	NA	3.53	3.39	4.97	14.56
March .....	258.115	0.904	7.52	NA	NA	3.82	3.67	5.07	14.86
April .....	256.389	0.759	6.31	NA	NA	4.16	4.00	5.18	15.18
May .....	256.394	0.759	6.31	NA	NA	4.62	4.44	5.13	15.03
June .....	257.797	0.830	6.90	NA	NA	5.96	5.73	5.15	15.10
July .....	259.101	0.866	7.20	NA	NA	6.78	6.52	5.12	15.00
August .....	259.918	0.864	7.18	NA	NA	7.08	6.81	5.12	15.01
September .....	260.280	0.868	7.22	NA	NA	6.53	6.28	5.21	15.26
October .....	260.388	0.856	7.11	NA	NA	4.74	4.56	5.22	15.31
November .....	260.229	0.830	6.90	NA	NA	R 4.25	R 4.09	R 5.13	R 15.04
December .....	260.474	0.858	7.13	NA	NA	NA	NA	NA	NA
<b>Average</b> .....	<b>258.811</b>	<b>0.866</b>	<b>7.20</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>
<b>2021 January</b> .....	261.582	0.914	7.60	NA	NA	NA	NA	NA	NA

<sup>a</sup> Data are U.S. city averages for all items, and are not seasonally adjusted.

<sup>b</sup> Includes taxes.

<sup>c</sup> Excludes taxes.

R=Revised. NA=Not available.


Notes: • See "Real Dollars" in Glossary. • Fuel costs are calculated by using the Urban Consumer Price Index (CPI) developed by the Bureau of Labor Statistics. • Annual averages may not equal average of months due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1960 and monthly data beginning in 1995.


Sources: • **Fuel Prices:** Tables 9.4 (All Grades), 9.8, and 9.10, adjusted by the CPI; and *Monthly Energy Review*, September 2012, Table 9.8c. • **Consumer Price Index, All Urban Consumers:** U.S. Department of Labor, Bureau of Labor Statistics, series ID CUUR0000SA0. • **Conversion Factors:** Tables A1, A3, A4, and A6.

**Figure 1.7 Primary Energy Consumption and Energy Expenditures Indicators**


Energy Consumption per Capita, 1949–2019



Primary Energy Consumption per Real Dollar [a] of Gross Domestic Product, 1949–2019



Energy Expenditures as Share of Gross Domestic Product and Gross Output,[b] 1970–2018



[a] See “Chained Dollars” and “Real Dollars” in Glossary.

[b] Gross output is the value of gross domestic product (GDP) plus the value of intermediate inputs used to produce GDP.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.7.

**Table 1.7 Primary Energy Consumption, Energy Expenditures, and Carbon Dioxide Emissions Indicators**

	Primary Energy Consumption <sup>a</sup>			Energy Expenditures <sup>b</sup>				Carbon Dioxide Emissions <sup>c</sup>		
	Consumption	Consumption per Capita	Consumption per Real Dollar <sup>d</sup> of GDP <sup>e</sup>	Expenditures	Expenditures per Capita	Expenditures as Share of GDP <sup>e</sup>	Expenditures as Share of Gross Output <sup>f</sup>	Emissions	Emissions per Capita	Emissions per Real Dollar <sup>d</sup> of GDP <sup>e</sup>
	Quadrillion Btu	Million Btu	Thousand Btu per Chained (2012) Dollar <sup>d</sup>	Million Nominal Dollars <sup>g</sup>	Nominal Dollars <sup>g</sup>	Percent	Percent	Million Metric Tons Carbon Dioxide	Metric Tons Carbon Dioxide	Metric Tons Carbon Dioxide per Million Chained (2012) Dollars <sup>d</sup>
1950 .....	34.599	227	15.11	NA	NA	NA	NA	2,382	15.6	1,040
1955 .....	40.178	242	13.99	NA	NA	NA	NA	2,685	16.2	935
1960 .....	45.041	249	13.82	NA	NA	NA	NA	2,914	16.1	894
1965 .....	53.953	278	12.94	NA	NA	NA	NA	3,462	17.8	830
1970 .....	67.817	331	13.70	82,875	404	7.7	4.4	4,261	20.8	861
1975 .....	71.931	333	12.74	171,854	796	10.2	5.6	4,426	20.5	784
1980 .....	78.021	343	11.54	374,350	1,647	13.1	6.9	4,750	20.9	703
1981 .....	76.057	331	10.97	427,901	1,865	13.3	7.1	4,627	20.2	668
1982 .....	73.046	315	10.73	426,482	1,841	12.8	6.9	4,394	19.0	646
1983 .....	72.915	312	10.24	417,622	1,786	11.5	6.3	4,371	18.7	614
1984 .....	76.571	325	10.03	435,313	1,846	10.8	6.0	4,596	19.5	602
1985 .....	76.334	321	9.60	438,343	1,842	10.1	5.6	4,587	19.3	577
1986 .....	76.599	319	9.31	384,091	1,599	8.4	4.8	4,598	19.1	559
1987 .....	79.008	326	9.28	397,627	1,641	8.2	4.6	4,756	19.6	559
1988 .....	82.659	338	9.32	411,568	1,683	7.9	4.4	4,981	20.4	562
1989 .....	84.740	343	9.22	439,051	1,779	7.8	4.4	5,068	20.5	551
1990 .....	84.433	338	9.02	474,652	1,901	8.0	4.5	5,040	20.2	538
1991 .....	84.380	334	9.02	472,440	1,867	7.7	4.4	4,995	19.7	534
1992 .....	85.725	334	8.85	476,845	1,859	7.3	4.2	5,095	19.9	526
1993 .....	87.266	336	8.77	492,275	1,894	7.2	4.1	5,186	20.0	521
1994 .....	88.983	338	8.60	504,856	1,919	6.9	3.9	5,264	20.0	508
1995 .....	90.931	341	8.55	514,624	1,933	6.7	3.8	5,323	20.0	501
1996 .....	93.935	349	8.52	560,293	2,080	6.9	3.9	5,512	20.5	500
1997 .....	94.507	347	8.20	567,962	2,083	6.6	3.7	5,583	20.5	485
1998 .....	94.920	344	7.88	526,283	1,908	5.8	3.2	5,631	20.4	468
1999 .....	96.545	346	7.66	558,627	2,002	5.8	3.2	5,693	20.4	451
2000 .....	98.702	350	7.52	687,711	2,437	6.7	3.7	5,867	20.8	447
2001 .....	96.064	337	7.24	696,242	2,443	6.6	3.7	5,765	20.2	435
2002 .....	97.535	339	7.23	663,964	2,308	6.1	3.5	5,809	20.2	431
2003 .....	97.835	337	7.05	755,070	2,603	6.6	3.7	5,860	20.2	422
2004 .....	100.002	342	6.94	871,210	2,975	7.1	4.0	5,979	20.4	415
2005 .....	100.102	339	6.71	1,045,730	3,539	8.0	4.4	5,999	20.3	402
2006 .....	99.392	333	6.48	1,158,821	3,884	8.4	4.6	5,914	19.8	386
2007 .....	100.893	335	6.46	1,233,869	4,096	8.5	4.7	6,003	19.9	384
2008 .....	98.754	325	6.33	1,408,759	4,633	9.6	5.2	5,817	19.1	373
2009 .....	93.942	306	6.18	1,066,293	3,476	7.4	4.3	5,392	17.6	355
2010 .....	97.513	315	6.25	1,214,045	3,925	8.1	4.6	5,585	18.1	358
2011 .....	96.863	311	6.11	1,391,711	4,467	9.0	5.0	5,446	17.5	344
2012 .....	94.374	301	5.83	1,355,033	<sup>R</sup> 4,317	8.4	4.6	5,229	16.7	323
2013 .....	97.117	307	5.89	1,376,142	<sup>R</sup> 4,354	8.2	4.5	5,356	16.9	325
2014 .....	98.276	309	5.81	1,394,926	<sup>R</sup> 4,381	8.0	4.4	5,413	17.0	320
2015 .....	97.375	304	5.59	1,128,068	<sup>R</sup> 3,517	6.2	3.5	5,263	16.4	302
2016 .....	<sup>R</sup> 97.338	301	5.49	1,038,272	<sup>R</sup> 3,214	5.5	3.2	5,171	16.0	292
2017 .....	<sup>R</sup> 97.599	300	5.38	1,136,189	<sup>R</sup> 3,495	5.8	3.3	5,131	15.8	283
2018 .....	<sup>R</sup> 101.169	310	5.41	1,271,064	<sup>R</sup> 3,889	6.2	3.5	5,284	16.2	283
2019 .....	<sup>R</sup> 100.289	305	5.25	NA	NA	NA	NA	5,146	15.7	270

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> Expenditures include taxes where data are available.

<sup>c</sup> Carbon dioxide emissions from energy consumption. See Table 11.1.

<sup>d</sup> See "Chained Dollars" and "Real Dollars" in Glossary.

<sup>e</sup> See "Gross Domestic Product (GDP)" in Glossary.

<sup>f</sup> Gross output is the value of GDP plus the value of intermediate inputs used to produce GDP. Through 1996, data have been adjusted by EIA based on DOC/BEA's 2012 comprehensive revision.

<sup>g</sup> See "Nominal Dollars" in Glossary.

<sup>R</sup>=Revised. NA=Not available.

Notes: • Data are estimates. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **Consumption:** Table 1.3. • **Consumption per Capita:**

Calculated as energy consumption divided by U.S. population (see Table C1).

• **Consumption per Real Dollar of GDP:** Calculated as energy consumption divided by U.S. gross domestic product in chained (2012) dollars (see Table C1).

• **Expenditures:** U.S. Energy Information Administration, "State Energy Price and Expenditure Estimates, 1970 Through 2018" (June 2020), U.S. Table ET.1.

• **Expenditures per Capita:** Calculated as energy expenditures divided by U.S. population (see Table C1).

• **Expenditures as Share of GDP:** Calculated as energy expenditures divided by U.S. gross domestic product in nominal dollars (see Table C1).


• **Expenditures as Share of Gross Output:** Calculated as energy expenditures divided by U.S. gross output (see Table C1).

• **Emissions:** 1949–1972—U.S. Energy Information Administration, *Annual Energy Review 2011*, Table 11.1. 1973 forward—Table 11.1.

• **Emissions per Capita:** Calculated as carbon dioxide emissions divided by U.S. population (see Table C1).

• **Emissions per Real Dollar of GDP:** Calculated as carbon dioxide emissions divided by U.S. gross domestic product in chained (2012) dollars (see Table C1).

**Figure 1.8 Motor Vehicle Mileage, Fuel Consumption, and Fuel Economy, 1949-2019**



[a] Through 1989, data are for passenger cars and motorcycles. For 1990–2006, data are for passenger cars only. Beginning in 2007, data are for light-duty vehicles (passenger cars, light trucks, vans, and sport utility vehicles) with a wheelbase less than or equal to 121 inches.

[b] For 1966–2000, data are for vans, pickup trucks, and sport utility vehicles. Beginning in 2007, data are for light-duty vehicles (passenger cars, light trucks, vans, and sport utility vehicles) with a wheelbase greater than 121 inches.

[c] For 1949–1965, data are for single-unit trucks with 2 axes and 6 or more

tires, combination trucks, and other vehicles with 2 axes and 4 tires that are not passenger cars. For 1966–2006 data are for single-unit truck with 2 axes and 6 or more tires, and combination trucks. Beginning in 2007, data are for single-unit trucks with 2 axes and 6 or more tires (or a gross vehicle weight rating exceeding 10,000 pounds), and combination trucks. Note: Through 1965, “Light-Duty Vehicles, Long Wheelbase” data are included in “Heavy-Duty Trucks.”

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.8.

**Table 1.8 Motor Vehicle Mileage, Fuel Consumption, and Fuel Economy**

	Light-Duty Vehicles, Short Wheelbase <sup>a</sup>			Light-Duty Vehicles, Long Wheelbase <sup>b</sup>			Heavy-Duty Trucks <sup>c</sup>			All Motor Vehicles <sup>d</sup>		
	Mileage	Fuel Consumption	Fuel Economy	Mileage	Fuel Consumption	Fuel Economy	Mileage	Fuel Consumption	Fuel Economy	Mileage	Fuel Consumption	Fuel Economy
	Miles per Vehicle	Gallons per Vehicle	Miles per Gallon	Miles per Vehicle	Gallons per Vehicle	Miles per Gallon	Miles per Vehicle	Gallons per Vehicle	Miles per Gallon	Miles per Vehicle	Gallons per Vehicle	Miles per Gallon
1950 .....	9,060	603	15.0	( <sup>e</sup> )	( <sup>e</sup> )	( <sup>e</sup> )	10,316	1,229	8.4	9,321	725	12.8
1955 .....	9,447	645	14.6	( <sup>e</sup> )	( <sup>e</sup> )	( <sup>e</sup> )	10,576	1,293	8.2	9,661	761	12.7
1960 .....	9,518	668	14.3	( <sup>e</sup> )	( <sup>e</sup> )	( <sup>e</sup> )	10,693	1,333	8.0	9,732	784	12.4
1965 .....	9,603	661	14.5	( <sup>e</sup> )	( <sup>e</sup> )	( <sup>e</sup> )	10,851	1,387	7.8	9,826	787	12.5
1970 .....	9,989	737	13.5	8,676	866	10.0	13,565	2,467	5.5	9,976	830	12.0
1975 .....	9,309	665	14.0	9,829	934	10.5	15,167	2,722	5.6	9,627	790	12.2
1980 .....	8,813	551	16.0	10,437	854	12.2	18,736	3,447	5.4	9,458	712	13.3
1981 .....	8,873	538	16.5	10,244	819	12.5	19,016	3,565	5.3	9,477	697	13.6
1982 .....	9,050	535	16.9	10,276	762	13.5	19,931	3,647	5.5	9,644	686	14.1
1983 .....	9,118	534	17.1	10,497	767	13.7	21,083	3,769	5.6	9,760	686	14.2
1984 .....	9,248	530	17.4	11,151	797	14.0	22,550	3,967	5.7	10,017	691	14.5
1985 .....	9,419	538	17.5	10,506	735	14.3	20,597	3,570	5.8	10,020	685	14.6
1986 .....	9,464	543	17.4	10,764	738	14.6	22,143	3,821	5.8	10,143	692	14.7
1987 .....	9,720	539	18.0	11,114	744	14.9	23,349	3,937	5.9	10,453	694	15.1
1988 .....	9,972	531	18.8	11,465	745	15.4	22,485	3,736	6.0	10,721	688	15.6
1989 .....	10,157	533	19.0	11,676	724	16.1	22,926	3,776	6.1	10,932	688	15.9
1990 .....	10,504	520	20.2	11,902	738	16.1	23,603	3,953	6.0	11,107	677	16.4
1991 .....	10,571	501	21.1	12,245	721	17.0	24,229	4,047	6.0	11,294	669	16.9
1992 .....	10,857	517	21.0	12,381	717	17.3	25,373	4,210	6.0	11,558	683	16.9
1993 .....	10,804	527	20.5	12,430	714	17.4	26,262	4,309	6.1	11,595	693	16.7
1994 .....	10,992	531	20.7	12,156	701	17.3	25,838	4,202	6.1	11,683	698	16.7
1995 .....	11,203	530	21.1	12,018	694	17.3	26,514	4,315	6.1	11,793	700	16.8
1996 .....	11,330	534	21.2	11,811	685	17.2	26,092	4,221	6.2	11,813	700	16.9
1997 .....	11,581	539	21.5	12,115	703	17.2	27,032	4,218	6.4	12,107	711	17.0
1998 .....	11,754	544	21.6	12,173	707	17.2	25,397	4,135	6.1	12,211	721	16.9
1999 .....	11,848	553	21.4	11,957	701	17.0	26,014	4,352	6.0	12,206	732	16.7
2000 .....	11,976	547	21.9	11,672	669	17.4	25,617	4,391	5.8	12,164	720	16.9
2001 .....	11,831	534	22.1	11,204	636	17.6	26,602	4,477	5.9	11,887	695	17.1
2002 .....	12,202	555	22.0	11,364	650	17.5	27,071	4,642	5.8	12,171	719	16.9
2003 .....	12,325	556	22.2	11,287	697	16.2	28,093	4,215	6.7	12,208	718	17.0
2004 .....	12,460	553	22.5	11,184	690	16.2	27,023	4,057	6.7	12,200	714	17.1
2005 .....	12,510	567	22.1	10,920	617	17.7	26,235	4,385	6.0	12,082	706	17.1
2006 .....	12,485	554	22.5	10,920	612	17.8	25,231	4,304	5.9	12,017	698	17.2
2007 .....	<sup>a</sup> 10,710	<sup>a</sup> 468	<sup>a</sup> 22.9	<sup>b</sup> 14,970	<sup>b</sup> 877	<sup>b</sup> 17.1	<sup>c</sup> 28,290	<sup>c</sup> 4,398	6.4	11,915	693	17.2
2008 .....	10,290	435	23.7	15,256	880	17.3	28,573	4,387	6.5	11,631	667	17.4
2009 .....	10,391	442	23.5	15,252	882	17.3	26,274	4,037	6.5	11,631	661	17.6
2010 .....	10,650	456	23.3	15,474	901	17.2	26,604	4,180	6.4	11,866	681	17.4
2011 .....	11,150	481	23.2	12,007	702	17.1	26,054	4,128	6.3	11,652	665	17.5
2012 .....	11,262	484	23.3	11,885	694	17.1	25,255	3,973	6.4	11,707	665	17.6
2013 .....	11,244	480	23.4	11,712	683	17.2	25,951	4,086	6.4	11,679	663	17.6
2014 .....	11,048	476	23.2	12,138	710	17.1	25,594	4,036	6.3	11,621	666	17.5
2015 .....	11,327	475	23.9	11,855	684	17.3	24,979	3,904	6.4	11,742	656	17.9
2016 .....	11,370	475	24.0	11,991	689	17.4	25,037	3,904	6.4	11,810	658	17.9
2017 .....	11,467	474	24.2	11,543	659	17.5	24,335	3,758	6.5	11,789	653	18.1
2018 .....	11,576	475	24.4	11,486	643	17.9	23,037	3,507	6.6	11,843	651	18.2
2019 .....	11,599	481	24.1	11,263	640	17.6	22,930	3,488	6.6	11,797	651	18.1

<sup>a</sup> Through 1989, data are for passenger cars and motorcycles. For 1990–2006, data are for passenger cars only. Beginning in 2007, data are for light-duty vehicles (passenger cars, light trucks, vans, and sport utility vehicles) with a wheelbase less than or equal to 121 inches.

<sup>b</sup> For 1966–2006, data are for vans, pickup trucks, and sport utility vehicles. Beginning in 2007, data are for light-duty vehicles (passenger cars, light trucks, vans, and sport utility vehicles) with a wheelbase greater than 121 inches.

<sup>c</sup> For 1949–1965, data are for single-unit trucks with 2 axles and 6 or more tires, combination trucks, and other vehicles with 2 axles and 4 tires that are not passenger cars. For 1966–2006, data are for single-unit trucks with 2 axles and 6 or more tires, and combination trucks. Beginning in 2007, data are for single-unit trucks with 2 axles and 6 or more tires (or a gross vehicle weight rating exceeding

10,000 pounds), and combination trucks.

<sup>d</sup> Includes buses and motorcycles, which are not separately displayed.

<sup>e</sup> Included in "Heavy-Duty Trucks."

Note: Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **Light-Duty Vehicles, Short Wheelbase: 1990–1994**—U.S. Department of Transportation, Bureau of Transportation Statistics, *National Transportation Statistics 1998*, Table 4-13. • **All Other Data: 1949–1994**—Federal Highway Administration (FHWA), *Highway Statistics Summary to 1995*, Table VM-201A. **1995 forward**—FHWA, *Highway Statistics*, annual reports, Table VM-1.

**Table 1.9 Heating Degree Days by Census Division**

	New England <sup>a</sup>	Middle Atlantic <sup>b</sup>	East North Central <sup>c</sup>	West North Central <sup>d</sup>	South Atlantic <sup>e</sup>	East South Central <sup>f</sup>	West South Central <sup>g</sup>	Mountain <sup>h</sup>	Pacific <sup>i</sup>	United States
<b>1950 Total</b> .....	6,794	6,324	7,027	7,455	3,521	3,547	2,277	6,341	3,906	5,367
<b>1955 Total</b> .....	6,872	6,231	6,486	6,912	3,508	3,513	2,294	6,704	4,320	5,246
<b>1960 Total</b> .....	6,828	6,391	6,908	7,184	3,780	4,134	2,767	6,281	3,799	5,404
<b>1965 Total</b> .....	7,029	6,393	6,587	6,932	3,372	3,501	2,237	6,086	3,819	5,146
<b>1970 Total</b> .....	7,022	6,388	6,721	7,090	3,452	3,823	2,558	6,119	3,726	5,218
<b>1975 Total</b> .....	6,547	5,892	6,406	6,880	2,970	3,437	2,312	6,260	4,117	4,905
<b>1980 Total</b> .....	7,071	6,477	6,975	6,836	3,378	3,964	2,494	5,554	3,539	5,080
<b>1985 Total</b> .....	6,749	5,971	6,668	7,262	2,899	3,660	2,535	6,059	3,935	4,889
<b>1990 Total</b> .....	5,987	5,252	5,780	6,137	2,307	2,942	1,968	5,391	3,603	4,180
<b>1995 Total</b> .....	6,684	6,093	6,740	6,911	2,988	3,648	2,147	5,101	3,269	4,640
<b>2000 Total</b> .....	6,625	5,999	6,315	6,500	2,905	3,551	2,153	4,971	3,460	4,494
<b>2001 Total</b> .....	6,202	5,541	5,844	6,221	2,604	3,327	2,162	5,004	3,545	4,257
<b>2002 Total</b> .....	6,234	5,550	6,128	6,485	2,664	3,443	2,292	5,197	3,510	4,356
<b>2003 Total</b> .....	6,975	6,258	6,536	6,593	2,884	3,559	2,205	4,817	3,355	4,544
<b>2004 Total</b> .....	6,709	5,892	6,178	6,329	2,715	3,291	2,041	5,010	3,346	4,344
<b>2005 Total</b> .....	6,644	5,950	6,222	6,213	2,775	3,380	1,985	4,896	3,377	4,348
<b>2006 Total</b> .....	5,885	5,211	5,703	5,821	2,475	3,211	1,802	4,915	3,557	4,040
<b>2007 Total</b> .....	6,537	5,756	6,074	6,384	2,525	3,187	2,105	4,939	3,506	4,268
<b>2008 Total</b> .....	6,434	5,782	6,677	7,118	2,712	3,600	2,125	5,233	3,566	4,494
<b>2009 Total</b> .....	6,644	5,922	6,512	6,841	2,812	3,536	2,152	5,139	3,538	4,481
<b>2010 Total</b> .....	5,934	5,553	6,185	6,565	3,167	3,948	2,449	5,082	3,624	4,463
<b>2011 Total</b> .....	6,114	5,483	6,172	6,565	2,565	3,343	2,114	5,322	3,818	4,312
<b>2012 Total</b> .....	5,561	4,970	5,356	5,515	2,306	2,876	1,650	4,574	3,411	3,769
<b>2013 Total</b> .....	6,426	5,838	6,621	7,135	2,736	3,648	2,326	5,273	3,362	4,465
<b>2014 Total</b> .....	6,675	6,203	7,194	7,304	2,951	3,932	2,422	4,744	2,774	4,550
<b>2015 Total</b> .....	6,521	5,777	6,165	6,088	2,487	3,222	2,087	4,602	2,898	4,087
<b>2016 Total</b> .....	5,929	5,353	5,701	5,786	2,456	3,094	1,752	4,619	3,031	3,878
<b>2017 Total</b> .....	6,038	5,333	5,684	5,997	2,232	2,835	1,582	4,568	3,187	3,828
<b>2018 January</b> .....	1,257	1,216	1,308	1,373	700	929	660	<sup>R</sup> 771	458	896
<b>February</b> .....	869	813	980	1,178	307	410	348	<sup>R</sup> 748	496	625
<b>March</b> .....	926	913	922	869	435	474	186	604	487	609
<b>April</b> .....	674	618	703	716	205	312	142	380	299	410
<b>May</b> .....	168	108	99	89	13	0	0	163	176	85
<b>June</b> .....	61	29	24	23	1	0	0	56	65	26
<b>July</b> .....	2	1	4	11	0	0	0	9	8	4
<b>August</b> .....	3	2	8	20	0	0	0	25	14	7
<b>September</b> .....	65	34	48	90	2	3	3	89	62	38
<b>October</b> .....	457	355	420	494	99	138	70	384	187	254
<b>November</b> .....	818	766	913	1,003	380	566	372	678	354	594
<b>December</b> .....	1,026	929	1,003	1,103	488	634	472	897	564	732
<b>Total</b> .....	<b>6,326</b>	<b>5,784</b>	<b>6,433</b>	<b>6,968</b>	<sup>R</sup> <b>2,628</b>	<b>3,478</b>	<b>2,252</b>	<b>4,803</b>	<sup>R</sup> <b>3,170</b>	<b>4,279</b>
<b>2019 January</b> .....	<sup>R</sup> 1,221	<sup>R</sup> 1,153	1,303	1,359	<sup>R</sup> 582	748	545	893	542	859
<b>February</b> .....	1,030	<sup>R</sup> 942	1,062	1,284	377	459	<sup>R</sup> 357	866	<sup>R</sup> 656	719
<b>March</b> .....	976	<sup>R</sup> 890	961	1,002	<sup>R</sup> 375	505	<sup>R</sup> 305	667	<sup>R</sup> 491	632
<b>April</b> .....	<sup>R</sup> 527	<sup>R</sup> 413	475	454	<sup>R</sup> 109	166	78	<sup>R</sup> 374	275	288
<b>May</b> .....	313	188	236	272	16	24	11	314	<sup>R</sup> 241	158
<b>June</b> .....	<sup>R</sup> 55	32	49	<sup>R</sup> 45	2	3	0	97	60	34
<b>July</b> .....	2	1	8	0	0	0	0	15	20	5
<b>August</b> .....	16	10	20	<sup>R</sup> 32	0	0	0	17	12	10
<b>September</b> .....	<sup>R</sup> 118	58	<sup>R</sup> 43	67	2	1	0	95	<sup>R</sup> 64	41
<b>October</b> .....	<sup>R</sup> 389	<sup>R</sup> 303	390	526	<sup>R</sup> 78	128	84	<sup>R</sup> 477	<sup>R</sup> 239	<sup>R</sup> 254
<b>November</b> .....	<sup>R</sup> 831	<sup>R</sup> 790	<sup>R</sup> 913	924	392	<sup>R</sup> 573	<sup>R</sup> 346	<sup>R</sup> 617	<sup>R</sup> 372	589
<b>December</b> .....	<sup>R</sup> 1,061	<sup>R</sup> 972	<sup>R</sup> 975	<sup>R</sup> 1,098	<sup>R</sup> 449	573	<sup>R</sup> 418	<sup>R</sup> 870	<sup>R</sup> 576	715
<b>Total</b> .....	<sup>R</sup> <b>6,539</b>	<sup>R</sup> <b>5,752</b>	<b>6,427</b>	<sup>R</sup> <b>7,074</b>	<sup>R</sup> <b>2,383</b>	<sup>R</sup> <b>3,181</b>	<b>2,146</b>	<sup>R</sup> <b>5,301</b>	<sup>R</sup> <b>3,548</b>	<sup>R</sup> <b>4,305</b>
<b>2020 January</b> .....	<sup>R</sup> 1,033	958	1,052	1,224	481	<sup>R</sup> 635	<sup>R</sup> 430	850	<sup>R</sup> 565	<sup>R</sup> 740
<b>February</b> .....	<sup>R</sup> 926	842	<sup>R</sup> 1,001	<sup>R</sup> 1,069	396	<sup>R</sup> 555	401	<sup>R</sup> 763	<sup>R</sup> 448	652
<b>March</b> .....	<sup>R</sup> 778	<sup>R</sup> 671	734	744	231	<sup>R</sup> 292	<sup>R</sup> 140	<sup>R</sup> 600	527	484
<b>April</b> .....	654	<sup>R</sup> 567	567	<sup>R</sup> 532	<sup>R</sup> 176	248	89	<sup>R</sup> 412	<sup>R</sup> 309	<sup>R</sup> 358
<b>May</b> .....	288	252	257	<sup>R</sup> 245	74	<sup>R</sup> 86	13	186	<sup>R</sup> 147	156
<b>June</b> .....	28	<sup>R</sup> 18	23	21	2	3	0	<sup>R</sup> 73	69	25
<b>July</b> .....	1	0	1	6	0	0	0	14	19	5
<b>August</b> .....	10	<sup>R</sup> 5	13	18	0	0	0	9	<sup>R</sup> 16	7
<b>September</b> .....	103	82	<sup>R</sup> 112	<sup>R</sup> 144	17	20	8	<sup>R</sup> 103	30	58
<b>October</b> .....	<sup>R</sup> 395	<sup>R</sup> 339	465	<sup>R</sup> 554	<sup>R</sup> 96	<sup>R</sup> 156	83	<sup>R</sup> 324	<sup>R</sup> 132	247
<b>November</b> .....	611	550	600	661	225	344	176	564	412	422
<b>11-Month Total</b> ...	<b>4,828</b>	<b>4,284</b>	<b>4,826</b>	<b>5,217</b>	<b>1,698</b>	<b>2,337</b>	<b>1,338</b>	<b>3,900</b>	<b>2,675</b>	<b>3,155</b>
<b>2019 11-Month Total</b> ...	<b>5,479</b>	<b>4,780</b>	<b>5,452</b>	<b>5,976</b>	<b>1,933</b>	<b>2,608</b>	<b>1,727</b>	<b>4,431</b>	<b>2,973</b>	<b>3,590</b>
<b>2018 11-Month Total</b> ...	<b>5,300</b>	<b>4,855</b>	<b>5,430</b>	<b>5,865</b>	<b>2,140</b>	<b>2,845</b>	<b>1,781</b>	<b>3,906</b>	<b>2,606</b>	<b>3,547</b>

<sup>a</sup> Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, and Vermont.

<sup>b</sup> New Jersey, New York, and Pennsylvania.

<sup>c</sup> Illinois, Indiana, Michigan, Ohio, and Wisconsin.

<sup>d</sup> Iowa, Kansas, Minnesota, Missouri, Nebraska, North Dakota, and South Dakota.

<sup>e</sup> Delaware, Florida, Georgia, Maryland (and the District of Columbia), North Carolina, South Carolina, Virginia, and West Virginia.

<sup>f</sup> Alabama, Kentucky, Mississippi, and Tennessee.

<sup>g</sup> Arkansas, Louisiana, Oklahoma, and Texas.

<sup>h</sup> Arizona, Colorado, Idaho, Montana, Nevada, New Mexico, Utah, and Wyoming.

<sup>i</sup> Alaska, California, Hawaii, Oregon, and Washington.

R=Revised.

Notes: • Degree days are relative measurements of outdoor air temperature used as an index for heating and cooling energy requirements. Heating degree days are the number of degrees that the daily average temperature falls below 65 degrees Fahrenheit (°F). Cooling degree days are the number of degrees that the

daily average temperature rises above 65°F. The daily average temperature is the mean of the maximum and minimum temperatures in a 24-hour period. For example, a weather station recording an average daily temperature of 40°F would report 25 heating degree days for that day (and 0 cooling degree days). If a weather station recorded an average daily temperature of 78°F, cooling degree days for that station would be 13 (and 0 heating degree days). • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: State-level degree day data are from U.S. Department of Commerce, National Oceanic and Atmospheric Administration, National Centers for Environmental Information. Using these state-level data, the U.S. Energy Information Administration calculates population-weighted census-division and U.S. degree day averages using state populations from the same year the degree days are measured. See methodology at [http://www.eia.gov/forecasts/steo/special/pdf/2012\\_sp\\_04.pdf](http://www.eia.gov/forecasts/steo/special/pdf/2012_sp_04.pdf).



**Table 1.10 Cooling Degree Days by Census Division**

	New England <sup>a</sup>	Middle Atlantic <sup>b</sup>	East North Central <sup>c</sup>	West North Central <sup>d</sup>	South Atlantic <sup>e</sup>	East South Central <sup>f</sup>	West South Central <sup>g</sup>	Mountain <sup>h</sup>	Pacific <sup>i</sup>	United States
<b>1950 Total</b> .....	295	401	505	647	1,414	1,420	2,282	682	629	871
<b>1955 Total</b> .....	532	761	922	1,139	1,636	1,674	2,508	780	558	1,144
<b>1960 Total</b> .....	318	487	626	871	1,583	1,532	2,367	974	796	1,000
<b>1965 Total</b> .....	310	498	618	832	1,613	1,552	2,461	780	577	979
<b>1970 Total</b> .....	423	615	747	980	1,744	1,571	2,282	971	734	1,079
<b>1975 Total</b> .....	422	584	721	937	1,791	1,440	2,162	903	597	1,049
<b>1980 Total</b> .....	438	680	769	1,158	1,911	1,754	2,651	1,071	653	1,214
<b>1985 Total</b> .....	324	509	602	780	1,878	1,522	2,519	1,095	761	1,121
<b>1990 Total</b> .....	429	562	602	913	2,054	1,563	2,526	1,212	838	1,200
<b>1995 Total</b> .....	471	704	877	928	2,028	1,613	2,398	1,213	794	1,261
<b>2000 Total</b> .....	279	458	632	983	1,925	1,674	2,775	1,480	772	1,232
<b>2001 Total</b> .....	464	623	722	994	1,897	1,478	2,543	1,508	861	1,255
<b>2002 Total</b> .....	508	772	899	1,045	2,182	1,757	2,515	1,467	783	1,363
<b>2003 Total</b> .....	475	615	619	907	1,980	1,452	2,496	1,553	978	1,268
<b>2004 Total</b> .....	368	591	585	722	2,038	1,517	2,482	1,290	828	1,217
<b>2005 Total</b> .....	598	892	944	1,063	2,098	1,676	2,647	1,372	777	1,388
<b>2006 Total</b> .....	485	693	734	1,034	2,053	1,648	2,786	1,466	922	1,360
<b>2007 Total</b> .....	447	694	881	1,102	2,219	1,892	2,475	1,564	828	1,392
<b>2008 Total</b> .....	462	667	883	818	1,993	1,537	2,501	1,385	918	1,282
<b>2009 Total</b> .....	350	524	534	698	2,029	1,479	2,590	1,393	894	1,241
<b>2010 Total</b> .....	635	908	964	1,096	2,269	1,977	2,757	1,358	674	1,456
<b>2011 Total</b> .....	554	836	859	1,074	2,259	1,727	3,112	1,450	736	1,470
<b>2012 Total</b> .....	565	815	974	1,221	2,162	1,762	2,915	1,573	917	1,495
<b>2013 Total</b> .....	540	683	690	892	2,000	1,441	2,536	1,462	892	1,306
<b>2014 Total</b> .....	420	596	610	814	2,009	1,493	2,474	1,431	1,068	1,299
<b>2015 Total</b> .....	555	804	729	942	2,405	1,718	2,741	1,478	1,068	1,488
<b>2016 Total</b> .....	626	888	958	1,073	2,412	1,957	2,882	1,497	928	1,559
<b>2017 Total</b> .....	450	661	709	911	2,254	1,585	2,718	1,548	1,053	1,428
<b>2018 January</b> .....	0	0	0	0	21	1	4	4	15	8
<b>February</b> .....	0	0	0	0	81	22	33	3	8	23
<b>March</b> .....	0	0	0	2	35	15	87	14	9	21
<b>April</b> .....	0	0	0	0	79	7	58	70	25	33
<b>May</b> .....	25	65	140	168	265	268	395	137	39	174
<b>June</b> .....	57	111	192	272	385	376	550	299	117	270
<b>July</b> .....	254	287	257	304	441	430	607	415	320	376
<b>August</b> .....	266	297	257	258	439	392	565	344	257	351
<b>September</b> .....	64	121	122	124	391	338	392	238	142	231
<b>October</b> .....	0	4	4	6	176	77	142	45	46	70
<b>November</b> .....	0	0	0	0	66	1	13	5	16	18
<b>December</b> .....	0	0	0	0	40	2	9	0	9	11
<b>Total</b> .....	667	885	972	1,134	2,418	1,928	2,856	1,573	1,002	1,585
<b>2019 January</b> .....	0	0	0	0	29	5	12	0	8	9
<b>February</b> .....	0	0	0	0	67	14	24	0	5	18
<b>March</b> .....	0	0	0	0	56	10	36	10	8	18
<b>April</b> .....	0	0	1	6	101	31	91	51	26	42
<b>May</b> .....	3	31	R 47	42	293	R 220	R 291	57	24	R 130
<b>June</b> .....	R 63	112	127	175	R 361	R 300	439	233	116	227
<b>July</b> .....	R 274	325	320	320	R 481	R 428	R 549	395	R 209	373
<b>August</b> .....	R 166	218	195	R 224	441	408	625	R 386	R 246	R 336
<b>September</b> .....	R 28	R 88	R 135	183	375	382	523	207	R 131	243
<b>October</b> .....	0	8	7	2	204	R 80	139	49	R 40	R 75
<b>November</b> .....	0	0	0	0	53	1	16	R 11	16	16
<b>December</b> .....	0	0	0	0	R 51	5	R 13	0	10	14
<b>Total</b> .....	R 535	R 783	R 831	952	R 2,513	R 1,886	R 2,758	R 1,399	R 840	R 1,502
<b>2020 January</b> .....	0	0	0	0	47	13	R 29	0	9	15
<b>February</b> .....	0	0	0	0	46	4	14	2	8	13
<b>March</b> .....	0	0	2	6	103	R 56	R 131	R 8	8	43
<b>April</b> .....	0	0	0	1	109	20	105	R 43	R 19	43
<b>May</b> .....	3	11	31	37	R 167	R 106	278	158	R 66	106
<b>June</b> .....	100	R 145	185	R 257	344	R 298	457	R 264	112	R 248
<b>July</b> .....	R 294	362	R 335	R 345	503	462	R 601	R 414	R 212	R 398
<b>August</b> .....	216	259	218	R 247	R 456	R 389	R 577	R 439	R 292	R 356
<b>September</b> .....	35	58	R 54	72	R 274	210	R 324	R 228	R 212	181
<b>October</b> .....	0	5	2	3	R 186	R 67	R 134	R 99	R 101	R 83
<b>November</b> .....	0	0	0	0	95	13	70	14	15	32
<b>11-Month Total</b> ...	648	840	828	968	2,330	1,637	2,718	1,670	1,054	1,517
<b>2019 11-Month Total</b> ...	535	783	831	952	2,462	1,880	2,745	1,399	830	1,488
<b>2018 11-Month Total</b> ...	667	885	972	1,134	2,378	1,926	2,847	1,573	993	1,574

<sup>a</sup> Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, and Vermont.

<sup>b</sup> New Jersey, New York, and Pennsylvania.

<sup>c</sup> Illinois, Indiana, Michigan, Ohio, and Wisconsin.

<sup>d</sup> Iowa, Kansas, Minnesota, Missouri, Nebraska, North Dakota, and South Dakota.

<sup>e</sup> Delaware, Florida, Georgia, Maryland (and the District of Columbia), North Carolina, South Carolina, Virginia, and West Virginia.

<sup>f</sup> Alabama, Kentucky, Mississippi, and Tennessee.

<sup>g</sup> Arkansas, Louisiana, Oklahoma, and Texas.

<sup>h</sup> Arizona, Colorado, Idaho, Montana, Nevada, New Mexico, Utah, and Wyoming.

<sup>i</sup> Alaska, California, Hawaii, Oregon, and Washington.

R=Revised.

Notes: • Degree days are relative measurements of outdoor air temperature used as an index for heating and cooling energy requirements. Cooling degree days are the number of degrees that the daily average temperature rises above 65 degrees Fahrenheit (°F). Heating degree days are the number of degrees that the

daily average temperature falls below 65°F. The daily average temperature is the mean of the maximum and minimum temperatures in a 24-hour period. For example, if a weather station recorded an average daily temperature of 78°F, cooling degree days for that station would be 13 (and 0 heating degree days). A weather station recording an average daily temperature of 40°F would report 25 heating degree days for that day (and 0 cooling degree days).

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: State-level degree day data are from U.S. Department of Commerce, National Oceanic and Atmospheric Administration, National Centers for Environmental Information. Using these state-level data, the U.S. Energy Information Administration calculates population-weighted census-division and U.S. degree day averages using state populations from the same year the degree days are measured. See methodology at [http://www.eia.gov/forecasts/steo/special/pdf/2012\\_sp\\_04.pdf](http://www.eia.gov/forecasts/steo/special/pdf/2012_sp_04.pdf).

Table 1.11a Non-Combustion Use of Fossil Fuels in Physical Units

			Petroleum								Total
	Coal	Natural Gas	Asphalt and Road Oil	Hydrocarbon Gas Liquids <sup>a</sup>	Lubricants	Petro-chemical Feedstocks <sup>b</sup>	Petroleum Coke	Special Naphthas	Other <sup>c</sup>		
	Thousand Short Tons	Billion Cubic Feet	Thousand Barrels per Day								
1973 Total .....	3,523	898	522	684	162	356	56	88	88	1,956	
1975 Total .....	3,105	761	419	654	137	320	54	75	122	1,781	
1980 Total .....	2,612	759	396	890	159	692	52	100	143	2,433	
1985 Total .....	1,536	642	425	982	145	395	58	83	95	2,184	
1990 Total .....	758	675	483	1,071	164	546	72	56	85	2,477	
1995 Total .....	921	868	486	1,357	156	590	62	37	70	2,758	
1996 Total .....	884	896	484	1,413	151	592	65	39	70	2,813	
1997 Total .....	842	909	505	1,447	160	686	62	38	72	2,970	
1998 Total .....	656	938	521	1,441	168	690	97	56	83	3,056	
1999 Total .....	654	906	547	1,578	169	651	106	76	77	3,204	
2000 Total .....	674	918	525	1,543	166	662	90	51	78	3,115	
2001 Total .....	607	839	519	1,386	153	586	97	41	83	2,864	
2002 Total .....	937	836	512	1,474	151	628	86	53	85	2,989	
2003 Total .....	961	808	503	1,397	140	676	84	42	80	2,923	
2004 Total .....	938	818	537	1,458	141	784	95	27	74	3,117	
2005 Total .....	929	761	546	1,369	141	729	91	33	75	2,983	
2006 Total .....	562	573	521	1,424	137	726	126	37	86	3,057	
2007 Total .....	556	587	494	1,444	142	664	123	41	82	2,989	
2008 Total .....	541	597	417	1,279	131	574	117	44	85	2,648	
2009 Total .....	375	513	360	1,401	118	507	108	24	85	2,604	
2010 Total .....	719	654	362	1,597	131	539	36	14	89	2,767	
2011 Total .....	730	680	355	1,639	125	520	34	12	91	2,775	
2012 Total .....	707	706	340	1,747	114	444	37	8	88	2,778	
2013 Total .....	732	721	323	1,870	121	448	34	52	93	2,943	
2014 Total .....	562	725	327	1,780	126	410	10	55	97	2,807	
2015 Total .....	520	703	343	1,918	138	378	10	52	99	2,938	
2016 Total .....	435	727	351	1,943	130	371	10	49	100	2,955	
2017 Total .....	463	746	351	2,023	121	394	9	52	103	3,053	
2018 January .....	39	74	158	2,384	105	351	10	56	101	3,165	
February .....	34	66	203	2,184	135	352	5	52	101	3,032	
March .....	39	70	278	2,236	132	377	9	53	99	3,185	
April .....	41	66	225	2,166	122	400	9	57	105	3,084	
May .....	42	63	385	2,152	103	383	10	54	105	3,192	
June .....	39	60	476	2,221	131	401	10	45	106	3,390	
July .....	42	61	460	2,404	128	414	9	49	105	3,569	
August .....	42	61	507	2,450	134	432	13	39	105	3,681	
September .....	42	60	385	2,398	99	407	12	45	104	3,450	
October .....	41	63	410	2,334	107	427	13	48	95	3,435	
November .....	41	69	247	2,403	118	376	8	37	106	3,295	
December .....	43	72	182	2,362	91	389	8	41	106	3,179	
Total .....	484	785	327	2,309	117	393	10	48	103	3,307	
2019 January .....	40	76	195	2,562	114	354	8	39	103	3,376	
February .....	37	68	201	2,522	105	344	3	48	94	3,316	
March .....	41	71	232	2,257	97	323	9	42	93	3,054	
April .....	38	63	318	R 2,276	156	357	7	55	91	R 3,261	
May .....	43	63	369	2,231	107	345	10	48	89	3,200	
June .....	42	58	413	2,288	104	355	13	51	90	3,315	
July .....	40	59	510	2,451	129	348	12	63	98	3,612	
August .....	39	61	507	2,380	115	386	10	51	97	R 3,545	
September .....	39	59	480	2,505	96	365	8	51	91	3,596	
October .....	39	63	438	2,480	130	285	8	53	89	R 3,483	
November .....	37	69	310	2,482	105	338	11	49	92	3,388	
December .....	40	73	198	2,494	94	387	12	47	97	3,328	
Total .....	474	784	348	2,410	113	349	9	50	94	3,373	
2020 January .....	38	74	191	2,457	123	367	7	46	101	3,294	
February .....	38	69	191	2,317	108	292	8	52	97	3,064	
March .....	37	67	204	2,507	62	325	7	47	95	3,247	
April .....	31	60	292	R 2,257	82	315	5	55	86	R 3,092	
May .....	28	57	365	2,373	83	299	6	38	79	3,244	
June .....	32	55	511	2,350	104	291	6	47	83	3,392	
July .....	27	58	491	2,599	116	306	7	42	93	3,652	
August .....	29	60	479	2,424	94	319	11	41	81	3,448	
September .....	28	60	422	2,379	103	303	9	40	84	R 3,340	
October .....	35	65	401	2,645	110	310	7	52	83	3,608	
November .....	22	67	318	2,858	111	312	10	41	82	3,732	
11-Month Total ...	344	693	352	2,471	100	313	8	45	87	3,376	
2019 11-Month Total ...	435	711	362	2,402	114	345	9	50	93	3,377	
2018 11-Month Total ...	441	713	341	2,304	119	393	10	49	103	3,319	

<sup>a</sup> Ethane, propane, normal butane, isobutane, natural gasoline, and refinery olefins (ethylene, propylene, butylene, and isobutylene).

<sup>b</sup> Includes still gas not burned as refinery fuel.

<sup>c</sup> Distillate fuel oil, residual fuel oil, waxes, and miscellaneous products.

R=Revised.

Notes: • Data are estimates. • Non-combustion use estimates are included in total energy consumption. See Table 1.3. • Non-combustion estimates are all for industrial sector consumption, except for some lubricants consumed by the

transportation sector. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia. • See Note 2, "Non-Combustion Use of Fossil Fuels," at end of section.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all available annual and monthly data beginning in 1973.

Sources: • See Note 2, "Non-Combustion Use of Fossil Fuels," at end of section.

**Table 1.11b Heat Content of Non-Combustion Use of Fossil Fuels**  
(Quadrillion Btu)

	Coal	Natural Gas	Petroleum								Total	Percent of Total Energy Consumption
			Asphalt and Road Oil	Hydro-carbon Gas Liquids <sup>a</sup>	Lubri-cants	Petro-chemical Feed-stocks <sup>b</sup>	Petro-leum Coke	Special Naphthas	Other <sup>c</sup>	Total		
1973 Total	0.113	0.916	1.264	0.872	0.359	0.726	0.117	0.169	0.185	3.691	4.720	6.2
1975 Total	.099	.777	1.014	.822	.304	.652	.113	.144	.256	3.306	4.182	5.8
1980 Total	.084	.777	.962	1.128	.354	1.426	.108	.193	.303	4.473	5.334	6.8
1985 Total	.049	.662	1.029	1.194	.322	.817	.120	.159	.201	3.843	4.554	6.0
1990 Total	.024	.695	1.170	1.345	.362	1.123	.150	.107	.179	4.437	5.156	6.1
1995 Total	.029	.892	1.178	1.716	.346	1.214	.129	.071	.145	4.799	5.720	6.3
1996 Total	.028	.921	1.176	1.779	.335	1.209	.136	.075	.146	4.855	5.804	6.2
1997 Total	.027	.933	1.224	1.821	.354	1.400	.130	.072	.150	5.151	6.111	6.5
1998 Total	.021	.969	1.263	1.819	.371	1.403	.203	.107	.174	5.339	6.329	6.7
1999 Total	.021	.932	1.324	1.989	.375	1.329	.221	.145	.161	5.545	6.498	6.7
2000 Total	.022	.942	1.276	1.928	.369	1.344	.188	.097	.164	5.367	6.330	6.4
2001 Total	.019	.863	1.257	1.725	.338	1.192	.203	.078	.174	4.968	5.850	6.1
2002 Total	.030	.856	1.240	1.831	.334	1.272	.180	.102	.178	5.138	6.025	6.2
2003 Total	.031	.832	1.220	1.748	.309	1.371	.176	.080	.169	5.074	5.936	6.1
2004 Total	.030	.840	1.304	1.820	.313	1.592	.199	.051	.156	5.436	6.305	6.3
2005 Total	.030	.782	1.323	1.701	.312	1.474	.190	.063	.157	5.220	6.031	6.0
2006 Total	.018	.589	1.261	1.754	.303	1.477	.264	.070	.180	5.310	5.917	6.0
2007 Total	.018	.603	1.197	1.768	.313	1.351	.256	.078	.173	5.136	5.757	5.7
2008 Total	.017	.613	1.012	1.564	.291	1.172	.245	.085	.180	4.550	5.180	5.2
2009 Total	.012	.526	.873	1.676	.262	1.031	.226	.046	.179	4.293	4.831	5.1
2010 Total	.023	.669	.878	1.931	.291	1.096	.074	.026	.188	4.483	5.175	5.3
2011 Total	.023	.695	.859	1.947	.276	1.057	.070	.023	.193	4.425	5.144	5.3
2012 Total	.023	.724	.827	2.109	.254	.901	.077	.015	.187	4.369	5.115	5.4
2013 Total	.023	.741	.783	2.270	.268	.901	.070	.100	.197	4.589	5.354	5.5
2014 Total	.018	.749	.793	2.125	.280	.827	.021	.106	.205	4.358	5.125	5.2
2015 Total	.017	.730	.832	2.317	.305	.760	.022	.099	.208	4.542	5.289	5.4
2016 Total	.014	.755	.853	2.330	.289	.754	.021	.094	.212	4.553	5.323	5.5
2017 Total	.015	.774	.849	2.393	.267	.797	.020	.100	.217	4.643	5.432	5.6
2018 January	.001	.076	.032	.238	.020	.060	.002	.009	.018	.380	.457	4.7
February	.001	.069	.038	.199	.023	.054	.001	.008	.016	.339	.408	5.1
March	.001	.073	.057	.218	.025	.065	.002	.009	.018	.393	.466	5.4
April	.001	.068	.045	.204	.022	.067	.002	.009	.018	.366	.436	5.5
May	.001	.065	.079	.213	.019	.066	.002	.009	.019	.407	.473	5.9
June	.001	.062	.095	.213	.024	.067	.002	.007	.018	.426	.489	6.0
July	.001	.063	.095	.240	.024	.071	.002	.008	.019	.458	.523	6.1
August	.001	.063	.104	.246	.025	.074	.002	.006	.019	.477	.542	6.2
September	.001	.063	.077	.233	.018	.067	.002	.007	.018	.422	.486	6.2
October	.001	.066	.084	.235	.020	.073	.002	.008	.017	.440	.507	6.3
November	.001	.071	.049	.233	.021	.062	.001	.006	.018	.392	.465	5.5
December	.001	.075	.037	.236	.017	.067	.001	.007	.019	.385	.461	5.1
Total	.015	.815	.793	2.708	.259	.794	.020	.092	.218	4.884	5.714	5.6
2019 January	.001	.079	.040	.257	.021	.061	.002	.006	.019	.405	.485	5.1
February	.001	.071	.037	.226	.018	.053	(s)	.007	.015	.357	.429	5.1
March	.001	.074	.048	.221	.018	.055	.002	.007	.017	.368	.443	5.1
April	.001	.066	.063	.215	.028	.059	.001	.009	.016	.392	.459	6.0
May	.001	.065	.076	.221	.020	.059	.002	.008	.016	.402	.468	5.9
June	.001	.061	.082	.224	.019	.059	.002	.008	.016	.410	.472	6.0
July	.001	.061	.105	.249	.024	.060	.002	.010	.018	.468	.531	6.2
August	.001	.064	.104	.242	.022	.066	.002	.008	.017	.461	.526	6.2
September	.001	.061	.096	.246	.018	.060	.001	.008	.016	.445	.507	6.5
October	.001	.066	.090	.252	.025	.049	.001	.009	.016	.442	.510	6.4
November	.001	.072	.062	.240	.019	.056	.002	.008	.016	.402	.475	5.7
December	.001	.076	.041	.248	.018	.066	.002	.008	.017	.399	.476	5.3
Total	.015	.815	.844	2.841	.250	.704	.019	.096	.198	4.951	5.781	5.8
2020 January	.001	.077	.039	.239	.023	.063	.001	.007	.018	.391	.469	5.2
February	.001	.071	.037	.207	.019	.047	.001	.008	.016	.336	.408	4.9
March	.001	.070	.042	.247	.012	.056	.001	.008	.017	.382	.453	5.8
April	.001	.062	.058	.210	.015	.053	.001	.009	.015	.360	.423	6.5
May	.001	.060	.075	.233	.016	.052	.001	.006	.014	.397	.457	6.7
June	.001	.057	.102	.222	.019	.048	.001	.007	.014	.413	.472	6.5
July	.001	.061	.101	.252	.022	.052	.001	.007	.017	.452	.513	6.3
August	.001	.062	.098	.240	.018	.054	.002	.007	.014	.434	.497	6.2
September	.001	.063	.084	.232	.019	.050	.002	.006	.015	.407	.471	6.4
October	.001	.068	.082	.268	.021	.053	.001	.008	.015	.448	.517	6.9
November	.001	.069	.063	.275	.020	.052	.002	.006	.014	.433	.503	6.6
11-Month Total	.011	.720	.782	2.624	.202	.579	.015	.080	.170	4.452	5.184	6.1
2018 11-Month Total	.014	.739	.803	2.594	.232	.638	.017	.088	.180	4.552	5.305	5.8
2017 11-Month Total	.014	.740	.755	2.472	.242	.727	.019	.085	.199	4.499	5.253	5.7

<sup>a</sup> Ethane, propane, normal butane, isobutane, natural gasoline, and refinery olefins (ethylene, propylene, butylene, and isobutylene).

<sup>b</sup> Includes still gas not burned as refinery fuel.

<sup>c</sup> Distillate fuel oil, residual fuel oil, waxes, and miscellaneous products.

R=Revised. (s)=Less than 0.5 trillion Btu.

Notes: • Data are estimates. • Non-combustion use estimates are included in total energy consumption. See Table 1.3. • Non-combustion estimates are all for industrial sector consumption, except for some lubricants consumed by the transportation sector. • Totals may not equal sum of components due to

independent rounding. • Geographic coverage is the 50 states and the District of Columbia. • See Note 2, "Non-Combustion Use of Fossil Fuels," at end of section.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all available annual and monthly data beginning in 1973.

Sources: • See Note 2, "Non-Combustion Use of Fossil Fuels," at end of section. • **Percent of Total Energy Consumption:** Calculated as total non-combustion use of fossil fuels divided by total primary energy consumption (see Table 1.3).

**Note 1. Merchandise Trade Value.** Imports data presented are based on the customs values. Those values do not include insurance and freight and are consequently lower than the cost, insurance, and freight (CIF) values, which are also reported by the Bureau of the Census. All exports data, and imports data through 1980, are on a free alongside ship (f.a.s.) basis.

“Balance” is exports minus imports; a positive balance indicates a surplus trade value and a negative balance indicates a deficit trade value. “Energy” includes mineral fuels, lubricants, and related material. “Non-Energy Balance” and “Total Merchandise” include foreign exports (i.e., re-exports) and nonmonetary gold and U.S. Department of Defense Grant-Aid shipments. The “Non-Energy Balance” is calculated by subtracting the “Energy” from the “Total Merchandise Balance.”

“Imports” consist of government and nongovernment shipments of merchandise into the 50 states, the District of Columbia, Puerto Rico, the U.S. Virgin Islands, and the U.S. Foreign Trade Zones. They reflect the total arrival from foreign countries of merchandise that immediately entered consumption channels, warehouses, the Foreign Trade Zones, or the Strategic Petroleum Reserve. They exclude shipments between the United States, Puerto Rico, and U.S. possessions, shipments to U.S. Armed Forces and diplomatic missions abroad for their own use, U.S. goods returned to the United States by its Armed Forces, and in-transit shipments.

**Note 2. Non-Combustion Use of Fossil Fuels.** Most fossil fuels consumed in the United States and elsewhere are combusted to produce heat and power. However, some are used directly for non-combustion use as construction materials, chemical feedstocks, lubricants, solvents, and waxes. For example, coal tars from coal coke manufacturing are used as feedstock in the chemical industry, for metallurgical work, and in anti-dandruff shampoos; natural gas is used to make nitrogenous fertilizers and as chemical feedstocks; asphalt and road oil are used for roofing and paving; hydrocarbon gas liquids are used to create intermediate products that are used in making plastics; lubricants, including motor oil and greases, are used in vehicles and various industrial processes; petrochemical feedstocks are used to make plastics, synthetic fabrics, and related products.

### *Coal*

The U.S. Energy Information Administration (EIA) assumes all non-combustion use of coal comes from the process of manufacturing coal coke in the industrial sector. Among the byproducts of the process are “coal tars” or “coal liquids,” which typically are rich in aromatic hydrocarbons, such as benzene, and are used as chemical feedstock. EIA estimates non-combustion use ratios of coal tar for 1973 forward. Prior to 1998, estimate ratios are based on coal tar production data from the United States International Trade Commission's *Synthetic Organic Chemicals*. For 1998 forward, coal tar production is estimated using chemicals industry coal, coke, and breeze nonfuel use data from EIA, Form EIA-846, “Manufacturing Energy Consumption Survey” (MECS). For Table 1.11b, coal tar values in Table 1.11a are multiplied by 32.0067 million Btu/short ton, which is the product of 4.95 barrels/short ton (the density of coal tar) and 6.466 million Btu/barrel (the approximate heat content of coal tar).

### *Natural Gas*

EIA assumes that all non-combustion use of natural gas takes place in the industrial sector. EIA estimates non-combustion ratios of natural gas using total natural gas nonfuel use data from MECS, and natural gas used as feedstock for hydrogen production data from EIA, Form EIA-820, “Annual Refinery Report.” For Table 1.11b, natural gas values in Table 1.11a are multiplied by the heat content factors for natural gas end-use sectors consumption shown in Table A4.

### *Asphalt and Road Oil*

EIA assumes all asphalt and road oil consumption is for non-combustion use. For Table 1.11b, asphalt and road oil values in Table 1.11a are multiplied by 6.636 million Btu/ barrel (the approximate heat content of asphalt and road oil) and the number of days in the period.

### *Distillate Fuel Oil*

EIA assumes that all non-combustion use of distillate fuel oil occurs in the industrial sector. EIA estimates non-combustion ratios of distillate fuel oil using total distillate fuel oil nonfuel use data from MECS. Ratios prior to 1985 are assumed to be equal to the 1985 ratio. For Table 1.11b, distillate fuel oil values in Table 1.11a are multiplied by the heat content factors for distillate fuel oil consumption shown in Table A3 and the number of days in the period. Distillate fuel oil is included in "other" petroleum products.

### *Hydrocarbon Gas Liquids (HGL)*

EIA estimates non-combustion ratios of hydrocarbon gas liquids (HGL), which include ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). EIA assumes that 100% of ethane, ethylene, and propylene consumption is for non-combustion use; 85% of normal butane, butylene, isobutane, and isobutylene consumption is for non-combustion use; and 50% of natural gasoline consumption is for non-combustion use. Non-combustion use of propane in the industrial sector is estimated using data from the American Petroleum Institute (API), the Propane Education & Research Council (PERC), and EIA's *Petroleum Supply Annual* (PSA). For 1984 through 2009, propane non-combustion ratios are estimated using API propane and propylene chemical industry sales data. Propane non-combustion ratios prior to 1984 are assumed to be equal to the 1984 ratio. For 2010 through 2016, propane non-combustion ratios are estimated by subtracting API data for total odorized propane sales from PSA data for total propane product supplied. Beginning in 2017, propane non-combustion ratios are estimated by subtracting PERC data for total odorized propane sales from PSA data for total propane product supplied. For Table 1.11b, HGL component values are multiplied by the appropriate heat content factors in Table A1 and the number of days in the period.

### *Lubricants*

EIA assumes all lubricants consumption is for non-combustion use. For Table 1.11b, lubricants values in Table 1.11a are multiplied by 6.065 million Btu/barrel (the approximate heat content of lubricants) and the number of days in the period.

### *Petrochemical Feedstocks, Naphtha*

EIA assumes all naphtha for petrochemical feedstocks is for non-combustion use. For Table 1.11b, naphtha petrochemical feedstock values in 1.11a are multiplied by 5.248 million Btu/barrel (the approximate heat content of naphtha for petrochemical feedstocks) and the number of days in the period.

### *Petrochemical Feedstocks, Other Oils*

EIA assumes all other oils for petrochemical feedstocks are for non-combustion use. For Table 1.11b, other oils petrochemical feedstock values in 1.11a are multiplied by 5.825 million Btu/barrel (the approximate heat content of other oils for petrochemical feedstocks) and the number of days in the period.

### *Petrochemical Feedstocks, Still Gas*

EIA assumes all still gas not burned as refinery fuel or for pipeline gas supplies is for non-combustion use. EIA estimates non-combustion ratios of still gas by subtracting data for all known fuel uses (refinery fuel use from the PSA, and pipeline gas supplies from EIA's *Natural Gas Annual*) from the products supplied values in the PSA. The remainder is assumed to be dispatched to chemical plants as a feedstock for non-combustion use. For Table 1.11b, still gas for petrochemical feedstock values in 1.11a are multiplied by the still gas heat content factors (through 2015, the still gas heat content factor is 6.000 million Btu per fuel oil equivalent barrel; beginning in 2016, the still gas heat content factor is 6.287 million Btu per residual fuel oil equivalent barrel) and the number of days in the period.

### *Petroleum Coke*

EIA assumes all non-combustion use of petroleum coke occurs in the industrial sector. Examples include petroleum coke used in the production of chemicals and metals. EIA estimates non-combustion ratios of petroleum coke by subtracting data for all known fuel use by refineries from PSA and MECS data. Non-combustion ratios prior to 1988 are assumed to be equal to the 1988 ratio. For Table 1.11b, petroleum coke values in 1.11a are multiplied by 5.719 million Btu/barrel (the approximate heat content of marketable petroleum coke) and the number of days in the period.

### *Residual Fuel Oil*

EIA assumes that all non-combustion use of residual fuel oil occurs in the industrial sector. EIA estimates non-combustion ratios of residual fuel oil using total minus chemicals industry residual fuel oil nonfuel use data from MECS. Ratios prior to 1994 are assumed to be equal to the 1994 ratio. For Table 1.11b, residual fuel oil values in Table 1.11a are multiplied by 6.287 million Btu/barrel (the approximate heat content of residual fuel oil) and the number of days in the period. Residual fuel oil is included in "other" petroleum products.

### *Special Naphthas*

EIA assumes all special naphthas consumption is for non-combustion use. For Table 1.11b, special naphthas values in Table 1.11a are multiplied by 5.248 million Btu/barrel (the approximate heat content of special naphthas) and the number of days in the period.

### *Waxes*

EIA assumes all waxes consumption is for non-combustion use. For Table 1.11b, waxes values in Table 1.11a are multiplied by 5.537 million Btu/barrel (the approximate heat content of waxes) and the number of days in the period. Waxes are included in "other" petroleum products.

### *Miscellaneous Petroleum Products*

Miscellaneous products include all finished petroleum products not classified elsewhere. EIA assumes all miscellaneous petroleum products consumption is for non-combustion use. For Table 1.11b, miscellaneous petroleum products values in Table 1.11a are multiplied by 5.796 million Btu/barrel (the approximate heat content of miscellaneous petroleum products) and the number of days in the period. Miscellaneous petroleum products are included in "other" petroleum products.

## **Table 1.2 Sources**

### *Coal*

1949–1988: Coal production data from Table 6.1 are converted to Btu by multiplying by the coal production heat content factors in Table A5.

1989 forward: Coal production data from Table 6.1 are converted to Btu by multiplying by the coal production heat content factors in Table A5. Waste coal supplied data from Table 6.1 are converted to Btu by multiplying by the waste coal supplied heat content factors in Table A5. Coal production (including waste coal supplied) is equal to coal production plus waste coal supplied.

### *Natural Gas (Dry)*

1949 forward: Natural gas (dry) production data from Table 4.1 are converted to Btu by multiplying by the natural gas (dry) production heat content factors in Table A4.

### *Crude Oil*

1949 forward: Crude oil (including lease condensate) production data from Table 3.1 are converted to Btu by multiplying by the crude oil (including lease condensate) production heat content factors in Table A2.

### *NGPL*

1949 forward: Natural gas plant liquids (NGPL) production data from Table 3.1 are converted to Btu by multiplying by the NGPL production heat content factors in Table A2.

### *Fossil Fuels Total*

1949 forward: Total fossil fuels production is the sum of the production values for coal, natural gas (dry), crude oil, and NGPL.

### *Nuclear Electric Power*

1949 forward: Nuclear electricity net generation data from Table 7.2a are converted to Btu by multiplying by the nuclear heat rate factors in Table A6.

## *Renewable Energy*

1949 forward: Table 10.1.

## *Total Primary Energy Production*

1949 forward: Total primary energy production is the sum of the production values for fossil fuels, nuclear electric power, and renewable energy.

## **Table 1.3 Sources**

### *Coal*

1949 forward: Coal consumption data from Table 6.1 are converted to Btu by multiplying by the total coal consumption heat content factors in Table A5.

### *Natural Gas*

1949–1979: Natural gas (including supplemental gaseous fuels) consumption data from Table 4.1 are converted to Btu by multiplying by the total natural gas consumption heat content factors in Table A4.

1980 forward: Natural gas (including supplemental gaseous fuels) consumption data from Table 4.1 are converted to Btu by multiplying by the total natural gas consumption heat content factors in Table A4. Supplemental gaseous fuels data in Btu are estimated using the method described in Note 3, “Supplemental Gaseous Fuels,” at the end of Section 4. Natural gas (excluding supplemental gaseous fuels) consumption is equal to natural gas (including supplemental gaseous fuels) consumption minus supplemental gaseous fuels.

### *Petroleum*

1949–1992: Petroleum (excluding biofuels) consumption is equal to total petroleum products supplied from Table 3.6.

1993–2008: Petroleum (excluding biofuels) consumption is equal to total petroleum products supplied from Table 3.6 minus fuel ethanol consumption from Table 10.3.

2009–2011: Petroleum (excluding biofuels) consumption is equal to: total petroleum products supplied from Table 3.6; minus fuel ethanol (minus denaturant) consumption from Table 10.3; minus biodiesel consumption (calculated using biodiesel data from U.S. Energy Information Administration (EIA), EIA-22M, “Monthly Biodiesel Production Survey”; and biomass-based diesel fuel data from EIA-810, “Monthly Refinery Report,” EIA-812, “Monthly Product Pipeline Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1); minus other renewable diesel fuel and other renewables fuels consumption from Table 10.4.

2012 forward: Petroleum (excluding biofuels) consumption is equal to: total petroleum products supplied from Table 3.6; minus fuel ethanol (minus denaturant) consumption from Table 10.3; minus biodiesel consumption from Table 10.4; minus other renewable diesel fuel and other renewables fuels consumption from Table 10.4.

### *Coal Coke Net Imports*

1949 forward: Table 1.4c.

### *Fossil Fuels Total*

1949 forward: Total fossil fuels consumption is the sum of the consumption values for coal, natural gas, and petroleum, plus coal coke net imports.

### *Nuclear Electric Power*

1949 forward: Nuclear electricity net generation data from Table 7.2a are converted to Btu by multiplying by the nuclear heat rate factors in Table A6.

## *Renewable Energy*

1949 forward: Table 10.1.

*Electricity Net Imports*  
1949 forward: Table 1.4c.

*Total Primary Energy Consumption*

1949 forward: Total primary energy consumption is the sum of the consumption values for fossil fuels, nuclear electric power, and renewable energy, plus electricity net imports.

**Table 1.4a Sources**

*Coal*

1949 forward: Coal imports data from Table 6.1 are converted to Btu by multiplying by the coal imports heat content factors in Table A5.

*Coal Coke*

1949 forward: Coal coke imports data from U.S. Department of Commerce, Bureau of the Census, Monthly Report IM 145, are converted to Btu by multiplying by the coal coke imports heat content factor in Table A5.

*Natural Gas*

1949 forward: Natural gas imports data from Table 4.1 are converted to Btu by multiplying by the natural gas imports heat content factors in Table A4.

*Crude Oil*

1949 forward: Crude oil imports data from Table 3.3b are converted to Btu by multiplying by the crude oil imports heat content factors in Table A2.

*Petroleum Products*

1949–1992: Petroleum products (excluding biofuels) imports are equal to total petroleum imports from Table 3.3b minus crude oil imports from Table 3.3b; petroleum products (excluding biofuels) imports data are converted to Btu by multiplying by the total petroleum products imports heat content factors in Table A2.

1993–2008: Petroleum products (excluding biofuels) imports are equal to petroleum products (including biofuels) imports (see 1949–1992 sources above) minus fuel ethanol (minus denaturant) imports (see “Biomass—Fuel Ethanol (Minus Denaturant)” sources below).

2009 forward: Renewable fuels (excluding fuel ethanol) imports data are from U.S. Energy Information Administration, Petroleum Supply Annual (PSA), Tables 1 and 25, and Petroleum Supply Monthly (PSM), Tables 1 and 37 (for biomass-based diesel fuel and other renewable fuels, the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1; for other renewable diesel fuel, the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Petroleum products (excluding biofuels) imports are equal to petroleum products (including biofuels) imports (see 1949–1992 sources above) minus fuel ethanol (minus denaturant) imports (see “Biomass—Fuel Ethanol (Minus Denaturant)” sources below) minus renewable fuels (excluding fuel ethanol) imports.

*Total Petroleum*

1949 forward: Total petroleum imports are equal to crude oil imports plus petroleum products imports.

*Biomass—Fuel Ethanol (Minus Denaturant)*

1993 forward: Fuel ethanol (including denaturant) imports data are from PSA/PSM Table 1. Fuel ethanol (minus denaturant) production is equal to fuel ethanol (including denaturant) production from Table 10.3 minus denaturant from Table 10.3. Fuel ethanol (minus denaturant) imports are equal to fuel ethanol (including denaturant) imports multiplied by the ratio of fuel ethanol (minus denaturant) production to fuel ethanol (including denaturant) production. Fuel ethanol (minus denaturant) imports data are converted to Btu by multiplying by 3.539 million Btu per barrel, the undenatured ethanol heat content factor in Table A3.



### *Biomass—Biodiesel*

2001 forward: Biodiesel imports data are from Table 10.4, and are converted to Btu by multiplying by the biodiesel heat content factor in Table A1.

### *Biomass—Other Renewable Fuels*

2009 forward: Other renewable fuels imports data are from PSA Table 25 and PSM Table 37. For other renewable diesel fuel, the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1; for other renewable fuels, the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1.

### *Total Biomass*

1993–2000: Total biomass imports are equal to fuel ethanol (minus denaturant) imports.

2001–2008: Total biomass imports are equal to fuel ethanol (minus denaturant) imports plus biodiesel imports.

2009 forward: Total biomass imports are the sum of imports values for fuel ethanol (minus denaturant), biodiesel, and other renewable fuels.

### *Electricity*

1949 forward: Electricity imports data from Table 7.1 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

### *Total Primary Energy Imports*

1949 forward: Total primary energy imports are the sum of the imports values for coal, coal coke, natural gas, total petroleum, total biomass, and electricity.

## **Table 1.4b Sources**

### *Coal*

1949 forward: Coal exports data from Table 6.1 are converted to Btu by multiplying by the coal exports heat content factors in Table A5.

### *Coal Coke*

1949 forward: Coal coke exports data from U.S. Department of Commerce, Bureau of the Census, Monthly Report EM 545, are converted to Btu by multiplying by the coal coke exports heat content factor in Table A5.

### *Natural Gas*

1949 forward: Natural gas exports data from Table 4.1 are converted to Btu by multiplying by the natural gas exports heat content factors in Table A4.

### *Crude Oil*

1949 forward: Crude oil exports data from Table 3.3b are converted to Btu by multiplying by the crude oil exports heat content factor in Table A2.

### *Petroleum Products*

1949–2009: Petroleum products (excluding biofuels) exports are equal to total petroleum exports from Table 3.3b minus crude oil exports from Table 3.3b; petroleum products (excluding biofuels) exports data are converted to Btu by multiplying by the total petroleum products exports heat content factors in Table A2.

2010: Petroleum products (including biofuels) exports are equal to total petroleum exports from Table 3.3b minus crude oil exports from Table 3.3b; petroleum products (including biofuels) exports data are converted to Btu by multiplying by the total petroleum products exports heat content factors in Table A2. Petroleum products (excluding biofuels) exports are equal to petroleum products (including biofuels) exports minus fuel ethanol (minus denaturant) exports (see “Biomass—Fuel Ethanol (Minus Denaturant)” sources below).

2011 forward: Biomass-based diesel fuel exports data are from U.S. Energy Information Administration (EIA), Petroleum Supply Annual (PSA), Table 31, and Petroleum Supply Monthly (PSM), Table 49, and are converted to Btu by multiplying

by the biodiesel heat content factor in Table A1. Petroleum products (excluding biofuels) exports are equal to petroleum products (including biofuels) exports (see 2010 sources above) minus fuel ethanol (minus denaturant) exports (see “Biomass—Fuel Ethanol (Minus Denaturant)” sources below) minus biomass-based diesel fuel exports.

#### *Total Petroleum*

1949 forward: Total petroleum exports are equal to crude oil exports plus petroleum products exports.

#### *Biomass—Fuel Ethanol (Minus Denaturant)*

2010 forward: Fuel ethanol (including denaturant) exports data are from PSA/PSM Table 1. Fuel ethanol (minus denaturant) production is equal to fuel ethanol (including denaturant) production from Table 10.3 minus denaturant from Table 10.3. Fuel ethanol (minus denaturant) exports are equal to fuel ethanol (including denaturant) exports multiplied by the ratio of fuel ethanol (minus denaturant) production to fuel ethanol (including denaturant) production. Fuel ethanol (minus denaturant) exports are converted to Btu by multiplying by 3.539 million Btu per barrel, the undenatured ethanol heat content factor in Table A3.

#### *Biomass—Biodiesel*

2001 forward: Biodiesel exports data are from Table 10.4, and are converted to Btu by multiplying by the biodiesel heat content factor in Table A1.

#### *Biomass—Densified Biomass*

2016 forward: Densified biomass exports data are from EIA, Form EIA-63C, “Densified Biomass Fuel Report.”

#### *Total Biomass*

2001–2009: Total biomass exports are equal to biodiesel exports.

2010–2015: Total biomass exports are equal to fuel ethanol (minus denaturant) exports plus biodiesel exports.

2016 forward: Total biomass exports are the sum of the exports values for fuel ethanol (minus denaturant), biodiesel, and densified biomass.

#### *Electricity*

1949 forward: Electricity exports data from Table 7.1 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

#### *Total Primary Energy Exports*

1949 forward: Total primary energy exports are the sum of the exports values for coal, coal coke, natural gas, total petroleum, total biomass, and electricity.

### **Table 1.5 Sources**

U.S. Department of Commerce, U.S. Census Bureau, Foreign Trade Division:

#### *Petroleum Exports*

1974–1987: “U.S. Exports,” FT-410, December issues.

1988 and 1989: “Report on U.S. Merchandise Trade,” Final Revisions.

1990–1992: “U.S. Merchandise Trade,” Final Report.

1993–2016: “U.S. International Trade in Goods and Services,” Annual Revisions.

2017–2019: “U.S. International Trade in Goods and Services,” 2019 Annual Revisions.

2020: “U.S. International Trade in Goods and Services,” FT-900, monthly.

#### *Petroleum Imports*

1974–1987: “U.S. Merchandise Trade,” FT-900, December issues, 1975–1988.

1988 and 1989: "Report on U.S. Merchandise Trade," Final Revisions.

1990–1993: "U.S. Merchandise Trade," Final Report.

1994–2016: "U.S. International Trade in Goods and Services," Annual Revisions.

2017–2019: "U.S. International Trade in Goods and Services," 2019 Annual Revisions.

2020: "U.S. International Trade in Goods and Services," FT-900, monthly.

### *Energy Exports and Imports*

1974–1987: U.S. merchandise trade press releases and database printouts for adjustments.

1988: January–July, monthly FT-900 supplement, 1989 issues. August–December, monthly FT-900, 1989 issues.

1989: Monthly FT-900, 1990 issues.

1990–1992: "U.S. Merchandise Trade," Final Report. 1993–2009: "U.S. International Trade in Goods and Services," Annual Revisions.

1993–2016: "U.S. International Trade in Goods and Services," Annual Revisions.

2017–2019: "U.S. International Trade in Goods and Services," 2019 Annual Revisions.

2020: "U.S. International Trade in Goods and Services," FT-900, monthly.

### *Petroleum Balance*

1974 forward: The petroleum balance is calculated by the U.S. Energy Information Administration (EIA) as petroleum imports minus petroleum exports.

### *Energy Balance*

1974 forward: The energy balance is calculated by EIA as energy imports minus energy exports.

### *Non-Energy Balance*

1974 forward: The non-energy balance is calculated by EIA as the total merchandise balance minus the energy balance.

### *Total Merchandise*

1974–1987: U.S. merchandise trade press releases and database printouts for adjustments.

1988: "Report on U.S. Merchandise Trade, 1988 Final Revisions," August 18, 1989.

1989: "Report on U.S. Merchandise Trade, 1989 Revisions," July 10, 1990.

1990: "U.S. Merchandise Trade, 1990 Final Report," May 10, 1991, and "U.S. Merchandise Trade, December 1992," February 18, 1993, page 3.

1991: "U.S. Merchandise Trade, 1992 Final Report," May 12, 1993.

1992–2016: "U.S. International Trade in Goods and Services," Annual Revisions.

2017–2019: "U.S. International Trade in Goods and Services," 2019 Annual Revisions.

2020: "U.S. International Trade in Goods and Services," FT-900, monthly.


THIS PAGE INTENTIONALLY LEFT BLANK

## **2. Energy Consumption By Sector**


---

**Figure 2.1 Energy Consumption by Sector**  
(Quadrillion Btu)


Total Consumption by End-Use Sector, 1949–2019



Total Consumption by End-Use Sector, Monthly



By Sector, November 2020



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.

Source: Table 2.1.

**Table 2.1 Energy Consumption by Sector**  
(Trillion Btu)

	End-Use Sectors								Electric Power Sector <sup>c,d</sup>	Balancing Item <sup>g</sup>	Primary Total <sup>h</sup>		
	Residential		Commercial <sup>a</sup>		Industrial <sup>b</sup>		Transportation						
	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>				
1950 Total	4,830	5,989	2,834	3,893	13,872	16,224	8,383	8,492	4,679	(s)	34,599		
1955 Total	5,608	7,278	2,561	3,895	16,073	19,455	9,474	9,550	6,461	(s)	40,178		
1960 Total	6,651	9,040	2,723	4,610	16,949	20,795	10,560	10,596	8,158	(s)	45,041		
1965 Total	7,280	10,640	3,177	5,846	20,085	25,035	12,399	12,432	11,012	(s)	53,953		
1970 Total	8,323	13,766	4,237	8,346	22,941	29,605	16,062	16,098	16,253	(s)	67,817		
1975 Total	7,990	14,814	4,059	9,493	21,400	29,379	18,211	18,245	20,270	1	71,931		
1980 Total	7,440	15,754	4,105	10,578	22,549	31,993	19,659	19,697	24,269	-1	78,021		
1985 Total	7,149	16,042	3,732	11,451	19,384	28,757	20,042	20,088	26,032	-4	76,334		
1990 Total	6,553	16,941	3,894	13,317	21,120	31,749	22,366	22,419	30,495	7	84,433		
1995 Total	6,935	18,517	4,101	14,690	22,657	33,908	23,757	23,812	33,479	3	90,931		
2000 Total	7,156	20,422	4,278	17,175	22,748	34,587	26,456	26,515	38,062	2	98,702		
2001 Total	6,864	20,038	4,085	17,137	21,726	32,653	26,179	26,242	37,215	-6	96,064		
2002 Total	6,907	20,786	4,132	17,346	21,727	32,590	26,747	26,808	38,016	5	97,535		
2003 Total	7,233	21,120	4,298	17,346	21,469	32,489	26,807	26,881	38,028	-1	97,835		
2004 Total	6,987	21,082	4,232	17,656	22,340	33,444	27,748	27,826	38,701	-6	100,002		
2005 Total	6,901	21,613	4,052	17,854	21,343	32,374	28,179	28,261	39,626	(s)	100,102		
2006 Total	6,155	20,671	3,748	17,707	21,455	32,317	28,618	28,697	39,417	(s)	99,392		
2007 Total	6,589	21,520	3,923	18,253	21,284	32,306	28,727	28,815	40,371	-1	100,893		
2008 Total	6,889	21,668	4,100	18,402	20,455	31,261	27,339	27,421	39,969	1	98,754		
2009 Total	6,637	21,082	4,056	17,888	18,670	28,380	26,510	26,592	38,069	(s)	93,942		
2010 Total	6,641	21,895	4,023	18,059	20,327	30,574	26,897	26,978	39,619	7	97,513		
2011 Total	6,473	21,382	4,066	17,982	20,505	30,893	26,518	26,599	39,293	8	96,863		
2012 Total	5,684	19,870	3,725	17,422	20,781	30,954	26,050	26,126	38,131	2	94,374		
2013 Total	6,689	21,052	4,161	17,930	21,378	31,525	26,533	26,612	38,357	-1	97,117		
2014 Total	7,006	21,446	4,390	18,265	21,455	31,691	26,789	26,869	38,629	6	98,276		
2015 Total	6,465	20,618	4,441	18,157	21,417	31,361	27,161	27,238	37,890	1	97,375		
2016 Total	6,030	20,179	4,321	18,030	21,554	31,347	27,710	27,786	37,727	-4	97,338		
2017 Total	6,097	19,887	4,368	17,900	21,953	31,798	27,939	28,014	37,241	(s)	97,599		
2018 January	1,248	2,738	704	1,853	1,999	2,798	2,262	2,269	3,446	2	9,660		
February	887	1,979	539	1,525	1,769	2,495	2,055	2,061	2,811	-2	8,058		
March	856	1,914	536	1,603	1,967	2,767	2,416	2,422	2,931	-4	8,702		
April	611	1,549	407	1,423	1,812	2,589	2,319	2,325	2,737	-6	7,881		
May	293	1,359	251	1,412	1,881	2,760	2,442	2,448	3,112	-2	7,977		
June	229	1,536	224	1,451	1,848	2,709	2,433	2,439	3,402	2	8,138		
July	215	1,753	219	1,536	1,909	2,803	2,501	2,508	3,756	5	8,604		
August	205	1,702	223	1,538	1,988	2,886	2,546	2,553	3,717	5	8,683		
September	221	1,458	226	1,396	1,857	2,678	2,316	2,322	3,234	1	7,855		
October	410	1,430	341	1,447	1,980	2,793	2,406	2,412	2,944	-2	8,079		
November	800	1,852	507	1,571	1,924	2,747	2,334	2,341	2,945	-2	8,509		
December	1,006	2,240	601	1,682	1,932	2,737	2,358	2,365	3,127	-2	9,022		
Total	6,982	21,510	4,776	18,440	22,866	32,761	28,389	28,465	38,163	-7	101,169		
2019 January	1,204	2,525	698	1,808	2,071	2,889	2,300	2,307	3,257	2	9,532		
February	1,025	2,146	698	1,580	1,787	2,522	2,123	2,129	2,843	(s)	8,377		
March	897	1,994	650	1,596	1,936	2,725	2,372	2,379	2,939	-2	8,692		
April	480	1,357	345	1,338	1,849	2,629	2,337	2,343	2,655	-4	7,662		
May	348	1,352	276	1,390	1,907	2,755	2,436	2,443	2,972	-2	7,937		
June	246	1,432	229	1,371	1,836	2,674	2,422	2,428	3,172	1	7,906		
July	229	1,732	226	1,506	1,912	2,799	2,498	2,504	3,676	7	8,548		
August	229	1,676	234	1,494	1,950	2,828	2,541	2,548	3,592	6	8,552		
September	221	1,463	222	1,375	1,874	2,688	2,318	2,324	3,215	3	7,853		
October	372	1,370	309	1,375	1,964	2,744	2,442	2,442	2,848	-2	7,928		
November	789	1,800	510	1,525	1,960	2,746	2,301	2,307	2,818	-1	8,377		
December	979	2,153	591	1,638	2,006	2,783	2,348	2,354	3,005	-3	8,925		
Total	7,017	20,997	4,788	17,997	23,052	32,782	28,433	28,507	36,992	6	100,289		
2020 January	1,035	2,244	615	1,673	2,005	2,757	2,282	2,289	3,025	-3	8,959		
February	927	2,012	560	1,549	1,867	2,601	2,145	2,151	2,815	-5	8,308		
March	702	1,696	446	1,429	1,911	2,653	2,061	2,067	2,724	-5	7,839		
April	534	1,458	328	1,187	1,630	2,290	1,577	1,582	2,448	-4	6,513		
May	383	1,443	256	1,196	1,688	2,404	1,808	1,812	2,721	-1	6,854		
June	254	1,566	215	1,302	1,660	2,412	1,991	1,995	3,156	2	7,278		
July	228	1,880	208	1,455	1,784	2,588	2,163	2,168	3,708	10	8,101		
August	217	1,781	210	1,411	1,823	2,636	2,175	2,181	3,584	10	8,019		
September	242	1,447	226	1,286	1,765	2,498	2,081	2,085	3,002	4	7,320		
October	382	1,382	299	1,320	1,894	2,670	2,127	2,132	2,803	-1	7,504		
November	601	1,587	393	1,356	1,897	2,649	2,004	2,009	2,707	2	7,603		
11-Month Total	5,504	18,497	3,755	15,164	19,925	28,159	22,414	22,472	32,693	8	84,299		
2019 11-Month Total	6,040	18,845	4,198	16,357	21,046	30,000	26,086	26,154	33,987	9	91,364		
2018 11-Month Total	5,977	19,271	4,176	16,756	20,933	30,025	26,031	26,100	35,034	-5	92,147		

<sup>a</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>d</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

<sup>e</sup> See "Primary Energy Consumption" in Glossary.

<sup>f</sup> Total energy consumption in the end-use sectors consists of primary energy consumption, electricity retail sales, and electrical system energy losses. See Note 1, "Electrical System Energy Losses," at end of section.

<sup>g</sup> A balancing item. The sum of primary consumption in the five energy-use sectors equals the sum of total consumption in the four end-use sectors. However, total energy consumption does not equal the sum of the sectoral components due

to the use of sector-specific conversion factors for coal and natural gas.

<sup>h</sup> Primary energy consumption total. See Table 1.3.

R=Revised. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.

Notes: • Data are estimates, except for the electric power sector. • See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: • End-Use Sectors: Tables 2.2–2.5. • Electric Power Sector: Table 2.6. • Balancing Item: Calculated as primary energy total consumption minus the sum of total energy consumption in the four end-use sectors.

• Primary Total: Table 1.3.


**Figure 2.2 Residential Sector Energy Consumption**

(Quadrillion Btu)


By Major Source, 1949–2019




By Major Source, Monthly



Total, January–November



By Major Source, November 2020



[a] Electricity retail sales.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.

Source: Table 2.2.



**Table 2.2 Residential Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>									Electricity Retail Sales <sup>e</sup>	Electrical System Energy Losses <sup>f</sup>	Total
	Fossil Fuels				Renewable Energy <sup>b</sup>				Total Primary			
	Coal	Natural Gas <sup>c</sup>	Petro- leum	Total	Geo- thermal	Solar <sup>d</sup>	Bio- mass	Total				
1950 Total .....	1,261	1,240	1,322	3,824	NA	NA	1,006	1,006	4,830	246	913	5,989
1955 Total .....	867	2,198	1,767	4,833	NA	NA	775	775	5,608	438	1,232	7,278
1960 Total .....	585	3,212	2,228	6,025	NA	NA	627	627	6,651	687	1,701	9,040
1965 Total .....	352	4,028	2,432	6,812	NA	NA	468	468	7,280	993	2,367	10,640
1970 Total .....	209	4,987	2,726	7,922	NA	NA	401	401	8,323	1,591	3,852	13,766
1975 Total .....	63	5,023	2,479	7,565	NA	NA	425	425	7,990	2,007	4,817	14,814
1980 Total .....	31	4,825	1,734	6,590	NA	NA	850	850	7,440	2,448	5,866	15,754
1985 Total .....	39	4,534	1,566	6,139	NA	NA	1,010	1,010	7,149	2,709	6,184	16,042
1990 Total .....	31	4,487	1,395	5,912	6	55	580	640	6,553	3,153	7,235	16,941
1995 Total .....	17	4,954	1,374	6,345	7	63	520	589	6,935	3,557	8,026	18,517
2000 Total .....	11	5,105	1,554	6,670	9	58	420	486	7,156	4,069	9,197	20,422
2001 Total .....	12	4,889	1,529	6,430	9	55	370	435	6,864	4,100	9,074	20,038
2002 Total .....	12	4,995	1,457	6,464	10	53	380	443	6,907	4,317	9,562	20,786
2003 Total .....	12	5,209	1,547	6,768	13	52	400	465	7,233	4,353	9,534	21,120
2004 Total .....	11	4,981	1,520	6,512	14	51	410	475	6,987	4,408	9,687	21,082
2005 Total .....	8	4,946	1,450	6,405	16	50	430	496	6,901	4,638	10,074	21,613
2006 Total .....	6	4,476	1,222	5,704	18	53	380	451	6,155	4,611	9,905	20,671
2007 Total .....	8	4,835	1,249	6,092	22	55	420	497	6,589	4,750	10,180	21,520
2008 Total .....	NA	5,010	1,325	6,335	26	58	470	555	6,889	4,711	10,068	21,668
2009 Total .....	NA	4,883	1,158	6,041	33	60	504	597	6,637	4,657	9,788	21,082
2010 Total .....	NA	4,878	1,120	5,999	37	65	541	642	6,641	4,933	10,321	21,895
2011 Total .....	NA	4,805	1,034	5,838	40	71	524	635	6,473	4,855	10,054	21,382
2012 Total .....	NA	4,242	886	5,128	40	79	438	557	5,684	4,690	9,496	19,870
2013 Total .....	NA	5,023	963	5,986	40	91	572	703	6,689	4,759	9,604	21,052
2014 Total .....	NA	5,242	1,036	6,279	40	110	579	728	7,006	4,801	9,638	21,446
2015 Total .....	NA	4,777	1,007	5,784	40	128	513	681	6,465	4,791	9,362	20,618
2016 Total .....	NA	4,506	878	5,384	40	162	R 445	R 646	R 6,030	4,815	9,334	R 20,179
2017 Total .....	NA	4,563	871	5,435	40	194	R 429	R 662	R 6,097	4,704	9,085	R 19,887
2018 January .....	NA	1,017	172	1,189	3	12	R 45	R 60	1,248	508	982	R 2,738
February .....	NA	715	116	830	3	13	40	56	R 887	388	704	R 1,979
March .....	NA	683	107	790	3	18	R 45	R 66	856	366	692	1,914
April .....	NA	456	88	544	3	21	43	R 67	R 611	326	613	1,549
May .....	NA	175	48	223	3	23	R 45	R 71	293	354	711	R 1,359
June .....	NA	123	36	160	3	23	43	69	229	443	864	1,536
July .....	NA	110	34	144	3	24	R 45	R 72	215	524	1,014	1,753
August .....	NA	103	31	135	3	23	R 45	R 71	205	524	973	1,702
September .....	NA	116	39	155	3	20	43	66	221	440	796	R 1,458
October .....	NA	264	80	345	3	18	R 45	R 66	410	365	654	R 1,430
November .....	NA	620	119	740	3	14	43	R 61	800	354	698	1,852
December .....	NA	793	152	945	3	13	R 45	61	1,006	420	814	2,240
Total .....	NA	5,174	1,022	6,197	40	221	R 524	R 785	R 6,982	5,013	9,515	R 21,510
2019 January .....	NA	990	R 151	R 1,140	3	13	R 46	R 63	R 1,204	455	867	R 2,525
February .....	NA	840	R 126	R 966	3	15	R 42	R 59	R 1,025	398	723	R 2,146
March .....	NA	714	R 112	R 827	3	21	R 46	R 70	R 897	384	712	R 1,994
April .....	NA	341	R 68	R 409	3	23	R 45	R 71	R 480	308	568	1,357
May .....	NA	220	R 52	R 272	3	26	R 46	R 75	348	342	662	1,352
June .....	NA	134	R 38	R 172	3	26	R 45	R 74	R 246	410	775	1,432
July .....	NA	116	R 36	R 152	3	27	R 46	R 77	229	525	978	1,732
August .....	NA	106	R 47	R 153	3	26	R 46	R 76	229	512	935	1,676
September .....	NA	114	R 36	R 150	3	23	R 45	R 71	221	449	794	1,463
October .....	NA	240	R 61	R 302	3	20	R 46	R 70	372	368	629	1,370
November .....	NA	611	R 114	R 725	3	16	R 45	R 64	R 789	350	661	R 1,800
December .....	NA	781	R 134	R 915	3	15	R 46	R 64	R 979	413	761	R 2,153
Total .....	NA	5,205	R 976	R 6,181	40	252	R 544	R 836	R 7,017	4,914	9,066	R 20,997
2020 January .....	NA	852	R 125	R 977	3	16	R 39	R 58	R 1,035	425	784	R 2,244
February .....	NA	760	R 109	R 869	3	18	R 36	R 57	R 927	382	704	R 2,012
March .....	NA	545	R 92	R 636	3	24	R 39	R 66	R 702	355	639	R 1,696
April .....	NA	389	R 77	R 467	3	27	R 38	R 67	R 534	333	592	R 1,458
May .....	NA	244	R 67	R 311	3	30	R 39	R 72	R 383	360	701	R 1,443
June .....	NA	141	R 42	R 183	3	30	R 38	R 71	R 254	448	865	R 1,566
July .....	NA	122	R 32	R 155	3	31	R 39	R 73	R 228	569	1,082	R 1,880
August .....	NA	114	R 32	R 146	3	30	R 39	R 72	R 217	542	1,022	R 1,781
September .....	NA	130	R 45	R 175	3	26	R 38	R 67	R 242	435	770	R 1,447
October .....	NA	253	R 63	R 316	3	24	R 39	R 66	R 382	360	R 640	R 1,382
November .....	NA	459	81	540	3	20	38	60	601	339	647	1,587
11-Month Total ...	NA	4,009	766	4,775	36	275	419	730	5,504	4,547	8,445	18,497
2019 11-Month Total ...	NA	4,425	842	5,267	36	238	498	772	6,040	4,501	8,304	18,845
2018 11-Month Total ...	NA	4,383	870	5,253	36	208	480	724	5,977	4,592	8,702	19,271

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> See Table 10.2a for notes on series components.

<sup>c</sup> Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.

<sup>d</sup> Distributed (small-scale) solar photovoltaic (PV) electricity generation in the residential sector and distributed solar thermal energy in the residential, commercial, and industrial sectors. See Tables 10.2a and 10.5.

<sup>e</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total

electricity retail sales. See Note 1, "Electrical System Energy Losses," at end of section.

R=Revised. NA=Not available.

Notes: • Data are estimates, except for electricity retail sales. • See Note 2, "Other Energy Losses," at end of section. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 2.3 Commercial Sector Energy Consumption**

(Quadrillion Btu)


By Major Source, 1949–2019




By Major Source, Monthly



Total, January–November



By Major Source, November 2020



[a] Electricity retail sales.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.

Source: Table 2.3.

**Table 2.3 Commercial Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>										Total Primary	Elec- tricity Retail Sales <sup>g</sup>	Electrical System Energy Losses <sup>h</sup>	Total
	Fossil Fuels				Renewable Energy <sup>b</sup>									
	Coal	Natural Gas <sup>c</sup>	Petro- leum <sup>d</sup>	Total	Hydro- electric Power <sup>e</sup>	Geo- thermal	Solar <sup>f</sup>	Wind	Bio- mass	Total				
1950 Total .....	1,542	401	872	2,815	NA	NA	NA	NA	19	19	2,834	225	834	3,893
1955 Total .....	801	651	1,095	2,547	NA	NA	NA	NA	15	15	2,561	350	984	3,895
1960 Total .....	407	1,056	1,248	2,711	NA	NA	NA	NA	12	12	2,723	543	1,344	4,610
1965 Total .....	265	1,490	1,413	3,168	NA	NA	NA	NA	9	9	3,177	789	1,880	5,846
1970 Total .....	165	2,473	1,592	4,229	NA	NA	NA	NA	8	8	4,237	1,201	2,908	8,346
1975 Total .....	147	2,558	1,346	4,051	NA	NA	NA	NA	8	8	4,059	1,598	3,835	9,493
1980 Total .....	115	2,651	1,318	4,084	NA	NA	NA	NA	21	21	4,105	1,906	4,567	10,578
1985 Total .....	137	2,488	1,083	3,708	NA	NA	NA	NA	24	24	3,732	2,351	5,368	11,451
1990 Total .....	124	2,680	991	3,795	1	3	(s)	—	94	98	3,894	2,860	6,564	13,317
1995 Total .....	117	3,096	769	3,982	1	5	(s)	—	113	119	4,101	3,252	7,337	14,690
2000 Total .....	92	3,252	807	4,150	1	8	1	—	119	128	4,278	3,956	8,942	17,175
2001 Total .....	97	3,097	789	3,983	1	8	1	—	92	101	4,085	4,062	8,990	17,137
2002 Total .....	90	3,212	725	4,027	(s)	9	1	—	95	105	4,132	4,110	9,104	17,346
2003 Total .....	82	3,261	842	4,184	1	11	1	—	101	114	4,298	4,090	8,958	17,346
2004 Total .....	103	3,201	809	4,113	1	12	1	—	105	120	4,232	4,198	9,225	17,656
2005 Total .....	97	3,073	761	3,931	1	14	2	—	105	121	4,052	4,351	9,451	17,854
2006 Total .....	65	2,902	661	3,627	1	14	3	—	103	120	3,748	4,435	9,525	17,707
2007 Total .....	70	3,085	646	3,801	1	14	4	—	103	122	3,923	4,560	9,771	18,253
2008 Total .....	81	3,228	660	3,970	1	15	6	—	109	131	4,100	4,559	9,743	18,402
2009 Total .....	73	3,187	659	3,919	1	17	8	(s)	112	137	4,056	4,459	9,373	17,888
2010 Total .....	70	3,165	647	3,881	1	19	12	(s)	111	142	4,023	4,539	9,497	18,059
2011 Total .....	62	3,216	632	3,910	(s)	20	20	(s)	115	155	4,066	4,531	9,385	17,982
2012 Total .....	44	2,960	560	3,563	(s)	20	33	1	108	162	3,725	4,528	9,168	17,422
2013 Total .....	41	3,380	558	3,979	(s)	20	41	1	120	182	4,161	4,562	9,206	17,930
2014 Total .....	40	3,572	578	4,190	(s)	20	52	1	127	200	4,390	4,614	9,261	18,265
2015 Total .....	31	3,316	864	4,211	(s)	20	57	1	152	230	4,441	4,643	9,073	18,157
2016 Total .....	24	3,224	832	4,079	2	20	62	1	158	242	4,321	4,665	9,044	18,030
2017 Total .....	21	3,273	820	4,113	2	20	76	1	156	255	4,368	4,616	8,916	17,900
2018 January .....	3	574	106	683	(s)	2	5	(s)	13	21	704	392	757	1,853
February .....	2	439	78	520	(s)	2	6	(s)	12	20	539	350	636	1,525
March .....	2	433	78	513	(s)	2	8	(s)	13	23	536	369	698	1,603
April .....	1	313	70	384	(s)	2	9	(s)	13	23	407	353	663	1,423
May .....	1	169	56	226	(s)	2	10	(s)	13	25	251	386	775	1,412
June .....	1	147	50	199	(s)	2	10	(s)	13	25	224	416	811	1,451
July .....	1	142	50	193	(s)	2	10	(s)	13	25	219	449	868	1,536
August .....	1	148	49	198	(s)	2	10	(s)	14	25	223	460	855	1,538
September .....	1	152	50	203	(s)	2	9	(s)	12	23	226	416	754	1,396
October .....	1	246	71	318	(s)	2	8	(s)	13	23	341	396	710	1,447
November .....	2	400	85	486	(s)	2	6	(s)	13	21	507	358	706	1,571
December .....	2	475	102	579	(s)	2	6	(s)	13	21	601	368	713	1,682
Total .....	19	3,638	845	4,502	2	20	94	2	156	274	4,776	4,715	8,949	18,440
2019 January .....	2	575	R 100	R 677	(s)	2	6	(s)	13	21	R 698	382	728	R 1,808
February .....	2	490	R 86	R 578	(s)	2	6	(s)	12	20	R 598	348	633	R 1,580
March .....	2	440	R 84	R 526	(s)	2	9	(s)	13	24	R 550	367	680	R 1,596
April .....	1	256	64	R 321	(s)	2	10	(s)	12	24	R 345	350	643	R 1,338
May .....	1	192	58	251	(s)	2	10	(s)	12	25	276	379	734	R 1,390
June .....	1	150	R 53	R 204	(s)	2	11	(s)	12	25	R 229	395	747	R 1,371
July .....	1	147	52	200	(s)	2	11	(s)	13	26	226	447	833	1,506
August .....	1	146	R 61	R 208	(s)	2	11	(s)	13	25	R 234	446	815	1,494
September .....	1	148	R 49	198	(s)	2	9	(s)	12	24	R 222	416	736	R 1,375
October .....	1	224	R 61	286	(s)	2	8	(s)	13	23	309	393	672	R 1,375
November .....	1	403	R 84	R 489	(s)	2	6	(s)	12	21	R 510	351	664	R 1,525
December .....	2	474	R 94	R 570	(s)	2	6	(s)	13	21	R 591	369	679	R 1,638
Total .....	17	3,645	R 847	R 4,508	2	24	103	2	149	279	R 4,788	4,643	8,566	R 17,997
2020 January .....	2	505	R 86	R 593	NM	2	7	(s)	13	22	R 615	371	686	R 1,673
February .....	2	460	R 76	R 538	NM	2	8	(s)	12	22	R 560	348	641	R 1,549
March .....	2	350	R 69	R 421	NM	2	10	(s)	12	25	R 446	351	632	R 1,429
April .....	1	246	57	R 304	(s)	2	11	(s)	11	24	R 328	309	550	1,187
May .....	1	167	R 62	R 230	NM	2	12	(s)	12	26	R 256	319	621	R 1,196
June .....	1	136	51	R 189	NM	2	12	(s)	12	26	R 215	371	716	R 1,302
July .....	1	133	R 47	R 181	NM	2	13	(s)	12	27	208	430	817	R 1,455
August .....	1	136	R 46	R 183	NM	2	12	(s)	12	27	R 210	416	785	1,411
September .....	1	148	R 53	R 201	(s)	2	11	(s)	11	25	R 226	383	677	R 1,286
October .....	1	215	R 59	275	NM	2	10	(s)	12	R 24	R 299	368	654	1,320
November .....	1	306	64	371	(s)	2	8	(s)	12	21	393	331	632	1,356
11-Month Total ...	14	2,803	670	3,486	2	22	114	1	129	268	3,755	3,997	7,412	15,164
2019 11-Month Total ...	15	3,172	753	3,939	2	22	97	1	137	258	4,198	4,275	7,885	16,357
2018 11-Month Total ...	17	3,163	743	3,923	2	18	88	1	143	253	4,176	4,346	8,234	16,756


a See "Primary Energy Consumption" in Glossary.  
b See Table 10.2a for notes on series components and estimation.  
c Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.  
d Does not include biofuels that have been blended with petroleum—biofuels are included in "Biomass."  
e Conventional hydroelectric power.  
f Solar photovoltaic (PV) electricity net generation in the commercial sector, both utility-scale and distributed (small-scale). See Tables 10.2a and 10.5.  
g Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.  
h Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Note 1, "Electrical System Energy Losses," at end of section.

R=Revised. NA=Not available. NM=Not meaningful. — =No data reported.  
(s)=Less than 0.5 trillion Btu.  
Notes: • Data are estimates, except for coal totals beginning in 2008; hydroelectric power; solar; wind; and electricity retail sales beginning in 1979.  
• The commercial sector includes commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • See Note 2, "Other Energy Losses," at end of section. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
Sources: See end of section.


**Figure 2.4 Industrial Sector Energy Consumption**

(Quadrillion Btu)


By Major Source, 1949–2019




By Major Source, Monthly



Total, January–November



By Major Source, November 2020



[a] Electricity retail sales.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.

Source: Table 2.4.

**Table 2.4 Industrial Sector Energy Consumption**  
(Trillion Btu)


	Primary Consumption <sup>a</sup>											Elec- tricity Retail Sales <sup>i</sup>	Electrical System Energy Losses <sup>j</sup>	Total <sup>k</sup>
	Fossil Fuels <sup>b</sup>				Renewable Energy <sup>c</sup>						Total Primary			
	Coal	Natural Gas <sup>d</sup>	Petro- leum <sup>e</sup>	Total <sup>f</sup>	Hydro- electric Power <sup>g</sup>	Geo- thermal	Solar <sup>h</sup>	Wind	Bio- mass	Total				
1950 Total .....	5,781	3,546	3,943	13,271	69	NA	NA	NA	532	602	13,872	500	1,852	16,224
1955 Total .....	5,620	4,701	5,093	15,404	38	NA	NA	NA	631	669	16,073	887	2,495	19,455
1960 Total .....	4,543	5,973	5,720	16,231	39	NA	NA	NA	680	719	16,949	1,107	2,739	20,795
1965 Total .....	5,127	7,339	6,750	19,197	33	NA	NA	NA	855	888	20,085	1,463	3,487	25,035
1970 Total .....	4,656	9,536	7,754	21,888	34	NA	NA	NA	1,019	1,053	22,941	1,948	4,716	29,605
1975 Total .....	3,667	8,532	8,092	20,304	32	NA	NA	NA	1,063	1,096	21,400	2,346	5,632	29,379
1980 Total .....	3,155	8,333	9,463	20,916	33	NA	NA	NA	1,600	1,633	22,549	2,781	6,664	31,993
1985 Total .....	2,760	7,032	7,655	17,433	33	NA	NA	NA	1,918	1,951	19,384	2,855	6,518	28,757
1990 Total .....	2,756	8,443	8,199	19,402	31	2	(s)	—	1,684	1,717	21,120	3,226	7,404	31,749
1995 Total .....	2,488	9,592	8,524	20,665	55	3	(s)	—	1,934	1,992	22,657	3,455	7,796	33,908
2000 Total .....	2,256	9,500	8,998	20,820	42	4	(s)	—	1,881	1,928	22,748	3,631	8,208	34,587
2001 Total .....	2,192	8,676	9,110	20,007	33	5	(s)	—	1,681	1,719	21,726	3,400	7,526	32,653
2002 Total .....	2,019	8,832	9,096	20,007	39	5	(s)	—	1,676	1,720	21,727	3,379	7,484	32,590
2003 Total .....	2,041	8,488	9,164	19,745	43	3	(s)	—	1,678	1,725	21,469	3,454	7,565	32,489
2004 Total .....	2,047	8,550	9,753	20,488	33	4	(s)	—	1,815	1,852	22,340	3,473	7,631	33,444
2005 Total .....	1,954	7,907	9,567	19,472	32	4	(s)	—	1,834	1,871	21,343	3,477	7,554	32,374
2006 Total .....	1,914	7,861	9,693	19,529	29	4	1	—	1,892	1,926	21,455	3,451	7,411	32,317
2007 Total .....	1,865	8,074	9,363	19,326	16	5	1	—	1,937	1,958	21,284	3,507	7,515	32,306
2008 Total .....	1,793	8,083	8,502	18,420	17	5	1	—	2,012	2,035	20,455	3,444	7,362	31,261
2009 Total .....	1,392	7,609	7,720	16,698	18	4	2	—	1,948	1,972	18,670	3,130	6,580	28,380
2010 Total .....	1,631	8,278	8,080	17,983	16	4	3	—	2,320	2,343	20,327	3,314	6,934	30,574
2011 Total .....	1,561	8,481	8,052	18,105	17	4	4	(s)	2,375	2,401	20,505	3,382	7,005	30,893
2012 Total .....	1,513	8,819	8,063	18,399	22	4	7	(s)	2,349	2,383	20,781	3,363	6,810	30,954
2013 Total .....	1,546	9,140	8,260	18,929	33	4	9	(s)	2,403	2,449	21,378	3,362	6,785	31,525
2014 Total .....	1,530	9,441	8,021	18,971	12	4	11	1	2,456	2,484	21,455	3,404	6,832	31,691
2015 Total .....	1,380	9,426	8,138	18,926	13	4	14	(s)	2,460	2,491	21,417	3,366	6,578	31,361
2016 Total .....	1,205	9,617	8,247	19,051	12	4	19	1	2,467	2,503	21,554	3,333	6,461	31,347
2017 Total .....	1,195	9,864	8,433	19,463	13	4	22	1	2,450	2,490	21,953	3,358	6,487	31,798
2018 January .....	98	950	742	1,786	1	(s)	1	(s)	211	213	1,999	273	527	2,798
February .....	93	853	631	1,576	1	(s)	1	(s)	190	193	1,769	258	468	2,495
March .....	99	908	751	1,755	1	(s)	2	(s)	208	211	1,967	277	523	2,767
April .....	98	861	655	1,612	1	(s)	2	(s)	197	200	1,812	270	508	2,589
May .....	99	840	735	1,672	1	(s)	2	(s)	206	210	1,881	292	587	2,760
June .....	95	813	737	1,644	1	(s)	2	(s)	200	204	1,848	292	569	2,709
July .....	98	840	758	1,695	1	(s)	3	(s)	210	214	1,909	305	590	2,803
August .....	98	843	834	1,773	1	(s)	2	(s)	211	214	1,988	314	584	2,886
September .....	98	830	732	1,658	1	(s)	2	(s)	195	199	1,857	292	529	2,678
October .....	101	865	809	1,772	1	(s)	2	(s)	205	208	1,980	291	521	2,793
November .....	101	916	705	1,719	1	(s)	2	(s)	202	205	1,924	277	546	2,747
December .....	103	954	664	1,718	1	(s)	1	(s)	212	215	1,932	274	530	2,737
Total .....	1,180	10,474	8,752	20,380	10	4	24	1	2,446	2,486	22,866	3,414	6,481	32,761
2019 January .....	97	989	R 777	R 1,861	1	(s)	2	(s)	207	210	R 2,071	282	537	R 2,889
February .....	93	889	R 615	R 1,597	1	(s)	2	(s)	187	190	R 1,787	261	474	R 2,522
March .....	98	938	R 696	R 1,731	1	(s)	2	(s)	201	205	R 1,936	277	513	R 2,725
April .....	90	855	R 708	R 1,652	1	(s)	3	(s)	193	197	R 1,849	275	505	R 2,629
May .....	95	861	R 749	R 1,703	1	(s)	3	(s)	200	204	R 1,907	289	559	R 2,755
June .....	94	814	R 728	R 1,635	1	(s)	3	(s)	197	201	R 1,836	290	549	R 2,674
July .....	91	837	R 778	R 1,704	1	(s)	3	(s)	204	208	R 1,912	310	577	R 2,799
August .....	91	863	R 790	R 1,743	1	(s)	3	(s)	203	207	R 1,950	311	567	R 2,828
September .....	91	829	R 764	R 1,681	(s)	(s)	3	(s)	189	193	R 1,874	294	520	R 2,688
October .....	93	878	R 793	R 1,762	1	(s)	2	(s)	198	202	R 1,964	288	492	R 2,744
November .....	90	927	R 744	R 1,759	1	(s)	2	(s)	199	202	R 1,960	272	514	R 2,746
December .....	94	978	R 726	R 1,795	1	(s)	2	(s)	208	211	R 2,006	273	503	R 2,783
Total .....	1,117	10,660	R 8,868	R 20,623	9	4	28	1	2,387	2,429	R 23,052	3,420	6,309	R 32,782
2020 January .....	90	989	R 718	R 1,796	1	(s)	2	(s)	206	209	R 2,005	264	488	R 2,757
February .....	90	915	R 669	R 1,672	1	(s)	2	(s)	192	195	R 1,867	258	476	R 2,601
March .....	88	914	R 713	R 1,713	1	(s)	3	(s)	194	198	R 1,911	265	476	R 2,653
April .....	72	826	R 566	R 1,462	1	(s)	3	(s)	164	168	R 1,630	237	422	R 2,290
May .....	69	802	R 635	R 1,506	1	(s)	3	(s)	178	182	R 1,688	243	473	R 2,404
June .....	74	781	R 624	R 1,479	1	(s)	3	1	177	182	R 1,660	257	495	R 2,412
July .....	70	824	R 697	R 1,591	1	(s)	3	1	187	193	R 1,784	277	527	R 2,588
August .....	72	838	R 723	R 1,633	1	(s)	3	1	185	190	R 1,823	282	531	R 2,636
September .....	71	R 828	R 678	R 1,577	1	(s)	3	1	183	188	R 1,765	264	468	R 2,498
October .....	84	880	R 736	R 1,699	1	(s)	3	1	191	196	R 1,894	279	497	R 2,670
November .....	72	895	734	1,698	1	(s)	2	1	194	198	1,897	259	494	2,649
11-Month Total ...	853	9,493	7,492	17,827	8	4	30	5	2,051	2,098	19,925	2,886	5,348	28,159
2019 11-Month Total ...	1,023	9,681	8,142	18,828	8	4	26	1	2,179	2,218	21,046	3,147	5,807	30,000
2018 11-Month Total ...	1,076	9,520	8,088	18,662	9	4	23	1	2,235	2,272	20,933	3,140	5,951	30,025

<sup>a</sup> See "Primary Energy Consumption" in Glossary.  
<sup>b</sup> Includes non-combustion use of fossil fuels.  
<sup>c</sup> See Table 10.2b for notes on series components and estimation.  
<sup>d</sup> Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.  
<sup>e</sup> Does not include biofuels that have been blended with petroleum—biofuels are included in "Biomass."  
<sup>f</sup> Includes coal coke net imports, which are not separately displayed. See Tables 1.4a and 1.4b.  
<sup>g</sup> Conventional hydroelectric power.  
<sup>h</sup> Solar photovoltaic (PV) electricity net generation in the industrial sector, both utility-scale and distributed (small-scale). See Tables 10.2b and 10.5.  
<sup>i</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.  
<sup>j</sup> Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total


electricity retail sales. See Note 1, "Electrical System Energy Losses," at end of section.  
<sup>k</sup> R=Revised. NA=Not available. —=No data reported. (s)=Less than 0.5 trillion Btu.  
Notes: • Data are estimates, except for coal totals; hydroelectric power in 1949–1978 and 1989 forward; solar; wind; and electricity retail sales. • The industrial sector includes industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • See Note 2, "Other Energy Losses," at end of section. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
Sources: See end of section.

**Figure 2.5 Transportation Sector Energy Consumption**  
(Quadrillion Btu)


By Major Source, 1949–2019




By Major Source, Monthly



Total, January–November



Total, Monthly



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.  
Source: Table 2.5.

**Table 2.5 Transportation Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>						Electricity Retail Sales <sup>e</sup>	Electrical System Energy Losses <sup>f</sup>	Total
	Fossil Fuels				Renewable Energy <sup>b</sup>	Total Primary			
	Coal	Natural Gas <sup>c</sup>	Petroleum <sup>d</sup>	Total	Biomass				
1950 Total .....	1,564	130	6,690	8,383	NA	8,383	23	86	8,492
1955 Total .....	421	254	8,799	9,474	NA	9,474	20	56	9,550
1960 Total .....	75	359	10,125	10,560	NA	10,560	10	26	10,596
1965 Total .....	16	517	11,866	12,399	NA	12,399	10	24	12,432
1970 Total .....	7	745	15,311	16,062	NA	16,062	11	26	16,098
1975 Total .....	1	595	17,615	18,211	NA	18,211	10	24	18,245
1980 Total .....	(g)	650	19,009	19,659	NA	19,659	11	27	19,697
1985 Total .....	(g)	519	19,472	19,992	50	20,042	14	32	20,088
1990 Total .....	(g)	679	21,626	22,305	60	22,366	16	37	22,419
1995 Total .....	(g)	724	22,920	23,644	112	23,757	17	38	23,812
2000 Total .....	(g)	672	25,649	26,321	135	26,456	18	42	26,515
2001 Total .....	(g)	658	25,379	26,037	142	26,179	20	43	26,242
2002 Total .....	(g)	699	25,879	26,578	170	26,747	19	42	26,808
2003 Total .....	(g)	627	25,950	26,577	230	26,807	23	51	26,881
2004 Total .....	(g)	602	26,856	27,458	290	27,748	25	54	27,826
2005 Total .....	(g)	624	27,217	27,840	339	28,179	26	56	28,261
2006 Total .....	(g)	625	27,518	28,143	475	28,618	25	54	28,697
2007 Total .....	(g)	663	27,462	28,126	602	28,727	28	60	28,815
2008 Total .....	(g)	692	25,823	26,515	825	27,339	26	56	27,421
2009 Total .....	(g)	715	24,860	25,575	935	26,510	27	56	26,592
2010 Total .....	(g)	719	25,103	25,822	1,075	26,897	26	55	26,978
2011 Total .....	(g)	734	24,626	25,360	1,159	26,518	26	54	26,599
2012 Total .....	(g)	780	24,111	24,890	1,160	26,050	25	51	26,126
2013 Total .....	(g)	887	24,362	25,249	1,284	26,533	26	53	26,612
2014 Total .....	(g)	760	24,727	25,487	1,302	26,789	26	53	26,869
2015 Total .....	(g)	745	25,082	25,827	1,334	27,161	26	51	27,238
2016 Total .....	(g)	757	25,511	26,268	1,443	27,710	26	50	27,786
2017 Total .....	(g)	799	25,702	26,500	1,439	27,939	26	50	28,014
2018 January .....	(g)	107	2,042	2,149	113	2,262	3	5	2,269
February .....	(g)	87	1,869	1,956	99	2,055	2	4	2,061
March .....	(g)	89	2,208	2,298	119	2,416	2	4	2,422
April .....	(g)	75	2,132	2,207	112	2,319	2	4	2,325
May .....	(g)	66	2,250	2,315	127	2,442	2	4	2,448
June .....	(g)	66	2,246	2,312	121	2,433	2	4	2,439
July .....	(g)	75	2,303	2,378	124	2,501	2	4	2,508
August .....	(g)	74	2,343	2,417	129	2,546	2	4	2,553
September .....	(g)	69	2,135	2,204	113	2,316	2	4	2,322
October .....	(g)	73	2,211	2,283	122	2,406	2	4	2,412
November .....	(g)	86	2,131	2,217	117	2,334	2	4	2,341
December .....	(g)	96	2,143	2,239	119	2,358	2	4	2,365
Total .....	(g)	962	26,012	26,975	1,415	28,389	26	50	28,465
2019 January .....	(g)	114	R 2,079	R 2,193	107	R 2,300	2	4	R 2,307
February .....	(g)	101	R 1,914	R 2,015	108	R 2,123	2	4	R 2,129
March .....	(g)	97	R 2,159	R 2,256	117	R 2,372	2	4	R 2,379
April .....	(g)	73	R 2,149	R 2,222	115	R 2,337	2	4	R 2,343
May .....	(g)	71	R 2,240	R 2,310	126	R 2,436	2	4	R 2,443
June .....	(g)	70	R 2,230	R 2,300	122	R 2,422	2	4	R 2,428
July .....	(g)	80	R 2,294	R 2,374	124	R 2,498	2	4	R 2,504
August .....	(g)	81	R 2,338	R 2,419	122	R 2,541	2	4	R 2,548
September .....	(g)	74	R 2,131	R 2,205	113	R 2,318	2	4	R 2,324
October .....	(g)	77	R 2,239	R 2,316	121	R 2,437	2	3	R 2,442
November .....	(g)	92	R 2,092	R 2,184	116	R 2,301	2	4	R 2,307
December .....	(g)	105	R 2,123	R 2,228	119	R 2,348	2	4	R 2,354
Total .....	(g)	1,035	R 25,988	R 27,023	1,411	R 28,433	26	48	R 28,507
2020 January .....	(g)	109	R 2,060	R 2,170	113	R 2,282	2	4	R 2,289
February .....	(g)	101	R 1,938	R 2,038	106	R 2,145	2	4	R 2,151
March .....	(g)	91	R 1,873	R 1,964	97	R 2,061	2	4	R 2,067
April .....	(g)	76	R 1,427	R 1,503	75	R 1,577	2	3	R 1,582
May .....	(g)	71	R 1,639	R 1,709	98	R 1,808	2	3	R 1,812
June .....	(g)	72	R 1,809	R 1,882	109	R 1,991	2	3	R 1,995
July .....	(g)	84	R 1,963	R 2,047	115	R 2,163	2	4	R 2,168
August .....	(g)	81	R 1,983	R 2,064	111	R 2,175	2	4	R 2,181
September .....	(g)	74	R 1,895	R 1,969	112	R 2,081	2	3	R 2,085
October .....	(g)	79	R 1,941	R 2,019	108	R 2,127	2	3	R 2,132
November .....	(g)	82	1,815	1,897	107	2,004	2	3	2,009
11-Month Total ...	(g)	919	20,343	21,262	1,151	22,414	20	38	22,472
2019 11-Month Total ...	(g)	931	23,864	24,795	1,291	26,086	24	44	26,154
2018 11-Month Total ...	(g)	867	23,869	24,736	1,295	26,031	24	45	26,100

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> See Table 10.2b for notes on series components.

<sup>c</sup> Natural gas only; does not include supplemental gaseous fuels—see Note 3, "Supplemental Gaseous Fuels," at end of Section 4. Data are for natural gas consumed in the operation of pipelines (primarily in compressors) and small amounts consumed as vehicle fuel—see Table 4.3.

<sup>d</sup> Does not include biofuels that have been blended with petroleum—biofuels are included in "Biomass." Includes non-combustion use of lubricants.

<sup>e</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

<sup>f</sup> Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Note 1, "Electrical System Energy Losses," at end of

section.

<sup>g</sup> Beginning in 1978, the small amounts of coal consumed for transportation are reported as industrial sector consumption.

R=Revised. NA=Not available.

Notes: • Data are estimates, except for coal totals through 1977; and electricity retail sales beginning in 1979. • See Note 2, "Other Energy Losses," at end of section. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 2.6 Electric Power Sector Energy Consumption**

(Quadrillion Btu)


By Major Source, 1949–2019




By Major Source, Monthly



Total, January–November



By Major Source, November 2020



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.

Source: Table 2.6.



**Table 2.6 Electric Power Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>												
	Fossil Fuels				Nuclear Electric Power	Renewable Energy <sup>b</sup>						Electricity Net Imports <sup>f</sup>	Total Primary
	Coal	Natural Gas <sup>c</sup>	Petroleum	Total		Hydro-electric Power <sup>d</sup>	Geo-thermal	Solar <sup>e</sup>	Wind	Bio-mass	Total		
1950 Total	2,199	651	472	3,322	0	1,346	NA	NA	NA	5	1,351	6	4,679
1955 Total	3,458	1,194	471	5,123	0	1,322	NA	NA	NA	3	1,325	14	6,461
1960 Total	4,228	1,785	553	6,565	6	1,569	(s)	NA	NA	2	1,571	15	8,158
1965 Total	5,821	2,395	722	8,938	43	2,026	2	NA	NA	3	2,031	(s)	11,012
1970 Total	7,227	4,054	2,117	13,399	239	2,600	6	NA	NA	4	2,609	7	16,253
1975 Total	8,786	3,240	3,166	15,191	1,900	3,122	34	NA	NA	2	3,158	21	20,270
1980 Total	12,123	3,778	2,634	18,534	2,739	2,867	53	NA	NA	4	2,925	71	24,269
1985 Total	14,542	3,135	1,090	18,767	4,076	2,937	97	(s)	(s)	14	3,049	140	26,032
1990 Total	16,261	3,309	1,289	20,859	6,104	3,014	161	4	29	317	3,524	8	30,495
1995 Total	17,466	4,302	755	22,523	7,075	3,149	138	5	33	422	3,747	134	33,479
2000 Total	20,220	5,293	1,144	26,658	7,862	2,768	144	5	57	453	3,427	115	38,062
2001 Total	19,614	5,458	1,276	26,348	8,029	2,209	142	6	70	337	2,763	75	37,215
2002 Total	19,783	5,767	961	26,511	8,145	2,650	147	6	105	380	3,288	72	38,016
2003 Total	20,185	5,246	1,205	26,636	7,960	2,749	146	5	113	397	3,411	22	38,028
2004 Total	20,305	5,595	1,201	27,101	8,223	2,655	148	6	142	388	3,339	39	38,701
2005 Total	20,737	6,015	1,222	27,974	8,161	2,670	147	6	178	406	3,406	85	39,626
2006 Total	20,462	6,375	637	27,474	8,215	2,839	145	5	264	412	3,665	63	39,417
2007 Total	20,808	7,005	648	28,461	8,459	2,430	145	6	341	423	3,345	107	40,371
2008 Total	20,513	6,829	459	27,801	8,426	2,494	146	9	546	435	3,630	112	39,969
2009 Total	18,225	7,022	382	25,630	8,355	2,650	146	9	721	441	3,967	116	38,069
2010 Total	19,133	7,528	370	27,031	8,434	2,521	148	12	923	459	4,064	89	39,619
2011 Total	18,035	7,712	295	26,042	8,269	3,085	149	17	1,167	437	4,855	127	39,293
2012 Total	15,821	9,287	214	25,322	8,062	2,606	148	40	1,339	453	4,586	161	38,131
2013 Total	16,451	8,376	255	25,082	8,244	2,529	151	83	1,600	470	4,833	197	38,357
2014 Total	16,427	8,362	295	25,085	8,338	2,454	151	165	1,726	530	5,026	182	38,629
2015 Total	14,138	9,926	276	24,341	8,337	2,308	148	228	1,776	525	4,985	227	37,890
2016 Total	12,996	10,301	244	23,542	8,427	2,459	146	328	2,094	505	5,531	227	37,727
2017 Total	12,622	9,555	218	22,395	8,419	2,752	147	486	2,341	510	6,235	192	37,241
2018 January	1,229	811	64	2,103	780	227	12	30	233	46	548	14	3,446
February	868	711	17	1,596	677	226	12	35	211	42	525	12	2,811
March	843	780	15	1,638	701	234	12	46	241	44	577	15	2,931
April	768	725	17	1,510	618	255	11	55	240	39	599	10	2,737
May	896	873	16	1,785	704	276	13	62	218	40	608	14	3,112
June	1,062	981	20	2,063	729	250	12	67	225	42	596	15	3,402
July	1,209	1,261	20	2,489	758	228	12	61	150	44	494	15	3,756
August	1,207	1,221	20	2,449	756	199	12	60	181	43	496	17	3,717
September	1,021	1,061	19	2,101	677	174	12	54	168	37	445	11	3,234
October	917	915	16	1,848	621	177	12	45	193	39	465	10	2,944
November	980	786	18	1,784	669	198	12	34	200	40	484	9	2,945
December	1,054	786	18	1,858	749	206	13	28	221	41	509	11	3,127
Total	12,053	10,912	260	23,225	8,438	2,651	145	576	2,480	496	6,348	152	38,163
2019 January	1,058	876	22	1,956	770	220	12	32	216	41	520	11	3,257
February	853	804	16	1,673	676	203	11	34	201	36	484	11	2,843
March	834	840	15	1,688	680	233	12	52	228	37	563	8	2,939
April	632	763	12	1,407	633	247	11	60	257	34	607	8	2,655
May	757	862	18	1,637	701	284	12	63	229	37	624	10	2,972
June	837	1,021	16	1,874	718	249	12	70	199	37	567	12	3,172
July	1,057	1,294	18	2,370	754	221	12	72	196	40	540	13	3,676
August	991	1,318	18	2,327	751	200	12	69	178	40	500	14	3,592
September	893	1,115	15	2,023	690	164	12	60	218	37	490	12	3,215
October	709	966	11	1,686	648	162	10	54	245	35	506	7	2,848
November	793	845	13	1,651	670	179	8	38	223	36	485	12	2,818
December	766	941	15	1,722	763	190	10	30	236	39	506	14	3,005
Total	10,181	11,645	189	22,015	8,452	2,552	134	635	2,623	448	6,392	133	36,992
2020 January	696	961	17	1,674	774	225	11	41	250	38	566	11	3,025
February	606	906	13	1,526	689	234	11	50	259	36	590	10	2,815
March	548	907	14	1,469	668	208	13	57	260	37	574	13	2,724
April	447	788	13	1,247	618	195	13	71	261	33	572	11	2,448
May	508	860	14	1,381	672	271	13	86	251	35	655	12	2,721
June	693	1,078	17	1,789	702	258	12	84	265	33	653	13	3,156
July	943	1,416	20	2,379	725	246	12	92	200	35	586	19	3,708
August	955	1,322	18	2,294	720	215	12	83	200	39	549	20	3,584
September	732	1,070	12	1,815	686	170	12	68	206	33	489	13	3,002
October	642	984	13	1,638	620	163	12	65	261	33	534	R 11	R 2,803
November	650	791	14	1,455	645	196	13	52	300	34	595	13	2,707
11-Month Total	7,419	11,083	164	18,666	7,519	2,380	134	749	2,713	386	6,363	146	32,693
2019 11-Month Total	9,415	10,704	173	20,292	7,689	2,362	124	604	2,388	409	5,887	119	33,987
2018 11-Month Total	10,999	10,125	242	21,367	7,689	2,444	132	548	2,259	455	5,838	141	35,034

<sup>a</sup> See "Primary Energy Consumption" in Glossary.  
<sup>b</sup> See Table 10.2c for notes on series components.  
<sup>c</sup> Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.  
<sup>d</sup> Conventional hydroelectric power.  
<sup>e</sup> Solar photovoltaic (PV) and solar thermal electricity net generation in the electric power sector. See Tables 10.2c and 10.5.  
<sup>f</sup> Net imports equal imports minus exports.  
<sup>g</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.  
R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for fuels consumed to produce electricity and useful thermal output.  
• The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
Sources: See end of section.

**Table 2.7 U.S. Government Energy Consumption by Agency, Fiscal Years**  
(Trillion Btu)

Fiscal Year <sup>a</sup>	Agri- culture	Defense	DHS <sup>b</sup>	Energy	GSA <sup>c</sup>	HHS <sup>d</sup>	Interior	Justice	NASA <sup>e</sup>	Postal Service	Trans- portation	Veterans Affairs	Other <sup>f</sup>	Total
1975 .....	9.5	1,360.2	--	50.4	22.3	6.5	9.4	5.9	13.4	30.5	19.3	27.1	10.5	1,565.0
1976 .....	9.3	1,183.3	--	50.3	20.6	6.7	9.4	5.7	12.4	30.0	19.5	25.0	11.2	1,383.4
1977 .....	8.9	1,192.3	--	51.6	20.4	6.9	9.5	5.9	12.0	32.7	20.4	25.9	11.9	1,398.5
1978 .....	9.1	1,157.8	--	50.1	20.4	6.5	9.2	5.9	11.2	30.9	20.6	26.8	12.4	1,360.9
1979 .....	9.2	1,175.8	--	49.6	19.6	6.4	10.4	6.4	11.1	29.3	19.6	25.7	12.3	1,375.4
1980 .....	8.6	1,183.1	--	47.4	18.1	6.0	8.5	5.7	10.4	27.2	19.2	24.8	12.3	1,371.2
1981 .....	7.9	1,239.5	--	47.3	18.0	6.7	7.6	5.4	10.0	27.9	18.8	24.0	11.1	1,424.2
1982 .....	7.6	1,264.5	--	49.0	18.1	6.4	7.4	5.8	10.1	27.5	19.1	24.2	11.6	1,451.4
1983 .....	7.4	1,248.3	--	49.5	16.1	6.2	7.7	5.5	10.3	26.5	19.4	24.1	10.8	1,431.8
1984 .....	7.9	1,292.1	--	51.6	16.2	6.4	8.4	6.4	10.6	27.7	19.8	24.6	10.7	1,482.5
1985 .....	8.4	1,250.6	--	52.2	20.7	6.0	7.8	8.2	10.9	27.8	19.6	25.1	13.1	1,450.3
1986 .....	6.8	1,222.8	--	46.9	14.0	6.2	6.9	8.6	11.2	28.0	19.4	25.0	10.8	1,406.7
1987 .....	7.3	1,280.5	--	48.5	13.1	6.6	6.6	8.1	11.3	28.5	19.0	24.9	11.9	1,466.3
1988 .....	7.8	1,165.8	--	49.9	12.4	6.4	7.0	9.4	11.3	29.6	18.7	26.3	15.8	1,360.3
1989 .....	8.7	1,274.4	--	44.2	12.7	6.7	7.1	7.7	12.4	30.3	18.5	26.2	15.6	1,464.7
1990 .....	9.6	1,241.7	--	43.5	17.5	7.1	7.4	7.0	12.4	30.6	19.0	24.9	17.5	1,438.0
1991 .....	9.6	1,269.3	--	42.1	14.0	6.2	7.1	8.0	12.5	30.8	19.0	25.1	18.1	1,461.7
1992 .....	9.1	1,104.0	--	44.3	13.8	6.8	7.0	7.5	12.6	31.7	17.0	25.3	15.7	1,294.8
1993 .....	9.3	1,048.8	--	43.4	14.1	7.2	7.5	9.1	12.4	33.7	19.4	25.7	16.2	1,246.8
1994 .....	9.4	977.0	--	42.1	14.0	7.5	7.9	10.3	12.6	35.0	19.8	25.6	17.1	1,178.2
1995 .....	9.0	926.0	--	47.3	13.7	6.1	6.4	10.2	12.4	36.2	18.7	25.4	17.1	1,128.5
1996 .....	9.1	904.5	--	44.6	14.5	6.6	4.3	12.1	11.5	36.4	19.6	26.8	17.7	1,107.7
1997 .....	7.4	880.0	--	43.1	14.4	7.9	6.6	12.0	12.0	40.8	19.1	27.3	20.8	1,091.2
1998 .....	7.9	837.1	--	31.5	14.1	7.4	6.4	15.8	11.7	39.5	18.5	27.6	19.5	1,037.1
1999 .....	7.8	810.7	--	27.0	14.4	7.1	7.5	15.4	11.4	39.8	22.6	27.5	19.8	1,010.9
2000 .....	7.4	779.1	--	30.5	17.6	8.0	7.8	19.7	11.1	43.3	21.2	27.0	20.3	993.1
2001 .....	7.4	787.2	--	31.1	18.4	8.5	9.5	19.7	10.9	43.4	17.8	27.7	20.7	1,002.3
2002 .....	7.2	837.5	--	30.7	17.5	8.0	8.2	17.7	10.7	41.6	18.3	27.7	18.4	1,043.4
2003 .....	7.7	895.1	18.3	31.9	18.5	10.1	7.3	22.7	10.8	50.9	5.5	30.6	22.7	1,132.3
2004 .....	7.0	960.7	23.5	31.4	18.3	8.8	8.7	17.5	9.9	50.5	5.2	29.9	20.4	1,191.7
2005 .....	7.5	933.2	18.9	29.6	18.4	9.6	8.6	18.8	10.3	53.5	5.0	30.0	23.2	1,166.4
2006 .....	6.8	843.7	17.1	32.9	18.2	9.3	8.1	23.5	10.2	51.8	4.6	29.3	20.9	1,076.4
2007 .....	6.8	864.6	17.1	31.5	19.1	9.9	7.5	20.7	10.6	45.8	5.6	30.0	21.0	1,090.2
2008 .....	6.5	910.8	21.7	32.1	18.8	10.3	7.1	19.0	10.8	47.1	7.7	29.0	22.4	1,143.2
2009 .....	6.6	874.3	18.6	31.1	18.6	10.8	7.9	16.5	10.2	44.2	4.3	29.9	21.8	1,094.8
2010 .....	6.8	889.9	21.2	31.7	18.8	10.4	7.3	15.7	10.1	43.3	5.7	30.2	21.8	1,112.7
2011 .....	8.3	890.3	20.3	33.1	18.5	10.5	7.3	13.9	10.1	43.0	6.7	30.6	21.4	1,114.1
2012 .....	6.7	828.5	20.1	30.3	16.3	10.0	6.7	15.1	8.9	40.8	5.6	29.7	20.5	1,039.3
2013 .....	7.3	749.5	18.9	28.9	16.4	10.5	6.2	15.3	8.7	41.9	5.3	29.9	20.4	959.3
2014 .....	6.3	730.6	18.5	29.4	17.0	9.5	6.2	15.6	8.3	43.0	5.2	31.4	20.6	941.5
2015 .....	6.2	734.5	17.9	30.1	16.3	9.0	6.8	16.2	8.4	44.0	6.0	30.7	19.8	945.8
2016 .....	6.2	709.2	18.1	28.9	15.8	8.7	6.4	15.6	8.5	43.9	6.0	30.3	19.5	917.2
2017 .....	6.3	707.9	19.2	28.8	15.0	8.8	5.9	15.5	8.6	43.7	6.6	29.1	19.7	915.1
2018 .....	6.1	690.6	16.8	27.3	15.6	10.0	6.1	16.2	8.4	45.5	5.8	29.7	18.8	897.0
2019 .....	5.9	682.1	16.2	26.4	15.4	9.8	6.2	15.8	8.6	46.0	5.9	31.9	18.9	889.0

<sup>a</sup> For 1975 and 1976, the U.S. Government's fiscal year was July 1 through June 30. Beginning in 1977, the U.S. Government's fiscal year is October 1 through September 30 (for example, fiscal year 2014 is October 2013 through September 2014).

<sup>b</sup> U.S. Department of Homeland Security.

<sup>c</sup> General Services Administration.

<sup>d</sup> U.S. Department of Health and Human Services.

<sup>e</sup> National Aeronautics and Space Administration.

<sup>f</sup> Includes all U.S. government agencies not separately displayed. See <http://ctsedweb.ee.doe.gov/Annual/Report/AgencyReference.aspx> for agency list.  
-- =Not applicable.

Notes: • Data in this table are developed using conversion factors that often

differ from those in Tables A1--A6. • Data include energy consumed at foreign installations and in foreign operations, including aviation and ocean bunkering, primarily by the U.S. Department of Defense. U.S. Government energy use for electricity generation and uranium enrichment is excluded. • Totals may not equal sum of components due to independent rounding.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all annual data beginning in 1975.

Sources: U.S. Department of Energy, Office of Energy Efficiency and Renewable Energy, Federal Energy Management Program. See <http://ctsedweb.ee.doe.gov/Annual/Report/Report.aspx>, "A-1 Total Site-Delivered Energy Use in All End-Use Sectors, by Federal Agency (Billion Btu)".

**Table 2.8 U.S. Government Energy Consumption by Source, Fiscal Years**  
(Trillion Btu)

Fiscal Year <sup>a</sup>	Coal	Natural Gas <sup>b</sup>	Petroleum						Other Mobility Fuels <sup>f</sup>	Electricity	Purchased Steam and Other <sup>g</sup>	Total
			Aviation Gasoline	Fuel Oil <sup>c</sup>	Jet Fuel	LPG <sup>d</sup>	Motor Gasoline <sup>e</sup>	Total				
1975 .....	77.9	166.2	22.0	376.0	707.4	5.6	63.2	1,174.2	0.0	141.5	5.1	1,565.0
1976 .....	71.3	151.8	11.6	329.7	610.0	4.7	60.4	1,016.4	.0	139.3	4.6	1,383.4
1977 .....	68.4	141.2	8.8	348.5	619.2	4.1	61.4	1,042.1	.0	141.1	5.7	1,398.5
1978 .....	66.0	144.7	6.2	332.3	601.1	3.0	60.1	1,002.9	.0	141.0	6.4	1,360.9
1979 .....	65.1	148.9	4.7	327.1	618.6	3.7	59.1	1,013.1	.0	141.2	7.1	1,375.4
1980 .....	63.5	147.3	4.9	307.7	638.7	3.8	56.5	1,011.6	.2	141.9	6.8	1,371.2
1981 .....	65.1	142.2	4.6	351.3	653.3	3.5	53.2	1,066.0	.2	144.5	6.2	1,424.2
1982 .....	68.6	146.2	3.6	349.4	672.7	3.7	53.1	1,082.5	.2	147.5	6.2	1,451.4
1983 .....	62.4	147.8	2.6	329.5	673.4	3.8	51.6	1,060.8	.2	151.5	9.0	1,431.8
1984 .....	65.3	157.4	1.9	342.9	693.7	3.9	51.2	1,093.6	.2	155.9	10.1	1,482.5
1985 .....	64.8	149.9	1.9	292.6	705.7	3.8	50.4	1,054.3	.2	167.2	13.9	1,450.3
1986 .....	63.8	140.9	1.4	271.6	710.2	3.6	45.3	1,032.1	.3	155.8	13.7	1,406.7
1987 .....	67.0	145.6	1.0	319.5	702.3	3.6	43.1	1,069.5	.4	169.9	13.9	1,466.3
1988 .....	60.2	144.6	6.0	284.8	617.2	2.7	41.2	951.9	.4	171.2	32.0	1,360.3
1989 .....	48.7	152.4	.8	245.3	761.7	3.5	41.1	1,052.4	2.2	188.6	20.6	1,464.7
1990 .....	44.3	159.4	.5	245.2	732.4	3.8	37.2	1,019.1	2.6	193.6	19.1	1,438.0
1991 .....	45.9	154.1	.4	232.6	774.5	3.0	34.1	1,044.7	6.0	192.7	18.3	1,461.7
1992 .....	51.7	151.2	1.0	200.6	628.2	3.0	35.6	868.4	8.4	192.5	22.5	1,294.8
1993 .....	38.3	152.9	.7	187.0	612.4	3.5	34.5	838.1	5.8	193.1	18.6	1,246.8
1994 .....	35.0	143.9	.6	198.5	550.7	3.2	29.5	782.6	7.7	190.9	18.2	1,178.2
1995 .....	31.7	149.4	.3	178.4	522.3	3.0	31.9	735.9	8.4	184.8	18.2	1,128.5
1996 .....	23.3	147.3	.2	170.5	513.0	3.1	27.6	714.4	18.7	184.0	20.1	1,107.7
1997 .....	22.5	153.8	.3	180.0	475.7	2.6	39.0	697.6	14.5	183.6	19.2	1,091.2
1998 .....	23.9	140.4	.2	174.5	445.5	3.5	43.0	666.8	5.9	181.4	18.8	1,037.1
1999 .....	21.2	137.4	.1	162.1	444.7	2.4	41.1	650.4	.4	180.0	21.5	1,010.9
2000 .....	22.7	133.8	.2	171.3	403.1	2.5	43.9	621.0	1.8	193.6	20.2	993.1
2001 .....	18.8	133.7	.2	176.9	415.2	3.1	42.5	638.0	4.8	188.4	18.6	1,002.3
2002 .....	16.9	133.7	.2	165.6	472.9	2.8	41.3	682.8	3.2	188.3	18.5	1,043.4
2003 .....	18.1	135.5	.3	190.8	517.9	3.2	46.3	758.4	3.3	193.8	23.2	1,132.3
2004 .....	17.4	135.3	.2	261.4	508.2	2.9	44.1	816.9	3.1	197.1	22.0	1,191.7
2005 .....	17.1	135.7	.4	241.4	492.2	3.4	48.8	786.1	5.6	197.6	24.3	1,166.4
2006 .....	23.5	132.6	.6	209.3	442.6	2.7	48.3	703.6	2.1	196.7	18.2	1,076.4
2007 .....	20.4	131.5	.4	212.9	461.1	2.7	46.5	723.7	2.9	194.9	16.7	1,090.2
2008 .....	20.8	129.6	.4	198.4	525.4	2.3	49.0	775.4	3.6	196.1	17.7	1,143.2
2009 .....	20.3	131.7	.3	166.4	505.7	3.2	48.3	723.9	10.1	191.3	17.7	1,094.8
2010 .....	20.0	130.1	.4	157.8	535.8	2.5	51.3	747.7	3.0	193.7	18.2	1,112.7
2011 .....	18.5	124.7	.9	166.5	533.6	2.0	52.7	755.8	2.7	193.2	19.1	1,114.1
2012 .....	15.9	116.2	.4	148.6	493.5	1.7	50.1	694.4	3.1	187.2	22.5	1,039.3
2013 .....	14.3	122.5	.7	140.0	424.0	1.9	46.6	613.2	2.8	184.7	21.8	959.3
2014 .....	13.5	125.6	.3	133.5	414.3	1.8	44.9	594.8	3.6	182.1	21.9	941.5
2015 .....	12.6	122.2	.3	134.4	418.9	1.8	46.8	602.2	3.7	184.3	20.9	945.8
2016 .....	10.2	115.4	.3	129.7	403.9	1.7	46.5	582.2	3.6	184.5	21.4	917.2
2017 .....	9.1	115.1	.3	135.1	400.1	1.5	46.4	583.5	2.7	181.7	23.0	915.1
2018 .....	6.2	125.8	.3	127.8	383.2	1.7	45.5	558.5	3.0	180.0	23.6	897.0
2019 .....	5.0	131.6	.3	125.4	376.9	1.8	46.6	551.0	2.7	178.1	20.6	889.0

<sup>a</sup> For 1975 and 1976, the U.S. Government's fiscal year was July 1 through June 30. Beginning in 1977, the U.S. Government's fiscal year is October 1 through September 30 (for example, fiscal year 2014 is October 2013 through September 2014).

<sup>b</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, including diesel fuel; and residual fuel oil, including Navy Special.

<sup>d</sup> Liquefied petroleum gases, primarily propane.

<sup>e</sup> Includes E10 (a mixture of 10% ethanol and 90% motor gasoline) and E15 (a mixture of 15% ethanol and 85% motor gasoline).

<sup>f</sup> Other types of fuel used in vehicles and equipment. Primarily includes alternative fuels such as compressed natural gas (CNG); liquefied natural gas (LNG); E85 (a mixture of 85% ethanol and 15% motor gasoline); B20 (a mixture of 20% biodiesel and 80% diesel fuel); B100 (100% biodiesel); hydrogen; and methanol.

<sup>g</sup> Other types of energy used in facilities. Primarily includes chilled water, but also includes small amounts of renewable energy such as wood and solar thermal.

Notes: • Data in this table are developed using conversion factors that often differ from those in Tables A1–A6. • Data include energy consumed at foreign installations and in foreign operations, including aviation and ocean bunkering, primarily by the U.S. Department of Defense. U.S. Government energy use for electricity generation and uranium enrichment is excluded. • Totals may not equal sum of components due to independent rounding.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all annual data beginning in 1975.

Sources: U.S. Department of Energy, Office of Energy Efficiency and Renewable Energy, Federal Energy Management Program. See <http://ctsweb.doe.gov/Annual/Report/Report.aspx>, "A-5 Historical Federal Energy Consumption and Cost Data by Agency and Energy Type (FY 1975 to Present)".

## Energy Consumption by Sector

**Note 1. Electrical System Energy Losses.** Electrical system energy losses are calculated as the difference between total primary consumption by the electric power sector (see Table 2.6) and the total energy content of electricity retail sales (see Tables 7.6 and A6). Most of these losses occur at steam-electric power plants (conventional and nuclear) in the conversion of heat energy into mechanical energy to turn electric generators. The loss is a thermodynamically necessary feature of the steam-electric cycle. Part of the energy input-to-output losses is a result of imputing fossil energy equivalent inputs for hydroelectric, geothermal, solar thermal, photovoltaic, and wind energy sources. In addition to conversion losses, other losses include power plant use of electricity, transmission and distribution of electricity from power plants to end-use consumers (also called "line losses"), and unaccounted-for electricity. Total losses are allocated to the end-use sectors in proportion to each sector's share of total electricity sales. Overall, about two thirds of total energy input is lost in conversion. Currently, of electricity generated, approximately 5% is lost in plant use and 7% is lost in transmission and distribution.

**Note 2. Other Energy Losses.** Similar to electrical system energy losses, there are also other energy losses from energy consumption not separately identified. There are losses in the production of energy, the transformation of one form of energy to another form of energy, and the distribution and use of energy. For example, there are transformation losses in the process of refining crude oil into usable petroleum products, processing natural gas into marketable dry gas, and in the process of converting energy from the sun into usable energy with solar panels. All uses of primary energy have efficiency losses, usually in the form of heat, when energy is converted to do useful work. Examples include when motor gasoline is burned to move vehicles, when natural gas is burned to heat homes, or in any household appliance that uses electricity. The Lawrence Livermore National Laboratory estimates primary energy losses by end-use sector by applying an end-use efficiency factor to EIA's *Monthly Energy Review* consumption data. <https://flowcharts.llnl.gov/>.

**Note 3. Energy Consumption Data and Surveys.** Most of the data in this section of the Monthly Energy Review (MER) are developed from a group of energy-related surveys, typically called "supply surveys," conducted by the U.S. Energy Information Administration (EIA). Supply surveys are directed to suppliers and marketers of specific energy sources. They measure the quantities of specific energy sources produced, or the quantities supplied to the market, or both. The data obtained from EIA's supply surveys are integrated to yield the summary consumption statistics published in this section (and in Section 1) of the MER.

Users of EIA's energy consumption statistics should be aware of a second group of energy-related surveys, typically called "consumption surveys." Consumption surveys gather information on the types of energy consumed by end users of energy, along with the characteristics of those end users that can be associated with energy use. For example, the "Manufacturing Energy Consumption Survey" belongs to the consumption survey group because it collects information directly from end users (the manufacturing establishments). There are important differences between the supply and consumption surveys that need to be taken into account in any analysis that uses both data sources. For information on those differences, see "Energy Consumption by End-Use Sector, A Comparison of Measures by Consumption and Supply Surveys," DOE/EIA-0533, U.S. Energy Information Administration, Washington, DC, April 6, 1990.

### Table 2.2 Sources

#### *Coal*

1949–2007: Residential sector coal consumption data from Table 6.2 are converted to Btu by multiplying by the residential and commercial sectors coal consumption heat content factors in Table A5.

#### *Natural Gas*

1949–1979: Residential sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4.

1980 forward: Residential sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4. The residential sector portion of supplemental gaseous fuels data in Btu is estimated using the method described in

Note 3, “Supplemental Gaseous Fuels,” at the end of Section 4. Residential sector natural gas (excluding supplemental gaseous fuels) consumption is equal to residential sector natural gas (including supplemental gaseous fuels) consumption minus the residential sector portion of supplemental gaseous fuels.

### ***Petroleum***

1949 forward: Table 3.8a.

### ***Fossil Fuels Total***

1949–2007: Residential sector total fossil fuels consumption is the sum of the residential sector consumption values for coal, natural gas, and petroleum.

2008 forward: Residential sector total fossil fuels consumption is the sum of the residential sector consumption values for natural gas and petroleum.

### ***Renewable Energy***

1949 forward: Table 10.2a.

### ***Total Primary Energy Consumption***

1949 forward: Residential sector total primary energy consumption is the sum of the residential sector consumption values for fossil fuels and renewable energy.

### ***Electricity Retail Sales***

1949 forward: Residential sector electricity retail sales from Table 7.6 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

### ***Electrical System Energy Losses***

1949 forward: Total electrical system energy losses are equal to electric power sector total primary energy consumption from Table 2.6 minus total electricity retail sales from Table 7.6 (converted to Btu by multiplying by the electricity heat content factor in Table A6). Total electrical system energy losses are allocated to the residential sector in proportion to the residential sector’s share of total electricity retail sales from Table 7.6. See Note 1, “Electrical System Energy Losses.”

### ***Total Energy Consumption***

1949 forward: Residential sector total energy consumption is the sum of the residential sector consumption values for total primary energy, electricity retail sales, and electrical system energy losses.

## **Table 2.3 Sources**

### ***Coal***

1949 forward: Commercial sector coal consumption data from Table 6.2 are converted to Btu by multiplying by the residential and commercial sectors coal consumption heat content factors in Table A5.

### ***Natural Gas***

1949–1979: Commercial sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4.

1980 forward: Commercial sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4. The commercial sector portion of supplemental gaseous fuels data in Btu is estimated using the method described in Note 3, “Supplemental Gaseous Fuels,” at the end of Section 4. Commercial sector natural gas (excluding supplemental gaseous fuels) consumption is equal to commercial sector natural gas (including supplemental gaseous fuels) consumption minus the commercial sector portion of supplemental gaseous fuels.

## ***Petroleum***

1949–1992: Table 3.8a.

1993–2008: The commercial sector share of motor gasoline consumption is equal to commercial sector motor gasoline consumption from Table 3.7a divided by motor gasoline product supplied from Table 3.5. Commercial sector fuel ethanol (including denaturant) consumption is equal to total fuel ethanol (including denaturant) consumption from Table 10.3 multiplied by the commercial sector share of motor gasoline consumption. Commercial sector petroleum (excluding biofuels) consumption is equal to commercial sector petroleum (including biofuels) consumption from Table 3.8a minus commercial sector fuel ethanol (including denaturant) consumption.

2009 forward: Commercial sector fuel ethanol (minus denaturant) consumption is equal to total fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the commercial sector share of motor gasoline consumption (see 1993–2008 sources above). Commercial sector petroleum (excluding biofuels) consumption is equal to commercial sector petroleum (including biofuels) consumption from Table 3.8a minus commercial sector fuel ethanol (minus denaturant) consumption.

## ***Fossil Fuels Total***

1949 forward: Commercial sector total fossil fuels consumption is the sum of the commercial sector consumption values for coal, natural gas, and petroleum.

## ***Renewable Energy***

1949 forward: Table 10.2a.

## ***Total Primary Energy Consumption***

1949 forward: Commercial sector total primary energy consumption is the sum of the commercial sector consumption values for fossil fuels and renewable energy.

## ***Electricity Retail Sales***

1949 forward: Commercial sector electricity retail sales from Table 7.6 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

## ***Electrical System Energy Losses***

1949 forward: Total electrical system energy losses are equal to electric power sector total primary energy consumption from Table 2.6 minus total electricity retail sales from Table 7.6 (converted to Btu by multiplying by the electricity heat content factor in Table A6). Total electrical system energy losses are allocated to the commercial sector in proportion to the commercial sector's share of total electricity retail sales from Table 7.6. See Note 1, "Electrical System Energy Losses."

## ***Total Energy Consumption***

1949 forward: Commercial sector total energy consumption is the sum of the commercial sector consumption values for total primary energy, electricity retail sales, and electrical system energy losses.

## **Table 2.4 Sources**

### ***Coal***

1949 forward: Coke plants coal consumption from Table 6.2 is converted to Btu by multiplying by the coke plants coal consumption heat content factors in Table A5. Other industrial coal consumption from Table 6.2 is converted to Btu by multiplying by the other industrial coal consumption heat content factors in Table A5. Industrial sector coal consumption is equal to coke plants coal consumption and other industrial coal consumption.

### ***Natural Gas***

1949–1979: Industrial sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4.

1980 forward: Industrial sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4. The industrial sector portion of supplemental gaseous fuels data in Btu is estimated using the method described in Note 3, "Supplemental Gaseous Fuels," at the end of Section 4. Industrial sector natural gas (excluding supplemental gaseous fuels) consumption is equal to industrial sector natural gas (including supplemental gaseous fuels) consumption minus the industrial sector portion of supplemental gaseous fuels.

### ***Petroleum***

1949–1992: Table 3.8b.

1993–2008: The industrial sector share of motor gasoline consumption is equal to industrial sector motor gasoline consumption from Table 3.7b divided by motor gasoline product supplied from Table 3.5. Industrial sector fuel ethanol (including denaturant) consumption is equal to total fuel ethanol (including denaturant) consumption from Table 10.3 multiplied by the industrial sector share of motor gasoline consumption. Industrial sector petroleum (excluding biofuels) consumption is equal to industrial sector petroleum (including biofuels) consumption from Table 3.8b minus industrial sector fuel ethanol (including denaturant) consumption.

2009 forward: Industrial sector fuel ethanol (minus denaturant) consumption is equal to total fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the industrial sector share of motor gasoline consumption (see 1993–2008 sources above). Industrial sector petroleum (excluding biofuels) consumption is equal to industrial sector petroleum (including biofuels) consumption from Table 3.8b minus industrial sector fuel ethanol (minus denaturant) consumption.

### ***Coal Coke Net Imports***

1949 forward: Coal coke net imports are equal to coal coke imports from Table 1.4a minus coal coke exports from Table 1.4b.

### ***Fossil Fuels Total***

1949 forward: Industrial sector total fossil fuels consumption is the sum of the industrial sector consumption values for coal, natural gas, and petroleum, plus coal coke net imports.

### ***Renewable Energy***

1949 forward: Table 10.2b.

### ***Total Primary Energy Consumption***

1949 forward: Industrial sector total primary energy consumption is the sum of the industrial sector consumption values for fossil fuels and renewable energy.

### ***Electricity Retail Sales***

1949 forward: Industrial sector electricity retail sales from Table 7.6 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

### ***Electrical System Energy Losses***

1949 forward: Total electrical system energy losses are equal to electric power sector total primary energy consumption from Table 2.6 minus total electricity retail sales from Table 7.6 (converted to Btu by multiplying by the electricity heat content factor in Table A6). Total electrical system energy losses are allocated to the industrial sector in proportion to the industrial sector's share of total electricity retail sales from Table 7.6. See Note 1, "Electrical System Energy Losses."

### ***Total Energy Consumption***

1949 forward: Industrial sector total energy consumption is the sum of the industrial sector consumption values for total primary energy, electricity retail sales, and electrical system energy losses.

## Table 2.5 Sources

### *Coal*

1949–1977: Transportation sector coal consumption data from Table 6.2 are converted to Btu by multiplying by the other industrial sector coal consumption heat content factors in Table A5.

### *Natural Gas*

1949 forward: Transportation sector natural gas consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4.

### *Petroleum*

1949–1992: Table 3.8c.

1993–2008: The transportation sector share of motor gasoline consumption is equal to transportation sector motor gasoline consumption from Table 3.7c divided by motor gasoline product supplied from Table 3.5. Transportation sector fuel ethanol (including denaturant) consumption is equal to total fuel ethanol (including denaturant) consumption from Table 10.3 multiplied by the transportation sector share of motor gasoline consumption. Transportation sector petroleum (excluding biofuels) consumption is equal to transportation sector petroleum (including biofuels) consumption from Table 3.8c minus transportation sector fuel ethanol (including denaturant) consumption.

2009–2011: Transportation sector fuel ethanol (minus denaturant) consumption is equal to total fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the transportation sector share of motor gasoline consumption (see 1993–2008 sources above). Transportation sector petroleum (excluding biofuels) consumption is equal to: transportation sector petroleum (including biofuels) consumption from Table 3.8c; minus transportation sector fuel ethanol (minus denaturant) consumption; minus biodiesel consumption (calculated using biodiesel data from U.S. Energy Information Administration (EIA), EIA-22M, "Monthly Biodiesel Production Survey"; and biomass-based diesel fuel data from EIA-810, "Monthly Refinery Report," EIA-812, "Monthly Product Pipeline Report," and EIA-815, "Monthly Bulk Terminal and Blender Report" (the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1); minus other renewable diesel fuel and other renewable fuels consumption from Table 10.4.

2012 forward: Transportation sector fuel ethanol (minus denaturant) consumption is equal to total fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the transportation sector share of motor gasoline consumption (see 1993–2008 sources above). Transportation sector petroleum (excluding biofuels) consumption is equal to: transportation sector petroleum (including biofuels) consumption from Table 3.8c; minus transportation sector fuel ethanol (minus denaturant) consumption; minus biodiesel consumption from Table 10.4; minus other renewable diesel fuel and other renewable fuels consumption from Table 10.4.

### *Fossil Fuels Total*

1949–1977: Transportation sector total fossil fuels consumption is the sum of the transportation sector consumption values for coal, natural gas, and petroleum.

1978 forward: Transportation sector total fossil fuels consumption is the sum of the transportation sector consumption values for natural gas and petroleum.

### *Renewable Energy*

1981 forward: Table 10.2b.

### Total Primary Energy Consumption

1949–1980: Transportation sector total primary energy consumption is equal to transportation sector fossil fuels consumption.

1981 forward: Transportation sector total primary energy consumption is the sum of the transportation sector consumption values for fossil fuels and renewable energy.



### ***Electricity Retail Sales***

1949 forward: Transportation sector electricity retail sales from Table 7.6 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

### ***Electrical System Energy Losses***

1949 forward: Total electrical system energy losses are equal to electric power sector total primary energy consumption from Table 2.6 minus total electricity retail sales from Table 7.6 (converted to Btu by multiplying by the electricity heat content factor in Table A6). Total electrical system energy losses are allocated to the transportation sector in proportion to the transportation sector's share of total electricity retail sales from Table 7.6. See Note 1, "Electrical System Energy Losses."

### ***Total Energy Consumption***

1949 forward: Transportation sector total energy consumption is the sum of the transportation sector consumption values for total primary energy, electricity retail sales, and electrical system energy losses.

## **Table 2.6 Sources**

### ***Coal***

1949 forward: Electric power sector coal consumption data from Table 6.2 are converted to Btu by multiplying by the electric power sector coal consumption heat content factors in Table A5.

### ***Natural Gas***

1949–1979: Electric power sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas electric power sector consumption heat content factors in Table A4.

1980 forward: Electric power sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas electric power sector consumption heat content factors in Table A4. The electric power sector portion of supplemental gaseous fuels data in Btu is estimated using the method described in Note 3, "Supplemental Gaseous Fuels," at the end of Section 4. Electric power sector natural gas (excluding supplemental gaseous fuels) consumption is equal to electric power sector natural gas (including supplemental gaseous fuels) consumption minus the electric power sector portion of supplemental gaseous fuels.

### ***Petroleum***

1949 forward: Table 3.8c.

### ***Fossil Fuels Total***

1949 forward: Electric power sector total fossil fuels consumption is the sum of the electric power sector consumption values for coal, natural gas, and petroleum.

### ***Nuclear Electric Power***

1949 forward: Nuclear electricity net generation data from Table 7.2a are converted to Btu by multiplying by the nuclear heat rate factors in Table A6.

### ***Renewable Energy***

1949 forward: Table 10.2c.

### ***Electricity Net Imports***

1949 forward: Electricity net imports are equal to electricity imports from Table 1.4a minus electricity exports from Table 1.4b.

### ***Total Primary Energy Consumption***

1949 forward: Electric power sector total primary energy consumption is the sum of the electric power sector consumption values for fossil fuels, nuclear electric power, and renewable energy, plus electricity net imports.


## 3. Petroleum

---


**Figure 3.1 Petroleum Overview**

(Million Barrels Per Day)


Overview, 1949–2020




Crude Oil and Natural Gas Liquids Field Production, 1949–2020



Overview, January



Total Field Production [a], Monthly



[a] Crude oil, including lease condensate, and natural gas liquids field production.

[b] Includes lease condensate.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
Source: Table 3.1.

**Table 3.1 Petroleum Overview**  
(Thousand Barrels per Day)

	Field Production <sup>a</sup>					Renewable Fuels and Oxy-genates <sup>e</sup>	Process-ing Gain <sup>f</sup>	Trade			Stock Change <sup>i</sup>	Adjust-ments <sup>c,j</sup>	Petroleum Products Supplied
	Crude Oil <sup>b,c</sup>			Natural Gas Liquids	Total <sup>c</sup>			Im-ports <sup>g</sup>	Ex-ports	Net Imports <sup>h</sup>			
	48 States <sup>d</sup>	Alaska	Total										
1950 Average .....	5,407	0	5,407	499	5,906	NA	2	850	305	545	-56	-51	6,458
1955 Average .....	6,807	0	6,807	771	7,578	NA	34	1,248	368	880	(s)	-37	8,455
1960 Average .....	7,034	2	7,035	929	7,965	NA	146	1,815	202	1,613	-83	-8	9,797
1965 Average .....	7,774	30	7,804	1,210	9,014	NA	220	2,468	187	2,281	-8	-10	11,512
1970 Average .....	9,408	229	9,637	1,660	11,297	NA	359	3,419	259	3,161	103	-16	14,697
1975 Average .....	8,183	191	8,375	1,633	10,007	NA	460	6,056	209	5,846	32	41	16,322
1980 Average .....	6,980	1,617	8,597	1,573	10,170	NA	597	6,909	544	6,365	140	64	17,056
1985 Average .....	7,146	1,825	8,971	1,609	10,581	NA	557	5,067	781	4,286	-103	200	15,726
1990 Average .....	5,582	1,773	7,355	1,559	8,914	NA	683	8,018	857	7,161	107	338	16,988
1995 Average .....	5,076	1,484	6,560	1,762	8,322	NA	774	8,835	949	7,886	-246	496	17,725
2000 Average .....	4,851	970	5,822	1,911	7,733	NA	948	11,459	1,040	10,419	-69	532	19,701
2001 Average .....	4,839	963	5,801	1,868	7,670	NA	903	11,871	971	10,900	325	501	19,649
2002 Average .....	4,759	985	5,744	1,880	7,624	NA	957	11,530	984	10,546	-105	529	19,761
2003 Average .....	4,675	974	5,649	1,719	7,369	NA	974	12,264	1,027	11,238	56	509	20,034
2004 Average .....	4,533	908	5,441	1,809	7,250	NA	1,051	13,145	1,048	12,097	209	542	20,731
2005 Average .....	4,320	864	5,184	1,717	6,901	NA	989	13,714	1,165	12,549	<sup>k</sup> 146	509	20,802
2006 Average .....	4,345	741	5,086	1,739	6,825	NA	994	13,707	1,317	12,390	59	537	20,687
2007 Average .....	4,352	722	5,074	1,783	6,857	NA	996	13,468	1,433	12,036	-152	640	20,680
2008 Average .....	4,317	683	5,000	1,784	6,783	NA	993	12,915	1,802	11,114	195	803	19,498
2009 Average .....	4,711	645	5,357	1,910	7,267	746	979	11,691	2,024	9,667	107	221	18,771
2010 Average .....	4,885	600	5,484	2,074	7,558	907	1,068	11,793	2,353	9,441	42	246	19,178
2011 Average .....	5,106	561	5,667	2,216	7,883	1,016	1,076	11,436	2,986	8,450	-138	332	18,896
2012 Average .....	5,995	526	6,521	2,408	8,929	964	1,059	10,598	3,205	7,393	151	289	18,482
2013 Average .....	6,979	515	7,494	2,606	10,100	1,002	1,087	9,859	3,621	6,237	-138	402	18,967
2014 Average .....	8,293	496	8,789	3,015	11,804	1,055	1,081	9,241	4,176	5,065	267	363	19,100
2015 Average .....	8,964	483	9,446	3,342	12,789	1,095	1,062	9,449	4,738	4,711	431	306	19,532
2016 Average .....	8,361	490	8,852	3,509	12,361	1,158	1,118	10,055	5,261	4,795	125	385	19,692
2017 Average .....	8,877	495	9,371	3,783	13,154	1,198	1,111	10,144	6,376	3,768	-364	356	19,952
2018 January .....	9,491	508	9,998	3,853	13,851	1,210	1,102	10,280	6,461	3,819	-405	176	20,564
February .....	9,748	513	10,261	4,061	14,321	1,228	1,097	9,586	6,907	2,679	-142	226	19,693
March .....	9,976	512	10,489	4,200	14,689	1,214	1,096	9,822	7,337	2,485	-457	791	20,731
April .....	9,999	497	10,496	4,286	14,782	1,205	1,113	10,375	7,797	2,578	119	478	20,038
May .....	9,961	496	10,457	4,352	14,809	1,230	1,141	10,227	7,717	2,510	169	731	20,251
June .....	10,154	451	10,605	4,337	14,942	1,260	1,133	10,726	7,824	2,902	-109	425	20,770
July .....	10,509	395	10,903	4,452	15,355	1,273	1,169	10,193	7,963	2,231	186	830	20,671
August .....	10,956	428	11,384	4,602	15,985	1,289	1,185	10,434	7,164	3,270	622	248	21,356
September .....	10,992	471	11,463	4,638	16,102	1,214	1,141	9,889	7,415	2,474	1,311	465	20,084
October .....	11,067	487	11,554	4,588	16,142	1,220	1,116	9,468	8,011	1,457	-520	332	20,786
November .....	11,410	497	11,907	4,563	16,470	1,240	1,149	9,272	8,281	991	-257	666	20,774
December .....	11,508	496	12,004	4,483	16,487	1,222	1,210	9,021	8,301	720	24	712	20,327
Average .....	10,485	479	10,964	4,369	15,333	1,234	1,138	9,943	7,601	2,341	44	509	20,512
2019 January .....	11,369	496	11,865	4,554	16,419	1,112	1,109	9,768	7,982	1,786	246	435	20,615
February .....	11,191	488	11,679	4,713	16,392	1,115	1,007	8,671	8,219	452	-597	722	20,284
March .....	11,456	481	11,937	4,729	16,667	1,087	1,038	8,905	7,946	959	-100	324	20,176
April .....	11,659	475	12,135	4,790	16,925	1,138	1,065	9,525	8,382	1,143	596	658	20,333
May .....	11,689	474	12,163	4,840	17,003	1,151	1,064	9,893	8,238	1,655	1,281	795	20,387
June .....	11,633	455	12,088	4,795	16,882	1,159	1,076	9,297	8,576	720	-99	718	20,654
July .....	11,371	448	11,819	4,707	16,526	1,155	1,066	9,601	8,084	1,517	158	629	20,735
August .....	12,043	382	12,425	4,766	17,191	1,133	1,099	9,387	8,438	949	-271	516	21,158
September .....	12,046	449	12,495	4,990	17,485	1,071	1,018	8,712	8,672	40	-77	559	20,248
October .....	12,198	475	12,673	5,022	17,695	1,093	1,014	8,599	9,039	-440	-532	821	20,714
November .....	12,376	484	12,860	4,995	17,854	1,129	1,131	8,103	8,741	-638	-284	976	20,736
December .....	12,321	481	12,802	4,992	17,794	1,157	1,133	9,159	9,331	-171	-44	486	20,443
Average .....	11,782	466	12,248	4,825	17,073	1,125	1,069	9,141	8,471	670	28	635	20,543
2020 January .....	E 12,272	E 482	E 12,755	E 5,145	E 17,900	1,161	1,136	8,572	9,177	-605	550	863	19,905
February .....	E 12,269	E 477	E 12,746	E 4,965	E 17,711	1,142	939	8,457	9,983	-1,526	-664	908	19,839
March .....	E 12,268	E 470	E 12,737	E 5,253	E 17,990	1,049	978	8,345	9,621	-1,276	1,334	876	18,284
April .....	E 11,547	E 463	E 12,010	E 4,934	E 16,944	668	767	7,236	8,452	-1,216	2,654	181	14,691
May .....	E 9,615	E 404	E 10,019	E 4,745	E 14,764	781	807	7,757	6,818	939	1,242	54	16,103
June .....	E 10,081	E 361	E 10,442	E 5,197	E 15,639	969	873	8,367	7,692	675	1,168	447	17,435
July .....	E 10,529	E 444	E 10,973	E 5,369	E 16,342	1,033	936	7,846	8,412	-566	-57	522	18,323
August .....	RE 10,140	E 444	E 10,584	E 5,325	E 15,909	1,025	924	7,465	8,498	-1,033	-756	<sup>R</sup> 858	18,439
September .....	RE 10,429	E 442	RE 10,870	E 5,309	RE 16,179	1,036	946	7,543	8,376	-833	-650	<sup>R</sup> 330	18,307
October .....	RE 9,972	E 459	RE 10,432	E 5,299	RE 15,731	1,053	925	7,372	8,356	-984	-1,288	<sup>R</sup> 612	18,624
November .....	RE 10,660	RE 464	RE 11,124	E 5,323	RE 16,447	<sup>R</sup> 1,096	<sup>R</sup> 934	<sup>R</sup> 7,616	<sup>R</sup> 7,823	<sup>R</sup> -207	<sup>R</sup> 109	<sup>R</sup> 542	<sup>R</sup> 18,702
December .....	RE 10,499	RE 511	RE 11,010	RE 5,309	RE 16,319	RE 978	RE 925	RE 7,472	RE 8,351	RE -878	RE -700	RE 639	RE 18,683
Average .....	RE 10,851	RE 452	RE 11,303	RE 5,182	RE 16,485	RE 999	RE 925	RE 7,836	RE 8,459	RE -623	RE 244	RE 570	RE 18,111
2021 January .....	E 10,446	E 508	E 10,955	E 5,304	E 16,258	E 958	E 961	E 8,088	E 8,155	E -67	E -766	E 567	E 19,444

<sup>a</sup> Crude oil production on leases, and natural gas processing plant production of natural gas liquids (ethane, propane, normal butane, isobutane, and natural gasoline). Through 1980, also includes natural gas processing plant production of finished petroleum products (aviation gasoline, distillate fuel oil, jet fuel, kerosene, motor gasoline, special naphthas, and miscellaneous products).

<sup>b</sup> Includes lease condensate.

<sup>c</sup> Once a month, data for crude oil production, total field production, and adjustments are revised going back as far as the data year of the U.S. Energy Information Administration's (EIA) last published *Petroleum Supply Annual* (PSA)—these revisions are released at the same time as EIA's *Petroleum Supply Monthly*. Once a year, data for these series are revised going back as far as 10 years—these revisions are released at the same time as the PSA.

<sup>d</sup> United States excluding Alaska and Hawaii.

<sup>e</sup> Renewable fuels and oxygenate plant net production of fuel ethanol, biodiesel, other renewable fuels, natural gasoline, finished motor gasoline, and motor gasoline blending components. For 2009–2018, also includes oxygenates (excluding fuel ethanol).

<sup>f</sup> Refinery and blender net production minus refinery and blender net inputs. See Table 3.2.

<sup>g</sup> Includes Strategic Petroleum Reserve imports. See Table 3.3b.

<sup>h</sup> Net imports equal imports minus exports.

<sup>i</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase. The current month stock change estimate is based on the change from the previous month's estimate, rather than the stocks values shown in Table 3.4. Includes crude oil stocks in the Strategic Petroleum Reserve, but excludes distillate fuel oil stocks in the Northeast Home Heating Oil Reserve. See Table 3.4.

<sup>j</sup> An adjustment for crude oil, hydrogen, oxygenates, renewable fuels, other hydrocarbons, motor gasoline blending components, finished motor gasoline, and distillate fuel oil. See EIA's *Petroleum Supply Monthly*, Appendix B, "PSM Explanatory Notes," for further information.

<sup>k</sup> Derived from the 2004 petroleum stocks value that excludes crude oil stocks on leases (1,628 million barrels), not the 2004 petroleum stocks value that includes crude oil stocks on leases (1,645 million barrels).

<sup>R</sup>=Revised. <sup>E</sup>=Estimate. <sup>NA</sup>=Not available. <sup>(s)</sup>=Less than 500 barrels per day and greater than -500 barrels per day.

Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 3.2 Refinery and Blender Net Inputs and Net Production**

(Million Barrels per Day)


Net Inputs and Net Production, 1949–2020




Net Production, Selected Products, 1949–2020



Net Inputs and Net Production, Monthly



Net Production, Selected Products, Monthly



[a] Includes lease condensate.

[b] Natural gas liquids and other liquids.

[c] Beginning in 1993, includes fuel ethanol blended into motor gasoline.

[d] Beginning in 2009, includes renewable diesel fuel (including biodiesel)

blended into distillate fuel oil.

[e] Beginning in 2005, includes kerosene-type jet fuel only.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Source: Table 3.2.

**Table 3.2 Refinery and Blender Net Inputs and Net Production**  
(Thousand Barrels per Day)


	Refinery and Blender Net Inputs <sup>a</sup>				Refinery and Blender Net Production <sup>b</sup>									
	Crude Oil <sup>c</sup>	Natural Gas Liquids <sup>d</sup>	Other Liquids <sup>e</sup>	Total	Distillate Fuel Oil <sup>f</sup>	Hydrocarbon Gas Liquids			Total <sup>h</sup>	Jet Fuel <sup>i</sup>	Motor Gasoline <sup>j</sup>	Residual Fuel Oil	Other Products <sup>k</sup>	Total
						Propane/Propylene		Total <sup>g</sup>						
						Propane	Propylene							
1950 Average	5,739	259	19	6,018	1,093	NA	NA	NA	80	(i)	2,735	1,165	947	6,019
1955 Average	7,480	345	32	7,857	1,651	NA	NA	NA	119	155	3,648	1,152	1,166	7,891
1960 Average	8,067	455	61	8,583	1,823	NA	NA	NA	212	241	4,126	908	1,420	8,729
1965 Average	9,043	618	88	9,750	2,096	NA	NA	NA	293	523	4,507	736	1,814	9,970
1970 Average	10,870	763	121	11,754	2,454	E 184	E 55	239	345	827	5,699	706	2,082	12,113
1975 Average	12,442	710	72	13,225	2,653	E 179	E 60	238	311	871	6,518	1,235	2,097	13,685
1980 Average	13,481	462	81	14,025	2,661	E 202	E 72	273	330	999	6,492	1,580	2,559	14,622
1985 Average	12,002	509	681	13,192	2,686	E 223	E 72	295	391	1,189	6,419	882	2,183	13,750
1990 Average	13,409	467	713	14,589	2,925	299	105	404	499	1,488	6,959	950	2,452	15,272
1995 Average	13,973	471	775	15,220	3,155	352	151	503	654	1,416	7,459	788	2,522	15,994
2000 Average	15,067	380	849	16,295	3,580	366	217	583	705	1,606	7,951	696	2,705	17,243
2001 Average	15,128	429	825	16,382	3,695	352	204	556	667	1,530	8,022	721	2,651	17,285
2002 Average	14,947	429	941	16,316	3,592	347	225	572	671	1,514	8,183	601	2,712	17,273
2003 Average	15,304	419	791	16,513	3,707	341	229	570	658	1,488	8,194	660	2,780	17,487
2004 Average	15,475	422	866	16,762	3,814	341	243	584	645	1,547	8,265	655	2,887	17,814
2005 Average	15,220	441	1,149	16,811	3,954	311	229	540	573	1,546	8,318	628	2,782	17,800
2006 Average	15,242	501	1,238	16,981	4,040	302	241	543	627	1,481	8,364	635	2,827	17,975
2007 Average	15,156	505	1,337	16,999	4,133	330	232	562	655	1,448	8,358	673	2,728	17,994
2008 Average	14,648	485	2,019	17,153	4,294	312	207	519	630	1,493	8,548	620	2,561	18,146
2009 Average	14,336	485	2,082	16,904	4,048	291	246	537	623	1,396	8,786	598	2,431	17,882
2010 Average	14,724	442	2,219	17,385	4,223	282	278	560	659	1,418	9,059	585	2,509	18,452
2011 Average	14,806	490	2,300	17,596	4,492	270	282	552	619	1,449	9,058	537	2,518	18,673
2012 Average	14,999	509	1,997	17,505	4,550	276	277	553	630	1,471	9,826	501	2,487	18,564
2013 Average	15,312	496	2,211	18,019	4,733	284	281	564	623	1,499	9,234	467	2,550	19,106
2014 Average	15,848	511	2,214	18,574	4,916	306	281	587	653	1,541	9,570	435	2,537	19,654
2015 Average	16,188	517	2,119	18,824	4,983	283	276	559	615	1,590	9,754	417	2,527	19,886
2016 Average	16,187	536	2,238	18,961	4,834	307	280	587	632	1,650	9,995	418	2,550	20,079
2017 Average	16,590	566	2,031	19,187	5,024	307	285	592	628	1,702	9,954	427	2,563	20,298
2018 January	16,599	630	1,233	18,463	5,006	296	304	600	393	1,687	9,529	467	2,483	19,565
February	15,936	629	1,718	18,283	4,584	295	274	568	409	1,688	9,797	462	2,440	19,380
March	16,665	556	1,923	19,144	4,823	295	276	571	632	1,781	10,053	403	2,550	20,240
April	16,766	497	2,326	19,589	5,120	307	286	593	800	1,795	9,974	450	2,563	20,703
May	16,969	454	2,465	19,887	5,214	300	292	591	855	1,804	10,138	415	2,602	21,028
June	17,666	456	2,309	20,430	5,410	321	286	607	874	1,893	10,314	348	2,724	21,563
July	17,357	442	2,414	20,213	5,257	320	286	607	870	1,894	10,174	444	2,742	21,382
August	17,623	504	2,316	20,443	5,369	310	293	604	880	1,955	10,243	391	2,790	21,629
September	16,991	565	2,035	19,591	5,230	296	294	590	650	1,856	9,927	429	2,639	20,732
October	16,412	687	2,196	19,295	5,035	279	294	574	464	1,691	10,301	397	2,522	20,411
November	17,162	746	1,704	19,612	5,350	294	314	608	395	1,769	10,240	450	2,558	20,762
December	17,409	732	1,474	19,615	5,576	303	313	616	373	1,856	10,020	440	2,561	20,826
Average	16,969	575	2,011	19,555	5,168	301	293	594	634	1,806	10,061	425	2,599	20,693
2019 January	16,783	675	1,415	18,873	5,250	297	292	589	368	1,771	9,747	398	2,448	19,981
February	15,846	592	1,935	18,372	4,905	257	289	545	429	1,689	9,744	309	2,303	19,379
March	15,935	512	2,580	19,027	4,968	288	261	549	629	1,728	10,060	357	2,323	20,065
April	16,341	486	2,482	19,309	5,059	295	272	567	804	1,728	10,020	389	2,374	20,374
May	16,719	460	2,519	19,699	5,212	295	283	577	867	1,729	10,229	363	2,362	20,763
June	17,236	431	2,469	20,136	5,351	300	290	591	859	1,883	10,236	430	2,454	21,212
July	17,175	448	2,593	20,216	5,246	292	286	579	852	1,922	10,240	390	2,632	21,282
August	17,297	481	2,580	20,358	5,266	295	284	579	806	1,924	10,437	410	2,613	21,456
September	16,403	601	2,178	19,182	5,035	272	282	553	613	1,799	9,916	383	2,454	20,199
October	15,681	712	2,357	18,749	4,794	252	281	533	409	1,653	10,259	340	2,308	19,764
November	16,482	744	1,972	19,197	5,231	294	287	581	272	1,833	10,229	314	2,449	20,328
December	16,793	716	1,735	19,244	5,309	316	280	596	348	1,890	9,992	249	2,589	20,377
Average	16,563	571	2,237	19,371	5,137	288	282	570	606	1,796	10,095	361	2,444	20,439
2020 January	16,231	699	1,608	18,538	5,085	297	269	566	388	1,855	9,626	229	2,491	19,674
February	15,867	638	1,793	18,298	4,812	280	234	514	381	1,666	9,742	229	2,407	19,237
March	15,226	498	1,363	17,088	4,951	279	245	525	621	1,359	8,575	232	2,328	18,067
April	12,786	318	1,134	14,238	5,101	230	264	494	683	619	6,352	145	2,106	15,005
May	12,958	336	1,660	14,953	4,821	234	258	492	671	505	7,477	167	2,118	15,760
June	13,732	402	2,202	16,336	4,580	249	255	504	710	731	8,745	239	2,204	17,209
July	14,338	456	2,283	17,077	4,842	265	258	522	732	836	9,026	225	2,350	18,012
August	14,151	422	2,675	17,249	4,823	274	252	527	712	851	9,312	192	2,282	18,173
September	13,573	536	2,263	16,372	4,493	260	270	530	556	800	9,090	165	2,214	17,318
October	13,445	587	2,057	16,089	4,213	258	280	538	410	821	9,252	163	2,154	17,013
November	R 14,124	R 637	R 1,477	R 16,238	R 4,522	R 275	R 285	R 560	R 333	R 1,062	R 8,882	R 153	R 2,219	R 17,171
December	RE 14,237	F 636	RE 1,884	RF 16,756	RE 4,656	NA	NA	RE 608	F 352	RE 1,146	RE 8,607	RE 160	RE 2,761	RE 17,682
Average	RE 14,221	RE 514	RE 1,868	RE 16,602	RE 4,742	NA	NA	RE 532	RE 546	RE 1,020	RE 8,723	RE 192	RE 2,304	RE 17,527
2021 January	E 14,703	F 611	E 1,213	F 16,527	E 4,590	NA	NA	E 677	F 346	E 1,240	E 8,506	E 178	E 2,628	E 17,488

<sup>a</sup> See "Refinery and Blender Net Inputs" in Glossary.  
<sup>b</sup> See "Refinery and Blender Net Production" in Glossary.  
<sup>c</sup> Includes lease condensate.  
<sup>d</sup> Ethane, propane, normal butane, isobutane, and natural gasoline (pentanes plus).  
<sup>e</sup> Unfinished oils (net). Beginning in 1981, also includes aviation gasoline blending components (net) and motor gasoline blending components (net). Beginning in 1993, also includes fuel ethanol. Beginning in 2009, also includes renewable fuels (excluding fuel ethanol), hydrogen, and other hydrocarbons. For 2009–2018, also includes oxygenates (excluding fuel ethanol).  
<sup>f</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.  
<sup>g</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures."  
<sup>h</sup> Ethane, propane, normal butane, isobutane, and refinery olefins (ethylene, propylene, butylene, and isobutylene).  
<sup>i</sup> Beginning in 1965, includes kerosene-type jet fuel. (Through 1964, kerosene-type jet fuel is included with kerosene in "Other Products.") For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet


fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other Products.")  
<sup>j</sup> Finished motor gasoline. Through 1963, also includes aviation gasoline and special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.  
<sup>k</sup> Asphalt and road oil, kerosene, lubricants, petrochemical feedstocks, petroleum coke, still gas (refinery gas), waxes, and miscellaneous products. Through 1964, also includes kerosene-type jet fuel. Beginning in 1964, also includes finished aviation gasoline and special naphthas. Beginning in 2005, also includes naphtha-type jet fuel.  
R=Revised. E=Estimate. F=Forecast. NA=Not available.  
Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
Sources: See end of section.

**Figure 3.3a Petroleum Trade: Overview**


Overview, November 2020



Imports From OPEC and Persian Gulf as Share of Total Imports, 1960–2019



Net Imports as Share of Products Supplied, 1949–2020



Note: OPEC=Organization of the Petroleum Exporting Countries.  
 Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
 Source: Table 3.3a.

Table 3.3a Petroleum Trade: Overview

	Imports From Persian Gulf <sup>a</sup>	Imports From OPEC <sup>b</sup>	Imports	Exports	Net Imports	Products Supplied	As Share of Products Supplied				As Share of Total Imports	
							Imports From Persian Gulf <sup>a</sup>	Imports From OPEC <sup>b</sup>	Imports	Net Imports	Imports From Persian Gulf <sup>a</sup>	Imports From OPEC <sup>b</sup>
							Thousand Barrels per Day					
1950 Average .....	NA	NA	850	305	545	6,458	NA	NA	13.2	8.4	NA	NA
1955 Average .....	NA	NA	1,248	368	880	8,455	NA	NA	14.8	10.4	NA	NA
1960 Average .....	326	1,233	1,815	202	1,613	9,797	3.3	12.6	18.5	16.5	17.9	68.0
1965 Average .....	359	1,439	2,468	187	2,281	11,512	3.1	12.5	21.4	19.8	14.5	58.3
1970 Average .....	184	1,294	3,419	259	3,161	14,697	1.3	8.8	23.3	21.5	5.4	37.8
1975 Average .....	1,165	3,601	6,056	209	5,846	16,322	7.1	22.1	37.1	35.8	19.2	59.5
1980 Average .....	1,519	4,300	6,909	544	6,365	17,056	8.9	25.2	40.5	37.3	22.0	62.2
1985 Average .....	311	1,830	5,067	781	4,286	15,726	2.0	11.6	32.2	27.3	6.1	36.1
1990 Average .....	1,966	4,296	8,018	857	7,161	16,988	11.6	25.3	47.2	42.2	24.5	53.6
1995 Average .....	1,573	4,002	8,835	949	7,886	17,725	8.9	22.6	49.8	44.5	17.8	45.3
2000 Average .....	2,488	5,203	11,459	1,040	10,419	19,701	12.6	26.4	58.2	52.9	21.7	45.4
2001 Average .....	2,761	5,528	11,871	971	10,900	19,649	14.1	28.1	60.4	55.5	23.3	46.6
2002 Average .....	2,269	4,605	11,530	984	10,546	19,761	11.5	23.3	58.3	53.4	19.7	39.9
2003 Average .....	2,501	5,162	12,264	1,027	11,238	20,034	12.5	25.8	61.2	56.1	20.4	42.1
2004 Average .....	2,493	5,701	13,145	1,048	12,097	20,731	12.0	27.5	63.4	58.4	19.0	43.4
2005 Average .....	2,334	5,587	13,714	1,165	12,549	20,802	11.2	26.9	65.9	60.3	17.0	40.7
2006 Average .....	2,211	5,517	13,707	1,317	12,390	20,687	10.7	26.7	66.3	59.9	16.1	40.2
2007 Average .....	2,163	5,980	13,468	1,433	12,036	20,680	10.5	28.9	65.1	58.2	16.1	44.4
2008 Average .....	2,370	5,954	12,915	1,802	11,114	19,498	12.2	30.5	66.2	57.0	18.4	46.1
2009 Average .....	1,689	4,776	11,691	2,024	9,667	18,771	9.0	25.4	62.3	51.5	14.4	40.9
2010 Average .....	1,711	4,906	11,793	2,353	9,441	19,178	8.9	25.6	61.5	49.2	14.5	41.6
2011 Average .....	1,861	4,555	11,436	2,986	8,450	18,896	9.9	24.1	60.5	44.7	16.3	39.8
2012 Average .....	2,156	4,271	10,598	3,205	7,393	18,482	11.7	23.1	57.3	40.0	20.3	40.3
2013 Average .....	2,009	3,720	9,859	3,621	6,237	18,967	10.6	19.6	52.0	32.9	20.4	37.7
2014 Average .....	1,875	3,237	9,241	4,176	5,065	19,100	9.8	16.9	48.4	26.5	20.3	35.0
2015 Average .....	1,507	2,894	9,449	4,738	4,711	19,532	7.7	14.8	48.4	24.1	15.9	30.6
2016 Average .....	1,766	3,446	10,055	5,261	4,795	19,692	9.0	17.5	51.1	24.3	17.6	34.3
2017 Average .....	1,746	3,366	10,144	6,376	3,768	19,952	8.8	16.9	50.8	18.9	17.2	33.2
2018 January .....	1,591	3,009	10,280	6,461	3,819	20,564	7.7	14.6	50.0	18.6	15.5	29.3
February .....	1,554	2,740	9,586	6,907	2,679	19,693	7.9	13.9	48.7	13.6	16.2	28.6
March .....	1,738	2,845	9,822	7,337	2,485	20,731	8.4	13.7	47.4	12.0	17.7	29.0
April .....	1,899	3,523	10,375	7,797	2,578	20,038	9.5	17.6	51.8	12.9	18.3	34.0
May .....	1,567	2,731	10,227	7,717	2,510	20,251	7.7	13.5	50.5	12.4	15.3	26.7
June .....	1,487	3,041	10,726	7,824	2,902	20,770	7.2	14.6	51.6	14.0	13.9	28.3
July .....	1,489	2,971	10,193	7,963	2,231	20,671	7.2	14.4	49.3	10.8	14.6	29.1
August .....	1,599	2,857	10,434	7,164	3,270	21,356	7.5	13.4	48.9	15.3	15.3	27.4
September .....	1,645	2,996	9,889	7,415	2,474	20,084	8.2	14.9	49.2	12.3	16.6	30.3
October .....	1,563	2,729	9,468	8,011	1,457	20,786	7.5	13.1	45.6	7.0	16.5	28.8
November .....	1,567	2,703	9,272	8,281	991	20,774	7.5	13.0	44.6	4.8	16.9	29.2
December .....	1,237	2,516	9,021	8,301	720	20,327	6.1	12.4	44.4	3.5	13.7	27.9
Average .....	1,578	2,888	9,943	7,601	2,341	20,512	7.7	14.1	48.5	11.4	15.9	29.0
2019 January .....	1,304	2,553	9,768	7,982	1,786	20,615	6.3	12.4	47.4	8.7	13.3	26.1
February .....	1,272	1,803	8,671	8,219	452	20,284	6.3	8.9	42.8	2.2	14.7	20.8
March .....	1,096	1,643	8,905	7,946	959	20,176	5.4	8.1	44.1	4.8	12.3	18.5
April .....	947	1,566	9,525	8,382	1,143	20,333	4.7	7.7	46.8	5.6	9.9	16.4
May .....	912	1,693	9,893	8,238	1,655	20,387	4.5	8.3	48.5	8.1	9.2	17.1
June .....	995	1,699	9,297	8,576	720	20,654	4.8	8.2	45.0	3.5	10.7	18.3
July .....	890	1,420	9,601	8,084	1,517	20,735	4.3	6.8	46.3	7.3	9.3	14.8
August .....	794	1,660	9,387	8,438	949	21,158	3.8	7.8	44.4	4.5	8.5	17.7
September .....	980	1,601	8,712	8,672	40	20,248	4.8	7.9	43.0	0.2	11.2	18.4
October .....	741	1,301	8,599	9,039	-440	20,714	3.6	6.3	41.5	-2.1	8.6	15.1
November .....	685	1,322	8,103	8,741	-638	20,736	3.3	6.4	39.1	-3.1	8.5	16.3
December .....	960	1,411	9,159	9,331	-171	20,443	4.7	6.9	44.8	-0.8	10.5	15.4
Average .....	963	1,639	9,141	8,471	670	20,543	4.7	8.0	44.5	3.3	10.5	17.9
2020 January .....	773	926	8,572	9,177	-605	19,905	3.9	4.7	43.1	-3.0	9.0	10.8
February .....	811	981	8,457	9,983	-1,526	19,839	4.1	4.9	42.6	-7.7	9.6	11.6
March .....	772	831	8,345	9,621	-1,276	18,284	4.2	4.5	45.6	-7.0	9.3	10.0
April .....	610	675	7,236	8,452	-1,216	14,691	4.2	4.6	49.3	-8.3	8.4	9.3
May .....	1,429	1,532	7,757	6,818	939	16,103	8.9	9.5	48.2	5.8	18.4	19.8
June .....	1,465	1,617	8,367	7,692	675	17,435	8.4	9.3	48.0	3.9	17.5	19.3
July .....	968	1,014	7,846	8,412	-566	18,323	5.3	5.5	42.8	-3.1	12.3	12.9
August .....	499	622	7,465	8,498	-1,033	18,439	2.7	3.4	40.5	-5.6	6.7	8.3
September .....	511	667	7,543	8,376	-833	18,307	2.8	3.6	41.2	-4.6	6.8	8.8
October .....	573	686	7,372	8,356	-984	18,624	3.1	3.7	39.6	-5.3	7.8	9.3
November .....	R 456	R 632	R 7,616	R 7,823	R -207	R 18,702	R 2.4	R 3.4	R 40.7	R -1.1	R 6.0	R 8.3
December .....	NA	NA	RE 7,472	RE 8,351	RE -878	RE 18,683	NA	NA	RE 40.0	RE -4.7	NA	NA
Average .....	NA	NA	RE 7,836	RE 8,459	RE -623	RE 18,111	NA	NA	RE 43.3	RE -3.4	NA	NA
2021 January .....	NA	NA	E 8,088	E 8,155	E -67	E 19,444	NA	NA	E 41.6	E -0.3	NA	NA

<sup>a</sup> Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, United Arab Emirates, and the Neutral Zone (between Kuwait and Saudi Arabia).

<sup>b</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. See Table 3.3c for notes on which countries are included in the data.

R=Revised. E=Estimate. NA=Not available.

Notes: • For the feature article "Measuring Dependence on Imported Oil," published in the August 1995 *Monthly Energy Review*, see [http://www.eia.gov/totalenergy/data/monthly/pdf/historical/imported\\_oil.pdf](http://www.eia.gov/totalenergy/data/monthly/pdf/historical/imported_oil.pdf).

• Beginning in October 1977, data include Strategic Petroleum Reserve imports. See Table 3.3b. • Annual averages may not equal average of months due to independent rounding. • U.S. geographic coverage is the 50 states and the District of Columbia. U.S. exports include shipments to U.S. territories, and imports include

receipts from U.S. territories.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: • **1949–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), *Energy Data Reports, Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports, and unpublished revisions. • **2020 and 2021:** EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.




**Figure 3.3b Petroleum Trade: Imports and Exports by Type**

(Million Barrels per Day)


Imports Overview, 1949–2020




Exports Overview, 1949–2020



Imports, Selected Products, Monthly



Exports, Selected Products, Monthly



[a] Includes fuel ethanol blended into motor gasoline.

[b] Includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

[c] Includes kerosene-type jet fuel only.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Sources: Tables 3.3b and 3.3e.

**Table 3.3b Petroleum Trade: Imports by Type**  
(Thousand Barrels per Day)

	Crude Oil <sup>a</sup>		Distillate Fuel Oil	Hydrocarbon Gas Liquids				Jet Fuel <sup>e</sup>	Motor Gasoline <sup>f</sup>	Residual Fuel Oil	Other <sup>g</sup>	Total
	SPR <sup>b</sup>	Total		Propane/Propylene			Total <sup>d</sup>					
				Propane	Propylene	Total <sup>c</sup>						
1950 Average .....	--	487	7	NA	NA	--	--	{ <sup>e</sup> e}	(s)	329	27	850
1955 Average .....	--	782	12	NA	NA	--	--		13	417	24	1,248
1960 Average .....	--	1,015	35	NA	NA	NA	4	34	27	637	62	1,815
1965 Average .....	--	1,238	36	NA	NA	NA	21	81	28	946	119	2,468
1970 Average .....	--	1,324	147	NA	NA	26	58	144	67	1,528	150	3,419
1975 Average .....	--	4,105	155	NA	NA	60	185	133	184	1,223	70	6,056
1980 Average .....	44	5,263	142	NA	NA	84	226	80	140	939	120	6,909
1985 Average .....	118	3,201	200	NA	NA	67	235	39	381	510	501	5,067
1990 Average .....	27	5,894	278	NA	NA	115	197	108	342	504	695	8,018
1995 Average .....	--	7,230	193	95	6	102	192	106	265	187	662	8,835
2000 Average .....	8	9,071	295	154	7	161	256	162	427	352	897	11,459
2001 Average .....	11	9,328	344	140	6	145	250	148	454	295	1,051	11,871
2002 Average .....	16	9,140	267	137	8	145	199	107	498	249	1,069	11,530
2003 Average .....	--	9,665	333	159	9	168	271	109	518	327	1,041	12,264
2004 Average .....	77	10,088	325	198	11	209	305	127	496	426	1,377	13,145
2005 Average .....	52	10,126	329	219	14	233	374	190	603	530	1,562	13,714
2006 Average .....	8	10,118	365	201	26	228	360	186	475	350	1,854	13,707
2007 Average .....	7	10,031	304	162	20	182	276	217	413	372	1,856	13,468
2008 Average .....	19	9,783	213	162	23	185	275	103	302	349	1,891	12,915
2009 Average .....	56	9,013	225	126	21	147	194	81	223	331	1,623	11,691
2010 Average .....	--	9,213	228	93	29	121	179	98	134	366	1,574	11,793
2011 Average .....	--	8,935	179	82	28	110	183	69	105	328	1,637	11,436
2012 Average .....	--	8,527	126	85	31	116	170	55	44	256	1,421	10,598
2013 Average .....	--	7,730	155	103	24	127	182	84	45	225	1,438	9,859
2014 Average .....	--	7,344	195	89	19	108	143	94	49	173	1,242	9,241
2015 Average .....	--	7,363	200	104	19	124	156	132	71	192	1,335	9,449
2016 Average .....	--	7,850	147	120	22	142	180	147	59	205	1,468	10,055
2017 Average .....	--	7,969	151	133	23	156	196	160	32	189	1,448	10,144
2018 January .....	--	8,018	290	224	15	240	273	121	19	234	1,325	10,280
February .....	--	7,498	284	175	22	197	230	93	33	167	1,281	9,586
March .....	--	7,620	157	149	23	172	216	85	38	234	1,471	9,822
April .....	--	8,254	91	131	10	141	168	88	33	190	1,552	10,375
May .....	--	7,834	122	114	21	135	158	140	62	259	1,652	10,227
June .....	--	8,487	90	85	21	105	136	154	42	224	1,593	10,726
July .....	--	7,936	144	104	21	125	161	151	35	213	1,553	10,193
August .....	--	7,989	176	100	21	121	160	152	82	237	1,638	10,434
September .....	--	7,593	172	110	14	124	172	181	94	227	1,451	9,889
October .....	--	7,354	161	133	15	147	197	116	42	223	1,374	9,468
November .....	--	7,542	227	156	13	169	228	103	29	142	1,003	9,272
December .....	--	7,097	190	190	15	206	268	105	29	180	1,152	9,021
Average .....	--	7,768	175	139	18	157	197	124	45	211	1,422	9,943
2019 January .....	--	7,558	307	214	15	230	297	100	45	197	1,263	9,768
February .....	--	6,670	361	173	13	186	246	140	52	165	1,038	8,671
March .....	--	6,783	180	176	10	186	254	144	103	132	1,308	8,905
April .....	--	6,999	121	124	18	143	207	197	76	136	1,788	9,525
May .....	--	7,154	160	107	21	129	183	188	151	169	1,888	9,893
June .....	--	7,152	126	105	20	125	169	174	53	97	1,525	9,297
July .....	--	6,938	174	106	16	122	180	214	91	102	1,902	9,601
August .....	--	6,944	154	105	17	122	178	175	148	144	1,642	9,387
September .....	--	6,483	118	102	17	119	176	186	111	166	1,472	8,712
October .....	--	6,242	186	116	15	131	198	148	124	116	1,585	8,599
November .....	--	5,818	258	132	13	145	191	131	100	198	1,407	8,103
December .....	--	6,833	295	134	15	149	200	171	62	165	1,435	9,159
Average .....	--	6,801	202	133	16	149	207	164	94	149	1,525	9,141
2020 January .....	--	6,408	217	156	11	168	210	148	91	192	1,306	8,572
February .....	--	6,519	148	120	9	129	157	165	90	169	1,208	8,457
March .....	--	6,296	164	111	15	126	159	150	122	129	1,324	8,345
April .....	--	5,520	231	92	14	105	128	143	90	210	916	7,236
May .....	--	6,087	190	79	14	93	116	125	114	150	975	7,757
June .....	--	6,397	154	59	12	72	109	137	120	155	1,295	8,367
July .....	--	5,906	116	95	14	109	140	166	124	130	1,263	7,846
August .....	--	5,432	145	83	13	95	130	166	115	187	1,289	7,465
September .....	--	5,398	180	124	13	137	172	169	152	206	1,268	7,543
October .....	--	5,293	280	125	14	139	166	145	94	187	1,207	7,372
November .....	--	R 5,570	R 305	R 137	R 12	R 149	R 185	R 148	R 62	R 180	R 1,166	R 7,616
December .....	--	RE 5,523	RE 446	NA	NA	RE 159	NA	RE 133	RE 78	RE 122	NA	RE 7,472
Average .....	--	RE 5,860	RE 215	NA	NA	RE 123	NA	RE 149	RE 104	RE 168	NA	RE 7,836
2021 January .....	--	E 5,953	E 441	NA	NA	E 168	NA	E 116	E 75	E 180	NA	E 8,088

<sup>a</sup> Includes lease condensate.

<sup>b</sup> "SPR" is the Strategic Petroleum Reserve, which began in October 1977. Through 2003, includes crude oil imports by SPR only; beginning in 2004, includes crude oil imports by SPR, and crude oil imports into SPR by others.

<sup>c</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."

<sup>d</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.

<sup>e</sup> Beginning in 1965, includes kerosene-type jet fuel. (Through 1964, kerosene-type jet fuel is included with kerosene in "Other.") For 1956–2004, also includes naphtha-type jet fuel. (Through 1955, naphtha-type jet fuel is included in "Motor Gasoline.") Beginning in 2005, naphtha-type jet fuel is included in "Other."

<sup>f</sup> Finished motor gasoline. Through 1955, also includes naphtha-type jet fuel. Through 1963, also includes aviation gasoline and special naphthas. Through 1980, also includes motor gasoline blending components.

<sup>g</sup> Asphalt and road oil, aviation gasoline blending components, kerosene, lubricants, petrochemical feedstocks, petroleum coke, unfinished oils, waxes, and miscellaneous products. Through 1964, also includes kerosene-type jet fuel. Beginning in 1964, also includes finished aviation gasoline and special naphthas.

Beginning in 1981, also includes motor gasoline blending components. Beginning in 1993, also includes fuel ethanol. Beginning in 2005, also includes naphtha-type jet fuel. Beginning in 2009, also includes renewable fuels (excluding fuel ethanol) and other hydrocarbons. For 2011–2018, also includes oxygenates (excluding fuel ethanol).

R=Revised. E=Estimate. NA=Not available. --=Not applicable. --=No data reported. (s)=Less than 500 barrels per day.

Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • 1949–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • 1976–1980: U.S. Energy Information Administration (EIA), *Energy Data Reports, Petroleum Statement, Annual*, annual reports. • 1981–2019: EIA, *Petroleum Supply Annual*, annual reports, and unpublished revisions. • 2020 and 2021: EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.

**Table 3.3c Petroleum Trade: Imports From OPEC Countries**  
(Thousand Barrels per Day)

	Algeria <sup>a</sup>	Angola <sup>b</sup>	Iraq	Kuwait <sup>c</sup>	Libya <sup>d</sup>	Nigeria <sup>e</sup>	Saudi Arabia <sup>c</sup>	United Arab Emirates	Venezuela	Other <sup>f</sup>	Total OPEC
1960 Average .....	(a)	(b)	22	182	(d)	(e)	84	NA	911	34	1,233
1965 Average .....	(a)	(b)	16	74	42	(e)	158	14	994	142	1,439
1970 Average .....	8	(b)	—	48	47	(e)	30	63	989	109	1,294
1975 Average .....	282	(b)	2	16	232	762	715	117	702	773	3,601
1980 Average .....	488	(b)	28	27	554	857	1,261	172	481	432	4,300
1985 Average .....	187	(b)	46	21	4	293	168	45	605	461	1,830
1990 Average .....	280	(b)	518	86	—	800	1,339	17	1,025	231	4,296
1995 Average .....	234	(b)	—	218	—	627	1,344	10	1,480	88	4,002
2000 Average .....	225	(b)	620	272	—	896	1,572	15	1,546	57	5,203
2001 Average .....	278	(b)	795	250	—	885	1,662	40	1,553	65	5,528
2002 Average .....	264	(b)	459	228	—	621	1,552	15	1,398	68	4,605
2003 Average .....	382	(b)	481	220	—	867	1,774	21	1,376	40	5,162
2004 Average .....	452	(b)	656	250	20	1,140	1,558	20	1,554	50	5,701
2005 Average .....	478	(b)	531	243	56	1,166	1,537	18	1,529	28	5,587
2006 Average .....	657	(b)	553	185	87	1,114	1,463	9	1,419	29	5,517
2007 Average .....	670	508	484	181	117	1,134	1,485	10	1,361	29	5,980
2008 Average .....	548	513	627	210	103	988	1,529	4	1,189	243	5,954
2009 Average .....	493	460	450	182	79	809	1,004	40	1,063	195	4,776
2010 Average .....	510	393	415	197	70	1,023	1,096	2	988	212	4,906
2011 Average .....	358	346	459	191	15	818	1,195	10	951	212	4,555
2012 Average .....	242	233	476	305	61	441	1,365	3	960	186	4,271
2013 Average .....	115	216	341	328	59	281	1,329	3	806	243	3,720
2014 Average .....	110	154	369	311	6	92	1,166	13	789	224	3,237
2015 Average .....	108	136	229	204	7	81	1,059	4	827	239	2,894
2016 Average .....	182	168	424	210	16	235	1,106	14	796	295	3,446
2017 Average .....	189	135	604	145	65	334	955	34	674	231	3,366
<b>2018</b> January .....	234	71	699	100	76	349	744	20	528	187	3,009
February .....	119	34	617	177	38	386	667	63	472	167	2,740
March .....	107	10	721	131	79	253	760	107	561	216	2,845
April .....	208	169	834	107	87	175	904	43	632	265	3,523
May .....	134	118	583	49	40	102	872	45	559	229	2,731
June .....	147	193	421	92	75	267	847	109	643	246	3,041
July .....	243	188	485	63	44	43	876	30	625	375	2,971
August .....	198	146	421	83	19	66	1,039	43	592	250	2,857
September .....	200	73	485	36	61	113	1,043	67	708	211	2,996
October .....	178	94	377	—	32	182	1,108	63	570	124	2,729
November .....	162	28	392	101	(s)	180	1,001	59	563	218	2,703
December .....	183	—	226	16	121	177	930	55	576	232	2,516
<b>Average</b> .....	<b>176</b>	<b>94</b>	<b>521</b>	<b>79</b>	<b>56</b>	<b>189</b>	<b>901</b>	<b>58</b>	<b>586</b>	<b>227</b>	<b>2,888</b>
<b>2019</b> January .....	98	10	429	21	60	181	777	27	634	317	2,553
February .....	51	—	422	106	36	33	663	32	289	171	1,803
March .....	136	10	275	129	25	142	666	3	69	187	1,643
April .....	125	43	265	61	88	137	583	22	114	128	1,566
May .....	142	46	366	57	111	243	462	22	11	233	1,693
June .....	122	123	355	26	55	251	579	16	(s)	171	1,699
July .....	75	—	360	20	39	193	454	36	—	243	1,420
August .....	63	47	249	46	66	380	461	19	—	329	1,660
September .....	49	71	400	—	69	245	458	121	—	189	1,601
October .....	23	75	252	—	86	128	444	22	—	271	1,301
November .....	34	25	283	41	90	211	355	5	—	278	1,322
December .....	16	11	436	43	34	163	470	—	—	238	1,411
<b>Average</b> .....	<b>78</b>	<b>38</b>	<b>341</b>	<b>45</b>	<b>63</b>	<b>193</b>	<b>530</b>	<b>27</b>	<b>92</b>	<b>231</b>	<b>1,639</b>
<b>2020</b> January .....	17	10	299	46	67	64	407	7	—	8	926
February .....	33	33	262	46	36	76	488	6	—	(s)	981
March .....	12	—	290	23	—	54	445	4	—	3	831
April .....	1	30	140	—	—	57	431	13	—	3	675
May .....	1	50	242	—	—	69	1,158	2	—	9	1,532
June .....	7	66	146	34	—	103	1,221	39	—	2	1,617
July .....	4	7	136	84	—	34	718	29	—	—	1,014
August .....	11	12	209	—	(s)	114	273	3	—	—	622
September .....	14	32	83	35	(s)	91	366	14	—	32	667
October .....	3	72	121	34	—	30	280	80	—	67	686
November .....	19	49	111	34	—	119	286	13	—	2	632
<b>11-Month Average</b> .....	<b>11</b>	<b>33</b>	<b>186</b>	<b>31</b>	<b>9</b>	<b>74</b>	<b>552</b>	<b>19</b>	<b>—</b>	<b>12</b>	<b>926</b>
<b>2019 11-Month Average</b> .....	<b>84</b>	<b>41</b>	<b>332</b>	<b>46</b>	<b>66</b>	<b>196</b>	<b>536</b>	<b>29</b>	<b>101</b>	<b>230</b>	<b>1,660</b>
<b>2018 11-Month Average</b> .....	<b>176</b>	<b>103</b>	<b>548</b>	<b>84</b>	<b>50</b>	<b>190</b>	<b>898</b>	<b>59</b>	<b>587</b>	<b>227</b>	<b>2,922</b>

<sup>a</sup> Algeria joined OPEC in 1969. For 1960–1968, Algeria is included in "Total Non-OPEC" on Table 3.3d.

<sup>b</sup> Angola joined OPEC in January 2007. For 1960–2006, Angola is included in "Total Non-OPEC" on Table 3.3d.

<sup>c</sup> Through 1970, includes half the imports from the Neutral Zone between Kuwait and Saudi Arabia. Beginning in 1971, imports from the Neutral Zone are reported as originating in either Kuwait or Saudi Arabia depending on the country reported to U.S. Customs.

<sup>d</sup> Libya joined OPEC in 1962. For 1960 and 1961, Libya is included in "Total Non-OPEC" on Table 3.3d.

<sup>e</sup> Nigeria joined OPEC in 1971. For 1960–1970, Nigeria is included in "Total Non-OPEC" on Table 3.3d.

<sup>f</sup> Includes these countries for the dates indicated: Congo-Brazzaville (June 2018 forward), Ecuador (1973–1992 and November 2007–2019), Equatorial Guinea (May 2017 forward), Gabon (1975–1994 and July 2016 forward), Indonesia (1962–2008 and January–November 2016), Iran (1960 forward), and Qatar (1961–2018).

NA=Not available. —=No data reported. (s)=Less than 500 barrels per day.

Notes: • See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. Petroleum imports not classified as "OPEC" on this table are included on Table 3.3d. • The country of origin for petroleum products may not be the country of origin for the crude oil from which the products were produced. For example, refined products imported from West European refining areas may have been produced from Middle East crude oil. • Includes imports for the Strategic Petroleum Reserve, which began in October 1977. • Totals may not equal sum of components due to independent rounding. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1960 and monthly data beginning in 1973.

Sources: • **1960–1972:** Bureau of Mines, *Minerals Yearbook*, annual reports. • **1973–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports. • **2020:** EIA, *Petroleum Supply Monthly*, monthly reports.

**Table 3.3d Petroleum Trade: Imports From Non-OPEC Countries**  
(Thousand Barrels per Day)

	Brazil	Canada	Colombia	Ecuador <sup>a</sup>	Mexico	Nether-lands	Norway	Russia <sup>b</sup>	United Kingdom	U.S. Virgin Islands	Other	Total Non-OPEC
1960 Average .....	1	120	42	NA	16	NA	NA	—	(s)	NA	NA	581
1965 Average .....	—	323	51	—	48	1	—	—	(s)	—	606	1,029
1970 Average .....	2	766	46	—	42	39	—	3	11	189	1,027	2,126
1975 Average .....	5	846	9	(a)	71	19	17	14	14	406	1,052	2,454
1980 Average .....	3	455	4	(a)	533	2	144	1	176	388	903	2,609
1985 Average .....	61	770	23	(a)	816	58	32	8	310	247	913	3,237
1990 Average .....	49	934	182	(a)	755	55	102	45	189	282	1,128	3,721
1995 Average .....	8	1,332	219	97	1,068	15	273	25	383	278	1,136	4,833
2000 Average .....	51	1,807	342	128	1,373	30	343	72	366	291	1,453	6,257
2001 Average .....	82	1,828	296	120	1,440	43	341	90	324	268	1,511	6,343
2002 Average .....	116	1,971	260	110	1,547	66	393	210	478	236	1,539	6,925
2003 Average .....	108	2,072	195	145	1,623	87	270	254	440	288	1,622	7,103
2004 Average .....	104	2,138	176	245	1,665	101	244	298	380	330	1,763	7,444
2005 Average .....	156	2,181	196	283	1,662	151	233	410	396	328	2,130	8,127
2006 Average .....	193	2,353	155	278	1,705	174	196	369	272	328	2,168	8,190
2007 Average .....	200	2,455	155	203	1,532	128	142	414	277	346	1,636	7,489
2008 Average .....	258	2,493	200	(a)	1,302	168	102	465	236	320	1,416	6,961
2009 Average .....	309	2,479	276	(a)	1,210	140	108	563	245	277	1,307	6,915
2010 Average .....	272	2,535	365	(a)	1,284	108	89	612	256	253	1,112	6,887
2011 Average .....	253	2,729	433	(a)	1,206	100	113	624	159	186	1,077	6,881
2012 Average .....	226	2,946	433	(a)	1,035	99	75	477	149	12	874	6,327
2013 Average .....	151	3,142	389	(a)	919	89	54	460	147	—	786	6,138
2014 Average .....	160	3,388	318	(a)	842	85	45	330	117	—	720	6,004
2015 Average .....	215	3,765	395	(a)	758	57	61	371	123	—	811	6,554
2016 Average .....	167	3,780	483	(a)	669	60	76	441	122	(s)	812	6,610
2017 Average .....	224	4,054	362	(a)	682	62	79	389	111	—	814	6,778
2018 January .....	272	4,442	512	(a)	669	68	57	386	79	—	786	7,271
February .....	187	4,263	477	(a)	713	50	56	297	110	—	692	6,846
March .....	84	4,195	364	(a)	784	91	91	356	84	—	929	6,977
April .....	184	4,278	282	(a)	632	64	122	243	205	—	843	6,852
May .....	123	4,467	437	(a)	608	78	72	491	180	—	1,039	7,496
June .....	283	4,553	240	(a)	886	53	85	439	152	—	995	7,685
July .....	179	4,173	319	(a)	681	43	166	454	164	—	1,042	7,222
August .....	249	4,239	319	(a)	935	68	39	515	175	—	1,038	7,577
September .....	77	4,038	229	(a)	771	44	74	519	207	—	935	6,893
October .....	230	4,193	229	(a)	718	89	138	271	106	—	765	6,739
November .....	93	4,384	259	(a)	601	49	136	254	155	—	640	6,569
December .....	92	4,277	333	(a)	635	49	94	271	132	—	620	6,505
Average .....	171	4,292	333	(a)	719	62	94	375	146	—	862	7,055
2019 January .....	141	4,655	380	(a)	569	103	88	344	122	—	813	7,215
February .....	90	4,320	420	(a)	720	108	69	226	47	—	867	6,868
March .....	172	4,429	412	(a)	712	68	80	363	118	—	907	7,262
April .....	153	4,412	472	(a)	680	124	112	566	182	—	1,258	7,958
May .....	256	4,428	468	(a)	656	218	147	564	266	—	1,198	8,200
June .....	213	4,398	395	(a)	574	88	190	534	156	—	1,050	7,598
July .....	338	4,674	379	(a)	670	121	51	496	182	—	1,270	8,181
August .....	197	4,379	384	(a)	744	138	94	617	146	—	1,027	7,726
September .....	186	4,285	283	(a)	589	121	123	486	179	—	859	7,111
October .....	285	4,422	266	(a)	548	95	40	675	130	—	838	7,298
November .....	125	3,963	284	(a)	705	96	46	649	139	—	774	6,782
December .....	143	4,784	340	(a)	641	76	48	696	81	—	939	7,749
Average .....	193	4,432	373	(a)	650	113	91	520	146	—	984	7,502
2020 January .....	101	4,505	337	242	854	48	1	601	109	—	848	7,646
February .....	134	4,583	343	236	804	64	—	614	74	—	624	7,476
March .....	120	4,366	322	260	801	114	18	645	62	—	805	7,514
April .....	104	4,088	277	176	631	93	16	408	54	—	713	6,561
May .....	110	3,682	250	58	889	24	44	350	101	—	716	6,225
June .....	159	3,760	369	112	849	98	99	551	87	—	667	6,751
July .....	115	3,981	331	108	755	72	12	563	84	—	808	6,831
August .....	113	3,877	186	242	769	91	20	552	64	—	928	6,843
September .....	92	3,945	351	227	715	125	15	527	91	—	789	6,876
October .....	113	3,968	248	165	574	56	60	660	113	—	727	6,685
November .....	166	4,287	175	227	611	72	36	570	66	—	775	6,984
11-Month Average ...	121	4,093	290	186	750	78	29	549	82	—	765	6,943
2019 11-Month Average ...	197	4,399	376	(a)	651	117	94	504	152	—	988	7,479
2018 11-Month Average ...	178	4,293	333	(a)	727	64	94	385	147	—	884	7,106

<sup>a</sup> Ecuador was a member of OPEC from 1973–1992 and November 2007–2019. For those time periods, Ecuador is included in "Total OPEC" on Table 3.3c.

<sup>b</sup> Through 1992, may include imports from republics other than Russia in the former U.S.S.R. See "Union of Soviet Socialist Republics (U.S.S.R.)" in Glossary. NA=Not available. —=No data reported. (s)=Less than 500 barrels per day.

Notes: • See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. Petroleum imports not classified as "OPEC" on Table 3.3c are included on this table. • The country of origin for petroleum products may not be the country of origin for the crude oil from which the products were produced. For example, refined products imported from West European refining areas may have been produced from Middle East crude oil. • Includes imports for the Strategic Petroleum Reserve, which began in October 1977. • Totals may not equal sum of

components due to independent rounding. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1960 and monthly data beginning in 1973.

Sources: • **1960–1972:** Bureau of Mines, *Minerals Yearbook*, annual reports. • **1973–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports. • **2020:** EIA, *Petroleum Supply Monthly*, monthly reports.

**Table 3.3e Petroleum Trade: Exports by Type**  
(Thousand Barrels per Day)

	Crude Oil <sup>a</sup>	Distillate Fuel Oil	Hydrocarbon Gas Liquids		Jet Fuel <sup>d</sup>	Motor Gasoline <sup>e</sup>	Residual Fuel Oil	Other <sup>f</sup>	Total
			Propane <sup>b</sup>	Total <sup>c</sup>					
1950 Average .....	95	34	NA	4	( <sup>d</sup> )	68	44	58	305
1955 Average .....	32	67	NA	12	(s)	95	93	69	368
1960 Average .....	8	27	NA	8	(s)	37	51	71	202
1965 Average .....	3	10	NA	21	3	2	41	108	187
1970 Average .....	14	2	13	27	6	1	54	154	259
1975 Average .....	6	1	13	26	2	2	15	158	209
1980 Average .....	287	3	10	21	1	1	33	197	544
1985 Average .....	204	67	48	64	13	10	197	225	781
1990 Average .....	109	109	28	41	43	55	211	287	857
1995 Average .....	95	183	38	59	26	104	136	12	949
2000 Average .....	50	173	53	78	32	144	139	46	1,040
2001 Average .....	20	119	31	45	29	133	191	433	971
2002 Average .....	9	112	55	67	15	124	177	479	984
2003 Average .....	12	107	37	59	20	125	197	506	1,027
2004 Average .....	27	110	28	45	40	124	205	497	1,048
2005 Average .....	32	138	37	60	53	136	251	496	1,165
2006 Average .....	25	215	45	68	41	142	283	544	1,317
2007 Average .....	27	268	42	70	41	127	330	569	1,433
2008 Average .....	29	528	53	101	61	172	355	555	1,802
2009 Average .....	44	587	85	139	69	195	415	574	2,024
2010 Average .....	42	656	109	164	84	296	405	706	2,353
2011 Average .....	47	854	124	249	97	479	424	835	2,986
2012 Average .....	67	1,007	171	314	132	409	388	886	3,205
2013 Average .....	134	1,134	302	468	156	373	362	994	3,621
2014 Average .....	351	1,101	423	703	163	442	364	1,052	4,176
2015 Average .....	465	1,176	615	966	168	476	326	1,161	4,738
2016 Average .....	591	1,179	799	1,211	175	635	298	1,171	5,261
2017 Average .....	1,158	1,381	914	1,404	184	749	308	1,192	6,376
<b>2018</b> January .....	1,362	999	849	1,456	197	975	279	1,194	6,461
February .....	1,735	1,034	818	1,436	176	934	313	1,278	6,907
March .....	1,969	1,128	889	1,427	247	951	332	1,281	7,337
April .....	1,919	1,464	876	1,670	226	867	323	1,329	7,797
May .....	2,067	1,372	1,003	1,753	245	720	394	1,167	7,717
June .....	2,279	1,467	877	1,619	215	686	353	1,205	7,824
July .....	2,307	1,302	1,075	1,663	269	821	334	1,267	7,963
August .....	1,859	1,278	1,033	1,660	223	681	384	1,079	7,164
September .....	2,015	1,298	823	1,582	166	815	279	1,260	7,415
October .....	2,256	1,334	928	1,614	277	1,009	330	1,190	8,011
November .....	2,400	1,392	1,038	1,659	215	1,072	231	1,313	8,281
December .....	2,391	1,385	1,163	1,671	211	1,017	301	1,325	8,301
<b>Average</b> .....	<b>2,048</b>	<b>1,289</b>	<b>949</b>	<b>1,602</b>	<b>223</b>	<b>879</b>	<b>321</b>	<b>1,240</b>	<b>7,601</b>
<b>2019</b> January .....	2,643	1,280	1,030	1,561	264	826	230	1,178	7,982
February .....	2,915	1,160	892	1,517	192	912	242	1,281	8,219
March .....	2,673	1,173	918	1,652	173	873	243	1,159	7,946
April .....	2,911	1,261	1,166	1,923	195	655	357	1,081	8,382
May .....	2,959	1,287	1,085	1,802	194	742	301	954	8,238
June .....	3,100	1,516	1,158	1,860	213	699	194	994	8,576
July .....	2,706	1,374	1,188	1,893	209	683	142	1,077	8,084
August .....	2,755	1,530	1,035	1,832	254	696	287	1,084	8,438
September .....	3,093	1,427	1,124	1,885	243	783	202	1,040	8,672
October .....	3,412	1,205	1,168	2,081	222	898	148	1,074	9,039
November .....	3,080	1,148	1,159	1,981	226	1,049	204	1,053	8,741
December .....	3,537	1,301	1,235	1,955	256	964	199	1,119	9,331
<b>Average</b> .....	<b>2,982</b>	<b>1,306</b>	<b>1,098</b>	<b>1,830</b>	<b>220</b>	<b>815</b>	<b>229</b>	<b>1,090</b>	<b>8,471</b>
<b>2020</b> January .....	3,251	1,263	1,263	2,163	215	822	169	1,294	9,177
February .....	3,708	1,380	1,191	2,202	246	881	231	1,335	9,983
March .....	3,557	1,459	1,337	2,139	214	777	152	1,325	9,621
April .....	3,077	1,096	1,213	2,067	66	762	157	1,226	8,452
May .....	2,929	733	1,053	1,846	23	314	145	828	6,818
June .....	2,753	1,330	1,250	2,032	44	468	154	912	7,692
July .....	3,267	1,368	1,218	2,008	54	597	121	997	8,412
August .....	3,298	1,337	1,139	1,996	30	764	125	946	8,498
September .....	3,238	1,177	1,210	2,015	45	782	141	978	8,376
October .....	2,935	1,078	1,375	2,285	40	824	100	1,094	8,356
November .....	<sup>R</sup> 2,726	<sup>R</sup> 982	<sup>R</sup> 1,331	<sup>R</sup> 2,135	<sup>R</sup> 79	<sup>R</sup> 832	<sup>R</sup> 128	<sup>R</sup> 942	<sup>R</sup> 7,823
December .....	<sup>RE</sup> 3,109	<sup>RE</sup> 1,144	NA	NA	<sup>RE</sup> 73	<sup>RE</sup> 841	<sup>RE</sup> 93	NA	<sup>RE</sup> 8,351
<b>Average</b> .....	<sup>RE</sup> <b>3,153</b>	<sup>RE</sup> <b>1,195</b>	<b>NA</b>	<b>NA</b>	<sup>RE</sup> <b>94</b>	<sup>RE</sup> <b>721</b>	<sup>RE</sup> <b>142</b>	<b>NA</b>	<sup>RE</sup> <b>8,459</b>
<b>2021</b> January .....	<sup>E</sup> 2,986	<sup>E</sup> 898	NA	NA	<sup>E</sup> 99	<sup>E</sup> 729	<sup>E</sup> 93	NA	<sup>E</sup> 8,155

<sup>a</sup> Includes lease condensate.

<sup>b</sup> Through 1983, also includes 40% of "Butane-Propane Mixtures." Through 2012, also includes propylene.

<sup>c</sup> Ethane, propane, normal butane, isobutane, and natural gasoline (pentanes plus). Through 2012, also includes refinery olefins (ethylene, propylene, butylene, and isobutylene).

<sup>d</sup> Beginning in 1965, includes kerosene-type jet fuel. (Through 1964, kerosene-type jet fuel is included with kerosene in "Other.") For 1953–2004, also includes naphtha-type jet fuel. (Through 1952, naphtha-type jet fuel is included in the products from which it was blended: motor gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other.")

<sup>e</sup> Finished motor gasoline. Through 1952, also includes naphtha-type jet fuel. Through 1963, also includes aviation gasoline and special naphthas. Through 1980, also includes motor gasoline blending components.

<sup>f</sup> Asphalt and road oil, kerosene, lubricants, petrochemical feedstocks, petroleum coke, unfinished oils, waxes, and miscellaneous products. Through 1964, also includes kerosene-type jet fuel. Beginning in 1964, also includes finished aviation gasoline and special naphthas. Beginning in 1981, also includes

motor gasoline blending components. Beginning in 2005, also includes naphtha-type jet fuel. For 2009–2018, also includes oxygenates (excluding fuel ethanol). Beginning in 2010, also includes fuel ethanol. Beginning in 2011, also includes renewable fuels (excluding fuel ethanol).

R=Revised. E=Estimate. NA=Not available. (s)=Less than 500 barrels per day.

Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **1949–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), *Energy Data Reports, Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports, and unpublished revisions. • **2020 and 2021:** EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.

**Table 3.3f Petroleum Trade: Exports by Country of Destination**  
(Thousand Barrels per Day)

	Brazil	Canada	China	India	Japan	Mexico	Nether-lands	Singa-pore	South Korea	United Kingdom	Other	Total
<b>1960 Average</b> .....	4	34	NA	NA	62	18	6	NA	NA	12	NA	202
<b>1965 Average</b> .....	3	26	NA	NA	40	27	10	NA	NA	12	NA	187
<b>1970 Average</b> .....	7	31	NA	NA	69	33	15	NA	NA	12	NA	259
<b>1975 Average</b> .....	6	22	NA	1	27	42	23	NA	NA	7	NA	209
<b>1980 Average</b> .....	4	108	—	1	32	28	23	6	2	7	335	544
<b>1985 Average</b> .....	3	74	—	2	108	61	44	24	27	14	424	781
<b>1990 Average</b> .....	2	91	—	6	92	89	54	15	60	11	438	857
<b>1995 Average</b> .....	16	73	2	3	76	125	33	46	57	14	505	949
<b>2000 Average</b> .....	28	110	3	3	90	358	42	36	20	10	342	1,040
<b>2001 Average</b> .....	23	112	6	3	62	274	45	67	14	13	352	971
<b>2002 Average</b> .....	26	106	14	3	74	254	23	81	11	12	380	984
<b>2003 Average</b> .....	27	141	24	7	69	228	15	51	10	6	447	1,027
<b>2004 Average</b> .....	27	158	13	11	63	209	36	41	12	14	464	1,048
<b>2005 Average</b> .....	39	181	12	11	56	268	25	43	16	21	492	1,165
<b>2006 Average</b> .....	42	159	11	8	58	255	83	45	21	28	607	1,317
<b>2007 Average</b> .....	46	189	14	14	54	279	81	71	16	9	660	1,433
<b>2008 Average</b> .....	54	264	13	10	54	333	131	77	18	17	830	1,802
<b>2009 Average</b> .....	55	223	44	30	58	322	192	115	23	33	928	2,024
<b>2010 Average</b> .....	123	233	52	10	88	448	165	128	13	19	1,073	2,353
<b>2011 Average</b> .....	157	351	73	17	79	570	248	121	15	35	1,320	2,986
<b>2012 Average</b> .....	166	416	85	36	89	565	239	115	16	41	1,435	3,205
<b>2013 Average</b> .....	179	549	129	41	117	532	274	136	13	36	1,616	3,621
<b>2014 Average</b> .....	217	809	89	70	150	559	241	124	46	53	1,817	4,176
<b>2015 Average</b> .....	188	955	191	78	166	690	226	122	65	89	1,968	4,738
<b>2016 Average</b> .....	260	935	203	140	250	880	265	147	108	92	1,980	5,261
<b>2017 Average</b> .....	395	871	447	200	350	1,081	251	210	176	186	2,209	6,376
<b>2018 January</b> .....	363	997	523	141	407	1,137	275	193	56	155	2,215	6,461
February .....	349	1,135	606	203	323	1,154	238	232	175	223	2,268	6,907
March .....	399	959	703	400	318	1,261	230	94	238	305	2,429	7,337
April .....	400	1,115	558	205	350	1,238	369	218	213	319	2,812	7,797
May .....	308	1,162	494	268	279	1,067	229	291	377	265	2,977	7,717
June .....	450	1,062	554	500	344	1,008	295	223	451	260	2,678	7,824
July .....	354	1,127	513	241	495	1,343	322	125	413	233	2,797	7,963
August .....	358	933	130	291	443	1,088	301	176	478	291	2,675	7,164
September .....	380	965	52	265	572	1,153	418	200	385	267	2,756	7,415
October .....	554	1,023	107	378	459	1,358	462	176	555	303	2,637	8,011
November .....	401	875	62	308	789	1,354	503	263	445	267	3,011	8,281
December .....	476	937	203	362	807	1,169	399	43	772	372	2,761	8,301
<b>Average</b> .....	<b>400</b>	<b>1,024</b>	<b>374</b>	<b>297</b>	<b>466</b>	<b>1,194</b>	<b>337</b>	<b>185</b>	<b>382</b>	<b>272</b>	<b>2,670</b>	<b>7,601</b>
<b>2019 January</b> .....	457	878	93	401	646	1,177	620	37	339	375	2,957	7,982
February .....	328	1,163	177	455	284	1,234	442	184	607	368	2,977	8,219
March .....	564	944	129	673	505	1,210	372	140	506	263	2,640	7,946
April .....	428	1,155	80	575	516	1,197	440	119	397	293	3,181	8,382
May .....	428	1,030	300	469	580	1,018	294	124	501	372	3,121	8,238
June .....	565	861	424	438	440	993	525	82	807	286	3,155	8,576
July .....	466	979	286	231	589	1,165	355	79	759	269	2,905	8,084
August .....	443	1,052	300	417	574	1,043	373	63	616	383	3,174	8,438
September .....	585	1,013	317	396	633	1,056	478	149	606	322	3,116	8,672
October .....	446	1,190	36	586	558	1,208	553	137	618	285	3,423	9,039
November .....	476	1,148	133	400	595	1,355	360	168	613	371	3,122	8,741
December .....	493	1,026	78	480	709	1,242	595	237	590	439	3,441	9,331
<b>Average</b> .....	<b>474</b>	<b>1,035</b>	<b>196</b>	<b>460</b>	<b>555</b>	<b>1,158</b>	<b>451</b>	<b>126</b>	<b>580</b>	<b>336</b>	<b>3,102</b>	<b>8,471</b>
<b>2020 January</b> .....	462	1,253	98	498	683	1,168	471	150	758	394	3,243	9,177
February .....	546	1,212	82	525	481	1,135	671	280	492	567	3,991	9,983
March .....	512	1,002	251	546	714	1,244	460	248	427	414	3,803	9,621
April .....	410	862	369	458	635	872	380	472	375	290	3,328	8,452
May .....	275	698	1,450	350	489	536	301	147	348	253	1,969	6,818
June .....	299	785	906	559	471	826	411	253	392	303	2,488	7,692
July .....	431	894	851	345	663	975	507	77	409	392	2,866	8,412
August .....	497	760	823	336	390	1,114	478	174	467	456	3,004	8,498
September .....	454	1,045	1,017	429	392	1,039	373	109	431	242	2,847	8,376
October .....	518	850	960	477	458	1,079	375	51	422	347	2,820	8,356
November .....	397	842	637	563	467	1,187	535	60	295	290	2,550	7,823
<b>11-Month Average</b> .....	<b>436</b>	<b>926</b>	<b>680</b>	<b>462</b>	<b>532</b>	<b>1,016</b>	<b>450</b>	<b>183</b>	<b>438</b>	<b>359</b>	<b>2,988</b>	<b>8,469</b>
<b>2019 11-Month Average</b> .....	<b>472</b>	<b>1,036</b>	<b>207</b>	<b>458</b>	<b>540</b>	<b>1,150</b>	<b>437</b>	<b>116</b>	<b>579</b>	<b>326</b>	<b>3,070</b>	<b>8,392</b>
<b>2018 11-Month Average</b> .....	<b>393</b>	<b>1,032</b>	<b>390</b>	<b>291</b>	<b>434</b>	<b>1,197</b>	<b>331</b>	<b>199</b>	<b>345</b>	<b>263</b>	<b>2,661</b>	<b>7,536</b>

NA=Not available. — =No data reported.


Notes: • Totals may not equal sum of components due to independent rounding. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1960 and monthly data beginning in 1981.


Sources: • **1960–1972:** Bureau of Mines, *Minerals Yearbook*, annual reports. • **1973–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports. • **2020:** EIA, *Petroleum Supply Monthly*, monthly reports.

**Figure 3.4 Petroleum Stocks**


Overview, 1949–2020




SPR and Non-SPR Crude Oil Stocks, 1949–2020



Overview, Monthly



Selected Products, Monthly



[a] Includes kerosene-type jet fuel only.

Notes: • SPR=Strategic Petroleum Reserve. • Stocks are at end of period.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Source: Table 3.4.

**Table 3.4 Petroleum Stocks**  
(Million Barrels)

	Crude Oil <sup>a</sup>			Distillate Fuel Oil <sup>e</sup>	Hydrocarbon Gas Liquids				Jet Fuel <sup>i</sup>	Motor Gasoline <sup>j</sup>	Residual Fuel Oil <sup>k</sup>	Other <sup>l</sup>	Total
					Propane/Propylene			Total <sup>h</sup>					
					SPR <sup>b</sup>	Non-SPR <sup>c,d</sup>	Total <sup>d</sup>		Propane				
1950 Year .....	--	248	248	72	NA	NA	NA	2	( i )	116	41	104	583
1955 Year .....	--	266	266	111	NA	NA	NA	7	3	165	39	123	715
1960 Year .....	--	240	240	138	NA	NA	NA	23	7	195	45	137	785
1965 Year .....	--	220	220	155	NA	NA	NA	35	19	175	56	176	836
1970 Year .....	--	276	276	195	NA	NA	44	74	28	209	54	181	1,018
1975 Year .....	--	271	271	209	NA	NA	82	133	30	235	74	181	1,133
1980 Year .....	108	358	466	205	NA	NA	71	137	42	261	92	189	1,392
1985 Year .....	493	321	814	144	NA	NA	39	82	40	223	50	165	1,519
1990 Year .....	586	323	908	132	NA	NA	49	104	52	220	49	156	1,621
1995 Year .....	592	303	895	130	NA	NA	43	100	40	202	37	158	1,563
2000 Year .....	541	286	826	118	NA	NA	41	88	45	196	36	159	1,468
2001 Year .....	550	312	862	145	NA	NA	66	128	42	210	41	158	1,586
2002 Year .....	599	278	877	134	NA	NA	53	113	39	209	31	144	1,548
2003 Year .....	638	269	907	137	NA	NA	50	101	39	207	38	140	1,568
2004 Year .....	676	286	961	126	NA	NA	55	111	40	218	42	146	1,645
2005 Year .....	685	308	992	136	NA	NA	57	117	42	208	37	148	1,682
2006 Year .....	689	296	984	144	NA	NA	62	125	39	212	42	157	1,703
2007 Year .....	697	268	965	134	NA	NA	52	106	39	218	39	146	1,648
2008 Year .....	702	308	1,010	146	NA	NA	55	127	38	214	36	149	1,719
2009 Year .....	727	307	1,034	166	NA	NA	50	113	43	223	37	142	1,758
2010 Year .....	727	312	1,039	164	46	2	47	118	43	219	41	145	1,770
2011 Year .....	696	308	1,004	149	48	2	50	121	41	223	34	146	1,720
2012 Year .....	695	338	1,033	135	63	2	64	148	40	231	34	154	1,775
2013 Year .....	696	327	1,023	128	40	1	42	121	37	228	38	149	1,724
2014 Year .....	691	361	1,052	136	72	2	74	170	38	240	34	151	1,822
2015 Year .....	695	449	1,144	161	91	2	93	192	40	235	42	164	1,979
2016 Year .....	695	485	1,180	166	77	2	79	196	43	239	41	161	2,025
2017 Year .....	663	422	1,084	146	62	2	64	187	41	237	29	167	1,892
2018 January .....	664	421	1,085	141	45	2	47	153	43	249	32	177	1,879
February .....	665	424	1,089	139	39	1	40	137	43	253	33	181	1,875
March .....	665	425	1,090	130	34	1	35	136	40	240	35	190	1,861
April .....	664	437	1,101	121	35	1	37	142	41	240	32	188	1,865
May .....	660	434	1,094	116	44	1	45	159	42	243	32	185	1,870
June .....	660	415	1,075	121	57	1	58	179	41	241	30	181	1,867
July .....	660	410	1,070	127	60	2	62	194	41	234	29	177	1,873
August .....	660	408	1,068	132	67	2	68	212	42	236	28	174	1,892
September .....	660	417	1,077	137	75	2	77	223	47	240	29	178	1,931
October .....	655	434	1,089	125	79	2	81	222	42	233	29	176	1,915
November .....	650	449	1,099	127	74	2	76	205	39	230	30	178	1,907
December .....	649	443	1,092	140	64	2	66	184	42	247	28	176	1,908
2019 January .....	649	449	1,098	140	51	1	53	161	41	262	30	182	1,914
February .....	649	452	1,101	136	46	1	47	151	42	252	28	187	1,897
March .....	649	459	1,108	132	49	2	51	160	42	237	29	186	1,894
April .....	649	470	1,118	128	53	2	55	175	41	231	29	190	1,912
May .....	645	481	1,126	130	63	2	65	202	39	236	30	189	1,952
June .....	645	463	1,108	131	72	2	73	224	41	230	30	184	1,949
July .....	645	442	1,086	138	78	2	80	238	43	235	31	182	1,954
August .....	645	430	1,075	136	91	2	93	256	43	230	29	177	1,946
September .....	645	426	1,070	132	96	3	98	263	44	232	30	172	1,943
October .....	641	443	1,085	120	95	2	97	253	40	224	30	176	1,927
November .....	635	446	1,081	126	88	2	90	232	41	234	33	172	1,918
December .....	635	433	1,068	140	80	2	81	212	40	254	31	172	1,917
2020 January .....	635	443	1,078	143	75	2	76	195	44	264	31	179	1,934
February .....	635	454	1,089	133	64	1	65	179	43	252	31	188	1,914
March .....	635	482	1,117	127	60	1	62	181	40	261	34	196	1,956
April .....	638	529	1,167	151	62	1	63	196	40	257	37	188	2,035
May .....	648	521	1,169	176	67	1	68	210	40	258	39	181	2,074
June .....	656	532	1,188	175	75	2	77	234	42	253	40	177	2,109
July .....	656	519	1,175	178	85	1	87	257	41	249	36	171	2,107
August .....	648	504	1,152	179	95	2	97	283	40	237	35	159	2,084
September .....	642	497	1,140	172	101	2	102	299	40	227	32	155	2,064
October .....	639	494	1,132	155	95	1	96	287	38	227	31	154	2,024
November .....	638	R 500	R 1,139	R 156	R 90	R 1	R 92	R 267	R 38	R 241	R 31	R 155	R 2,028
December .....	RE 638	RE 485	RE 1,124	RE 158	NA	NA	RE 73	RF 233	RE 39	RE 241	RE 30	RE 157	RE 1,982
2021 January .....	E 638	E 473	E 1,111	E 162	NA	NA	E 54	F 188	E 42	E 254	E 33	E 168	E 1,958

<sup>a</sup> Includes lease condensate.  
<sup>b</sup> "SPR" is the Strategic Petroleum Reserve, which began in October 1977. Crude oil stocks in the SPR include non-U.S. stocks held under foreign or commercial storage agreements.  
<sup>c</sup> All crude oil stocks other than those in "SPR."  
<sup>d</sup> Beginning in 1981, includes stocks of Alaskan crude oil in transit.  
<sup>e</sup> Excludes stocks in the Northeast Home Heating Oil Reserve. Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.  
<sup>f</sup> Includes propylene stocks at refineries only.  
<sup>g</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."  
<sup>h</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.  
<sup>i</sup> Beginning in 1965, includes kerosene-type jet fuel. (Through 1964, kerosene-type jet fuel is included with kerosene in "Other.") For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other.")  
<sup>j</sup> Includes finished motor gasoline and motor gasoline blending components; excludes oxygenates. Through 1963, also includes aviation gasoline and special naphthas.  
<sup>k</sup> Through 2019, includes residual fuel oil stocks at (or in) refineries, bulk terminals, and pipelines. Beginning in 2020, includes residual fuel oil stocks at


refineries and bulk terminals only.  
<sup>l</sup> Asphalt and road oil, aviation gasoline blending components, kerosene, lubricants, petrochemical feedstocks, petroleum coke, unfinished oils, waxes, and miscellaneous products. Through 1964, also includes kerosene-type jet fuel. Beginning in 1964, also includes finished aviation gasoline and special naphthas. Beginning in 1993, also includes fuel ethanol. Beginning in 2005, also includes naphtha-type jet fuel. For 2005–2018, also includes oxygenates (excluding fuel ethanol). Beginning in 2009, also includes renewable fuels (excluding fuel ethanol) and other hydrocarbons.  
R=Revised. E=Estimate. F=Forecast. NA=Not available. -- =Not applicable.  
Notes: • Stocks are at end of period. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
Sources: • 1949–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • 1976–1980: U.S. Energy Information Administration (EIA), *Energy Data Reports, Petroleum Statement, Annual*, annual reports. • 1981–2019: EIA, *Petroleum Supply Annual*, annual reports, and unpublished revisions. • 2020 and 2021: EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system, Short-Term Integrated Forecasting System, and *Monthly Energy Review* data system calculations.




**Figure 3.5 Petroleum Products Supplied by Type**

(Million Barrels per Day)


Total Petroleum and Motor Gasoline, 1949–2020




Selected Products, 1949–2020



Selected Products, Monthly



Total, January



[a] Beginning in 1993, includes fuel ethanol blended into motor gasoline.

[b] Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

[c] Beginning in 2005, includes kerosene-type jet fuel only.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
Source: Table 3.5.

**Table 3.5 Petroleum Products Supplied by Type**  
(Thousand Barrels per Day)

	Asphalt and Road Oil	Aviation Gasoline	Distillate Fuel Oil <sup>a</sup>	Hydrocarbon Gas Liquids				Jet Fuel <sup>d</sup>	Kerosene	Lubricants	Motor Gasoline <sup>e</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>f</sup>	Total
				Propane/Propylene			Total <sup>c</sup>								
				Propane	Propylene	Total <sup>b</sup>									
1950 Average	180	108	1,082	E 146	E 13	E 158	234	( <sup>d</sup> )	323	106	2,616	41	1,517	250	6,458
1955 Average	254	192	1,592	E 251	E 22	E 273	404	154	320	116	3,463	67	1,526	366	8,455
1960 Average	302	161	1,872	E 386	E 33	E 419	621	371	271	117	3,969	149	1,529	435	9,797
1965 Average	368	120	2,126	E 523	E 45	E 568	841	602	267	129	4,593	202	1,608	657	11,512
1970 Average	447	55	2,540	E 727	E 55	782	1,224	967	263	136	5,785	212	2,204	866	14,697
1975 Average	419	39	2,851	E 730	E 60	790	1,352	1,001	159	137	6,675	247	2,462	982	16,322
1980 Average	396	35	2,866	E 742	E 72	813	1,590	1,068	158	159	6,579	237	2,508	1,460	17,056
1985 Average	425	27	2,868	E 810	E 72	883	1,721	1,218	114	145	6,831	264	1,202	909	15,726
1990 Average	483	24	3,021	E 812	E 105	917	1,705	1,522	43	164	7,235	339	1,229	1,225	16,988
1995 Average	486	21	3,207	E 938	E 157	1,096	2,100	1,514	54	156	7,789	365	852	1,180	17,725
2000 Average	525	20	3,722	E 1,011	E 224	1,235	2,434	1,725	67	166	8,472	406	909	1,255	19,701
2001 Average	519	19	3,847	E 932	E 210	1,142	2,200	1,655	72	153	8,610	437	811	1,325	19,649
2002 Average	512	18	3,776	E 1,015	E 233	1,248	2,295	1,614	43	151	8,848	463	700	1,342	19,761
2003 Average	503	16	3,927	E 977	E 238	1,215	2,205	1,578	55	140	8,935	455	772	1,448	20,034
2004 Average	537	17	4,058	E 1,021	E 255	1,276	2,264	1,630	64	141	9,105	524	865	1,525	20,731
2005 Average	546	19	4,118	E 986	E 243	1,229	2,146	1,679	70	141	9,159	515	920	1,489	20,802
2006 Average	521	18	4,169	E 947	E 268	1,215	2,135	1,633	54	137	9,253	522	689	1,557	20,687
2007 Average	494	17	4,196	E 983	E 252	1,235	2,191	1,622	32	142	9,286	490	723	1,487	20,680
2008 Average	417	15	3,945	E 924	E 230	1,154	2,044	1,539	14	131	8,989	464	622	1,317	19,498
2009 Average	360	14	3,631	E 893	E 267	1,160	2,127	1,393	18	118	8,997	427	511	1,175	18,771
2010 Average	362	15	3,800	852	305	1,157	2,263	1,432	20	131	8,993	376	535	1,251	19,178
2011 Average	355	15	3,899	851	310	1,161	2,250	1,425	12	125	8,753	361	461	1,240	18,896
2012 Average	340	14	3,741	862	308	1,170	2,293	1,398	5	114	8,682	360	369	1,165	18,482
2013 Average	323	12	3,827	969	306	1,275	2,501	1,434	5	121	8,843	354	319	1,227	18,967
2014 Average	327	12	4,037	870	298	1,167	2,443	1,470	9	126	8,921	347	257	1,151	19,100
2015 Average	343	11	3,995	865	295	1,160	2,550	1,548	6	138	9,178	349	259	1,153	19,532
2016 Average	351	11	3,877	833	301	1,134	2,541	1,614	9	130	9,317	345	326	1,170	19,692
2017 Average	351	11	3,932	803	309	1,111	2,637	1,682	5	121	9,327	316	342	1,228	19,952
2018 January	158	10	4,491	1,461	331	1,792	3,537	1,568	35	105	8,788	339	323	1,211	20,564
February	203	7	3,979	1,207	312	1,520	3,157	1,590	3	135	8,796	198	299	1,326	19,693
March	278	13	4,196	1,049	306	1,355	3,094	1,706	6	132	9,465	292	236	1,313	20,731
April	225	12	4,139	879	288	1,167	2,863	1,630	3	122	9,206	304	408	1,126	20,038
May	385	12	4,209	524	311	835	2,582	1,685	8	103	9,515	305	296	1,153	20,251
June	476	14	3,959	488	308	796	2,604	1,857	2	131	9,797	353	280	1,295	20,770
July	460	16	3,963	648	294	942	2,843	1,773	2	128	9,640	323	346	1,177	20,671
August	507	15	4,196	625	314	938	2,903	1,858	2	134	9,778	440	292	1,232	21,356
September	385	9	4,022	771	302	1,073	2,902	1,704	(s)	99	9,153	402	349	1,060	20,084
October	410	16	4,348	838	315	1,152	2,976	1,675	1	107	9,294	414	273	1,271	20,786
November	247	7	4,204	1,047	328	1,375	3,325	1,756	1	118	9,290	270	342	1,213	20,774
December	182	12	4,019	1,137	325	1,462	3,381	1,676	1	91	9,179	269	367	1,150	20,327
Average	327	12	4,146	888	311	1,199	3,014	1,707	5	117	9,329	327	318	1,210	20,512
2019 January	195	9	4,327	1,372	320	1,692	3,715	1,621	26	114	8,778	294	319	1,217	20,615
February	201	9	4,307	1,237	299	1,536	3,590	1,607	17	105	9,072	128	279	969	20,284
March	232	13	4,184	963	265	1,228	3,136	1,711	(s)	97	9,184	295	221	1,102	20,176
April	318	12	4,120	657	289	945	2,886	1,756	2	156	9,411	235	177	1,261	20,333
May	369	15	4,110	558	302	860	2,745	1,773	1	107	9,497	320	192	1,257	20,387
June	413	16	3,993	525	311	836	2,753	1,802	1	104	9,703	403	322	1,144	20,654
July	510	17	3,911	591	297	888	2,930	1,847	1	129	9,533	405	342	1,110	20,735
August	507	13	4,029	541	294	834	2,854	1,841	(s)	115	9,834	337	329	1,299	21,158
September	480	15	3,921	761	283	1,044	3,041	1,702	6	96	9,198	263	305	1,222	20,248
October	438	14	4,224	895	316	1,211	3,148	1,727	2	130	9,308	232	319	1,172	20,714
November	310	12	4,201	1,169	301	1,470	3,398	1,711	12	105	9,209	347	208	1,222	20,736
December	198	9	3,927	1,172	306	1,478	3,499	1,809	14	94	8,971	363	284	1,275	20,443
Average	348	13	4,103	868	298	1,166	3,139	1,743	7	113	9,309	303	275	1,189	20,543
2020 January	191	14	3,998	1,087	282	1,369	3,396	1,673	24	123	8,761	251	258	1,217	19,905
February	191	8	4,011	1,243	254	1,497	3,208	1,629	30	108	8,967	261	150	1,276	19,839
March	204	8	3,913	936	257	1,193	3,311	1,387	7	62	7,781	255	109	1,247	18,284
April	292	6	3,505	746	278	1,024	2,857	691	2	82	5,853	189	125	1,088	14,691
May	365	14	3,533	626	274	900	2,881	596	(s)	83	7,188	219	81	1,143	16,103
June	511	11	3,492	394	263	657	2,760	786	1	104	8,286	227	232	1,026	17,435
July	491	13	3,610	494	275	770	3,021	964	1	116	8,458	247	341	1,062	18,323
August	479	11	3,663	563	259	822	2,891	1,016	10	94	8,508	375	305	1,088	18,439
September	422	12	3,818	686	285	971	2,923	921	8	103	8,545	294	320	940	18,307
October	401	12	4,022	870	299	1,168	3,373	1,007	3	110	8,255	233	276	932	18,624
November	R 318	R 11	R 3,889	R 957	R 300	R 1,257	R 3,701	R 1,130	R 1	R 111	R 7,978	R 310	R 207	R 1,048	R 18,702
December	F 187	RE 7	RE 3,650	NA	NA	RE 1,613	RE 3,727	RE 1,138	F 12	RE 81	RE 7,863	F 257	RE 207	RE 1,554	RE 18,683
Average	RE 338	RE 11	RE 3,758	NA	NA	RE 1,103	RE 3,172	RE 1,077	E 8	RE 98	RE 8,036	RE 260	RE 218	RE 1,135	RE 18,111
2021 January	F 194	F 12	E 4,014	NA	NA	E 1,808	F 3,727	E 1,149	F 8	F 106	E 7,816	F 260	E 188	E 1,969	E 19,444

<sup>a</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>b</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."

<sup>c</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.

<sup>d</sup> Beginning in 1957, includes kerosene-type jet fuel. For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other.")

<sup>e</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>f</sup> Petrochemical feedstocks, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1964, also includes special naphthas. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified

as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

R=Revised, E=Estimate, F=Forecast, NA=Not available, (s)=Less than 500 barrels per day and greater than -500 barrels per day.

Notes: • Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c.


See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: See end of section.

**Figure 3.6 Heat Content of Petroleum Products Supplied by Type**


Total, 1949–2020



Petroleum Products Supplied as Share of Total Energy Consumption, 1949–2019



By Product, January 2021



[a] Includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

[b] Includes kerosene-type jet fuel only.

[c] Includes fuel ethanol blended into motor gasoline.

[d] All petroleum products not separately displayed.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Sources: Tables 1.1 and 3.6.

**Table 3.6 Heat Content of Petroleum Products Supplied by Type**  
(Trillion Btu)

	Asphalt and Road Oil	Aviation Gasoline	Distillate Fuel Oil <sup>a</sup>	Hydrocarbon Gas Liquids				Jet Fuel <sup>d</sup>	Kerosene	Lubricants	Motor Gasoline <sup>e</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>f</sup>	Total
				Propane/Propylene			Total <sup>c</sup>								
				Propane	Propylene	Total <sup>b</sup>									
1950 Total	435	199	2,300	E 204	E 18	E 222	326	( <sup>d</sup> )	668	236	5,015	90	3,482	546	13,298
1955 Total	615	354	3,385	E 352	E 30	E 383	562	301	662	258	6,640	147	3,502	798	17,225
1960 Total	734	298	3,992	E 543	E 47	E 589	866	739	563	259	7,631	328	3,517	947	19,874
1965 Total	890	222	4,519	E 733	E 63	E 796	1,170	1,215	553	286	8,806	444	3,691	1,390	23,184
1970 Total	1,082	100	5,401	E 1,019	E 77	E 1,096	1,667	1,973	544	301	11,091	465	5,057	1,817	29,499
1975 Total	1,014	71	6,061	E 1,024	E 84	E 1,108	1,811	2,047	329	304	12,798	542	5,649	2,071	32,699
1980 Total	962	64	6,110	E 1,043	E 100	E 1,143	2,135	2,190	329	354	12,648	522	5,772	3,073	34,159
1985 Total	1,029	50	6,098	E 1,136	E 101	E 1,237	2,252	2,497	236	322	13,098	582	2,759	1,945	30,866
1990 Total	1,170	45	6,422	E 1,138	E 147	E 1,285	2,259	3,129	88	362	13,872	745	2,820	2,589	33,500
1995 Total	1,178	40	6,812	E 1,316	E 220	E 1,536	2,791	3,132	112	346	14,794	802	1,955	2,499	34,458
2000 Total	1,276	36	7,927	E 1,421	E 315	E 1,735	3,216	3,580	140	369	16,127	895	2,091	2,636	38,292
2001 Total	1,257	35	8,170	E 1,306	E 294	E 1,600	2,895	3,426	150	338	16,345	961	1,861	2,793	38,231
2002 Total	1,240	34	8,020	E 1,423	E 326	E 1,749	3,006	3,340	90	334	16,790	1,018	1,605	2,816	38,293
2003 Total	1,220	30	8,341	E 1,370	E 333	E 1,702	2,905	3,265	113	309	16,949	1,000	1,772	3,043	38,947
2004 Total	1,304	31	8,642	E 1,435	E 358	E 1,793	2,976	3,383	133	313	17,316	1,148	1,990	3,205	40,441
2005 Total	1,323	35	8,745	E 1,382	E 341	E 1,723	2,812	3,475	144	312	17,358	1,125	2,111	3,122	40,561
2006 Total	1,261	33	8,831	E 1,328	E 375	E 1,703	2,768	3,379	111	303	17,511	1,141	1,581	3,276	40,196
2007 Total	1,197	32	8,858	E 1,379	E 352	E 1,731	2,835	3,358	67	313	17,428	1,072	1,659	3,134	39,952
2008 Total	1,012	28	8,346	E 1,299	E 323	E 1,622	2,656	3,193	30	291	16,799	1,017	1,432	2,788	37,591
2009 Total	873	27	7,657	E 1,252	E 374	E 1,626	2,707	2,883	36	262	16,714	937	1,173	2,483	35,752
2010 Total	878	27	8,011	E 1,194	E 428	E 1,621	2,881	2,963	41	291	16,632	831	1,228	2,645	36,427
2011 Total	859	27	8,211	E 1,194	E 434	E 1,628	2,811	2,950	25	276	16,175	801	1,058	2,621	35,815
2012 Total	827	25	7,898	E 1,212	E 432	E 1,645	2,887	2,901	11	254	16,085	802	849	2,474	35,012
2013 Total	783	22	8,051	E 1,358	E 429	E 1,787	3,166	2,969	11	268	16,332	786	731	2,583	35,702
2014 Total	793	22	8,492	E 1,219	E 417	E 1,636	3,067	3,042	19	280	16,473	772	590	2,430	35,978
2015 Total	832	21	8,402	E 1,212	E 413	E 1,626	3,221	3,204	13	305	16,941	776	595	2,435	36,745
2016 Total	853	20	8,170	E 1,171	E 423	E 1,594	3,184	3,350	18	289	17,238	771	751	2,553	37,198
2017 Total	849	21	8,263	E 1,126	E 432	E 1,557	3,272	3,481	11	267	17,201	708	784	2,667	37,525
2018 January	32	1	802	174	39	213	377	276	6	20	1,377	64	63	223	3,242
February	38	1	642	130	34	163	305	252	(s)	23	1,245	34	53	220	2,813
March	57	2	749	125	36	161	321	300	1	25	1,483	55	46	242	3,281
April	45	2	715	101	33	134	285	277	1	22	1,396	56	77	201	3,077
May	79	2	751	62	37	99	266	296	1	19	1,491	58	58	213	3,235
June	95	2	684	56	35	92	259	316	(s)	24	1,485	65	53	232	3,214
July	95	3	707	77	35	112	295	312	(s)	24	1,510	61	67	218	3,292
August	104	2	749	74	37	112	302	327	(s)	25	1,532	84	57	228	3,410
September	77	1	695	89	35	124	293	290	(s)	18	1,388	74	66	190	3,091
October	84	3	776	100	37	137	314	294	(s)	20	1,456	79	53	233	3,313
November	49	1	726	121	38	158	342	299	(s)	21	1,409	50	65	217	3,178
December	37	2	718	135	39	174	360	295	(s)	17	1,438	51	72	213	3,203
Total	793	22	8,715	1,245	436	1,680	3,720	3,533	11	259	17,209	730	729	2,630	38,351
2019 January	40	1	773	163	38	201	397	285	5	21	1,375	56	62	225	3,240
February	37	1	695	133	32	165	343	255	3	18	1,283	22	49	162	2,869
March	48	2	747	115	31	146	328	301	(s)	18	1,438	56	43	204	3,185
April	63	2	712	76	33	109	288	299	(s)	28	1,426	43	33	225	3,120
May	76	2	733	66	36	102	285	312	(s)	20	1,487	61	37	232	3,246
June	82	2	690	61	36	96	281	306	(s)	19	1,471	74	61	205	3,191
July	105	3	698	70	35	106	310	325	(s)	24	1,493	77	67	206	3,306
August	104	2	719	64	35	99	302	324	(s)	22	1,540	64	64	240	3,380
September	96	2	677	88	33	120	311	290	1	18	1,394	48	57	218	3,112
October	90	2	754	107	38	144	334	304	(s)	25	1,458	44	62	217	3,290
November	62	2	726	135	35	169	347	291	2	19	1,396	64	39	219	3,166
December	41	1	701	140	36	176	370	318	2	18	1,405	69	55	235	3,216
Total	844	23	8,625	1,217	418	1,635	3,897	3,608	14	250	17,166	678	631	2,585	38,322
2020 January	39	2	714	129	33	163	352	294	4	23	1,372	48	50	225	3,123
February	37	1	670	138	28	167	307	268	5	19	1,314	46	27	221	2,914
March	42	1	699	112	31	142	345	244	1	12	1,219	48	21	230	2,862
April	58	1	605	86	32	118	280	118	(s)	15	887	35	24	194	2,217
May	75	2	631	75	33	107	295	105	(s)	16	1,126	42	16	211	2,518
June	102	2	603	45	30	76	272	134	(s)	19	1,256	42	44	184	2,656
July	101	2	644	59	33	92	306	169	(s)	22	1,325	47	66	196	2,878
August	98	2	654	67	31	98	300	178	2	18	1,333	71	59	201	2,915
September	84	2	659	79	33	112	298	157	1	19	1,295	54	60	169	2,798
October	82	2	718	104	36	139	359	177	(s)	21	1,293	44	54	172	2,922
November	R 63	F 1	R 672	R 110	R 35	R 145	R 376	R 192	(s)	R 20	R 1,209	R 57	R 39	R 187	R 2,818
December	F 39	F 1	RE 652	NA	NA	RE 192	RF 387	RE 200	F 2	F 15	RE 1,231	F 49	RE 40	RE 317	RE 2,934
Total	RE 821	E 19	RE 7,919	NA	NA	RE 1,550	RE 3,875	RE 2,236	E 17	RE 218	RE 14,859	RE 583	RE 502	RE 2,507	RE 33,555
2021 January	F 40	F 2	E 716	NA	NA	E 215	F 386	E 202	F 1	F 20	E 1,224	F 49	E 37	E 376	E 3,054

<sup>a</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>b</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."

<sup>c</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.

<sup>d</sup> Beginning in 1957, includes kerosene-type jet fuel. For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other.")

<sup>e</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>f</sup> Petrochemical feedstocks, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1964, also includes special naphthas. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified

as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

R=Revised. E=Estimate. F=Forecast. NA=Not available. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.


Notes: • Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: See end of section.

**Figure 3.7 Petroleum Consumption by Sector**


By Sector, 1949–2019



By Sector, November 2020



Sector Shares, 1949 and 2019



[a] Includes combined-heat-and-power plants and a small number of electricity-only plants.

(s)=Less than 0.5 percent.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
Sources: Tables 3.7a–3.7c.

**Table 3.7a Petroleum Consumption: Residential and Commercial Sectors**  
(Thousand Barrels per Day)

	Residential Sector				Commercial Sector <sup>a</sup>						
	Distillate Fuel Oil	HGL <sup>b</sup>	Kero-sene	Total	Distillate Fuel Oil	HGL <sup>b</sup>	Kero-sene	Motor Gasoline <sup>c,d</sup>	Petroleum Coke	Residual Fuel Oil	Total
		Propane				Propane					
1950 Average .....	390	104	168	662	123	28	23	52	NA	185	411
1955 Average .....	562	144	179	885	177	38	24	69	NA	209	519
1960 Average .....	736	217	171	1,123	232	58	23	35	NA	243	590
1965 Average .....	805	275	161	1,242	251	74	26	40	NA	281	672
1970 Average .....	883	392	144	1,419	276	102	30	45	NA	311	764
1975 Average .....	850	365	78	1,293	276	92	24	46	NA	214	653
1980 Average .....	617	222	51	890	243	63	20	56	NA	245	626
1985 Average .....	514	224	77	815	297	68	16	50	NA	99	530
1990 Average .....	460	252	31	742	252	73	6	58	0	100	489
1995 Average .....	426	282	36	743	225	78	11	10	(s)	62	385
2000 Average .....	424	395	46	865	230	107	14	23	(s)	40	415
2001 Average .....	427	375	46	849	239	102	15	20	(s)	30	406
2002 Average .....	404	384	29	817	209	101	8	24	(s)	35	376
2003 Average .....	438	389	34	861	233	112	9	32	(s)	48	434
2004 Average .....	433	364	41	839	221	108	10	23	(s)	53	416
2005 Average .....	402	366	40	809	210	94	10	24	(s)	50	389
2006 Average .....	335	318	32	685	189	88	7	26	(s)	33	343
2007 Average .....	342	345	21	708	181	87	4	32	(s)	33	337
2008 Average .....	354	394	10	758	181	113	2	24	(s)	31	351
2009 Average .....	276	391	13	680	187	99	2	28	(s)	31	348
2010 Average .....	266	378	14	658	185	100	2	28	(s)	27	343
2011 Average .....	248	351	9	608	186	102	2	24	(s)	23	336
2012 Average .....	228	281	4	513	168	96	1	21	(s)	14	300
2013 Average .....	233	331	4	568	163	108	(s)	22	(s)	11	304
2014 Average .....	253	349	7	609	169	114	1	29	(s)	3	318
2015 Average .....	262	318	5	584	171	106	1	<sup>d</sup> 204	(s)	2	483
2016 Average .....	206	306	7	518	154	107	1	203	(s)	2	467
2017 Average .....	205	307	4	517	153	111	1	196	(s)	2	462
<b>2018 January .....</b>	465	706	26	1,197	296	208	4	187	(s)	3	699
February .....	332	574	2	907	211	177	(s)	187	(s)	2	577
March .....	249	520	4	773	158	164	1	202	(s)	1	526
April .....	237	400	2	640	151	135	(s)	196	(s)	1	484
May .....	141	182	6	328	90	82	1	203	0	1	376
June .....	113	144	1	258	72	73	(s)	209	0	1	354
July .....	102	129	2	233	65	70	(s)	205	0	1	341
August .....	86	131	2	219	55	70	(s)	208	0	(s)	334
September .....	123	152	(s)	275	79	75	(s)	195	(s)	1	349
October .....	255	290	1	546	162	108	(s)	198	(s)	1	471
November .....	340	523	1	864	217	164	(s)	198	(s)	2	581
December .....	451	599	1	1,051	287	183	(s)	195	(s)	3	668
<b>Average .....</b>	<b>241</b>	<b>361</b>	<b>4</b>	<b>606</b>	<b>153</b>	<b>126</b>	<b>1</b>	<b>199</b>	<b>(s)</b>	<b>1</b>	<b>480</b>
<b>2019 January .....</b>	<sup>R</sup> 383	663	19	<sup>R</sup> 1,065	<sup>R</sup> 266	197	3	<sup>R</sup> 189	(s)	2	<sup>R</sup> 657
February .....	<sup>R</sup> 353	624	13	<sup>R</sup> 989	<sup>R</sup> 245	188	2	<sup>R</sup> 195	(s)	2	<sup>R</sup> 632
March .....	<sup>R</sup> 282	520	(s)	<sup>R</sup> 803	<sup>R</sup> 196	163	(s)	<sup>R</sup> 197	(s)	1	<sup>R</sup> 558
April .....	<sup>R</sup> 187	310	1	<sup>R</sup> 499	<sup>R</sup> 130	112	(s)	<sup>R</sup> 202	(s)	1	<sup>R</sup> 446
May .....	<sup>R</sup> 142	223	1	<sup>R</sup> 366	<sup>R</sup> 99	91	(s)	<sup>R</sup> 204	0	1	<sup>R</sup> 395
June .....	<sup>R</sup> 123	146	1	<sup>R</sup> 270	<sup>R</sup> 86	73	(s)	<sup>R</sup> 209	0	1	<sup>R</sup> 368
July .....	<sup>R</sup> 115	127	1	<sup>R</sup> 243	<sup>R</sup> 80	68	(s)	<sup>R</sup> 205	0	1	<sup>R</sup> 354
August .....	<sup>R</sup> 177	130	(s)	<sup>R</sup> 307	<sup>R</sup> 123	69	(s)	<sup>R</sup> 211	0	1	<sup>R</sup> 404
September .....	<sup>R</sup> 102	150	4	<sup>R</sup> 257	<sup>R</sup> 71	74	1	<sup>R</sup> 198	0	<sup>R</sup> (s)	<sup>R</sup> 344
October .....	<sup>R</sup> 154	283	2	<sup>R</sup> 438	<sup>R</sup> 107	106	(s)	<sup>R</sup> 200	0	1	<sup>R</sup> 414
November .....	<sup>R</sup> 312	506	9	<sup>R</sup> 827	<sup>R</sup> 217	159	1	<sup>R</sup> 198	0	<sup>R</sup> 1	<sup>R</sup> 577
December .....	<sup>R</sup> 358	573	10	<sup>R</sup> 940	<sup>R</sup> 249	176	2	<sup>R</sup> 193	(s)	2	<sup>R</sup> 620
<b>Average .....</b>	<sup>R</sup> <b>223</b>	<b>353</b>	<b>5</b>	<sup>R</sup> <b>582</b>	<sup>R</sup> <b>155</b>	<b>123</b>	<b>1</b>	<sup>R</sup> <b>200</b>	<b>(s)</b>	<b>1</b>	<sup>R</sup> <b>480</b>
<b>2020 January .....</b>	<sup>R</sup> 292	588	18	<sup>R</sup> 897	<sup>R</sup> 203	179	3	<sup>R</sup> 188	(s)	<sup>R</sup> 1	<sup>R</sup> 575
February .....	<sup>R</sup> 256	561	22	<sup>R</sup> 839	<sup>R</sup> 178	173	4	<sup>R</sup> 193	(s)	1	<sup>R</sup> 549
March .....	<sup>R</sup> 224	427	5	<sup>R</sup> 656	<sup>R</sup> 156	140	1	<sup>R</sup> 167	0	1	<sup>R</sup> 465
April .....	<sup>R</sup> 208	356	2	<sup>R</sup> 565	<sup>R</sup> 145	123	(s)	<sup>R</sup> 126	0	1	<sup>R</sup> 395
May .....	<sup>R</sup> 227	222	(s)	<sup>R</sup> 449	<sup>R</sup> 158	91	(s)	<sup>R</sup> 155	0	1	<sup>R</sup> 405
June .....	<sup>R</sup> 148	140	1	<sup>R</sup> 288	<sup>R</sup> 103	71	(s)	<sup>R</sup> 178	0	1	<sup>R</sup> 353
July .....	<sup>R</sup> 96	126	1	<sup>R</sup> 223	<sup>R</sup> 67	68	(s)	<sup>R</sup> 182	0	<sup>R</sup> (s)	<sup>R</sup> 317
August .....	<sup>R</sup> 85	128	7	<sup>R</sup> 220	<sup>R</sup> 59	68	1	<sup>R</sup> 183	0	(s)	<sup>R</sup> 312
September .....	<sup>R</sup> 146	161	6	<sup>R</sup> 313	<sup>R</sup> 102	76	1	<sup>R</sup> 184	0	1	<sup>R</sup> 363
October .....	<sup>R</sup> 164	278	2	<sup>R</sup> 445	<sup>R</sup> 114	105	(s)	<sup>R</sup> 177	0	1	<sup>R</sup> 397
November .....	205	397	1	603	143	133	(s)	171	0	1	448
<b>11-Month Average ...</b>	<b>186</b>	<b>307</b>	<b>6</b>	<b>499</b>	<b>130</b>	<b>111</b>	<b>1</b>	<b>173</b>	<b>(s)</b>	<b>1</b>	<b>416</b>
<b>2019 11-Month Average ...</b>	<b>211</b>	<b>333</b>	<b>4</b>	<b>548</b>	<b>147</b>	<b>118</b>	<b>1</b>	<b>201</b>	<b>(s)</b>	<b>1</b>	<b>467</b>
<b>2018 11-Month Average ...</b>	<b>221</b>	<b>339</b>	<b>4</b>	<b>565</b>	<b>141</b>	<b>120</b>	<b>1</b>	<b>199</b>	<b>(s)</b>	<b>1</b>	<b>462</b>

<sup>a</sup> Commercial sector fuel use, including that at commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Hydrocarbon gas liquids.

<sup>c</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>d</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

R=Revised. NA=Not available. (s)=Less than 500 barrels per day and greater than -500 barrels per day.

Notes: • Data are estimates. • For total petroleum consumption by all sectors, see petroleum products supplied data in Table 3.5. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 3.7b Petroleum Consumption: Industrial Sector**  
(Thousand Barrels per Day)

	Industrial Sector <sup>a</sup>												
	Asphalt and Road Oil	Distillate Fuel Oil	Hydrocarbon Gas Liquids				Kerosene	Lubricants	Motor Gasoline <sup>d,e</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>f</sup>	Total
			Propane/Propylene			Total <sup>c</sup>							
			Propane	Propylene	Total <sup>b</sup>								
1950 Average .....	180	328	12	13	24	100	132	43	131	41	617	250	1,822
1955 Average .....	254	466	59	22	81	212	116	47	173	67	686	366	2,387
1960 Average .....	302	476	98	33	131	333	78	48	198	149	689	435	2,708
1965 Average .....	368	541	152	45	197	470	80	62	179	202	689	657	3,247
1970 Average .....	447	577	201	55	256	699	89	70	150	203	708	866	3,808
1975 Average .....	419	630	242	60	302	863	58	68	116	246	658	982	4,038
1980 Average .....	396	621	445	72	516	1,293	87	82	82	234	586	1,460	4,842
1985 Average .....	425	526	497	72	569	1,408	21	75	114	261	326	909	4,065
1990 Average .....	483	541	471	105	576	1,364	6	84	97	325	179	1,225	4,304
1995 Average .....	486	532	566	157	723	1,727	7	80	105	328	147	1,180	4,594
2000 Average .....	525	563	500	224	724	1,923	8	86	79	361	105	1,255	4,903
2001 Average .....	519	611	444	210	654	1,713	11	79	155	390	89	1,325	4,892
2002 Average .....	512	566	521	233	754	1,801	7	78	163	383	83	1,342	4,934
2003 Average .....	503	551	463	238	701	1,691	12	72	171	375	96	1,448	4,918
2004 Average .....	537	570	535	255	790	1,778	14	73	195	423	108	1,525	5,222
2005 Average .....	546	594	506	243	749	1,666	19	72	187	404	123	1,489	5,100
2006 Average .....	521	594	521	268	789	1,710	14	71	198	425	104	1,557	5,193
2007 Average .....	494	595	536	252	787	1,744	6	73	161	412	84	1,487	5,056
2008 Average .....	417	637	389	230	619	1,510	2	67	131	394	84	1,317	4,559
2009 Average .....	360	509	383	267	650	1,617	2	61	128	363	57	1,175	4,272
2010 Average .....	362	547	369	305	674	1,780	4	61	140	310	52	1,251	4,508
2011 Average .....	355	586	393	310	703	1,792	2	58	138	295	59	1,240	4,523
2012 Average .....	340	602	480	308	788	1,910	1	53	136	319	30	1,165	4,558
2013 Average .....	323	601	525	306	831	2,057	1	57	142	295	21	1,227	4,723
2014 Average .....	327	648	401	298	698	1,974	1	59	114	290	18	1,151	4,582
2015 Average .....	343	555	437	295	732	2,122	1	64	<sup>e</sup> 140	295	15	1,153	4,688
2016 Average .....	351	548	415	301	717	2,123	1	61	142	289	23	1,170	4,707
2017 Average .....	351	572	379	309	688	2,214	1	56	143	269	22	1,228	4,856
2018 January .....	158	734	541	331	873	2,617	5	50	138	279	18	1,211	5,209
February .....	203	569	451	312	764	2,402	(s)	63	138	144	19	1,326	4,864
March .....	278	715	360	306	666	2,405	1	62	148	252	14	1,313	5,188
April .....	225	593	338	288	626	2,322	(s)	57	144	259	24	1,126	4,751
May .....	385	681	254	311	565	2,312	1	48	149	272	17	1,153	5,019
June .....	476	493	265	308	573	2,382	(s)	62	153	300	17	1,295	5,179
July .....	460	487	444	294	738	2,639	(s)	60	151	265	20	1,177	5,259
August .....	507	631	418	314	732	2,696	(s)	63	153	384	17	1,232	5,683
September .....	385	588	539	302	841	2,670	(s)	47	143	349	20	1,060	5,260
October .....	410	663	433	315	748	2,572	(s)	51	146	378	17	1,271	5,508
November .....	247	580	355	328	683	2,632	(s)	55	145	226	22	1,213	5,121
December .....	182	399	349	325	674	2,593	(s)	43	144	218	23	1,150	4,751
Average .....	327	595	396	311	707	2,521	1	55	146	278	19	1,210	5,152
2019 January .....	195	<sup>R</sup> 766	<sup>R</sup> 507	320	826	<sup>R</sup> 2,850	4	54	<sup>R</sup> 136	242	<sup>R</sup> 21	1,217	<sup>R</sup> 5,485
February .....	201	<sup>R</sup> 716	420	299	719	2,773	2	49	<sup>R</sup> 141	79	<sup>R</sup> 19	969	<sup>R</sup> 4,950
March .....	232	<sup>R</sup> 649	275	265	539	2,448	(s)	46	<sup>R</sup> 143	258	<sup>R</sup> 15	1,102	<sup>R</sup> 4,892
April .....	318	<sup>R</sup> 612	229	289	517	<sup>R</sup> 2,458	(s)	74	<sup>R</sup> 146	210	<sup>R</sup> 12	1,261	<sup>R</sup> 5,090
May .....	369	<sup>R</sup> 603	238	302	540	2,425	(s)	50	<sup>R</sup> 147	274	<sup>R</sup> 12	1,257	<sup>R</sup> 5,138
June .....	413	<sup>R</sup> 488	<sup>R</sup> 301	311	612	2,529	(s)	49	<sup>R</sup> 151	368	<sup>R</sup> 21	1,144	<sup>R</sup> 5,162
July .....	510	<sup>R</sup> 427	390	297	687	2,729	(s)	61	<sup>R</sup> 148	357	<sup>R</sup> 22	1,110	<sup>R</sup> 5,363
August .....	507	<sup>R</sup> 424	336	294	630	2,650	(s)	54	<sup>R</sup> 153	293	<sup>R</sup> 20	1,299	<sup>R</sup> 5,399
September .....	480	<sup>R</sup> 531	<sup>R</sup> 531	283	814	2,812	1	45	<sup>R</sup> 143	226	<sup>R</sup> 19	1,222	<sup>R</sup> 5,478
October .....	438	<sup>R</sup> 669	<sup>R</sup> 500	316	<sup>R</sup> 816	<sup>R</sup> 2,753	(s)	61	<sup>R</sup> 145	221	<sup>R</sup> 21	1,172	<sup>R</sup> 5,480
November .....	310	<sup>R</sup> 584	498	301	799	2,728	2	50	<sup>R</sup> 143	326	<sup>R</sup> 14	1,222	<sup>R</sup> 5,377
December .....	198	<sup>R</sup> 412	418	306	724	2,745	2	44	<sup>R</sup> 139	332	<sup>R</sup> 19	1,275	<sup>R</sup> 5,166
Average .....	348	<sup>R</sup> 573	387	298	685	2,658	1	53	<sup>R</sup> 145	267	<sup>R</sup> 18	1,189	<sup>R</sup> 5,251
2020 January .....	191	<sup>R</sup> 669	315	282	597	2,624	3	58	<sup>R</sup> 136	209	<sup>R</sup> 16	1,217	<sup>R</sup> 5,124
February .....	191	<sup>R</sup> 689	504	254	758	<sup>R</sup> 2,470	4	51	<sup>R</sup> 139	228	<sup>R</sup> 10	1,276	<sup>R</sup> 5,059
March .....	204	<sup>R</sup> 550	<sup>R</sup> 364	257	620	<sup>R</sup> 2,738	1	29	<sup>R</sup> 121	213	<sup>R</sup> 7	1,247	<sup>R</sup> 5,109
April .....	292	<sup>R</sup> 229	262	278	<sup>R</sup> 540	<sup>R</sup> 2,373	(s)	39	<sup>R</sup> 91	152	<sup>R</sup> 8	1,088	<sup>R</sup> 4,271
May .....	365	<sup>R</sup> 179	308	274	583	2,563	(s)	39	<sup>R</sup> 112	182	5	1,143	<sup>R</sup> 4,588
June .....	511	<sup>R</sup> 167	178	263	<sup>R</sup> 440	2,544	(s)	49	<sup>R</sup> 129	177	<sup>R</sup> 15	1,026	<sup>R</sup> 4,617
July .....	491	<sup>R</sup> 266	295	275	570	2,821	(s)	55	<sup>R</sup> 131	191	<sup>R</sup> 22	1,062	<sup>R</sup> 5,038
August .....	479	<sup>R</sup> 299	361	259	620	2,689	1	44	<sup>R</sup> 132	326	<sup>R</sup> 20	1,088	<sup>R</sup> 5,078
September .....	422	<sup>R</sup> 428	443	285	728	2,680	1	48	<sup>R</sup> 133	268	<sup>R</sup> 21	940	<sup>R</sup> 4,941
October .....	401	<sup>R</sup> 539	481	299	780	2,984	(s)	52	<sup>R</sup> 128	213	<sup>R</sup> 17	932	<sup>R</sup> 5,267
November .....	318	509	422	300	722	3,165	(s)	52	124	275	13	1,048	5,504
11-Month Average ...	352	410	357	275	632	2,697	1	47	125	221	14	1,097	4,964
2019 11-Month Average ...	362	587	384	298	682	2,650	1	54	145	261	18	1,181	5,258
2018 11-Month Average ...	341	613	400	310	710	2,515	1	56	146	284	19	1,215	5,190

<sup>a</sup> Industrial sector fuel use, including that at industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>b</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."

<sup>c</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.

<sup>d</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>e</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>f</sup> Petrochemical feedstocks, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1964, also includes special naphthas. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified

as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

R=Revised. (s)=Less than 500 barrels per day and greater than -500 barrels per day.

Notes: • Data are estimates. • For total petroleum consumption by all sectors, see petroleum products supplied data in Table 3.5. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a-3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 3.7c Petroleum Consumption: Transportation and Electric Power Sectors**  
(Thousand Barrels per Day)

	Transportation Sector								Electric Power Sector <sup>a</sup>			
	Aviation Gasoline	Distillate Fuel Oil <sup>c</sup>	HGL <sup>b</sup>	Jet Fuel <sup>e</sup>	Lubri- cants	Motor Gasoline <sup>f,g</sup>	Residual Fuel Oil	Total	Distillate Fuel Oil <sup>h</sup>	Petroleum Coke	Residual Fuel Oil <sup>i</sup>	Total
			Propane <sup>d</sup>									
1950 Average .....	108	226	2	( <sup>e</sup> )	64	2,433	524	3,356	15	NA	192	207
1955 Average .....	192	372	9	154	70	3,221	440	4,458	15	NA	191	206
1960 Average .....	161	418	13	371	68	3,736	367	5,135	10	NA	231	241
1965 Average .....	120	514	23	602	67	4,374	336	6,036	14	NA	302	316
1970 Average .....	55	738	32	967	66	5,589	332	7,778	66	9	853	928
1975 Average .....	39	998	31	992	70	6,512	310	8,951	107	1	1,280	1,388
1980 Average .....	35	1,311	13	1,062	77	6,441	608	9,546	79	2	1,069	1,151
1985 Average .....	27	1,491	21	1,218	71	6,667	342	9,838	40	3	435	478
1990 Average .....	24	1,722	16	1,522	80	7,080	443	10,888	45	14	507	566
1995 Average .....	21	1,973	13	1,514	76	7,674	397	11,668	51	37	247	334
2000 Average .....	20	2,422	8	1,725	81	8,370	386	13,012	82	45	378	505
2001 Average .....	19	2,489	10	1,655	74	8,435	255	12,938	80	47	437	564
2002 Average .....	18	2,536	10	1,614	73	8,662	295	13,208	60	80	287	427
2003 Average .....	16	2,629	13	1,578	68	8,733	249	13,286	76	79	379	534
2004 Average .....	17	2,783	14	1,630	69	8,887	321	13,720	52	101	382	535
2005 Average .....	19	2,858	20	1,679	68	8,948	365	13,957	54	111	382	547
2006 Average .....	18	3,017	20	1,633	67	9,029	395	14,178	35	97	157	289
2007 Average .....	17	3,037	16	1,622	69	9,093	433	14,287	42	78	173	293
2008 Average .....	15	2,738	29	1,539	64	8,834	402	13,621	34	70	104	209
2009 Average .....	14	2,626	20	1,393	57	8,841	344	13,297	33	63	79	175
2010 Average .....	15	2,764	<sup>d</sup> 5	1,432	70	8,824	389	13,499	38	65	67	170
2011 Average .....	15	2,849	5	1,425	67	8,591	338	13,291	30	66	41	137
2012 Average .....	14	2,719	5	1,398	61	8,525	291	13,013	25	41	33	99
2013 Average .....	12	2,804	5	1,434	65	8,679	253	13,253	26	59	34	119
2014 Average .....	12	2,928	5	1,470	67	8,778	195	13,455	39	57	41	137
2015 Average .....	11	2,974	5	1,548	74	<sup>g</sup> 8,835	202	13,649	33	54	41	128
2016 Average .....	11	2,944	5	1,614	70	8,973	271	13,887	26	57	31	113
2017 Average .....	11	2,976	5	1,682	64	8,988	290	14,016	26	47	29	101
2018 January .....	10	2,826	5	1,568	56	8,463	185	13,112	169	60	118	348
February .....	7	2,844	5	1,590	71	8,471	255	13,244	24	54	23	101
March .....	13	3,051	5	1,706	70	9,115	199	14,160	23	40	21	84
April .....	12	3,132	5	1,630	64	8,866	359	14,069	26	45	24	94
May .....	12	3,267	5	1,685	54	9,164	252	14,440	30	33	25	89
June .....	14	3,252	5	1,857	69	9,435	233	14,866	30	54	29	113
July .....	16	3,285	5	1,773	68	9,284	298	14,729	23	58	28	110
August .....	15	3,398	5	1,858	71	9,417	245	15,009	25	56	30	111
September .....	9	3,209	5	1,704	52	8,814	296	14,090	24	53	33	110
October .....	16	3,242	5	1,675	57	8,950	227	14,172	25	36	28	89
November .....	7	3,037	5	1,756	62	8,947	294	14,109	30	44	25	99
December .....	12	2,855	5	1,676	48	8,839	320	13,757	27	51	22	100
Average .....	12	3,118	5	1,707	62	8,984	263	14,152	38	49	34	121
2019 January .....	9	R 2,874	5	1,621	60	R 8,453	R 263	R 13,286	38	52	33	123
February .....	9	R 2,967	5	1,607	55	R 8,736	R 238	R 13,617	26	48	21	95
March .....	13	R 3,034	5	1,711	51	R 8,844	R 185	R 13,843	23	37	20	80
April .....	12	R 3,169	5	1,756	83	R 9,062	R 144	R 14,230	21	25	21	67
May .....	15	R 3,240	5	1,773	56	R 9,146	R 155	R 14,391	26	47	24	97
June .....	16	R 3,270	5	1,802	55	R 9,344	R 274	R 14,766	26	35	27	88
July .....	17	R 3,265	5	1,847	68	R 9,180	R 291	R 14,673	24	48	29	101
August .....	13	R 3,283	5	1,841	61	R 9,470	R 277	R 14,949	24	43	31	98
September .....	15	R 3,193	5	1,702	51	R 8,857	R 258	R 14,082	23	38	27	87
October .....	14	R 3,271	5	1,727	69	R 8,964	R 272	R 14,322	23	11	26	60
November .....	12	R 3,063	5	1,711	56	R 8,868	R 169	R 13,884	25	21	24	70
December .....	9	R 2,882	5	1,809	50	R 8,639	R 239	R 13,633	27	31	25	83
Average .....	13	R 3,127	5	1,743	60	8,965	R 231	R 14,143	26	36	26	88
2020 January .....	14	R 2,807	5	1,673	65	R 8,436	R 215	R 13,217	27	41	25	93
February .....	8	R 2,863	5	1,629	57	8,635	118	R 13,315	23	32	21	77
March .....	8	R 2,965	5	1,387	33	7,493	R 82	R 11,974	19	42	19	79
April .....	6	R 2,907	5	691	44	5,637	98	R 9,388	16	37	18	72
May .....	14	R 2,951	5	596	44	R 6,922	56	R 10,587	19	37	19	75
June .....	11	R 3,050	5	786	55	R 7,979	R 192	R 12,079	24	50	24	98
July .....	13	R 3,155	5	964	61	R 8,145	R 293	R 12,636	25	56	26	108
August .....	11	R 3,197	5	1,016	50	R 8,193	R 259	R 12,731	23	49	26	98
September .....	12	R 3,124	5	921	54	R 8,229	R 275	R 12,621	18	26	25	69
October .....	12	R 3,182	5	1,007	58	7,950	R 232	R 12,446	22	21	26	69
November .....	11	3,011	5	1,130	59	7,682	171	12,070	21	34	22	77
11-Month Average ...	11	3,020	5	1,072	53	7,754	181	12,096	22	39	23	83
2019 11-Month Average ...	13	3,149	5	1,737	61	8,995	230	14,190	25	37	26	88
2018 11-Month Average ...	12	3,143	5	1,710	63	8,998	258	14,189	39	48	35	123

<sup>a</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>b</sup> Hydrocarbon gas liquids.

<sup>c</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>d</sup> There is a discontinuity in this time series between 2009 and 2010 due to a change in data sources.

<sup>e</sup> Beginning in 1957, includes kerosene-type jet fuel. For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other" on Table 3.7b.)

<sup>f</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>g</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>h</sup> Fuel oil nos. 1, 2, and 4. Through 1979, data are for gas turbine and internal combustion plant use of petroleum. Through 2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>i</sup> Fuel oil nos. 5 and 6. Through 1979, data are for steam plant use of petroleum. Through 2000, electric utility data also include a small amount of fuel oil no. 4.

R=Revised. NA=Not available.

Notes: • Transportation sector data are estimates. • For total petroleum consumption by all sectors, see petroleum products supplied data in Table 3.5. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: See end of section.




**Figure 3.8a Heat Content of Petroleum Consumption by End-Use Sector, 1949-2019**

(Quadrillion Btu)


Residential and Commercial [a] Sectors, Selected Products



Industrial [a] Sector, Selected Products



Transportation Sector, Selected Products



[a] Includes combined-heat-and-power plants and a small number of electricity-only plants.

[b] Hydrocarbon gas liquids.

[c] Beginning in 1993, includes fuel ethanol blended into motor gasoline.

[d] Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

[e] Beginning in 2005, includes kerosene-type jet fuel only.

Note: Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft.


Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Sources: Tables 3.8a–3.8c.


**Figure 3.8b Heat Content of Petroleum Consumption by End-Use Sector, Monthly**

(Quadrillion Btu)


Residential and Commercial [a] Sectors, Selected Products



Industrial [a] Sector, Selected Products



Transportation Sector, Selected Products



[a] Includes combined-heat-and-power plants and a small number of electricity-only plants.

[b] Hydrocarbon gas liquids.

[c] Includes fuel ethanol blended into motor gasoline.

[d] Includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

[e] Includes kerosene-type jet fuel only.

Note: Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Sources: Tables 3.8a–3.8c.

**Table 3.8a Heat Content of Petroleum Consumption: Residential and Commercial Sectors**  
(Trillion Btu)

	Residential Sector				Commercial Sector <sup>a</sup>						
	Distillate Fuel Oil	HGL <sup>b</sup>	Kero-sene	Total	Distillate Fuel Oil	HGL <sup>b</sup>	Kero-sene	Motor Gasoline <sup>c,d</sup>	Petroleum Coke	Residual Fuel Oil	Total
		Propane				Propane					
1950 Total .....	829	146	347	1,322	262	39	47	100	NA	424	872
1955 Total .....	1,194	202	371	1,767	377	54	51	133	NA	480	1,095
1960 Total .....	1,568	305	354	2,228	494	81	48	67	NA	559	1,248
1965 Total .....	1,713	386	334	2,432	534	103	54	77	NA	645	1,413
1970 Total .....	1,878	549	298	2,726	587	143	61	86	NA	714	1,592
1975 Total .....	1,807	512	161	2,479	587	130	49	89	NA	492	1,346
1980 Total .....	1,316	312	107	1,734	518	88	41	107	NA	565	1,318
1985 Total .....	1,092	315	159	1,566	631	95	33	96	NA	228	1,083
1990 Total .....	978	353	64	1,395	536	102	12	111	0	230	991
1995 Total .....	904	395	74	1,374	478	109	22	18	(s)	141	769
2000 Total .....	904	556	95	1,554	490	151	30	44	(s)	92	807
2001 Total .....	907	526	95	1,529	508	143	31	37	(s)	70	790
2002 Total .....	859	538	60	1,457	444	141	16	45	(s)	80	726
2003 Total .....	931	545	70	1,547	496	157	19	60	(s)	111	842
2004 Total .....	923	512	85	1,520	470	152	20	45	(s)	122	810
2005 Total .....	853	514	84	1,450	447	132	22	46	(s)	116	762
2006 Total .....	709	446	66	1,222	400	123	15	48	(s)	75	662
2007 Total .....	721	484	44	1,249	381	122	9	60	(s)	75	648
2008 Total .....	750	553	21	1,325	384	158	4	45	(s)	71	663
2009 Total .....	582	548	28	1,158	395	139	4	52	(s)	71	662
2010 Total .....	562	530	29	1,120	391	140	5	52	(s)	62	650
2011 Total .....	523	493	19	1,034	391	143	3	44	(s)	54	635
2012 Total .....	482	396	8	886	355	136	1	39	(s)	31	562
2013 Total .....	491	463	8	963	344	152	1	40	(s)	24	561
2014 Total .....	533	490	14	1,036	357	160	2	54	1	8	581
2015 Total .....	551	446	10	1,007	360	148	1	<sup>d</sup> 376	1	4	890
2016 Total .....	435	430	14	878	326	150	2	375	(s)	4	858
2017 Total .....	432	431	8	871	323	156	1	361	(s)	4	845
2018 January .....	83	84	5	172	53	25	1	29	(s)	1	108
February .....	54	62	(s)	116	34	19	(s)	27	(s)	(s)	80
March .....	45	62	1	107	28	19	(s)	32	(s)	(s)	80
April .....	41	46	(s)	88	26	16	(s)	30	(s)	(s)	72
May .....	25	22	1	48	16	10	(s)	32	0	(s)	58
June .....	19	17	(s)	36	12	8	(s)	32	0	(s)	53
July .....	18	15	(s)	34	12	8	(s)	32	0	(s)	52
August .....	15	16	(s)	31	10	8	(s)	33	0	(s)	51
September .....	21	17	(s)	39	14	9	(s)	30	(s)	(s)	52
October .....	46	35	(s)	80	29	13	(s)	31	(s)	(s)	73
November .....	59	60	(s)	119	37	19	(s)	30	(s)	(s)	87
December .....	81	71	(s)	152	51	22	(s)	31	(s)	(s)	104
Total .....	508	507	8	1,022	323	176	1	366	(s)	3	870
2019 January .....	<sup>R</sup> 68	79	3	<sup>R</sup> 151	<sup>R</sup> 48	23	1	<sup>R</sup> 30	(s)	(s)	<sup>R</sup> 102
February .....	<sup>R</sup> 57	67	2	<sup>R</sup> 126	<sup>R</sup> 40	20	(s)	<sup>R</sup> 28	(s)	(s)	<sup>R</sup> 88
March .....	<sup>R</sup> 50	62	(s)	<sup>R</sup> 112	<sup>R</sup> 35	19	(s)	31	(s)	(s)	<sup>R</sup> 86
April .....	<sup>R</sup> 32	36	(s)	<sup>R</sup> 68	<sup>R</sup> 23	13	(s)	<sup>R</sup> 31	(s)	(s)	<sup>R</sup> 66
May .....	<sup>R</sup> 25	27	(s)	<sup>R</sup> 52	<sup>R</sup> 18	11	(s)	32	0	(s)	<sup>R</sup> 61
June .....	<sup>R</sup> 21	17	(s)	<sup>R</sup> 38	<sup>R</sup> 15	8	(s)	<sup>R</sup> 32	0	(s)	<sup>R</sup> 55
July .....	<sup>R</sup> 21	15	(s)	<sup>R</sup> 36	14	8	(s)	32	0	(s)	<sup>R</sup> 55
August .....	<sup>R</sup> 32	15	(s)	<sup>R</sup> 47	<sup>R</sup> 22	8	(s)	33	0	(s)	<sup>R</sup> 63
September .....	<sup>R</sup> 18	17	1	<sup>R</sup> 36	12	9	(s)	30	0	(s)	<sup>R</sup> 51
October .....	<sup>R</sup> 28	34	(s)	<sup>R</sup> 61	19	13	(s)	31	0	(s)	<sup>R</sup> 63
November .....	<sup>R</sup> 54	58	2	<sup>R</sup> 114	<sup>R</sup> 38	18	(s)	30	0	(s)	<sup>R</sup> 86
December .....	<sup>R</sup> 64	68	2	<sup>R</sup> 134	<sup>R</sup> 44	21	(s)	30	(s)	(s)	<sup>R</sup> 96
Total .....	<sup>R</sup> 471	495	10	<sup>R</sup> 976	<sup>R</sup> 327	172	2	<sup>R</sup> 369	(s)	<sup>R</sup> 2	<sup>R</sup> 873
2020 January .....	<sup>R</sup> 52	70	3	<sup>R</sup> 125	<sup>R</sup> 36	21	1	29	(s)	(s)	<sup>R</sup> 88
February .....	<sup>R</sup> 43	62	4	<sup>R</sup> 109	<sup>R</sup> 30	19	1	28	(s)	(s)	<sup>R</sup> 78
March .....	<sup>R</sup> 40	51	1	<sup>R</sup> 92	<sup>R</sup> 28	17	(s)	26	0	(s)	<sup>R</sup> 71
April .....	<sup>R</sup> 36	41	(s)	<sup>R</sup> 77	<sup>R</sup> 25	14	(s)	19	0	(s)	<sup>R</sup> 59
May .....	<sup>R</sup> 41	26	(s)	<sup>R</sup> 67	28	11	(s)	24	0	(s)	<sup>R</sup> 64
June .....	<sup>R</sup> 26	16	(s)	<sup>R</sup> 42	<sup>R</sup> 18	8	(s)	27	0	(s)	<sup>R</sup> 53
July .....	<sup>R</sup> 17	15	(s)	<sup>R</sup> 32	12	8	(s)	28	0	(s)	<sup>R</sup> 49
August .....	<sup>R</sup> 15	15	1	<sup>R</sup> 32	<sup>R</sup> 11	8	(s)	<sup>R</sup> 29	0	(s)	<sup>R</sup> 48
September .....	<sup>R</sup> 25	19	1	<sup>R</sup> 45	<sup>R</sup> 18	9	(s)	28	0	(s)	<sup>R</sup> 55
October .....	<sup>R</sup> 29	33	(s)	<sup>R</sup> 63	20	12	(s)	28	0	(s)	<sup>R</sup> 61
November .....	36	46	(s)	81	25	15	(s)	26	0	(s)	66
11-Month Total .....	360	395	11	766	250	143	2	293	(s)	2	690
2019 11-Month Total .....	407	427	9	842	283	151	1	339	(s)	2	776
2018 11-Month Total .....	427	435	8	870	272	154	1	336	(s)	3	766

<sup>a</sup> Commercial sector fuel use, including that at commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Hydrocarbon gas liquids.

<sup>c</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>d</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.

Notes: • Data are estimates. • For total heat content of petroleum consumption by all sectors, see data for heat content of petroleum products supplied in Table 3.6. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 3.8b Heat Content of Petroleum Consumption: Industrial Sector**  
(Trillion Btu)

	Industrial Sector <sup>a</sup>												
	Asphalt and Road Oil	Distillate Fuel Oil	Hydrocarbon Gas Liquids				Kerosene	Lubricants	Motor Gasoline <sup>d,e</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>f</sup>	Total
			Propane/Propylene			Total <sup>c</sup>							
			Propane	Propylene	Total <sup>b</sup>								
1950 Total .....	435	698	17	18	34	138	274	94	251	90	1,416	546	3,943
1955 Total .....	615	991	83	30	113	293	241	103	332	147	1,573	798	5,093
1960 Total .....	734	1,016	137	47	184	461	161	107	381	328	1,584	947	5,720
1965 Total .....	890	1,150	213	63	276	649	165	137	342	444	1,582	1,390	6,750
1970 Total .....	1,082	1,226	282	77	359	930	185	155	288	446	1,624	1,817	7,754
1975 Total .....	1,014	1,339	339	84	423	1,126	119	149	223	540	1,509	2,071	8,092
1980 Total .....	962	1,324	625	100	726	1,718	181	182	158	516	1,349	3,073	9,463
1985 Total .....	1,029	1,119	696	101	798	1,813	44	166	218	575	748	1,944	7,655
1990 Total .....	1,170	1,150	660	147	807	1,781	12	186	185	714	411	2,588	8,199
1995 Total .....	1,178	1,130	794	220	1,014	2,269	15	178	200	721	337	2,498	8,525
2000 Total .....	1,276	1,199	703	315	1,017	2,498	16	190	150	796	241	2,635	8,999
2001 Total .....	1,257	1,299	623	294	917	2,212	23	174	295	858	203	2,793	9,113
2002 Total .....	1,240	1,203	730	326	1,056	2,313	14	172	308	842	190	2,816	9,099
2003 Total .....	1,220	1,169	649	333	982	2,185	24	159	323	825	220	3,043	9,169
2004 Total .....	1,304	1,213	752	358	1,109	2,292	28	161	371	937	249	3,205	9,760
2005 Total .....	1,323	1,262	709	341	1,050	2,138	39	160	354	894	281	3,122	9,574
2006 Total .....	1,261	1,258	731	375	1,106	2,171	30	156	374	938	239	3,276	9,703
2007 Total .....	1,197	1,256	751	352	1,103	2,207	13	161	302	910	193	3,134	9,373
2008 Total .....	1,012	1,348	547	323	870	1,904	4	150	245	870	194	2,788	8,514
2009 Total .....	873	1,073	537	374	911	1,992	4	135	238	805	130	2,483	7,733
2010 Total .....	878	1,153	517	428	944	2,204	7	136	260	694	120	2,645	8,096
2011 Total .....	859	1,236	551	434	985	2,169	4	127	254	663	135	2,621	8,069
2012 Total .....	827	1,271	674	432	1,107	2,349	2	118	252	717	70	2,474	8,080
2013 Total .....	783	1,266	736	429	1,165	2,544	1	125	263	663	48	2,583	8,277
2014 Total .....	793	1,366	562	417	979	2,409	3	131	210	653	41	2,430	8,035
2015 Total .....	832	1,170	612	413	1,025	2,621	2	142	<sup>e</sup> 258	663	34	2,435	8,156
2016 Total .....	853	1,157	584	423	1,007	2,597	2	135	262	653	52	2,553	8,265
2017 Total .....	849	1,205	532	432	964	2,679	1	125	264	610	50	2,667	8,451
2018 January .....	32	131	64	39	104	268	1	9	22	54	3	223	744
February .....	38	92	49	34	82	224	(s)	11	19	25	3	220	632
March .....	57	128	43	36	79	239	(s)	12	23	48	3	242	752
April .....	45	103	39	33	72	223	(s)	10	22	48	5	201	657
May .....	79	122	30	37	67	234	(s)	9	23	52	3	213	737
June .....	95	85	31	35	66	233	(s)	11	23	56	3	232	738
July .....	95	87	53	35	88	270	(s)	11	24	51	4	218	760
August .....	104	113	50	37	87	278	(s)	12	24	74	3	228	835
September .....	77	102	62	35	97	267	(s)	8	22	65	4	190	733
October .....	84	119	52	37	89	266	(s)	10	23	72	3	233	810
November .....	49	101	41	38	79	262	(s)	10	22	42	4	217	707
December .....	37	71	42	39	80	267	(s)	8	23	42	4	213	665
Total .....	793	1,254	554	436	990	3,029	2	122	269	629	43	2,630	8,771
2019 January .....	40	<sup>R</sup> 137	60	38	98	294	1	10	<sup>R</sup> 21	47	4	225	<sup>R</sup> 779
February .....	37	<sup>R</sup> 116	45	32	77	255	(s)	8	<sup>R</sup> 20	14	3	162	<sup>R</sup> 617
March .....	48	<sup>R</sup> 116	33	31	64	246	(s)	9	<sup>R</sup> 22	49	3	204	<sup>R</sup> 697
April .....	63	<sup>R</sup> 106	26	33	60	239	(s)	13	22	39	2	225	<sup>R</sup> 709
May .....	76	<sup>R</sup> 108	28	36	64	247	(s)	9	23	53	2	232	<sup>R</sup> 750
June .....	82	<sup>R</sup> 84	35	36	71	255	(s)	9	23	68	4	205	<sup>R</sup> 730
July .....	105	<sup>R</sup> 76	46	35	82	286	(s)	11	23	68	4	206	<sup>R</sup> 780
August .....	104	<sup>R</sup> 76	40	35	75	278	(s)	10	24	56	4	240	<sup>R</sup> 792
September .....	96	<sup>R</sup> 92	61	33	94	285	(s)	8	22	42	<sup>R</sup> 4	218	<sup>R</sup> 765
October .....	90	<sup>R</sup> 120	60	38	97	<sup>R</sup> 287	(s)	12	23	42	4	217	<sup>R</sup> 795
November .....	62	<sup>R</sup> 101	57	35	92	270	(s)	9	22	60	<sup>R</sup> 3	219	<sup>R</sup> 745
December .....	41	<sup>R</sup> 74	50	36	86	280	(s)	8	22	63	<sup>R</sup> 4	235	<sup>R</sup> 727
Total .....	844	<sup>R</sup> 1,206	542	418	960	3,222	2	118	<sup>R</sup> 267	602	<sup>R</sup> 41	2,585	<sup>R</sup> 8,886
2020 January .....	39	<sup>R</sup> 120	38	33	71	260	1	11	21	40	3	225	<sup>R</sup> 720
February .....	37	<sup>R</sup> 115	56	28	84	224	1	9	<sup>R</sup> 20	41	2	221	<sup>R</sup> 670
March .....	42	<sup>R</sup> 98	43	31	74	277	(s)	6	19	41	1	230	<sup>R</sup> 714
April .....	58	<sup>R</sup> 40	30	32	62	224	(s)	7	14	28	1	194	<sup>R</sup> 567
May .....	75	<sup>R</sup> 32	37	33	69	258	(s)	7	<sup>R</sup> 17	35	1	211	<sup>R</sup> 637
June .....	102	<sup>R</sup> 29	<sup>R</sup> 20	30	51	247	(s)	9	<sup>R</sup> 19	33	3	184	<sup>R</sup> 625
July .....	101	<sup>R</sup> 48	35	33	68	282	(s)	10	21	37	4	196	<sup>R</sup> 699
August .....	98	<sup>R</sup> 53	43	31	74	276	(s)	8	21	63	4	201	<sup>R</sup> 724
September .....	84	<sup>R</sup> 74	51	33	84	270	(s)	9	20	50	4	169	<sup>R</sup> 680
October .....	82	<sup>R</sup> 96	57	36	93	312	(s)	10	20	41	3	172	<sup>R</sup> 737
November .....	63	88	49	35	83	314	(s)	9	19	51	3	187	735
11-Month Total ...	782	793	459	353	813	2,943	2	95	212	460	30	2,190	7,507
2019 11-Month Total ...	803	1,132	492	381	874	2,942	2	109	245	539	37	2,350	8,159
2018 11-Month Total ...	755	1,182	513	397	910	2,763	2	114	247	587	39	2,417	8,106

<sup>a</sup> Industrial sector fuel use, including that at industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>b</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."

<sup>c</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.

<sup>d</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>e</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>f</sup> Petrochemical feedstocks, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1964, also includes special naphthas. Beginning in 1981,

also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

<sup>R</sup>=Revised. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.

Notes: • Data are estimates. • For total heat content of petroleum consumption by all sectors, see data for heat content of petroleum products supplied in Table 3.6. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia. Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 3.8c Heat Content of Petroleum Consumption: Transportation and Electric Power Sectors** (Trillion Btu)

	Transportation Sector								Electric Power Sector <sup>a</sup>			
	Aviation Gasoline	Distillate Fuel Oil <sup>c</sup>	HGL <sup>b</sup>	Jet Fuel <sup>e</sup>	Lubricants	Motor Gasoline <sup>f,g</sup>	Residual Fuel Oil	Total	Distillate Fuel Oil <sup>h</sup>	Petroleum Coke	Residual Fuel Oil <sup>i</sup>	Total
			Propane <sup>d</sup>									
1950 Total .....	199	480	3	( <sup>e</sup> )	141	4,664	1,201	6,690	32	NA	440	472
1955 Total .....	354	791	13	301	155	6,175	1,009	8,799	32	NA	439	471
1960 Total .....	298	892	19	739	152	7,183	844	10,125	22	NA	530	553
1965 Total .....	222	1,093	32	1,215	149	8,386	770	11,866	29	NA	693	722
1970 Total .....	100	1,569	44	1,973	147	10,716	761	15,311	141	19	1,958	2,117
1975 Total .....	71	2,121	43	2,029	155	12,485	711	17,615	226	2	2,937	3,166
1980 Total .....	64	2,795	18	2,179	172	12,383	1,398	19,009	169	5	2,459	2,634
1985 Total .....	50	3,170	30	2,497	156	12,784	786	19,472	85	7	998	1,090
1990 Total .....	45	3,661	23	3,129	176	13,575	1,016	21,626	97	30	1,163	1,289
1995 Total .....	40	4,191	18	3,132	168	14,576	911	23,036	108	81	566	755
2000 Total .....	36	5,159	12	3,580	179	15,933	888	25,787	175	99	871	1,144
2001 Total .....	35	5,286	14	3,426	164	16,013	586	25,524	170	103	1,003	1,276
2002 Total .....	34	5,387	14	3,340	162	16,437	677	26,051	127	175	659	961
2003 Total .....	30	5,584	18	3,265	150	16,565	571	26,184	161	175	869	1,205
2004 Total .....	31	5,925	19	3,383	152	16,901	740	27,150	111	211	879	1,201
2005 Total .....	35	6,068	28	3,475	151	16,958	837	27,553	114	231	876	1,222
2006 Total .....	33	6,390	28	3,379	147	17,088	906	27,972	73	203	361	637
2007 Total .....	32	6,411	22	3,358	152	17,066	994	28,034	89	163	397	648
2008 Total .....	28	5,792	40	3,193	141	16,510	926	26,630	73	146	240	459
2009 Total .....	27	5,537	28	2,883	127	16,425	791	25,817	70	132	181	382
2010 Total .....	27	5,826	<sup>d</sup> 7	2,963	155	16,320	892	26,190	80	137	154	370
2011 Total .....	27	5,997	7	2,950	148	15,877	776	25,783	64	138	93	295
2012 Total .....	25	5,736	7	2,901	135	15,795	671	25,270	52	85	77	214
2013 Total .....	22	5,894	7	2,969	143	16,030	581	25,646	55	123	77	255
2014 Total .....	22	6,154	7	3,042	149	16,209	447	26,030	82	118	95	295
2015 Total .....	21	6,251	7	3,204	163	<sup>g</sup> 16,308	463	26,416	70	112	94	276
2016 Total .....	20	6,197	7	3,350	154	16,601	623	26,953	55	118	71	244
2017 Total .....	21	6,248	7	3,481	142	16,576	665	27,140	55	97	66	218
2018 January .....	1	504	1	276	10	1,326	36	2,155	30	11	23	64
February .....	1	458	1	252	12	1,199	45	1,968	4	9	4	17
March .....	2	544	1	300	13	1,428	39	2,327	4	7	4	15
April .....	2	541	1	277	12	1,344	68	2,244	4	8	4	17
May .....	2	583	1	296	10	1,436	49	2,377	5	6	5	16
June .....	2	561	1	316	13	1,431	44	2,367	5	9	6	20
July .....	3	586	1	312	13	1,455	58	2,426	4	10	6	20
August .....	2	606	1	327	13	1,475	48	2,472	4	10	6	20
September .....	1	554	1	290	10	1,336	56	2,247	4	9	6	19
October .....	3	578	1	294	11	1,402	44	2,333	4	6	6	16
November .....	1	524	1	299	11	1,357	55	2,248	5	8	5	18
December .....	2	509	1	295	9	1,385	62	2,263	5	9	4	18
<b>Total</b> .....	<b>22</b>	<b>6,550</b>	<b>8</b>	<b>3,533</b>	<b>137</b>	<b>16,573</b>	<b>604</b>	<b>27,427</b>	<b>81</b>	<b>101</b>	<b>78</b>	<b>260</b>
2019 January .....	1	<sup>R</sup> 513	1	285	11	1,324	<sup>R</sup> 51	<sup>R</sup> 2,186	7	9	6	22
February .....	1	<sup>R</sup> 478	1	255	9	1,236	42	<sup>R</sup> 2,022	4	8	4	16
March .....	2	<sup>R</sup> 541	1	301	10	1,385	36	<sup>R</sup> 2,275	4	7	4	15
April .....	2	<sup>R</sup> 547	1	299	15	<sup>R</sup> 1,373	27	<sup>R</sup> 2,264	4	4	4	12
May .....	2	<sup>R</sup> 578	1	312	11	1,432	30	<sup>R</sup> 2,366	5	8	5	18
June .....	2	<sup>R</sup> 564	1	306	10	1,416	52	<sup>R</sup> 2,352	5	6	5	16
July .....	3	<sup>R</sup> 582	1	325	13	1,438	57	<sup>R</sup> 2,417	4	8	6	18
August .....	2	<sup>R</sup> 586	1	324	11	1,483	54	<sup>R</sup> 2,460	4	8	6	18
September .....	2	<sup>R</sup> 551	1	290	9	1,342	49	<sup>R</sup> 2,244	4	6	5	15
October .....	2	<sup>R</sup> 584	1	304	13	1,404	53	<sup>R</sup> 2,360	4	2	5	11
November .....	2	<sup>R</sup> 529	1	291	10	1,344	32	<sup>R</sup> 2,209	4	4	5	13
December .....	1	<sup>R</sup> 514	1	318	9	1,353	47	<sup>R</sup> 2,243	5	6	5	15
<b>Total</b> .....	<b>23</b>	<sup>R</sup> <b>6,567</b>	<b>8</b>	<b>3,608</b>	<b>132</b>	<sup>R</sup> <b>16,531</b>	<sup>R</sup> <b>529</b>	<sup>R</sup> <b>27,398</b>	<b>54</b>	<b>76</b>	<b>59</b>	<b>189</b>
2020 January .....	2	<sup>R</sup> 501	1	294	12	1,321	42	<sup>R</sup> 2,173	5	7	5	17
February .....	1	<sup>R</sup> 478	1	268	10	1,265	<sup>R</sup> 21	<sup>R</sup> 2,044	4	5	4	13
March .....	1	<sup>R</sup> 529	1	244	6	<sup>R</sup> 1,173	16	<sup>R</sup> 1,970	3	7	4	14
April .....	1	<sup>R</sup> 502	1	118	8	854	18	<sup>R</sup> 1,502	3	6	3	13
May .....	2	<sup>R</sup> 526	1	105	8	1,084	11	<sup>R</sup> 1,737	3	7	4	14
June .....	2	<sup>R</sup> 527	1	134	10	1,209	<sup>R</sup> 36	<sup>R</sup> 1,918	4	9	4	17
July .....	2	<sup>R</sup> 563	1	169	12	1,276	57	<sup>R</sup> 2,079	5	10	5	20
August .....	2	<sup>R</sup> 570	1	178	9	1,283	<sup>R</sup> 50	<sup>R</sup> 2,094	4	9	5	18
September .....	2	<sup>R</sup> 539	1	157	10	1,247	52	<sup>R</sup> 2,007	3	4	5	12
October .....	2	<sup>R</sup> 568	1	177	11	1,245	<sup>R</sup> 45	<sup>R</sup> 2,048	4	4	5	13
November .....	2	520	1	192	11	1,164	32	1,922	4	6	4	14
<b>11-Month Total</b> ...	<b>18</b>	<b>5,822</b>	<b>7</b>	<b>2,036</b>	<b>107</b>	<b>13,123</b>	<b>382</b>	<b>21,494</b>	<b>42</b>	<b>74</b>	<b>48</b>	<b>164</b>
2019 11-Month Total ...	22	6,053	7	3,290	123	15,178	483	25,155	49	70	54	173
2018 11-Month Total ...	20	6,041	7	3,238	128	15,189	542	25,164	76	92	74	242

<sup>a</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>b</sup> Hydrocarbon gas liquids.

<sup>c</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>d</sup> There is a discontinuity in this time series between 2009 and 2010 due to a change in data sources.

<sup>e</sup> Beginning in 1957, includes kerosene-type jet fuel. For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other" on Table 3.8b.)

<sup>f</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>g</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>h</sup> Fuel oil nos. 1, 2, and 4. Through 1979, data are for gas turbine and internal

combustion plant use of petroleum. Through 2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>i</sup> Fuel oil nos. 5 and 6. Through 1979, data are for steam plant use of petroleum. Through 2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>R</sup>=Revised. NA=Not available.

Notes: • Transportation sector data are estimates. • For total heat content of petroleum consumption by all sectors, see data for heat content of petroleum products supplied in Table 3.6. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Note 1. Petroleum Products Supplied and Petroleum Consumption.** Total petroleum products supplied is the sum of the products supplied for each petroleum product, crude oil, unfinished oils, and gasoline blending components. This also includes petroleum products supplied for non-combustion use in the industrial and transportation sectors (see Tables 1.11a and 1.11b). In general, except for crude oil, product supplied of each product is computed as follows: field production, plus renewable fuels and oxygenate plant net production, plus refinery and blender net production, plus imports, plus net receipts, plus adjustments, minus stock change, minus refinery and blender net inputs, minus exports. Crude oil product supplied is the sum of crude oil burned on leases and at pipeline pump stations as reported on Form EIA-813, "Monthly Crude Oil Report." Prior to 1983, crude oil burned on leases and used at pipeline pump stations was reported as either distillate or residual fuel oil and was included as product supplied for these products. Petroleum product supplied (see Tables 3.5 and 3.6) is an approximation of petroleum consumption and is synonymous with the term "Petroleum Consumption" in Tables 3.7a–3.8c.

**Note 2. Petroleum Survey Respondents.** The U.S. Energy Information Administration (EIA) uses a number of sources and methods to maintain the survey respondent lists. On a regular basis, survey managers review such industry publications as the *Oil & Gas Journal* and *Oil Daily* for information on facilities or companies starting up or closing down operations. Those sources are augmented by articles in newspapers, communications from respondents indicating changes in status, and information received from survey systems.

To supplement routine frames maintenance and to provide more thorough coverage, a comprehensive frames investigation is conducted every 3 years. This investigation results in the reassessment and recompilation of the complete frame for each survey. The effort also includes the evaluation of the impact of potential frame changes on the historical time series of data from these respondents. The results of this frame study are usually implemented in January to provide a full year under the same frame.

**Note 3. Historical Petroleum Data.** Detailed information on petroleum data through 1993 can be found in Notes 1–6 on pages 60 and 61 in the July 2013 *Monthly Energy Review* (MER) at <http://www.eia.gov/totalenergy/data/monthly/archive/00351307.pdf>. The notes discuss:

Note 1, "Petroleum Survey Respondents": In 1993, EIA added numerous companies that produce, blend, store, or import oxygenates to the monthly surveys.

Note 2, "Motor Gasoline": In 1981, EIA expanded its universe to include nonrefinery blenders and separated blending components from finished motor gasoline as a reporting category. In 1993, EIA made adjustments to finished motor gasoline product supplied data to more accurately account for fuel ethanol and motor gasoline blending components blended into finished motor gasoline.

Note 3, "Distillate and Residual Fuel Oils": In 1981, EIA eliminated the requirement to report crude oil in pipelines or burned on leases as either distillate or residual fuel oil.

Note 4, "Petroleum New Stock Basis": In 1975, 1979, 1981, and 1983, EIA added numerous respondents to bulk terminal and pipeline surveys; in 1984, EIA made changes in the reporting of natural gas liquids; and in 1993, EIA changed how it collected bulk terminal and pipeline stocks of oxygenates. These changes affected stocks reported and stock change calculations.

Note 5, "Stocks of Alaskan Crude Oil": In 1981, EIA began to include data for stocks of Alaskan crude oil in transit.

Note 6, "Petroleum Data Discrepancies": In 1976, 1978, and 1979, there are some small discrepancies between data in the MER and the *Petroleum Supply Annual*.

## Table 3.1 Sources

1949–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports.

1976–1980: U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports.

1981–2001: EIA, *Petroleum Supply Annual* (PSA), annual reports.

2002 forward: EIA, PSA, annual reports, and unpublished revisions; *Petroleum Supply Monthly*, monthly reports; revisions to crude oil production, total field production, and adjustments (based on crude oil production data from: Form EIA-914, "Monthly Crude Oil, Lease Condensate, and Natural Gas Production Report"; state government agencies; U.S. Department of the Interior, Bureau of Safety and Environmental Enforcement, and predecessor agencies; and Form EIA-182, "Domestic Crude Oil First Purchase Report"); and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.

### Table 3.2 Sources

1949–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports; and U.S. Energy Information Administration (EIA) estimates. (For 1967–1975, refinery and blender net production estimates for propylene are equal to "Propane/Propylene Production at Refineries for Chemical Use"; and estimates for propane are equal to total propane/propylene minus propylene.)

1976–1980: EIA, Energy Data Reports, *Petroleum Statement, Annual*, annual reports, and estimates. (Refinery and blender net production estimates for propylene are equal to "Propane/Propylene Production at Refineries for Chemical Use"; and estimates for propane are equal to total propane/propylene minus propylene.)

1981–2019: EIA, *Petroleum Supply Annual*, annual reports, unpublished revisions, and estimates. (For 1981–1985, refinery and blender net production estimates for propylene are equal to "Propane/Propylene Production at Refineries for Petrochemical Use"; and estimates for propane are equal to total propane/propylene minus propylene. For 1986–1988, refinery and blender net production estimates for propylene are created using the 1989 annual propylene share of "Net Refinery Production of Propane/Propylene"; and estimates for propane are equal to total propane/propylene minus propylene.)

2020 and 2021: EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system, Short-Term Integrated Forecasting System, and *Monthly Energy Review* data system calculations.

### Table 3.5 Sources

1949–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports; and U.S. Energy Information Administration (EIA) estimates. (For 1949–1966, product supplied estimates for total propane/propylene are created using sales and shipments data from Bureau of Mines, Mineral Industry Surveys, *Sales of Liquefied Petroleum Gases and Ethane*, annual reports, and *Shipments of Liquefied Petroleum Gases and Ethane*, annual reports—annual growth rates of sales and shipments are applied to the 1967 total propane/propylene product supplied value to create historical annual estimates. For 1949–1966, product supplied estimates for propylene are created using the 1967 annual propylene share of total propane/propylene product supplied; and estimates for propane are equal to total propane/propylene minus propylene. For 1967–1975, product supplied estimates for propylene are equal to propylene refinery and blender net production from Table 3.2; and estimates for propane are equal to total propane/propylene minus propylene.)

1976–1980: EIA, Energy Data Reports, *Petroleum Statement, Annual*, annual reports, and estimates. (Product supplied estimates for propylene are equal to propylene refinery and blender net production from Table 3.2; and estimates for propane are equal to total propane/propylene minus propylene.)

1981–2019: EIA, *Petroleum Supply Annual*, annual reports, unpublished revisions, and estimates. (For 1981–1992, product supplied estimates for propylene are equal to propylene refinery and blender net production from Table 3.2; and estimates for propane are equal to total propane/propylene minus propylene. For 1993–2009, product supplied

estimates for propylene are equal to propylene refinery and blender net production from Table 3.2, plus propylene imports from Table 3.3b; and estimates for propane are equal to total propane/propylene minus propylene.)

2020 and 2021: EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system, Short-Term Integrated Forecasting System, and *Monthly Energy Review* data system calculations.

## Table 3.6 Sources

### *Asphalt and Road Oil*

Product supplied data in thousand barrels per day for asphalt and road oil are from Table 3.5, and are converted to trillion Btu by multiplying by the asphalt and road oil heat content factor in Table A1.

### *Aviation Gasoline*

Product supplied data in thousand barrels per day for aviation gasoline are from Table 3.5, and are converted to trillion Btu by multiplying by the aviation gasoline (finished) heat content factor in Table A1.

### *Distillate Fuel Oil*

1949–2008: Product supplied data in thousand barrels per day for distillate fuel oil are from Table 3.5, and are converted to trillion Btu by multiplying by the distillate fuel oil heat content factors in Table A3.

2009–2011: Consumption data for biodiesel are calculated using biodiesel data from U.S. Energy Information Administration (EIA), EIA-22M, “Monthly Biodiesel Production Survey”; and biomass-based diesel fuel data from EIA-810, “Monthly Refinery Report,” EIA-812, “Monthly Product Pipeline Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1). Consumption data for other renewable diesel fuel are set equal to refinery and blender net inputs data from EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Product supplied data for distillate fuel oil from Table 3.5, minus consumption data for biodiesel and other renewable diesel fuel, are converted to Btu by multiplying by the distillate fuel oil heat content factors in Table A3. Total distillate fuel oil product supplied is the sum of values for distillate fuel oil (excluding biodiesel and other renewable diesel fuel), biodiesel, and other renewable diesel fuel.

2012 forward: Consumption data for biodiesel are from Table 10.4. Consumption data for other renewable diesel fuel are set equal to refinery and blender net inputs data from EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Product supplied data for distillate fuel oil from Table 3.5, minus consumption data for biodiesel and other renewable diesel fuel, are converted to Btu by multiplying by the distillate fuel oil heat content factors in Table A3. Total distillate fuel oil product supplied is the sum of the values for distillate fuel oil (excluding biodiesel and other renewable diesel fuel), biodiesel, and other renewable diesel fuel.

### *Hydrocarbon Gas Liquids (HGL)—Propane*

Product supplied data in thousand barrels per day for propane are from Table 3.5, and are converted to trillion Btu by multiplying by the propane heat content factor in Table A1.

### *Hydrocarbon Gas Liquids (HGL)—Propylene*

Product supplied data in thousand barrels per day for propylene are from Table 3.5, and are converted to trillion Btu by multiplying by the propylene heat content factor in Table A1.

### *Hydrocarbon Gas Liquids (HGL)—Propane/Propylene Total*

Prior to the current two months, total propane/propylene product supplied is the sum of the data in trillion Btu for propane and propylene.

For the current two months, product supplied data in thousand barrels per day for total propane/propylene are from Table 3.5, and are converted to trillion Btu by multiplying by the propane/propylene heat content factor in Table A1.



### ***Hydrocarbon Gas Liquids (HGL)—Total***

Prior to the current two months, product supplied data in thousand barrels per day for the component products of HGL (ethane, propane, normal butane, isobutane, natural gasoline, and refinery olefins—ethylene, propylene, butylene, and isobutylene) are from the PSA, PSM, and earlier publications (see sources for Table 3.5). These data are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1. Total HGL product supplied is the sum of the data in trillion Btu for the HGL component products.

For the current two months: Note that "liquefied petroleum gases" ("LPG") below include ethane, propane, normal butane, isobutane, and refinery olefins (ethylene, propylene, butylene, and isobutylene), but exclude natural gasoline. Product supplied data in thousand barrels per day for LPG are from EIA's Short-Term Integrated Forecasting System (STIFS). (The STIFS model results are used in EIA's *Short-Term Energy Outlook*, which is accessible on the Web at <https://www.eia.gov/outlooks/steo/>.) These data are converted to trillion Btu by multiplying by the previous year's quantity-weighted LPG heat content factor (derived using LPG component heat content factors in Table A1). Product supplied data in thousand barrels per day for natural gasoline are from STIFS, and are converted to trillion Btu by multiplying by the natural gasoline heat content factor in Table A1. Total HGL product supplied is the sum of the data in trillion Btu for LPG and natural gasoline.

### ***Jet Fuel***

Product supplied data in thousand barrels per day for kerosene-type jet fuel and, through 2004, naphtha-type jet fuel are from the PSA, PSM, and earlier publications (see sources for Table 3.5). These data are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1. Total jet fuel product supplied is the sum of the data in trillion Btu for kerosene-type and naphtha-type jet fuel.

### ***Kerosene***

Product supplied data in thousand barrels per day for kerosene are from Table 3.5, and are converted to trillion Btu by multiplying by the kerosene heat content factor in Table A1.

### ***Lubricants***

Product supplied data in thousand barrels per day for lubricants are from Table 3.5, and are converted to trillion Btu by multiplying by the lubricants heat content factor in Table A1.

### ***Motor Gasoline***

Product supplied data in thousand barrels per day for motor gasoline are from Table 3.5, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

### ***Other Petroleum Products***

Prior to the current two months, product supplied data in thousand barrels per day for "other" petroleum products are from the PSA, PSM, and earlier publications (see sources for Table 3.5). "Other" petroleum products include petrochemical feedstocks, special naphthas, still gas (refinery gas), waxes, and miscellaneous products; beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components; beginning in 1983, also includes crude oil burned as fuel; and beginning in 2005, also includes naphtha-type jet fuel. These data are converted to trillion Btu by multiplying by the appropriate heat content factors in MER Table A1. Total "Other" petroleum product supplied is the sum of the data in trillion Btu for the individual products.

For the current two months, total "Other" petroleum products supplied is calculated by first estimating total petroleum products supplied (product supplied data in thousand barrels per day for total petroleum from Table 3.5 are converted to trillion Btu by multiplying by the total petroleum consumption heat content factor in Table A3), and then subtracting data in trillion Btu (from Table 3.6) for asphalt and road oil, aviation gasoline, distillate fuel oil, jet fuel, kerosene, total HGL, lubricants, motor gasoline, petroleum coke, and residual fuel oil.

### ***Petroleum Coke***

Product supplied data in thousand barrels per day for petroleum coke are from Table 3.5, and are converted to trillion Btu by multiplying by the petroleum coke heat content factors in Table A3.

### ***Residual Fuel Oil***

Product supplied data in thousand barrels per day for residual fuel oil are from Table 3.5, and are converted to trillion Btu by multiplying by the residual fuel oil heat content factor in Table A1.

### ***Total Petroleum***

Total petroleum products supplied is the sum of the data in trillion Btu for the products (except "Propane") shown in Table 3.6.

## **Tables 3.7a–3.7c Sources**

Petroleum consumption data for 1949–1972 are from the following sources:

1949–1959: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports, and U.S. Energy Information Administration (EIA) estimates.

1960–1972: EIA, State Energy Data System.

Petroleum consumption data beginning in 1973 are derived from data for "petroleum products supplied" from the following sources:

1973–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement Annual*, annual reports.

1976–1980: EIA, Energy Data Reports, *Petroleum Statement Annual*, annual reports.

1981–2019: EIA, *Petroleum Supply Annual* (PSA), annual reports, and unpublished revisions.

2020: EIA, *Petroleum Supply Monthly* (PSM), monthly reports.

Beginning in 1973, energy-use allocation procedures by individual product are as follows:

### ***Asphalt and Road Oil***

All consumption of asphalt and road oil is assigned to the industrial sector.

### ***Aviation Gasoline***

All consumption of aviation gasoline is assigned to the transportation sector.

### ***Distillate Fuel Oil***

Distillate fuel oil consumption is assigned to the sectors as follows:

#### ***Distillate Fuel Oil, Electric Power Sector***

See sources for Table 7.4b. For 1973–1979, electric utility consumption of distillate fuel oil is assumed to be the amount of petroleum (minus small amounts of kerosene and kerosene-type jet fuel deliveries) consumed in gas turbine and internal combustion plants. For 1980–2000, electric utility consumption of distillate fuel oil is assumed to be the amount of light oil (fuel oil nos. 1 and 2, plus small amounts of kerosene and jet fuel) consumed.

#### ***Distillate Fuel Oil, End-Use Sectors, Annual Data***

The aggregate end-use amount is total distillate fuel oil product supplied minus the amount consumed by the electric power sector. The end-use total consumed annually is allocated to the individual end-use sectors (residential, commercial, industrial, and transportation) in proportion to each sector's share of sales as reported in EIA's *Fuel Oil and Kerosene Sales (Sales)* report series (DOE/EIA-0535), which is based primarily on data collected by Form EIA-821, "Annual Fuel Oil and Kerosene Sales Report" (previously Form EIA-172). Shares for the current year are based on the most recent Sales report.

Following are notes on the individual sector groupings:

Beginning in 1979, the residential sector sales total is directly from the Sales reports. Through 1978, each year's sales subtotal of the heating plus industrial category is split into residential, commercial, and industrial (including farm) in proportion to the 1979 shares.

Beginning in 1979, the commercial sector sales total is directly from the Sales reports. Through 1978, each year's sales subtotal of the heating plus industrial category is split into residential, commercial, and industrial (including farm) in proportion to the 1979 shares.

Beginning in 1979, the industrial sector sales total is the sum of the sales for industrial, farm, oil company, off-highway diesel, and all other uses. Through 1978, each year's sales subtotal of the heating plus industrial category is split into residential, commercial, and industrial (including farm) in proportion to the 1979 shares, and this estimated industrial portion is added to oil company, off-highway diesel, and all other uses.

The transportation sector sales total is the sum of the sales for railroad, vessel bunkering, on-highway diesel, and military uses for all years.

### ***Distillate Fuel Oil, End-Use Sectors, Monthly Data***

Residential sector and commercial sector monthly consumption is estimated by allocating the annual estimates, which are described above, into the months in proportion to each month's share of the year's sales of No. 2 heating oil. (For each month of the current year, the residential and commercial consumption increase from the same month in the previous year is based on the percent increase in that month's No. 2 heating oil sales from the same month in the previous year.) The years' No. 2 heating oil sales totals are from the following sources: for 1973–1980, the Ethyl Corporation, *Monthly Report of Heating Oil Sales*; for 1981 and 1982, the American Petroleum Institute, *Monthly Report of Heating Oil Sales*; and for 1983 forward, EIA, Form EIA-782A, "Refiners'/Gas Plant Operators' Monthly Petroleum Product Sales Report," No. 2 Fuel Oil Sales to End Users and for Resale.

The transportation highway use portion is allocated into the months in proportion to each month's share of the year's total sales for highway use as reported by the Federal Highway Administration's Table MF-25, "Private and Commercial Highway Use of Special Fuels by Months." Beginning in 1994, the sales-for-highway-use data are no longer available as a monthly series; the 1993 data are used for allocating succeeding year's totals into months.

A distillate fuel oil "balance" is calculated as total distillate fuel oil product supplied minus the amount consumed by the electric power sector, residential sector, commercial sector, and for highway use.

Industrial sector monthly consumption is estimated by multiplying each month's distillate fuel oil "balance" by the annual industrial consumption share of the annual distillate fuel oil "balance."

Total transportation sector monthly consumption is estimated as total distillate fuel oil product supplied minus the amount consumed by the residential, commercial, industrial, and electric power sectors.

### ***Hydrocarbon Gas Liquids (HGL)—Propane***

Annual residential sector propane consumption: Through 2002, annual residential sector propane consumption is estimated by applying the average of the state residential shares for 2003–2008 to the combined residential and commercial propane sales. Beginning in 2003, annual residential sector propane consumption is assumed to equal propane retail sales to the residential sector and sales to retailers/cylinder markets.

Monthly residential sector propane consumption: Beginning in 1973, annual residential sector propane consumption is split into the estimated portion for residential space heating and water heating, and the estimated portion for all other residential uses. The annual values in thousand barrels for residential space heating and water heating are allocated to the months in proportion to U.S. heating degree days in Table 1.9. The annual values in thousand barrels for all other residential uses are allocated to the months by dividing the annual values by the number of days in the year and then multiplying by the number of days in the month. Monthly total residential sector propane consumption is the sum of the monthly values for residential space heating and water heating and for all other residential uses.

Annual commercial sector propane consumption: Through 2002, annual commercial sector propane consumption is equal to the combined residential and commercial propane sales minus residential sector propane consumption. Beginning in 2003, annual commercial sector propane consumption is assumed to equal commercial sector propane sales.

Monthly commercial sector propane consumption: Beginning in 1973, annual commercial sector propane consumption is split into the estimated portion for commercial space heating and water heating, and the estimated portion for all other commercial uses. The annual values in thousand barrels for commercial space heating and water heating are allocated to the months in proportion to U.S. heating degree days in Table 1.9. The annual values in thousand barrels for all other commercial uses are allocated to the months by dividing the annual values by the number of days in the year and then multiplying by the number of days in the month. Monthly total commercial sector propane consumption is the sum of the monthly values for commercial space heating and water heating and for all other commercial uses.

Annual transportation sector propane consumption: Through 2009, annual transportation sector propane consumption is assumed to equal the transportation portion of propane sales for internal combustion engines (these sales are allocated between the transportation and industrial sectors using data for special fuels used on highways provided by the U.S. Department of Transportation, Federal Highway Administration). Beginning in 2010, annual transportation sector propane consumption is from EIA, *Annual Energy Outlook*, Table 37, "Transportation Sector Energy Use by Fuel Type within a Mode."

Monthly transportation sector propane consumption: Beginning in 1973, the annual values in thousand barrels for transportation sector propane consumption are allocated to the months by dividing the annual values by the number of days in the year and then multiplying by the number of days in the month.

Annual and monthly industrial sector propane consumption: Industrial sector propane consumption is estimated as the difference between propane total product supplied from Table 3.5 and the sum of the estimated propane consumption by the residential, commercial, and transportation sectors.

Sources of the annual consumption estimates for creating annual sector shares are:

1973–1982: EIA's "Sales of Liquefied Petroleum Gases and Ethane" reports, based primarily on data collected by Form EIA-174, "Sales of Liquefied Petroleum Gases."

1983: End-use consumption estimates for 1983 are based on 1982 end-use consumption because the collection of data under Form EIA-174 was discontinued after data year 1982.

1984–2007: American Petroleum Institute (API), "Sales of Natural Gas Liquids and Liquefied Refinery Gases," table on sales of natural gas liquids and liquefied refinery gases by end use. EIA adjusts the data to remove quantities of natural gasoline and to estimate withheld values.

2008 and 2009: Propane consumption is from API, "Sales of Natural Gas Liquids and Liquefied Refinery Gases," table on sales of propane by end use. EIA adjusts the data to estimate withheld values. Other LPG consumption is from EIA, PSA, annual reports, and is allocated to the industrial sector.

2010–2016: Propane consumption is from API, "Sales of Natural Gas Liquids and Liquefied Refinery Gases," table on sales of odorized propane by end use; and EIA, *Annual Energy Outlook*, Table 37, "Transportation Sector Energy Use by Fuel Type Within a Mode." EIA adjusts the data to estimate withheld values. Other LPG consumption is from EIA, PSA, annual reports, and is allocated to the industrial sector.

2017 forward: Propane consumption is from Propane Education & Research Council, "Retail Propane Sales Report," data on propane sales by sector; and EIA, *Annual Energy Outlook*, Table 37, "Transportation Sector Energy Use by Fuel Type Within a Mode." EIA adjusts the data to estimate withheld values. Other LPG consumption is from EIA, PSA, annual reports, and is allocated to the industrial sector.

### ***Hydrocarbon Gas Liquids (HGL)—Propylene***

Industrial sector propylene consumption is equal to propylene product supplied in Table 3.5.

### ***Hydrocarbon Gas Liquids (HGL)—Propane/Propylene Total***

Industrial sector total propane/propylene consumption is the sum of the industrial sector consumption values for propane and propylene.

### ***Hydrocarbon Gas Liquids (HGL)—Total***

The residential, commercial, and transportation sector total HGL consumption values are equal to the propane consumption values for those sectors. The industrial sector total HGL consumption value is equal to total HGL product supplied in Table 3.5 minus propane consumption in the residential, commercial, and transportation sectors.

### ***Jet Fuel***

Through 1982, small amounts of kerosene-type jet fuel were consumed by the electric power sector. Kerosene-type jet fuel deliveries to the electric power sector as reported on Form FERC-423 (formerly Form FPC-423) were used as estimates of this consumption. Through 2004, all remaining jet fuel (kerosene-type and naphtha-type) is assigned to the transportation sector. Beginning in 2005, kerosene-type jet fuel is assigned to the transportation sector, while naphtha-type jet fuel is classified under "Other Petroleum Products," which is assigned to the industrial sector. (Note: Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft.)

### ***Kerosene***

Kerosene product supplied is allocated to the individual end-use sectors (residential, commercial, and industrial) in proportion to each sector's share of sales as reported in EIA's *Fuel Oil and Kerosene Sales (Sales)* report series (DOE/EIA-0535), which is based primarily on data collected by Form EIA-821, "Annual Fuel Oil and Kerosene Sales Report" (previously Form EIA-172).

Beginning in 1979, the residential sector sales total is directly from the Sales reports. Through 1978, each year's sales category called "heating" is allocated to the residential, commercial, and industrial sectors in proportion to the 1979 shares.

Beginning in 1979, the commercial sector sales total is directly from the Sales reports. Through 1978, each year's sales category called "heating" is allocated to the residential, commercial, and industrial sectors in proportion to the 1979 shares.

Beginning in 1979, the industrial sector sales total is the sum of the sales for industrial, farm, and all other uses. Through 1978, each year's sales category called "heating" is allocated to the residential, commercial and industrial sectors in proportion to the 1979 shares, and the estimated industrial (including farm) portion is added to all other uses.

### ***Lubricants***

1973–2009: The consumption of lubricants is allocated to the industrial and transportation sectors for all months according to proportions developed from annual sales of lubricants to the two sectors from U.S. Department of Commerce, U.S. Census Bureau, *Current Industrial Reports*, "Sales of Lubricating and Industrial Oils and Greases." The 1973 shares are applied to 1973 and 1974; the 1975 shares are applied to 1975 and 1976; and the 1977 shares are applied to 1977 through 2009.

2010 forward: The consumption of lubricants in the industrial sector is estimated by EIA based on Kline & Company data on finished lubricant demand for industrial (less marine and railroad) use. The consumption of lubricants in the transportation sector is estimated by EIA based on Kline & Company data on finished lubricant demand for consumer total, commercial total, marine, and railroad use. Estimates for lubricant consumption from 2010 forward are not compatible with data before 2010.

### ***Motor Gasoline***

The total monthly consumption of motor gasoline is allocated to the sectors in proportion to aggregations of annual sales categories created on the basis of the U.S. Department of Transportation, Federal Highway Administration, *Highway Statistics*, Tables MF-21, MF-24, and MF-25, as follows:

Through 2014, commercial sales are the sum of sales for public non-highway use and miscellaneous use. Beginning in 2015, commercial sales are the sum of sales for public non-highway use, lawn and garden use, and miscellaneous use.

For all years, industrial sales are the sum of sales for agriculture, construction, and "industrial and commercial" use (as classified in the *Highway Statistics*).

Through 2014, transportation sales are the sum of sales for highway use (minus the sales of special fuels, which are primarily diesel fuel and are accounted for in the transportation sector of distillate fuel) and sales for marine use. Beginning in 2015, transportation sales are the sum of sales for highway use (minus the sales of special fuels, which are primarily diesel fuel and are accounted for in the transportation sector of distillate fuel) and sales for boating use and recreational vehicle use.

### ***Petroleum Coke***

Portions of petroleum coke are consumed by the electric power sector (see sources for Table 7.4b) and the commercial sector (see sources for Table 7.4c). The remaining petroleum coke is assigned to the industrial sector.

### ***Residual Fuel Oil***

Residual fuel oil consumption is assigned to the sectors as follows:

#### ***Residual Fuel Oil, Electric Power Sector***

See sources for Table 7.4b. For 1973–1979, electric utility consumption of residual fuel oil is assumed to be the amount of petroleum consumed in steam-electric power plants. For 1980–2000, electric utility consumption of residual fuel oil is assumed to be the amount of heavy oil (fuel oil nos. 4, 5, and 6) consumed.

#### ***Residual Fuel Oil, End-Use Sectors, Annual Data***

The aggregate end-use amount is total residual fuel oil product supplied minus the amount consumed by the electric power sector. The end-use total consumed annually is allocated to the individual end-use sectors (commercial, industrial, and transportation) in proportion to each sector's share of sales as reported in EIA's *Fuel Oil and Kerosene Sales (Sales)* report series (DOE/EIA-535), which is based primarily on data collected by Form EIA-821, "Annual Fuel Oil and Kerosene Sales Report" (previously Form EIA-172). Shares for the current year are based on the most recent Sales report.

Following are notes on the individual sector groupings:

Beginning in 1979, commercial sales data are directly from the Sales reports. Through 1978, each year's sales subtotal of the heating plus industrial category is allocated to the commercial and industrial sectors in proportion to the 1979 shares.

Beginning in 1979, industrial sales data are the sum of sales for industrial, oil company, and all other uses. Through 1978, each year's sales subtotal of the heating plus industrial category is allocated to the commercial and industrial sectors in proportion to the 1979 shares, and the estimated industrial portion is added to oil company and all other uses.

Transportation sales are the sum of sales for railroad, vessel bunkering, and military uses for all years.

#### ***Residual Fuel Oil, End-Use Sectors, Monthly Data***

Commercial sector monthly consumption is estimated by allocating the annual estimates, which are described above, into the months in proportion to each month's share of the year's sales of No. 2 heating oil. (For each month of the current year, the consumption increase from the same month in the previous year is based on the percent increase in that month's No. 2 heating oil sales from the same month in the previous year.) The years' No. 2 heating oil sales totals are from the following sources: for 1973–1980, the Ethyl Corporation, *Monthly Report of Heating Oil Sales*; for 1981 and 1982, the American Petroleum Institute, *Monthly Report of Heating Oil Sales*; and for 1983 forward, EIA, Form EIA-782A, "Refiners'/Gas Plant Operators' Monthly Petroleum Product Sales Report," No. 2 Fuel Oil Sales to End Users and for Resale.

A residual fuel oil "balance" is calculated as total residual fuel oil product supplied minus the amount consumed by the electric power sector, commercial sector, and by industrial combined-heat-and-power plants (see sources for Table 7.4c).

Transportation sector monthly consumption is estimated by multiplying each month's residual fuel oil "balance" by the annual transportation consumption share of the annual residual fuel oil "balance."

Total industrial sector monthly consumption is estimated as total residual fuel oil product supplied minus the amount consumed by the commercial, transportation, and electric power sectors.

### *Other Petroleum Products*

Consumption of all remaining petroleum products is assigned to the industrial sector. Other petroleum products include petrochemical feedstocks, special naphthas, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

## **Table 3.8a Sources**

### *Distillate Fuel Oil*

Residential and commercial sector consumption data in thousand barrels per day for distillate fuel oil are from Table 3.7a, and are converted to trillion Btu by multiplying by the distillate fuel oil heat content factors in Table A3.

### *Hydrocarbon Gas Liquids (HGL)—Propane*

Residential and commercial sector consumption data in thousand barrels per day for propane are from Table 3.7a, and are converted to trillion Btu by multiplying by the propane heat content factor in Table A1. The residential and commercial sector total HGL consumption values are equal to the propane consumption values for those sectors.

### *Kerosene*

Residential and commercial sector consumption data in thousand barrels per day for kerosene are from Table 3.7a, and are converted to trillion Btu by multiplying by the kerosene heat content factor in Table A1.

### *Motor Gasoline*

Commercial sector consumption data in thousand barrels per day for motor gasoline are from Table 3.7a, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

### *Petroleum Coke*

1949–2003: Commercial sector consumption data in thousand barrels per day for petroleum coke are from Table 3.7a, and are converted to trillion Btu by multiplying by the total petroleum coke heat content factor in Table A1.

2004 forward: Commercial sector consumption data in thousand barrels per day for petroleum coke are from Table 3.7a, and are converted to trillion Btu by multiplying by the marketable petroleum coke heat content factor in Table A1.

### *Residual Fuel Oil*

Commercial sector consumption data in thousand barrels per day for residual fuel oil are from Table 3.7a, and are converted to trillion Btu by multiplying by the residual fuel oil heat content factor in Table A1.

### *Total Petroleum*

Residential sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under "Residential Sector" in Table 3.8a. Commercial sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under "Commercial Sector" in Table 3.8a.

## **Table 3.8b Sources**

### *Asphalt and Road Oil*

Industrial sector consumption data in thousand barrels per day for asphalt and road oil are from Table 3.7b, and are converted to trillion Btu by multiplying by the asphalt and road oil heat content factor in Table A1.

### ***Distillate Fuel Oil***

Industrial sector consumption data in thousand barrels per day for distillate fuel oil are from Table 3.7b, and are converted to trillion Btu by multiplying by the distillate fuel oil heat content factors in Table A3.

### ***Hydrocarbon Gas Liquids (HGL)—Propane***

Industrial sector propane consumption data are calculated by subtracting propane consumption data in trillion Btu for the residential (Table 3.8a), commercial (Table 3.8a), and transportation (Table 3.8c) sectors from total propane consumption (see sources for Table 3.6).

### ***Hydrocarbon Gas Liquids (HGL)—Propylene***

Product supplied data in thousand barrels per day for propylene are from Table 3.5, and are converted to trillion Btu by multiplying by the propylene heat content factor in Table A1.

### ***Hydrocarbon Gas Liquids (HGL)—Propane/Propylene Total***

Total industrial sector propane/propylene consumption is the sum of the data in trillion Btu for propane and propylene.

### ***Hydrocarbon Gas Liquids (HGL)—Total***

Industrial sector consumption data for HGL are calculated by subtracting HGL consumption data in trillion Btu for the residential (Table 3.8a), commercial (Table 3.8a), and transportation (Table 3.8c) sectors from total HGL consumption (Table 3.6).

### ***Kerosene***

Industrial sector consumption data in thousand barrels per day for kerosene are from Table 3.7b, and are converted to trillion Btu by multiplying by the kerosene heat content factor in Table A1.

### ***Lubricants***

Industrial sector consumption data in thousand barrels per day for lubricants are from Table 3.7b, and are converted to trillion Btu by multiplying by the lubricants heat content factor in Table A1.

### ***Motor Gasoline***

Industrial sector consumption data in thousand barrels per day for motor gasoline are from Table 3.7b, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

### ***Other Petroleum Products***

Industrial sector "Other" petroleum data are equal to the "Other" petroleum data in Table 3.6.

### ***Petroleum Coke***

1949–2003: Industrial sector consumption data in thousand barrels per day for petroleum coke are from Table 3.7b, and are converted to trillion Btu by multiplying by the total petroleum coke heat content factor in Table A1.

2004 forward: Industrial sector consumption data for petroleum coke are calculated by subtracting petroleum coke consumption data in trillion Btu for the commercial (Table 3.8a) and electric power (Table 3.8c) sectors from total petroleum coke consumption (Table 3.6).

### ***Residual Fuel Oil***

Industrial sector consumption data in thousand barrels per day for residual fuel oil are from Table 3.7b, and are converted to trillion Btu by multiplying by the residual fuel oil heat content factor in Table A1.

### ***Total Petroleum***

Industrial sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown in Table 3.8b.



## Table 3.8c Sources

### *Aviation Gasoline*

Transportation sector consumption data in thousand barrels per day for aviation gasoline are from Table 3.7c, and are converted to trillion Btu by multiplying by the aviation gasoline (finished) heat content factor in Table A1.

### *Distillate Fuel Oil, Electric Power Sector*

Electric power sector consumption data in thousand barrels per day for distillate fuel oil are from Table 3.7c, and are converted to trillion Btu by multiplying by the distillate fuel oil heat content factors in Table A3.

### *Distillate Fuel Oil, Transportation Sector*

1949–2008: Transportation sector consumption data in thousand barrels per day for distillate fuel oil are from Table 3.7c, and are converted to trillion Btu by multiplying by the distillate fuel oil heat content factors in Table A3.

2009–2011: Consumption data for biodiesel are calculated using biodiesel data from U.S. Energy Information Administration (EIA), EIA-22M, “Monthly Biodiesel Production Survey”; and biomass-based diesel fuel data from EIA-810, “Monthly Refinery Report,” EIA-812, “Monthly Product Pipeline Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1). Consumption data for other renewable diesel fuel are set equal to refinery and blender net inputs data from EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Transportation sector distillate fuel oil consumption data from Table 3.7c, minus consumption data for biodiesel and other renewable diesel fuel, are converted to Btu by multiplying by the distillate fuel heat content factors in Table A3. Total transportation sector distillate fuel oil consumption is the sum of the values for distillate fuel oil (excluding biodiesel and other renewable diesel fuel), biodiesel, and other renewable diesel fuel.

2012 forward: Consumption data for biodiesel are from Table 10.4. Consumption data for other renewable diesel fuel are set equal to refinery and blender net inputs data from EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Transportation sector distillate fuel oil consumption data from Table 3.7c, minus consumption data for biodiesel and other renewable diesel fuel, are converted to Btu by multiplying by the distillate fuel oil heat content factors in Table A3. Total transportation sector distillate fuel oil consumption is the sum of the values for distillate fuel oil (excluding biodiesel and other renewable diesel fuel), biodiesel, and other renewable diesel fuel.

### *Hydrocarbon Gas Liquids (HGL)—Propane*

Transportation sector consumption data in thousand barrels per day for propane are from Table 3.7c, and are converted to trillion Btu by multiplying by the propane heat content factor in Table A1. The transportation sector total HGL consumption values are equal to the transportation sector propane consumption values.

### *Jet Fuel*

Transportation sector consumption data in thousand barrels per day for kerosene-type jet fuel and, through 2004, naphtha-type jet fuel (see sources for Table 3.7c) are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1. Total transportation sector jet fuel consumption is the sum of the data in trillion Btu for kerosene-type and naphtha-type jet fuel. (Note: Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term “petroleum consumption” in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft.)

### *Lubricants*

Transportation sector consumption data in thousand barrels per day for lubricants are from Table 3.7c, and are converted to trillion Btu by multiplying by the lubricants heat content factor in Table A1.

### ***Motor Gasoline***

Transportation sector consumption data in thousand barrels per day for motor gasoline are from Table 3.7c, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

### ***Petroleum Coke***

1949–2003: Electric power sector consumption data in thousand barrels per day for petroleum coke are from Table 3.7c, and are converted to trillion Btu by multiplying by the total petroleum coke heat content factor in Table A1.

2004 forward: Electric power sector consumption data in thousand barrels per day for petroleum coke are from Table 3.7c, and are converted to trillion Btu by multiplying by the marketable petroleum coke heat content factor in Table A1.

### ***Residual Fuel Oil***

Transportation and electric power consumption data in thousand barrels per day for residual fuel oil are from Table 3.7c, and are converted to trillion Btu by multiplying by the residual fuel oil heat content factor in Table A1.

### ***Total Petroleum***


Transportation sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under "Transportation Sector" in Table 3.8c. Electric power sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under "Electric Power Sector" in Table 3.8c.

## 4. Natural Gas


---

**Figure 4.1 Natural Gas**  
(Trillion Cubic Feet)


Overview, 1949–2019




Consumption by Sector, 1949–2019



Overview, Monthly



Consumption by Sector, Monthly



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#naturalgas>.  
Sources: Tables 4.1 and 4.3.

**Table 4.1 Natural Gas Overview**  
(Billion Cubic Feet)

	Gross Withdrawals <sup>a</sup>	Marketed Production (Wet) <sup>b</sup>	NGPL Production <sup>c</sup>	Dry Gas Production <sup>d</sup>	Supplemental Gaseous Fuels <sup>e</sup>	Trade			Net Storage Withdrawals <sup>f</sup>	Balancing Item <sup>g</sup>	Consumption <sup>h</sup>
						Imports	Exports	Net Imports			
<b>1950 Total</b> .....	<b>8,480</b>	<b>6,282</b>	<b>260</b>	<b>6,022</b>	<b>NA</b>	<b>0</b>	<b>26</b>	<b>-26</b>	<b>-54</b>	<b>-175</b>	<b>5,767</b>
<b>1955 Total</b> .....	<b>11,720</b>	<b>9,405</b>	<b>377</b>	<b>9,029</b>	<b>NA</b>	<b>11</b>	<b>31</b>	<b>-20</b>	<b>-68</b>	<b>-247</b>	<b>8,694</b>
<b>1960 Total</b> .....	<b>15,088</b>	<b>12,771</b>	<b>543</b>	<b>12,228</b>	<b>NA</b>	<b>156</b>	<b>11</b>	<b>144</b>	<b>-132</b>	<b>-274</b>	<b>11,967</b>
<b>1965 Total</b> .....	<b>17,963</b>	<b>16,040</b>	<b>753</b>	<b>15,286</b>	<b>NA</b>	<b>456</b>	<b>26</b>	<b>430</b>	<b>-118</b>	<b>-319</b>	<b>15,280</b>
<b>1970 Total</b> .....	<b>23,786</b>	<b>21,921</b>	<b>906</b>	<b>21,014</b>	<b>NA</b>	<b>821</b>	<b>70</b>	<b>751</b>	<b>-398</b>	<b>-228</b>	<b>21,139</b>
<b>1975 Total</b> .....	<b>21,104</b>	<b>20,109</b>	<b>872</b>	<b>19,236</b>	<b>NA</b>	<b>953</b>	<b>73</b>	<b>880</b>	<b>-344</b>	<b>-235</b>	<b>19,538</b>
<b>1980 Total</b> .....	<b>21,870</b>	<b>20,180</b>	<b>777</b>	<b>19,403</b>	<b>155</b>	<b>985</b>	<b>49</b>	<b>936</b>	<b>23</b>	<b>-640</b>	<b>19,877</b>
<b>1985 Total</b> .....	<b>19,607</b>	<b>17,270</b>	<b>816</b>	<b>16,454</b>	<b>126</b>	<b>950</b>	<b>55</b>	<b>894</b>	<b>235</b>	<b>-428</b>	<b>17,281</b>
<b>1990 Total</b> .....	<b>21,523</b>	<b>18,594</b>	<b>784</b>	<b>17,810</b>	<b>123</b>	<b>1,532</b>	<b>86</b>	<b>1,447</b>	<b>-513</b>	<b>307</b>	<b>19,174</b>
<b>1995 Total</b> .....	<b>23,744</b>	<b>19,506</b>	<b>908</b>	<b>18,599</b>	<b>110</b>	<b>2,841</b>	<b>154</b>	<b>2,687</b>	<b>415</b>	<b>396</b>	<b>22,207</b>
<b>2000 Total</b> .....	<b>24,174</b>	<b>20,198</b>	<b>1,016</b>	<b>19,182</b>	<b>90</b>	<b>3,782</b>	<b>244</b>	<b>3,538</b>	<b>829</b>	<b>-306</b>	<b>23,333</b>
<b>2001 Total</b> .....	<b>24,501</b>	<b>20,570</b>	<b>954</b>	<b>19,616</b>	<b>86</b>	<b>3,977</b>	<b>373</b>	<b>3,604</b>	<b>-1,166</b>	<b>99</b>	<b>22,239</b>
<b>2002 Total</b> .....	<b>23,941</b>	<b>19,885</b>	<b>957</b>	<b>18,928</b>	<b>68</b>	<b>4,015</b>	<b>516</b>	<b>3,499</b>	<b>467</b>	<b>65</b>	<b>23,027</b>
<b>2003 Total</b> .....	<b>24,119</b>	<b>19,974</b>	<b>876</b>	<b>19,099</b>	<b>68</b>	<b>3,944</b>	<b>680</b>	<b>3,264</b>	<b>-197</b>	<b>44</b>	<b>22,277</b>
<b>2004 Total</b> .....	<b>23,970</b>	<b>19,517</b>	<b>927</b>	<b>18,591</b>	<b>60</b>	<b>4,259</b>	<b>854</b>	<b>3,404</b>	<b>-114</b>	<b>461</b>	<b>22,403</b>
<b>2005 Total</b> .....	<b>23,457</b>	<b>18,927</b>	<b>876</b>	<b>18,051</b>	<b>64</b>	<b>4,341</b>	<b>729</b>	<b>3,612</b>	<b>52</b>	<b>236</b>	<b>22,014</b>
<b>2006 Total</b> .....	<b>23,535</b>	<b>19,410</b>	<b>906</b>	<b>18,504</b>	<b>66</b>	<b>4,186</b>	<b>724</b>	<b>3,462</b>	<b>-436</b>	<b>103</b>	<b>21,699</b>
<b>2007 Total</b> .....	<b>24,664</b>	<b>20,196</b>	<b>930</b>	<b>19,266</b>	<b>63</b>	<b>4,608</b>	<b>822</b>	<b>3,785</b>	<b>192</b>	<b>-203</b>	<b>23,104</b>
<b>2008 Total</b> .....	<b>25,636</b>	<b>21,112</b>	<b>953</b>	<b>20,159</b>	<b>61</b>	<b>3,984</b>	<b>963</b>	<b>3,021</b>	<b>34</b>	<b>2</b>	<b>23,277</b>
<b>2009 Total</b> .....	<b>26,057</b>	<b>21,648</b>	<b>1,024</b>	<b>20,624</b>	<b>65</b>	<b>3,751</b>	<b>1,072</b>	<b>2,679</b>	<b>-355</b>	<b>-103</b>	<b>22,910</b>
<b>2010 Total</b> .....	<b>26,816</b>	<b>22,382</b>	<b>1,066</b>	<b>21,316</b>	<b>65</b>	<b>3,741</b>	<b>1,137</b>	<b>2,604</b>	<b>-13</b>	<b>115</b>	<b>24,087</b>
<b>2011 Total</b> .....	<b>28,479</b>	<b>24,036</b>	<b>1,134</b>	<b>22,902</b>	<b>60</b>	<b>3,469</b>	<b>1,506</b>	<b>1,963</b>	<b>-354</b>	<b>-94</b>	<b>24,477</b>
<b>2012 Total</b> .....	<b>29,542</b>	<b>25,283</b>	<b>1,250</b>	<b>24,033</b>	<b>61</b>	<b>3,138</b>	<b>1,619</b>	<b>1,519</b>	<b>-9</b>	<b>-66</b>	<b>25,538</b>
<b>2013 Total</b> .....	<b>29,523</b>	<b>25,562</b>	<b>1,357</b>	<b>24,206</b>	<b>55</b>	<b>2,883</b>	<b>1,572</b>	<b>1,311</b>	<b>546</b>	<b>38</b>	<b>26,155</b>
<b>2014 Total</b> .....	<b>31,405</b>	<b>27,498</b>	<b>1,608</b>	<b>25,890</b>	<b>60</b>	<b>2,695</b>	<b>1,514</b>	<b>1,181</b>	<b>-254</b>	<b>-283</b>	<b>26,593</b>
<b>2015 Total</b> .....	<b>32,915</b>	<b>28,772</b>	<b>1,707</b>	<b>27,065</b>	<b>59</b>	<b>2,718</b>	<b>1,784</b>	<b>935</b>	<b>-547</b>	<b>-268</b>	<b>27,244</b>
<b>2016 Total</b> .....	<b>32,592</b>	<b>28,400</b>	<b>1,808</b>	<b>26,592</b>	<b>57</b>	<b>3,006</b>	<b>2,335</b>	<b>671</b>	<b>340</b>	<b>-216</b>	<b>27,444</b>
<b>2017 Total</b> .....	<b>33,292</b>	<b>29,204</b>	<b>1,897</b>	<b>27,306</b>	<b>66</b>	<b>3,033</b>	<b>3,154</b>	<b>-121</b>	<b>254</b>	<b>-360</b>	<b>27,146</b>
<b>2018 January</b> .....	<b>2,993</b>	<b>2,618</b>	<b>177</b>	<b>2,441</b>	<b>6</b>	<b>300</b>	<b>300</b>	<b>(s)</b>	<b>913</b>	<b>-19</b>	<b>3,341</b>
<b>February</b> .....	<b>2,751</b>	<b>2,414</b>	<b>163</b>	<b>2,251</b>	<b>5</b>	<b>237</b>	<b>276</b>	<b>-38</b>	<b>477</b>	<b>16</b>	<b>2,711</b>
<b>March</b> .....	<b>3,069</b>	<b>2,704</b>	<b>183</b>	<b>2,521</b>	<b>6</b>	<b>271</b>	<b>291</b>	<b>-21</b>	<b>293</b>	<b>-2</b>	<b>2,797</b>
<b>April</b> .....	<b>2,976</b>	<b>2,613</b>	<b>177</b>	<b>2,436</b>	<b>5</b>	<b>242</b>	<b>279</b>	<b>-37</b>	<b>-37</b>	<b>-17</b>	<b>2,351</b>
<b>May</b> .....	<b>3,099</b>	<b>2,731</b>	<b>185</b>	<b>2,546</b>	<b>6</b>	<b>227</b>	<b>272</b>	<b>-45</b>	<b>-433</b>	<b>-18</b>	<b>2,055</b>
<b>June</b> .....	<b>2,973</b>	<b>2,656</b>	<b>180</b>	<b>2,476</b>	<b>6</b>	<b>228</b>	<b>262</b>	<b>-34</b>	<b>-358</b>	<b>-27</b>	<b>2,063</b>
<b>July</b> .....	<b>3,138</b>	<b>2,799</b>	<b>189</b>	<b>2,610</b>	<b>6</b>	<b>247</b>	<b>306</b>	<b>-59</b>	<b>-194</b>	<b>-12</b>	<b>2,351</b>
<b>August</b> .....	<b>3,206</b>	<b>2,856</b>	<b>193</b>	<b>2,662</b>	<b>6</b>	<b>237</b>	<b>311</b>	<b>-74</b>	<b>-244</b>	<b>-36</b>	<b>2,314</b>
<b>September</b> .....	<b>3,154</b>	<b>2,809</b>	<b>190</b>	<b>2,619</b>	<b>6</b>	<b>214</b>	<b>302</b>	<b>-88</b>	<b>-344</b>	<b>-37</b>	<b>2,156</b>
<b>October</b> .....	<b>3,315</b>	<b>2,939</b>	<b>199</b>	<b>2,740</b>	<b>6</b>	<b>215</b>	<b>307</b>	<b>-92</b>	<b>-299</b>	<b>-70</b>	<b>2,286</b>
<b>November</b> .....	<b>3,260</b>	<b>2,894</b>	<b>196</b>	<b>2,698</b>	<b>6</b>	<b>212</b>	<b>338</b>	<b>-125</b>	<b>212</b>	<b>-75</b>	<b>2,716</b>
<b>December</b> .....	<b>3,391</b>	<b>2,976</b>	<b>201</b>	<b>2,774</b>	<b>6</b>	<b>257</b>	<b>364</b>	<b>-107</b>	<b>329</b>	<b>-3</b>	<b>3,000</b>
<b>Total</b> .....	<b>37,326</b>	<b>33,009</b>	<b>2,235</b>	<b>30,774</b>	<b>69</b>	<b>2,889</b>	<b>3,608</b>	<b>-719</b>	<b>314</b>	<b>-299</b>	<b>30,140</b>
<b>2019 January</b> .....	<b>3,385</b>	<b>2,981</b>	<b>208</b>	<b>2,773</b>	<b>5</b>	<b>291</b>	<b>365</b>	<b>-74</b>	<b>730</b>	<b>-17</b>	<b>3,417</b>
<b>February</b> .....	<b>3,067</b>	<b>2,709</b>	<b>189</b>	<b>2,520</b>	<b>5</b>	<b>233</b>	<b>330</b>	<b>-97</b>	<b>586</b>	<b>-1</b>	<b>3,013</b>
<b>March</b> .....	<b>3,396</b>	<b>3,019</b>	<b>211</b>	<b>2,809</b>	<b>5</b>	<b>253</b>	<b>374</b>	<b>-121</b>	<b>257</b>	<b>-28</b>	<b>2,922</b>
<b>April</b> .....	<b>3,329</b>	<b>2,934</b>	<b>205</b>	<b>2,729</b>	<b>5</b>	<b>207</b>	<b>338</b>	<b>-132</b>	<b>-401</b>	<b>8</b>	<b>2,209</b>
<b>May</b> .....	<b>3,432</b>	<b>3,055</b>	<b>213</b>	<b>2,842</b>	<b>5</b>	<b>208</b>	<b>369</b>	<b>-161</b>	<b>-494</b>	<b>-62</b>	<b>2,131</b>
<b>June</b> .....	<b>3,317</b>	<b>2,969</b>	<b>207</b>	<b>2,761</b>	<b>5</b>	<b>201</b>	<b>360</b>	<b>-159</b>	<b>-452</b>	<b>-39</b>	<b>2,117</b>
<b>July</b> .....	<b>3,412</b>	<b>3,084</b>	<b>215</b>	<b>2,869</b>	<b>5</b>	<b>230</b>	<b>393</b>	<b>-163</b>	<b>-270</b>	<b>-50</b>	<b>2,391</b>
<b>August</b> .....	<b>3,467</b>	<b>3,159</b>	<b>220</b>	<b>2,939</b>	<b>5</b>	<b>220</b>	<b>385</b>	<b>-165</b>	<b>-303</b>	<b>-46</b>	<b>2,430</b>
<b>September</b> .....	<b>3,399</b>	<b>3,054</b>	<b>213</b>	<b>2,841</b>	<b>5</b>	<b>208</b>	<b>395</b>	<b>-186</b>	<b>-440</b>	<b>-17</b>	<b>2,203</b>
<b>October</b> .....	<b>3,571</b>	<b>3,200</b>	<b>223</b>	<b>2,977</b>	<b>5</b>	<b>211</b>	<b>426</b>	<b>-215</b>	<b>-364</b>	<b>-98</b>	<b>2,305</b>
<b>November</b> .....	<b>3,496</b>	<b>3,120</b>	<b>218</b>	<b>2,902</b>	<b>5</b>	<b>224</b>	<b>441</b>	<b>-218</b>	<b>159</b>	<b>-71</b>	<b>2,778</b>
<b>December</b> .....	<b>3,621</b>	<b>3,232</b>	<b>226</b>	<b>3,007</b>	<b>5</b>	<b>256</b>	<b>481</b>	<b>-225</b>	<b>453</b>	<b>-58</b>	<b>3,163</b>
<b>Total</b> .....	<b>40,892</b>	<b>36,515</b>	<b>2,548</b>	<b>33,968</b>	<b>62</b>	<b>2,742</b>	<b>4,656</b>	<b>-1,915</b>	<b>-438</b>	<b>-478</b>	<b>31,079</b>
<b>2020 January</b> .....	<b>E 3,590</b>	<b>E 3,182</b>	<b>234</b>	<b>E 2,948</b>	<b>6</b>	<b>262</b>	<b>510</b>	<b>-248</b>	<b>571</b>	<b>20</b>	<b>3,296</b>
<b>February</b> .....	<b>E 3,342</b>	<b>E 2,959</b>	<b>212</b>	<b>E 2,747</b>	<b>6</b>	<b>238</b>	<b>454</b>	<b>-216</b>	<b>535</b>	<b>-40</b>	<b>3,033</b>
<b>March</b> .....	<b>E 3,561</b>	<b>E 3,166</b>	<b>235</b>	<b>E 2,931</b>	<b>6</b>	<b>217</b>	<b>497</b>	<b>-280</b>	<b>49</b>	<b>3</b>	<b>2,708</b>
<b>April</b> .....	<b>E 3,372</b>	<b>E 3,002</b>	<b>214</b>	<b>E 2,788</b>	<b>6</b>	<b>193</b>	<b>421</b>	<b>-227</b>	<b>-306</b>	<b>-15</b>	<b>2,245</b>
<b>May</b> .....	<b>E 3,298</b>	<b>E 2,934</b>	<b>212</b>	<b>E 2,722</b>	<b>5</b>	<b>189</b>	<b>395</b>	<b>-206</b>	<b>-448</b>	<b>-2</b>	<b>2,071</b>
<b>June</b> .....	<b>E 3,225</b>	<b>E 2,876</b>	<b>226</b>	<b>E 2,650</b>	<b>5</b>	<b>190</b>	<b>338</b>	<b>-149</b>	<b>-358</b>	<b>-14</b>	<b>2,135</b>
<b>July</b> .....	<b>E 3,383</b>	<b>E 3,023</b>	<b>241</b>	<b>E 2,783</b>	<b>6</b>	<b>213</b>	<b>349</b>	<b>-136</b>	<b>-161</b>	<b>3</b>	<b>2,494</b>
<b>August</b> .....	<b>E 3,388</b>	<b>E 3,037</b>	<b>R 240</b>	<b>RE 2,797</b>	<b>4</b>	<b>214</b>	<b>359</b>	<b>-145</b>	<b>-227</b>	<b>R -22</b>	<b>2,407</b>
<b>September</b> .....	<b>RE 3,273</b>	<b>RE 2,914</b>	<b>230</b>	<b>RE 2,684</b>	<b>4</b>	<b>174</b>	<b>395</b>	<b>-220</b>	<b>-323</b>	<b>R 29</b>	<b>2,174</b>
<b>October</b> .....	<b>RE 3,380</b>	<b>E 2,996</b>	<b>238</b>	<b>E 2,758</b>	<b>5</b>	<b>202</b>	<b>R 481</b>	<b>R -279</b>	<b>-92</b>	<b>R -62</b>	<b>2,329</b>
<b>November</b> .....	<b>E 3,368</b>	<b>E 2,988</b>	<b>231</b>	<b>E 2,757</b>	<b>5</b>	<b>216</b>	<b>527</b>	<b>-311</b>	<b>-4</b>	<b>-2</b>	<b>2,446</b>
<b>11-Month Total</b> .....	<b>E 37,181</b>	<b>E 33,077</b>	<b>2,512</b>	<b>E 30,565</b>	<b>58</b>	<b>2,309</b>	<b>4,727</b>	<b>-2,418</b>	<b>-765</b>	<b>-102</b>	<b>27,338</b>
<b>2019 11-Month Total</b> .....	<b>37,272</b>	<b>33,283</b>	<b>2,322</b>	<b>30,961</b>	<b>56</b>	<b>2,486</b>	<b>4,175</b>	<b>-1,690</b>	<b>-991</b>	<b>-420</b>	<b>27,916</b>
<b>2018 11-Month Total</b> .....	<b>33,934</b>	<b>30,033</b>	<b>2,033</b>	<b>28,000</b>	<b>63</b>	<b>2,632</b>	<b>3,244</b>	<b>-612</b>	<b>-15</b>	<b>-295</b>	<b>27,141</b>

<sup>a</sup> Gases withdrawn from natural gas, crude oil, coalbed, and shale gas wells. Includes natural gas, natural gas plant liquids, and nonhydrocarbon gases; but excludes lease condensate.

<sup>b</sup> Gross withdrawals minus repressuring, nonhydrocarbon gases removed, and vented and flared. See Note 1, "Natural Gas Production," at end of section.

<sup>c</sup> Natural gas plant liquids (NGPL) production, gaseous equivalent. This data series was previously called "Extraction Loss." See Note 2, "Natural Gas Plant Liquids Production," at end of section.

<sup>d</sup> Marketed production (wet) minus NGPL production.

<sup>e</sup> See Note 3, "Supplemental Gaseous Fuels," at end of section.

<sup>f</sup> Net withdrawals from underground storage. For 1980–2017, also includes net withdrawals of liquefied natural gas in above-ground tanks. See Note 4, "Natural Gas Storage," at end of section.

<sup>g</sup> See Note 5, "Natural Gas Balancing Item," at end of section. Beginning in 1980, excludes transit shipments that cross the U.S.-Canada border (i.e., natural gas delivered to its destination via the other country).

<sup>h</sup> See Note 6, "Natural Gas Consumption," at end of section.

<sup>i</sup> Through 1979, may include unknown quantities of nonhydrocarbon gases.

<sup>j</sup> For 1989–1992, a small amount of consumption at independent power producers may be counted in both "Other Industrial" and "Electric Power Sector" on

Table 4.3. See Note 7, "Natural Gas Consumption, 1989–1992," at end of section. R=Revised. E=Estimate. (s)=Less than 0.5 billion cubic feet and greater than -0.5 billion cubic feet. NA=Not available.

Notes: • See Note 8, "Natural Gas Data Adjustments, 1993–2000," at end of section. • Through 1964, all volumes are shown on a pressure base of 14.65 psia (pounds per square inch absolute) at 60° Fahrenheit; beginning in 1965, the pressure

**Table 4.2 Natural Gas Trade by Country**  
(Billion Cubic Feet)

	Imports									Exports <sup>a</sup>				
	Algeria <sup>b</sup>	Canada <sup>c</sup>	Egypt <sup>b</sup>	Mexico <sup>c</sup>	Nigeria <sup>b</sup>	Qatar <sup>b</sup>	Trinidad and Tobago <sup>b</sup>	Other <sup>b,d</sup>	Total	Canada <sup>c</sup>	Japan <sup>b</sup>	Mexico <sup>c</sup>	Other <sup>b,e</sup>	Total
1950 Total .....	0	0	0	0	0	0	0	0	0	3	0	23	0	26
1955 Total .....	0	11	0	(s)	0	0	0	0	11	11	0	20	0	31
1960 Total .....	0	109	0	47	0	0	0	0	156	6	0	6	0	11
1965 Total .....	0	405	0	52	0	0	0	0	456	18	0	8	0	26
1970 Total .....	1	779	0	(s)	0	0	0	0	821	11	44	15	0	70
1975 Total .....	5	948	0	0	0	0	0	0	953	10	53	9	0	73
1980 Total .....	86	797	0	102	0	0	0	0	985	(s)	45	2	0	49
1985 Total .....	24	926	0	0	0	0	0	0	950	(s)	53	2	0	55
1990 Total .....	84	1,448	0	0	0	0	0	0	1,532	17	53	16	0	86
1995 Total .....	18	2,816	0	7	0	0	0	0	2,841	28	65	61	0	154
2000 Total .....	47	3,544	0	12	13	46	99	21	3,782	73	66	106	0	244
2001 Total .....	65	3,729	0	10	38	23	98	14	3,977	167	66	141	0	373
2002 Total .....	27	3,785	0	2	8	35	151	8	4,015	189	63	263	0	516
2003 Total .....	53	3,437	0	0	50	14	378	11	3,944	271	66	343	0	680
2004 Total .....	120	3,607	0	0	12	12	462	46	4,259	395	62	397	0	854
2005 Total .....	97	3,700	73	9	8	3	439	11	4,341	358	65	305	0	729
2006 Total .....	17	3,590	120	13	57	0	389	0	4,186	341	61	322	0	724
2007 Total .....	77	3,783	115	54	95	18	448	18	4,608	482	47	292	2	822
2008 Total .....	0	3,589	55	43	12	3	267	15	3,984	559	39	365	0	963
2009 Total .....	0	3,271	160	28	13	13	236	29	3,751	701	31	338	3	1,072
2010 Total .....	0	3,280	73	30	42	46	190	81	3,741	739	33	333	32	1,137
2011 Total .....	0	3,117	35	3	2	91	129	92	3,469	937	18	499	52	1,506
2012 Total .....	0	2,963	3	(s)	0	34	112	26	3,138	971	14	620	14	1,619
2013 Total .....	0	2,786	0	1	3	7	70	17	2,883	911	0	661	0	1,572
2014 Total .....	0	2,635	0	1	0	0	43	16	2,695	770	13	729	3	1,514
2015 Total .....	0	2,626	0	1	0	0	71	20	2,718	701	8	1,054	20	1,784
2016 Total .....	0	2,918	0	1	0	0	84	3	3,006	771	11	1,405	148	2,335
2017 Total .....	0	2,955	0	1	6	0	70	0	3,033	917	53	1,671	513	3,154
2018 January .....	0	283	0	(s)	0	0	14	3	300	91	4	147	58	300
February .....	0	230	0	1	0	0	7	0	237	76	7	140	52	276
March .....	0	264	0	(s)	0	0	4	3	271	68	0	161	63	291
April .....	0	239	0	(s)	0	0	3	0	242	63	11	142	64	279
May .....	0	225	0	(s)	0	0	2	0	227	40	13	151	68	272
June .....	0	226	0	(s)	0	0	3	0	228	51	10	164	37	262
July .....	0	241	0	1	0	0	5	0	247	57	13	172	64	306
August .....	0	231	0	1	0	0	5	0	237	66	10	175	60	311
September .....	0	211	0	(s)	0	0	3	0	214	70	17	161	54	302
October .....	0	209	0	(s)	0	0	6	0	215	65	3	159	80	307
November .....	0	210	0	(s)	0	0	3	0	212	90	24	147	77	338
December .....	0	242	0	(s)	3	0	12	0	257	100	14	152	98	364
Total .....	0	2,811	0	3	3	0	66	6	2,889	836	126	1,871	775	3,608
2019 January .....	0	276	0	(s)	0	0	12	3	291	87	17	165	95	365
February .....	0	226	0	(s)	0	0	7	0	233	92	10	142	86	330
March .....	0	249	0	(s)	0	0	3	0	253	93	7	157	117	374
April .....	0	204	0	(s)	0	0	3	0	207	71	14	150	102	338
May .....	0	208	0	(s)	0	0	0	0	208	70	7	174	117	369
June .....	0	201	0	(s)	0	0	0	0	201	62	15	173	110	360
July .....	0	228	0	(s)	0	0	3	0	230	69	21	192	111	393
August .....	0	217	0	(s)	0	0	0	0	220	78	18	182	107	385
September .....	0	208	0	(s)	0	0	0	0	208	72	28	173	122	395
October .....	0	205	0	(s)	0	0	6	0	211	76	25	178	147	426
November .....	0	221	0	(s)	0	0	3	0	224	92	18	162	170	441
December .....	0	245	0	1	3	0	7	0	256	109	21	161	189	481
Total .....	0	2,687	0	2	3	0	47	3	2,742	972	201	2,010	1,474	4,656
2020 January .....	0	249	0	(s)	2	0	9	3	262	99	32	168	211	510
February .....	0	232	0	(s)	0	0	6	0	238	77	21	154	201	454
March .....	0	214	0	(s)	0	0	3	(s)	217	87	22	174	215	497
April .....	0	190	0	(s)	0	0	3	0	193	72	18	139	192	421
May .....	0	187	0	(s)	0	0	3	0	189	68	14	145	169	395
June .....	0	185	0	(s)	3	0	2	0	190	67	22	163	87	338
July .....	0	209	0	(s)	0	0	4	0	213	72	11	181	86	349
August .....	0	211	0	(s)	0	0	3	0	214	61	23	189	86	359
September .....	0	173	0	(s)	0	0	1	0	174	62	7	185	141	395
October .....	0	202	0	(s)	0	0	0	0	202	R 73	32	193	184	R 481
November .....	0	213	0	(s)	0	0	3	(s)	216	80	33	169	245	527
11-Month Total ...	0	2,263	0	2	4	0	36	3	2,309	817	234	1,859	1,816	4,727
2019 11-Month Total ...	0	2,443	0	1	0	0	40	3	2,486	862	180	1,849	1,284	4,175
2018 11-Month Total ...	0	2,569	0	3	0	0	54	6	2,632	736	112	1,720	677	3,244

<sup>a</sup> Includes re-exports.  
<sup>b</sup> As liquefied natural gas.  
<sup>c</sup> By pipeline, except for small amounts of: liquefied natural gas (LNG) imported from Canada in 1973, 1977, 1981, and 2013 forward; LNG exported to Canada in 2007 and 2012 forward; compressed natural gas (CNG) imported from Canada in 2014 forward; CNG exported to Canada in 2013 forward; and LNG exported to Mexico beginning in 1998. See Note 9, "Natural Gas Imports and Exports," at end of section.  
<sup>d</sup> Australia in 1997–2001 and 2004; Brunei in 2002; Equatorial Guinea in 2007; Indonesia in 1986 and 2000; Malaysia in 1999 and 2002–2005; Norway in 2008–2016; Oman in 2000–2005; Peru in 2010 and 2011; United Arab Emirates in 1996–2000; United Kingdom in 2018; Yemen in 2010–2015; and Other (unassigned) in 2004–2015.  
<sup>e</sup> Argentina in 2016–2020; Bahamas in 2017–2020; Bangladesh 2019 and 2020; Barbados in 2016–2020; Belgium in 2019 and 2020; Brazil in 2010–2012, and 2014–2020; Chile in 2011, 2016–2020; China in 2011, 2016–2020; Colombia in 2018–2020; Dominican Republic in 2016–2020; Egypt in 2015–2018; France in 2018–2020; Greece in 2018–2020; Haiti 2019 and 2020; India in 2010–2012, 2016–2020; Israel 2018 and 2020; Italy in 2016–2020; Jamaica 2018–2020; Jordan in 2016–2020; Kuwait in 2016–2020; Lithuania in 2017 and 2019–2020; Malaysia in 2019; Malta in 2017–2020; Netherlands in 2017–2020; Pakistan in 2017–2020; Panama in 2018–2020; Poland in 2017–2020; Portugal in 2012, 2016–2020;

Russia in 2007; Singapore in 2018–2020; South Korea in 2009–2011, 2016–2020; Spain in 2010–2011, 2016–2020; Taiwan in 2015, 2017–2020; Thailand in 2017, 2019–2020; Turkey in 2015–2020; United Arab Emirates in 2016–2020; and United Kingdom in 2010, 2011, 2017–2020.  
R=Revised. (s)=Less than 500 million cubic feet.  
Notes: • See Note 9, "Natural Gas Imports and Exports," at end of section.  
• Through 1964, all volumes are shown on a pressure base of 14.65 psia (pounds per square inch absolute) at 60° Fahrenheit; beginning in 1965, the pressure base is 14.73 psia at 60° Fahrenheit. • Totals may not equal sum of components due to independent rounding. • U.S. geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
Sources: • 1949–1954: U.S. Energy Information Administration (EIA) estimates based on Bureau of Mines, Minerals Yearbook, "Natural Gas" chapter.  
• 1955–1971: Federal Power Commission data. • 1972–1987: EIA, Form FPC-14, "Annual Report for Importers and Exporters of Natural Gas."  
• 1988–2019: EIA, *Natural Gas Annual*, annual reports. • 2020 forward: EIA, *Natural Gas Monthly*, January 2021, Tables 4 and 5; and U.S. Department of Energy, Office of Fossil Energy, "Natural Gas Imports and Exports."

**Table 4.3 Natural Gas Consumption by Sector**  
(Billion Cubic Feet)

	End-Use Sectors										Electric Power Sector <sup>f,g</sup>	Total
	Residential	Commercial <sup>a</sup>	Industrial					Transportation				
			Lease and Plant Fuel	Other Industrial			Total	Pipelines <sup>d</sup> and Distribution <sup>e</sup>	Vehicle Fuel	Total		
				CHP <sup>b</sup>	Non-CHP <sup>c</sup>	Total						
1950 Total .....	1,198	388	928	(h)	2,498	2,498	3,426	126	NA	126	629	5,767
1955 Total .....	2,124	629	1,131	(h)	3,411	3,411	4,542	245	NA	245	1,153	8,694
1960 Total .....	3,103	1,020	1,237	(h)	4,535	4,535	5,771	347	NA	347	1,725	11,967
1965 Total .....	3,903	1,444	1,156	(h)	5,955	5,955	7,112	501	NA	501	2,321	15,280
1970 Total .....	4,837	2,399	1,399	(h)	7,851	7,851	9,249	722	NA	722	3,932	21,139
1975 Total .....	4,924	2,508	1,396	(h)	6,968	6,968	8,365	583	NA	583	3,158	19,538
1980 Total .....	4,752	2,611	1,026	(h)	7,172	7,172	8,198	635	NA	635	3,682	19,877
1985 Total .....	4,433	2,432	966	(h)	5,901	5,901	6,867	504	NA	504	3,044	17,281
1990 Total .....	4,391	2,623	1,236	1,055	5,963	7,018	8,255	660	(s)	660	3,245	19,174
1995 Total .....	4,850	3,031	1,220	1,258	6,906	8,164	9,384	700	5	705	4,237	22,207
2000 Total .....	4,996	3,182	1,151	1,386	6,757	8,142	9,293	642	13	655	5,206	23,333
2001 Total .....	4,771	3,023	1,119	1,310	6,035	7,344	8,463	625	15	640	5,342	22,239
2002 Total .....	4,889	3,144	1,113	1,240	6,287	7,527	8,640	667	15	682	5,672	23,027
2003 Total .....	5,079	3,179	1,122	1,144	6,007	7,150	8,273	591	18	610	5,135	22,277
2004 Total .....	4,869	3,129	1,098	1,191	6,066	7,256	8,354	566	21	587	5,464	22,403
2005 Total .....	4,827	2,999	1,112	1,084	5,518	6,601	7,713	584	23	607	5,869	22,014
2006 Total .....	4,368	2,832	1,142	1,115	5,412	6,527	7,669	584	24	608	6,222	21,699
2007 Total .....	4,722	3,013	1,226	1,050	5,604	6,655	7,881	621	25	646	6,841	23,104
2008 Total .....	4,892	3,153	1,220	955	5,715	6,670	7,890	648	26	674	6,668	23,277
2009 Total .....	4,779	3,119	1,275	990	5,178	6,167	7,443	670	27	697	6,873	22,910
2010 Total .....	4,782	3,103	1,286	1,029	5,797	6,826	8,112	674	29	703	7,387	24,087
2011 Total .....	4,714	3,155	1,323	1,063	5,931	6,994	8,317	688	30	718	7,574	24,477
2012 Total .....	4,150	2,895	1,396	1,149	6,077	7,226	8,622	731	30	761	9,111	25,538
2013 Total .....	4,897	3,295	1,483	1,170	6,255	7,425	8,909	833	30	863	8,191	26,155
2014 Total .....	5,087	3,466	1,512	1,145	6,501	7,646	9,158	700	35	735	8,146	26,593
2015 Total .....	4,613	3,202	1,576	1,222	6,300	7,522	9,098	678	39	718	9,613	27,244
2016 Total .....	4,347	3,110	1,545	1,209	6,519	7,729	9,274	687	42	729	9,985	27,444
2017 Total .....	4,412	3,164	1,584	1,257	6,693	7,949	9,533	722	48	770	9,266	27,146
2018 January .....	981	554	134	115	667	782	917	99	4	103	786	3,341
February .....	690	424	124	101	599	699	823	80	4	84	690	2,711
March .....	659	418	139	105	633	738	877	82	4	86	757	2,797
April .....	441	302	134	102	595	697	831	68	4	72	704	2,351
May .....	169	164	140	105	566	671	811	59	4	63	848	2,055
June .....	119	142	136	107	542	649	785	59	4	64	953	2,063
July .....	106	138	144	116	552	668	811	68	4	72	1,224	2,351
August .....	100	143	147	116	552	668	814	67	4	71	1,186	2,314
September .....	112	147	144	110	547	657	801	62	4	66	1,030	2,156
October .....	255	237	151	110	575	684	835	66	4	70	888	2,286
November .....	599	386	149	113	623	736	884	79	4	83	763	2,716
December .....	766	459	153	115	653	768	921	88	4	92	762	3,000
Total .....	4,998	3,514	1,694	1,314	7,103	8,417	10,112	877	50	927	10,590	30,140
2019 January .....	953	554	151	121	680	801	952	105	4	110	848	3,417
February .....	809	472	137	108	611	719	856	93	4	97	779	3,013
March .....	688	424	153	113	638	751	903	89	4	93	813	2,922
April .....	328	246	148	105	571	676	824	66	4	71	740	2,209
May .....	212	185	154	111	564	675	830	64	4	68	836	2,131
June .....	129	145	150	111	524	635	785	64	4	68	990	2,117
July .....	112	142	156	118	532	650	806	73	4	77	1,255	2,391
August .....	102	141	160	120	552	672	832	74	4	78	1,278	2,430
September .....	110	143	154	114	530	644	799	67	4	71	1,081	2,203
October .....	232	216	162	114	570	684	846	70	4	74	937	2,305
November .....	589	389	158	117	618	735	893	85	4	89	819	2,778
December .....	752	457	163	122	657	779	942	96	4	101	911	3,163
Total .....	5,016	3,513	1,846	1,374	7,047	8,422	10,268	944	51	995	11,287	31,079
2020 January .....	821	487	E 161	125	666	791	952	E 100	E 5	E 105	931	3,296
February .....	733	443	E 150	114	618	732	881	E 92	E 5	E 97	879	3,033
March .....	525	337	E 160	115	605	720	880	E 82	E 5	E 87	879	2,708
April .....	375	237	E 152	107	537	644	796	E 68	E 5	E 73	764	2,245
May .....	235	161	E 148	108	517	625	773	E 63	E 5	E 68	834	2,071
June .....	136	132	E 145	110	497	607	753	E 65	E 5	E 70	1,045	2,135
July .....	118	129	E 153	116	525	641	794	E 76	E 5	E 81	1,373	2,494
August .....	110	131	E 154	117	537	654	807	E 73	E 5	E 78	1,281	2,407
September .....	125	142	E 147	107	543	651	798	E 66	E 5	E 71	1,037	2,174
October .....	244	208	E 152	112	584	696	848	E 71	E 5	E 76	954	2,329
November .....	442	295	E 151	111	601	712	863	E 74	E 5	E 79	767	2,446
11-Month Total ...	3,864	2,701	E 1,673	1,243	6,230	7,473	9,145	E 830	E 54	E 884	10,743	27,338
2019 11-Month Total ...	4,263	3,056	1,683	1,252	6,391	7,643	9,326	848	47	895	10,376	27,916
2018 11-Month Total ...	4,232	3,055	1,541	1,199	6,450	7,649	9,191	789	46	835	9,828	27,141

<sup>a</sup> All commercial sector fuel use, including that at commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Table 7.4c for CHP fuel use.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and a small number of industrial electricity-only plants.

<sup>c</sup> All industrial sector fuel use other than that in "Lease and Plant Fuel" and "CHP."

<sup>d</sup> Natural gas consumed in the operation of pipelines, primarily in compressors. Beginning in 2009, includes line loss, which is known volumes of natural gas that are the result of leaks, damage, accidents, migration, and/or blow down.

<sup>e</sup> Natural gas used as fuel in the delivery of natural gas to consumers. Beginning in 2009, includes line loss, which is known volumes of natural gas that are the result of leaks, damage, accidents, migration, and/or blow down.

<sup>f</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>g</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

<sup>h</sup> Included in "Non-CHP."

<sup>i</sup> For 1989–1992, a small amount of consumption at independent power producers may be counted in both "Other Industrial" and "Electric Power Sector." See Note 7, "Natural Gas Consumption, 1989–1992," at end of section.

E=Estimate. NA=Not available. (s)=Less than 500 million cubic feet.

Notes: • Data are for natural gas, plus a small amount of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of section.

• See Note 8, "Natural Gas Data Adjustments, 1993–2000," at end of section.

• See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of

Section 7. • Through 1964, all volumes are shown on a pressure base of 14.65 psia (pounds per square inch absolute) at 60° Fahrenheit; beginning in 1965, the pressure base is 14.73 psia at 60° Fahrenheit. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **Residential, Commercial, Lease and Plant Fuel, Other Industrial Total and Pipelines and Distribution: 1949–2019**—U.S. Energy Information Administration (EIA), *Natural Gas Annual (NGA)*, annual reports and unpublished revisions. **2020 forward**—EIA, *Natural Gas Monthly (NGM)*, January 2021, Table 2. • **Other Industrial CHP:** Table 7.4c. • **Other Industrial Non-CHP:** Calculated as other industrial total minus other industrial CHP. • **Industrial Total:** Calculated as lease and plant fuel plus other industrial total. • **Vehicle Fuel: 1990 and 1991**—EIA, *NGA 2000*, (November 2001), Table 95. **1992–1998**—EIA, "Alternatives to Traditional Transportation Fuels 1999" (October 1999), Table 10, and "Alternatives to Traditional Transportation Fuels 2003" (February 2004), Table 10. Data for compressed natural gas and liquefied natural gas in gasoline-equivalent gallons were converted to cubic feet by multiplying by the motor gasoline conversion factor (see Table A3) and dividing by the natural gas end-use sectors conversion factor (see Table A4). **1999–2019**—EIA, *NGA*, annual reports.

**2020 forward—January 2021, Table 2. • Transportation Total:** Calculated as pipelines and distribution plus vehicle fuel. • **Electric Power Sector:** Table 7.4b. • **Total Consumption:** Calculated as the sum of residential, commercial, industrial total, transportation total, and electric power sector.

**Table 4.4 Natural Gas in Underground Storage**  
(Volumes in Billion Cubic Feet)

	Natural Gas in Underground Storage, End of Period			Change in Working Gas From Same Period Previous Year		Storage Activity		
	Base Gas	Working Gas	Total <sup>a</sup>	Volume	Percent	Withdrawals	Injections	Net <sup>b,c</sup>
1950 Total	NA	NA	NA	NA	NA	175	230	-54
1955 Total	863	505	1,368	40	8.7	437	505	-68
1960 Total	NA	NA	2,184	NA	NA	713	844	-132
1965 Total	1,848	1,242	3,090	83	7.2	960	1,078	-118
1970 Total	2,326	1,678	4,004	257	18.1	1,459	1,857	-398
1975 Total	3,162	2,212	5,374	162	7.9	1,760	2,104	-344
1980 Total	3,642	2,655	6,297	-99	-3.6	1,910	1,896	14
1985 Total	3,842	2,607	6,448	-270	-9.4	2,359	2,128	231
1990 Total	3,868	3,068	6,936	555	22.1	1,934	2,433	-499
1995 Total	4,349	2,153	6,503	-453	-17.4	2,974	2,566	408
2000 Total	4,352	1,719	6,071	-806	-31.9	3,498	2,684	814
2001 Total	4,301	2,904	7,204	1,185	68.9	2,309	3,464	-1,156
2002 Total	4,340	2,375	6,715	-528	-18.2	3,138	2,670	468
2003 Total	4,303	2,563	6,866	187	7.9	3,099	3,292	-193
2004 Total	4,201	2,696	6,897	133	5.2	3,037	3,150	-113
2005 Total	4,200	2,635	6,835	-61	-2.3	3,057	3,002	55
2006 Total	4,211	3,070	7,281	435	16.5	2,493	2,924	-431
2007 Total	4,234	2,879	7,113	-191	-6.2	3,325	3,133	192
2008 Total	4,232	2,840	7,073	-39	-1.4	3,374	3,340	34
2009 Total	4,277	3,130	7,407	290	10.2	2,966	3,315	-349
2010 Total	4,301	3,111	7,412	-19	-6	3,274	3,291	-17
2011 Total	4,302	3,462	7,764	351	11.3	3,074	3,422	-348
2012 Total	4,372	3,413	7,785	-49	-1.4	2,818	2,825	-7
2013 Total	4,365	2,890	7,255	-523	-15.3	3,702	3,156	546
2014 Total	4,365	3,141	7,506	251	8.7	3,586	3,839	-253
2015 Total	4,372	3,667	8,038	525	16.7	3,100	3,638	-539
2016 Total	4,380	3,297	7,677	-370	-10.1	3,325	2,977	348
2017 Total	4,360	3,033	7,392	-264	-8.0	3,590	3,337	254
2018 January	4,357	2,141	6,498	-482	-18.4	1,037	141	896
February	4,357	1,673	6,030	-665	-28.4	599	133	467
March	4,353	1,390	5,743	-672	-32.6	449	164	285
April	4,350	1,427	5,777	-864	-37.7	224	256	-32
May	4,352	1,847	6,199	-779	-29.7	66	489	-423
June	4,354	2,195	6,549	-712	-24.5	88	436	-349
July	4,354	2,381	6,736	-673	-22.0	175	362	-186
August	4,355	2,617	6,972	-633	-19.5	172	407	-235
September	4,356	2,950	7,306	-617	-17.3	130	464	-334
October	4,357	3,236	7,593	-580	-15.2	131	422	-291
November	4,356	3,030	7,386	-679	-18.3	418	213	205
December	4,361	2,708	7,069	-324	-10.7	511	191	320
Total	4,361	2,708	7,069	-324	-10.7	3,999	3,676	324
2019 January	4,366	1,994	6,360	-147	-6.8	804	95	709
February	4,366	1,426	5,792	-246	-14.7	672	104	568
March	4,361	1,185	5,545	-205	-14.8	435	190	245
April	4,367	1,559	5,927	133	9.3	104	486	-382
May	4,372	2,031	6,403	184	9.9	85	557	-472
June	4,375	2,461	6,835	266	12.1	92	523	-431
July	4,374	2,714	7,089	333	14.0	162	416	-254
August	4,377	2,998	7,374	381	14.6	168	453	-286
September	4,378	3,415	7,793	465	15.7	109	529	-419
October	4,379	3,762	8,141	526	16.2	116	461	-346
November	4,380	3,610	7,990	580	19.1	351	201	150
December	4,380	3,188	7,568	480	17.7	556	138	418
Total	4,380	3,188	7,568	480	17.7	3,653	4,153	-500
2020 January	4,380	2,616	6,997	622	31.2	665	94	571
February	4,379	2,081	6,460	655	45.9	634	99	535
March	4,379	2,030	6,409	845	71.3	285	236	49
April	4,384	2,333	6,717	773	49.6	131	437	-306
May	4,387	2,778	7,165	747	36.8	74	522	-448
June	4,389	3,133	7,523	672	27.3	85	443	-358
July	4,390	3,294	7,684	579	21.3	151	312	-161
August	4,390	3,522	7,912	524	17.5	174	401	-227
September	4,389	3,840	8,229	425	12.4	126	450	-323
October	4,393	3,929	8,321	166	4.4	191	283	-92
November	4,394	3,932	8,325	322	8.9	214	218	-4
11-Month Total	--	--	--	--	--	2,730	3,496	-765
2019 11-Month Total	--	--	--	--	--	3,097	4,015	-918
2018 11-Month Total	--	--	--	--	--	3,489	3,485	3

<sup>a</sup> For total underground storage capacity at the end of each calendar year, see Note 4, "Natural Gas Storage," at end of section.

<sup>b</sup> For 1980–2018, data differ from those shown on Table 4.1, which includes liquefied natural gas storage for that period.

<sup>c</sup> Positive numbers indicate that withdrawals are greater than injections. Negative numbers indicate that injections are greater than withdrawals. Net withdrawals or injections may not equal the difference between applicable ending stocks. See Note 4, "Natural Gas Storage," at end of section.

-- = Not applicable. NA = Not available.

Notes: • Through 1964, all volumes are shown on a pressure base of 14.65 psia (pounds per square inch absolute) at 60° Fahrenheit; beginning in 1965, the pressure base is 14.73 psia at 60° Fahrenheit. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia (except Alaska, which is excluded through 2012).

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data

beginning in 1973.

Sources: • **Storage Activity: 1949–1975**—U.S. Energy Information Administration (EIA), *Natural Gas Annual 1994, Volume 2*, Table 9. **1976–1979**—EIA, *Natural Gas Production and Consumption 1979*, Table 1. **1980–1995**—EIA, *Historical Natural Gas Annual 1930 Through 2000*, Table 11. **1996–2014**—EIA, *Natural Gas Monthly (NGM)*, monthly issues. **2015 forward**—EIA, NGM, January 2021, Table 8. • **All Other Data: 1954–1974**—American Gas Association, *Gas Facts*, annual issues. **1975 and 1976**—Federal Energy Administration (FEA), Form FEA-G318-M-0, "Underground Gas Storage Report," and Federal Power Commission (FPC), Form FPC-8, "Underground Gas Storage Report." **1977 and 1978**—EIA, Form FEA-G318-M-0, "Underground Gas Storage Report," and Federal Energy Regulatory Commission (FERC), Form FERC-8, "Underground Gas Storage Report." **1979–1995**—EIA, Form EIA-191, "Underground Gas Storage Report," and FERC, Form FERC-8, "Underground Gas Storage Report." **1996–2019**—EIA, NGA, annual reports. **2020 forward**—EIA, NGM, January 2021, Table 8.



**Note 1. Natural Gas Production.** Final annual data are from the U.S. Energy Information Administration's (EIA) *Natural Gas Annual (NGA)*.

Data for the two most recent months presented are estimated. Some of the data for earlier months are also estimated or computed. For a discussion of computation and estimation procedures, see EIA's *Natural Gas Monthly (NGM)*.

Monthly data are considered preliminary until after publication of the NGA. Preliminary monthly data are gathered from reports to the Interstate Oil Compact Commission and the U.S. Minerals Management Service. Volumetric data are converted, as necessary, to a standard pressure base of 14.73 psia (pounds per square inch absolute) at 60° Fahrenheit. Unless there are major changes, data are not revised until after publication of the NGA.

Differences between annual data in the NGA and the sum of preliminary monthly data (January–December) are allocated proportionally to the months to create final monthly data.

**Note 2. Natural Gas Plant Liquids Production.** Natural gas plant liquids (NGPL) production is the reduction in volume of natural gas resulting from the removal of natural gas liquid constituents at natural gas processing plants—these natural gas plant liquids are transferred to petroleum supply.

Annual data are from EIA's *Natural Gas Annual (NGA)*, where they are estimated on the basis of the type and quantity of liquid products extracted from the gas stream and the calculated volume of such products at standard conditions. For a detailed explanation of the calculations used to derive estimated NGPL production, see the NGA.

Through 2006, preliminary monthly data are estimated on the basis of NGPL production as an annual percentage of marketed production. Beginning in 2007, preliminary monthly data are estimated on the basis of NGPL production reported on Form EIA-816, "Monthly Natural Gas Liquids Report."

Monthly data are revised and considered final after publication of the NGA. Final monthly data are estimated by allocating annual NGPL production data to the months on the basis of total natural gas marketed production data from the NGA.

**Note 3. Supplemental Gaseous Fuels.** Supplemental gaseous fuels are any substances that, introduced into or commingled with natural gas, increase the volume available for disposition. Such substances include, but are not limited to, propane-air, refinery gas, coke oven gas, still gas, manufactured gas, biomass gas, and air or inert gases added for Btu stabilization.

Annual data beginning with 1980 are from EIA's *Natural Gas Annual (NGA)*. Unknown quantities of supplemental gaseous fuels are included in consumption data for 1979 and earlier years. Monthly data are considered preliminary until after publication of the NGA. Monthly estimates are based on the annual ratio of supplemental gaseous fuels to the sum of dry gas production, net imports, and net withdrawals from storage. The ratio is applied to the monthly sum of the three elements to compute a monthly supplemental gaseous fuels figure.

Although the total amount of supplemental gaseous fuels consumed is known for 1980 forward, the amount consumed by each energy-use sector is estimated by EIA. These estimates are used to create natural gas (without supplemental gaseous fuels) data for Tables 1.3, 2.2, 2.3, 2.4, and 2.6 (note: to avoid double-counting in these tables, supplemental gaseous fuels are accounted for in their primary energy category: "Coal," "Petroleum," or "Biomass"). It is assumed that supplemental gaseous fuels are commingled with natural gas consumed by the residential, commercial, other industrial, and electric power sectors, but are not commingled with natural gas used for lease and plant fuel, pipelines and distribution, or vehicle fuel. The estimated consumption of supplemental gaseous fuels by each sector (residential, commercial, other industrial, and electric power) is calculated as that sector's natural gas consumption (see Table 4.3) divided by the sum of natural gas consumption by the residential, commercial, other industrial, and electric power sectors (see Table 4.3), and then multiplied by total supplemental gaseous fuels consumption (see Table 4.1). For estimated sectoral consumption of supplemental gaseous fuels in Btu, the residential, commercial, and other industrial values in cubic feet are multiplied by the "End-Use Sectors" conversion factors (see Table A4), and the electric power

values in cubic feet are multiplied by the "Electric Power Sector" conversion factors (see Table A4). Total supplemental gaseous fuels consumption in Btu is calculated as the sum of the Btu values for the sectors.

**Note 4. Natural Gas Storage.** Natural gas in storage at the end of a reporting period may not equal the quantity derived by adding or subtracting net injections or withdrawals from the quantity in storage at the end of the previous period. Injection and withdrawal data from the FERC-8/EIA-191 survey may be adjusted to correspond to data from Form EIA-176 for publication of EIA's *Natural Gas Annual (NGA)*.

Total underground storage capacity, which includes both active and inactive fields, at the end of each calendar year since 1975 (first year data were available), in billion cubic feet, was:

Total underground storage capacity, including active and inactive fields (billion cubic feet)										
Decade	Year-0	Year-1	Year-2	Year-3	Year-4	Year-5	Year-6	Year-7	Year-8	Year-9
1970s						6,280	6,544	6,678	6,890	6,929
1980s	7,434	7,805	7,915	7,985	8,043	8,087	8,145	8,124	8,124	8,120
1990s	7,794	7,993	7,932	7,989	8,043	7,953	7,980	8,332	8,179	8,229
2000s	8,241	8,182	8,207	8,206	8,255	8,268	8,330	8,402	8,499	8,656
2010s	8,764	8,849	8,991	9,173	9,233	9,231	9,239	9,261	9,241	9,231

Through 1990, monthly underground storage data are collected from the Federal Energy Regulatory Commission Form FERC-8 (interstate data) and EIA Form EIA-191 (intrastate data). Beginning in 1991, all data are collected on the revised Form EIA-191. Injection and withdrawal data from the EIA-191 survey may be adjusted to correspond to data from Form EIA-176 following publication of EIA's NGA.

The final monthly and annual storage and withdrawal data for 1980–2017 include both underground and liquefied natural gas (LNG) storage. Annual data on LNG additions and withdrawals are from Form EIA-176. Monthly data are estimated by computing the ratio of each month's underground storage additions and withdrawals to annual underground storage additions and withdrawals and applying the ratio to the annual LNG data.

**Note 5. Natural Gas Balancing Item.** The balancing item for natural gas represents the difference between the sum of the components of natural gas supply and the sum of components of natural gas disposition. The differences may be due to quantities lost or to the effects of data reporting problems. Reporting problems include differences due to the net result of conversions of flow data metered at varying temperature and pressure bases and converted to a standard temperature and pressure base; the effect of variations in company accounting and billing practices; differences between billing cycle and calendar period time frames; and imbalances resulting from the merger of data reporting systems that vary in scope, format, definitions, and type of respondents.

**Note 6. Natural Gas Consumption.** Natural gas consumption statistics include data for the following: "Residential Sector": residential deliveries; "Commercial Sector": commercial deliveries, including to commercial combined-heat-and-power (CHP) and commercial electricity-only plants; "Industrial Sector": lease and plant fuel use, and other industrial deliveries, including to industrial CHP and industrial electricity-only plants also includes the relatively small amount of natural gas consumption for non-combustion use (see Tables 1.11a and 1.11b); "Transportation Sector": pipelines and distribution use, and vehicle fuel use; and "Electric Power Sector": electric utility and independent power producer use.

Final data for series other than "Other Industrial CHP" and "Electric Power Sector" are from EIA's *Natural Gas Annual (NGA)*. Monthly data are considered preliminary until after publication of the NGA. For more detailed information on the methods of estimating preliminary and final monthly data, see EIA's *Natural Gas Monthly*.

**Note 7. Natural Gas Consumption, 1989–1992.** Prior to 1993, deliveries to nonutility generators were not separately collected from natural gas companies on Form EIA-176, "Annual Report of Natural and Supplemental Gas Supply and Disposition." As a result, for 1989–1992, those volumes are probably included in both the industrial and electric power sectors and double-counted in total consumption. In 1993, 0.28 trillion cubic feet was reported as delivered to nonutility generators.

**Note 8. Natural Gas Data Adjustments, 1993–2000.** For 1993–2000, the original data for natural gas delivered to industrial consumers (now "Other Industrial" in Table 4.3) included deliveries to both industrial users and independent power producers (IPPs). These data were adjusted to remove the estimated consumption at IPPs from "Other Industrial" and include it with electric utilities under "Electric Power Sector." (To estimate the monthly IPP consumption, the monthly pattern for Other Industrial CHP in Table 4.3 was used.)

For 1996–2000, monthly data for several natural gas series shown in EIA's Natural Gas Navigator (see [http://www.eia.gov/dnav/ng/ng\\_cons\\_sum\\_dcu\\_nus\\_m.htm](http://www.eia.gov/dnav/ng/ng_cons_sum_dcu_nus_m.htm)) were not reconciled and updated to be consistent with the final annual data in EIA's *Natural Gas Annual*. In the *Monthly Energy Review*, monthly data for these series were adjusted so that the monthly data sum to the final annual values. The Table 4.1 data series (and years) that were adjusted are: Gross Withdrawals (1996, 1997), Marketed Production (1997), NGPL Production (1997, 1998, and 2000), Dry Gas Production (1996, 1997), Supplemental Gaseous Fuels (1997–2000), Balancing Item (1997–2000), and Total Consumption (1997–2000). The Table 4.3 data series (and years) that were adjusted are: Lease and Plant Fuel (1997–2000), Total Industrial (1997–2000), Pipelines and Distribution (2000), Total Transportation (2000), and Total Consumption (1997–2000).

**Note 9. Natural Gas Imports and Exports.** The United States imports natural gas via pipeline from Canada and Mexico; and imports liquefied natural gas (LNG) via tanker from Algeria, Australia, Brunei, Egypt, Equatorial Guinea, Indonesia, Malaysia, Nigeria, Norway, Oman, Peru, Qatar, Trinidad and Tobago, the United Arab Emirates, and Yemen. In addition, small amounts of LNG arrived from Canada in 1973 (667 million cubic feet), 1977 (572 million cubic feet), 1981 (6 million cubic feet), 2013 (555 million cubic feet), 2014 (132 million cubic feet), 2015 (437 million cubic feet), 2016 (924 million cubic feet), 2017 (1,569 million cubic feet), 2018 (1,885 million cubic feet), 2019 (226 million cubic feet), and 2020 (36 million cubic feet). Also, small amounts of compressed natural gas (CNG) were imported from Canada in 2014 forward. The United States exports natural gas via pipeline to Canada and Mexico; and exports LNG via tanker to Argentina, Bahamas, Bangladesh, Barbados, Belgium, Brazil, Chile, China, Columbia, Dominican Republic, Egypt, France, Greece, Haiti, India, Israel, Italy, Jamaica, Japan, Jordan, Kuwait, Lithuania, Malaysia, Malta, Netherlands, Pakistan, Panama, Poland, Portugal, Russia, Singapore, South Korea, Spain, Taiwan, Thailand, Turkey, United Arab Emirates, and United Kingdom. Also, small amounts of LNG have gone to Mexico since 1998 and to Canada in 2007 and 2012 forward. Small amounts of CNG have been exported to Canada since 2013.

Annual and final monthly data are from the annual EIA Form FPC-14, "Annual Report for Importers and Exporters of Natural Gas," which requires data to be reported by month for the calendar year.


Preliminary monthly data are EIA estimates. For a discussion of estimation procedures, see EIA's *Natural Gas Monthly*. Preliminary data are revised after publication of EIA's *U.S. Imports and Exports of Natural Gas*.

## **5. Crude Oil and Natural Gas Resource Development**


---

**Figure 5.1 Crude Oil and Natural Gas Resource Development Indicators**


Rotary Rigs in Operation by Type, 1949–2020




Rotary Rigs in Operation by Type, Monthly



Active Well Service Rig Count, Monthly



Total Wells Drilled by Type, 1949–2010



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#crude>.

Sources: Tables 5.1 and 5.2.

**Table 5.1 Crude Oil and Natural Gas Drilling Activity Measurements**  
(Number of Rigs)

	Rotary Rigs in Operation <sup>a</sup>					Active Well Service Rig Count <sup>c</sup>
	By Site		By Type		Total <sup>b</sup>	
	Onshore	Offshore	Crude Oil	Natural Gas		
1950 Average .....	NA	NA	NA	NA	2,154	NA
1955 Average .....	NA	NA	NA	NA	2,686	NA
1960 Average .....	NA	NA	NA	NA	1,748	NA
1965 Average .....	NA	NA	NA	NA	1,388	NA
1970 Average .....	NA	NA	NA	NA	1,028	NA
1975 Average .....	1,554	106	NA	NA	1,660	2,486
1980 Average .....	2,678	231	NA	NA	2,909	4,089
1985 Average .....	1,774	206	NA	NA	1,980	4,716
1990 Average .....	902	108	532	464	1,010	3,658
1995 Average .....	622	101	323	385	723	3,041
2000 Average .....	778	140	197	720	918	2,692
2001 Average .....	1,003	153	217	939	1,156	2,267
2002 Average .....	717	113	137	691	830	1,830
2003 Average .....	924	108	157	872	1,032	1,967
2004 Average .....	1,095	97	165	1,025	1,192	2,064
2005 Average .....	1,287	94	194	1,184	1,381	2,222
2006 Average .....	1,559	90	274	1,372	1,649	2,364
2007 Average .....	1,695	72	297	1,466	1,768	2,388
2008 Average .....	1,814	65	379	1,491	1,879	2,515
2009 Average .....	1,046	44	278	801	1,089	1,722
2010 Average .....	1,514	31	591	943	1,546	1,854
2011 Average .....	1,846	32	984	887	1,879	2,075
2012 Average .....	1,871	48	1,357	558	1,919	2,113
2013 Average .....	1,705	56	1,373	383	1,761	2,064
2014 Average .....	1,804	57	1,527	333	1,862	2,024
2015 Average .....	943	35	750	226	978	1,481
2016 Average .....	486	23	408	100	509	1,061
2017 Average .....	856	20	703	172	876	1,187
2018 January .....	919	18	750	187	937	1,183
February .....	952	17	788	180	969	1,232
March .....	976	13	799	188	989	1,246
April .....	995	16	817	193	1,011	1,276
May .....	1,026	20	845	198	1,046	1,293
June .....	1,037	19	861	193	1,056	1,321
July .....	1,032	18	861	187	1,050	1,326
August .....	1,031	19	864	184	1,050	1,338
September .....	1,033	20	864	187	1,053	1,347
October .....	1,041	21	870	192	1,063	1,334
November .....	1,055	22	884	193	1,077	1,319
December .....	1,054	24	880	198	1,077	1,294
Average .....	1,013	19	841	190	1,032	1,292
2019 January .....	1,044	21	866	199	1,065	1,295
February .....	1,029	20	853	195	1,048	1,299
March .....	1,001	22	830	193	1,023	1,292
April .....	990	22	824	189	1,013	1,321
May .....	965	21	802	184	986	1,316
June .....	945	24	790	179	970	1,297
July .....	930	25	782	172	955	1,297
August .....	900	26	760	166	926	1,272
September .....	852	26	726	152	878	1,221
October .....	825	23	708	139	848	1,173
November .....	788	22	678	130	810	1,149
December .....	781	23	673	128	804	1,108
Average .....	920	23	774	169	943	1,253
2020 January .....	770	21	671	118	791	1,086
February .....	768	23	678	110	790	1,046
March .....	752	20	663	106	771	802
April .....	548	18	471	93	565	456
May .....	335	13	267	79	348	490
June .....	262	12	196	76	274	549
July .....	243	12	181	72	255	617
August .....	237	13	178	70	250	674
September .....	242	15	181	73	257	741
October .....	266	14	204	73	280	788
November .....	298	12	234	74	311	800
December .....	326	15	260	80	341	R 811
Average .....	417	15	345	85	433	R 738
2021 January .....	358	16	287	86	374	NA

<sup>a</sup> Rotary rigs in operation are reported weekly on Fridays. Monthly data are averages of 4- or 5-week reporting periods. Multi-month data are averages of the reported weekly data over the covered months. Annual data are averages of 52- or 53-week reporting periods. Published data are rounded to the nearest whole number.

<sup>b</sup> Sum of rigs drilling for crude oil, rigs drilling for natural gas, and other rigs (not shown) drilling for miscellaneous purposes, such as service wells, injection wells, and stratigraphic tests. Therefore, "Total" values may not equal the sum of "Crude Oil" and "Natural Gas." "Total" values may not equal the sum of "Onshore" and "Offshore" due to independent rounding.

<sup>c</sup> The number of rigs doing true workovers (where tubing is pulled from the well), or doing rod string and pump repair operations, and that are, on average, crewed

and working every day of the month.

R=Revised. NA=Not available.

Note: Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#crude> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **Rotary Rigs in Operation:** Baker Hughes, Inc., Houston, TX, "North America Rig Count," used with permission. See <http://phx.corporate-ir.net/phoenix.zhtml?c=79687&p=irol-reports> other. • **Active Well Service Rig Count:** Assoc. of Energy Service Companies, Friendswood, TX. See <https://www.aesc.net/aesc-rig-counts.html>.

**Table 5.2 Crude Oil and Natural Gas Exploratory and Development Wells**

	Wells Drilled												Total Footage Drilled
	Exploratory				Development				Total				
	Crude Oil	Natural Gas	Dry	Total	Crude Oil	Natural Gas	Dry	Total	Crude Oil	Natural Gas	Dry	Total	
	Number												
1950 Total .....	1,583	431	8,292	10,306	22,229	3,008	6,507	31,744	23,812	3,439	14,799	42,050	157,358
1955 Total .....	2,236	874	11,832	14,942	28,196	3,392	8,620	40,208	30,432	4,266	20,452	55,150	226,182
1960 Total .....	1,321	868	9,515	11,704	20,937	4,281	8,697	33,915	22,258	5,149	18,212	45,619	192,176
1965 Total .....	946	515	8,005	9,466	17,119	3,967	8,221	29,307	18,065	4,482	16,226	38,773	174,882
1970 Total .....	757	477	6,162	7,396	12,211	3,534	4,869	20,614	12,968	4,011	11,031	28,010	138,556
1975 Total .....	982	1,248	7,129	9,359	15,966	6,879	6,517	29,362	16,948	8,127	13,646	38,721	180,494
1980 Total .....	1,777	2,099	9,081	12,957	31,182	15,362	11,704	58,248	32,959	17,461	20,785	71,205	316,943
1985 Total .....	1,680	1,200	8,954	11,834	33,581	13,124	12,257	58,962	35,261	14,324	21,211	70,796	314,409
1990 Total .....	778	811	3,652	5,241	12,061	10,435	4,593	27,089	12,839	11,246	8,245	32,330	156,044
1995 Total .....	570	558	2,024	3,152	7,678	7,524	2,790	17,992	8,248	8,082	4,814	21,144	117,156
2000 Total .....	288	657	1,341	2,286	7,802	16,394	2,805	27,001	8,090	17,051	4,146	29,287	144,425
2001 Total .....	357	1,052	1,733	3,142	8,531	21,020	2,865	32,416	8,888	22,072	4,598	35,558	180,141
2002 Total .....	258	844	1,282	2,384	6,517	16,498	2,472	25,487	6,775	17,342	3,754	27,871	145,159
2003 Total .....	350	997	1,297	2,644	7,779	19,725	2,685	30,189	8,129	20,722	3,982	32,833	177,239
2004 Total .....	383	1,671	1,350	3,404	8,406	22,515	2,732	33,653	8,789	24,186	4,082	37,057	204,279
2005 Total .....	539	2,141	1,462	4,142	10,240	26,449	3,191	39,880	10,779	28,590	4,653	44,022	240,307
2006 Total .....	646	2,456	1,547	4,649	12,739	30,382	3,659	46,780	13,385	32,838	5,206	51,429	282,675
2007 Total .....	808	2,794	1,582	5,184	12,563	29,925	3,399	45,887	13,371	32,719	4,981	51,071	301,515
2008 January .....	88	208	144	440	1,111	2,321	272	3,704	1,199	2,529	416	4,144	25,306
February .....	82	230	107	419	1,080	2,261	247	3,588	1,162	2,491	354	4,007	24,958
March .....	66	216	127	409	1,132	2,363	271	3,766	1,198	2,579	398	4,175	26,226
April .....	68	189	130	387	1,177	2,415	281	3,873	1,245	2,604	411	4,260	26,920
May .....	88	206	124	418	1,317	2,449	240	4,006	1,405	2,655	364	4,424	27,947
June .....	63	195	139	397	1,428	2,540	299	4,267	1,491	2,735	438	4,664	28,739
July .....	79	163	171	413	1,439	2,695	344	4,478	1,518	2,858	515	4,891	29,140
August .....	67	165	144	376	1,448	2,735	379	4,562	1,515	2,900	523	4,938	28,942
September .....	52	166	164	382	1,488	2,667	355	4,510	1,540	2,833	519	4,892	28,960
October .....	80	243	173	496	1,549	2,841	373	4,763	1,629	3,084	546	5,259	31,505
November .....	97	192	160	449	1,361	2,418	334	4,113	1,458	2,610	494	4,562	29,276
December .....	67	172	132	371	1,206	2,196	313	3,715	1,273	2,368	445	4,086	26,222
Total .....	897	2,345	1,715	4,957	15,736	29,901	3,708	49,345	16,633	32,246	5,423	54,302	334,141
2009 January .....	80	171	99	350	1,192	2,253	250	3,695	1,272	2,424	349	4,045	28,077
February .....	62	125	88	275	991	1,925	195	3,111	1,053	2,050	283	3,386	25,440
March .....	59	146	88	293	867	1,771	210	2,848	926	1,917	298	3,141	25,304
April .....	36	68	93	197	755	1,396	205	2,356	791	1,464	298	2,553	21,406
May .....	47	90	80	217	584	1,136	156	1,876	631	1,226	236	2,093	20,055
June .....	44	91	75	210	804	1,297	189	2,290	848	1,388	264	2,500	16,301
July .....	40	100	101	241	789	1,188	217	2,194	829	1,288	318	2,435	13,543
August .....	49	84	88	221	867	1,372	207	2,446	916	1,456	295	2,667	15,970
September .....	61	71	96	228	945	1,170	207	2,322	1,006	1,241	303	2,550	15,547
October .....	55	79	78	212	966	1,167	222	2,355	1,021	1,246	300	2,567	17,261
November .....	38	83	85	206	931	1,133	199	2,263	969	1,216	284	2,469	16,236
December .....	34	98	84	216	894	1,074	213	2,181	928	1,172	297	2,397	16,424
Total .....	605	1,206	1,055	2,866	10,585	16,882	2,470	29,937	11,190	18,088	3,525	32,803	231,562
2010 January .....	55	91	81	227	898	1,264	169	2,331	953	1,355	250	2,558	15,304
February .....	44	71	67	182	871	1,096	144	2,111	915	1,167	211	2,293	16,862
March .....	59	85	88	232	1,062	1,224	216	2,502	1,121	1,309	304	2,734	15,102
April .....	49	78	77	204	1,173	1,152	249	2,574	1,222	1,230	326	2,778	17,904
May .....	48	107	86	241	1,282	1,208	255	2,745	1,330	1,315	341	2,986	17,987
June .....	61	100	90	251	1,385	1,250	302	2,937	1,446	1,350	392	3,188	19,408
July .....	46	103	105	254	1,386	1,443	390	3,219	1,432	1,546	495	3,473	20,847
August .....	56	104	94	254	1,434	1,402	314	3,150	1,490	1,506	408	3,404	22,923
September .....	57	73	88	218	1,374	1,358	268	3,000	1,431	1,431	356	3,218	23,037
October .....	75	87	117	279	1,502	1,463	283	3,248	1,577	1,550	400	3,527	22,123
November .....	62	114	103	279	1,400	1,352	263	3,015	1,462	1,466	366	3,294	24,561
December .....	57	92	70	219	1,317	1,379	243	2,939	1,374	1,471	313	3,158	23,189
Total .....	669	1,105	1,066	2,840	15,084	15,591	3,096	33,771	15,753	16,696	4,162	36,611	239,247

Notes: • Data are estimates. • For 1960–1969, data are for well completion reports received by the American Petroleum Institute during the reporting year; for all other years, data are for well completions in a given year. • Through 1989, these well counts include only the original drilling of a hole intended to discover or further develop already discovered crude oil or natural gas resources. Other drilling activities, such as drilling an old well deeper, drilling of laterals from the original well, drilling of service and injection wells, and drilling for resources other than crude oil or natural gas are excluded. Beginning in 1990, a new well is defined as the first hole in the ground whether it is lateral or not. Due to the methodology used to estimate ultimate well counts from the available partially reported data, the counts shown on this page are frequently revised. See Note, "Crude Oil and

Natural Gas Exploratory and Development Wells," at end of section. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#crude> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **1949–1965:** Gulf Publishing Company, *World Oil*, "Forecast-Review" issue. • **1966–1969:** American Petroleum Institute (API), *Quarterly Review of Drilling Statistics for the United States*, annual summaries and monthly reports. • **1970–1989:** U.S. Energy Information Administration (EIA) computations based on well reports submitted to the API. • **1990 forward:** EIA computations based on well reports submitted to IHS, Inc., Denver, CO.

Data for 2011 forward in this table have been removed while EIA evaluates the quality of the data and the estimation methodology.

## Crude Oil and Natural Gas Resource Development

---

**Note. Crude Oil and Natural Gas Exploratory and Development Wells.** Three well types are considered in the *Monthly Energy Review* (MER) drilling statistics: “completed for crude oil,” “completed for natural gas,” and “dry hole.” Wells that productively encounter both crude oil and natural gas are categorized as “completed for crude oil.” Both development wells and exploratory wells (new field wildcats, new pool tests, and extension tests) are included in the statistics. All other classes of wells drilled in connection with the search for producible hydrocarbons are excluded. If a lateral is drilled at the same time as the original hole it is not counted separately, but its footage is included.

Prior to the March 1985 MER, drilling statistics consisted of completion data for the above types and classes of wells as reported to the American Petroleum Institute (API) during a given month. Due to time lags between the date of well completion and the date of completion reporting to the API, as-reported well completions proved to be an inaccurate indicator of drilling activity. During 1982, for example, as-reported well completions rose, while the number of actual completions fell. Consequently, the drilling statistics published since the March 1985 MER are U.S. Energy Information Administration (EIA) estimates produced by statistically imputing well counts and footage based on the partial data available from the API. These estimates are subject to continuous revision as new data, some of which pertain to earlier months and years, become available. Additional information about the EIA estimation methodology may be found in “Estimating Well Completions,” a feature article published in the March 1985 MER.




## 6. Coal

---


**Figure 6.1 Coal**

(Million Short Tons)


Overview, 1949–2020




Consumption by Sector, 1949–2019



Overview, Monthly



Electric Power Sector Consumption, Monthly



[a] Includes combined-heat-power (CHP) plants and a small number of electricity-only plants.

[b] For 1978 forward, small amounts of transportation sector use are

included in "Industrial."

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#coal>.

Sources: Tables 6.1 and 6.2.

**Table 6.1 Coal Overview**  
(Thousand Short Tons)

	Production <sup>a</sup>	Waste Coal Supplied <sup>b</sup>	Trade			Stock Change <sup>d,e</sup>	Losses and Unaccounted for <sup>e,f</sup>	Consumption
			Imports	Exports	Net Imports <sup>c</sup>			
<b>1950 Total</b> .....	560,388	NA	365	29,360	-28,995	27,829	9,462	494,102
<b>1955 Total</b> .....	490,838	NA	337	54,429	-54,092	-3,974	-6,292	447,012
<b>1960 Total</b> .....	434,329	NA	262	37,981	-37,719	-3,194	1,722	398,081
<b>1965 Total</b> .....	526,954	NA	184	51,032	-50,848	1,897	2,244	471,965
<b>1970 Total</b> .....	612,661	NA	36	71,733	-71,697	11,100	6,633	523,231
<b>1975 Total</b> .....	654,641	NA	940	66,309	-65,369	32,154	-5,522	562,640
<b>1980 Total</b> .....	829,700	NA	1,194	91,742	-90,548	25,595	10,827	702,730
<b>1985 Total</b> .....	883,638	NA	1,952	92,680	-90,727	-27,934	2,796	818,049
<b>1990 Total</b> .....	1,029,076	3,339	2,699	105,804	-103,104	26,542	-1,730	904,498
<b>1995 Total</b> .....	1,032,974	8,561	9,473	88,547	-79,074	-275	632	962,104
<b>2000 Total</b> .....	1,073,612	9,089	12,513	58,489	-45,976	-48,309	938	1,084,095
<b>2001 Total</b> .....	1,127,689	10,085	19,787	48,666	-28,879	41,630	7,120	1,060,146
<b>2002 Total</b> .....	1,094,283	9,052	16,875	39,601	-22,726	10,215	4,040	1,066,355
<b>2003 Total</b> .....	1,071,753	10,016	25,044	43,014	-17,970	-26,659	-4,403	1,094,861
<b>2004 Total</b> .....	1,112,099	11,299	27,280	47,998	-20,718	-11,462	6,887	1,107,255
<b>2005 Total</b> .....	1,131,498	13,352	30,460	49,942	-19,482	-9,702	9,092	1,125,978
<b>2006 Total</b> .....	1,162,750	14,409	36,246	49,647	-13,401	42,642	8,824	1,112,292
<b>2007 Total</b> .....	1,146,635	14,076	36,347	59,163	-22,816	5,812	4,085	1,127,998
<b>2008 Total</b> .....	1,171,809	14,146	34,208	81,519	-47,311	12,354	5,740	1,120,548
<b>2009 Total</b> .....	1,074,923	13,666	22,639	59,097	-36,458	39,668	14,985	997,478
<b>2010 Total</b> .....	1,084,368	13,651	19,353	81,716	-62,363	-13,039	182	1,048,514
<b>2011 Total</b> .....	1,095,628	13,209	13,088	107,259	-94,171	211	11,506	1,002,948
<b>2012 Total</b> .....	1,016,458	11,196	9,159	125,746	-116,586	6,902	14,980	889,185
<b>2013 Total</b> .....	984,842	11,279	8,906	117,659	-108,753	-38,525	1,451	924,442
<b>2014 Total</b> .....	1,000,049	12,090	11,350	97,257	-85,907	-2,601	11,101	917,731
<b>2015 Total</b> .....	896,941	9,969	11,318	73,958	-62,640	40,704	5,452	798,115
<b>2016 Total</b> .....	728,364	10,138	9,850	60,271	-50,421	-45,441	2,452	731,071
<b>2017 Total</b> .....	774,609	9,951	7,803	96,945	-89,142	-26,033	4,596	716,856
<b>2018 January</b> .....	61,971	1,090	500	8,659	-8,160	-13,881	-470	69,254
February .....	60,269	909	349	8,983	-8,633	-2,738	5,258	50,025
March .....	65,504	997	518	9,886	-9,368	5,081	3,181	48,870
April .....	58,046	704	494	11,032	-10,538	1,275	2,144	44,793
May .....	61,211	600	544	9,400	-8,856	-1,134	2,515	51,574
June .....	61,572	818	509	10,107	-9,598	-6,753	-694	60,240
July .....	62,967	928	692	9,924	-9,232	-12,556	-863	68,083
August .....	69,325	949	484	9,995	-9,511	-5,714	-1,499	67,976
September .....	62,438	818	263	9,683	-9,420	-2,520	-1,803	58,159
October .....	66,532	723	304	10,768	-10,464	3,885	96	52,811
November .....	62,857	923	400	8,920	-8,520	-166	-744	56,170
December .....	63,474	971	898	8,888	-7,990	-1,937	-1,757	60,149
<b>Total</b> .....	<b>756,167</b>	<b>10,431</b>	<b>5,954</b>	<b>116,244</b>	<b>-110,290</b>	<b>-37,160</b>	<b>5,363</b>	<b>688,105</b>
<b>2019 January</b> .....	65,836	976	625	9,329	-8,704	-4,032	1,940	60,199
February .....	58,315	824	358	6,752	-6,393	1,568	1,978	49,200
March .....	55,667	850	706	9,132	-8,427	-1,181	926	48,346
April .....	61,213	598	537	8,642	-8,105	9,904	6,519	37,282
May .....	61,862	648	408	8,979	-8,572	9,271	607	44,060
June .....	56,706	700	660	8,308	-7,648	1,561	-71	48,267
July .....	59,069	574	511	6,469	-5,958	-5,366	-751	59,802
August .....	63,795	593	519	7,749	-7,230	934	-86	56,310
September .....	58,597	410	651	7,742	-7,091	1,748	-944	51,113
October .....	57,674	498	742	6,590	-5,848	9,909	898	41,517
November .....	54,393	611	466	7,582	-7,116	4,816	-2,796	45,869
December .....	53,184	723	515	6,491	-5,976	6,411	-3,054	44,574
<b>Total</b> .....	<b>706,309</b>	<b>8,003</b>	<b>6,697</b>	<b>93,765</b>	<b>-87,068</b>	<b>35,542</b>	<b>5,164</b>	<b>586,539</b>
<b>2020 January</b> .....	55,612	679	535	6,234	-5,699	6,092	3,785	40,715
February .....	47,379	664	343	6,829	-6,486	5,202	374	35,982
March .....	46,061	527	461	6,914	-6,453	4,812	2,524	32,799
April .....	39,000	515	365	5,480	-5,115	6,797	899	26,704
May .....	36,934	499	498	4,719	-4,222	2,620	769	29,822
June .....	39,259	510	284	4,579	-4,295	-5,691	1,326	39,838
July .....	43,196	636	473	5,359	-4,886	-14,364	378	52,933
August .....	47,499	691	314	4,522	-4,209	-7,847	-1,807	53,635
September .....	45,119	647	501	5,371	-4,870	-1,237	301	41,833
October .....	46,599	F 763	263	5,045	-4,782	6,644	-1,641	37,576
November .....	45,960	RF 763	639	7,018	-6,379	2,805	R -57	R 37,596
December .....	46,436	NA	R 423	R 7,001	R -6,578	NA	NA	NA
<b>Total</b> .....	<b>539,053</b>	<b>NA</b>	<b>R 5,098</b>	<b>R 69,071</b>	<b>R -63,972</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>
<b>2021 January</b> .....	48,565	NA	NA	NA	NA	NA	NA	NA

<sup>a</sup> Beginning in 2001, includes a small amount of refuse recovery (coal recaptured from a refuse mine and cleaned to reduce the concentration of noncombustible materials).

<sup>b</sup> Waste coal (including fine coal, coal obtained from a refuse bank or slurry dam, anthracite culm, bituminous gob, and lignite waste) consumed by the electric power and industrial sectors. Beginning in 1989, waste coal supplied is counted as a supply-side item to balance the same amount of waste coal included in "Consumption."

<sup>c</sup> Net imports equal imports minus exports. A minus sign indicates exports are greater than imports.

<sup>d</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase. See Table 6.3 for stocks data coverage.

<sup>e</sup> In 1949, stock change is included in "Losses and Unaccounted for."

<sup>f</sup> The difference between calculated coal supply and disposition, due to coal

quantities lost or to data reporting problems.

R=Revised. NA=Not available. F=Forecast.

Notes: • For methodology used to calculate production, consumption, and stocks, see Note 1, "Coal Production," Note 2, "Coal Consumption," and Note 3, "Coal Stocks," at end of section. • Data values preceded by "F" are derived from the U.S. Energy Information Administration's Short-Term Integrated Forecasting System. See Note 4, "Coal Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#coal> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 6.2 Coal Consumption by Sector**  
(Thousand Short Tons)

	End-Use Sectors										Electric Power Sector <sup>e,f</sup>	Total
	Residential	Commercial			Coke Plants	Industrial			Transportation			
		CHP <sup>a</sup>	Other <sup>b</sup>	Total		Other Industrial		Total				
						CHP <sup>c</sup>	Non-CHP <sup>d</sup>					
1950 Total	51,562	(g)	63,021	63,021	104,014	(h)	120,623	120,623	224,637	63,011	91,871	494,102
1955 Total	35,590	(g)	32,852	32,852	107,743	(h)	110,096	110,096	217,839	16,972	143,759	447,012
1960 Total	24,159	(g)	16,789	16,789	81,385	(h)	96,017	96,017	177,402	3,046	176,685	398,081
1965 Total	14,635	(g)	11,041	11,041	95,286	(h)	105,560	105,560	200,846	655	244,788	471,965
1970 Total	9,024	(g)	7,090	7,090	96,481	(h)	90,156	90,156	186,637	298	320,182	523,231
1975 Total	2,823	(g)	6,587	6,587	83,598	(h)	63,646	63,646	147,244	24	405,962	562,640
1980 Total	1,355	(g)	5,097	5,097	66,657	(h)	60,347	60,347	127,004	(h)	569,274	702,730
1985 Total	1,711	(g)	6,068	6,068	41,056	(h)	75,372	75,372	116,429	(h)	693,841	818,049
1990 Total	1,345	1,191	4,189	5,379	38,877	27,781	48,549	76,330	115,207	(h)	<sup>f</sup> 782,567	904,498
1995 Total	755	1,419	3,633	5,052	33,011	29,363	43,693	73,055	106,067	(h)	850,230	962,104
2000 Total	454	1,547	2,126	3,673	28,939	28,031	37,177	65,208	94,147	(h)	985,821	1,084,095
2001 Total	481	1,448	2,441	3,888	26,075	25,755	39,514	65,268	91,344	(h)	964,433	1,060,146
2002 Total	533	1,405	2,506	3,912	23,656	26,232	34,515	60,747	84,403	(h)	977,507	1,066,355
2003 Total	551	1,816	1,869	3,685	24,248	24,846	36,415	61,261	85,509	(h)	1,005,116	1,094,861
2004 Total	512	1,917	2,693	4,610	23,670	26,613	35,582	62,195	85,865	(h)	1,016,268	1,107,255
2005 Total	378	1,922	2,420	4,342	23,434	25,875	34,465	60,340	83,774	(h)	1,037,485	1,125,978
2006 Total	290	1,886	1,050	2,936	22,957	25,262	34,210	59,472	82,429	(h)	1,026,636	1,112,292
2007 Total	353	1,927	1,247	3,173	22,715	22,537	34,078	56,615	79,331	(h)	1,045,141	1,127,998
2008 Total	(i)	2,021	1,485	3,506	22,070	21,902	32,491	54,393	76,463	(h)	1,040,580	1,120,548
2009 Total	(i)	1,798	1,412	3,210	15,326	19,766	25,549	45,314	60,641	(h)	933,627	997,478
2010 Total	(i)	1,720	1,361	3,081	21,092	24,638	24,650	49,289	70,381	(h)	975,052	1,048,514
2011 Total	(i)	1,668	1,125	2,793	21,434	22,319	23,919	46,238	67,671	(h)	932,484	1,002,948
2012 Total	(i)	1,450	595	2,045	20,751	20,065	22,773	42,838	63,589	(h)	823,551	889,185
2013 Total	(i)	1,356	595	1,951	21,474	19,761	23,294	43,055	64,529	(h)	857,962	924,442
2014 Total	(i)	1,063	824	1,887	21,297	19,076	23,870	42,946	64,243	(h)	851,602	917,731
2015 Total	(i)	798	706	1,503	19,708	16,984	21,475	38,459	58,167	(h)	738,444	798,115
2016 Total	(i)	683	500	1,183	16,485	14,720	20,129	34,849	51,333	(h)	678,554	731,071
2017 Total	(i)	610	451	1,061	17,538	12,975	20,289	33,264	50,801	(h)	664,993	716,856
2018 January	(i)	76	64	140	1,458	1,242	1,453	2,695	4,153	(h)	64,960	69,254
February	(i)	59	50	110	1,288	1,122	1,608	2,730	4,018	(h)	45,897	50,025
March	(i)	57	48	105	1,482	1,109	1,612	2,721	4,203	(h)	44,562	48,870
April	(i)	47	28	75	1,549	960	1,607	2,567	4,116	(h)	40,603	44,793
May	(i)	39	23	62	1,596	979	1,581	2,561	4,156	(h)	47,356	51,574
June	(i)	36	21	57	1,465	969	1,595	2,564	4,029	(h)	56,154	60,240
July	(i)	40	15	55	1,600	962	1,572	2,534	4,135	(h)	63,894	68,083
August	(i)	42	16	58	1,577	949	1,583	2,532	4,108	(h)	63,810	67,976
September	(i)	45	17	62	1,585	943	1,583	2,525	4,110	(h)	53,987	58,159
October	(i)	42	35	76	1,549	891	1,822	2,713	4,262	(h)	48,474	52,811
November	(i)	47	39	87	1,558	1,015	1,705	2,720	4,278	(h)	51,806	56,170
December	(i)	47	39	86	1,630	1,093	1,627	2,720	4,350	(h)	55,714	60,149
Total	(i)	577	395	972	18,337	12,233	19,347	31,580	49,917	(h)	637,217	688,105
2019 January	(i)	59	51	111	1,515	1,119	1,487	2,606	4,121	(h)	55,967	60,199
February	(i)	54	47	102	1,393	1,005	1,577	2,582	3,974	(h)	45,124	49,200
March	(i)	58	50	108	1,556	932	1,654	2,587	4,142	(h)	44,096	48,346
April	(i)	40	27	67	1,450	893	1,444	2,337	3,786	(h)	33,429	37,282
May	(i)	38	26	64	1,624	873	1,455	2,328	3,952	(h)	40,045	44,060
June	(i)	27	18	45	1,586	845	1,494	2,338	3,925	(h)	44,297	48,267
July	(i)	35	13	48	1,498	846	1,478	2,324	3,822	(h)	55,932	59,802
August	(i)	37	14	51	1,487	854	1,487	2,341	3,829	(h)	52,431	56,310
September	(i)	40	15	55	1,469	814	1,526	2,340	3,810	(h)	47,248	51,113
October	(i)	37	27	65	1,494	856	1,579	2,436	3,930	(h)	37,523	41,517
November	(i)	44	32	76	1,387	904	1,524	2,429	3,816	(h)	41,977	45,869
December	(i)	49	36	86	1,508	950	1,498	2,448	3,956	(h)	40,533	44,574
Total	(i)	519	357	876	17,967	10,892	18,203	29,095	47,062	(h)	538,601	586,539
2020 January	(i)	41	55	96	1,435	984	1,400	2,384	3,818	(h)	36,801	40,715
February	(i)	49	66	115	1,434	939	1,427	2,366	3,801	(h)	32,066	35,982
March	(i)	41	55	96	1,408	886	1,431	2,318	3,725	(h)	28,978	32,799
April	(i)	29	14	44	1,192	773	1,072	1,845	3,037	(h)	23,623	26,704
May	(i)	32	15	47	1,055	749	1,100	1,849	2,904	(h)	26,870	29,822
June	(i)	35	17	52	1,208	699	1,204	1,903	3,111	(h)	36,675	39,838
July	(i)	35	11	46	1,019	761	1,195	1,956	2,975	(h)	49,912	52,933
August	(i)	37	11	49	1,086	735	1,253	1,988	3,074	(h)	50,513	53,635
September	(i)	41	13	54	1,058	775	1,213	1,988	3,046	(h)	38,733	41,833
October	(i)	34	F 26	F 61	F 1,324	850	F 1,398	F 2,247	F 3,572	(h)	33,944	37,576
November	(i)	36	F 26	F 62	F 817	825	F 1,505	F 2,330	F 3,147	(h)	34,387	37,596
11-Month Total	(i)	410	E 310	E 720	E 13,035	8,977	E 14,198	E 23,175	E 36,210	(h)	392,502	429,432
2019 11-Month Total	(i)	470	321	790	16,459	9,942	16,705	26,647	43,106	(h)	498,068	541,965
2018 11-Month Total	(i)	530	356	886	16,707	11,141	17,720	28,860	45,567	(h)	581,503	627,956

<sup>a</sup> Commercial combined-heat-and-power (CHP) and a small number of commercial electricity-only plants, such as those at hospitals and universities. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>b</sup> All commercial sector fuel use other than that in "Commercial CHP."

<sup>c</sup> Industrial combined-heat-and-power (CHP) and a small number of industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>d</sup> All industrial sector fuel use other than that in "Coke Plants" and "Industrial CHP."

<sup>e</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>f</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

<sup>g</sup> Included in "Commercial Other."

<sup>h</sup> Included in "Industrial Non-CHP."

<sup>i</sup> Beginning in 2008, residential coal consumption data are no longer collected by the U.S. Energy Information Administration (EIA).

E=Estimate. F=Forecast.

Notes: • CHP monthly values are from Table 7.4c; electric power sector monthly values are from Table 7.4b; all other monthly values are estimates derived from collected quarterly and annual data. See Note 2, "Coal Consumption," at end of section. • Data values preceded by "F" are derived from EIA's Short-Term Integrated Forecasting System. See Note 4, "Coal Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#coal> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 6.3 Coal Stocks by Sector**  
(Thousand Short Tons)

	Producers and Distributors	End-Use Sectors					Electric Power Sector <sup>c,d</sup>	Total
		Residential <sup>a</sup> and Commercial	Industrial			Total		
			Coke Plants	Other <sup>b</sup>	Total			
1950 Year .....	NA	2,462	16,809	26,182	42,991	45,453	31,842	77,295
1955 Year .....	NA	998	13,422	15,880	29,302	30,300	41,391	71,691
1960 Year .....	NA	666	11,122	11,637	22,759	23,425	51,735	75,160
1965 Year .....	NA	353	10,640	13,122	23,762	24,115	54,525	78,640
1970 Year .....	NA	300	9,045	11,781	20,826	21,126	71,908	93,034
1975 Year .....	12,108	233	8,797	8,529	17,326	17,559	110,724	140,391
1980 Year .....	24,379	NA	9,067	11,951	21,018	21,018	183,010	228,407
1985 Year .....	33,133	NA	3,420	10,438	13,857	13,857	156,376	203,367
1990 Year .....	33,418	NA	3,329	8,716	12,044	12,044	156,166	201,629
1995 Year .....	34,444	NA	2,632	5,702	8,334	8,334	126,304	169,083
2000 Year .....	31,905	NA	1,494	4,587	6,081	6,081	102,296	140,282
2001 Year .....	35,900	NA	1,510	6,006	7,516	7,516	138,496	181,912
2002 Year .....	43,257	NA	1,364	5,792	7,156	7,156	141,714	192,127
2003 Year .....	38,277	NA	905	4,718	5,623	5,623	121,567	165,468
2004 Year .....	41,151	NA	1,344	4,842	6,186	6,186	106,669	154,006
2005 Year .....	34,971	NA	2,615	5,582	8,196	8,196	101,137	144,304
2006 Year .....	36,548	NA	2,928	6,506	9,434	9,434	140,964	186,946
2007 Year .....	33,977	NA	1,936	5,624	7,560	7,560	151,221	192,758
2008 Year .....	34,688	498	2,331	6,007	8,338	8,836	161,589	205,112
2009 Year .....	47,718	529	1,957	5,109	7,066	7,595	189,467	244,780
2010 Year .....	49,820	552	1,925	4,525	6,451	7,003	174,917	231,740
2011 Year .....	51,897	603	2,610	4,455	7,065	7,668	172,387	231,951
2012 Year .....	46,157	583	2,522	4,475	6,997	7,581	185,116	238,853
2013 Year .....	45,652	495	2,200	4,097	6,297	6,792	147,884	200,328
2014 Year .....	38,894	449	2,640	4,196	6,836	7,285	151,548	197,727
2015 Year .....	35,871	394	2,236	4,382	6,618	7,012	195,548	238,431
2016 Year .....	25,309	360	1,675	3,637	5,312	5,672	162,009	192,990
2017 Year .....	23,999	310	1,718	3,242	4,960	5,270	137,687	166,956
2018 January .....	24,769	298	1,648	3,125	4,773	5,072	123,235	153,075
February .....	24,938	287	1,578	3,008	4,586	4,873	120,526	150,337
March .....	24,736	275	1,508	2,891	4,399	4,674	126,008	155,418
April .....	23,417	268	1,544	2,893	4,437	4,705	128,571	156,693
May .....	22,841	262	1,580	2,895	4,474	4,736	127,982	155,559
June .....	22,997	256	1,616	2,896	4,512	4,768	121,041	148,806
July .....	21,025	257	1,681	2,939	4,619	4,876	110,348	136,250
August .....	21,806	259	1,746	2,981	4,727	4,985	103,744	130,535
September .....	22,537	260	1,811	3,023	4,834	5,094	100,384	128,015
October .....	21,878	256	1,809	3,102	4,911	5,166	104,855	131,900
November .....	22,419	251	1,808	3,180	4,988	5,239	104,075	131,733
December .....	21,692	247	1,807	3,258	5,065	5,312	102,793	129,796
2019 January .....	21,391	238	1,873	3,116	4,989	5,227	99,147	125,765
February .....	23,551	229	1,939	2,974	4,913	5,142	98,639	127,332
March .....	24,160	221	2,005	2,832	4,837	5,058	96,933	126,151
April .....	22,767	214	2,102	2,883	4,985	5,199	108,089	136,055
May .....	24,273	208	2,199	2,934	5,133	5,341	115,712	145,326
June .....	24,529	201	2,296	2,985	5,281	5,483	116,876	146,887
July .....	25,240	212	2,352	3,046	5,398	5,609	110,672	141,521
August .....	26,441	222	2,407	3,107	5,514	5,736	110,278	142,455
September .....	27,714	232	2,463	3,168	5,631	5,863	110,626	144,203
October .....	29,683	237	2,420	3,198	5,618	5,855	118,574	154,112
November .....	30,717	242	2,376	3,228	5,605	5,846	122,364	158,927
December .....	31,320	246	2,333	3,258	5,591	5,838	128,180	165,338
2020 January .....	F 31,382	235	2,271	3,178	5,449	5,684	134,364	171,430
February .....	F 31,803	223	2,210	3,097	5,307	5,530	139,299	176,632
March .....	F 30,829	212	2,148	3,017	5,165	5,376	145,238	181,444
April .....	F 31,168	212	2,106	3,010	5,116	5,329	151,744	188,240
May .....	F 31,522	212	2,064	3,004	5,068	5,281	154,058	190,861
June .....	F 29,510	213	2,022	2,998	5,020	5,233	150,427	185,170
July .....	F 27,716	220	2,007	2,957	4,963	5,183	137,907	170,806
August .....	F 28,138	227	1,991	2,915	4,906	5,133	129,688	162,959
September .....	F 27,537	234	1,975	2,874	4,849	5,083	129,102	161,721
October .....	F 29,025	F 196	F 2,140	F 3,607	F 5,747	F 5,943	133,398	168,366
November .....	F 29,152	F 187	F 2,078	F 3,562	F 5,640	F 5,828	136,191	171,170

<sup>a</sup> Through 1979, data are for the residential and commercial sectors. Beginning in 2008, data are for the commercial sector only.

<sup>b</sup> Through 1979, data are for manufacturing plants and the transportation sector. For 1980–2007, data are for manufacturing plants only. Beginning in 2008, data are for manufacturing plants and coal transformation/processing plants.

<sup>c</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>d</sup> Excludes waste coal. Through 1998, data are for electric utilities only.

Beginning in 1999, data are for electric utilities and independent power producers.

NA=Not available. F=Forecast.

Notes: • Stocks are at end of period. • Electric power sector monthly values

are from Table 7.5; producers and distributors monthly values are estimates derived from collected annual data; all other monthly values are estimates derived from collected quarterly values. • Data values preceded by "F" are derived from the U.S. Energy Information Administration's Short-Term Integrated Forecasting System. See Note 4, "Coal Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#coal> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Note 1. Coal Production.** Preliminary monthly estimates of national coal production are the sum of weekly estimates developed by the U.S. Energy Information Administration (EIA) and published in the *Weekly Coal Production* report. When a week extends into a new month, production is allocated on a daily basis and added to the appropriate month. Weekly estimates are based on Association of American Railroads (AAR) data showing the number of railcars loaded with coal during the week by Class I and certain other railroads.

Through 2001, the weekly coal production model converted AAR data into short tons of coal by using the average number of short tons of coal per railcar loaded reported in the “Quarterly Freight Commodity Statistics” from the Surface Transportation Board. If an average coal tonnage per railcar loaded was not available for a specific railroad, the national average was used. To derive the estimate of total weekly production, the total rail tonnage for the week was divided by the ratio of quarterly production shipped by rail and total quarterly production. Data for the corresponding quarter of previous years were used to derive this ratio. This method ensured that the seasonal variations were preserved in the production estimates.

From 2002 through 2014, the weekly coal production model used statistical auto regressive methods to estimate national coal production as a function of railcar loadings of coal, heating degree-days, and cooling degree-days. On Thursday of each week, EIA received from the AAR data for the previous week. The latest weekly national data for heating degree-days and cooling degree-days were obtained from the National Oceanic and Atmospheric Administration’s Climate Prediction Center.

Beginning in 2015, the revised weekly coal production model uses statistical auto regressive methods to estimate national coal production as a function of railcar loadings of coal. EIA receives AAR data on Thursday of each week for prior week car loadings. The weekly coal model is run and a national level coal production estimate is obtained. From there, state-level estimates are calculated using historical state production share. The state estimates are then aggregated to various regional-level estimates. The weekly coal model is refit every quarter after preliminary coal data are available.

When preliminary quarterly data become available, the monthly and weekly estimates are adjusted to conform to the quarterly figures. The adjustment procedure uses historical state-level production data, the methodology for which can be seen in the documentation located at <http://www.eia.gov/coal/production/weekly/>. Initial estimates of annual production published in January of the following year are based on preliminary production data covering the first nine months (three quarters) and weekly/monthly estimates for the fourth quarter. All quarterly, monthly, and weekly production figures are adjusted to conform to the final annual production data published in the *Monthly Energy Review* in the fall of the following year.

**Note 2. Coal Consumption.** Forecast data (designated by an “F”) are derived from forecasted values shown in EIA’s *Short-Term Energy Outlook* (DOE/EIA-0202) table titled “U.S. Coal Supply, Consumption, and Inventories.” The monthly estimates are based on the quarterly values, which are released in March, June, September, and December. The estimates are revised quarterly as collected data become available from the data sources. Sector-specific information follows.

**Residential and Commercial**—Through 2007, coal consumption by the residential and commercial sectors is reported to EIA for the two sectors combined; EIA estimates the amount consumed by the sectors individually. To create the estimates, it is first assumed that an occupied coal-heated housing unit consumes fuel at the same Btu rate as an oil-heated housing unit. Then, for the years in which data are available on the number of occupied housing units by heating source (1973–1981 and subsequent odd-numbered years), residential consumption of coal is estimated using the following steps: a ratio is created of the number of occupied housing units heated by coal to the number of occupied housing units heated by oil; that ratio is then multiplied by the Btu quantity of oil consumed by the residential sector to derive an estimate of the Btu quantity of coal consumed by the residential sector; and, finally, the amount estimated as the residential sector consumption is subtracted from the residential and commercial sectors’ combined consumption to derive the commercial sector’s estimated consumption. Beginning in 2008, residential coal consumption data are not collected by EIA, and commercial coal consumption data are taken directly from reported data.

**Industrial Coke Plants**—Through 1979, monthly coke plant consumption data were taken directly from reported data. For 1980–1987, coke plant consumption estimates were derived by proportioning reported quarterly data by using the ratios of monthly-to-quarterly consumption data in 1979, the last year in which monthly data were reported. Beginning in 1988, monthly coke plant consumption estimates are derived from the reported quarterly data by using monthly ratios of raw steel production data from the American Iron and Steel Institute. The ratios are the monthly raw steel production from open hearth and basic oxygen process furnaces as a proportion of the quarterly production from those kinds of furnaces. Coal coke consumption values also include the relatively small amount consumed for non-combustion use (See Tables 1.11a and 1.11b).

**Industrial Other**—Through 1977, monthly consumption data for the other industrial sector (all industrial users minus coke plants) were derived by using reported data to modify baseline consumption figures from the most recent U.S. Census Bureau Annual Survey of Manufactures or Census of Manufactures. For 1978 and 1979, monthly estimates were derived from data reported on Forms EIA-3 and EIA-6. For 1980–1987, monthly figures were estimated by proportioning quarterly data by using the ratios of monthly-to-quarterly consumption data in 1979, the last year in which monthly data were reported on Form EIA-3. Beginning in 1988, monthly consumption for the other industrial sector is estimated from reported quarterly data by using ratios derived from industrial production indices published by the Board of Governors of the Federal Reserve System. Indices for six major industry groups are used as the basis for calculating the ratios: food manufacturing, which is North American Industry Classification System (NAICS) code 311; paper manufacturing, NAICS 322; chemical manufacturing, NAICS 325; petroleum and coal products, NAICS 324; non-metallic mineral products manufacturing, NAICS 327; and primary metal manufacturing, NAICS 331. The monthly ratios are computed as the monthly sum of the weighted indices as a proportion of the quarterly sum of the weighted indices by using the 1977 proportion as the weights. Through 2007, quarterly consumption data for the other industrial sector were derived by adding beginning stocks at manufacturing plants to current receipts and subtracting ending stocks at manufacturing plants. In this calculation, current receipts are the greater of either reported receipts from manufacturing plants (Form EIA-3) or reported shipments to the other industrial sector (Form EIA-6), thereby ensuring that agriculture, forestry, fishing, and construction consumption data were included where appropriate. Beginning in 2008, quarterly consumption totals for other industrial coal include data for manufacturing and mining only. Over time, surveyed coal consumption data for agriculture, forestry, fishing, and construction dwindled to about 20–30 thousand short tons annually. Therefore, in 2008, EIA consolidated its programs by eliminating agriculture, forestry, fishing, and construction as surveyed sectors.

**Electric Power Sector**—Monthly consumption data for electric power plants are taken directly from reported data.

**Note 3. Coal Stocks.** Coal stocks data are reported by major end-use sector. Forecast data (designated by an “F”) are derived from forecasted values shown in EIA’s *Short-Term Energy Outlook* (DOE/EIA-0202) table titled “U.S. Coal Supply, Consumption, and Inventories.” The monthly estimates are based on the quarterly values (released in March, June, September, and December) or annual values. The estimates are revised as collected data become available from the data sources. Sector-specific information follows.

**Producers and Distributors**—Through 1997, quarterly stocks at producers and distributors were taken directly from reported data. Monthly data were estimated by using one-third of the current quarterly change to indicate the monthly change in stocks. Beginning in 1998, end-of-year stocks are taken from reported data. Monthly stocks are estimated by a model.

**Residential and Commercial**—Through 1979, stock estimates for the residential and commercial sector were taken directly from reported data. For 1980–2007, stock estimates were not collected. Beginning in 2008, quarterly commercial (excluding residential) stocks data are collected on Form EIA-3 (data for “Commercial and Institutional Coal Users”).

**Industrial Coke Plants**—Through 1979, monthly stocks at coke plants were taken directly from reported data. Beginning

in 1980, coke plant stocks are estimated by using one-third of the current quarterly change to indicate the monthly change in stocks. Quarterly stocks are taken directly from data reported on Form EIA-5.

**Industrial Other**—Through 1977, stocks for the other industrial sector were derived by using reported data to modify baseline figures from a one-time Bureau of Mines survey of consumers. For 1978–1982, monthly estimates were derived by judgmentally proportioning reported quarterly data based on representative seasonal patterns of supply and demand. Beginning in 1983, other industrial coal stocks are estimated as indicated above for coke plants. Quarterly stocks are taken directly from data reported on Form EIA-3 and therefore include only manufacturing industries; data for agriculture, forestry, fishing, mining, and construction stocks are not available.

**Electric Power Sector**—Monthly stocks data at electric power plants are taken directly from reported data.

**Note 4. Coal Forecast Values.** Data values preceded by “F” in this section are forecast values. They are derived from EIA’s Short-Term Integrated Forecasting System (STIFS). The model is driven primarily by data and assumptions about key macroeconomic variables, the world oil price, and weather. The coal forecast relies on other variables as well, such as alternative fuel prices (natural gas and oil) and power generation by sources other than fossil fuels, including nuclear and hydroelectric power. Each month, EIA staff review the model output and make adjustments, if appropriate, based on their knowledge of developments in the coal industry.

The STIFS model results are published monthly in EIA’s *Short-Term Energy Outlook*, which is accessible on the Web at <http://www.eia.gov/forecasts/steo/>.

## Table 6.1 Sources

### *Production*

1949–September 1977: U.S. Department of the Interior, Bureau of Mines, *Minerals Yearbook and Minerals Industry Surveys*.

October 1977 forward: U.S. Energy Information Administration (EIA), *Weekly Coal Production*.

### *Waste Coal Supplied*

1989–1997: EIA, Form EIA-867, “Annual Nonutility Power Producer Report.”

1998–2000: EIA, Form EIA-860B, “Annual Electric Generator Report—Nonutility.”

2001–2003: EIA, Form EIA-906, “Power Plant Report,” and Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms.

2004–2007: EIA, Form EIA-906, “Power Plant Report,” Form EIA-920, “Combined Heat and Power Plant Report,” and Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms.

2008 forward: EIA, Form EIA-923, “Power Plant Operations Report,” and Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called, “Quarterly Survey of Non-Electric Sector Coal Data”); and, for forecast values, EIA, Short-Term Integrated Forecasting System.

### *Imports and Exports*

1949 forward: U.S. Department of Commerce, U.S. Census Bureau, Monthly Reports IM 145 (Imports) and EM 545 (Exports).

### *Stock Change*

1950 forward: Calculated from data in Table 6.3.

### *Losses and Unaccounted for*

1949 forward: Calculated as the sum of production, imports, and waste coal supplied, minus exports, stock change, and consumption.



## Table 6.2 Sources

### *Residential and Commercial Total*

Through 2007, coal consumption by the residential and commercial sectors combined is reported to the U.S. Energy Information Administration (EIA). EIA estimates the sectors individually using the method described in Note 2, “Consumption,” at the end of Section 6. Data for the residential and commercial sectors combined are from:

1949–1976: U.S. Department of the Interior (DOI), Bureau of Mines (BOM), *Minerals Yearbook*.

January–September 1977: DOI, BOM, Form 6-1400, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.” October 1977–1979: EIA, Form EIA-2, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

1980–1997: EIA, Form EIA-6, “Coal Distribution Report,” quarterly.

1998–2007: DOI, Mine Safety and Health Administration, Form 7000-2, “Quarterly Coal Consumption and Quality Report—Coke Plants.”

### *Commercial Total*

Beginning in 2008, coal consumption by the commercial (excluding residential) sector is reported to EIA. Data for total commercial consumption are from: 2008 forward: EIA, Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called, “Quarterly Survey of Non-Electric Sector Coal Data”); and, for forecast values, EIA, Short-Term Integrated Forecasting System (STIFS).

### *Commercial CHP*

1989 forward: Table 7.4c.

### *Commercial Other*

1949 forward: Calculated as “Commercial Total” minus “Commercial CHP.”

### *Industrial Coke Plants*

1949–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–1980: EIA, Form EIA-5/5A, “Coke and Coal Chemicals—Monthly/Annual Supplement.”

1981–1984: EIA, Form EIA-5/5A, “Coke Plant Report—Quarterly/Annual Supplement.”

1985 forward: EIA, Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants”; and, for forecast values, EIA, STIFS.

### *Other Industrial Total*

1949–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–1979: EIA, Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms.

1980–1997: EIA, Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms and Form EIA-6, “Coal Distribution Report,” quarterly.

1998–2007: EIA, Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms, Form EIA-6A, “Coal Distribution Report,” annual, and Form EIA-7A, “Coal Production Report,” annual.

2008 forward: EIA, Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called, “Quarterly Survey of Non-Electric Sector Coal Data”) and Form EIA-7A, “Coal Production Report,” annual; and, for forecast values, EIA, STIFS.

### *Other Industrial CHP*

1989 forward: Table 7.4c.

### *Other Industrial Non-CHP*

1949 forward: Calculated as “Other Industrial Total” minus “Other Industrial CHP.”

### *Transportation*

1949–1976: DOI, BOM, *Minerals Yearbook*.

January–September 1977: DOI, BOM, Form 6-1400, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

October–December 1977: EIA, Form EIA-6, “Coal Distribution Report,” quarterly.

### *Electric Power*

1949 forward: Table 7.4b.

## **Table 6.3 Sources**

### *Producers and Distributors*

1973–1979: U.S. Department of the Interior (DOI), Bureau of Mines (BOM), Form 6-1419Q, “Distribution of Bituminous Coal and Lignite Shipments.”

1980–1997: U.S. Energy Information Administration (EIA), Form EIA-6, “Coal Distribution Report,” quarterly.

1998–2007: EIA, Form EIA-6A, “Coal Distribution Report,” annual.

2008 forward: EIA, Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called, “Quarterly Survey of Non-Electric Sector Coal Data”); (data for “Commercial and Institutional Coal Users”); and, for forecast values, EIA, STIFS.

### *Residential and Commercial*

1949–1976: DOI, BOM, *Minerals Yearbook*.

January–September 1977: DOI, BOM, Form 6-1400, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

October 1977–1979: EIA, Form EIA-2, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

2008 forward: EIA, Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Coal Data”); and, for forecast values, EIA, STIFS.

### *Industrial Coke Plants*

1949–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–1980: EIA, Form EIA-5/5A, “Coke and Coal Chemicals—Monthly/Annual.”

1981–1984: EIA, Form EIA-5/5A, “Coke Plant Report—Quarterly/Annual Supplement.”

1985 forward: EIA, Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants” and, for forecast values, EIA, STIFS.

### *Industrial Other*

1949–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–2007: EIA, Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms.

2008 forward: EIA, Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called, “Quarterly Survey of Non-Electric Sector Coal Data”); and, for forecast values, EIA, STIFS.

### *Electric Power*

1949 forward: Table 7.5.


## 7. Electricity

---


**Figure 7.1 Electricity Overview**

(Billion Kilowatthours)


Overview, 2019




Net Generation [a] by Sector, 1989–2019



Net Generation [a] by Sector, Monthly



Trade, 1949–2019



[a] Data are for utility-scale facilities.

[b] Electricity retail sales to ultimate customers reported by electric utilities and other energy service providers.

[c] See “Direct Use” in Glossary.

[d] Includes commercial sector.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.  
Source: Table 7.1.

**Table 7.1 Electricity Overview**  
(Billion Kilowatthours)

	Net Generation <sup>a</sup>				Trade			T&D Losses <sup>f</sup> and Unaccounted for <sup>g</sup>	End Use		
	Electric Power Sector <sup>b</sup>	Com- mercial Sector <sup>c</sup>	Indus- trial Sector <sup>d</sup>	Total	Imports <sup>e</sup>	Exports <sup>e</sup>	Net Imports <sup>e</sup>		Retail Sales <sup>h</sup>	Direct Use <sup>i</sup>	Total
1950 Total .....	329	NA	5	334	2	(s)	2	44	291	NA	291
1955 Total .....	547	NA	3	550	5	(s)	4	58	497	NA	497
1960 Total .....	756	NA	4	759	5	1	5	76	688	NA	688
1965 Total .....	1,055	NA	3	1,058	4	4	(s)	104	954	NA	954
1970 Total .....	1,532	NA	3	1,535	6	4	2	145	1,392	NA	1,392
1975 Total .....	1,918	NA	3	1,921	11	5	6	180	1,747	NA	1,747
1980 Total .....	2,286	NA	3	2,290	25	4	21	216	2,094	NA	2,094
1985 Total .....	2,470	NA	3	2,473	46	5	41	190	2,324	NA	2,324
1990 Total .....	2,901	6	<sup>d</sup> 131	3,038	18	16	2	203	2,713	125	2,837
1995 Total .....	3,194	8	151	3,353	43	4	39	229	3,013	151	3,164
2000 Total .....	3,638	8	157	3,802	49	15	34	244	3,421	171	3,592
2001 Total .....	3,580	7	149	3,737	39	16	22	202	3,394	163	3,557
2002 Total .....	3,698	7	153	3,858	37	16	21	248	3,465	166	3,632
2003 Total .....	3,721	7	155	3,883	30	24	6	228	3,494	168	3,662
2004 Total .....	3,808	8	154	3,971	34	23	11	266	3,547	168	3,716
2005 Total .....	3,902	8	145	4,055	44	19	25	269	3,661	150	3,811
2006 Total .....	3,908	8	148	4,065	43	24	18	266	3,670	147	3,817
2007 Total .....	4,005	8	143	4,157	51	20	31	298	3,765	126	3,890
2008 Total .....	3,974	8	137	4,119	57	24	33	286	3,734	132	3,866
2009 Total .....	3,810	8	132	3,950	52	18	34	261	3,597	127	3,724
2010 Total .....	3,972	9	144	4,125	45	19	26	264	3,755	132	3,887
2011 Total .....	3,948	10	142	4,100	52	15	37	255	3,750	133	3,883
2012 Total .....	3,890	11	146	4,048	59	12	47	263	3,695	138	3,832
2013 Total .....	3,904	12	150	4,066	69	11	58	256	3,725	143	3,868
2014 Total .....	3,937	13	144	4,094	67	13	53	244	3,765	139	3,903
2015 Total .....	3,919	13	146	4,078	76	9	67	244	3,759	141	3,900
2016 Total .....	3,918	13	146	4,077	73	6	67	241	3,762	140	3,902
2017 Total .....	3,877	13	144	4,034	66	9	56	226	3,723	141	3,864
2018 January .....	359	1	13	373	5	1	4	20	344	<sup>E</sup> 12	357
February .....	295	1	11	307	5	1	4	7	293	<sup>E</sup> 11	304
March .....	309	1	12	322	6	1	4	17	297	<sup>E</sup> 12	309
April .....	289	1	11	301	5	2	3	14	278	<sup>E</sup> 11	289
May .....	326	1	12	339	5	1	4	28	303	<sup>E</sup> 12	315
June .....	359	1	12	372	5	1	4	26	338	<sup>E</sup> 12	350
July .....	397	1	13	411	5	1	4	28	375	<sup>E</sup> 13	388
August .....	393	1	13	408	6	1	5	19	381	<sup>E</sup> 13	394
September .....	343	1	12	356	4	1	3	10	337	<sup>E</sup> 12	349
October .....	312	1	12	325	4	1	3	7	309	<sup>E</sup> 12	321
November .....	309	1	12	322	4	1	3	22	291	<sup>E</sup> 12	302
December .....	328	1	13	342	4	1	3	21	312	<sup>E</sup> 12	325
Total .....	4,018	13	147	4,178	58	14	44	219	3,859	144	4,003
2019 January .....	345	1	13	359	5	1	3	22	329	<sup>E</sup> 13	341
February .....	303	1	11	315	5	1	3	11	296	<sup>E</sup> 11	307
March .....	313	1	12	327	5	3	2	15	302	<sup>E</sup> 12	314
April .....	284	1	11	297	4	2	2	14	274	<sup>E</sup> 11	285
May .....	317	1	12	330	5	2	3	25	297	<sup>E</sup> 11	308
June .....	340	1	12	353	5	2	4	23	321	<sup>E</sup> 12	333
July .....	395	1	13	410	6	2	4	25	376	<sup>E</sup> 13	389
August .....	387	1	13	401	6	2	4	20	373	<sup>E</sup> 13	385
September .....	347	1	12	360	5	2	4	11	340	<sup>E</sup> 12	353
October .....	307	1	12	320	4	1	2	2	308	<sup>E</sup> 12	320
November .....	302	1	13	316	5	1	4	22	286	<sup>E</sup> 12	298
December .....	324	1	13	338	5	1	4	20	310	<sup>E</sup> 13	322
Total .....	3,965	14	149	4,127	59	20	39	211	3,811	143	3,955
2020 January .....	326	1	13	340	5	1	3	19	311	<sup>E</sup> 13	324
February .....	305	1	12	318	4	2	3	19	290	<sup>E</sup> 12	302
March .....	294	1	12	307	5	1	4	14	285	<sup>E</sup> 12	297
April .....	264	1	11	276	5	1	3	10	258	<sup>E</sup> 11	269
May .....	292	1	11	304	5	2	4	26	270	<sup>E</sup> 11	281
June .....	340	1	12	353	5	1	4	30	316	<sup>E</sup> 11	327
July .....	401	1	12	415	7	1	5	33	375	<sup>E</sup> 12	387
August .....	386	1	12	400	7	1	6	30	364	<sup>E</sup> 12	376
September .....	322	1	11	334	5	1	4	9	318	<sup>E</sup> 11	329
October .....	302	1	11	314	<sup>F</sup> 4	<sup>F</sup> 1	<sup>F</sup> 4	12	296	<sup>E</sup> 11	307
November .....	289	1	12	302	<sup>F</sup> 4	<sup>F</sup> 1	<sup>F</sup> 4	22	273	<sup>E</sup> 11	284
11-Month Total ...	3,520	12	130	3,663	56	13	43	224	3,356	<sup>E</sup> 126	3,482
2019 11-Month Total ...	3,641	13	135	3,789	54	19	35	191	3,501	<sup>E</sup> 131	3,632
2018 11-Month Total ...	3,690	12	134	3,836	54	13	41	199	3,547	<sup>E</sup> 132	3,679

<sup>a</sup> Electricity net generation at utility-scale facilities. Does not include distributed (small-scale) solar photovoltaic (PV) generation shown on Table 10.6. See Note 1, "Coverage of Electricity Statistics," at end of section.

<sup>b</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>c</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>d</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants. Through 1988, data are for industrial hydroelectric power only.

<sup>e</sup> Electricity transmitted across U.S. borders. Net imports equal imports minus exports.

<sup>f</sup> Transmission and distribution losses (electricity losses that occur between the point of generation and delivery to the customer). See Note 1, "Electrical System Energy Losses," at end of Section 2.

<sup>g</sup> Data collection frame differences and nonsampling error.

<sup>h</sup> Electricity retail sales to ultimate customers by electric utilities and, beginning

in 1996, other energy service providers.

<sup>i</sup> Use of electricity that is 1) self-generated, 2) produced by either the same entity that consumes the power or an affiliate, and 3) used in direct support of a service or industrial process located within the same facility or group of facilities that house the generating equipment. Direct use is exclusive of station use.

<sup>E</sup>=Estimate. <sup>NA</sup>=Not available. <sup>F</sup>=Forecast. (s)=Less than 0.5 billion kilowatthours.

Notes: • See Note 1, "Coverage of Electricity Statistics," and Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of section.

• Data values preceded by "F" are derived from the U.S. Energy Information Administration's Short-Term Integrated Forecasting System. See Note 3, "Electricity Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 7.2 Electricity Net Generation**

(Billion Kilowatthours)


Total (All Sectors), Major Sources, 1949–2019




Total (All Sectors), Major Sources, Monthly




Electric Power Sector, Major Sources, 2019



Commercial Sector, Major Sources, 2019



Industrial Sector, Major Sources, 2019



[a] Conventional hydroelectric power, wood, waste, geothermal, solar, and wind.

[b] Blast furnace gas, and other manufactured and waste derived from fossil fuels.

[c] Conventional hydroelectric power.

Note: Data are for utility-scale facilities.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.

Sources: Tables 7.2a–7.2c.

**Table 7.2a Electricity Net Generation: Total (All Sectors)**  
(Sum of Tables 7.2b and 7.2c; Million Kilowatthours)

	Fossil Fuels				Nuclear Electric Power	Hydro-electric Pumped Storage <sup>a</sup>	Renewable Energy						Total
	Coal <sup>a</sup>	Petroleum <sup>b</sup>	Natural Gas <sup>c</sup>	Other Gases <sup>d</sup>			Conventional Hydro-electric Power <sup>f</sup>	Biomass		Geo-thermal	Solar <sup>i</sup>	Wind	
								Wood <sup>g</sup>	Waste <sup>h</sup>				
1950 Total .....	154,520	33,734	44,559	NA	0	{ }	100,885	390	NA	NA	NA	NA	334,088
1955 Total .....	301,363	37,138	95,285	NA	0	{ }	116,236	276	NA	NA	NA	NA	550,299
1960 Total .....	403,067	47,987	157,970	NA	518	{ }	149,440	140	NA	33	NA	NA	759,156
1965 Total .....	570,926	64,801	221,559	NA	3,657	{ }	196,984	269	NA	189	NA	NA	1,058,386
1970 Total .....	704,394	184,183	372,890	NA	21,804	{ }	250,957	136	220	525	NA	NA	1,535,111
1975 Total .....	852,786	289,095	299,778	NA	172,505	{ }	303,153	18	174	3,246	NA	NA	1,920,755
1980 Total .....	1,161,562	245,994	346,240	NA	251,116	{ }	279,182	275	158	5,073	NA	NA	2,289,600
1985 Total .....	1,402,128	100,202	291,946	NA	383,691	{ }	284,311	743	640	9,325	11	6	2,473,002
1990 Total <sup>k</sup> .....	1,594,011	126,460	372,765	10,383	576,862	-3,508	292,866	32,522	13,260	15,434	367	2,789	3,037,827
1995 Total .....	1,709,426	74,554	496,058	13,870	673,402	-2,725	310,833	36,521	20,405	13,378	497	3,164	3,353,487
2000 Total .....	1,966,265	111,221	601,038	13,955	753,893	-5,539	275,573	37,595	23,131	14,093	493	5,593	3,802,105
2001 Total .....	1,903,956	124,880	639,129	9,039	768,826	-8,823	216,961	35,200	14,548	13,741	543	6,737	3,736,644
2002 Total .....	1,933,130	94,567	691,006	11,463	780,064	-8,743	264,329	38,665	15,044	14,491	555	10,354	3,858,452
2003 Total .....	1,973,737	119,406	649,908	15,600	763,733	-8,535	275,806	37,529	15,812	14,424	534	11,187	3,883,185
2004 Total .....	1,978,301	121,145	710,100	15,252	788,528	-8,488	268,417	38,117	15,421	14,811	575	14,144	3,970,555
2005 Total .....	2,012,873	122,225	760,960	13,464	781,986	-6,558	270,321	38,856	15,420	14,692	550	17,811	4,055,423
2006 Total .....	1,990,511	64,166	816,441	14,177	787,219	-6,558	289,246	38,762	16,099	14,568	508	26,589	4,064,702
2007 Total .....	2,016,456	65,739	896,590	13,453	806,425	-6,896	247,510	39,014	16,525	14,637	612	34,450	4,156,745
2008 Total .....	1,985,801	46,243	882,981	11,707	806,208	-6,288	254,831	37,300	17,734	14,840	864	55,363	4,119,388
2009 Total .....	1,755,904	38,937	920,979	10,632	798,855	-4,627	273,445	36,050	18,443	15,009	891	73,886	3,950,331
2010 Total .....	1,847,290	37,061	987,697	11,313	806,968	-5,501	260,203	37,172	18,917	15,219	1,212	94,652	4,125,060
2011 Total .....	1,733,430	30,182	1,013,689	11,566	790,204	-6,421	319,355	37,449	19,222	15,316	1,818	120,177	4,100,141
2012 Total .....	1,514,043	23,190	1,225,894	11,898	769,331	-4,950	276,240	37,799	19,823	15,562	4,327	140,822	4,047,765
2013 Total .....	1,581,115	27,164	1,124,836	12,853	789,016	-4,681	268,565	40,028	20,830	15,775	9,036	167,840	4,065,964
2014 Total .....	1,581,710	30,232	1,126,609	12,022	797,166	-6,174	259,367	42,340	21,650	15,877	17,691	181,655	4,093,606
2015 Total .....	1,352,398	28,249	1,333,482	13,117	797,178	-5,091	249,080	41,929	21,703	15,918	24,893	190,719	4,077,601
2016 Total .....	1,239,149	24,205	1,378,307	12,807	805,694	-6,686	267,812	40,947	21,813	15,826	36,054	226,993	4,076,675
2017 Total .....	1,205,835	21,390	1,296,442	12,469	804,950	-6,495	300,333	41,124	21,610	15,927	53,287	254,303	4,034,271
2018 January .....	119,284	6,520	110,293	1,097	74,649	-547	25,064	3,686	1,817	1,341	3,319	25,599	373,230
February .....	82,050	1,558	98,512	1,092	64,790	-315	24,902	3,235	1,716	1,274	3,896	23,189	306,894
March .....	80,626	1,472	106,524	1,158	67,033	-490	25,861	3,547	1,822	1,367	5,056	26,464	321,547
April .....	73,346	1,538	98,371	1,099	59,133	-377	28,115	3,102	1,726	1,188	6,057	26,431	300,756
May .....	85,227	1,557	115,284	1,167	67,320	-390	30,444	3,352	1,732	1,383	6,849	23,953	338,948
June .....	101,503	1,901	130,826	1,091	69,688	-433	27,597	3,471	1,720	1,300	7,415	24,703	371,886
July .....	115,376	1,901	164,749	1,172	72,456	-644	25,100	3,749	1,750	1,370	6,755	16,447	411,290
August .....	115,129	1,927	161,676	1,301	72,282	-747	22,017	3,630	1,758	1,367	6,695	19,846	408,028
September .....	96,544	1,854	141,786	1,104	64,725	-603	19,166	3,281	1,590	1,328	5,961	18,520	356,258
October .....	87,264	1,577	123,142	1,016	59,397	-492	19,548	3,216	1,743	1,273	4,970	21,194	324,932
November .....	92,819	1,661	108,168	1,045	63,954	-343	21,913	3,264	1,724	1,331	3,743	22,016	322,369
December .....	100,319	1,761	109,802	1,120	71,657	-522	22,797	3,404	1,799	1,446	3,110	24,306	342,139
Total .....	1,149,487	25,226	1,469,133	13,463	807,084	-5,905	292,524	40,936	20,896	15,967	63,825	272,667	4,178,277
2019 January .....	100,905	2,221	121,582	1,025	73,701	-323	24,798	3,465	1,672	1,390	3,580	24,248	359,457
February .....	79,929	1,514	112,135	948	64,715	-389	22,881	3,042	1,498	1,293	3,836	22,547	314,951
March .....	78,352	1,401	115,806	1,086	65,080	-409	26,334	3,217	1,625	1,422	5,899	25,677	326,568
April .....	59,922	1,189	104,053	948	60,581	-103	27,820	2,807	1,510	1,254	6,752	28,854	296,602
May .....	71,885	1,685	117,053	1,054	67,124	-368	31,982	3,051	1,564	1,342	7,162	25,695	330,343
June .....	78,540	1,529	137,828	1,009	68,805	-385	28,078	3,159	1,581	1,328	7,971	22,385	352,928
July .....	100,771	1,800	171,942	1,185	72,199	-622	24,875	3,498	1,617	1,375	8,133	22,043	409,973
August .....	94,040	1,738	174,955	1,147	71,911	-579	22,579	3,539	1,636	1,393	7,877	19,951	401,397
September .....	85,707	1,512	149,688	1,112	66,064	-671	18,526	3,211	1,530	1,368	6,817	24,448	360,452
October .....	66,777	1,151	130,941	924	62,033	-373	18,306	3,063	1,573	1,141	6,093	27,521	320,250
November .....	75,549	1,240	117,904	1,047	64,125	-509	20,218	3,137	1,525	984	4,364	25,042	315,708
December .....	72,581	1,459	131,830	1,107	73,074	-529	21,478	3,355	1,633	1,183	3,453	26,496	338,253
Total .....	964,957	18,438	1,585,717	12,591	809,409	-5,261	287,874	38,543	18,964	15,473	71,937	294,906	4,126,882
2020 January .....	65,100	1,626	133,154	1,104	74,170	-377	25,425	3,345	1,672	1,265	4,690	28,149	340,408
February .....	56,101	1,266	125,554	1,132	65,950	-247	26,393	3,145	1,515	1,274	5,717	29,092	317,853
March .....	50,643	1,399	123,654	1,009	63,997	-353	23,423	3,196	1,682	1,517	6,434	29,204	306,887
April .....	40,593	1,227	107,929	747	59,170	-325	21,957	2,970	1,594	1,450	8,048	29,336	275,763
May .....	46,529	1,294	115,855	808	64,338	-367	30,559	3,099	1,617	1,449	9,734	28,163	304,167
June .....	65,274	1,673	143,180	756	67,205	-499	29,138	2,993	1,459	1,369	9,529	29,872	352,967
July .....	89,845	1,870	185,433	854	69,385	-686	27,753	3,112	1,564	1,431	10,379	22,579	414,610
August .....	91,165	1,735	174,130	1,002	68,982	-784	24,228	3,302	1,589	1,426	9,370	22,571	399,812
September .....	68,396	1,252	141,407	947	65,727	-525	19,182	2,938	1,512	1,390	7,757	23,176	334,167
October .....	59,840	1,233	131,644	897	59,362	-423	18,350	2,802	1,516	1,379	7,326	29,419	314,401
November .....	61,291	1,404	107,821	938	61,760	-369	22,069	3,105	1,476	1,487	5,890	33,848	301,776
11-Month Total .....	694,777	15,979	1,489,761	10,194	720,048	-4,954	268,478	34,008	17,196	15,437	84,875	305,409	3,662,811
2019 11-Month Total .....	892,376	16,979	1,453,887	11,484	736,336	-4,731	266,396	35,188	17,330	14,290	68,484	268,411	3,788,629
2018 11-Month Total .....	1,049,169	23,465	1,359,331	12,342	735,427	-5,382	269,727	37,532	19,096	14,521	60,716	248,361	3,836,138

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, waste oil, and, beginning in 2011, propane.

<sup>c</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>d</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>e</sup> Pumped storage facility production minus energy used for pumping.

<sup>f</sup> Through 1989, hydroelectric pumped storage is included in "Conventional Hydroelectric Power."

<sup>g</sup> Wood and wood-derived fuels.

<sup>h</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>i</sup> Electricity net generation from solar thermal and photovoltaic (PV) energy at utility-scale facilities. Does not include distributed (small-scale) solar photovoltaic

generation. See Table 10.6.

<sup>j</sup> Includes batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, all data except hydroelectric are for electric utilities only; hydroelectric data through 1988 include industrial plants as well as electric utilities. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

NA=Not available.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section, "Table 7.2b Sources" and "Table 7.2c Sources."

**Table 7.2b Electricity Net Generation: Electric Power Sector**  
(Subset of Table 7.2a; Million Kilowatthours)

	Fossil Fuels				Nuclear Electric Power	Hydro- electric Pumped Storage <sup>e</sup>	Renewable Energy						Total <sup>j</sup>
	Coal <sup>a</sup>	Petro- leum <sup>b</sup>	Natural Gas <sup>c</sup>	Other Gases <sup>d</sup>			Conven- tional Hydro- electric Power <sup>f</sup>	Biomass		Geo- thermal	Solar <sup>i</sup>	Wind	
								Wood <sup>g</sup>	Waste <sup>h</sup>				
1950 Total .....	154,520	33,734	44,559	NA	0	{ f }	95,938	390	NA	NA	NA	NA	329,141
1955 Total .....	301,363	37,138	95,285	NA	0	{ f }	112,975	276	NA	NA	NA	NA	547,038
1960 Total .....	403,067	47,987	157,970	NA	518	{ f }	145,833	140	NA	33	NA	NA	755,549
1965 Total .....	570,926	64,801	221,559	NA	3,657	{ f }	193,851	269	NA	189	NA	NA	1,055,252
1970 Total .....	704,394	184,183	372,890	NA	21,804	{ f }	247,714	136	220	525	NA	NA	1,531,868
1975 Total .....	852,786	289,095	299,778	NA	172,505	{ f }	300,047	18	174	3,246	NA	NA	1,917,649
1980 Total .....	1,161,562	245,994	346,240	NA	251,116	{ f }	276,021	275	158	5,073	NA	NA	2,286,439
1985 Total .....	1,402,128	100,202	291,946	NA	383,691	{ f }	281,149	743	640	9,325	11	6	2,469,841
1990 Total <sup>k</sup> .....	1,572,109	118,864	309,486	621	576,862	-3,508	289,753	7,032	11,500	15,434	367	2,789	2,901,322
1995 Total .....	1,686,056	68,146	419,179	1,927	673,402	-2,725	305,410	7,597	17,986	13,378	497	3,164	3,194,230
2000 Total .....	1,943,111	105,192	517,978	2,028	753,893	-5,539	271,338	8,916	20,307	14,093	493	5,593	3,637,529
2001 Total .....	1,882,826	119,149	554,940	586	768,826	-8,823	213,749	8,294	12,944	13,741	543	6,737	3,580,053
2002 Total .....	1,910,613	89,733	607,683	1,970	780,064	-8,743	260,491	9,009	13,145	14,491	555	10,354	3,698,458
2003 Total .....	1,952,714	113,697	567,303	2,647	763,733	-8,535	271,512	9,528	13,808	14,424	534	11,187	3,721,159
2004 Total .....	1,957,188	114,678	627,172	3,568	788,528	-8,488	265,064	9,736	13,062	14,811	575	14,144	3,808,360
2005 Total .....	1,992,054	116,482	683,829	3,777	781,986	-6,558	267,040	10,570	13,031	14,692	550	17,811	3,902,192
2006 Total .....	1,969,737	59,708	734,417	4,254	787,219	-6,558	286,254	10,341	13,927	14,568	508	26,589	3,908,077
2007 Total .....	1,998,390	61,306	814,752	4,042	806,425	-6,896	245,843	10,711	14,294	14,637	612	34,450	4,005,343
2008 Total .....	1,968,838	42,881	802,372	3,200	806,208	-6,288	253,096	10,638	15,379	14,840	864	55,363	3,974,349
2009 Total .....	1,741,123	35,811	841,006	3,058	798,855	-4,627	271,506	10,738	15,954	15,009	891	73,886	3,809,837
2010 Total .....	1,827,738	34,679	901,389	2,967	806,968	-5,501	258,455	11,446	16,376	15,219	1,206	94,636	3,972,386
2011 Total .....	1,717,891	28,202	926,290	2,939	790,204	-6,421	317,531	10,733	15,989	15,316	1,727	120,121	3,948,186
2012 Total .....	1,500,557	20,072	1,132,791	2,984	769,331	-4,950	273,859	11,050	16,555	15,562	4,164	140,749	3,890,358
2013 Total .....	1,567,722	24,510	1,028,949	4,322	789,016	-4,681	265,058	12,302	16,918	15,775	8,724	167,742	3,903,715
2014 Total .....	1,568,774	28,043	1,033,172	3,358	797,166	-6,174	258,046	15,027	17,602	15,877	17,304	181,496	3,937,003
2015 Total .....	1,340,993	26,505	1,237,656	3,715	797,178	-5,091	247,636	14,563	17,823	15,918	24,456	190,547	3,919,294
2016 Total .....	1,229,663	22,710	1,279,380	3,912	805,694	-6,686	266,326	13,420	18,183	15,826	35,497	226,790	3,918,078
2017 Total .....	1,197,838	20,039	1,196,753	4,126	804,950	-6,495	298,711	13,641	18,084	15,927	52,724	254,074	3,877,453
2018 January .....	118,557	6,348	101,469	344	74,649	-547	24,962	1,320	1,532	1,341	3,288	25,570	359,449
February .....	81,399	1,451	90,702	337	64,790	-315	24,794	1,137	1,455	1,274	3,863	23,165	294,633
March .....	79,983	1,368	98,597	348	67,033	-490	25,752	1,200	1,534	1,367	5,009	26,435	308,747
April .....	72,787	1,446	90,614	354	59,133	-377	27,990	948	1,450	1,188	6,002	26,406	288,509
May .....	84,634	1,453	107,014	389	67,320	-390	30,319	1,038	1,456	1,383	6,788	23,932	325,905
June .....	100,894	1,795	122,172	316	69,688	-433	27,502	1,168	1,460	1,300	7,347	24,683	358,523
July .....	114,749	1,784	155,264	359	72,456	-644	25,003	1,271	1,480	1,370	6,691	16,432	396,854
August .....	114,516	1,829	152,150	392	72,282	-747	21,908	1,217	1,483	1,367	6,634	19,830	393,497
September .....	95,962	1,762	132,992	332	64,725	-603	19,060	1,044	1,341	1,328	5,911	18,502	342,917
October .....	86,736	1,473	114,533	254	59,397	-492	19,426	989	1,465	1,273	4,926	21,170	311,750
November .....	92,258	1,565	99,419	311	63,954	-343	21,781	1,030	1,453	1,331	3,711	21,991	309,062
December .....	99,698	1,655	100,896	349	71,657	-522	22,651	1,022	1,514	1,413	3,083	24,282	328,320
Total .....	1,142,173	23,928	1,365,822	4,086	807,084	-5,905	291,148	13,385	17,623	15,934	63,253	272,396	4,018,167
2019 January .....	100,294	2,112	112,137	360	73,701	-323	24,658	1,141	1,412	1,348	3,546	24,220	345,271
February .....	79,382	1,427	103,943	351	64,715	-389	22,772	947	1,266	1,252	3,798	22,522	302,559
March .....	77,819	1,318	107,117	383	65,080	-409	26,208	939	1,364	1,378	5,841	25,651	313,296
April .....	59,426	1,096	95,855	329	60,581	-103	27,695	769	1,276	1,227	6,690	28,826	284,248
May .....	71,388	1,607	108,439	324	67,124	-368	31,857	965	1,347	1,304	7,095	25,672	317,418
June .....	78,043	1,444	128,921	329	68,805	-385	27,965	975	1,346	1,294	7,898	22,365	339,649
July .....	100,225	1,658	162,237	372	72,199	-622	24,788	1,151	1,383	1,342	8,053	22,027	395,482
August .....	93,517	1,644	165,127	377	71,911	-579	22,504	1,172	1,393	1,362	7,803	19,936	386,872
September .....	85,216	1,425	140,473	342	66,064	-671	18,461	1,045	1,303	1,338	6,754	24,428	346,828
October .....	66,311	1,065	121,927	189	62,033	-373	18,232	899	1,334	1,103	6,040	27,495	306,897
November .....	75,046	1,153	108,676	326	64,125	-509	20,139	957	1,288	941	4,323	25,017	302,111
December .....	72,065	1,369	122,189	354	73,074	-529	21,374	1,060	1,380	1,140	3,423	26,468	324,025
Total .....	958,732	17,318	1,477,042	4,037	809,409	-5,261	286,652	12,020	16,091	15,031	71,265	294,628	3,964,656
2020 January .....	64,547	1,528	123,290	354	74,170	-377	25,315	1,053	1,423	1,229	4,648	28,124	325,954
February .....	55,577	1,187	116,645	370	65,950	-247	26,282	1,004	1,284	1,233	5,667	29,065	304,601
March .....	50,143	1,315	114,756	288	63,997	-353	23,311	953	1,437	1,473	6,374	29,177	293,532
April .....	40,158	1,164	100,045	150	59,170	-325	21,847	826	1,364	1,410	7,975	29,308	263,720
May .....	46,094	1,217	107,833	161	64,338	-367	30,441	950	1,382	1,410	9,646	28,138	291,868
June .....	64,860	1,583	134,637	133	67,205	-499	29,029	912	1,247	1,336	9,444	29,795	340,254
July .....	89,382	1,772	176,303	162	69,385	-686	27,649	997	1,339	1,401	10,287	22,496	401,133
August .....	90,727	1,642	164,983	303	68,982	-784	24,131	1,159	1,365	1,396	9,290	22,499	386,347
September .....	67,925	1,173	133,094	297	65,727	-525	19,096	847	1,307	1,357	7,690	23,090	321,674
October .....	59,386	1,148	123,631	238	59,362	-423	18,266	808	1,292	1,341	7,263	29,308	302,214
November .....	60,854	1,310	99,569	306	61,760	-369	21,973	922	1,253	1,446	5,839	33,727	289,190
11-Month Total .....	689,653	15,039	1,394,786	2,761	720,048	-4,954	267,341	10,430	14,692	15,032	84,124	304,726	3,520,489
2019 11-Month Total .....	886,667	15,949	1,354,853	3,683	736,336	-4,731	265,278	10,960	14,711	13,891	67,841	268,160	3,640,631
2018 11-Month Total .....	1,042,475	22,273	1,264,926	3,737	735,427	-5,382	268,497	12,363	16,110	14,521	60,170	248,115	3,689,847

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, waste oil, and, beginning in 2011, propane.

<sup>c</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>d</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>e</sup> Pumped storage facility production minus energy used for pumping.

<sup>f</sup> Through 1989, hydroelectric pumped storage is included in "Conventional Hydroelectric Power."

<sup>g</sup> Wood and wood-derived fuels.

<sup>h</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>i</sup> Electricity net generation from solar thermal and photovoltaic (PV) energy at utility-scale facilities. Does not include distributed (small-scale) solar photovoltaic

generation. See Table 10.6.

<sup>j</sup> Includes batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

NA=Not available.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of



**Table 7.2c Electricity Net Generation: Commercial and Industrial Sectors**  
(Subset of Table 7.2a; Million Kilowatthours)

	Commercial Sector <sup>a</sup>					Industrial Sector <sup>b</sup>							
	Coal <sup>c</sup>	Petro- leum <sup>d</sup>	Natural Gas <sup>e</sup>	Biomass Waste <sup>f</sup>	Total <sup>g</sup>	Coal <sup>c</sup>	Petro- leum <sup>d</sup>	Natural Gas <sup>e</sup>	Other Gases <sup>h</sup>	Hydro- electric Power <sup>i</sup>	Biomass		Total <sup>k</sup>
											Wood <sup>j</sup>	Waste <sup>l</sup>	
1950 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	4,946	NA	NA	4,946
1955 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,261	NA	NA	3,261
1960 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,607	NA	NA	3,607
1965 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,134	NA	NA	3,134
1970 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,244	NA	NA	3,244
1975 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,106	NA	NA	3,106
1980 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,161	NA	NA	3,161
1985 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,161	NA	NA	3,161
1990 Total .....	796	589	3,272	812	5,837	21,107	7,008	60,007	9,641	2,975	25,379	949	130,830
1995 Total .....	998	379	5,162	1,519	8,232	22,372	6,030	71,717	11,943	5,304	28,868	900	151,025
2000 Total .....	1,097	432	4,262	1,985	7,903	22,056	5,597	78,798	11,927	4,135	28,652	839	156,673
2001 Total .....	995	438	4,434	1,007	7,416	20,135	5,293	79,755	8,454	3,145	26,888	596	149,175
2002 Total .....	992	431	4,310	1,053	7,415	21,525	4,403	79,013	9,493	3,825	29,643	846	152,580
2003 Total .....	1,206	423	3,899	1,289	7,496	19,817	5,285	78,705	12,953	4,222	27,988	715	154,530
2004 Total .....	1,340	499	3,969	1,562	8,270	19,773	5,967	78,959	11,684	3,248	28,367	797	153,925
2005 Total .....	1,353	375	4,249	1,657	8,492	19,466	5,368	72,882	9,687	3,195	28,271	733	144,739
2006 Total .....	1,310	235	4,355	1,599	8,371	19,464	4,223	77,669	9,923	2,899	28,400	572	148,254
2007 Total .....	1,371	189	4,257	1,599	8,273	16,694	4,243	77,580	9,411	1,590	28,287	631	143,128
2008 Total .....	1,261	142	4,188	1,534	7,926	15,703	3,219	76,421	8,507	1,676	26,641	821	137,113
2009 Total .....	1,096	163	4,225	1,748	8,165	13,686	2,963	75,748	7,574	1,868	25,292	740	132,329
2010 Total .....	1,111	124	4,725	1,672	8,592	18,441	2,258	81,583	8,343	1,668	25,706	869	144,082
2011 Total .....	1,049	89	5,487	2,315	10,080	14,490	1,891	81,911	8,624	1,799	26,691	917	141,875
2012 Total .....	883	196	6,603	2,319	11,301	12,603	2,922	86,500	8,913	2,353	26,725	948	146,107
2013 Total .....	839	124	7,154	2,567	12,234	12,554	2,531	88,733	8,531	3,463	27,691	1,346	150,015
2014 Total .....	595	255	7,227	2,681	12,520	12,341	1,934	86,209	8,664	1,282	27,239	1,367	144,083
2015 Total .....	509	191	7,471	2,637	12,595	10,896	1,552	88,355	9,401	1,410	27,318	1,243	145,712
2016 Total .....	383	82	7,730	2,496	12,706	9,103	1,412	91,197	8,895	1,269	27,458	1,134	145,890
2017 Total .....	329	112	8,042	2,515	13,060	7,669	1,239	91,647	8,343	1,382	27,412	1,012	143,758
2018 January .....	40	42	671	203	1,114	687	130	8,153	752	83	2,357	81	12,668
February .....	32	8	626	184	995	619	99	7,184	755	89	2,091	77	11,265
March .....	27	9	647	204	1,058	616	95	7,280	811	87	2,342	84	11,742
April .....	24	9	585	199	989	535	83	7,172	744	102	2,151	77	11,258
May .....	21	7	656	203	1,076	572	97	7,614	778	101	2,310	73	11,967
June .....	20	7	737	202	1,163	590	98	7,918	775	74	2,294	57	12,199
July .....	21	11	875	205	1,298	606	106	8,609	813	78	2,470	65	13,138
August .....	23	9	892	208	1,318	590	89	8,634	909	91	2,402	66	13,212
September .....	24	8	771	193	1,156	558	85	8,022	773	90	2,228	56	12,185
October .....	20	7	668	204	1,055	507	97	7,941	762	108	2,223	74	12,127
November .....	25	13	622	193	993	536	83	8,127	734	116	2,231	78	12,313
December .....	24	10	669	205	1,095	596	95	8,237	771	130	2,374	80	12,724
Total .....	303	140	8,419	2,404	13,312	7,011	1,157	94,892	9,377	1,149	27,475	868	146,798
2019 January .....	29	21	706	195	1,160	581	88	8,739	664	124	2,317	65	13,025
February .....	27	10	654	171	1,057	521	77	7,538	597	94	2,086	61	11,335
March .....	33	9	711	189	1,173	500	74	7,978	702	108	2,267	71	12,099
April .....	22	8	646	168	1,053	475	85	7,552	619	106	2,034	65	11,301
May .....	18	7	663	159	1,072	479	70	7,951	730	104	2,084	58	11,854
June .....	13	6	711	178	1,133	484	79	8,196	680	95	2,179	57	12,147
July .....	18	9	869	180	1,313	528	133	8,837	813	71	2,331	55	13,178
August .....	17	12	852	185	1,290	506	83	8,976	770	59	2,357	57	13,236
September .....	21	10	731	179	1,150	470	77	8,483	770	52	2,157	48	12,474
October .....	21	9	666	173	1,072	445	76	8,348	735	63	2,157	67	12,281
November .....	23	9	667	171	1,066	480	77	8,561	721	67	2,174	67	12,531
December .....	27	11	735	181	1,151	489	80	8,906	753	91	2,289	72	13,077
Total .....	268	121	8,610	2,129	13,689	5,957	1,000	100,065	8,554	1,033	26,433	743	148,537
2020 January .....	22	11	748	177	1,164	530	87	9,115	750	93	2,284	72	13,290
February .....	29	6	672	166	1,080	495	73	8,237	763	92	2,135	65	12,172
March .....	22	6	648	181	1,078	477	78	8,250	721	96	2,238	65	12,277
April .....	13	5	550	165	953	422	58	7,334	596	95	2,144	64	11,090
May .....	14	7	599	174	1,039	422	69	7,423	647	95	2,146	62	11,259
June .....	17	7	672	163	1,095	398	83	7,871	623	86	2,074	49	11,618
July .....	17	10	809	173	1,255	447	88	8,322	692	84	2,101	52	12,221
August .....	15	10	790	172	1,219	423	82	8,357	699	80	2,130	51	12,246
September .....	24	8	710	162	1,110	446	71	7,602	650	73	2,084	44	11,382
October .....	17	8	617	163	1,017	437	77	7,396	659	71	1,985	61	11,170
November .....	19	8	616	166	1,016	417	87	7,636	632	81	2,175	57	11,570
11-Month Total ...	209	88	7,431	1,863	12,025	4,915	852	87,544	7,433	946	23,497	641	130,297
2019 11-Month Total ...	241	110	7,875	1,948	12,538	5,468	920	91,159	7,801	943	24,144	671	135,461
2018 11-Month Total ...	279	129	7,750	2,199	12,217	6,415	1,062	86,655	8,605	1,019	25,101	788	134,074

<sup>a</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>d</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>g</sup> Includes a small amount of conventional hydroelectric power, geothermal, other gases, solar photovoltaic (PV) energy, wind, wood, and other, which are not separately displayed. Does not include distributed (small-scale) solar photovoltaic generation, shown on Table 10.6.

<sup>h</sup> Blast furnace gas, and other manufactured and waste gases derived from

fossil fuels. Through 2010, also includes propane gas.

<sup>i</sup> Conventional hydroelectric power.

<sup>j</sup> Wood and wood-derived fuels.

<sup>k</sup> Includes photovoltaic (PV) energy, wind, batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels). Does not include distributed (small-scale) solar photovoltaic generation shown on Table 10.6.

NA=Not available.


Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: See end of section.

**Figure 7.3 Consumption of Selected Combustible Fuels for Electricity Generation**


Coal by Sector, 1989–2019




Petroleum by Sector, 1989–2019




Natural Gas by Sector, 1989–2019




Other Gases [b] by Sector, 1989–2019



Wood by Sector, 1989–2019



Waste by Sector, 1989–2019



[a] Includes commercial sector.

[b] Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

Note: Data are for utility-scale facilities.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.

Sources: Tables 7.3a-7.3c.

**Table 7.3a Consumption of Combustible Fuels for Electricity Generation:  
Total (All Sectors) (Sum of Tables 7.3b and 7.3c)**

	Coal <sup>a</sup>	Petroleum					Natural Gas <sup>f</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	Total <sup>e</sup>			Wood <sup>h</sup>	Waste <sup>i</sup>	
	Thousand Short Tons	Thousand Barrels			Thousand Short Tons	Thousand Barrels	Billion Cubic Feet		Trillion Btu		
1950 Total .....	91,871	5,423	69,998	NA	NA	75,421	629	NA	5	NA	NA
1955 Total .....	143,759	5,412	69,862	NA	NA	75,274	1,153	NA	3	NA	NA
1960 Total .....	176,685	3,824	84,371	NA	NA	88,195	1,725	NA	2	NA	NA
1965 Total .....	244,788	4,928	110,274	NA	NA	115,203	2,321	NA	3	NA	NA
1970 Total .....	320,182	24,123	311,381	NA	636	338,686	3,932	NA	1	2	NA
1975 Total .....	405,962	38,907	467,221	NA	70	506,479	3,158	NA	(s)	2	NA
1980 Total .....	569,274	29,051	391,163	NA	179	421,110	3,682	NA	3	2	NA
1985 Total .....	693,841	14,635	158,779	NA	231	174,571	3,044	NA	8	7	NA
1990 Total <sup>k</sup> .....	792,457	18,143	190,652	437	1,914	218,800	3,692	112	442	211	36
1995 Total .....	860,594	19,615	95,507	680	3,355	132,578	4,738	133	480	316	42
2000 Total .....	994,933	31,675	143,381	1,450	3,744	195,228	5,691	126	496	330	46
2001 Total .....	972,691	31,150	165,312	855	3,871	216,672	5,832	97	486	228	160
2002 Total .....	987,583	23,286	109,235	1,894	6,836	168,597	6,126	131	605	257	191
2003 Total .....	1,014,058	29,672	142,518	2,947	6,303	206,653	5,616	156	519	249	193
2004 Total .....	1,020,523	20,163	142,088	2,856	7,677	203,494	5,675	135	344	230	183
2005 Total .....	1,041,448	20,651	141,518	2,968	8,330	206,785	6,036	110	355	230	173
2006 Total .....	1,030,556	13,174	58,473	2,174	7,363	110,634	6,462	115	350	241	172
2007 Total .....	1,046,795	15,683	63,833	2,917	6,036	112,615	7,089	115	353	245	168
2008 Total .....	1,042,335	12,832	38,191	2,822	5,417	80,932	6,896	97	339	267	172
2009 Total .....	934,683	12,658	28,576	2,328	4,821	67,668	7,121	84	320	272	170
2010 Total .....	979,684	14,050	23,997	2,056	4,994	65,071	7,680	90	350	281	184
2011 Total .....	934,938	11,231	14,251	1,844	5,012	52,387	7,884	91	348	279	205
2012 Total .....	825,734	9,285	11,755	1,565	3,675	40,977	9,485	103	390	290	204
2013 Total .....	860,729	9,784	11,766	1,681	4,852	47,492	8,596	115	398	298	200
2014 Total .....	853,634	14,465	14,704	2,363	4,412	53,593	8,544	110	431	314	200
2015 Total .....	739,594	12,438	14,124	2,363	4,044	49,145	10,017	106	407	313	204
2016 Total .....	677,371	9,662	11,195	1,548	4,253	43,671	10,170	74	360	305	199
2017 Total .....	663,911	9,707	10,442	1,547	3,490	39,144	9,508	71	364	304	190
2018 January .....	64,845	5,238	3,644	585	377	11,353	806	6	33	26	16
February .....	45,793	676	658	117	305	2,976	707	6	29	24	15
March .....	44,474	735	650	112	255	2,770	772	7	31	26	16
April .....	40,515	794	707	100	271	2,956	723	7	27	25	15
May .....	47,293	958	786	118	212	2,923	869	7	30	25	16
June .....	56,078	916	873	106	338	3,583	974	6	31	25	16
July .....	63,818	754	874	125	367	3,590	1,246	7	33	25	16
August .....	63,737	803	931	136	352	3,631	1,209	8	32	25	17
September .....	53,914	752	976	136	325	3,488	1,052	6	29	23	15
October .....	48,422	798	874	142	229	2,956	909	6	28	24	16
November .....	51,702	920	754	125	271	3,154	785	6	29	24	16
December .....	55,624	879	679	182	321	3,347	783	6	30	25	16
Total .....	636,213	14,223	12,407	1,985	3,623	46,727	10,833	79	362	298	190
2019 January .....	55,834	1,206	996	303	326	4,135	873	6	31	23	17
February .....	45,025	739	580	163	272	2,844	801	5	27	21	15
March .....	43,974	734	611	131	235	2,651	836	6	28	23	16
April .....	33,353	648	621	149	155	2,194	763	5	24	21	16
May .....	40,015	830	735	136	294	3,169	863	6	27	22	17
June .....	44,218	812	790	145	216	2,828	1,016	6	28	22	17
July .....	55,863	775	895	148	309	3,363	1,284	7	31	23	17
August .....	52,348	758	961	150	276	3,251	1,306	6	32	23	18
September .....	47,188	725	786	157	231	2,824	1,109	6	28	22	17
October .....	37,431	742	794	172	83	2,123	964	5	26	22	16
November .....	41,907	779	718	130	129	2,272	847	6	27	22	16
December .....	40,461	873	763	179	197	2,800	939	6	29	23	17
Total .....	537,616	9,620	9,251	1,965	2,724	34,454	11,601	72	338	267	199
2020 January .....	36,767	859	761	158	261	3,082	958	6	28	23	16
February .....	32,039	696	616	131	190	2,393	902	6	27	21	14
March .....	28,988	593	583	192	262	2,678	902	6	27	23	16
April .....	23,622	504	544	137	221	2,288	783	4	24	21	15
May .....	26,849	596	588	104	231	2,442	854	5	26	22	16
June .....	36,637	749	700	120	308	3,111	1,068	5	25	20	15
July .....	49,838	814	801	131	356	3,526	1,396	5	27	21	16
August .....	50,430	747	800	128	305	3,199	1,304	6	29	22	16
September .....	38,701	563	732	115	159	2,206	1,058	6	24	21	15
October .....	33,890	714	787	143	131	2,300	974	5	24	21	15
November .....	34,351	655	614	121	211	2,445	790	6	26	20	15
11-Month Total ...	392,112	7,491	7,527	1,480	2,634	29,668	10,989	60	287	234	170
2019 11-Month Total ...	497,155	8,748	8,487	1,785	2,527	31,654	10,661	66	309	244	182
2018 11-Month Total ...	580,590	13,344	11,728	1,803	3,301	43,381	10,051	72	332	273	174

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Fuel oil nos. 1, 2, and 4. For 1949–1979, data are for gas turbine and internal combustion plant use of petroleum. For 1980–2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1949–1979, data are for steam plant use of petroleum. For 1980–2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and

tire-derived fuels).

<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • Data are for fuels consumed to produce electricity. Data also include fuels consumed to produce useful thermal output at a small number of electric utility combined-heat-and-power (CHP) plants. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See "Table 7.3b Sources" at end of section and sources for Table 7.3c.

**Table 7.3b Consumption of Combustible Fuels for Electricity Generation: Electric Power Sector** (Subset of Table 7.3a)

	Coal <sup>a</sup>	Petroleum					Natural Gas <sup>f</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	Total <sup>e</sup>			Wood <sup>h</sup>	Waste <sup>i</sup>	
	Thousand Short Tons	Thousand Barrels			Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu			
1950 Total .....	91,871	5,423	69,998	NA	NA	75,421	629	NA	5	NA	NA
1955 Total .....	143,759	5,412	69,862	NA	NA	75,274	1,153	NA	3	NA	NA
1960 Total .....	176,685	3,824	84,371	NA	NA	88,195	1,725	NA	2	NA	NA
1965 Total .....	244,788	4,928	110,274	NA	NA	115,203	2,321	NA	3	NA	NA
1970 Total .....	320,182	24,123	311,381	NA	636	338,686	3,932	NA	1	2	NA
1975 Total .....	405,962	38,907	467,221	NA	70	506,479	3,158	NA	(s)	2	NA
1980 Total .....	569,274	29,051	391,163	NA	179	421,110	3,682	NA	3	2	NA
1985 Total .....	693,841	14,635	158,779	NA	231	174,571	3,044	NA	8	7	NA
1990 Total <sup>k</sup> .....	781,301	16,394	183,285	25	1,008	204,745	3,147	6	106	180	(s)
1995 Total .....	847,854	18,066	88,895	441	2,452	119,663	4,094	18	106	282	2
2000 Total .....	982,713	29,722	138,047	403	3,155	183,946	5,014	19	126	294	1
2001 Total .....	961,523	29,056	159,150	374	3,308	205,119	5,142	9	116	205	109
2002 Total .....	975,251	21,810	104,577	1,243	5,705	156,154	5,408	25	141	224	137
2003 Total .....	1,003,036	27,441	137,361	1,937	5,719	195,336	4,909	30	156	216	136
2004 Total .....	1,012,459	18,793	138,831	2,511	7,135	195,809	5,075	27	150	206	131
2005 Total .....	1,033,567	19,450	138,337	2,591	7,877	199,760	5,485	24	166	205	116
2006 Total .....	1,022,802	12,578	56,347	1,783	6,905	105,235	5,891	28	163	216	117
2007 Total .....	1,041,346	15,135	62,072	2,496	5,523	107,316	6,502	27	165	221	117
2008 Total .....	1,036,891	12,318	37,222	2,608	5,000	77,149	6,342	23	159	242	122
2009 Total .....	929,692	11,848	27,768	2,110	4,485	64,151	6,567	21	160	244	115
2010 Total .....	971,245	13,677	23,560	1,848	4,679	62,477	7,085	20	177	249	116
2011 Total .....	928,857	10,961	13,861	1,655	4,726	50,105	7,265	18	166	241	133
2012 Total .....	820,762	9,000	11,292	1,339	2,861	35,937	8,788	19	171	250	132
2013 Total .....	855,546	9,511	11,322	1,488	4,189	43,265	7,888	41	187	251	130
2014 Total .....	848,803	14,052	14,132	2,157	4,039	50,537	7,849	29	220	266	127
2015 Total .....	735,433	12,056	13,893	2,086	3,789	46,978	9,322	29	215	268	127
2016 Total .....	674,239	9,421	11,056	1,284	4,018	41,853	9,590	20	191	261	126
2017 Total .....	661,033	9,398	10,299	1,332	3,273	37,394	8,917	21	195	262	121
2018 January .....	64,579	5,148	3,615	566	362	11,142	753	2	19	22	11
February .....	45,555	654	644	90	294	2,855	660	2	16	21	10
March .....	44,241	712	637	95	241	2,649	725	2	17	22	11
April .....	40,315	772	697	83	256	2,834	676	2	14	21	10
May .....	47,076	928	779	96	197	2,790	819	2	15	22	10
June .....	55,862	889	864	89	320	3,439	922	2	17	22	11
July .....	63,599	715	868	87	350	3,423	1,189	2	18	22	11
August .....	63,526	767	922	122	338	3,500	1,152	2	17	22	11
September .....	53,708	716	969	127	310	3,359	999	2	15	19	10
October .....	48,243	772	862	125	212	2,820	858	1	14	21	10
November .....	51,493	884	739	109	258	3,023	733	1	14	21	10
December .....	55,397	840	664	168	305	3,198	730	2	15	22	11
Total .....	633,593	13,795	12,259	1,757	3,444	45,030	10,215	21	189	257	125
2019 January .....	55,611	1,160	982	286	313	3,991	815	2	17	20	11
February .....	44,821	715	570	141	261	2,731	750	2	14	18	10
March .....	43,797	708	602	113	222	2,531	782	2	14	19	11
April .....	33,185	623	614	121	139	2,055	712	2	11	18	10
May .....	39,832	805	731	116	280	3,050	809	2	14	19	11
June .....	44,040	786	785	126	202	2,708	962	2	14	19	11
July .....	55,665	742	891	131	285	3,189	1,223	2	16	20	12
August .....	52,153	725	957	132	261	3,120	1,245	2	17	20	12
September .....	47,007	688	781	138	216	2,689	1,051	2	15	19	11
October .....	37,268	709	787	155	68	1,990	908	1	13	19	11
November .....	41,727	749	710	107	116	2,144	789	2	13	19	11
December .....	40,273	844	754	159	183	2,670	880	2	15	20	12
Total .....	535,378	9,254	9,163	1,724	2,545	32,868	10,927	21	171	231	133
2020 January .....	36,574	832	754	135	245	2,948	898	2	14	19	11
February .....	31,853	675	608	114	178	2,285	847	2	14	18	10
March .....	28,814	569	578	173	249	2,564	847	2	13	20	11
April .....	23,474	485	540	121	212	2,204	734	1	11	19	11
May .....	26,703	570	582	84	218	2,326	803	1	13	19	11
June .....	36,501	721	695	104	294	2,991	1,014	1	12	17	10
July .....	49,690	779	796	115	341	3,396	1,339	1	13	19	11
August .....	50,285	715	794	118	289	3,072	1,246	2	16	19	11
September .....	38,545	530	728	103	146	2,094	1,006	1	11	18	11
October .....	33,735	685	783	126	119	2,187	924	1	12	18	10
November .....	34,201	625	608	105	196	2,319	738	2	12	17	10
11-Month Total ...	390,378	7,185	7,467	1,299	2,487	28,385	10,395	15	140	203	118
2019 11-Month Total ...	495,105	8,410	8,409	1,566	2,363	30,198	10,048	19	156	211	121
2018 11-Month Total ...	578,196	12,955	11,596	1,589	3,138	41,832	9,486	20	174	236	114

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Fuel oil nos. 1, 2, and 4. For 1949–1979, data are for gas turbine and internal combustion plant use of petroleum. For 1980–2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1949–1979, data are for steam plant use of petroleum. For 1980–2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • Data are for fuels consumed to produce electricity. Data also include fuels consumed to produce useful thermal output at a small number of electric utility combined-heat-and-power (CHP) plants. • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 7.3c Consumption of Selected Combustible Fuels for Electricity Generation: Commercial and Industrial Sectors** (Subset of Table 7.3a)

	Commercial Sector <sup>a</sup>				Industrial Sector <sup>b</sup>						
	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Biomass	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
				Waste <sup>f</sup>					Wood <sup>h</sup>	Waste <sup>f</sup>	
	Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu	Thousand Short Tons	Thousand Barrels	Billion Cubic Feet		Trillion Btu		
<b>1990 Total</b> .....	<b>417</b>	<b>953</b>	<b>28</b>	<b>15</b>	<b>10,740</b>	<b>13,103</b>	<b>517</b>	<b>104</b>	<b>335</b>	<b>16</b>	<b>36</b>
<b>1995 Total</b> .....	<b>569</b>	<b>649</b>	<b>43</b>	<b>21</b>	<b>12,171</b>	<b>12,265</b>	<b>601</b>	<b>114</b>	<b>373</b>	<b>13</b>	<b>40</b>
<b>2000 Total</b> .....	<b>514</b>	<b>823</b>	<b>37</b>	<b>26</b>	<b>11,706</b>	<b>10,459</b>	<b>640</b>	<b>107</b>	<b>369</b>	<b>10</b>	<b>45</b>
<b>2001 Total</b> .....	<b>532</b>	<b>1,023</b>	<b>36</b>	<b>15</b>	<b>10,636</b>	<b>10,530</b>	<b>654</b>	<b>88</b>	<b>370</b>	<b>7</b>	<b>44</b>
<b>2002 Total</b> .....	<b>477</b>	<b>834</b>	<b>33</b>	<b>18</b>	<b>11,855</b>	<b>11,608</b>	<b>685</b>	<b>106</b>	<b>464</b>	<b>15</b>	<b>43</b>
<b>2003 Total</b> .....	<b>582</b>	<b>894</b>	<b>38</b>	<b>19</b>	<b>10,440</b>	<b>10,424</b>	<b>668</b>	<b>127</b>	<b>362</b>	<b>13</b>	<b>46</b>
<b>2004 Total</b> .....	<b>377</b>	<b>766</b>	<b>33</b>	<b>19</b>	<b>7,687</b>	<b>6,919</b>	<b>566</b>	<b>108</b>	<b>194</b>	<b>5</b>	<b>41</b>
<b>2005 Total</b> .....	<b>377</b>	<b>585</b>	<b>34</b>	<b>20</b>	<b>7,504</b>	<b>6,440</b>	<b>518</b>	<b>85</b>	<b>189</b>	<b>5</b>	<b>46</b>
<b>2006 Total</b> .....	<b>347</b>	<b>333</b>	<b>35</b>	<b>21</b>	<b>7,408</b>	<b>5,066</b>	<b>536</b>	<b>87</b>	<b>187</b>	<b>3</b>	<b>45</b>
<b>2007 Total</b> .....	<b>361</b>	<b>258</b>	<b>34</b>	<b>19</b>	<b>5,089</b>	<b>5,041</b>	<b>554</b>	<b>88</b>	<b>188</b>	<b>4</b>	<b>41</b>
<b>2008 Total</b> .....	<b>369</b>	<b>166</b>	<b>33</b>	<b>20</b>	<b>5,075</b>	<b>3,617</b>	<b>520</b>	<b>73</b>	<b>179</b>	<b>5</b>	<b>39</b>
<b>2009 Total</b> .....	<b>317</b>	<b>190</b>	<b>34</b>	<b>23</b>	<b>4,674</b>	<b>3,328</b>	<b>520</b>	<b>62</b>	<b>160</b>	<b>4</b>	<b>42</b>
<b>2010 Total</b> .....	<b>314</b>	<b>172</b>	<b>39</b>	<b>24</b>	<b>8,125</b>	<b>2,422</b>	<b>555</b>	<b>70</b>	<b>172</b>	<b>8</b>	<b>55</b>
<b>2011 Total</b> .....	<b>347</b>	<b>137</b>	<b>47</b>	<b>31</b>	<b>5,735</b>	<b>2,145</b>	<b>572</b>	<b>74</b>	<b>182</b>	<b>7</b>	<b>57</b>
<b>2012 Total</b> .....	<b>307</b>	<b>279</b>	<b>63</b>	<b>33</b>	<b>4,665</b>	<b>4,761</b>	<b>633</b>	<b>84</b>	<b>219</b>	<b>8</b>	<b>54</b>
<b>2013 Total</b> .....	<b>513</b>	<b>335</b>	<b>67</b>	<b>36</b>	<b>4,670</b>	<b>3,892</b>	<b>642</b>	<b>74</b>	<b>210</b>	<b>11</b>	<b>50</b>
<b>2014 Total</b> .....	<b>202</b>	<b>462</b>	<b>72</b>	<b>36</b>	<b>4,629</b>	<b>2,594</b>	<b>623</b>	<b>81</b>	<b>210</b>	<b>11</b>	<b>54</b>
<b>2015 Total</b> .....	<b>163</b>	<b>260</b>	<b>70</b>	<b>35</b>	<b>3,999</b>	<b>1,907</b>	<b>625</b>	<b>77</b>	<b>191</b>	<b>10</b>	<b>58</b>
<b>2016 Total</b> .....	<b>111</b>	<b>116</b>	<b>46</b>	<b>34</b>	<b>3,021</b>	<b>1,701</b>	<b>534</b>	<b>53</b>	<b>169</b>	<b>10</b>	<b>53</b>
<b>2017 Total</b> .....	<b>95</b>	<b>204</b>	<b>50</b>	<b>34</b>	<b>2,783</b>	<b>1,545</b>	<b>541</b>	<b>49</b>	<b>169</b>	<b>8</b>	<b>49</b>
<b>2018 January</b> .....	<b>11</b>	<b>68</b>	<b>4</b>	<b>3</b>	<b>255</b>	<b>144</b>	<b>49</b>	<b>5</b>	<b>15</b>	<b>1</b>	<b>4</b>
February .....	9	16	4	3	230	105	43	5	13	1	3
March .....	8	13	4	3	224	108	43	5	15	1	4
April .....	7	15	4	3	193	107	43	5	13	1	4
May .....	6	18	4	3	211	115	46	5	15	1	4
June .....	6	18	5	3	210	126	47	5	15	(s)	4
July .....	6	27	6	3	212	140	51	5	16	1	4
August .....	7	24	6	3	204	108	52	6	15	1	4
September .....	7	19	5	3	199	110	48	5	14	(s)	3
October .....	6	17	4	3	173	120	47	5	14	1	4
November .....	7	24	4	3	202	108	48	4	14	1	4
December .....	7	21	4	3	221	128	49	5	15	1	4
<b>Total</b> .....	<b>87</b>	<b>279</b>	<b>53</b>	<b>33</b>	<b>2,534</b>	<b>1,418</b>	<b>565</b>	<b>57</b>	<b>172</b>	<b>7</b>	<b>46</b>
<b>2019 January</b> .....	<b>8</b>	<b>34</b>	<b>5</b>	<b>3</b>	<b>214</b>	<b>109</b>	<b>54</b>	<b>4</b>	<b>15</b>	<b>1</b>	<b>4</b>
February .....	8	16	4	2	197	97	46	4	13	1	3
March .....	9	17	5	3	168	103	49	4	14	1	4
April .....	6	16	4	2	161	123	46	4	13	1	3
May .....	6	17	4	2	178	102	50	4	13	(s)	4
June .....	4	17	5	3	174	104	50	4	14	(s)	4
July .....	5	24	6	3	193	150	55	5	15	(s)	4
August .....	5	21	5	3	190	110	56	5	15	(s)	4
September .....	6	27	5	2	175	108	53	5	13	(s)	4
October .....	6	23	4	2	157	109	52	4	14	1	4
November .....	6	23	4	2	173	105	53	4	14	1	4
December .....	7	23	5	3	180	107	55	5	14	1	4
<b>Total</b> .....	<b>76</b>	<b>257</b>	<b>56</b>	<b>30</b>	<b>2,161</b>	<b>1,329</b>	<b>618</b>	<b>51</b>	<b>167</b>	<b>6</b>	<b>45</b>
<b>2020 January</b> .....	<b>5</b>	<b>24</b>	<b>5</b>	<b>2</b>	<b>187</b>	<b>109</b>	<b>56</b>	<b>4</b>	<b>14</b>	<b>1</b>	<b>3</b>
February .....	9	13	4	2	177	94	50	5	13	1	3
March .....	6	17	4	2	168	97	51	4	14	1	3
April .....	4	12	4	2	144	72	45	4	13	(s)	3
May .....	4	20	4	2	142	96	47	4	13	(s)	3
June .....	5	20	4	2	130	101	50	4	13	(s)	3
July .....	5	25	5	2	143	105	53	4	13	(s)	3
August .....	4	24	5	2	140	102	53	4	13	(s)	3
September .....	7	23	4	2	149	89	48	4	13	(s)	3
October .....	5	17	4	2	149	96	47	4	12	(s)	3
November .....	6	20	4	2	144	106	48	4	14	(s)	3
<b>11-Month Total</b> ...	<b>62</b>	<b>216</b>	<b>47</b>	<b>25</b>	<b>1,673</b>	<b>1,067</b>	<b>547</b>	<b>46</b>	<b>147</b>	<b>5</b>	<b>34</b>
<b>2019 11-Month Total</b> ...	<b>69</b>	<b>235</b>	<b>51</b>	<b>27</b>	<b>1,981</b>	<b>1,222</b>	<b>563</b>	<b>47</b>	<b>152</b>	<b>6</b>	<b>41</b>
<b>2018 11-Month Total</b> ...	<b>80</b>	<b>258</b>	<b>49</b>	<b>30</b>	<b>2,313</b>	<b>1,290</b>	<b>516</b>	<b>53</b>	<b>157</b>	<b>6</b>	<b>42</b>

<sup>a</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>d</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous

technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

(s)=Less than 0.5 trillion Btu.


Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of section. • Data are for fuels consumed to produce electricity. Through 1988, data are not available. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual and monthly data beginning in 1989.


Sources: • **1989–1997:** U.S. Energy Information Administration (EIA), Form EIA-867, "Annual Nonutility Power Producer Report." • **1998–2000:** EIA, Form EIA-860B, "Annual Electric Generator Report—Nonutility." • **2001–2003:** EIA, Form EIA-906, "Power Plant Report." • **2004–2007:** EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." • **2008 forward:** EIA, Form EIA-923, "Power Plant Operations Report."

**Figure 7.4 Consumption of Selected Combustible Fuels for Electricity Generation and Useful Thermal Output**


Coal by Sector, 1989–2019




Petroleum by Sector, 1989–2019




Natural Gas by Sector, 1989–2019




Other Gases [b] by Sector, 1989–2019



Wood by Sector, 1989–2019



Waste by Sector, 1989–2019



[a] Includes commercial sector.

[b] Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

Note: Data are for utility-scale facilities.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.

Sources: Tables 7.4a–7.4c.

**Table 7.4a Consumption of Combustible Fuels for Electricity Generation and Useful Thermal Output: Total (All Sectors)** (Sum of Tables 7.4b and 7.4c)

		Petroleum					Natural Gas <sup>f</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>j</sup>
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	Total <sup>e</sup>			Wood <sup>h</sup>	Waste <sup>i</sup>	
	Coal <sup>a</sup>	Thousand Short Tons	Thousand Barrels			Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu		
1950 Total .....	91,871	5,423	69,998	NA	NA	75,421	629	NA	5	NA	NA
1955 Total .....	143,759	5,412	69,862	NA	NA	75,274	1,153	NA	3	NA	NA
1960 Total .....	176,685	3,824	84,371	NA	NA	88,195	1,725	NA	2	NA	NA
1965 Total .....	244,788	4,928	110,274	NA	NA	115,203	2,321	NA	3	NA	NA
1970 Total .....	320,182	24,123	311,381	NA	636	338,686	3,932	NA	1	2	NA
1975 Total .....	405,962	38,907	467,221	NA	70	506,479	3,158	NA	(s)	2	NA
1980 Total .....	569,274	29,051	391,163	NA	179	421,110	3,682	NA	3	2	NA
1985 Total .....	693,841	14,635	158,779	NA	231	174,571	3,044	NA	8	7	NA
1990 Total <sup>k</sup> .....	811,538	20,194	209,081	1,332	2,832	244,765	4,346	288	1,256	257	86
1995 Total .....	881,012	21,697	112,168	1,322	4,590	158,140	5,572	313	1,382	374	97
2000 Total .....	1,015,398	34,572	156,673	2,904	4,669	217,494	6,677	356	1,380	401	109
2001 Total .....	991,635	33,724	177,137	1,418	4,532	234,940	6,731	263	1,182	263	229
2002 Total .....	1,005,144	24,749	118,637	3,257	7,353	183,409	6,986	278	1,287	289	252
2003 Total .....	1,031,778	31,825	152,859	4,576	7,067	224,593	6,337	294	1,266	293	262
2004 Total .....	1,044,798	23,520	157,478	4,764	8,721	229,364	6,727	353	1,360	282	254
2005 Total .....	1,065,281	24,446	156,915	4,270	9,113	231,193	7,021	348	1,353	289	237
2006 Total .....	1,053,783	14,655	69,846	3,396	8,622	131,005	7,404	341	1,399	300	247
2007 Total .....	1,069,606	17,042	74,616	4,237	7,299	132,389	7,962	329	1,336	304	239
2008 Total .....	1,064,503	14,137	43,477	3,765	6,314	92,948	7,689	300	1,263	328	212
2009 Total .....	955,190	14,800	33,672	3,218	5,828	80,830	7,938	259	1,137	333	228
2010 Total .....	1,001,411	15,247	26,944	2,777	6,053	75,231	8,502	262	1,226	346	237
2011 Total .....	956,470	11,735	16,877	2,540	6,092	61,610	8,724	282	1,241	340	261
2012 Total .....	845,066	9,945	13,571	2,185	5,021	50,805	10,371	302	1,273	355	252
2013 Total .....	879,078	10,277	14,199	2,212	6,338	58,378	9,479	305	1,318	376	236
2014 Total .....	871,741	15,107	16,615	2,908	5,695	63,106	9,410	304	1,378	395	236
2015 Total .....	756,226	12,924	16,136	3,008	5,188	58,009	10,952	290	1,351	398	237
2016 Total .....	693,958	10,278	12,231	2,173	5,352	51,441	11,322	296	1,330	383	238
2017 Total .....	678,578	10,168	11,508	2,033	4,467	46,043	10,677	299	1,303	375	226
2018 January .....	66,279	5,607	3,894	668	466	12,497	913	28	114	33	19
February .....	47,079	707	759	164	382	3,542	801	28	102	31	18
March .....	45,728	782	723	148	327	3,286	873	30	110	33	19
April .....	41,610	825	774	138	354	3,508	816	27	101	31	18
May .....	48,374	998	853	159	281	3,417	963	30	107	31	19
June .....	57,159	946	962	149	413	4,122	1,071	29	107	29	20
July .....	64,895	798	927	184	448	4,151	1,353	30	114	29	19
August .....	64,801	843	1,001	169	429	4,157	1,315	34	112	30	20
September .....	54,975	800	1,030	163	399	3,988	1,151	29	102	27	17
October .....	49,406	831	989	183	306	3,532	1,008	31	104	31	19
November .....	52,868	981	879	167	342	3,739	887	28	105	31	19
December .....	56,853	947	795	284	404	4,048	889	29	113	32	19
Total .....	650,027	15,066	13,584	2,578	4,552	53,988	12,039	353	1,291	367	226
2019 January .....	57,146	1,427	1,121	362	399	4,905	982	24	112	29	21
February .....	46,183	802	659	217	338	3,368	898	22	100	26	18
March .....	45,086	779	685	172	308	3,175	937	24	105	28	19
April .....	34,362	680	679	201	227	2,693	854	23	96	26	18
May .....	40,956	967	785	177	364	3,747	957	23	101	26	19
June .....	45,168	839	840	183	287	3,295	1,112	22	101	26	19
July .....	56,813	806	942	180	385	3,851	1,386	25	108	26	20
August .....	53,322	800	1,003	188	346	3,720	1,410	24	109	27	21
September .....	48,102	768	841	198	310	3,356	1,206	23	101	25	19
October .....	38,416	776	860	213	146	2,581	1,061	23	101	27	19
November .....	42,925	821	787	267	186	2,803	947	23	103	27	19
December .....	41,533	903	847	222	269	3,317	1,045	24	108	29	20
Total .....	550,013	10,369	10,049	2,580	3,563	40,811	12,797	281	1,246	322	234
2020 January .....	37,825	892	817	201	336	3,590	1,068	25	106	29	18
February .....	33,055	723	676	166	239	2,757	1,003	25	100	26	17
March .....	29,905	620	630	231	301	2,988	1,005	25	101	28	18
April .....	24,425	530	589	168	252	2,546	880	20	97	26	18
May .....	27,652	628	637	143	290	2,858	951	20	103	26	18
June .....	37,409	783	753	154	379	3,585	1,166	19	93	23	17
July .....	50,708	850	853	174	425	4,002	1,501	21	98	25	19
August .....	51,285	785	864	164	383	3,731	1,409	22	99	25	19
September .....	39,549	607	783	142	228	2,674	1,155	21	95	24	17
October .....	34,828	759	839	181	205	2,803	1,077	22	97	25	18
November .....	35,248	709	693	153	280	2,956	888	22	101	25	18
11-Month Total ...	401,889	7,887	8,134	1,877	3,318	34,489	12,104	241	1,090	282	197
2019 11-Month Total ...	508,480	9,466	9,201	2,358	3,294	37,494	11,751	257	1,138	293	214
2018 11-Month Total ...	593,173	14,119	12,789	2,293	4,148	49,940	11,151	324	1,178	335	207

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Fuel oil nos. 1, 2, and 4. For 1949–1979, data are for gas turbine and internal combustion plant use of petroleum. For 1980–2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1949–1979, data are for steam plant use of petroleum. For 1980–2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes

non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See "Table 7.4b Sources" at end of section and sources for Table 7.4c.

**Table 7.4b Consumption of Combustible Fuels for Electricity Generation and Useful Thermal Output: Electric Power Sector** (Subset of Table 7.4a)

	Coal <sup>a</sup>	Petroleum					Natural Gas <sup>f</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	Total <sup>e</sup>			Wood <sup>h</sup>	Waste <sup>i</sup>	
	Thousand Short Tons	Thousand Barrels			Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu			
1950 Total .....	91,871	5,423	69,998	NA	NA	75,421	629	NA	5	NA	NA
1955 Total .....	143,759	5,412	69,862	NA	NA	75,274	1,153	NA	3	NA	NA
1960 Total .....	176,685	3,824	84,371	NA	NA	88,195	1,725	NA	2	NA	NA
1965 Total .....	244,788	4,928	110,274	NA	NA	115,203	2,321	NA	3	NA	NA
1970 Total .....	320,182	24,123	311,381	NA	636	338,686	3,932	NA	1	2	NA
1975 Total .....	405,962	38,907	467,221	NA	70	506,479	3,158	NA	(s)	2	NA
1980 Total .....	569,274	29,051	391,163	NA	179	421,110	3,682	NA	3	2	NA
1985 Total .....	693,841	14,635	158,779	NA	231	174,571	3,044	NA	8	7	NA
1990 Total <sup>k</sup> .....	782,567	16,567	184,915	26	1,008	206,550	3,245	11	129	188	(s)
1995 Total .....	850,230	18,553	90,023	499	2,674	122,447	4,237	24	125	296	2
2000 Total .....	985,821	30,016	138,513	454	3,275	185,358	5,206	25	134	318	1
2001 Total .....	964,433	29,274	159,504	377	3,427	206,291	5,342	15	126	211	113
2002 Total .....	977,507	21,876	104,773	1,267	5,816	156,996	5,672	33	150	230	143
2003 Total .....	1,005,116	27,632	138,279	2,026	5,799	196,932	5,135	41	167	230	140
2004 Total .....	1,016,268	19,107	139,816	2,713	7,372	198,498	5,464	58	165	223	138
2005 Total .....	1,037,485	19,675	139,409	2,685	8,083	202,184	5,869	84	185	221	123
2006 Total .....	1,026,636	12,646	57,345	1,870	7,101	107,365	6,222	65	182	231	125
2007 Total .....	1,045,141	15,327	63,086	2,594	5,685	109,431	6,841	61	186	237	124
2008 Total .....	1,040,580	12,547	38,241	2,670	5,119	79,056	6,668	61	177	258	131
2009 Total .....	933,627	12,035	28,782	2,210	4,611	66,081	6,873	55	180	261	124
2010 Total .....	975,052	13,790	24,503	1,877	4,777	64,055	7,387	52	196	264	124
2011 Total .....	932,484	11,021	14,803	1,658	4,837	51,667	7,574	50	182	255	143
2012 Total .....	823,551	9,080	12,203	1,339	2,974	37,495	9,111	54	190	262	143
2013 Total .....	857,962	9,598	12,283	1,489	4,285	44,794	8,191	60	207	262	139
2014 Total .....	851,602	14,235	15,132	2,208	4,132	52,235	8,146	44	251	279	137
2015 Total .....	738,444	12,193	14,929	2,131	3,907	48,787	9,613	44	244	281	136
2016 Total .....	678,554	9,510	11,242	1,322	4,138	42,763	9,985	45	224	281	139
2017 Total .....	664,993	9,481	10,464	1,375	3,399	38,318	9,266	46	229	280	132
2018 January .....	64,960	5,254	3,672	594	373	11,385	786	4	21	24	12
February .....	45,897	659	653	91	302	2,916	690	4	19	23	11
March .....	44,562	717	647	96	251	2,715	757	4	20	24	12
April .....	40,603	777	707	84	267	2,904	704	4	16	23	11
May .....	47,356	937	790	97	204	2,844	848	4	17	23	11
June .....	56,154	895	875	90	322	3,471	953	4	19	23	12
July .....	63,894	719	877	88	360	3,486	1,224	4	21	23	12
August .....	63,810	771	932	123	348	3,566	1,186	4	20	23	12
September .....	53,987	723	982	128	318	3,422	1,030	4	17	21	10
October .....	48,474	777	875	127	222	2,888	888	4	17	23	11
November .....	51,806	893	752	110	267	3,089	763	4	17	23	11
December .....	55,714	845	683	227	315	3,327	762	4	18	23	11
Total .....	637,217	13,967	12,446	1,855	3,549	46,013	10,590	47	221	275	136
2019 January .....	55,967	1,181	1,009	297	322	4,096	848	4	19	22	12
February .....	45,124	729	586	142	271	2,809	779	4	16	19	11
March .....	44,096	714	618	114	231	2,602	813	5	16	21	12
April .....	33,429	627	629	122	151	2,132	740	4	14	20	11
May .....	40,045	812	745	117	289	3,117	836	4	16	21	12
June .....	44,297	790	799	127	210	2,768	990	4	16	20	12
July .....	55,932	745	902	132	295	3,255	1,255	4	19	21	13
August .....	52,431	730	967	133	270	3,179	1,278	4	19	21	13
September .....	47,248	693	799	139	226	2,760	1,081	4	17	20	12
October .....	37,523	714	804	157	70	2,027	937	3	15	21	12
November .....	41,977	754	725	109	126	2,218	819	4	16	20	12
December .....	40,533	849	769	160	194	2,749	911	4	18	22	13
Total .....	538,601	9,336	9,352	1,750	2,655	33,712	11,287	47	201	248	145
2020 January .....	36,801	836	763	137	256	3,016	931	4	17	21	12
February .....	32,066	679	616	115	188	2,350	879	4	16	20	11
March .....	28,978	574	587	175	258	2,628	879	4	16	21	12
April .....	23,623	492	551	122	222	2,277	764	3	13	20	12
May .....	26,870	575	593	85	229	2,399	834	3	15	20	12
June .....	36,675	726	705	105	301	3,042	1,045	2	15	18	11
July .....	49,912	784	809	116	348	3,451	1,373	2	16	20	12
August .....	50,513	720	806	120	301	3,150	1,281	4	19	20	12
September .....	38,733	535	741	104	156	2,162	1,037	3	13	19	11
October .....	33,944	692	799	128	128	2,260	954	3	14	19	11
November .....	34,387	629	646	106	207	2,416	767	4	15	19	11
11-Month Total ...	392,502	7,243	7,616	1,312	2,596	29,151	10,743	36	169	218	129
2019 11-Month Total ...	498,068	8,487	8,583	1,590	2,461	30,963	10,376	43	183	226	132
2018 11-Month Total ...	581,503	13,122	11,763	1,628	3,234	42,686	9,828	43	203	252	125

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Fuel oil nos. 1, 2, and 4. For 1949–1979, data are for gas turbine and internal combustion plant use of petroleum. For 1980–2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1949–1979, data are for steam plant use of petroleum. For 1980–2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and

tire-derived fuels).

<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.



**Table 7.4c Consumption of Selected Combustible Fuels for Electricity Generation and Useful Thermal Output: Commercial and Industrial Sectors** (Subset of Table 7.4a)

	Commercial Sector <sup>a</sup>				Industrial Sector <sup>b</sup>						
	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Biomass	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
				Waste <sup>f</sup>					Wood <sup>h</sup>	Waste <sup>f</sup>	
	Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu	Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu			
1990 Total .....	1,191	2,056	46	28	27,781	36,159	1,055	275	1,125	41	86
1995 Total .....	1,419	1,245	78	40	29,363	34,448	1,258	290	1,255	38	95
2000 Total .....	1,547	1,615	85	47	28,031	30,520	1,386	331	1,244	35	108
2001 Total .....	1,448	1,832	79	25	25,755	26,817	1,310	248	1,054	27	101
2002 Total .....	1,405	1,250	74	26	26,232	25,163	1,240	245	1,136	34	92
2003 Total .....	1,816	1,449	58	29	24,846	26,212	1,144	253	1,097	34	103
2004 Total .....	1,917	2,009	72	34	26,613	28,857	1,191	295	1,193	24	94
2005 Total .....	1,922	1,630	68	34	25,875	27,380	1,084	264	1,166	34	94
2006 Total .....	1,886	935	68	36	25,262	22,706	1,115	277	1,216	33	102
2007 Total .....	1,927	752	70	31	22,537	22,207	1,050	268	1,148	36	98
2008 Total .....	2,021	671	66	34	21,902	13,222	955	239	1,084	35	60
2009 Total .....	1,798	521	76	36	19,766	14,228	990	204	955	35	82
2010 Total .....	1,720	437	86	36	24,638	10,740	1,029	210	1,029	47	91
2011 Total .....	1,668	333	87	43	22,319	9,610	1,063	232	1,057	43	94
2012 Total .....	1,450	457	111	45	20,065	12,853	1,149	249	1,082	47	81
2013 Total .....	1,356	887	118	47	19,761	12,697	1,170	246	1,109	67	69
2014 Total .....	1,063	758	119	47	19,076	10,112	1,145	260	1,122	70	72
2015 Total .....	798	622	116	47	16,984	8,600	1,222	246	1,103	70	73
2016 Total .....	683	404	127	48	14,720	8,273	1,209	251	1,100	54	70
2017 Total .....	610	516	154	48	12,975	7,209	1,257	253	1,069	47	65
2018 January .....	76	186	12	4	1,242	926	115	24	92	5	5
February .....	59	48	11	4	1,122	578	101	24	83	4	5
March .....	57	42	11	4	1,109	530	105	26	90	5	5
April .....	47	36	10	4	960	568	102	23	85	4	5
May .....	39	34	10	4	979	539	105	25	89	4	5
June .....	36	33	11	4	969	618	107	26	87	2	5
July .....	40	55	13	4	962	610	116	26	92	3	5
August .....	42	46	13	4	949	545	116	30	92	3	6
September .....	45	39	11	4	943	528	110	25	85	2	5
October .....	42	36	11	4	891	608	110	27	87	4	5
November .....	47	62	11	4	1,015	588	113	24	88	4	5
December .....	47	65	11	4	1,093	656	115	25	95	5	5
Total .....	577	681	135	47	12,233	7,294	1,314	306	1,065	45	62
2019 January .....	59	100	12	4	1,119	708	121	20	92	4	6
February .....	54	51	11	3	1,005	508	108	18	83	4	5
March .....	58	53	11	3	932	521	113	20	89	4	5
April .....	40	39	10	3	893	522	105	19	82	3	5
May .....	38	137	10	3	873	493	111	19	85	2	5
June .....	27	29	11	3	845	498	111	19	84	3	5
July .....	35	48	13	3	846	548	118	21	89	2	5
August .....	37	44	12	3	854	498	120	20	90	2	5
September .....	40	54	11	3	814	541	114	20	83	2	5
October .....	37	44	11	3	856	510	114	19	86	3	5
November .....	44	55	11	3	904	530	117	19	86	4	5
December .....	49	52	12	3	950	516	122	20	90	4	5
Total .....	519	707	135	39	10,892	6,393	1,374	234	1,040	35	61
2020 January .....	41	60	12	3	984	514	125	21	88	4	4
February .....	49	37	11	3	939	370	114	21	84	4	4
March .....	41	37	11	3	886	323	115	20	85	3	4
April .....	29	24	9	3	773	245	107	17	83	3	4
May .....	32	42	10	3	749	417	108	18	87	3	4
June .....	35	38	10	3	699	505	110	17	78	2	4
July .....	35	53	12	3	761	498	116	18	82	2	4
August .....	37	57	12	3	735	524	117	18	80	2	4
September .....	41	45	11	3	775	466	107	18	81	2	4
October .....	34	35	10	3	850	508	112	19	83	3	4
November .....	36	45	10	3	825	495	111	18	86	3	4
11-Month Total ...	410	473	118	33	8,977	4,865	1,243	205	918	32	46
2019 11-Month Total ...	470	654	123	36	9,942	5,877	1,252	213	950	32	56
2018 11-Month Total ...	530	617	123	43	11,141	6,638	1,199	281	970	40	56

<sup>a</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>d</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).


Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual and monthly data beginning in 1989.


Sources: • **1989–1997:** U.S. Energy Information Administration (EIA), Form EIA-867, "Annual Nonutility Power Producer Report." • **1998–2000:** EIA, Form EIA-860B, "Annual Electric Generator Report—Nonutility." • **2001–2003:** EIA, Form EIA-906, "Power Plant Report." • **2004–2007:** EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." • **2008 forward:** EIA, Form EIA-923, "Power Plant Operations Report."

**Figure 7.5 Stocks of Coal and Petroleum: Electric Power Sector**


Coal, 1949–2019




Total Petroleum, 1949–2019



Coal, Monthly



Total Petroleum, Monthly



Note: Data are for utility-sale facilities.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.

Source: Table 7.5.

**Table 7.5 Stocks of Coal and Petroleum: Electric Power Sector**

	Coal <sup>a</sup>	Petroleum				
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	Total <sup>e,f</sup>
	Thousand Short Tons	Thousand Barrels			Thousand Short Tons	Thousand Barrels
1950 Year .....	31,842	NA	NA	NA	NA	10,201
1955 Year .....	41,391	NA	NA	NA	NA	13,671
1960 Year .....	51,735	NA	NA	NA	NA	19,572
1965 Year .....	54,525	NA	NA	NA	NA	25,647
1970 Year .....	71,908	NA	NA	NA	239	39,151
1975 Year .....	110,724	16,432	108,825	NA	31	125,413
1980 Year .....	183,010	30,023	105,351	NA	52	135,635
1985 Year .....	156,376	16,386	57,304	NA	49	73,933
1990 Year .....	156,166	16,471	67,030	NA	94	83,970
1995 Year .....	126,304	15,392	35,102	NA	65	50,821
2000 Year <sup>g</sup> .....	102,296	15,127	24,748	NA	211	40,932
2001 Year .....	138,496	20,486	34,594	NA	390	57,031
2002 Year .....	141,714	17,413	25,723	800	1,711	52,490
2003 Year .....	121,567	19,153	25,820	779	1,484	53,170
2004 Year .....	106,669	19,275	26,596	879	937	51,434
2005 Year .....	101,137	18,778	27,624	1,012	530	50,062
2006 Year .....	140,964	18,013	28,823	1,380	674	51,583
2007 Year .....	151,221	18,395	24,136	1,902	554	47,203
2008 Year .....	161,589	17,761	21,088	1,634	739	44,178
2009 Year .....	189,467	17,886	19,068	1,651	1,394	45,575
2010 Year .....	174,917	16,758	16,629	1,454	1,019	39,936
2011 Year .....	172,387	16,649	15,491	1,603	508	36,282
2012 Year .....	185,116	16,433	12,999	1,430	495	33,336
2013 Year .....	147,884	16,068	12,926	1,393	390	32,336
2014 Year .....	151,548	18,309	12,764	1,249	827	36,459
2015 Year .....	195,548	17,955	12,566	1,173	1,340	38,396
2016 Year .....	162,009	17,855	11,789	949	845	34,818
2017 Year .....	137,687	16,342	10,930	816	864	32,407
<b>2018 January</b> .....	<b>123,235</b>	<b>15,489</b>	<b>9,763</b>	<b>601</b>	<b>720</b>	<b>29,454</b>
February .....	120,526	15,844	10,320	667	692	30,293
March .....	126,008	15,809	10,286	668	736	30,446
April .....	128,571	15,742	10,194	672	731	30,262
May .....	127,982	15,911	10,127	756	709	30,337
June .....	121,041	15,664	10,146	684	591	29,448
July .....	110,348	15,650	9,583	679	668	29,249
August .....	103,744	15,210	8,923	682	625	27,939
September .....	100,384	15,238	8,671	686	608	27,634
October .....	104,855	15,297	8,665	630	541	27,297
November .....	104,075	15,581	8,499	640	557	27,504
<b>December</b> .....	<b>102,793</b>	<b>16,436</b>	<b>8,785</b>	<b>756</b>	<b>539</b>	<b>28,674</b>
<b>2019 January</b> .....	<b>99,147</b>	<b>16,430</b>	<b>8,672</b>	<b>689</b>	<b>528</b>	<b>28,429</b>
February .....	98,639	16,462	9,011	680	505	28,680
March .....	96,933	16,489	9,034	679	503	28,715
April .....	108,089	16,635	9,007	688	513	28,895
May .....	115,712	16,716	8,994	697	444	28,625
June .....	116,876	16,632	8,854	700	388	28,125
July .....	110,672	16,554	8,570	703	354	27,599
August .....	110,278	16,413	8,090	706	380	27,109
September .....	110,626	16,460	8,281	708	292	26,910
October .....	118,574	16,557	8,156	701	292	26,876
November .....	122,364	16,434	8,563	722	464	28,038
<b>December</b> .....	<b>128,180</b>	<b>16,733</b>	<b>8,549</b>	<b>678</b>	<b>471</b>	<b>28,317</b>
<b>2020 January</b> .....	<b>134,364</b>	<b>16,419</b>	<b>8,076</b>	<b>630</b>	<b>508</b>	<b>27,665</b>
February .....	139,299	16,251	8,129	620	600	27,999
March .....	145,238	16,500	8,286	549	541	28,041
April .....	151,744	16,374	8,480	546	541	28,107
May .....	154,058	16,593	8,424	536	529	28,196
June .....	150,427	16,540	8,507	526	480	27,972
July .....	137,907	17,197	8,561	500	445	28,481
August .....	129,688	16,951	7,775	518	407	27,278
September .....	129,102	17,018	8,212	514	415	27,819
October .....	133,398	16,960	8,270	506	455	28,012
November .....	136,191	16,777	8,129	500	473	27,769

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, and lignite; excludes waste coal.

<sup>b</sup> Fuel oil nos. 1, 2 and 4. For 1973–1979, data are for gas turbine and internal combustion plant stocks of petroleum. For 1980–2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1973–1979, data are for steam plant stocks of petroleum. For 1980–2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel and kerosene. Through 2003, data also include a small amount of waste oil.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Distillate fuel oil and residual fuel oil. Beginning in 1970, also includes petroleum coke. Beginning in 2002, also includes other liquids.

<sup>g</sup> Through 1998, data are for electric utilities only. Beginning in 1999, data are for electric utilities and independent power producers.

NA=Not available.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose

primary business is to sell electricity, or electricity and heat, to the public. • Stocks are at end of period. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **1949–September 1977:** Federal Power Commission, Form FPC-4, "Monthly Power Plant Report." • **October 1977–1981:** Federal Energy Regulatory Commission, Form FPC-4, "Monthly Power Plant Report." • **1982–1988:** U.S. Energy Information Administration (EIA), Form EIA-759, "Monthly Power Plant Report." • **1989–1997:** EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report." • **1998–2000:** EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility." • **2001–2003:** EIA, Form EIA-906, "Power Plant Report." • **2004–2007:** EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." • **2008 forward:** EIA, Form EIA-923, "Power Plant Operations Report."


**Figure 7.6 Electricity End Use**

(Billion Kilowatthours)


Electricity End Use Overview, 1989–2019




Retail Sales [a] by Sector, November 2020




Retail Sales [a] by Sector, 1949–2019



Retail Sales [a] by Sector, Monthly



Retail Sales [a] Total, January–November



[a] Electricity retail sales to ultimate customers reported by utilities and other energy service providers.

[b] See “Direct Use” in Glossary.

[c] Commercial sector, including public street and highway lighting, inter-

departmental sales, and other sales to public authorities.

[d] Transportation sector, including sales to railroads and railways.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.

Source: Table 7.6.

**Table 7.6 Electricity End Use**  
(Million Kilowatthours)

	Retail Sales <sup>a</sup>					Direct Use <sup>f</sup>	Total End Use <sup>g</sup>
	Residential	Commercial <sup>b</sup>	Industrial <sup>c</sup>	Transportation <sup>d</sup>	Total Retail Sales <sup>e</sup>		
1950 Total .....	72,200	E 65,971	146,479	E 6,793	291,443	NA	291,443
1955 Total .....	128,401	E 102,547	259,974	E 5,826	496,748	NA	496,748
1960 Total .....	201,463	E 159,144	324,402	E 3,066	688,075	NA	688,075
1965 Total .....	291,013	E 231,126	428,727	E 2,923	953,789	NA	953,789
1970 Total .....	466,291	E 352,041	570,854	E 3,115	1,392,300	NA	1,392,300
1975 Total .....	588,140	E 468,296	687,680	E 2,974	1,747,091	NA	1,747,091
1980 Total .....	717,495	558,643	815,067	3,244	2,094,449	NA	2,094,449
1985 Total .....	793,934	689,121	836,772	4,147	2,323,974	NA	2,323,974
1990 Total .....	924,019	838,263	945,522	4,751	2,712,555	124,529	2,837,084
1995 Total .....	1,042,501	953,117	1,012,693	4,975	3,013,287	150,677	3,163,963
2000 Total .....	1,192,446	1,159,347	1,064,239	5,382	3,421,414	170,943	3,592,357
2001 Total .....	1,201,607	1,190,518	996,609	5,724	3,394,458	162,649	3,557,107
2002 Total .....	1,265,180	1,204,531	990,238	5,517	3,465,466	166,184	3,631,650
2003 Total .....	1,275,824	1,198,728	1,012,373	6,810	3,493,734	168,295	3,662,029
2004 Total .....	1,291,982	1,230,425	1,017,850	7,224	3,547,479	168,470	3,715,949
2005 Total .....	1,359,227	1,275,079	1,019,156	7,506	3,660,969	150,016	3,810,984
2006 Total .....	1,351,520	1,299,744	1,011,298	7,358	3,669,919	146,927	3,816,845
2007 Total .....	1,392,241	1,336,315	1,027,832	8,173	3,764,561	125,670	3,890,231
2008 Total .....	1,380,662	1,336,133	1,009,516	7,653	3,733,965	132,197	3,866,161
2009 Total .....	1,364,758	1,306,853	917,416	7,768	3,596,795	126,938	3,723,733
2010 Total .....	1,445,708	1,330,199	971,221	7,712	3,754,841	131,910	3,886,752
2011 Total .....	1,422,801	1,328,057	991,316	7,672	3,749,846	132,754	3,882,600
2012 Total .....	1,374,515	1,327,101	985,714	7,320	3,694,650	137,657	3,832,306
2013 Total .....	1,394,812	1,337,079	985,352	7,625	3,724,868	143,462	3,868,330
2014 Total .....	1,407,208	1,352,158	997,576	7,758	3,764,700	138,574	3,903,274
2015 Total .....	1,404,096	1,360,752	986,508	7,637	3,758,992	141,168	3,900,160
2016 Total .....	1,411,058	1,367,191	976,715	7,497	3,762,462	139,844	3,902,306
2017 Total .....	1,378,648	1,352,888	984,298	7,523	3,723,356	141,114	3,864,470
<b>2018 January</b> .....	148,917	114,925	79,890	745	344,478	E 12,405	356,882
February .....	113,751	102,685	75,661	634	292,732	E 11,036	303,768
March .....	107,218	108,108	81,053	620	296,999	E 11,521	308,521
April .....	95,454	103,331	79,083	599	278,468	E 11,023	289,491
May .....	103,848	113,175	85,638	587	303,248	E 11,740	314,988
June .....	129,913	122,011	85,536	623	338,083	E 12,027	350,110
July .....	153,566	131,522	89,301	634	375,023	E 12,994	388,017
August .....	153,496	134,848	92,106	680	381,131	E 13,079	394,209
September .....	128,910	122,033	85,679	640	337,263	E 12,008	349,271
October .....	107,049	116,133	85,301	631	309,114	E 11,865	320,979
November .....	103,790	104,983	81,118	616	290,507	E 11,977	302,484
December .....	123,180	107,998	80,306	655	312,140	E 12,438	324,578
<b>Total</b> .....	<b>1,469,093</b>	<b>1,381,755</b>	<b>1,000,673</b>	<b>7,665</b>	<b>3,859,185</b>	<b>144,114</b>	<b>4,003,299</b>
<b>2019 January</b> .....	133,318	112,012	82,610	670	328,609	E 12,544	341,154
February .....	116,608	102,071	76,447	672	295,798	E 10,958	306,756
March .....	112,605	107,468	81,093	686	301,853	E 11,737	313,589
April .....	90,384	102,446	80,460	610	273,900	E 10,925	284,825
May .....	100,331	111,201	84,661	608	296,802	E 11,430	308,232
June .....	120,116	115,745	84,992	608	321,462	E 11,743	333,205
July .....	153,749	130,951	90,752	642	376,095	E 12,814	388,909
August .....	150,083	130,776	91,062	653	372,574	E 12,845	385,419
September .....	131,567	122,059	86,160	677	340,463	E 12,048	352,511
October .....	107,997	115,305	84,396	543	308,241	E 11,808	320,050
November .....	102,453	102,840	79,625	614	285,532	E 12,023	297,556
December .....	121,078	108,001	80,095	648	309,823	E 12,582	322,405
<b>Total</b> .....	<b>1,440,289</b>	<b>1,360,877</b>	<b>1,002,353</b>	<b>7,632</b>	<b>3,811,150</b>	<b>143,458</b>	<b>3,954,609</b>
<b>2020 January</b> .....	124,414	108,857	77,426	664	311,361	E 12,782	324,143
February .....	111,931	101,905	75,650	622	290,109	E 11,719	301,827
March .....	104,006	102,937	77,565	577	285,085	E 11,810	296,894
April .....	97,465	90,631	69,591	458	258,145	E 10,649	268,794
May .....	105,412	93,406	71,220	448	270,486	E 10,875	281,361
June .....	131,242	108,695	75,211	480	315,628	E 11,242	326,871
July .....	166,891	125,994	81,276	555	374,716	E 11,918	386,633
August .....	158,821	122,025	82,582	562	363,990	E 11,907	375,897
September .....	127,584	112,214	77,505	494	317,796	E 11,047	328,843
October .....	105,537	107,778	81,861	562	295,738	E 10,777	306,514
November .....	99,385	97,076	75,851	525	272,838	E 11,130	283,968
<b>11-Month Total</b> ...	<b>1,332,689</b>	<b>1,171,518</b>	<b>845,737</b>	<b>5,946</b>	<b>3,355,890</b>	<b>E 125,857</b>	<b>3,481,747</b>
<b>2019 11-Month Total</b> ...	<b>1,319,211</b>	<b>1,252,875</b>	<b>922,258</b>	<b>6,984</b>	<b>3,501,328</b>	<b>E 130,876</b>	<b>3,632,204</b>
<b>2018 11-Month Total</b> ...	<b>1,345,913</b>	<b>1,273,757</b>	<b>920,366</b>	<b>7,010</b>	<b>3,547,046</b>	<b>E 131,675</b>	<b>3,678,721</b>

<sup>a</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

<sup>b</sup> Commercial sector, including public street and highway lighting, interdepartmental sales, and other sales to public authorities.

<sup>c</sup> Industrial sector. Through 2002, excludes agriculture and irrigation; beginning in 2003, includes agriculture and irrigation.

<sup>d</sup> Transportation sector, including sales to railroads and railways.

<sup>e</sup> The sum of "Residential," "Commercial," "Industrial," and "Transportation."

<sup>f</sup> Use of electricity that is 1) self-generated, 2) produced by either the same entity that consumes the power or an affiliate, and 3) used in direct support of a service or industrial process located within the same facility or group of facilities

that house the generating equipment. Direct use is exclusive of station use.

<sup>g</sup> The sum of "Total Retail Sales" and "Direct Use."

E=Estimate. NA=Not available.

Notes: • See Note 1, "Coverage of Electricity Statistics," at end of section.

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Note 1. Coverage of Electricity Statistics.** Data in Section 7 cover the following:

Through 1984, data for electric utilities also include institutions (such as universities) and military facilities that generated electricity primarily for their own use; beginning in 1985, data for electric utilities exclude institutions and military facilities. Beginning in 1989, data for the commercial sector include institutions and military facilities.

The generation, consumption, and stocks data in Section 7 are for utility-scale facilities—those with a combined generation nameplate capacity of 1 megawatt or more. Data exclude distributed (small-scale) facilities—those with a combined generator nameplate capacity of less than 1 megawatt. For data on distributed solar photovoltaic (PV) generation in the residential, commercial, and industrial sectors, see Table 10.6.

**Note 2. Classification of Power Plants into Energy-Use Sectors.** The U.S. Energy Information Administration (EIA) classifies power plants (both electricity-only and combined-heat-and-power plants) into energy-use sectors based on the North American Industry Classification System (NAICS), which replaced the Standard Industrial Classification (SIC) system in 1997. Plants with a NAICS code of 22 are assigned to the Electric Power Sector. Those with NAICS codes beginning with 11 (agriculture, forestry, fishing, and hunting); 21 (mining, including oil and gas extraction); 23 (construction); 31–33 (manufacturing); 2212 (natural gas distribution); and 22131 (water supply and irrigation systems) are assigned to the Industrial Sector. Those with all other codes are assigned to the Commercial Sector. Form EIA-860, "Annual Electric Generator Report," asks respondents to indicate the primary purpose of the facility by assigning a NAICS code from the list at [http://www.eia.gov/survey/form/eia\\_860/instructions.pdf](http://www.eia.gov/survey/form/eia_860/instructions.pdf).

**Note 3. Electricity Forecast Values.** Data values preceded by "F" in this section are forecast values. They are derived from EIA's Short-Term Integrated Forecasting System (STIFS). STIFS is driven primarily by data and assumptions about key macroeconomic variables, energy prices, and weather. The electricity forecast relies on additional variables such as alternative fuel prices (natural gas and oil) and power generation by sources other than fossil fuels, including nuclear, renewables, and hydroelectric power. Each month, EIA staff review the model output and make adjustments, if appropriate, based on their knowledge of developments in the electricity industry.

The STIFS model results are published monthly in EIA's Short-Term Energy Outlook, which is accessible on the Web at <http://www.eia.gov/forecasts/steo/>.

## Table 7.1 Sources

### *Net Generation, Electric Power Sector*

1949 forward: Table 7.2b.

### *Net Generation, Commercial and Industrial Sectors*

1949 forward: Table 7.2c.

### *Trade*

1949–September 1977: Unpublished Federal Power Commission data.

October 1977–1980: Unpublished Economic Regulatory Administration (ERA) data.

1981: U.S. Department of Energy (DOE), Office of Energy Emergency Operations, "Report on Electric Energy Exchanges with Canada and Mexico for Calendar Year 1981," April 1982 (revised June 1982).

1982 and 1983: DOE, ERA, *Electricity Exchanges Across International Borders*.

1984–1986: DOE, ERA, *Electricity Transactions Across International Borders*.

1987 and 1988: DOE, ERA, Form ERA-781R, "Annual Report of International Electrical Export/Import Data."

1989: DOE, Fossil Energy, Form FE-781R, "Annual Report of International Electrical Export/Import Data."

1990–2000: National Energy Board of Canada; and DOE, Office of Electricity Delivery and Energy Reliability, Form FE-781R, "Annual Report of International Electrical Export/Import Data."

2001–May 2011: National Energy Board of Canada; DOE, Office of Electricity Delivery and Energy Reliability, Form OE-781R, "Monthly Electricity Imports and Exports Report," and predecessor form; and California Independent System Operator.

June 2011–2015: National Energy Board of Canada; California Independent System Operator; and EIA estimates for Texas transfers.

2016 forward: EIA, Form EIA-111, "Quarterly Electricity Imports and Exports Report"; and for forecast values, EIA Short-Term Integrated Forecasting System (STIFS).

### ***T&D Losses and Unaccounted for***

1949 forward: Calculated as the sum of total net generation and imports minus end use and exports.

### ***End Use***

1949 forward: Table 7.6.

## **Table 7.2b Sources**

1949–September 1977: Federal Power Commission, Form FPC-4, "Monthly Power Plant Report."

October 1977–1981: Federal Energy Regulatory Commission, Form FPC-4, "Monthly Power Plant Report."

1982–1988: U.S. Energy Information Administration (EIA), Form EIA-759, "Monthly Power Plant Report."

1989–1997: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report."

1998–2000: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility."

2001–2003: EIA, Form EIA-906, "Power Plant Report."

2004–2007: EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report."

2008 forward: EIA, Form EIA-923, "Power Plant Operations Report".

## **Table 7.2c Sources**

### **Industrial Sector, Hydroelectric Power, 1949–1988**

1949–September 1977: Federal Power Commission (FPC), Form FPC-4, "Monthly Power Plant Report," for plants with generating capacity exceeding 10 megawatts, and FPC, Form FPC-12C, "Industrial Electric Generating Capacity," for all other plants.

October 1977–1978: Federal Energy Regulatory Commission (FERC), Form FPC-4, "Monthly Power Plant Report," for plants with generating capacity exceeding 10 megawatts, and FERC, Form FPC-12C, "Industrial Electric Generating Capacity," for all other plants.

1979: FERC, Form FPC-4, "Monthly Power Plant Report," for plants with generating capacity exceeding 10 megawatts, and U.S. Energy Information Administration (EIA) estimates for all other plants.

1980–1988: Estimated by EIA as the average generation over the 6-year period of 1974–1979.

### ***All Data, 1989 Forward***

1989–1997: EIA, Form EIA-867, "Annual Nonutility Power Producer Report."

1998–2000: EIA, Form EIA-860B, "Annual Electric Generator Report—Nonutility."

2001–2003: EIA, Form EIA-906, "Power Plant Report."

2004–2007: EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report."

2008 forward: EIA, Form EIA-923, "Power Plant Operations Report".

### Table 7.3b Sources

1949–September 1977: Federal Power Commission, Form FPC-4, "Monthly Power Plant Report."

October 1977–1981: Federal Energy Regulatory Commission, Form FPC-4, "Monthly Power Plant Report."

1982–1988: U.S. Energy Information Administration (EIA), Form EIA-759, "Monthly Power Plant Report."

1989–1997: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report."

1998–2000: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility."

2001–2003: EIA, Form EIA-906, "Power Plant Report."

2004–2007: EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report."

2008 forward: EIA, Form EIA-923, "Power Plant Operations Report".

### Table 7.4b Sources

1949–September 1977: Federal Power Commission, Form FPC-4, "Monthly Power Plant Report."

October 1977–1981: Federal Energy Regulatory Commission, Form FPC-4, "Monthly Power Plant Report."

1982–1988: U.S. Energy Information Administration (EIA), Form EIA-759, "Monthly Power Plant Report."

1989–1997: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report."

1998–2000: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility."

2001–2003: EIA, Form EIA-906, "Power Plant Report."

2004–2007: EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report."

2008 forward: EIA, Form EIA-923, "Power Plant Operations Report".

### Table 7.6 Sources

#### *Retail Sales, Residential and Industrial*

1949–September 1977: Federal Power Commission, Form FPC-5, "Monthly Statement of Electric Operating Revenue and Income."

October 1977–February 1980: Federal Energy Regulatory Commission (FERC), Form FPC-5, "Monthly Statement of Electric Operating Revenue and Income."

March 1980–1982: FERC, Form FPC-5, "Electric Utility Company Monthly Statement."



1983: U.S. Energy Information Administration (EIA), Form EIA-826, "Electric Utility Company Monthly Statement."

1984–2003: EIA, Form EIA-861, "Annual Electric Utility Report."

2004 forward: EIA, *Electric Power Monthly (EPM)* January 2021, Table 5.1.

### ***Retail Sales, Commercial***

1949–2002: Data are estimates. See estimation methodology at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_elec.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_elec.pdf).

2003: EIA, Form EIA-861, "Annual Electric Utility Report."

2004 forward: EIA, EPM, January 2021, Table 5.1.

### ***Retail Sales, Transportation***

1949–2002: Data are estimates. See estimation methodology at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_elec.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_elec.pdf).

2003: EIA, Form EIA-861, "Annual Electric Utility Report."

2004 forward: EIA, EPM January 2021, Table 5.1.

### ***Direct Use, Annual***

1989–1997: EIA, Form EIA-867, "Annual Nonutility Power Producer Report."

1998–2000: EIA, Form EIA-860B, "Annual Electric Generator Report—Nonutility."

2001–2019: EIA, *Electric Power Annual* 2019, October 2020, Table 2.2.

2020: Sum of monthly estimates.

### ***Direct Use, Monthly***


1989 forward: Annual shares are calculated as annual direct use divided by annual commercial and industrial net generation (on Table 7.1). Then monthly direct use estimates are calculated as the annual share multiplied by the monthly commercial and industrial net generation values. For 2020, the 2019 annual share is used.

## 8. Nuclear Energy


---

**Figure 8.1 Nuclear Energy Overview**


Electricity Net Generation, 1957–2019




Nuclear Share of Electricity Net Generation, 1957–2019



Nuclear Electricity Net Generation–November



Capacity Factor, Monthly



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#nuclear>.

Sources: Tables 7.2a and 8.1.

**Table 8.1 Nuclear Energy Overview**

	Total Operable Units <sup>a,b</sup>	Net Summer Capacity of Operable Units <sup>b,c</sup>	Nuclear Electricity Net Generation	Nuclear Share of Electricity Net Generation	Capacity Factor <sup>d</sup>
	Number	Million Kilowatts	Million Kilowatthours	Percent	
<b>1957 Total</b> .....	<b>1</b>	<b>0.055</b>	<b>10</b>	<b>(s)</b>	<b>NA</b>
<b>1960 Total</b> .....	<b>3</b>	<b>.411</b>	<b>518</b>	<b>.1</b>	<b>NA</b>
<b>1965 Total</b> .....	<b>13</b>	<b>.793</b>	<b>3,657</b>	<b>.3</b>	<b>NA</b>
<b>1970 Total</b> .....	<b>20</b>	<b>7.004</b>	<b>21,804</b>	<b>1.4</b>	<b>NA</b>
<b>1975 Total</b> .....	<b>57</b>	<b>37.267</b>	<b>172,505</b>	<b>9.0</b>	<b>55.9</b>
<b>1980 Total</b> .....	<b>71</b>	<b>51.810</b>	<b>251,116</b>	<b>11.0</b>	<b>56.3</b>
<b>1985 Total</b> .....	<b>96</b>	<b>79.397</b>	<b>383,691</b>	<b>15.5</b>	<b>58.0</b>
<b>1990 Total</b> .....	<b>112</b>	<b>99.624</b>	<b>576,862</b>	<b>19.0</b>	<b>66.0</b>
<b>1995 Total</b> .....	<b>109</b>	<b>99.515</b>	<b>673,402</b>	<b>20.1</b>	<b>77.4</b>
<b>2000 Total</b> .....	<b>104</b>	<b>97.860</b>	<b>753,893</b>	<b>19.8</b>	<b>88.1</b>
<b>2001 Total</b> .....	<b>104</b>	<b>98.159</b>	<b>768,826</b>	<b>20.6</b>	<b>89.4</b>
<b>2002 Total</b> .....	<b>104</b>	<b>98.657</b>	<b>780,064</b>	<b>20.2</b>	<b>90.3</b>
<b>2003 Total</b> .....	<b>104</b>	<b>99.209</b>	<b>763,733</b>	<b>19.7</b>	<b>87.9</b>
<b>2004 Total</b> .....	<b>104</b>	<b>99.628</b>	<b>788,528</b>	<b>19.9</b>	<b>90.1</b>
<b>2005 Total</b> .....	<b>104</b>	<b>99.988</b>	<b>781,986</b>	<b>19.3</b>	<b>89.3</b>
<b>2006 Total</b> .....	<b>104</b>	<b>100.334</b>	<b>787,219</b>	<b>19.4</b>	<b>89.6</b>
<b>2007 Total</b> .....	<b>104</b>	<b>100.266</b>	<b>806,425</b>	<b>19.4</b>	<b>91.8</b>
<b>2008 Total</b> .....	<b>104</b>	<b>100.755</b>	<b>806,208</b>	<b>19.6</b>	<b>91.1</b>
<b>2009 Total</b> .....	<b>104</b>	<b>101.004</b>	<b>798,855</b>	<b>20.2</b>	<b>90.3</b>
<b>2010 Total</b> .....	<b>104</b>	<b>101.167</b>	<b>806,968</b>	<b>19.6</b>	<b>91.1</b>
<b>2011 Total</b> .....	<b>104</b>	<b>101.419</b>	<b>790,204</b>	<b>19.3</b>	<b>89.1</b>
<b>2012 Total</b> .....	<b>104</b>	<b>101.885</b>	<b>769,331</b>	<b>19.0</b>	<b>86.1</b>
<b>2013 Total</b> .....	<b>100</b>	<b>99.240</b>	<b>789,016</b>	<b>19.4</b>	<b>89.9</b>
<b>2014 Total</b> .....	<b>99</b>	<b>98.569</b>	<b>797,166</b>	<b>19.5</b>	<b>91.7</b>
<b>2015 Total</b> .....	<b>99</b>	<b>98.672</b>	<b>797,178</b>	<b>19.6</b>	<b>92.3</b>
<b>2016 Total</b> .....	<b>99</b>	<b>99.565</b>	<b>805,694</b>	<b>19.8</b>	<b>92.3</b>
<b>2017 Total</b> .....	<b>99</b>	<b>99.629</b>	<b>804,950</b>	<b>20.0</b>	<b>92.3</b>
<b>2018 January</b> .....	<b>99</b>	<b>99.731</b>	<b>74,649</b>	<b>20.0</b>	<b>100.6</b>
February .....	99	99.731	64,790	21.1	96.7
March .....	99	99.731	67,033	20.8	90.3
April .....	99	99.731	59,133	19.7	82.4
May .....	99	99.731	67,320	19.9	90.7
June .....	99	99.731	69,688	18.7	97.1
July .....	99	99.731	72,456	17.6	97.7
August .....	99	99.731	72,282	17.7	97.4
September .....	98	99.278	64,725	18.2	90.3
October .....	98	99.278	59,397	18.3	80.4
November .....	98	99.433	63,954	19.8	89.3
December .....	98	99.433	71,657	20.9	96.9
<b>Total</b> .....	<b>98</b>	<b>99.433</b>	<b>807,084</b>	<b>19.3</b>	<b>92.5</b>
<b>2019 January</b> .....	<b>98</b>	<b>99.440</b>	<b>73,701</b>	<b>20.5</b>	<b>99.6</b>
February .....	98	99.440	64,715	20.5	96.8
March .....	98	99.440	65,080	19.9	88.0
April .....	98	99.595	60,581	20.4	84.5
May .....	97	98.922	67,124	20.3	90.8
June .....	97	98.922	68,805	19.5	96.6
July .....	97	98.922	72,199	17.6	98.1
August .....	97	98.922	71,911	17.9	97.7
September .....	96	98.119	66,064	18.3	93.1
October .....	96	98.119	62,033	19.4	85.0
November .....	96	98.119	64,125	20.3	90.8
December .....	96	98.119	73,074	21.6	100.1
<b>Total</b> .....	<b>96</b>	<b>98.119</b>	<b>809,409</b>	<b>19.6</b>	<b>93.5</b>
<b>2020 January</b> .....	<b>96</b>	<b>E 98.137</b>	<b>74,170</b>	<b>21.8</b>	<b>E 101.6</b>
February .....	96	E 98.137	65,950	20.7	E 96.6
March .....	96	E 98.137	63,997	20.9	E 87.7
April .....	95	E 97.121	59,170	21.5	E 83.8
May .....	95	E 97.121	64,338	21.2	E 89.0
June .....	95	E 97.121	67,205	19.0	E 96.1
July .....	95	E 97.121	69,385	16.7	E 96.0
August .....	95	E 97.121	68,982	17.3	E 95.5
September .....	94	E 96.520	65,727	19.7	E 94.6
October .....	94	E 96.560	59,362	18.9	E 82.6
November .....	94	E 96.560	61,760	20.5	E 88.8
<b>11-Month Total</b> .....	<b>94</b>	<b>E 96.560</b>	<b>720,048</b>	<b>19.7</b>	<b>E 92.0</b>
<b>2019 11-Month Total</b> .....	<b>96</b>	<b>98.119</b>	<b>736,336</b>	<b>19.4</b>	<b>92.8</b>
<b>2018 11-Month Total</b> .....	<b>98</b>	<b>99.433</b>	<b>735,427</b>	<b>19.2</b>	<b>92.1</b>

<sup>a</sup> Total of nuclear generating units holding full-power licenses, or equivalent permission to operate, at end of period. See Note 1, "Operable Nuclear Reactors," at end of section.

<sup>b</sup> At end of period.

<sup>c</sup> For the definition of "Net Summer Capacity," see Note 2, "Nuclear Capacity," at end of section. Beginning in 2011, monthly capacity values are estimated in two steps: 1) uprates and derates reported on Form EIA-860M are added to specific months; and 2) the difference between the resulting year-end capacity (from data reported on Form EIA-860M) and final capacity (reported on Form EIA-860) is allocated to the month of January.

<sup>d</sup> Beginning in 2008, capacity factor data are calculated using a new

methodology. For an explanation of the method of calculating the capacity factor, see Note 2, "Nuclear Capacity," at end of section.

E=Estimate. NA=Not available. (s)=Less than 0.05%.

Notes: • For a discussion of nuclear reactor unit coverage, see Note 1, "Operable Nuclear Reactors," at end of section. • Nuclear electricity net generation totals may not equal sum of components due to independent rounding.


• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#nuclear> (Excel and CSV files) for all available annual data beginning in 1957 and monthly data beginning in 1973.


Sources: See end of section.

**Figure 8.2 Uranium Overview**


Production and Trade, 1949–2019



Inventories, End of Year 1981–2019



Average Prices, 1981–2019



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.  
Note: See “Uranium Oxide” in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#nuclear>.  
Source: Table 8.2.

**Table 8.2 Uranium Overview**

	Domestic Concentrate Production <sup>a</sup>	Purchased Imports <sup>b</sup>	Export <sup>b</sup> Sales	Electric Plant Purchases From Domestic Suppliers	Loaded Into U.S. Nuclear Reactors <sup>c</sup>	Inventories			Average Price	
						Domestic Suppliers	Electric Plants	Total	Purchased Imports	Domestic Purchases
						Million Pounds Uranium Oxide			Dollars <sup>d</sup> per Pound Uranium Oxide	
1950 .....	0.92	5.5	0.0	NA	NA	NA	NA	NA	NA	NA
1955 .....	5.56	7.6	.0	NA	NA	NA	NA	NA	NA	NA
1960 .....	35.28	36.0	.0	NA	NA	NA	NA	NA	NA	NA
1965 .....	20.88	8.0	.0	NA	NA	NA	NA	NA	NA	NA
1970 .....	25.81	.0	4.2	NA	NA	NA	NA	NA	—	NA
1975 .....	23.20	1.4	1.0	NA	NA	NA	NA	NA	NA	NA
1980 .....	43.70	3.6	5.8	NA	NA	NA	NA	NA	NA	NA
1981 .....	38.47	6.6	4.4	32.6	NA	NA	NA	159.2	32.90	34.65
1982 .....	26.87	17.1	6.2	27.1	NA	NA	NA	174.8	27.23	38.37
1983 .....	21.16	8.2	3.3	24.2	NA	NA	NA	191.8	26.16	38.21
1984 .....	14.88	12.5	2.2	22.5	NA	25.0	160.2	185.2	21.86	32.65
1985 .....	11.31	11.7	5.3	21.7	NA	23.7	153.2	176.9	20.08	31.43
1986 .....	13.51	13.5	1.6	18.9	NA	27.0	144.1	171.1	20.07	30.01
1987 .....	12.99	15.1	1.0	20.8	NA	25.4	137.8	163.2	19.14	27.37
1988 .....	13.13	15.8	3.3	17.6	NA	19.3	125.5	144.8	19.03	26.15
1989 .....	13.84	13.1	2.1	18.4	NA	22.2	115.8	138.1	16.75	19.56
1990 .....	8.89	23.7	2.0	20.5	NA	26.4	102.7	129.1	12.55	15.70
1991 .....	7.95	16.3	3.5	26.8	34.6	20.7	98.0	118.7	15.55	13.66
1992 .....	5.65	23.3	2.8	23.4	43.0	25.2	92.1	117.3	11.34	13.45
1993 .....	3.06	21.0	3.0	15.5	45.1	24.5	81.2	105.7	10.53	13.14
1994 .....	3.35	36.6	17.7	22.7	40.4	21.5	65.4	86.9	8.95	10.30
1995 .....	6.04	41.3	9.8	22.3	51.1	13.7	58.7	72.5	10.20	11.11
1996 .....	6.32	45.4	11.5	23.7	46.2	13.9	66.1	80.0	13.15	13.81
1997 .....	5.64	43.0	17.0	19.4	48.2	40.4	65.9	106.2	11.81	12.87
1998 .....	4.70	43.7	15.1	21.6	38.2	70.7	65.8	136.5	11.19	12.31
1999 .....	4.61	47.6	8.5	21.4	58.8	68.8	58.3	127.1	10.55	11.88
2000 .....	3.98	44.9	13.6	24.3	51.5	56.5	54.8	111.3	9.84	11.45
2001 .....	2.64	46.7	11.7	27.5	52.7	48.1	55.6	103.8	9.51	10.45
2002 .....	e,E 2.34	52.7	15.4	22.7	57.2	48.7	53.5	102.1	10.05	10.35
2003 .....	e,E 2.00	53.0	13.2	21.7	62.3	39.9	45.6	85.5	10.59	10.84
2004 .....	2.28	66.1	13.2	28.2	50.1	37.5	57.7	95.2	12.25	11.91
2005 .....	2.69	65.5	20.5	27.3	58.3	29.1	64.7	93.8	14.83	13.98
2006 .....	4.11	64.8	18.7	27.9	51.7	29.1	77.5	106.6	19.31	18.54
2007 .....	4.53	54.1	14.8	18.5	45.5	31.2	81.2	112.4	34.18	33.13
2008 .....	3.90	57.1	17.2	20.4	51.3	27.0	83.0	110.0	41.30	43.43
2009 .....	3.71	58.9	23.5	17.6	49.4	26.8	84.8	111.5	41.23	44.53
2010 .....	4.23	55.3	23.1	16.2	44.3	24.7	86.5	111.3	47.01	44.88
2011 .....	3.99	54.4	16.7	19.8	50.9	22.3	89.8	112.1	54.00	53.41
2012 .....	4.15	56.2	18.0	21.5	49.5	23.3	97.6	120.9	51.44	56.51
2013 .....	4.66	57.4	18.9	23.3	42.6	21.3	113.1	134.4	48.27	52.51
2014 .....	4.89	56.5	20.0	20.5	50.5	18.7	114.0	132.7	44.03	43.99
2015 .....	3.34	64.2	25.7	19.6	47.4	14.3	121.1	135.5	42.95	43.03
2016 .....	2.92	50.7	17.2	18.8	41.7	16.7	128.0	144.6	40.45	41.64
2017 .....	2.44	42.1	14.0	14.0	45.5	17.8	123.9	141.7	37.09	38.57
2018 .....	1.65	41.5	13.9	11.1	50.4	19.3	111.2	130.5	35.73	42.98
2019 .....	P 1.17	42.9	11.7	W	P 43.2	P 14.3	P 112.8	P 127.1	34.77	W

<sup>a</sup> See "Uranium Concentrate" in Glossary.

<sup>b</sup> Import quantities through 1970 are reported for fiscal years. Prior to 1968, the Atomic Energy Commission was the sole purchaser of all imported uranium oxide. Trade data prior to 1982 were for transactions conducted by uranium suppliers only. For 1982 forward, transactions by uranium buyers (consumers) have been included. Buyer imports and exports prior to 1982 are believed to be small.

<sup>c</sup> Does not include any fuel rods removed from reactors and later reloaded.

<sup>d</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>e</sup> Value has been rounded to avoid disclosure of individual company data.

P=Preliminary. E=Estimate. NA=Not available. W=Value withheld to avoid disclosure of individual company data. — =Not applicable.

Note: See "Uranium Oxide" in Glossary.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly#nuclear> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **1949–1966:** U.S. Department of Energy, Grand Junction Office, *Statistical Data of the Uranium Industry*, Report No. GJO-100, annual reports.

• **1967–2002:** U.S. Energy Information Administration (EIA), *Uranium Industry Annual*, annual reports. • **2003–2017:** EIA, "Domestic Uranium Production Report," annual reports; and EIA, "Uranium Marketing Annual Report," annual reports. • **2018 forward:** EIA, "2019 Domestic Uranium Production Report" (May 2020), Table 3; and EIA, "2019 Uranium Marketing Annual Report" (May 2020), Tables 5, 18, 19, 21, and 22.

**Note 1. Operable Nuclear Reactors.** A reactor is defined as operable when it possesses a full-power license from the Nuclear Regulatory Commission or its predecessor, the Atomic Energy Commission, or equivalent permission to operate, at the end of the year or month shown. The definition includes units retaining full-power licenses during long, non-routine shutdowns that for a time rendered them unable to generate electricity.

**Note 2. Nuclear Capacity.** Nuclear generating units may have more than one type of net capacity rating, including the following:

(a) Net Summer Capacity—The steady hourly output that generating equipment is expected to supply to system load, exclusive of auxiliary power, as demonstrated by test at the time of summer peak demand. Auxiliary power of a typical nuclear power plant is about 5% of gross generation.

(b) Net Design Capacity or Net Design Electrical Rating (DER)—The nominal net electrical output of a unit, specified by the utility and used for plant design.

Through 2007, the monthly capacity factors are calculated as the monthly nuclear electricity net generation divided by the maximum possible nuclear electricity net generation for that month. The maximum possible nuclear electricity net generation is the number of hours in the month (assuming 24-hour days, with no adjustment for changes to or from Daylight Savings Time) multiplied by the net summer capacity of operable nuclear generating units at the end of the month. That fraction is then multiplied by 100 to obtain a percentage. Annual capacity factors are calculated as the annual nuclear electricity net generation divided by the annual maximum possible nuclear electricity net generation (the sum of the monthly values for maximum possible nuclear electricity net generation). For the methodology used to calculate capacity factors beginning in 2008, see U.S. Energy Information Administration, *Electric Power Monthly*, Appendix C notes on “Average Capacity Factors.”

### Table 8.1 Sources

#### *Total Operable Units and Net Summer Capacity of Operable Units*

1957–1982: Compiled from various sources, primarily U.S. Department of Energy, Office of Nuclear Reactor Programs, “U.S. Central Station Nuclear Electric Generating Units: Significant Milestones.”

1983 forward: U.S. Energy Information Administration (EIA), Form EIA-860, “Annual Electric Generator Report,” and predecessor forms; Form EIA-860M, “Monthly Update to the Annual Electric Generator Report”; and monthly updates as appropriate. See <https://www.eia.gov/nuclear/generation/index.html> for a list of operable units.

#### *Nuclear Electricity Net Generation and Nuclear Share of Electricity Net Generation*

1957 forward: Table 7.2a.

#### *Capacity Factor*

1973–2007: Calculated by EIA using the method described above in Note 2.

2008 forward: EIA, Form EIA-860, “Annual Electric Generator Report”; Form EIA-860M, “Monthly Update to the Annual Electric Generator Report”; and Form EIA-923, “Power Plant Operations Report.”


## 9. Energy Prices

---




**Figure 9.1 Petroleum Prices**


Crude Oil Prices, 1949–2019



Composite Refiner Acquisition Cost, Monthly



Refiner Prices to End Users: Select Products, November 2020



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
Sources: Tables 9.1, 9.5 and 9.7.

**Table 9.1 Crude Oil Price Summary**  
(Dollars<sup>a</sup> per Barrel)

	Domestic First Purchase Price <sup>c</sup>	F.O.B. Cost of Imports <sup>d</sup>	Landed Cost of Imports <sup>e</sup>	Refiner Acquisition Cost <sup>b</sup>		
				Domestic	Imported	Composite
<b>1950 Average</b> .....	2.51	NA	NA	NA	NA	NA
<b>1955 Average</b> .....	2.77	NA	NA	NA	NA	NA
<b>1960 Average</b> .....	2.88	NA	NA	NA	NA	NA
<b>1965 Average</b> .....	2.86	NA	NA	NA	NA	NA
<b>1970 Average</b> .....	3.18	NA	NA	<sup>E</sup> 3.46	<sup>E</sup> 2.96	<sup>E</sup> 3.40
<b>1975 Average</b> .....	7.67	11.18	12.70	8.39	13.93	10.38
<b>1980 Average</b> .....	21.59	32.37	33.67	24.23	33.89	28.07
<b>1985 Average</b> .....	24.09	25.84	26.67	26.66	26.99	26.75
<b>1990 Average</b> .....	20.03	20.37	21.13	22.59	21.76	22.22
<b>1995 Average</b> .....	14.62	15.69	16.78	17.33	17.14	17.23
<b>2000 Average</b> .....	26.72	26.27	27.53	29.11	27.70	28.26
<b>2001 Average</b> .....	21.84	20.46	21.82	24.33	22.00	22.95
<b>2002 Average</b> .....	22.51	22.63	23.91	24.65	23.71	24.10
<b>2003 Average</b> .....	27.56	25.86	27.69	29.82	27.71	28.53
<b>2004 Average</b> .....	36.77	33.75	36.07	38.97	35.90	36.98
<b>2005 Average</b> .....	50.28	47.60	49.29	52.94	48.86	50.24
<b>2006 Average</b> .....	59.69	57.03	59.11	62.62	59.02	60.24
<b>2007 Average</b> .....	66.52	66.36	67.97	69.65	67.04	67.94
<b>2008 Average</b> .....	94.04	90.32	93.33	98.47	92.77	94.74
<b>2009 Average</b> .....	56.35	57.78	60.23	59.49	59.17	59.29
<b>2010 Average</b> .....	74.71	74.19	76.50	78.01	75.86	76.69
<b>2011 Average</b> .....	95.73	101.66	102.92	100.71	102.63	101.87
<b>2012 Average</b> .....	94.52	99.78	101.00	100.72	101.09	100.93
<b>2013 Average</b> .....	95.99	96.56	96.99	102.91	98.11	100.49
<b>2014 Average</b> .....	87.39	85.65	88.16	94.05	89.56	92.02
<b>2015 Average</b> .....	44.39	41.91	45.38	49.94	46.38	48.39
<b>2016 Average</b> .....	38.29	36.37	38.56	42.41	38.75	40.66
<b>2017 Average</b> .....	48.05	45.58	48.50	52.05	49.12	50.68
<b>2018 January</b> .....	62.25	55.73	58.25	66.08	59.71	63.25
February .....	61.18	53.42	56.76	64.68	58.03	61.74
March .....	60.68	53.35	56.32	64.03	56.82	60.81
April .....	63.50	58.56	60.62	67.14	61.24	64.41
May .....	66.16	62.95	65.15	71.29	65.89	68.91
June .....	62.80	63.09	65.48	69.63	66.82	68.35
July .....	67.00	62.35	65.44	73.33	66.62	70.29
August .....	62.64	61.41	64.16	69.45	65.48	67.68
September .....	63.54	61.56	63.69	71.09	66.70	69.29
October .....	65.18	60.23	61.78	73.07	67.79	70.99
November .....	55.65	44.66	47.16	62.47	54.40	59.01
December .....	47.63	36.91	39.14	53.25	42.80	48.83
<b>Average</b> .....	<b>61.40</b>	<b>56.31</b>	<b>58.89</b>	<b>67.05</b>	<b>60.95</b>	<b>64.38</b>
<b>2019 January</b> .....	48.00	48.70	49.25	54.06	49.71	52.29
February .....	52.60	54.23	56.17	58.24	56.66	57.62
March .....	57.46	57.54	59.48	61.97	61.14	61.64
April .....	63.00	61.31	63.62	67.21	65.42	66.51
May .....	59.73	60.74	63.70	65.17	65.03	65.11
June .....	54.34	54.56	57.43	59.81	58.16	59.16
July .....	56.47	54.51	57.00	61.47	59.18	60.53
August .....	53.63	51.98	54.91	57.88	55.41	56.90
September .....	55.14	52.68	55.06	59.41	57.31	58.60
October .....	53.14	50.40	53.74	56.69	54.44	55.85
November .....	54.96	51.87	54.48	59.42	55.27	57.88
December .....	58.41	51.57	53.92	62.23	56.85	60.27
<b>Average</b> .....	<b>55.59</b>	<b>54.27</b>	<b>56.60</b>	<b>60.31</b>	<b>57.94</b>	<b>59.38</b>
<b>2020 January</b> .....	56.86	46.98	51.03	60.36	53.96	57.94
February .....	50.03	41.65	44.57	53.98	47.42	51.37
March .....	31.80	24.10	26.77	34.98	28.50	32.55
April .....	15.99	13.91	17.18	21.25	16.74	19.41
May .....	18.09	19.28	22.73	24.97	22.56	23.84
June .....	33.53	32.41	36.05	37.25	36.14	36.80
July .....	37.55	35.35	38.91	40.55	39.33	40.07
August .....	39.42	35.99	40.15	42.82	41.72	42.41
September .....	36.89	<sup>R</sup> 35.45	<sup>R</sup> 37.96	40.42	38.76	39.83
October .....	36.46	<sup>R</sup> 34.32	<sup>R</sup> 36.88	40.06	37.80	39.21
November .....	<sup>R</sup> 38.18	<sup>R</sup> 35.45	<sup>R</sup> 38.00	<sup>R</sup> 41.56	<sup>R</sup> 38.72	<sup>R</sup> 40.48
December .....	NA	NA	NA	<sup>E</sup> 46.57	<sup>E</sup> 43.20	<sup>E</sup> 45.26

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 1, "Crude Oil Refinery Acquisition Costs," at end of section.

<sup>c</sup> See Note 2, "Crude Oil Domestic First Purchase Prices," at end of section.

<sup>d</sup> See Note 3, "Crude Oil F.O.B. Costs," at end of section.

<sup>e</sup> See Note 4, "Crude Oil Landed Costs," at end of section.

<sup>R</sup>=Revised. <sup>NA</sup>=Not available. <sup>E</sup>=Estimate.

Notes: • Domestic first purchase prices and refinery acquisition costs for the current two months are preliminary. F.O.B. and landed costs for the current three months are preliminary. • Through 1980, F.O.B. and landed costs reflect the

period of reporting; beginning in 1981, they reflect the period of loading. • Annual averages are the averages of the monthly prices, weighted by volume. • Geographic coverage is the 50 states, the District of Columbia, Puerto Rico, the Virgin Islands, and all U.S. Territories and Possessions.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 9.2 F.O.B. Costs of Crude Oil Imports From Selected Countries**  
(Dollars<sup>a</sup> per Barrel)

	Selected Countries							Persian Gulf Nations <sup>b</sup>	Total OPEC <sup>c</sup>	Total Non-OPEC <sup>c</sup>
	Angola	Colombia	Mexico	Nigeria	Saudi Arabia	United Kingdom	Venezuela			
1973 Average <sup>d</sup>	W	W	—	7.81	3.25	—	5.39	3.68	5.43	4.80
1975 Average	10.97	—	11.44	11.82	10.87	—	11.04	10.88	11.34	10.62
1980 Average	33.45	W	31.06	35.93	28.17	34.36	24.81	28.92	32.21	32.85
1985 Average	26.30	—	25.33	28.04	22.04	27.64	23.64	23.31	25.67	25.96
1990 Average	20.23	20.75	19.26	22.46	20.36	23.43	19.55	18.54	20.40	20.32
1995 Average	16.58	16.73	15.64	17.40	W	16.94	13.86	W	15.36	16.02
2000 Average	27.90	29.04	25.39	28.70	24.62	27.21	24.45	24.72	25.56	26.77
2001 Average	23.25	24.25	18.89	24.85	18.98	23.30	18.01	18.89	19.73	21.04
2002 Average	24.09	24.64	21.60	25.38	23.92	24.50	20.13	23.38	22.18	22.93
2003 Average	28.22	28.89	24.83	29.40	25.03	28.76	23.81	25.17	25.36	26.21
2004 Average	37.26	37.73	31.55	38.71	34.08	37.30	31.78	33.08	33.95	33.58
2005 Average	52.48	51.89	43.00	55.95	47.96	54.48	46.39	47.21	49.60	45.79
2006 Average	62.23	59.77	52.91	65.69	56.09	66.03	55.80	56.02	59.18	55.35
2007 Average	67.80	67.93	61.35	76.64	W	69.96	64.10	69.93	69.58	62.69
2008 Average	95.66	91.17	84.61	102.06	93.03	96.33	88.06	91.44	93.15	87.15
2009 Average	57.07	57.90	56.47	64.61	57.87	65.63	55.58	59.53	58.53	57.16
2010 Average	78.18	72.56	72.46	80.83	76.44	W	70.30	75.65	75.23	73.24
2011 Average	111.82	100.21	100.90	115.35	107.08	—	97.23	106.47	105.34	98.49
2012 Average	111.23	106.43	101.84	114.51	106.65	—	100.15	105.45	104.39	95.71
2013 Average	107.71	101.24	98.40	110.06	101.16	W	97.52	100.62	100.57	93.67
2014 Average	W	80.75	86.55	W	95.60	—	84.51	94.03	89.76	82.95
2015 Average	W	47.52	44.90	W	47.53	—	40.73	46.95	43.25	41.19
2016 Average	42.68	35.28	36.22	46.20	39.30	W	34.71	38.76	38.51	34.81
2017 Average	W	48.34	46.66	54.77	51.30	W	45.60	50.16	49.55	43.30
2018 January	W	61.24	58.75	W	65.03	W	62.07	63.50	64.12	51.34
February	W	59.66	56.74	W	63.19	W	55.72	61.90	61.07	49.79
March	—	W	56.73	W	65.04	W	56.84	61.90	60.90	49.09
April	W	65.95	57.68	W	68.33	W	63.28	66.05	66.09	53.73
May	—	W	63.32	W	70.57	W	66.56	69.66	70.07	58.99
June	W	W	64.46	W	71.32	W	64.82	70.18	69.44	59.81
July	W	68.32	66.21	—	70.62	—	62.93	70.30	67.64	59.85
August	W	67.29	63.08	W	71.08	W	63.09	70.11	68.40	57.46
September	W	W	68.15	W	72.90	W	68.94	72.05	71.80	56.39
October	W	W	73.91	W	74.73	W	68.44	74.61	73.26	54.18
November	—	64.87	63.76	W	62.34	W	53.25	63.44	60.58	36.18
December	—	50.04	52.70	W	57.79	—	46.46	55.74	53.04	28.95
Average	74.44	62.51	62.75	71.41	68.23	71.65	61.25	66.55	65.61	51.41
2019 January	—	53.27	54.81	W	W	W	48.25	58.54	54.94	46.13
February	—	56.59	58.52	W	W	W	—	62.58	63.09	51.63
March	—	61.28	60.66	W	67.34	W	—	65.62	65.95	55.66
April	—	67.09	63.13	W	70.60	70.45	—	68.89	70.54	59.56
May	W	65.40	62.16	70.81	W	69.74	—	65.97	67.80	59.17
June	W	61.09	58.75	W	W	W	—	62.67	63.28	51.82
July	W	W	58.93	W	W	W	—	62.08	63.82	52.32
August	—	59.37	50.72	W	59.24	W	—	57.90	59.51	50.47
September	—	W	56.73	W	60.27	W	—	58.79	59.66	51.05
October	—	W	51.74	W	W	W	—	56.42	58.30	48.81
November	—	59.42	51.24	W	60.69	W	—	58.47	60.86	49.22
December	—	58.95	55.23	—	63.59	W	—	61.63	61.72	50.26
Average	66.97	60.61	56.72	67.21	63.48	65.20	48.57	61.43	62.11	52.36
2020 January	—	56.90	53.70	W	49.26	W	—	50.36	53.02	46.47
February	—	W	47.74	W	W	W	—	W	53.00	40.64
March	W	27.34	28.59	W	W	W	—	24.18	28.28	23.56
April	W	19.88	12.25	W	21.44	—	—	21.44	22.79	11.81
May	—	W	22.92	W	W	W	—	29.19	30.80	18.09
June	—	33.32	34.36	W	W	W	—	40.84	41.40	31.38
July	—	W	37.95	W	42.86	—	—	40.60	41.48	34.64
August	—	40.34	40.16	W	W	—	—	W	44.02	35.77
September	—	37.36	38.42	W	—	—	—	W	<sup>R</sup> 41.19	35.17
October	W	W	<sup>R</sup> 37.03	<sup>R</sup> W	—	—	—	—	<sup>R</sup> 40.10	<sup>R</sup> 33.97
November	—	W	39.04	—	—	—	—	W	W	35.33

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, United Arab Emirates, and the Neutral Zone (between Kuwait and Saudi Arabia).

<sup>c</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary for exact years of each country's membership. On this table, "Total OPEC" for all years includes Algeria, Iran, Iraq, Kuwait, Libya, Nigeria, Qatar, Saudi Arabia, United Arab Emirates, and Venezuela; Angola is included in "Total OPEC" 2007 forward; Gabon is included in "Total OPEC" 1974–1995 and July 2016 forward; Ecuador is included in "Total OPEC" 1973–1992 and 2008 forward; Indonesia is included in "Total OPEC" 1973–2008 and 2016.

<sup>d</sup> Based on October, November, and December data only.

<sup>R</sup>=Revised. —=No data reported. W=Value withheld to avoid disclosure of individual company data.

Notes: • The Free on Board (F.O.B.) cost at the country of origin excludes all

costs related to insurance and transportation. See "F.O.B. (Free on Board)" in Glossary, and Note 3, "Crude Oil F.O.B. Costs," at end of section. • Values for the current two months are preliminary. • Through 1980, prices reflect the period of reporting; beginning in 1981, prices reflect the period of loading. • Annual averages are averages of the monthly prices, including prices not published, weighted by volume. • Cargoes that are purchased on a "netback" basis, or under similar contractual arrangements whereby the actual purchase price is not established at the time the crude oil is acquired for importation into the United States, are not included in the published data until the actual prices have been determined and reported. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Table 9.3 Landed Costs of Crude Oil Imports From Selected Countries**  
(Dollars<sup>a</sup> per Barrel)

	Selected Countries								Persian Gulf Nations <sup>b</sup>	Total OPEC <sup>c</sup>	Total Non-OPEC <sup>c</sup>
	Angola	Canada	Colombia	Mexico	Nigeria	Saudi Arabia	United Kingdom	Venezuela			
1973 Average <sup>d</sup>	W	5.33	W	—	9.08	5.37	—	5.99	5.91	6.85	5.64
1975 Average	11.81	12.84	—	12.61	12.70	12.50	—	12.36	12.64	12.70	12.70
1980 Average	34.76	30.11	W	31.77	37.15	29.80	35.68	25.92	30.59	33.56	33.99
1985 Average	27.39	25.71	—	25.63	28.96	24.72	28.36	24.43	25.50	26.86	26.53
1990 Average	21.51	20.48	22.34	19.64	23.33	21.82	22.65	20.31	20.55	21.23	20.98
1995 Average	17.66	16.65	17.45	16.19	18.25	16.84	17.91	14.81	16.78	16.61	16.95
2000 Average	29.57	26.69	29.68	26.03	30.04	26.58	29.26	26.05	26.77	27.29	27.80
2001 Average	25.13	20.72	25.88	19.37	26.55	20.98	25.32	19.81	20.73	21.52	22.17
2002 Average	25.43	22.98	25.28	22.09	26.45	24.77	26.35	21.93	24.13	23.83	23.97
2003 Average	30.14	26.76	30.55	25.48	31.07	27.50	30.62	25.70	27.54	27.70	27.68
2004 Average	39.62	34.51	39.03	32.25	40.95	37.11	39.28	33.79	36.53	36.84	35.29
2005 Average	54.31	44.73	53.42	43.47	57.55	50.31	55.28	47.87	49.68	51.36	47.31
2006 Average	64.85	53.90	62.13	53.76	68.26	59.19	67.44	57.37	58.92	61.21	57.14
2007 Average	71.27	60.38	70.91	62.31	78.01	70.78	72.47	66.13	69.83	71.14	63.96
2008 Average	98.18	90.00	93.43	85.97	104.83	94.75	96.95	90.76	93.59	95.49	90.59
2009 Average	61.32	57.60	58.50	57.35	68.01	62.14	63.87	57.78	62.15	61.90	58.58
2010 Average	80.61	72.80	74.25	72.86	83.14	79.29	80.29	72.43	78.60	78.28	74.68
2011 Average	114.05	89.92	102.57	101.21	116.43	108.83	118.45	100.14	108.01	107.84	98.64
2012 Average	114.95	84.24	107.07	102.45	116.88	108.15	W	101.58	107.74	107.56	95.05
2013 Average	110.81	84.41	103.00	99.06	112.87	102.60	111.23	99.34	102.53	102.98	91.99
2014 Average	99.25	81.30	88.29	87.48	102.16	94.91	W	86.88	95.30	93.10	84.67
2015 Average	51.73	41.99	49.53	45.51	54.70	49.78	W	42.87	49.43	47.44	44.09
2016 Average	44.65	36.27	38.86	36.64	48.11	42.14	W	35.50	41.20	40.54	37.09
2017 Average	54.17	44.93	50.60	47.73	56.48	52.56	56.11	47.02	51.42	51.26	46.67
2018 January	66.55	51.17	63.25	59.86	69.15	64.81	W	62.79	63.83	64.78	54.69
February	W	48.27	62.55	57.37	69.60	65.30	68.19	55.98	63.21	62.93	53.05
March	70.27	47.01	63.59	56.99	70.59	66.77	W	57.72	63.72	63.53	51.07
April	W	52.22	66.34	58.62	W	69.44	73.82	63.62	67.09	66.95	56.32
May	W	58.19	70.63	64.03	79.38	71.28	W	67.45	70.85	71.50	61.72
June	76.28	58.57	70.64	65.38	W	72.17	72.88	65.81	71.49	70.65	62.95
July	75.55	59.00	71.20	66.82	W	72.56	—	63.67	71.62	70.54	62.54
August	75.45	56.78	68.79	64.18	W	72.85	72.41	64.12	71.64	70.48	60.79
September	75.83	52.35	73.88	69.79	W	72.56	W	70.73	72.26	72.45	58.76
October	W	47.96	74.22	74.76	W	73.75	W	69.31	72.24	72.19	57.15
November	—	28.06	66.20	64.52	68.03	65.87	W	55.70	64.99	63.30	38.56
December	—	21.62	54.71	53.89	62.21	60.39	W	48.93	58.67	57.11	30.89
Average	73.42	48.34	66.75	63.48	71.93	69.40	73.28	62.46	67.55	67.22	54.27
2019 January	—	40.33	56.26	56.12	W	61.69	W	51.68	59.80	57.34	45.44
February	—	50.48	59.69	59.72	W	66.37	W	52.72	64.07	62.76	53.82
March	—	54.61	64.65	61.82	W	67.50	W	55.25	65.81	65.30	57.85
April	W	59.01	69.08	64.18	75.99	69.74	73.00	—	68.83	69.89	62.21
May	72.84	58.49	68.17	62.81	72.66	67.93	71.30	W	67.05	68.82	62.19
June	W	50.84	65.87	59.32	69.37	65.06	65.41	—	63.71	65.04	55.30
July	W	51.14	64.10	59.50	67.57	64.14	64.63	—	63.83	64.76	55.02
August	—	50.68	59.22	51.59	65.76	61.59	W	—	60.87	61.75	52.99
September	W	50.64	58.77	57.73	66.34	61.59	64.40	—	61.03	61.58	53.27
October	W	49.64	57.88	53.03	65.73	62.36	63.06	—	59.89	60.99	51.93
November	W	49.20	60.91	52.57	69.20	64.85	W	—	62.06	62.97	51.97
December	—	48.36	62.66	56.78	W	65.83	W	—	63.23	63.52	52.13
Average	68.58	51.10	62.83	57.96	68.78	64.86	66.65	52.36	63.27	63.41	54.65
2020 January	—	45.70	62.93	55.93	W	53.68	W	—	55.30	57.36	49.70
February	—	39.83	54.16	49.62	62.07	52.48	W	—	52.65	54.24	42.80
March	W	23.47	35.15	29.42	W	23.94	W	—	27.04	29.04	25.97
April	30.93	13.34	23.24	13.73	W	22.33	W	—	22.78	23.66	14.91
May	W	17.45	28.61	24.35	W	28.84	W	—	29.99	30.70	20.75
June	—	34.85	33.13	35.04	W	39.88	W	—	40.56	41.07	35.20
July	—	37.69	37.64	38.72	W	43.68	W	—	42.74	43.46	38.38
August	—	38.89	41.71	40.88	W	43.83	—	—	42.75	43.04	39.86
September	W	35.66	38.27	39.01	W	43.13	W	—	41.83	42.13	37.39
October	W	35.69	38.29	37.44	W	W	W	—	W	40.78	36.60
November	W	36.66	42.56	39.54	W	W	W	—	41.54	42.87	37.71

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.  
<sup>b</sup> Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, United Arab Emirates, and the Neutral Zone (between Kuwait and Saudi Arabia).  
<sup>c</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary for exact years of each country's membership. On this table, "Total OPEC" for all years includes Algeria, Iran, Iraq, Kuwait, Libya, Nigeria, Qatar, Saudi Arabia, United Arab Emirates, and Venezuela; Angola is included in "Total OPEC" 2007 forward; Gabon is included in "Total OPEC" 1974–1995 and July 2016 forward; Ecuador is included in "Total OPEC" 1973–1992 and 2008 forward; Indonesia is included in "Total OPEC" 1973–2008 and 2016.  
<sup>d</sup> Based on October, November, and December data only.  
 R=Revised. —=No data reported. W=Value withheld to avoid disclosure of individual company data.  
 Notes: • See "Landed Costs" in Glossary, and Note 4, "Crude Oil Landed Costs," at end of section. • Values for the current two months are preliminary.  
 • Through 1980, prices reflect the period of reporting; beginning in 1981, prices

reflect the period of loading. • Annual averages are averages of the monthly prices, including prices not published, weighted by volume. • Cargoes that are purchased on a "netback" basis, or under similar contractual arrangements whereby the actual purchase price is not established at the time the crude oil is acquired for importation into the United States, are not included in the published data until the actual prices have been determined and reported. • U.S. geographic coverage is the 50 states and the District of Columbia.  
 Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual and monthly data beginning in 1973.  
 Sources: • **October 1973–September 1977:** Federal Energy Administration, Form FEA-F701-M-0, "Transfer Pricing Report." • **October 1977–December 1977:** U.S. Energy Information Administration (EIA), Form FEA-F701-M-0, "Transfer Pricing Report." • **1978–2007:** EIA, *Petroleum Marketing Annual 2008*, Table 22. • **2008 forward:** EIA, *Petroleum Marketing Monthly*, February 2021, Table 22.

**Table 9.4 Retail Motor Gasoline and On-Highway Diesel Fuel Prices**  
(Dollars<sup>a</sup> per Gallon, Including Taxes)

	Platt's / Bureau of Labor Statistics Data				U.S. Energy Information Administration Data			
	Motor Gasoline by Grade				Regular Motor Gasoline by Area Type			On-Highway Diesel Fuel
	Leaded Regular	Unleaded Regular	Unleaded Premium <sup>b</sup>	All Grades <sup>c</sup>	Conventional Gasoline Areas <sup>d</sup>	Reformulated Gasoline Areas <sup>e</sup>	All Areas	
1950 Average .....	0.268	NA	NA	NA	--	--	--	--
1955 Average .....	.291	NA	NA	NA	--	--	--	--
1960 Average .....	.311	NA	NA	NA	--	--	--	--
1965 Average .....	.312	NA	NA	NA	--	--	--	--
1970 Average .....	.357	NA	NA	NA	--	--	--	--
1975 Average .....	.567	NA	NA	NA	--	--	--	--
1980 Average .....	1.191	1.245	NA	1.221	--	--	--	--
1985 Average .....	1.115	1.202	1.340	1.196	--	--	--	--
1990 Average .....	1.149	1.164	1.349	1.217	NA	NA	NA	NA
1995 Average .....	--	1.147	1.336	1.205	1.103	1.163	1.111	1.109
2000 Average .....	--	1.510	1.693	1.563	1.462	1.543	1.484	1.491
2001 Average .....	--	1.461	1.657	1.531	1.384	1.498	1.420	1.401
2002 Average .....	--	1.358	1.556	1.441	1.313	1.408	1.345	1.319
2003 Average .....	--	1.591	1.777	1.638	1.516	1.655	1.561	1.509
2004 Average .....	--	1.880	2.068	1.923	1.812	1.937	1.852	1.810
2005 Average .....	--	2.295	2.491	2.338	2.240	2.335	2.270	2.402
2006 Average .....	--	2.589	2.805	2.635	2.533	2.654	2.572	2.705
2007 Average .....	--	2.801	3.033	2.849	2.767	2.857	2.796	2.885
2008 Average .....	--	3.266	3.519	3.317	3.213	3.314	3.246	3.803
2009 Average .....	--	2.350	2.607	2.401	2.315	2.433	2.353	2.467
2010 Average .....	--	2.788	3.047	2.836	2.742	2.864	2.782	2.992
2011 Average .....	--	3.527	3.792	3.577	3.476	3.616	3.521	3.840
2012 Average .....	--	3.644	3.922	3.695	3.552	3.757	3.618	3.968
2013 Average .....	--	3.526	3.843	3.584	3.443	3.635	3.505	3.922
2014 Average .....	--	3.367	3.713	3.425	3.299	3.481	3.358	3.825
2015 Average .....	--	2.448	2.866	2.510	2.334	2.629	2.429	2.707
2016 Average .....	--	2.142	2.610	2.204	2.070	2.296	2.143	2.304
2017 Average .....	--	2.408	2.911	2.469	2.333	2.586	2.415	2.650
2018 January .....	--	2.539	3.042	2.596	2.467	2.738	2.555	3.018
February .....	--	2.575	3.091	2.632	2.488	2.795	2.587	3.046
March .....	--	2.572	3.101	2.631	2.488	2.808	2.591	2.988
April .....	--	2.737	3.258	2.795	2.652	2.978	2.757	3.096
May .....	--	2.907	3.423	2.963	2.808	3.096	2.901	3.244
June .....	--	2.914	3.440	2.970	2.802	3.078	2.891	3.253
July .....	--	2.873	3.399	2.930	2.770	3.015	2.849	3.233
August .....	--	2.862	3.384	2.919	2.768	2.983	2.836	3.218
September .....	--	2.873	3.400	2.930	2.769	2.979	2.836	3.262
October .....	--	2.887	3.431	2.945	2.785	3.017	2.860	3.365
November .....	--	2.671	3.251	2.733	2.561	2.829	2.647	3.300
December .....	--	2.414	3.015	2.479	2.263	2.581	2.366	3.123
Average .....	--	2.735	3.270	2.794	2.631	2.904	2.719	3.178
2019 January .....	--	2.289	2.874	2.352	2.145	2.464	2.248	2.980
February .....	--	2.353	2.901	2.412	2.223	2.495	2.309	2.997
March .....	--	2.564	3.079	2.620	2.443	2.673	2.516	3.076
April .....	--	2.835	3.382	2.894	2.694	3.023	2.798	3.121
May .....	--	2.901	3.471	2.963	2.731	3.136	2.859	3.161
June .....	--	2.752	3.328	2.814	2.601	2.963	2.716	3.089
July .....	--	2.776	3.327	2.836	2.640	2.954	2.740	3.045
August .....	--	2.655	3.222	2.716	2.521	2.836	2.621	3.005
September .....	--	2.630	3.214	2.694	2.489	2.814	2.592	3.016
October .....	--	2.673	3.297	2.741	2.497	2.907	2.627	3.053
November .....	--	2.620	3.254	2.687	2.480	2.853	2.598	3.069
December .....	--	2.587	3.190	2.652	2.469	2.744	2.555	3.055
Average .....	--	2.636	3.212	2.698	2.501	2.827	2.604	3.056
2020 January .....	--	2.567	3.157	2.631	2.459	2.740	2.548	3.048
February .....	--	2.465	3.071	2.530	2.348	2.645	2.442	2.910
March .....	--	2.267	2.893	2.334	2.126	2.468	2.234	2.729
April .....	--	1.876	2.527	1.946	1.721	2.096	1.841	2.493
May .....	--	1.879	2.490	1.946	1.769	2.084	1.870	2.392
June .....	--	2.076	2.673	2.141	1.998	2.263	2.082	2.408
July .....	--	2.176	2.783	2.243	2.099	2.365	2.183	2.434
August .....	--	2.177	2.795	2.245	2.093	2.374	2.182	2.429
September .....	--	2.193	2.810	2.260	2.095	2.375	2.183	2.414
October .....	--	2.159	2.782	2.228	2.073	2.344	2.158	2.389
November .....	--	2.090	2.727	2.159	2.015	2.312	2.108	2.432
December .....	--	2.168	2.778	2.235	2.105	2.387	2.195	2.585
Average .....	--	2.174	2.791	2.242	2.074	2.370	2.168	2.551
2021 January .....	--	2.326	2.921	2.391	2.244	2.527	2.334	2.681

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.  
<sup>b</sup> The 1981 average (available in Web file) is based on September through December data only.  
<sup>c</sup> Also includes grades of motor gasoline not shown separately.  
<sup>d</sup> Any area that does not require the sale of reformulated gasoline.  
<sup>e</sup> "Reformulated Gasoline Areas" are ozone nonattainment areas designated by the U.S. Environmental Protection Agency that require the use of reformulated gasoline (RFG). Areas are reclassified each time a shift in or out of an RFG program occurs due to federal or state regulations.  
 NA=Not available. --=Not applicable.  
 Notes: • See Note 5, "Motor Gasoline Prices," at end of section. • See "Motor Gasoline Grades," "Motor Gasoline, Conventional," "Motor Gasoline, Oxygenated," and "Motor Gasoline, Reformulated" in Glossary. • Geographic coverage: for columns 1-4, current coverage is 85 urban areas; for columns 5-7, coverage is the 50 states and the District of Columbia; for column 8, coverage is the 48 contiguous

states and the District of Columbia.  
 Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
 Sources: • **Motor Gasoline by Grade, Monthly Data: October 1973 forward**—U.S. Department of Labor, Bureau of Labor Statistics (BLS), *U.S. City Average Gasoline Prices*. • **Motor Gasoline by Grade, Annual Data: 1949-1973**—Platt's Oil Price Handbook and Oilmanac, 1974, 51st Edition. **1974 forward**—calculated by the U.S. Energy Information Administration (EIA) as simple averages of the BLS monthly data. • **Regular Motor Gasoline by Area Type:** EIA, calculated as simple averages of weighted weekly estimates from "Weekly U.S. Retail Gasoline Prices, Regular Grade." • **On-Highway Diesel Fuel:** EIA, calculated as simple averages of weighted weekly estimates from "Weekly Retail On-Highway Diesel Prices."

**Table 9.5 Refiner Prices of Residual Fuel Oil**  
(Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Residual Fuel Oil Sulfur Content Less Than or Equal to 1%		Residual Fuel Oil Sulfur Content Greater Than 1%		Average	
	Sales for Resale	Sales to End Users	Sales for Resale	Sales to End Users	Sales for Resale	Sales to End Users
<b>1978 Average</b> .....	<b>0.293</b>	<b>0.314</b>	<b>0.245</b>	<b>0.275</b>	<b>0.263</b>	<b>0.298</b>
<b>1980 Average</b> .....	<b>.608</b>	<b>.675</b>	<b>.479</b>	<b>.523</b>	<b>.528</b>	<b>.607</b>
<b>1985 Average</b> .....	<b>.610</b>	<b>.644</b>	<b>.560</b>	<b>.582</b>	<b>.577</b>	<b>.610</b>
<b>1990 Average</b> .....	<b>.472</b>	<b>.505</b>	<b>.372</b>	<b>.400</b>	<b>.413</b>	<b>.444</b>
<b>1995 Average</b> .....	<b>.383</b>	<b>.436</b>	<b>.338</b>	<b>.377</b>	<b>.363</b>	<b>.392</b>
<b>2000 Average</b> .....	<b>.627</b>	<b>.708</b>	<b>.512</b>	<b>.566</b>	<b>.566</b>	<b>.602</b>
<b>2001 Average</b> .....	<b>.523</b>	<b>.642</b>	<b>.428</b>	<b>.492</b>	<b>.476</b>	<b>.531</b>
<b>2002 Average</b> .....	<b>.546</b>	<b>.640</b>	<b>.508</b>	<b>.544</b>	<b>.530</b>	<b>.569</b>
<b>2003 Average</b> .....	<b>.728</b>	<b>.804</b>	<b>.588</b>	<b>.651</b>	<b>.661</b>	<b>.698</b>
<b>2004 Average</b> .....	<b>.764</b>	<b>.835</b>	<b>.601</b>	<b>.692</b>	<b>.681</b>	<b>.739</b>
<b>2005 Average</b> .....	<b>1.115</b>	<b>1.168</b>	<b>.842</b>	<b>.974</b>	<b>.971</b>	<b>1.048</b>
<b>2006 Average</b> .....	<b>1.202</b>	<b>1.342</b>	<b>1.085</b>	<b>1.173</b>	<b>1.136</b>	<b>1.218</b>
<b>2007 Average</b> .....	<b>1.406</b>	<b>1.436</b>	<b>1.314</b>	<b>1.350</b>	<b>1.350</b>	<b>1.374</b>
<b>2008 Average</b> .....	<b>1.918</b>	<b>2.144</b>	<b>1.843</b>	<b>1.889</b>	<b>1.866</b>	<b>1.964</b>
<b>2009 Average</b> .....	<b>1.337</b>	<b>1.413</b>	<b>1.344</b>	<b>1.306</b>	<b>1.342</b>	<b>1.341</b>
<b>2010 Average</b> .....	<b>1.756</b>	<b>1.920</b>	<b>1.679</b>	<b>1.619</b>	<b>1.697</b>	<b>1.713</b>
<b>2011 Average</b> .....	<b>2.389</b>	<b>2.736</b>	<b>2.316</b>	<b>2.257</b>	<b>2.336</b>	<b>2.401</b>
<b>2012 Average</b> .....	<b>2.548</b>	<b>3.025</b>	<b>2.429</b>	<b>2.433</b>	<b>2.457</b>	<b>2.592</b>
<b>2013 Average</b> .....	<b>2.363</b>	<b>2.883</b>	<b>2.249</b>	<b>2.353</b>	<b>2.278</b>	<b>2.482</b>
<b>2014 Average</b> .....	<b>2.153</b>	<b>2.694</b>	<b>1.996</b>	<b>2.221</b>	<b>2.044</b>	<b>2.325</b>
<b>2015 Average</b> .....	<b>.971</b>	<b>1.529</b>	<b>.999</b>	<b>1.227</b>	<b>.996</b>	<b>1.285</b>
<b>2016 Average</b> .....	<b>.736</b>	<b>1.138</b>	<b>.746</b>	<b>.897</b>	<b>.745</b>	<b>.945</b>
<b>2017 Average</b> .....	<b>1.112</b>	<b>W</b>	<b>1.117</b>	<b>1.237</b>	<b>1.116</b>	<b>1.287</b>
<b>2018 January</b> .....	<b>1.301</b>	<b>W</b>	<b>1.311</b>	<b>1.476</b>	<b>1.310</b>	<b>1.507</b>
February .....	1.221	W	1.325	1.415	1.319	1.490
March .....	1.227	W	1.306	1.386	1.302	1.452
April .....	1.311	W	1.349	1.438	1.348	1.504
May .....	1.462	W	1.501	1.615	1.500	1.667
June .....	1.487	W	1.558	1.643	1.553	1.731
July .....	1.543	W	1.583	1.709	1.581	1.767
August .....	1.499	W	1.552	1.680	1.549	1.764
September .....	1.520	W	1.561	1.696	1.560	1.761
October .....	1.620	W	1.703	1.816	1.700	1.875
November .....	1.360	W	1.562	1.731	1.556	1.827
December .....	1.252	W	1.295	1.467	1.293	1.608
<b>Average</b> .....	<b>1.397</b>	<b>W</b>	<b>1.466</b>	<b>1.587</b>	<b>1.463</b>	<b>1.662</b>
<b>2019 January</b> .....	<b>1.626</b>	<b>W</b>	<b>1.326</b>	<b>1.417</b>	<b>1.357</b>	<b>1.425</b>
February .....	1.808	W	1.458	1.553	1.508	1.568
March .....	W	W	1.542	1.606	1.581	1.639
April .....	W	W	1.549	1.648	1.577	1.685
May .....	W	W	1.502	1.607	1.505	1.635
June .....	W	W	1.367	1.527	1.372	1.601
July .....	1.455	W	1.492	1.572	1.489	1.625
August .....	1.331	W	1.235	1.345	1.247	1.466
September .....	W	W	1.325	1.511	1.337	1.560
October .....	1.535	W	1.188	1.393	1.263	1.543
November .....	1.681	W	1.220	1.364	1.353	1.594
December .....	1.758	W	1.460	1.543	1.597	1.745
<b>Average</b> .....	<b>1.649</b>	<b>W</b>	<b>1.391</b>	<b>1.510</b>	<b>1.428</b>	<b>1.584</b>
<b>2020 January</b> .....	<b>1.788</b>	<b>W</b>	<b>1.526</b>	<b>1.634</b>	<b>1.675</b>	<b>1.939</b>
February .....	1.673	W	1.336	1.557	1.540	1.735
March .....	1.188	W	.993	1.146	1.121	1.371
April .....	.796	W	.639	.942	.733	.976
May .....	.792	W	NA	.727	.775	.817
June .....	1.018	W	1.013	.894	1.017	.949
July .....	1.153	W	1.089	.981	1.137	1.071
August .....	1.189	W	1.068	1.026	1.135	1.224
September .....	1.098	W	1.000	1.035	1.066	1.200
October .....	1.078	W	.996	1.071	1.041	1.151
November .....	1.164	W	1.098	1.068	1.145	1.145

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.  
NA=Not available. W=Value withheld to avoid disclosure of individual company data.

Notes: • Sales for resale are those made to purchasers other than ultimate consumers. Sales to end users are those made directly to ultimate consumers, including bulk consumers (such as agriculture, industry, and electric utilities) and commercial consumers. • Values for the current month are preliminary.  
• Through 1982, prices are U.S. Energy Information Administration (EIA)

estimates. See Note 6, "Historical Petroleum Prices," at end of section.  
• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1978 and monthly data beginning in 1982.

Sources: • **1978–2007:** EIA, *Petroleum Marketing Annual 2007*, Table 17.  
• **2008 forward:** EIA, *Petroleum Marketing Monthly*, February 2021, Table 16.

**Table 9.6 Refiner Prices of Petroleum Products for Resale**  
(Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Finished Motor Gasoline <sup>b</sup>	Finished Aviation Gasoline	Kerosene-Type Jet Fuel	Kerosene	No. 2 Fuel Oil	No. 2 Diesel Fuel	Propane (Consumer Grade)
<b>1978 Average</b> .....	<b>0.434</b>	<b>0.537</b>	<b>0.386</b>	<b>0.404</b>	<b>0.369</b>	<b>0.365</b>	<b>0.237</b>
<b>1980 Average</b> .....	<b>.941</b>	<b>1.128</b>	<b>.868</b>	<b>.864</b>	<b>.803</b>	<b>.801</b>	<b>.415</b>
<b>1985 Average</b> .....	<b>.835</b>	<b>1.130</b>	<b>.794</b>	<b>.874</b>	<b>.776</b>	<b>.772</b>	<b>.398</b>
<b>1990 Average</b> .....	<b>.786</b>	<b>1.063</b>	<b>.773</b>	<b>.839</b>	<b>.697</b>	<b>.694</b>	<b>.386</b>
<b>1995 Average</b> .....	<b>.626</b>	<b>.975</b>	<b>.539</b>	<b>.580</b>	<b>.511</b>	<b>.538</b>	<b>.344</b>
<b>2000 Average</b> .....	<b>.963</b>	<b>1.330</b>	<b>.880</b>	<b>.969</b>	<b>.886</b>	<b>.898</b>	<b>.595</b>
<b>2001 Average</b> .....	<b>.886</b>	<b>1.256</b>	<b>.763</b>	<b>.821</b>	<b>.756</b>	<b>.784</b>	<b>.540</b>
<b>2002 Average</b> .....	<b>.828</b>	<b>1.146</b>	<b>.716</b>	<b>.752</b>	<b>.694</b>	<b>.724</b>	<b>.431</b>
<b>2003 Average</b> .....	<b>1.002</b>	<b>1.288</b>	<b>.871</b>	<b>.955</b>	<b>.881</b>	<b>.883</b>	<b>.607</b>
<b>2004 Average</b> .....	<b>1.288</b>	<b>1.627</b>	<b>1.208</b>	<b>1.271</b>	<b>1.125</b>	<b>1.187</b>	<b>.751</b>
<b>2005 Average</b> .....	<b>1.670</b>	<b>2.076</b>	<b>1.723</b>	<b>1.757</b>	<b>1.623</b>	<b>1.737</b>	<b>.933</b>
<b>2006 Average</b> .....	<b>1.969</b>	<b>2.490</b>	<b>1.961</b>	<b>2.007</b>	<b>1.834</b>	<b>2.012</b>	<b>1.031</b>
<b>2007 Average</b> .....	<b>2.182</b>	<b>2.758</b>	<b>2.171</b>	<b>2.249</b>	<b>2.072</b>	<b>2.203</b>	<b>1.194</b>
<b>2008 Average</b> .....	<b>2.586</b>	<b>3.342</b>	<b>3.020</b>	<b>2.851</b>	<b>2.745</b>	<b>2.994</b>	<b>1.437</b>
<b>2009 Average</b> .....	<b>1.767</b>	<b>2.480</b>	<b>1.719</b>	<b>1.844</b>	<b>1.657</b>	<b>1.713</b>	<b>.921</b>
<b>2010 Average</b> .....	<b>2.165</b>	<b>2.874</b>	<b>2.185</b>	<b>2.299</b>	<b>2.147</b>	<b>2.214</b>	<b>1.212</b>
<b>2011 Average</b> .....	<b>2.867</b>	<b>3.739</b>	<b>3.014</b>	<b>3.065</b>	<b>2.907</b>	<b>3.034</b>	<b>1.467</b>
<b>2012 Average</b> .....	<b>2.929</b>	<b>3.919</b>	<b>3.080</b>	<b>3.163</b>	<b>3.031</b>	<b>3.109</b>	<b>1.033</b>
<b>2013 Average</b> .....	<b>2.812</b>	<b>3.869</b>	<b>2.953</b>	<b>3.084</b>	<b>2.966</b>	<b>3.028</b>	<b>1.048</b>
<b>2014 Average</b> .....	<b>2.618</b>	<b>3.687</b>	<b>2.763</b>	<b>2.882</b>	<b>2.741</b>	<b>2.812</b>	<b>1.165</b>
<b>2015 Average</b> .....	<b>1.726</b>	<b>2.764</b>	<b>1.592</b>	<b>1.735</b>	<b>1.565</b>	<b>1.667</b>	<b>.555</b>
<b>2016 Average</b> .....	<b>1.454</b>	<b>2.404</b>	<b>1.295</b>	<b>1.383</b>	<b>1.239</b>	<b>1.378</b>	<b>.523</b>
<b>2017 Average</b> .....	<b>1.689</b>	<b>2.682</b>	<b>1.603</b>	<b>1.730</b>	<b>1.600</b>	<b>1.691</b>	<b>.800</b>
<b>2018 January</b> .....	<b>1.849</b>	<b>2.900</b>	<b>1.969</b>	<b>2.209</b>	<b>1.990</b>	<b>2.042</b>	<b>.990</b>
February .....	1.823	2.893	1.911	2.088	1.889	1.972	.889
March .....	1.889	2.904	1.893	1.969	1.848	1.952	.827
April .....	2.054	3.085	2.032	2.075	1.982	2.099	.792
May .....	2.205	3.181	2.175	2.205	2.143	2.258	.867
June .....	2.135	3.138	2.152	2.145	2.089	2.203	.807
July .....	2.148	3.111	2.140	2.133	2.079	2.192	.854
August .....	2.118	3.085	2.148	2.169	2.114	2.203	.907
September .....	2.136	3.124	2.214	2.246	2.214	2.282	.951
October .....	2.090	3.099	2.296	2.437	2.281	2.379	.948
November .....	1.732	2.762	2.100	2.206	2.098	2.130	.826
December .....	1.514	2.463	1.811	1.954	1.796	1.794	.798
<b>Average</b> .....	<b>1.980</b>	<b>3.006</b>	<b>2.073</b>	<b>2.160</b>	<b>2.002</b>	<b>2.130</b>	<b>.877</b>
<b>2019 January</b> .....	<b>1.483</b>	<b>2.394</b>	<b>1.822</b>	<b>2.021</b>	<b>1.813</b>	<b>1.789</b>	<b>.775</b>
February .....	1.624	2.527	1.925	2.111	1.907	1.950	.772
March .....	1.881	2.874	1.960	2.087	1.958	2.020	.754
April .....	2.138	3.100	2.022	2.073	1.993	2.100	.660
May .....	2.110	3.021	2.061	2.057	1.989	2.106	.595
June .....	1.909	2.841	1.879	1.914	1.824	1.874	.493
July .....	1.984	2.988	1.938	1.969	1.847	1.938	.478
August .....	1.820	2.854	1.864	1.861	1.795	1.865	.458
September .....	1.854	2.829	1.898	1.984	1.901	1.955	.477
October .....	1.871	2.857	1.931	2.003	1.926	1.984	.544
November .....	1.819	2.783	1.922	2.046	1.884	1.974	.655
December .....	1.757	2.734	1.932	2.087	1.919	1.943	.632
<b>Average</b> .....	<b>1.858</b>	<b>2.842</b>	<b>1.929</b>	<b>2.017</b>	<b>1.895</b>	<b>1.958</b>	<b>.622</b>
<b>2020 January</b> .....	<b>1.743</b>	<b>2.752</b>	<b>1.891</b>	<b>2.008</b>	<b>1.863</b>	<b>1.858</b>	<b>.557</b>
February .....	1.669	2.698	1.613	1.802	1.627	1.671	.530
March .....	1.127	2.279	1.189	1.115	1.238	1.278	.410
April .....	.645	1.590	.703	.837	.872	.908	.378
May .....	1.049	1.869	.690	.848	.795	.878	.454
June .....	1.311	2.134	1.002	1.099	1.002	1.135	.514
July .....	1.380	2.253	1.144	1.172	1.152	1.254	.507
August .....	1.389	2.219	1.162	1.250	1.179	1.275	.536
September .....	1.354	2.246	1.076	1.215	1.091	1.195	.516
October .....	1.312	2.217	1.107	1.293	1.089	1.215	.597
November .....	1.286	2.123	1.180	1.322	1.156	1.315	.629

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 5, "Motor Gasoline Prices," at end of section.

Notes: • Sales for resale are those made to purchasers other than ultimate consumers. Sales to end users are shown in Table 9.7; they are sales made directly to ultimate consumers, including bulk consumers (such as agriculture, industry, and electric utilities) and residential and commercial consumers. • Values for the current month are preliminary. • Through 1982, prices are U.S. Energy Information Administration (EIA) estimates. See Note 6, "Historical Petroleum

Prices," at end of section. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1978 and monthly data beginning in 1982.

Sources: • **1978–2007:** EIA, *Petroleum Marketing Annual 2007*, Table 4.  
• **2008 forward:** EIA, *Petroleum Marketing Monthly*, February 2021, Table 4.

**Table 9.7 Refiner Prices of Petroleum Products to End Users**(Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Finished Motor Gasoline <sup>b</sup>	Finished Aviation Gasoline	Kerosene-Type Jet Fuel	Kerosene	No. 2 Fuel Oil	No. 2 Diesel Fuel	Propane (Consumer Grade)
<b>1978 Average</b> .....	<b>0.484</b>	<b>0.516</b>	<b>0.387</b>	<b>0.421</b>	<b>0.400</b>	<b>0.377</b>	<b>0.335</b>
<b>1980 Average</b> .....	<b>1.035</b>	<b>1.084</b>	<b>.868</b>	<b>.902</b>	<b>.788</b>	<b>.818</b>	<b>.482</b>
<b>1985 Average</b> .....	<b>.912</b>	<b>1.201</b>	<b>.796</b>	<b>1.030</b>	<b>.849</b>	<b>.789</b>	<b>.717</b>
<b>1990 Average</b> .....	<b>.883</b>	<b>1.120</b>	<b>.766</b>	<b>.923</b>	<b>.734</b>	<b>.725</b>	<b>.745</b>
<b>1995 Average</b> .....	<b>.765</b>	<b>1.005</b>	<b>.540</b>	<b>.589</b>	<b>.562</b>	<b>.560</b>	<b>.492</b>
<b>2000 Average</b> .....	<b>1.106</b>	<b>1.306</b>	<b>.899</b>	<b>1.123</b>	<b>.927</b>	<b>.935</b>	<b>.603</b>
<b>2001 Average</b> .....	<b>1.032</b>	<b>1.323</b>	<b>.775</b>	<b>1.045</b>	<b>.829</b>	<b>.842</b>	<b>.506</b>
<b>2002 Average</b> .....	<b>.947</b>	<b>1.288</b>	<b>.721</b>	<b>.990</b>	<b>.737</b>	<b>.762</b>	<b>.419</b>
<b>2003 Average</b> .....	<b>1.156</b>	<b>1.493</b>	<b>.872</b>	<b>1.224</b>	<b>.933</b>	<b>.944</b>	<b>.577</b>
<b>2004 Average</b> .....	<b>1.435</b>	<b>1.819</b>	<b>1.207</b>	<b>1.160</b>	<b>1.173</b>	<b>1.243</b>	<b>.839</b>
<b>2005 Average</b> .....	<b>1.829</b>	<b>2.231</b>	<b>1.735</b>	<b>1.957</b>	<b>1.705</b>	<b>1.786</b>	<b>1.089</b>
<b>2006 Average</b> .....	<b>2.128</b>	<b>2.682</b>	<b>1.998</b>	<b>2.244</b>	<b>1.982</b>	<b>2.096</b>	<b>1.358</b>
<b>2007 Average</b> .....	<b>2.345</b>	<b>2.849</b>	<b>2.165</b>	<b>2.263</b>	<b>2.241</b>	<b>2.267</b>	<b>1.489</b>
<b>2008 Average</b> .....	<b>2.775</b>	<b>3.273</b>	<b>3.052</b>	<b>3.283</b>	<b>2.986</b>	<b>3.150</b>	<b>1.892</b>
<b>2009 Average</b> .....	<b>1.888</b>	<b>2.442</b>	<b>1.704</b>	<b>2.675</b>	<b>1.962</b>	<b>1.834</b>	<b>1.220</b>
<b>2010 Average</b> .....	<b>2.301</b>	<b>3.028</b>	<b>2.201</b>	<b>3.063</b>	<b>2.462</b>	<b>2.314</b>	<b>1.481</b>
<b>2011 Average</b> .....	<b>3.050</b>	<b>3.803</b>	<b>3.054</b>	<b>3.616</b>	<b>3.193</b>	<b>3.117</b>	<b>1.709</b>
<b>2012 Average</b> .....	<b>3.154</b>	<b>3.971</b>	<b>3.104</b>	<b>3.843</b>	<b>3.358</b>	<b>3.202</b>	<b>1.139</b>
<b>2013 Average</b> .....	<b>3.049</b>	<b>3.932</b>	<b>2.979</b>	<b>3.842</b>	<b>3.335</b>	<b>3.122</b>	<b>1.028</b>
<b>2014 Average</b> .....	<b>2.855</b>	<b>3.986</b>	<b>2.772</b>	<b>W</b>	<b>3.329</b>	<b>2.923</b>	<b>1.097</b>
<b>2015 Average</b> .....	<b>2.003</b>	<b>W</b>	<b>1.629</b>	<b>W</b>	<b>2.016</b>	<b>1.819</b>	<b>.481</b>
<b>2016 Average</b> .....	<b>1.730</b>	<b>W</b>	<b>1.319</b>	<b>W</b>	<b>1.716</b>	<b>1.511</b>	<b>.498</b>
<b>2017 Average</b> .....	<b>1.976</b>	<b>W</b>	<b>1.629</b>	<b>W</b>	<b>2.010</b>	<b>1.811</b>	<b>.772</b>
<b>2018</b>							
January .....	2.108	W	2.012	W	2.206	2.144	.971
February .....	2.127	W	1.970	W	2.365	2.107	.948
March .....	2.160	W	1.924	W	2.484	2.076	.842
April .....	2.315	W	2.080	W	2.486	2.201	.839
May .....	2.494	W	2.221	3.219	2.478	2.368	.916
June .....	2.469	W	2.196	3.292	2.413	2.340	.883
July .....	2.442	W	2.176	W	2.436	2.316	.956
August .....	2.421	W	2.183	3.272	2.499	2.327	.989
September .....	2.428	W	2.257	3.189	2.612	2.388	1.062
October .....	2.441	W	2.349	W	2.696	2.500	.988
November .....	2.205	W	2.162	W	2.431	2.282	.876
December .....	1.973	W	1.852	W	2.222	1.981	.794
<b>Average</b> .....	<b>2.303</b>	<b>W</b>	<b>2.119</b>	<b>3.113</b>	<b>2.380</b>	<b>2.256</b>	<b>.925</b>
<b>2019</b>							
January .....	1.854	W	1.827	W	2.195	1.960	.756
February .....	1.949	W	1.956	W	2.367	2.080	.784
March .....	2.137	W	2.005	W	2.376	2.158	.761
April .....	2.487	W	2.063	W	2.461	2.259	.686
May .....	2.520	W	2.141	W	2.389	2.272	.599
June .....	2.366	W	1.907	3.312	2.156	2.078	.464
July .....	2.375	W	1.973	3.260	2.206	2.100	.487
August .....	2.252	W	1.901	W	2.155	2.037	.461
September .....	2.242	W	1.937	3.203	2.200	2.101	.473
October .....	2.289	W	1.965	W	2.174	2.134	.516
November .....	2.229	W	1.979	W	2.321	2.126	.635
December .....	2.182	W	1.979	W	2.361	2.072	.601
<b>Average</b> .....	<b>2.245</b>	<b>W</b>	<b>1.970</b>	<b>W</b>	<b>2.269</b>	<b>2.114</b>	<b>.603</b>
<b>2020</b>							
January .....	2.150	W	1.958	W	2.328	2.002	.502
February .....	2.060	W	1.667	W	2.113	1.835	.469
March .....	1.862	W	1.257	W	1.813	1.486	.378
April .....	1.490	W	.740	W	1.220	1.137	.368
May .....	1.598	W	.728	W	1.162	1.130	.421
June .....	1.768	W	1.046	3.321	1.338	1.354	.515
July .....	1.806	2.761	1.175	3.059	1.394	1.431	.518
August .....	1.814	2.805	1.188	3.163	1.464	1.456	.541
September .....	1.804	2.613	1.110	W	1.411	1.386	.508
October .....	<sup>R</sup> 1.773	<sup>R</sup> 2.495	<sup>R</sup> 1.134	W	1.360	1.400	.548
November .....	1.736	2.485	1.216	W	1.760	1.482	.577

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.<sup>b</sup> See Note 5, "Motor Gasoline Prices," at end of section.

R=Revised. W=Value withheld to avoid disclosure of individual company data.

Notes: • Sales to end users are those made directly to ultimate consumers, including bulk consumers (such as agriculture, industry, and electric utilities) and residential and commercial consumers. Sales for resale are shown in Table 9.6; they are sales made to purchasers other than ultimate consumers. • Values for the current month are preliminary. • Through 1982, prices are U.S. Energy

Information Administration (EIA) estimates. See Note 6, "Historical Petroleum Prices," at end of section. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1978 and monthly data beginning in 1982.


Sources: • **1978–2007:** EIA, *Petroleum Marketing Annual 2007*, Table 2. • **2008 forward:** EIA, *Petroleum Marketing Monthly*, February 2021, Table 2.




**Figure 9.2 Average Retail Prices of Electricity**

(Cents [a] per Kilowatthour)


By Sector, 1960–2019




By Sector, Monthly



Total, January–November



By Sector, November 2020



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.  
 [b] Public street and highway lighting, interdepartmental sales, other sales to public authorities, agricultural and irrigation, and transportation including railroads and railways.

Note: Includes taxes.  
 Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
 Source: Table 9.8.

**Table 9.8 Average Retail Prices of Electricity**  
(Cents<sup>a</sup> per Kilowatthour, Including Taxes)

	Residential	Commercial <sup>b</sup>	Industrial <sup>c</sup>	Transportation <sup>d</sup>	Other <sup>e</sup>	Total
<b>1960 Average</b> .....	2.60	2.40	1.10	NA	1.90	1.80
<b>1965 Average</b> .....	2.40	2.20	1.00	NA	1.80	1.70
<b>1970 Average</b> .....	2.20	2.10	1.00	NA	1.80	1.70
<b>1975 Average</b> .....	3.50	3.50	2.10	NA	3.10	2.90
<b>1980 Average</b> .....	5.40	5.50	3.70	NA	4.80	4.70
<b>1985 Average</b> .....	7.39	7.27	4.97	NA	6.09	6.44
<b>1990 Average</b> .....	7.83	7.34	4.74	NA	6.40	6.57
<b>1995 Average</b> .....	8.40	7.69	4.66	NA	6.88	6.89
<b>2000 Average</b> .....	8.24	7.43	4.64	NA	6.56	6.81
<b>2001 Average</b> .....	8.58	7.92	5.05	NA	7.20	7.29
<b>2002 Average</b> .....	8.44	7.89	4.88	NA	6.75	7.20
<b>2003 Average</b> .....	8.72	8.03	5.11	7.54	--	7.44
<b>2004 Average</b> .....	8.95	8.17	5.25	7.18	--	7.61
<b>2005 Average</b> .....	9.45	8.67	5.73	8.57	--	8.14
<b>2006 Average</b> .....	10.40	9.46	6.16	9.54	--	8.90
<b>2007 Average</b> .....	10.65	9.65	6.39	9.70	--	9.13
<b>2008 Average</b> .....	11.26	10.26	6.96	10.71	--	9.74
<b>2009 Average</b> .....	11.51	10.16	6.83	10.66	--	9.82
<b>2010 Average</b> .....	11.54	10.19	6.77	10.56	--	9.83
<b>2011 Average</b> .....	11.72	10.24	6.82	10.46	--	9.90
<b>2012 Average</b> .....	11.88	10.09	6.67	10.21	--	9.84
<b>2013 Average</b> .....	12.13	10.26	6.89	10.55	--	10.07
<b>2014 Average</b> .....	12.52	10.74	7.10	10.45	--	10.44
<b>2015 Average</b> .....	12.65	10.64	6.91	10.09	--	10.41
<b>2016 Average</b> .....	12.55	10.43	6.76	9.63	--	10.27
<b>2017 Average</b> .....	12.89	10.66	6.88	9.68	--	10.48
<b>2018 January</b> .....	12.22	10.49	6.94	9.39	--	10.41
February .....	12.63	10.65	6.78	9.78	--	10.42
March .....	12.97	10.51	6.63	9.40	--	10.34
April .....	12.88	10.46	6.57	9.47	--	10.18
May .....	13.12	10.51	6.79	9.39	--	10.35
June .....	13.03	10.84	7.17	10.23	--	10.75
July .....	13.13	11.00	7.32	10.05	--	10.99
August .....	13.26	11.03	7.25	9.50	--	11.01
September .....	13.01	10.72	7.05	10.05	--	10.66
October .....	12.85	10.77	6.87	9.79	--	10.41
November .....	12.90	10.54	6.85	9.70	--	10.35
December .....	12.43	10.33	6.67	9.71	--	10.21
<b>Average</b> .....	<b>12.87</b>	<b>10.67</b>	<b>6.92</b>	<b>9.70</b>	--	<b>10.53</b>
<b>2019 January</b> .....	12.47	10.30	6.58	9.83	--	10.24
February .....	12.72	10.54	6.69	10.02	--	10.40
March .....	12.84	10.46	6.73	9.25	--	10.34
April .....	13.25	10.52	6.51	9.45	--	10.24
May .....	13.31	10.54	6.69	9.46	--	10.38
June .....	13.32	10.90	6.87	10.01	--	10.74
July .....	13.26	11.02	7.14	9.82	--	11.00
August .....	13.30	11.02	7.40	9.65	--	11.05
September .....	13.16	10.96	7.06	9.78	--	10.82
October .....	12.81	10.74	6.84	9.72	--	10.39
November .....	13.03	10.57	6.72	9.52	--	10.38
December .....	12.68	10.32	6.38	9.46	--	10.22
<b>Average</b> .....	<b>13.01</b>	<b>10.68</b>	<b>6.81</b>	<b>9.66</b>	--	<b>10.54</b>
<b>2020 January</b> .....	12.79	10.24	6.33	9.56	--	10.28
February .....	12.85	10.36	6.41	9.41	--	10.29
March .....	13.09	10.41	6.38	9.82	--	10.29
April .....	13.28	10.42	6.40	9.63	--	10.42
May .....	13.15	10.46	6.53	9.29	--	10.47
June .....	13.28	10.95	6.94	10.44	--	10.96
July .....	13.26	10.90	7.17	10.20	--	11.14
August .....	13.31	10.95	7.09	10.20	--	11.11
September .....	13.55	11.07	7.01	10.41	--	11.07
October .....	13.60	10.73	6.72	9.80	--	10.64
November .....	13.35	10.59	6.48	9.89	--	10.45
<b>11-Month Average</b> .....	<b>13.23</b>	<b>10.66</b>	<b>6.69</b>	<b>9.87</b>	--	<b>10.68</b>
<b>2019 11-Month Average</b> .....	<b>13.04</b>	<b>10.71</b>	<b>6.85</b>	<b>9.68</b>	--	<b>10.57</b>
<b>2018 11-Month Average</b> .....	<b>12.91</b>	<b>10.70</b>	<b>6.94</b>	<b>9.70</b>	--	<b>10.56</b>


<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Price" in Glossary.  
<sup>b</sup> Commercial sector. For 1960–2002, prices exclude public street and highway lighting, interdepartmental sales, and other sales to public authorities.  
<sup>c</sup> Industrial sector. For 1960–2002, prices exclude agriculture and irrigation.  
<sup>d</sup> Transportation sector, including railroads and railways.  
<sup>e</sup> Public street and highway lighting, interdepartmental sales, other sales to public authorities, agriculture and irrigation, and transportation including railroads and railways.  
NA=Not available. -- =Not applicable.  
Notes: • Beginning in 2003, the category "Other" has been replaced by "Transportation," and the categories "Commercial" and "Industrial" have been redefined. • Prices are calculated by dividing revenue by sales. Revenue may not correspond to sales for a particular month because of energy service provider billing and accounting procedures. That lack of correspondence could result in uncharacteristic increases or decreases in the monthly prices. • Prices include state and local taxes, energy or demand charges, customer service charges, environmental surcharges, franchise fees, fuel adjustments, and other miscellaneous charges applied to end-use customers during normal billing operations. Prices do not include deferred charges, credits, or other adjustments, such as fuel or revenue from purchased power, from previous reporting periods. • Through 1979, data are for Classes A and B privately owned electric utilities only.

(Class A utilities are those with operating revenues of \$2.5 million or more; Class B utilities are those with operating revenues between \$1 million and \$2.5 million.) For 1980–1982, data are for selected Class A utilities whose electric operating revenues were \$100 million or more during the previous year. For 1983, data are for a selected sample of electric utilities. Beginning in 1984, data are for a census of electric utilities. Beginning in 1996, data also include energy service providers selling to retail customers. • See Note 7, "Electricity Retail Prices," at end of section for plant coverage, and for information on preliminary and final values. • Geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1960 and monthly data beginning in 1976.  
Sources: • **1960–September 1977:** Federal Power Commission, Form FPC-5, "Monthly Statement of Electric Operating Revenues and Income." • **October 1977–February 1980:** Federal Energy Regulatory Commission (FERC), Form FPC-5, "Monthly Statement of Electric Operating Revenues and Income." • **March 1980–1982:** FERC, Form FERC-5, "Electric Utility Company Monthly Statement." • **1983:** U.S. Energy Information Administration (EIA), Form EIA-826, "Electric Utility Company Monthly Statement." • **1984–2010:** EIA, Form EIA-861, "Annual Electric Power Industry Report." • **2011 forward:** EIA, *Electric Power Monthly*, January 2021, Table 5.3.


**Figure 9.3 Cost of Fossil-Fuel Receipts at Electric Generating Plants**

(Dollars [a] per Million Btu, Including Taxes)

Costs, 1973–2019




Costs, Monthly



By Fuel Type

■ November 2018 ■ November 2019 ■ November 2020



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
Source: Table 9.9.

**Table 9.9 Cost of Fossil-Fuel Receipts at Electric Generating Plants**(Dollars<sup>a</sup> per Million Btu, Including Taxes)

	Coal	Petroleum				Natural Gas <sup>e</sup>	All Fossil Fuels <sup>f</sup>
		Residual Fuel Oil <sup>b</sup>	Distillate Fuel Oil <sup>c</sup>	Petroleum Coke	Total <sup>d</sup>		
1973 Average .....	0.41	0.79	NA	NA	0.80	0.34	0.48
1975 Average .....	.81	2.01	NA	NA	2.02	.75	1.04
1980 Average .....	1.35	4.27	NA	NA	4.35	2.20	1.93
1985 Average .....	1.65	4.24	NA	NA	4.32	3.44	2.09
1990 Average .....	1.45	3.32	5.38	.80	3.35	2.32	1.69
1995 Average .....	1.32	2.59	3.99	.65	2.57	1.98	1.45
2000 Average .....	1.20	4.29	6.65	.58	4.18	4.30	1.74
2001 Average .....	1.23	3.73	6.30	.78	3.69	4.49	1.73
2002 Average <sup>g</sup> .....	1.25	3.73	5.34	.78	3.34	3.56	1.86
2003 Average .....	1.28	4.66	6.82	.72	4.33	5.39	2.28
2004 Average .....	1.36	4.73	8.02	.83	4.29	5.96	2.48
2005 Average .....	1.54	7.06	11.72	1.11	6.44	8.21	3.25
2006 Average .....	1.69	7.85	13.28	1.33	6.23	6.94	3.02
2007 Average .....	1.77	8.64	14.85	1.51	7.17	7.11	3.23
2008 Average .....	2.07	13.62	21.46	2.11	10.87	9.01	4.12
2009 Average .....	2.21	8.98	13.22	1.61	7.02	4.74	3.04
2010 Average .....	2.27	12.57	16.61	2.28	9.54	5.09	3.26
2011 Average .....	2.39	18.35	22.46	3.03	12.48	4.72	3.29
2012 Average .....	2.38	21.03	23.49	2.24	12.48	3.42	2.83
2013 Average .....	2.34	19.26	23.03	2.18	11.57	4.33	3.09
2014 Average .....	2.37	18.30	21.88	1.98	11.60	5.00	3.31
2015 Average .....	2.22	9.89	14.06	1.84	6.74	3.23	2.65
2016 Average .....	2.11	8.45	10.90	1.65	5.24	2.87	2.47
2017 Average .....	2.06	11.00	13.22	2.13	7.10	3.37	2.65
2018 January .....	2.06	11.45	16.07	2.38	11.95	5.06	3.59
February .....	2.07	11.46	15.19	2.43	8.61	3.61	2.82
March .....	2.04	12.10	15.02	2.54	8.00	3.18	2.59
April .....	2.07	12.20	16.19	2.56	8.35	3.14	2.61
May .....	2.04	12.83	16.73	2.41	10.61	3.06	2.59
June .....	2.04	13.81	16.59	2.73	9.50	3.13	2.64
July .....	2.05	13.76	16.21	2.71	8.40	3.23	2.73
August .....	2.06	14.38	16.93	2.79	8.48	3.28	2.72
September .....	2.05	13.91	17.39	2.94	9.06	3.12	2.65
October .....	2.04	14.52	17.76	2.48	10.61	3.43	2.76
November .....	2.06	15.25	16.39	2.21	9.91	4.18	3.05
December .....	2.11	13.56	14.54	2.03	9.51	4.72	3.29
Average .....	2.06	12.97	16.16	2.54	9.68	3.55	2.83
2019 January .....	2.10	11.30	14.12	2.08	8.53	4.00	3.01
February .....	2.07	12.28	15.19	2.27	9.60	3.63	2.86
March .....	2.08	13.68	15.70	2.43	10.52	3.46	2.81
April .....	2.07	13.89	16.35	2.71	11.12	2.89	2.50
May .....	2.05	13.47	16.19	2.24	9.52	2.77	2.44
June .....	2.03	12.92	14.85	2.18	9.64	2.58	2.36
July .....	2.02	12.93	15.10	2.01	7.99	2.54	2.34
August .....	2.00	13.72	14.82	1.72	6.94	2.42	2.26
September .....	1.96	11.53	15.04	1.67	9.23	2.59	2.34
October .....	1.96	12.65	15.37	1.57	10.58	2.49	2.27
November .....	1.96	12.05	15.28	1.46	7.75	2.96	2.50
December .....	1.91	12.85	14.73	1.14	8.68	2.91	2.47
Average .....	2.02	12.66	15.19	1.91	9.07	2.89	2.50
2020 January .....	1.94	13.15	14.54	1.53	6.32	2.63	2.33
February .....	1.91	12.68	13.78	1.47	7.12	2.40	2.22
March .....	1.94	10.29	10.83	1.36	6.61	2.14	2.09
April .....	1.93	8.19	8.82	1.38	4.55	2.10	2.04
May .....	1.90	5.69	7.29	1.61	4.26	2.16	2.07
June .....	1.91	6.25	8.97	1.46	4.61	2.01	1.99
July .....	1.91	7.38	10.69	1.62	5.45	2.03	2.01
August .....	1.90	9.66	10.44	1.82	5.17	2.39	2.21
September .....	1.94	9.56	9.83	W	6.21	2.42	2.23
October .....	1.92	8.68	10.07	2.08	6.63	2.49	2.26
November .....	1.91	9.03	10.35	2.25	5.89	2.99	2.48
11-Month Average ...	1.92	9.09	10.48	1.65	5.73	2.33	2.18
2019 11-Month Average ...	2.03	12.64	15.24	1.99	9.11	2.88	2.51
2018 11-Month Average ...	2.05	12.91	16.29	2.58	9.70	3.46	2.79

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.<sup>b</sup> For 1973–2001, electric utility data are for heavy oil (fuel oil nos. 5 and 6, and small amounts of fuel oil no. 4).<sup>c</sup> For 1973–2001, electric utility data are for light oil (fuel oil nos. 1 and 2).<sup>d</sup> For all years, includes residual fuel oil and distillate fuel oil. For 1990 forward, also includes petroleum coke. For 1973–2012, also includes jet fuel, kerosene, and waste oil. For 1983–2012, also includes other petroleum, such as propane and refined motor oil.<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels. For 1973–2000, data also include a small amount of blast furnace gas and other gases derived from fossil fuels.<sup>f</sup> Weighted average of costs shown under "Coal," "Petroleum," and "Natural Gas."<sup>g</sup> Through 2001, data are for electric utilities only. Beginning in 2002, data also include independent power producers, and electric generating plants in the

commercial and industrial sectors.

NA=Not available. W=Value withheld to avoid disclosure of individual company data.

Notes: • Receipts are purchases of fuel. • Yearly costs are averages of monthly values, weighted by quantities in Btu. • For this table, there are several breaks in the data series related to what plants and fuels are covered. Beginning in 2013, data cover all regulated generating plants; plus unregulated plants whose total fossil-fueled nameplate generating capacity is 50 megawatts or more for coal, and 200 megawatts or more for natural gas, residual fuel oil, distillate fuel oil, and petroleum coke. For data coverage before 2013, see EIA, *Electric Power Monthly*, Appendix C, Form EIA-923 notes, "Receipts and cost and quality of fossil fuels" section. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.


**Figure 9.4 Natural Gas Prices**

(Dollars [a] per Thousand Cubic Feet)


Wellhead and Citygate, 1949–2019



Consuming Sectors, 1967–2019



Consuming Sectors, Monthly



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.  
[b] Includes taxes.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
Source: Table 9.10.

**Table 9.10 Natural Gas Prices**  
(Dollars<sup>a</sup> per Thousand Cubic Feet)

	Wellhead Price <sup>f</sup>	City-gate Price <sup>g</sup>	Consuming Sectors <sup>b</sup>								
			Residential		Commercial <sup>c</sup>		Industrial <sup>d</sup>		Transportation	Electric Power <sup>e</sup>	
			Price <sup>h</sup>	Percentage of Sector <sup>i</sup>	Price <sup>h</sup>	Percentage of Sector <sup>i</sup>	Price <sup>h</sup>	Percentage of Sector <sup>i</sup>	Vehicle Fuel <sup>j</sup> Price <sup>h</sup>	Price <sup>h</sup>	Percentage of Sector <sup>i,k</sup>
1950 Average	0.07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1955 Average	.10	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1960 Average	.14	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1965 Average	.16	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1970 Average	.17	NA	1.09	NA	.77	NA	.37	NA	NA	.29	NA
1975 Average	.44	NA	1.71	NA	1.35	NA	.96	NA	NA	.77	96.1
1980 Average	1.59	NA	3.68	NA	3.39	NA	2.56	NA	NA	2.27	96.9
1985 Average	2.51	3.75	6.12	NA	5.50	NA	3.95	68.8	NA	3.55	94.0
1990 Average	1.71	3.03	5.80	99.2	4.83	86.6	2.93	35.2	3.39	2.38	76.8
1995 Average	1.55	2.78	6.06	99.0	5.05	76.7	2.71	24.5	3.98	2.02	71.4
2000 Average	3.68	4.62	7.76	92.6	6.59	63.9	4.45	19.8	5.54	4.38	50.5
2001 Average	4.00	5.72	9.63	92.4	8.43	66.0	5.24	20.8	6.60	4.61	40.2
2002 Average	2.95	4.12	7.89	97.9	6.63	77.4	4.02	22.7	5.10	3.68	83.9
2003 Average	4.88	5.85	9.63	97.5	8.40	78.2	5.89	22.1	6.19	5.57	91.2
2004 Average	5.46	6.65	10.75	97.7	9.43	78.0	6.53	23.6	7.16	6.11	89.8
2005 Average	7.33	8.67	12.70	98.1	11.34	82.1	8.56	24.0	9.14	8.47	91.3
2006 Average	6.39	8.61	13.73	98.1	12.00	80.8	7.87	23.4	8.72	7.11	93.4
2007 Average	6.25	8.16	13.08	98.0	11.34	80.4	7.68	22.2	8.50	7.31	92.2
2008 Average	7.97	9.18	13.89	97.5	12.23	79.7	9.65	20.4	11.75	9.26	101.1
2009 Average	3.67	6.48	12.14	97.4	10.06	77.8	5.33	18.8	8.13	4.93	101.1
2010 Average	4.48	6.18	11.39	97.4	9.47	77.5	5.49	18.0	6.25	5.27	100.8
2011 Average	3.95	5.63	11.03	96.3	8.91	67.3	5.13	16.3	7.48	4.89	101.2
2012 Average	E 2.66	4.73	10.65	95.8	8.10	65.2	3.88	16.2	8.04	3.54	95.5
2013 Average	NA	4.88	10.32	95.7	8.08	65.8	4.64	16.6	9.76	4.49	94.9
2014 Average	NA	5.71	10.97	95.5	8.90	65.8	5.62	15.9	NA	5.19	94.6
2015 Average	NA	4.26	10.38	95.6	7.91	65.7	3.93	14.8	NA	3.38	94.6
2016 Average	NA	3.71	10.05	95.8	7.28	64.8	3.51	14.9	NA	2.99	95.6
2017 Average	NA	4.16	10.91	95.9	7.88	65.4	4.08	14.8	NA	3.51	95.4
2018 January	NA	4.36	8.90	96.1	7.40	71.5	4.46	15.2	NA	5.38	94.4
February	NA	3.99	9.63	96.0	7.74	69.3	4.85	14.8	NA	3.75	94.4
March	NA	3.69	9.76	95.9	7.71	68.6	4.00	15.3	NA	3.32	95.1
April	NA	3.65	10.05	95.6	7.65	65.4	3.89	15.0	NA	3.26	95.9
May	NA	4.14	13.52	94.8	8.34	60.0	3.80	14.1	NA	3.16	94.8
June	NA	4.49	16.47	95.7	8.58	57.7	3.77	14.1	NA	3.23	96.3
July	NA	4.50	17.85	95.8	8.84	56.4	3.75	13.9	NA	3.35	95.2
August	NA	5.25	18.56	95.6	8.69	55.1	3.67	14.2	NA	3.39	95.8
September	NA	4.72	17.23	96.2	8.57	56.9	3.75	14.0	NA	3.23	96.2
October	NA	4.10	12.22	96.5	7.69	61.3	4.03	14.3	NA	3.52	96.4
November	NA	4.28	9.42	96.4	7.34	66.6	4.51	14.5	NA	4.34	94.6
December	NA	4.72	9.62	96.2	7.70	69.0	5.47	14.5	NA	4.89	95.6
Average	NA	4.23	10.50	96.0	7.79	65.8	4.19	14.5	NA	3.68	95.4
2019 January	NA	4.03	9.36	96.4	7.67	70.1	5.02	13.7	NA	4.16	96.4
February	NA	3.91	9.40	96.1	7.55	69.3	4.62	14.1	NA	3.78	95.5
March	NA	4.07	9.42	96.0	7.41	69.1	4.31	13.7	NA	3.60	95.7
April	NA	3.72	10.85	95.6	7.73	64.1	3.99	13.0	NA	2.99	96.2
May	NA	3.66	12.76	95.7	8.06	60.6	3.64	12.6	NA	2.85	97.9
June	NA	4.17	15.55	95.6	8.23	58.1	3.54	12.4	NA	2.66	97.1
July	NA	4.17	17.74	95.9	8.47	56.0	3.34	13.0	NA	2.63	96.7
August	NA	4.15	18.38	96.1	8.42	55.6	3.20	12.3	NA	2.50	96.5
September	NA	4.07	17.61	96.2	8.34	56.2	3.34	12.2	NA	2.68	96.8
October	NA	3.42	12.50	96.8	7.64	60.3	3.42	12.0	NA	2.58	96.5
November	NA	3.46	9.33	96.6	6.98	66.7	3.86	12.7	NA	3.08	96.3
December	NA	3.50	9.30	96.4	7.19	68.8	3.88	12.8	NA	3.04	96.4
Average	NA	3.81	10.51	96.2	7.61	65.5	3.90	12.9	NA	2.99	96.5
2020 January	NA	3.28	9.51	96.4	7.25	69.4	3.66	13.1	NA	2.74	89.2
February	NA	3.10	9.12	96.3	6.87	68.9	3.54	13.2	NA	2.50	90.4
March	NA	3.23	9.85	96.1	7.32	66.5	3.34	13.0	NA	2.23	89.0
April	NA	3.05	10.66	95.9	7.28	63.7	2.96	12.8	NA	2.20	89.7
May	NA	3.37	11.85	95.7	7.74	59.0	2.86	13.2	NA	2.25	89.6
June	NA	3.85	15.37	95.9	8.19	56.6	2.72	12.9	NA	2.08	88.3
July	NA	3.87	17.57	96.4	8.47	55.7	2.55	12.8	NA	2.10	85.5
August	NA	3.95	18.41	95.9	8.50	54.3	2.92	12.4	NA	2.47	87.2
September	NA	4.10	16.99	96.6	8.47	54.8	3.16	13.2	NA	2.49	87.8
October	NA	3.47	12.35	96.6	7.63	60.6	3.25	12.9	NA	2.57	88.5
November	NA	3.80	11.07	96.8	7.66	65.4	3.93	13.2	NA	3.09	90.5
11-Month Average	NA	3.40	11.03	96.3	7.49	63.9	3.20	13.0	NA	2.41	88.4
2019 11-Month Average	NA	3.87	10.71	96.1	7.67	65.0	3.90	12.9	NA	2.99	96.5
2018 11-Month Average	NA	4.15	10.66	96.0	7.80	65.3	4.06	14.5	NA	3.59	95.4

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 8, "Natural Gas Prices," at end of section.

<sup>c</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>d</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>e</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 2001, data are for electric utilities only; beginning in 2002, data also include independent power producers.

<sup>f</sup> See "Natural Gas Wellhead Price" in Glossary.

<sup>g</sup> See "Citygate" in Glossary.

<sup>h</sup> Includes taxes.

<sup>i</sup> The percentage of the sector's consumption in Table 4.3 for which price data are available. For details on how the percentages are derived, see Table 9.10 sources at end of section.

<sup>j</sup> Much of the natural gas delivered for vehicle fuel represents deliveries to fueling stations that are used primarily or exclusively by fleet vehicles. Thus, the prices are often those associated with the cost of gas in the operation of fleet vehicles.

<sup>k</sup> Percentages exceed 100% when reported natural gas receipts are greater than reported natural gas consumption—this can occur when combined-heat-and-power plants report fuel receipts related to non-electric generating activities.

NA=Not available. E=Estimate.

Notes: • Prices are for natural gas, plus a small amount of supplemental gaseous fuels. • Prices are intended to include all taxes. See Note 8, "Natural Gas Prices," at end of section. • Wellhead annual and year-to-date prices are simple averages of the monthly prices; all other annual and year-to-date prices are volume-weighted averages of the monthly prices. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1976.

Sources: See end of section.

**Note 1. Crude Oil Refinery Acquisition Costs.** Beginning with January 1981, refiner acquisition costs of crude oil are from data collected on U.S. Energy Information Administration (EIA) Form EIA-14, "Refiners' Monthly Cost Report." Those costs were previously published from data collected on Economic Regulatory Administration (ERA) Form ERA-49, "Domestic Crude Oil Entitlements Program Refiners Monthly Report." Form ERA-49 was discontinued with the decontrol of crude oil on January 28, 1981. Crude oil purchases and costs are defined for Form EIA-14 in accordance with conventions used for Form ERA-49. The respondents for the two forms are also essentially the same. However, due to possible different interpretations of the filing requirements and a different method for handling prior period adjustments, care must be taken when comparing the data collected on the two forms.

The refiner acquisition cost of crude oil is the average price paid by refiners for crude oil booked into their refineries in accordance with accounting procedures generally accepted and consistently and historically applied by the refiners concerned. Domestic crude oil is that oil produced in the United States or from the outer continental shelf as defined in 43 USC Section 1331. Imported crude oil is either that oil reported on Form ERA-51, "Transfer Pricing Report," or any crude oil that is not domestic oil. The composite cost is the weighted average of domestic and imported crude oil costs.

Crude oil costs and volumes reported on Form ERA-49 excluded unfinished oils but included the Strategic Petroleum Reserve (SPR). Crude oil costs and volumes reported on Federal Energy Administration (FEA) Form FEA-P110-M-1, "Refiners' Monthly Cost Allocation Report," included unfinished oils but excluded SPR. Imported averages derived from Form ERA-49 exclude oil purchased for SPR, whereas the composite averages derived from Form ERA-49 include SPR. None of the prices derived from Form EIA-14 include either unfinished oils or SPR.

**Note 2. Crude Oil Domestic First Purchase Prices.** The average domestic first purchase price represents the average price at which all domestic crude oil is purchased. Crude oil domestic first purchase prices were derived as follows: for 1949–1973, weighted average domestic first purchase values as reported by state agencies and calculated by the Bureau of Mines; for 1974 and 1975, weighted averages of a sample survey of major first purchasers' purchases; for 1976 forward, weighted averages of all first purchasers' purchases. The data series was previously called "Actual Domestic Wellhead Price."

**Note 3. Crude Oil F.O.B. Costs.** F.O.B. literally means "Free on Board." It denotes a transaction whereby the seller makes the product available with an agreement on a given port at a given price; it is the responsibility of the buyer to arrange for the transportation and insurance.

**Note 4. Crude Oil Landed Costs.** The landed cost of imported crude oil from selected countries does not represent the total cost of all imported crude. Prior to April 1975, imported crude costs to U.S. company-owned refineries in the Caribbean were not included in the landed cost, and costs of crude oil from countries that export only small amounts to the United States were also excluded. Beginning in April 1975, however, coverage was expanded to include U.S. company-owned refineries in the Caribbean. Landed costs do not include supplemental fees.

**Note 5. Motor Gasoline Prices.** Several different series of motor gasoline prices are published in this section. U.S. city average retail prices of motor gasoline by grade are calculated monthly by the Bureau of Labor Statistics during the development of the Consumer Price Index (CPI). These prices include all federal, state, and local taxes paid at the time of sale. Prior to 1977, prices were collected in 56 urban areas. From 1978 forward, prices are collected from a new sample of service stations in 85 urban areas selected to represent all urban consumers—about 80 percent of the total U.S. population. The service stations are selected initially, and on a replacement basis, in such a way that they represent the purchasing habits of the CPI population. Service stations in the current sample include those providing all types of service (i.e., full-, mini-, and self-serve).

Regular motor gasoline prices by area type are determined by EIA in a weekly survey of retail motor gasoline outlets (Form EIA-878, "Motor Gasoline Price Survey"). Prices include all federal, state, and local taxes paid at the time of sale. A representative sample of outlets by geographic area and size is randomly selected from a sampling frame of approximately 115,000 retail motor gasoline outlets. Monthly and annual prices are simple averages of weighted

weekly estimates from "Weekly U.S. Retail Gasoline Prices, Regular Grade." For more information on the survey methodology, see EIA, *Weekly Petroleum Status Report*, Appendix B, "Weekly Petroleum Price Surveys" section.

Refiner prices of finished motor gasoline for resale and to end users are determined by EIA in a monthly survey of refiners and gas plant operators (Form EIA-782A). The prices do not include any federal, state, or local taxes paid at the time of sale. Estimates of prices prior to January 1983 are based on Form FEA-P302-M-1/EIA-460, "Petroleum Industry Monthly Report for Product Prices," and also exclude all federal, state, or local taxes paid at the time of sale. Sales for resale are those made to purchasers who are other-than-ultimate consumers. Sales to end users are sales made directly to the consumer of the product, including bulk consumers (such as agriculture, industry, and utilities) and residential and commercial consumers.

**Note 6. Historical Petroleum Prices.** Starting in January 1983, Form EIA-782, "Monthly Petroleum Product Sales Report," replaced 10 previous surveys. Every attempt was made to continue the most important price series. However, prices published through December 1982 and those published since January 1983 do not necessarily form continuous data series due to changes in survey forms, definitions, instructions, populations, samples, processing systems, and statistical procedures. To provide historical data, continuous series were generated for annual data 1978–1982 and for monthly data 1981 and 1982 by estimating the prices that would have been published had Form EIA-782 survey and system been in operation at that time. This form of estimation was performed after detailed adjustment was made for product and sales type matching and for discontinuity due to other factors. An important difference between the previous and present prices is the distinction between wholesale and resale and between retail and end user. The resale category continues to include sales among resellers. However, sales to bulk consumers, such as utility, industrial, and commercial accounts previously included in the wholesale category, are now counted as made to end users. The end-user category continues to include retail sales through company-owned and operated outlets but also includes sales to the bulk consumers such as agriculture, industry, and electric utilities. Additional information may be found in "Estimated Historic Time Series for the EIA-782," a feature article by Paula Weir, printed in the December 1983 [3] *Petroleum Marketing Monthly*, published by EIA.

**Note 7. Electricity Retail Prices.** Average annual retail prices of electricity have the following plant coverage: Through 1979, annual data are for Classes A and B privately owned electric utilities only. For 1980–1982, annual data are for selected Class A utilities whose electric operating revenues were \$100 million or more during the previous year. For 1983, annual data are for a selected sample of electric utilities. Beginning in 1984, data are for a census of electric utilities. Beginning in 1996, annual data also include energy service providers selling to retail customers.

Average monthly retail prices of electricity have the following plant coverage: Through 1985, monthly data are derived from selected privately owned electric utilities and, therefore, are not national averages. Beginning in 1986, monthly data are based on a sample of publicly and privately owned electric utilities. Beginning in 1996, monthly data also include energy service providers selling to retail customers.

Preliminary monthly data are from Form EIA-861M (formerly Form EIA-826), "Monthly Electric Power Industry Report," which is a monthly collection of data from approximately 450 of the largest publicly and privately owned electric utilities as well as a census of energy service providers with retail sales in deregulated states; a model is then applied to the collected data to estimate for the entire universe of U.S. electric utilities. Preliminary annual data are the sum of the monthly revenues divided by the sum of the monthly sales. When final annual data become available each year from Form EIA-861, "Annual Electric Power Industry Report," their ratios to the preliminary Form EIA-861M values are used to derive adjusted final monthly values.

**Note 8. Natural Gas Prices.** Natural gas prices are intended to include all taxes. Instructions on the data collection forms specifically direct that all federal, state, and local taxes, surcharges, and/or adjustments billed to consumers are to be included. However, sales and other taxes itemized on more than 3,000 consumers' bills are sometimes excluded by the reporting utilities. Delivered-to-consumers prices for 1987 forward represent natural gas delivered and sold to residential, commercial, industrial, vehicle fuel, and electric power consumers. They do not include the price of natural



gas delivered on behalf of third parties to residential, commercial, industrial, and vehicle fuel customers except for certain states in the residential and commercial sectors for 2002 forward. Volumes of natural gas delivered on behalf of third parties are included in the consumption data shown in Table 4.3. Additional information is available in EIA, *Natural Gas Monthly*, Appendix C.

## Table 9.1 Sources

### *Domestic First Purchase Price*

1949–1976: U.S. Department of the Interior (DOI), Bureau of Mines (BOM), *Minerals Yearbook*, "Crude Petroleum and Petroleum Products" chapter.

1977: Federal Energy Administration, based on Form FEA-P124, "Domestic Crude Oil Purchaser's Monthly Report."

1978–2009: U.S. Energy Information Administration (EIA), *Petroleum Marketing Annual* 2009, Table 1.

2010 forward: EIA, *Petroleum Marketing Monthly*, February 2021, Table 1.

### *F.O.B. and Landed Cost of Imports*

October 1973–September 1977: Federal Energy Administration, Form FEA-F701-M-0, "Transfer Pricing Report."

October–December 1977: EIA, Form FEA-F701-M-0, "Transfer Pricing Report."

1978–2009: EIA, *Petroleum Marketing Annual* 2009, Table 1.

2010 forward: EIA, *Petroleum Marketing Monthly*, February 2021, Table 1.

### *Refiner Acquisition Cost*

1968–1973: EIA estimates. The cost of domestic crude oil was derived by adding estimated transportation costs to the reported average domestic first purchase price. The cost of imported crude oil was derived by adding an estimated ocean transport cost based on the published "Average Freight Rate Assessment" to the average "Free Alongside Ship" value published by the U.S. Census Bureau.

1974–1976: DOI, BOM, *Minerals Yearbook*, "Crude Petroleum and Petroleum Products" chapter.

1977: January–September, FEA, based on Form FEA-P110-M-1, "Refiners' Monthly Cost Allocation Report."

1977: October–December, EIA, based on Form FEA-P110-M-1, "Refiners' Monthly Cost Allocation Report."

1978–2009: EIA, *Petroleum Marketing Annual* 2009, Table 1.

2010 forward: EIA, *Petroleum Marketing Monthly*, February 2021, Table 1.

## Table 9.2 Sources

October 1973–September 1977: Federal Energy Administration, Form FEA-F701-M-0, "Transfer Pricing Report."

October 1977–December 1977: U.S. Energy Information Administration (EIA), Form FEA-F701-M-0, "Transfer Pricing Report."

1978–2009: EIA, *Petroleum Marketing Annual* 2009, Table 21.

2010 forward: EIA, *Petroleum Marketing Monthly*, February 2021, Table 21.

## Table 9.9 Sources

1973–September 1977: Federal Power Commission, Form FPC-423, "Monthly Report of Cost and Quality of Fuels for

Electric Utility Plants." October 1977–December 1977: Federal Energy Regulatory Commission, Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants."

1978 and 1979: U.S. Energy Information Administration (EIA), Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants."

1980–1989: EIA, *Electric Power Monthly*, June issues.

1990–2000: EIA, *Electric Power Monthly*, March 2003, Table 26.

2001–2007: EIA, *Electric Power Monthly*, October 2008, Table 4.1; Federal Energy Regulatory Commission, Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants"; and EIA, Form EIA-423, "Monthly Cost and Quality of Fuels for Electric Plants Report."

2008 forward: EIA, *Electric Power Monthly*, January 2021, Table 4.1; and Form EIA-923, "Power Plant Operations Report."

## Table 9.10 Sources

### *All Prices Except Vehicle Fuel and Electric Power*

1949–2015: U.S. Energy Information Administration (EIA), *Natural Gas Annual* (NGA), annual reports and unpublished revisions.

2016 forward: EIA, *Natural Gas Monthly* (NGM), January 2021, Table 3.

### *Vehicle Fuel Price*

1989–2013: EIA, NGA, annual reports.

### *Electric Power Sector Price*

1967–1972: EIA, NGA, annual reports.

1973–1998: EIA, NGA 2000, Table 96.

1999–2002: EIA, NGM, November 2004, Table 4.

2003–2007: Federal Energy Regulatory Commission, Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants," and EIA, Form EIA-423 "Monthly Cost and Quality of Fuels for Electric Plants Report."

2008 forward: Form EIA-923, "Power Plant Operations Report."

### *Percentage of Residential Sector*

1989–2013: EIA, Form EIA-176, "Annual Report of Natural and Supplemental Gas Supply and Disposition." Calculated as the total amount of natural gas delivered to residential consumers minus the amount delivered for the account of others, and then divided by the total amount delivered to residential consumers.

2014 forward: EIA, Form EIA-857, "Monthly Report of Natural Gas Purchases and Deliveries to Consumers."

### *Percentage of Commercial Sector*

1987–2015: EIA, NGA, annual reports. Calculated as the total amount of natural gas delivered to commercial consumers minus the amount delivered for the account of others, and then divided by the total amount delivered to commercial consumers.

2016 forward: EIA, NGM, January 2021, Table 3.

### ***Percentage of Industrial Sector***

1982–2015: EIA, NGA, annual reports. Calculated as the total amount of natural gas delivered to industrial consumers minus the amount delivered for the account of others, and then divided by the total amount delivered to industrial consumers.

2016 forward: EIA, NGM, January 2021, Table 3.

### ***Percentage of Electric Power Sector***

1973–2001: Calculated by EIA as the quantity of natural gas receipts by electric utilities reported on Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants" (and predecessor forms) divided by the quantity of natural gas consumed by the electric power sector (for 1973 –1988, see *Monthly Energy Review (MER)*, Table 7.3b; for 1989–2001, see MER, Table 7.4b).

2002–2007: Calculated by EIA as the quantity of natural gas receipts by electric utilities and independent power producers reported on Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants," and EIA-423, "Monthly Cost and Quality of Fuels for Electric Plants Report," divided by the quantity of natural gas consumed by the electric power sector (see MER, Table 7.4b).

2008 forward: Calculated by EIA as the quantity of natural gas receipts by electric utilities and independent power producers reported on Form EIA-923, "Power Plant Operations Report," divided by the quantity of natural gas consumed by the electric power sector (see MER, Table 7.4b).


# 10. Renewable Energy

---


**Figure 10.1 Renewable Energy Consumption**

(Quadrillion Btu)


Major Sources, 1949–2019




By Source, 2019



By Sector, 2019



Compared With Other Resources, 1949–2019



[a] See Table 10.1 for definition.

[b] Conventional hydroelectric power.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#renewable>.

Sources: Tables 1.3 and 10.1–10.2c.

**Table 10.1 Renewable Energy Production and Consumption by Source**  
(Trillion Btu)

	Production <sup>a</sup>				Consumption								
	Biomass			Total Renewable Energy <sup>e</sup>	Hydroelectric Power <sup>f</sup>	Geothermal <sup>g</sup>	Solar <sup>h</sup>	Wind <sup>i</sup>	Biomass				Total Renewable Energy
	Wood <sup>b</sup>	Bio-fuels <sup>c</sup>	Total <sup>d</sup>						Wood <sup>j</sup>	Waste <sup>k</sup>	Bio-fuels <sup>l</sup>	Total	
1950 Total	1,562	NA	1,562	2,978	1,415	NA	NA	NA	1,562	NA	NA	1,562	2,978
1955 Total	1,424	NA	1,424	2,784	1,360	NA	NA	NA	1,424	NA	NA	1,424	2,784
1960 Total	1,320	NA	1,320	2,928	1,608	(s)	NA	NA	1,320	NA	NA	1,320	2,928
1965 Total	1,335	NA	1,335	3,396	2,059	2	NA	NA	1,335	NA	NA	1,335	3,396
1970 Total	1,429	NA	1,431	4,070	2,634	6	NA	NA	1,429	2	NA	1,431	4,070
1975 Total	1,497	NA	1,499	4,687	3,155	34	NA	NA	1,497	2	NA	1,499	4,687
1980 Total	2,474	NA	2,475	5,428	2,900	53	NA	NA	2,474	2	NA	2,475	5,428
1985 Total	2,687	93	3,016	6,084	2,970	97	(s)	(s)	2,687	236	93	3,016	6,084
1990 Total	2,216	111	2,735	6,040	3,046	171	59	29	2,216	408	111	2,735	6,040
1995 Total	2,370	198	3,099	6,557	3,205	152	68	33	2,370	531	200	3,101	6,559
2000 Total	2,262	233	3,006	6,102	2,811	164	63	57	2,262	511	236	3,008	6,104
2001 Total	2,006	254	2,624	5,162	2,242	164	62	70	2,006	364	253	2,622	5,160
2002 Total	1,995	308	2,705	5,731	2,689	171	60	105	1,995	402	303	2,701	5,726
2003 Total	2,002	401	2,805	5,942	2,793	173	58	113	2,002	401	403	2,806	5,944
2004 Total	2,121	486	2,996	6,063	2,688	178	58	142	2,121	389	498	3,008	6,075
2005 Total	2,137	561	3,101	6,221	2,703	181	58	178	2,137	403	574	3,114	6,234
2006 Total	2,099	716	3,212	6,586	2,869	181	61	264	2,099	397	766	3,262	6,637
2007 Total	2,089	970	3,472	6,510	2,446	186	66	341	2,089	413	983	3,485	6,523
2008 Total	2,059	1,374	3,868	7,192	2,511	192	74	546	2,059	435	1,357	3,851	7,175
2009 Total	1,935	1,570	3,957	7,625	2,669	200	78	721	1,935	452	1,553	3,940	7,608
2010 Total	2,217	1,868	4,553	8,314	2,539	208	91	923	2,217	468	1,821	4,506	8,267
2011 Total	2,213	2,029	4,704	9,300	3,103	212	112	1,168	2,213	462	1,934	4,609	9,204
2012 Total	2,151	1,929	4,547	8,886	2,629	212	159	1,340	2,151	467	1,890	4,508	8,847
2013 Total	2,338	1,981	4,816	9,418	2,562	214	225	1,601	2,338	496	2,014	4,848	9,451
2014 Total	2,401	2,103	5,020	9,767	2,467	214	338	1,728	2,401	516	2,077	4,994	9,740
2015 Total	2,312	2,161	4,992	9,729	2,321	212	427	1,777	2,312	518	2,153	4,983	9,721
2016 Total	R 2,299	2,275	R 5,077	R 10,425	2,472	210	570	2,096	R 2,226	503	2,287	R 5,017	R 10,365
2017 Total	R 2,263	2,344	R 5,103	R 11,200	2,767	210	777	2,343	R 2,185	495	2,304	R 4,983	R 11,081
2018 January	R 203	200	R 446	R 973	228	18	49	233	R 197	43	187	R 427	R 954
February	R 185	184	R 408	R 918	227	16	55	211	R 177	40	166	R 383	R 893
March	R 199	202	R 444	R 1,012	235	18	74	241	R 193	43	192	R 429	R 996
April	R 188	191	R 420	R 1,019	256	16	86	241	R 181	41	181	R 403	R 1,002
May	R 198	202	R 440	R 1,050	277	18	96	218	R 190	41	201	R 431	R 1,041
June	R 196	200	R 435	R 1,030	251	17	102	225	R 187	39	194	R 420	R 1,015
July	R 203	210	R 452	R 946	229	18	97	150	R 197	39	199	R 436	R 929
August	R 203	212	R 455	R 949	200	18	95	181	R 195	40	206	R 441	R 935
September	R 191	194	R 421	R 866	174	17	85	169	R 182	37	182	R 401	R 846
October	R 197	204	R 442	R 902	178	17	72	193	R 187	41	196	R 424	R 884
November	R 194	198	R 433	R 906	199	17	56	200	R 185	41	189	R 415	R 888
December	R 205	200	R 448	R 944	208	19	48	221	R 196	42	191	R 430	R 926
Total	R 2,362	2,397	R 5,245	R 11,515	2,663	209	916	2,482	R 2,268	487	2,283	R 5,038	R 11,308
2019 January	R 203	195	R 438	R 945	221	18	52	216	R 197	39	177	R 414	R 921
February	R 185	177	R 397	R 875	204	16	56	201	R 177	36	172	R 384	R 862
March	R 197	191	R 427	R 992	234	18	84	229	R 190	38	186	R 414	R 980
April	R 186	193	R 415	R 1,032	248	16	95	257	R 178	36	185	R 399	R 1,015
May	R 194	202	R 432	R 1,065	285	17	102	229	R 186	36	199	R 421	R 1,054
June	R 192	197	R 425	R 1,002	250	17	110	199	R 183	36	194	R 413	R 989
July	R 201	203	R 441	R 989	221	18	113	196	R 193	37	197	R 426	R 975
August	R 204	199	R 440	R 946	201	18	109	178	R 194	37	194	R 425	R 930
September	R 192	182	R 409	R 904	165	17	95	218	R 182	35	179	R 396	R 891
October	R 194	192	R 423	R 932	163	16	85	245	R 185	37	191	R 414	R 922
November	R 194	192	R 423	R 903	180	14	63	223	R 184	37	187	R 408	R 888
December	R 202	203	R 445	R 941	191	16	53	236	R 192	39	194	R 425	R 921
Total	R 2,346	2,328	R 5,116	R 11,524	2,563	201	1,018	2,626	R 2,242	442	2,255	R 4,939	R 11,348
2020 January	R 190	203	R 432	R 992	226	17	66	251	R 183	39	187	R 408	R 968
February	R 181	187	R 404	R 992	235	16	78	259	R 173	36	174	R 382	R 971
March	R 188	184	R 410	R 991	209	19	93	260	R 178	38	162	R 379	R 960
April	R 180	113	R 328	R 915	196	18	112	261	R 171	36	112	R 319	R 906
May	R 188	137	R 360	R 1,033	272	18	131	251	R 180	36	146	R 362	R 1,034
June	R 177	164	R 375	R 1,047	259	17	130	266	R 168	33	167	R 368	R 1,040
July	R 182	181	R 398	R 1,003	247	18	139	201	R 175	35	179	R 389	R 994
August	R 185	179	R 400	R 962	216	18	128	201	R 176	35	175	R 386	R 949
September	R 180	175	R 388	R 892	171	18	109	206	R 169	33	174	R 377	R 880
October	R 183	184	R 403	R 947	163	18	101	262	R 174	36	173	R 382	R 926
November	R 184	186	R 405	R 1,003	197	18	81	301	R 176	35	173	R 384	R 982
11-Month Total	2,017	1,893	4,303	10,777	2,391	196	1,169	2,719	1,923	392	1,822	4,137	10,611
2019 11-Month Total	2,143	2,124	4,671	10,583	2,372	185	965	2,390	2,050	404	2,061	4,514	10,427
2018 11-Month Total	2,156	2,196	4,798	10,572	2,456	190	867	2,261	2,071	445	2,092	4,608	10,382

<sup>a</sup> For hydroelectric power, geothermal, solar, wind, and biomass waste, production equals consumption.

<sup>b</sup> Wood and wood-derived fuels. Through 2015, wood production equals consumption. Beginning in 2016, wood production equals consumption plus densified biomass exports.

<sup>c</sup> Total biomass inputs to the production of fuel ethanol and biodiesel.

<sup>d</sup> Includes biomass waste.

<sup>e</sup> Hydroelectric power, geothermal, solar, wind, and biomass.

<sup>f</sup> Conventional hydroelectricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>g</sup> Geothermal electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), and geothermal heat pump and direct use energy.

<sup>h</sup> Solar photovoltaic (PV) and solar thermal electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), and solar thermal direct use energy.

<sup>i</sup> Wind electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>j</sup> Wood and wood-derived fuels.

<sup>k</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>l</sup> Fuel ethanol (minus denaturant), biodiesel, other renewable diesel fuel, and other renewable fuels consumption; plus losses and co-products from the production of fuel ethanol and biodiesel.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Production data are estimates. Consumption data are estimates, except for hydroelectric power in 1949–1978 and 1989 forward, and wind. • See Note, "Renewable Energy Production and Consumption," at end of section.

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **Production:** Tables 10.2a–10.4 and U.S. Energy Information Administration, Form EIA-63C, "Densified Biomass Fuel Report."

• **Consumption:** Tables 10.2a–10.2c.

**Table 10.2a Renewable Energy Consumption: Residential and Commercial Sectors**  
(Trillion Btu)

	Residential Sector				Commercial Sector <sup>a</sup>								
	Geo-thermal <sup>b</sup>	Solar <sup>c</sup>	Biomass	Total	Hydro-electric Power <sup>e</sup>	Geo-thermal <sup>f</sup>	Solar <sup>g</sup>	Wind <sup>h</sup>	Biomass				Total
			Wood <sup>d</sup>						Waste <sup>i</sup>	Fuel Ethanol <sup>j,k</sup>	Total		
1950 Total .....	NA	NA	1,006	1,006	NA	NA	NA	NA	19	NA	NA	19	19
1955 Total .....	NA	NA	775	775	NA	NA	NA	NA	15	NA	NA	15	15
1960 Total .....	NA	NA	627	627	NA	NA	NA	NA	12	NA	NA	12	12
1965 Total .....	NA	NA	468	468	NA	NA	NA	NA	9	NA	NA	9	9
1970 Total .....	NA	NA	401	401	NA	NA	NA	NA	8	NA	NA	8	8
1975 Total .....	NA	NA	425	425	NA	NA	NA	NA	8	NA	NA	8	8
1980 Total .....	NA	NA	850	850	NA	NA	NA	NA	21	NA	NA	21	21
1985 Total .....	NA	NA	1,010	1,010	NA	NA	NA	NA	24	NA	(s)	24	24
1990 Total .....	6	55	580	640	1	3	(s)	—	66	28	(s)	94	98
1995 Total .....	7	63	520	589	1	5	(s)	—	72	40	(s)	113	119
2000 Total .....	9	58	420	486	1	8	1	—	71	47	(s)	119	128
2001 Total .....	9	55	370	435	1	8	1	—	67	25	(s)	92	101
2002 Total .....	10	53	380	443	(s)	9	1	—	69	26	(s)	95	105
2003 Total .....	13	52	400	465	1	11	1	—	71	29	1	101	114
2004 Total .....	14	51	410	475	1	12	1	—	70	34	1	105	120
2005 Total .....	16	50	430	496	1	14	2	—	70	34	1	105	121
2006 Total .....	18	53	380	451	1	14	3	—	65	36	1	103	120
2007 Total .....	22	55	420	497	1	14	4	—	70	31	2	103	122
2008 Total .....	26	58	470	555	1	15	6	—	73	34	2	109	131
2009 Total .....	33	60	504	597	1	17	8	(s)	73	36	3	112	137
2010 Total .....	37	65	541	642	1	19	12	(s)	72	36	3	111	142
2011 Total .....	40	71	524	635	(s)	20	20	(s)	69	43	3	115	155
2012 Total .....	40	79	438	557	(s)	20	33	1	61	45	3	108	162
2013 Total .....	40	91	572	703	(s)	20	41	1	70	47	3	120	182
2014 Total .....	40	110	579	728	(s)	20	52	1	76	47	4	127	200
2015 Total .....	40	128	513	681	(s)	20	57	1	79	47	<sup>k</sup> 26	152	230
2016 Total .....	40	162	<sup>R</sup> 445	<sup>R</sup> 646	2	20	62	1	84	48	26	158	242
2017 Total .....	40	194	<sup>R</sup> 429	<sup>R</sup> 662	2	20	76	1	84	48	25	156	255
2018 January .....	3	12	<sup>R</sup> 45	<sup>R</sup> 60	(s)	2	5	(s)	7	4	2	13	21
February .....	3	13	<sup>R</sup> 40	<sup>R</sup> 56	(s)	2	6	(s)	7	4	2	12	20
March .....	3	18	<sup>R</sup> 45	<sup>R</sup> 66	(s)	2	8	(s)	7	4	2	13	23
April .....	3	21	<sup>R</sup> 43	<sup>R</sup> 67	(s)	2	9	(s)	7	4	2	13	23
May .....	3	23	<sup>R</sup> 45	<sup>R</sup> 71	(s)	2	10	(s)	7	4	2	13	25
June .....	3	23	<sup>R</sup> 43	<sup>R</sup> 69	(s)	2	10	(s)	7	4	2	13	25
July .....	3	24	<sup>R</sup> 45	<sup>R</sup> 72	(s)	2	10	(s)	7	4	2	13	25
August .....	3	23	<sup>R</sup> 45	<sup>R</sup> 71	(s)	2	10	(s)	7	4	2	14	25
September .....	3	20	<sup>R</sup> 43	<sup>R</sup> 66	(s)	2	9	(s)	7	4	2	12	23
October .....	3	18	<sup>R</sup> 45	<sup>R</sup> 66	(s)	2	8	(s)	7	4	2	13	23
November .....	3	14	<sup>R</sup> 43	<sup>R</sup> 61	(s)	2	6	(s)	7	4	2	13	21
December .....	3	13	<sup>R</sup> 45	<sup>R</sup> 61	(s)	2	6	(s)	7	4	2	13	21
Total .....	40	221	<sup>R</sup> 524	<sup>R</sup> 785	2	20	94	2	84	47	25	156	274
2019 January .....	3	13	<sup>R</sup> 46	<sup>R</sup> 63	(s)	2	6	(s)	7	4	2	13	21
February .....	3	15	<sup>R</sup> 42	<sup>R</sup> 59	(s)	2	6	(s)	7	3	2	12	20
March .....	3	21	<sup>R</sup> 46	<sup>R</sup> 70	(s)	2	9	(s)	7	3	2	13	24
April .....	3	23	<sup>R</sup> 45	<sup>R</sup> 71	(s)	2	10	(s)	7	3	2	12	24
May .....	3	26	<sup>R</sup> 46	<sup>R</sup> 75	(s)	2	10	(s)	7	3	2	12	25
June .....	3	26	<sup>R</sup> 45	<sup>R</sup> 74	(s)	2	11	(s)	7	3	2	12	25
July .....	3	27	<sup>R</sup> 46	<sup>R</sup> 77	(s)	2	11	(s)	7	3	2	13	26
August .....	3	26	<sup>R</sup> 46	<sup>R</sup> 76	(s)	2	11	(s)	7	3	2	13	25
September .....	3	23	<sup>R</sup> 45	<sup>R</sup> 71	(s)	2	9	(s)	7	3	2	12	24
October .....	3	20	<sup>R</sup> 46	<sup>R</sup> 70	(s)	2	8	(s)	7	3	2	13	23
November .....	3	16	<sup>R</sup> 45	<sup>R</sup> 64	(s)	2	6	(s)	7	3	2	12	21
December .....	3	15	<sup>R</sup> 46	<sup>R</sup> 64	(s)	2	6	(s)	7	3	2	13	21
Total .....	40	252	<sup>R</sup> 544	<sup>R</sup> 836	2	24	103	2	84	39	26	149	279
2020 January .....	3	16	<sup>R</sup> 39	<sup>R</sup> 58	NM	2	7	(s)	7	3	2	13	22
February .....	3	18	<sup>R</sup> 36	<sup>R</sup> 57	NM	2	8	(s)	7	3	2	12	22
March .....	3	24	<sup>R</sup> 39	<sup>R</sup> 66	NM	2	10	(s)	7	3	2	12	25
April .....	3	27	<sup>R</sup> 38	<sup>R</sup> 67	(s)	2	11	(s)	7	3	1	11	24
May .....	3	30	<sup>R</sup> 39	<sup>R</sup> 72	NM	2	12	(s)	7	3	2	12	26
June .....	3	30	<sup>R</sup> 38	<sup>R</sup> 71	NM	2	12	(s)	7	3	2	12	26
July .....	3	31	<sup>R</sup> 39	<sup>R</sup> 73	NM	2	13	(s)	7	3	2	12	27
August .....	3	30	<sup>R</sup> 39	<sup>R</sup> 72	NM	2	12	(s)	7	3	2	12	27
September .....	3	26	<sup>R</sup> 38	<sup>R</sup> 67	(s)	2	11	(s)	7	3	2	11	25
October .....	3	24	<sup>R</sup> 39	<sup>R</sup> 66	NM	2	10	(s)	7	3	2	12	<sup>R</sup> 24
November .....	3	20	<sup>R</sup> 38	<sup>R</sup> 60	NM	2	8	(s)	7	3	2	12	21
11-Month Total ...	36	275	419	730	2	22	114	1	76	33	21	129	268
2019 11-Month Total ...	36	238	498	772	2	22	97	1	77	36	24	137	258
2018 11-Month Total ...	36	208	480	724	2	18	88	1	77	43	23	143	253

<sup>a</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>b</sup> Geothermal heat pump and direct use energy.

<sup>c</sup> Distributed (small-scale) solar photovoltaic (PV) electricity generation in the residential sector (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6) and distributed solar thermal energy in the residential, commercial, and industrial sectors. See Table 10.5.

<sup>d</sup> Wood and wood-derived fuels.

<sup>e</sup> Conventional hydroelectricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>f</sup> Geothermal heat pump and direct use energy. Beginning in December 2018, also includes geothermal electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>g</sup> Solar photovoltaic (PV) electricity net generation in the commercial sector (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), both utility-scale and distributed (small-scale). See Table 10.5.

<sup>h</sup> Wind electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste,

agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>j</sup> The fuel ethanol (minus denaturant) portion of motor fuels, such as E10, consumed by the commercial sector.

<sup>k</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of fuel ethanol consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>R</sup>=Revised. NA=Not available. NM=Not meaningful. —=No data reported. (s)=Less than 0.5 trillion Btu.

Notes: • Residential sector data are estimates. Commercial sector data are estimates, except for hydroelectric power, wind, and biomass waste. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 10.2b Renewable Energy Consumption: Industrial and Transportation Sectors**  
(Trillion Btu)

	Industrial Sector <sup>a</sup>										Transportation Sector			
	Hydro-electric Power <sup>b</sup>	Geo-thermal <sup>c</sup>	Solar <sup>d</sup>	Wind <sup>e</sup>	Biomass					Total	Biomass			
					Wood <sup>f</sup>	Waste <sup>g</sup>	Fuel Ethanol <sup>h,i</sup>	Losses and Co-products <sup>j</sup>	Total		Fuel Ethanol <sup>h,k</sup>	Bio-diesel <sup>l</sup>	Other <sup>m</sup>	Total
1950 Total .....	69	NA	NA	NA	532	NA	NA	NA	532	602	NA	NA	NA	NA
1955 Total .....	38	NA	NA	NA	631	NA	NA	NA	631	669	NA	NA	NA	NA
1960 Total .....	39	NA	NA	NA	680	NA	NA	NA	680	719	NA	NA	NA	NA
1965 Total .....	33	NA	NA	NA	855	NA	NA	NA	855	888	NA	NA	NA	NA
1970 Total .....	34	NA	NA	NA	1,019	NA	NA	NA	1,019	1,053	NA	NA	NA	NA
1975 Total .....	32	NA	NA	NA	1,063	NA	NA	NA	1,063	1,096	NA	NA	NA	NA
1980 Total .....	33	NA	NA	NA	1,600	NA	NA	NA	1,600	1,633	NA	NA	NA	NA
1985 Total .....	33	NA	NA	NA	1,645	230	1	42	1,918	1,951	50	NA	NA	50
1990 Total .....	31	2	(s)	—	1,442	192	1	49	1,684	1,717	60	NA	NA	60
1995 Total .....	55	3	(s)	—	1,652	195	2	86	1,934	1,992	112	NA	NA	112
2000 Total .....	42	4	(s)	—	1,636	145	1	99	1,881	1,928	135	NA	NA	135
2001 Total .....	33	5	(s)	—	1,443	129	3	108	1,681	1,719	141	1	NA	142
2002 Total .....	39	5	(s)	—	1,396	146	3	130	1,676	1,720	168	2	NA	170
2003 Total .....	43	3	(s)	—	1,363	142	4	168	1,678	1,725	228	2	NA	230
2004 Total .....	33	4	(s)	—	1,476	132	6	201	1,815	1,852	286	3	NA	290
2005 Total .....	32	4	(s)	—	1,452	148	7	227	1,834	1,871	327	12	NA	339
2006 Total .....	29	4	1	—	1,472	130	10	280	1,892	1,926	442	33	NA	475
2007 Total .....	16	5	1	—	1,413	145	10	369	1,937	1,958	557	45	NA	602
2008 Total .....	17	5	1	—	1,339	143	12	519	2,012	2,035	786	39	NA	825
2009 Total .....	18	4	2	—	1,178	154	13	603	1,948	1,972	894	41	—	935
2010 Total .....	16	4	3	—	1,409	168	17	727	2,320	2,343	1,041	33	(s)	1,075
2011 Total .....	17	4	4	(s)	1,438	165	17	756	2,375	2,401	1,045	113	1	1,159
2012 Total .....	22	4	7	(s)	1,462	159	17	711	2,349	2,383	1,045	115	1	1,160
2013 Total .....	33	4	9	(s)	1,489	187	18	709	2,403	2,449	1,072	182	30	1,284
2014 Total .....	12	4	11	1	1,495	190	14	757	2,456	2,484	1,093	181	28	1,302
2015 Total .....	13	4	14	(s)	1,476	190	18	776	2,460	2,491	1,110	191	33	1,334
2016 Total .....	12	4	19	1	1,474	174	18	801	2,467	2,503	1,143	266	34	1,443
2017 Total .....	13	4	22	1	1,442	168	18	821	2,450	2,490	1,156	253	30	1,439
2018 January .....	1	(s)	1	(s)	124	15	2	70	211	213	96	15	1	113
February .....	1	(s)	1	(s)	111	14	1	64	190	193	82	15	2	99
March .....	1	(s)	2	(s)	122	15	2	70	208	211	96	20	3	119
April .....	1	(s)	2	(s)	115	14	1	66	197	200	90	20	2	112
May .....	1	(s)	2	(s)	121	14	2	70	206	210	104	21	2	127
June .....	1	(s)	2	(s)	118	12	2	69	200	204	98	23	1	121
July .....	1	(s)	3	(s)	124	13	2	72	210	214	101	21	1	124
August .....	1	(s)	2	(s)	123	13	2	73	211	214	104	24	1	129
September .....	1	(s)	2	(s)	115	12	1	66	195	199	90	22	1	113
October .....	1	(s)	2	(s)	119	14	2	70	205	208	99	22	1	122
November .....	1	(s)	2	(s)	118	14	2	68	202	205	95	20	2	117
December .....	1	(s)	1	(s)	127	15	2	68	212	215	97	21	2	119
Total .....	10	4	24	1	1,438	165	19	824	2,446	2,486	1,152	243	19	1,415
2019 January .....	1	(s)	2	(s)	124	14	1	67	207	210	89	16	2	107
February .....	1	(s)	2	(s)	112	13	1	61	187	190	90	17	1	108
March .....	1	(s)	2	(s)	120	14	2	66	201	205	95	20	1	117
April .....	1	(s)	3	(s)	113	13	2	66	193	197	94	20	2	115
May .....	1	(s)	3	(s)	117	13	2	69	200	204	103	22	2	126
June .....	1	(s)	3	(s)	115	12	2	68	197	201	100	20	2	122
July .....	1	(s)	3	(s)	121	12	2	69	204	208	100	22	2	124
August .....	1	(s)	3	(s)	121	12	2	68	203	207	100	21	2	122
September .....	(s)	(s)	3	(s)	114	12	R 1	62	189	193	93	19	1	113
October .....	1	(s)	2	(s)	117	14	2	66	198	202	101	19	1	121
November .....	1	(s)	2	(s)	117	13	2	67	199	202	99	17	(s)	116
December .....	1	(s)	2	(s)	122	14	2	71	208	211	98	19	2	119
Total .....	9	4	28	1	1,413	156	19	800	2,387	2,429	1,162	231	18	1,411
2020 January .....	1	(s)	2	(s)	120	14	2	70	206	209	95	17	2	113
February .....	1	(s)	2	(s)	113	13	1	64	192	195	86	19	1	106
March .....	1	(s)	3	(s)	117	14	1	62	194	198	78	18	1	97
April .....	1	(s)	3	(s)	114	13	1	36	164	168	53	19	3	75
May .....	1	(s)	3	(s)	118	13	1	44	178	182	78	19	1	98
June .....	1	(s)	3	1	109	12	1	55	177	182	89	19	1	109
July .....	1	(s)	3	1	113	12	1	60	187	193	91	23	1	115
August .....	1	(s)	3	1	112	12	1	60	185	190	89	21	2	111
September .....	1	(s)	3	1	112	12	1	59	183	188	89	22	1	112
October .....	1	(s)	3	1	114	13	1	62	191	196	85	21	2	108
November .....	1	(s)	2	1	117	13	1	63	194	198	86	19	2	107
11-Month Total ...	8	4	30	5	1,259	142	15	635	2,051	2,098	919	216	17	1,151
2019 11-Month Total ...	8	4	26	1	1,291	142	17	729	2,179	2,218	1,063	213	15	1,291
2018 11-Month Total ...	9	4	23	1	1,311	150	17	756	2,235	2,272	1,055	222	18	1,295

<sup>a</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>b</sup> Conventional hydroelectricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>c</sup> Geothermal heat pump and direct use energy.

<sup>d</sup> Solar photovoltaic (PV) electricity net generation in the industrial sector (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), both utility-scale and distributed (small-scale). See Table 10.5.

<sup>e</sup> Wind electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>f</sup> Wood and wood-derived fuels.

<sup>g</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>h</sup> The fuel ethanol (minus denaturant) portion of motor fuels, such as E10, consumed by the industrial sector.

<sup>i</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of fuel ethanol consumption are larger than in 2014, while the transportation sector share

is smaller.

<sup>j</sup> Losses and co-products from the production of fuel ethanol and biodiesel. Does not include natural gas, electricity, and other non-biomass energy used in the production of fuel ethanol and biodiesel—these are included in the industrial sector consumption statistics for the appropriate energy source.

<sup>k</sup> The fuel ethanol (minus denaturant) portion of motor fuels, such as E10 and E85, consumed by the transportation sector.

<sup>l</sup> Although there is biodiesel use in other sectors, all biodiesel consumption is assigned to the transportation sector.

<sup>m</sup> Other renewable diesel fuel and other renewable fuels consumption. See "Renewable Diesel Fuel (Other)" and "Renewable Fuels (Other)" in Glossary.

<sup>n</sup> R=Revised. NA=Not available. —=No data reported. (s)=Less than 0.5 trillion Btu.

Notes: • Industrial sector data are estimates, except for hydroelectric power in 1949–1978 and 1989 forward, and wind. Transportation sector data are estimates, except for biodiesel beginning in 2012. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.



**Table 10.2c Renewable Energy Consumption: Electric Power Sector**  
(Trillion Btu)

	Hydro-electric Power <sup>a</sup>	Geo-thermal <sup>b</sup>	Solar <sup>c</sup>	Wind <sup>d</sup>	Biomass			Total
					Wood <sup>e</sup>	Waste <sup>f</sup>	Total	
<b>1950 Total</b> .....	1,346	NA	NA	NA	5	NA	5	1,351
<b>1955 Total</b> .....	1,322	NA	NA	NA	3	NA	3	1,325
<b>1960 Total</b> .....	1,569	(s)	NA	NA	2	NA	2	1,571
<b>1965 Total</b> .....	2,026	2	NA	NA	3	NA	3	2,031
<b>1970 Total</b> .....	2,600	6	NA	NA	1	2	4	2,609
<b>1975 Total</b> .....	3,122	34	NA	NA	(s)	2	2	3,158
<b>1980 Total</b> .....	2,867	53	NA	NA	3	2	4	2,925
<b>1985 Total</b> .....	2,937	97	(s)	(s)	8	7	14	3,049
<b>1990 Total</b> <sup>9</sup> .....	3,014	161	4	29	129	188	317	3,524
<b>1995 Total</b> .....	3,149	138	5	33	125	296	422	3,747
<b>2000 Total</b> .....	2,768	144	5	57	134	318	453	3,427
<b>2001 Total</b> .....	2,209	142	6	70	126	211	337	2,763
<b>2002 Total</b> .....	2,650	147	6	105	150	230	380	3,288
<b>2003 Total</b> .....	2,749	146	5	113	167	230	397	3,411
<b>2004 Total</b> .....	2,655	148	6	142	165	223	388	3,339
<b>2005 Total</b> .....	2,670	147	6	178	185	221	406	3,406
<b>2006 Total</b> .....	2,839	145	5	264	182	231	412	3,665
<b>2007 Total</b> .....	2,430	145	6	341	186	237	423	3,345
<b>2008 Total</b> .....	2,494	146	9	546	177	258	435	3,630
<b>2009 Total</b> .....	2,650	146	9	721	180	261	441	3,967
<b>2010 Total</b> .....	2,521	148	12	923	196	264	459	4,064
<b>2011 Total</b> .....	3,085	149	17	1,167	182	255	437	4,855
<b>2012 Total</b> .....	2,606	148	40	1,339	190	262	453	4,586
<b>2013 Total</b> .....	2,529	151	83	1,600	207	262	470	4,833
<b>2014 Total</b> .....	2,454	151	165	1,726	251	279	530	5,026
<b>2015 Total</b> .....	2,308	148	228	1,776	244	281	525	4,985
<b>2016 Total</b> .....	2,459	146	328	2,094	224	281	505	5,531
<b>2017 Total</b> .....	2,752	147	486	2,341	229	280	510	6,235
<b>2018</b> January .....	227	12	30	233	21	24	46	548
February .....	226	12	35	211	19	23	42	525
March .....	234	12	46	241	20	24	44	577
April .....	255	11	55	240	16	23	39	599
May .....	276	13	62	218	17	23	40	608
June .....	250	12	67	225	19	23	42	596
July .....	228	12	61	150	21	23	44	494
August .....	199	12	60	181	20	23	43	496
September .....	174	12	54	168	17	21	37	445
October .....	177	12	45	193	17	23	39	465
November .....	198	12	34	200	17	23	40	484
December .....	206	13	28	221	18	23	41	509
<b>Total</b> .....	2,651	145	576	2,480	221	275	496	6,348
<b>2019</b> January .....	220	12	32	216	19	22	41	520
February .....	203	11	34	201	16	19	36	484
March .....	233	12	52	228	16	21	37	563
April .....	247	11	60	257	14	20	34	607
May .....	284	12	63	229	16	21	37	624
June .....	249	12	70	199	16	20	37	567
July .....	221	12	72	196	19	21	40	540
August .....	200	12	69	178	19	21	40	500
September .....	164	12	60	218	17	20	37	490
October .....	162	10	54	245	15	21	35	506
November .....	179	8	38	223	16	20	36	485
December .....	190	10	30	236	18	22	39	506
<b>Total</b> .....	2,552	134	635	2,623	201	248	448	6,392
<b>2020</b> January .....	225	11	41	250	17	21	38	566
February .....	234	11	50	259	16	20	36	590
March .....	208	13	57	260	16	21	37	574
April .....	195	13	71	261	13	20	33	572
May .....	271	13	86	251	15	20	35	655
June .....	258	12	84	265	15	18	33	653
July .....	246	12	92	200	16	20	35	586
August .....	215	12	83	200	19	20	39	549
September .....	170	12	68	206	13	19	33	489
October .....	163	12	65	261	14	19	33	534
November .....	196	13	52	300	15	19	34	595
<b>11-Month Total</b> ...	2,380	134	749	2,713	169	218	386	6,363
<b>2019 11-Month Total</b> ...	2,362	124	604	2,388	183	226	409	5,887
<b>2018 11-Month Total</b> ...	2,444	132	548	2,259	203	252	455	5,838

<sup>a</sup> Conventional hydroelectricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>b</sup> Geothermal electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>c</sup> Solar photovoltaic (PV) and solar thermal electricity net generation in the electric power sector (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6). See Table 10.5.

<sup>d</sup> Wind electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>e</sup> Wood and wood-derived fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and

tire-derived fuels).

<sup>9</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: Tables 7.2b, 7.4b, and A6.

Table 10.3 Fuel Ethanol Overview

	Feed-stock <sup>a</sup>	Losses and Co-products <sup>b</sup>	Denaturant <sup>c</sup>	Production <sup>d</sup>			Trade <sup>d</sup>	Stocks <sup>d,f</sup>	Stock Change <sup>d,g</sup>	Consumption <sup>d</sup>			Consumption Minus Denaturant <sup>h</sup>
							Net Imports <sup>e</sup>						
	TBtu	TBtu	Mbbl	Mbbl	MMgal	TBtu	Mbbl	Mbbl	Mbbl	Mbbl	MMgal	TBtu	TBtu
1981 Total	13	6	40	1,978	83	7	NA	NA	NA	1,978	83	7	7
1985 Total	93	42	294	14,693	617	52	NA	NA	NA	14,693	617	52	51
1990 Total	111	49	356	17,802	748	63	NA	NA	NA	17,802	748	63	62
1995 Total	198	86	647	32,325	1,358	115	387	2,186	-207	32,919	1,383	117	114
2000 Total	233	99	773	38,627	1,622	138	116	3,400	-624	39,367	1,653	140	137
2001 Total	253	108	841	42,028	1,765	150	315	4,298	898	41,445	1,741	148	144
2002 Total	307	130	1,019	50,956	2,140	182	306	6,200	1,902	49,360	2,073	176	171
2003 Total	400	168	1,335	66,772	2,804	238	292	5,978	-222	67,286	2,826	240	233
2004 Total	482	201	1,621	81,058	3,404	289	3,542	6,002	24	84,576	3,552	301	293
2005 Total	550	227	1,859	92,961	3,904	331	3,234	5,563	-439	96,634	4,059	344	335
2006 Total	683	280	2,326	116,294	4,884	414	17,408	8,760	3,197	130,505	5,481	465	453
2007 Total	907	368	3,105	155,263	6,521	553	10,457	10,535	1,775	163,945	6,886	584	569
2008 Total	1,286	518	4,433	221,637	9,309	790	12,610	14,226	3,691	230,556	9,683	822	800
2009 Total	1,503	602	5,688	260,424	10,938	928	4,720	16,594	2,368	262,776	11,037	937	910
2010 Total	1,823	726	6,506	316,617	13,298	1,128	-9,115	17,941	1,347	306,155	12,858	1,091	1,061
2011 Total	1,904	754	6,649	331,646	13,929	1,181	-24,365	18,238	297	306,984	12,893	1,093	1,065
2012 Total	1,801	709	6,264	314,714	13,218	1,120	-5,891	20,350	2,112	306,711	12,882	1,092	1,064
2013 Total	1,805	707	6,181	316,493	13,293	1,127	-5,761	16,424	-3,926	314,658	13,216	1,120	1,092
2014 Total	1,938	755	6,476	340,781	14,313	1,213	-18,371	18,739	2,315	320,095	13,444	1,139	1,111
2015 Total	1,998	774	6,636	352,553	14,807	1,254	-17,632	21,596	2,857	332,064	13,947	1,181	1,153
2016 Total	2,072	798	6,920	366,981	15,413	1,306	-27,002	19,758	-1,838	341,817	14,356	1,216	1,187
2017 Total	2,138	819	6,657	379,435	15,936	1,349	-31,268	23,043	3,285	344,882	14,485	1,226	1,199
2018 January	183	70	506	32,577	1,368	116	-2,522	24,342	1,299	28,756	1,208	102	100
February	167	64	443	29,674	1,246	105	-4,838	24,722	380	24,456	1,027	87	85
March	182	69	487	32,390	1,360	115	-5,516	23,084	-1,638	28,512	1,198	101	99
April	173	66	465	30,680	1,289	109	-3,675	23,379	295	26,710	1,122	95	93
May	182	69	490	32,389	1,360	115	-2,262	22,654	-725	30,852	1,296	110	108
June	180	68	473	31,924	1,341	113	-3,585	21,877	-777	29,116	1,223	103	102
July	188	72	519	33,430	1,404	119	-2,439	22,668	791	30,200	1,268	107	105
August	190	72	527	33,773	1,418	120	-2,494	22,824	156	31,123	1,307	111	108
September	173	66	471	30,667	1,288	109	-2,313	24,412	1,588	26,766	1,124	95	93
October	182	69	450	32,358	1,359	115	-3,614	23,698	-714	29,458	1,237	105	103
November	178	68	470	31,529	1,324	112	-3,229	23,618	-80	28,380	1,192	101	99
December	178	68	518	31,736	1,333	113	-2,924	23,418	-200	29,012	1,219	103	101
Total	2,156	821	5,819	383,127	16,091	1,361	-39,410	23,418	375	343,342	14,420	1,220	1,197
2019 January	177	67	550	31,603	1,327	112	-3,243	25,115	1,697	26,663	1,120	95	93
February	160	61	498	28,599	1,201	102	-2,283	24,506	-609	26,925	1,131	96	94
March	173	65	504	30,863	1,296	110	-3,653	23,396	-1,110	28,320	1,189	101	99
April	174	66	462	30,981	1,301	110	-3,195	23,331	-65	27,851	1,170	99	97
May	182	69	471	32,466	1,364	115	-2,355	22,843	-488	30,599	1,285	109	107
June	179	68	505	31,898	1,340	113	-2,340	22,583	-260	29,818	1,252	106	104
July	182	69	512	32,541	1,367	116	-2,312	22,892	309	29,920	1,257	106	104
August	179	68	513	31,921	1,341	113	-2,397	22,727	-165	29,689	1,247	106	103
September	164	62	474	29,232	1,228	104	-1,237	23,012	285	27,710	1,164	99	96
October	173	66	504	30,941	1,300	110	-1,998	21,784	-1,228	30,171	1,267	107	105
November	176	66	536	31,358	1,317	111	-2,029	21,646	-138	29,467	1,238	105	102
December	186	71	560	33,275	1,398	118	-3,234	22,352	706	29,335	1,232	104	102
Total	2,104	796	6,089	375,678	15,778	1,336	-30,276	22,352	-1,066	346,468	14,552	1,232	1,206
2020 January	186	70	543	33,343	1,400	119	-3,426	24,047	<sup>i</sup> 1,698	28,219	1,185	100	98
February	170	64	478	30,516	1,282	108	-4,376	24,555	508	25,632	1,077	91	89
March	164	62	478	29,406	1,235	105	-3,082	27,501	2,946	23,378	982	83	81
April	94	36	311	16,945	712	60	-2,457	26,102	-1,399	15,887	667	56	55
May	118	44	382	21,098	886	75	-1,622	22,247	-3,855	23,331	980	83	81
June	145	54	472	25,958	1,090	92	-1,883	19,826	-2,421	26,496	1,113	94	92
July	160	60	530	28,707	1,206	102	-1,508	19,784	-42	27,241	1,144	97	95
August	158	60	512	28,419	1,194	101	-1,563	20,143	359	26,497	1,113	94	92
September	155	58	497	27,778	1,167	99	-1,410	20,027	-116	26,484	1,112	94	92
October	164	62	569	29,402	1,235	105	-2,525	21,422	1,395	25,482	1,070	91	88
November	166	63	611	29,908	1,256	106	-2,275	23,257	1,835	25,798	1,084	92	89
11-Month Total	1,680	632	5,383	301,480	12,662	1,072	-26,127	23,257	908	274,445	11,527	976	954
2019 11-Month Total	1,918	726	5,529	342,403	14,381	1,217	-27,041	21,646	-1,772	317,134	13,320	1,127	1,104
2018 11-Month Total	1,978	753	5,301	351,391	14,758	1,248	-36,487	23,618	575	314,329	13,202	1,117	1,096

<sup>a</sup> Total corn and other biomass inputs to the production of undenatured ethanol used for fuel ethanol.

<sup>b</sup> Losses and co-products from the production of fuel ethanol. Does not include natural gas, electricity, and other non-biomass energy used in the production of fuel ethanol—these are included in the industrial sector consumption statistics for the appropriate energy source.

<sup>c</sup> The amount of denaturant in fuel ethanol produced.

<sup>d</sup> Includes denaturant.

<sup>e</sup> Through 2009, data are for fuel ethanol imports only; data for fuel ethanol exports are not available. Beginning in 2010, data are for fuel ethanol imports minus fuel ethanol (including industrial alcohol) exports.

<sup>f</sup> Stocks are at end of period.

<sup>g</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase.

<sup>h</sup> Consumption of fuel ethanol minus denaturant. Data for fuel ethanol minus denaturant are used to develop data for "Renewable Energy/Biomass" in Tables 10.1–10.2b, as well as in Sections 1 and 2.

<sup>i</sup> Derived from the preliminary 2019 stocks value (22,349 thousand barrels), not the final 2019 value (22,352 thousand barrels) that is shown under "Stocks."

NA=Not available.

Notes: • Mbbl = thousand barrels. MMgal = million U.S. gallons. TBtu = trillion Btu. • Fuel ethanol data in thousand barrels are converted to million gallons by multiplying by 0.042, and are converted to Btu by multiplying by the approximate heat content of fuel ethanol—see Table A3. • Through 1980, data are not available. For 1981–1992, data are estimates. For 1993–2008, only data for feedstock, losses and co-products, and denaturant are estimates. Beginning in 2009, only data for feedstock, and losses and co-products, are estimates. • See "Denaturant," "Ethanol," "Fuel Ethanol," and "Fuel Ethanol Minus Denaturant" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual and monthly data beginning in 1981.

Sources: See end of section.

**Table 10.4 Biodiesel and Other Renewable Fuels Overview**

	Biodiesel													Other Renewable Fuels <sup>f</sup>
	Feed-stock <sup>a</sup>	Losses and Co-products <sup>b</sup>	Production			Trade			Stocks <sup>d</sup>	Stock Change <sup>e</sup>	Consumption			
						Imports	Exports	Net Imports <sup>c</sup>						
			TBtu	TBtu	Mbbl	MMgal	TBtu	Mbbl			Mbbl	Mbbl	Mbbl	
2001 Total .....	1	(s)	204	9	1	81	41	40	NA	NA	244	10	1	NA
2002 Total .....	1	(s)	250	10	1	197	57	140	NA	NA	390	16	2	NA
2003 Total .....	2	(s)	338	14	2	97	113	-17	NA	NA	322	14	2	NA
2004 Total .....	4	(s)	666	28	4	101	128	-27	NA	NA	639	27	3	NA
2005 Total .....	12	(s)	2,162	91	12	214	213	1	NA	NA	2,163	91	12	NA
2006 Total .....	32	(s)	5,963	250	32	1,105	856	250	NA	NA	6,213	261	33	NA
2007 Total .....	63	1	11,662	490	62	3,455	6,696	-3,241	NA	NA	8,422	354	45	NA
2008 Total .....	88	1	16,145	678	87	7,755	16,673	-8,918	NA	NA	7,228	304	39	NA
2009 Total .....	67	1	12,281	516	66	1,906	6,546	-4,640	711	711	<sup>g</sup> 7,663	322	41	—
2010 Total .....	44	1	8,177	343	44	564	2,588	-2,024	672	-39	6,192	260	33	(s)
2011 Total .....	125	2	23,035	967	123	890	1,799	-908	2,005	<sup>h</sup> 1,028	21,099	886	113	1
2012 Total .....	128	2	23,588	991	126	853	3,056	-2,203	1,984	-20	21,406	899	115	1
2013 Total .....	176	2	32,368	1,359	173	8,152	4,675	3,477	3,810	1,825	34,020	1,429	182	30
2014 Total .....	165	2	30,452	1,279	163	4,578	1,974	2,604	3,131	-679	33,735	1,417	181	28
2015 Total .....	163	2	30,080	1,263	161	8,399	2,091	6,308	3,943	813	35,575	1,494	191	33
2016 Total .....	203	3	37,327	1,568	200	16,879	2,098	14,781	6,398	2,454	49,653	2,085	266	34
2017 Total .....	206	3	37,993	1,596	204	9,374	2,228	7,146	4,268	-2,130	47,269	1,985	253	30
2018 January .....	16	(s)	2,989	126	16	246	84	162	4,565	297	2,853	120	15	1
February .....	17	(s)	3,046	128	16	146	103	43	4,934	369	2,720	114	15	2
March .....	19	(s)	3,551	149	19	457	257	200	4,925	-9	3,760	158	20	3
April .....	18	(s)	3,393	143	18	308	217	91	4,716	-209	3,693	155	20	2
May .....	20	(s)	3,603	151	19	325	396	-71	4,275	-441	3,972	167	21	2
June .....	21	(s)	3,783	159	20	296	276	20	3,850	-425	4,228	178	23	1
July .....	22	(s)	3,960	166	21	157	259	-102	3,742	-107	3,966	167	21	1
August .....	22	(s)	4,102	172	22	281	263	18	3,425	-318	4,437	186	24	1
September .....	21	(s)	3,914	164	21	277	191	86	3,371	-54	4,054	170	22	1
October .....	22	(s)	4,070	171	22	467	204	263	3,647	276	4,058	170	22	1
November .....	21	(s)	3,816	160	20	473	143	330	4,039	392	3,754	158	20	2
December .....	22	(s)	3,995	168	21	536	77	459	4,662	623	3,831	161	21	2
Total .....	240	3	44,222	1,857	237	3,969	2,470	1,499	4,662	394	45,326	1,904	243	19
2019 January .....	19	(s)	3,427	144	18	308	85	223	5,354	692	2,957	124	16	2
February .....	17	(s)	3,108	131	17	233	91	142	5,502	148	3,101	130	17	1
March .....	18	(s)	3,353	141	18	543	226	317	5,389	-113	3,783	159	20	1
April .....	20	(s)	3,623	152	19	410	370	40	5,330	-59	3,721	156	20	2
May .....	20	(s)	3,681	155	20	281	440	-159	4,815	-515	4,037	170	22	2
June .....	18	(s)	3,370	142	18	310	300	10	4,408	-406	3,787	159	20	2
July .....	21	(s)	3,776	159	20	333	392	-59	4,088	-321	4,039	170	22	2
August .....	20	(s)	3,712	156	20	216	291	-75	3,860	-228	3,865	162	21	2
September .....	18	(s)	3,377	142	18	280	238	42	3,706	-154	3,574	150	19	1
October .....	19	(s)	3,436	144	18	314	158	156	3,738	32	3,560	150	19	1
November .....	16	(s)	3,034	127	16	417	56	361	3,887	149	3,246	136	17	(s)
December .....	17	(s)	3,163	133	17	433	83	350	3,907	20	3,493	147	19	2
Total .....	223	3	41,060	1,725	220	4,078	2,730	1,348	3,907	-756	43,163	1,813	231	18
2020 January .....	17	(s)	3,196	134	17	336	31	305	4,312	<sup>i</sup> 394	3,107	130	17	2
February .....	17	(s)	3,067	129	16	302	76	226	4,046	-266	3,559	149	19	1
March .....	20	(s)	3,594	151	19	333	215	118	4,419	373	3,339	140	18	1
April .....	19	(s)	3,407	143	18	611	526	85	4,392	-27	3,519	148	19	3
May .....	19	(s)	3,505	147	19	475	496	-21	4,340	-51	3,535	148	19	1
June .....	20	(s)	3,590	151	19	446	494	-48	4,318	-23	3,565	150	19	1
July .....	21	(s)	3,849	162	21	346	341	5	3,878	-440	4,294	180	23	1
August .....	21	(s)	3,872	163	21	234	524	-290	3,560	-318	3,900	164	21	2
September .....	21	(s)	3,790	159	20	360	426	-66	3,220	-340	4,064	171	22	1
October .....	21	(s)	3,798	160	20	420	113	307	3,476	256	3,849	162	21	2
November .....	20	(s)	3,593	151	19	448	73	375	3,922	445	3,522	148	19	2
11-Month Total ...	213	3	39,260	1,649	210	4,311	3,315	996	3,922	3	40,253	1,691	216	17
2019 11-Month Total ...	206	3	37,897	1,592	203	3,645	2,647	998	3,887	-775	39,670	1,666	213	15
2018 11-Month Total ...	219	3	40,227	1,690	216	3,433	2,393	1,040	4,039	-229	41,495	1,743	222	18

<sup>a</sup> Total vegetable oil and other biomass inputs to the production of biodiesel—calculated by multiplying biodiesel production by 5.433 million Btu per barrel. See "Biodiesel Feedstock" entry in the "Thermal Conversion Factor Source Documentation" at the end of Appendix A.

<sup>b</sup> Losses and co-products from the production of biodiesel. Does not include natural gas, electricity, and other non-biomass energy used in the production of biodiesel—these are included in the industrial sector consumption statistics for the appropriate energy source.

<sup>c</sup> Net imports equal imports minus exports.

<sup>d</sup> Stocks are at end of period. Includes biodiesel stocks at (or in) refineries, pipelines, and bulk terminals. Beginning in 2011, also includes stocks at biodiesel production plants.

<sup>e</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase.

<sup>f</sup> Other renewable diesel fuel and other renewable fuels consumption. See "Renewable Diesel Fuel (Other)" and "Renewable Fuels (Other)" in Glossary.

<sup>g</sup> In 2009, because of incomplete data coverage and differing data sources, a "Balancing Item" amount of 733 thousand barrels (653 thousand barrels in January 2009; 80 thousand barrels in February 2009) is used to balance biodiesel supply

and disposition.

<sup>h</sup> Derived from the final 2010 stocks value for bulk terminals and biodiesel production plants (977 thousand barrels), not the final 2010 value for bulk terminals only (672 thousand barrels) that is shown under "Stocks."

<sup>i</sup> Derived from the preliminary 2019 stocks value (3,919 thousand barrels), not the final 2019 value (3,907 thousand barrels) that is shown under "Stocks."

NA=Not available. —=No data reported. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu, or less than 500 barrels and greater than -500 barrels.

Notes: • Mbbl = thousand barrels. MMgal = million U.S. gallons. TBtu = trillion Btu. • Biodiesel data in thousand barrels are converted to million gallons by multiplying by 0.042, and are converted to Btu by multiplying by 5.359 million Btu per barrel (the approximate heat content of biodiesel—see Table A1). • Through 2000, data are not available. Beginning in 2001, data not from U.S. Energy Information Administration (EIA) surveys are estimates. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual and monthly data beginning in 2001.

Sources: See end of section.

**Table 10.5 Solar Energy Consumption**  
(Trillion Btu)

	Distributed <sup>a</sup> Solar Energy <sup>b</sup>						Utility-Scale <sup>c</sup> Solar Energy <sup>b</sup>				Total <sup>k</sup>
	Heat <sup>f</sup>	Electricity <sup>d</sup>				Total <sup>g</sup>	Electricity <sup>e</sup>				
		Residential Sector	Commercial Sector	Industrial Sector	Total		Commercial Sector <sup>h</sup>	Industrial Sector <sup>i</sup>	Electric Power Sector <sup>j</sup>	Total	
1985 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	(s)	(s)	(s)
1990 Total .....	55	(s)	(s)	(s)	(s)	55	—	—	4	4	59
1995 Total .....	63	(s)	(s)	(s)	1	63	—	—	5	5	68
2000 Total .....	57	(s)	1	(s)	1	58	—	—	5	5	63
2001 Total .....	55	(s)	1	(s)	1	56	—	—	6	6	62
2002 Total .....	53	1	1	(s)	2	54	—	—	6	6	60
2003 Total .....	51	1	1	(s)	2	53	—	—	5	5	58
2004 Total .....	50	1	1	(s)	2	53	—	—	6	6	58
2005 Total .....	49	1	2	(s)	3	52	—	—	6	6	58
2006 Total .....	51	2	3	1	5	56	—	—	5	5	61
2007 Total .....	53	2	4	1	7	60	—	—	6	6	66
2008 Total .....	54	4	6	1	11	66	(s)	—	9	9	74
2009 Total .....	55	5	8	2	15	69	(s)	—	9	9	78
2010 Total .....	56	9	12	3	24	79	(s)	(s)	12	12	91
2011 Total .....	58	13	20	4	37	95	1	(s)	17	18	112
2012 Total .....	59	20	32	7	59	118	1	(s)	40	41	159
2013 Total .....	61	31	38	9	78	138	3	(s)	83	86	225
2014 Total .....	62	47	49	11	107	169	4	(s)	165	168	338
2015 Total .....	63	65	53	14	132	195	4	(s)	228	232	427
2016 Total .....	64	98	57	19	174	238	5	(s)	328	333	570
2017 Total .....	65	128	71	22	221	286	5	(s)	486	491	777
2018 January .....	4	8	5	1	15	18	(s)	(s)	30	30	49
February .....	4	9	6	1	16	20	(s)	(s)	35	35	55
March .....	5	13	7	2	22	28	(s)	(s)	46	46	74
April .....	6	14	8	2	25	31	(s)	(s)	55	55	86
May .....	7	16	9	2	27	34	1	(s)	62	62	96
June .....	7	16	9	2	28	35	1	(s)	67	68	102
July .....	7	17	9	3	29	36	1	(s)	61	61	97
August .....	7	16	9	2	27	34	1	(s)	60	61	95
September .....	6	14	8	2	24	30	(s)	(s)	54	54	85
October .....	5	13	7	2	22	27	(s)	(s)	45	45	72
November .....	4	10	6	2	17	22	(s)	(s)	34	34	56
December .....	4	9	5	1	16	20	(s)	(s)	28	28	48
Total .....	66	156	89	24	269	334	5	(s)	576	581	916
2019 January .....	4	10	6	1	17	21	(s)	(s)	32	32	52
February .....	4	11	6	2	18	22	(s)	(s)	34	34	56
March .....	6	15	8	2	26	31	(s)	(s)	52	53	84
April .....	6	17	9	2	29	35	(s)	(s)	60	60	95
May .....	7	19	10	3	32	38	1	(s)	63	64	102
June .....	7	19	10	3	32	39	1	(s)	70	71	110
July .....	7	20	10	3	33	41	1	(s)	72	72	113
August .....	7	19	10	3	32	39	1	(s)	69	70	109
September .....	6	17	9	3	29	35	(s)	(s)	60	61	95
October .....	5	15	8	2	25	31	(s)	(s)	54	54	85
November .....	4	12	6	2	20	24	(s)	(s)	38	39	63
December .....	4	11	6	2	18	22	(s)	(s)	30	31	53
Total .....	66	186	98	27	311	377	5	1	635	641	1,018
2020 January .....	4	12	7	2	21	24	(s)	(s)	41	42	66
February .....	4	14	7	2	23	27	(s)	(s)	50	51	78
March .....	6	18	10	3	31	36	(s)	(s)	57	57	93
April .....	6	21	11	3	34	40	1	(s)	71	72	112
May .....	7	23	12	3	38	45	1	(s)	86	87	131
June .....	7	23	12	3	38	45	1	(s)	84	85	130
July .....	7	24	12	3	40	47	1	(s)	92	92	139
August .....	7	23	12	3	38	45	1	(s)	83	83	128
September .....	6	20	11	3	33	40	(s)	(s)	68	69	109
October .....	5	19	9	3	30	36	(s)	(s)	65	65	101
November .....	4	15	7	2	25	29	(s)	(s)	52	52	81
11-Month Total .....	62	212	109	29	351	413	6	1	749	756	1,169
2019 11-Month Total .....	62	175	92	25	293	355	5	1	604	610	965
2018 11-Month Total .....	62	146	84	23	253	314	5	(s)	548	553	867

<sup>a</sup> Data are estimates for distributed (small-scale) facilities (combined generator nameplate capacity less than 1 megawatt).

<sup>b</sup> See "Photovoltaic Energy" and "Solar Thermal Energy" in Glossary.

<sup>c</sup> Data are for utility-scale facilities (combined generator nameplate capacity of 1 megawatt or more).

<sup>d</sup> Solar photovoltaic (PV) electricity generation at distributed (small-scale) facilities connected to the electric power grid (converted to Btu by multiplying by the fossil fuels heat rate factors in Table A6).

<sup>e</sup> Solar photovoltaic (PV) and solar thermal electricity net generation at utility-scale facilities (converted to Btu by multiplying by the fossil fuels heat rate factors in Table A6).

<sup>f</sup> Solar thermal direct use energy in the residential, commercial, and industrial sectors for all end uses, such as pool heating, hot water heating, and space heating.

<sup>g</sup> Data are the sum of "Distributed Solar Energy Heat" and "Distributed Solar Energy Electricity."

<sup>h</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at

end of Section 7.

<sup>i</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>j</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>k</sup> Data are the sum of "Distributed Solar Energy Total" and "Utility-Scale Solar Energy Total."

NA=Not available. —=No data reported. (s)=Less than 0.5 trillion Btu.

Notes: • Distributed (small-scale) solar energy data for all years, and utility-scale solar energy data for the current two years, are estimates. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual and monthly data beginning in 1984.

Sources: See end of section.

**Table 10.6 Solar Electricity Net Generation**  
(Million Kilowatthours)

	Distributed <sup>a</sup> Solar Generation <sup>b</sup>				Utility-Scale <sup>c</sup> Solar Generation <sup>b</sup>				Total
	Residential Sector	Commercial Sector	Industrial Sector	Total	Commercial Sector <sup>d</sup>	Industrial Sector <sup>e</sup>	Electric Power Sector <sup>f</sup>	Total	
<b>1985 Total</b> .....	NA	NA	NA	NA	NA	NA	11	11	11
<b>1990 Total</b> .....	12	18	4	33	—	—	367	367	400
<b>1995 Total</b> .....	20	30	7	58	—	—	497	497	554
<b>2000 Total</b> .....	39	59	13	110	—	—	493	493	604
<b>2001 Total</b> .....	47	71	16	134	—	—	543	543	676
<b>2002 Total</b> .....	56	84	19	158	—	—	555	555	713
<b>2003 Total</b> .....	65	98	22	185	—	—	534	534	719
<b>2004 Total</b> .....	81	121	27	229	—	—	575	575	804
<b>2005 Total</b> .....	121	182	40	344	—	—	550	550	894
<b>2006 Total</b> .....	177	266	59	501	—	—	508	508	1,009
<b>2007 Total</b> .....	250	375	83	708	—	—	612	612	1,319
<b>2008 Total</b> .....	401	603	133	1,137	(s)	—	864	864	2,002
<b>2009 Total</b> .....	539	810	179	1,529	(s)	—	891	891	2,420
<b>2010 Total</b> .....	900	1,237	274	2,411	5	2	1,206	1,212	3,623
<b>2011 Total</b> .....	1,358	2,020	447	3,825	84	7	1,727	1,818	5,643
<b>2012 Total</b> .....	2,058	3,351	742	6,151	148	14	4,164	4,327	10,478
<b>2013 Total</b> .....	3,217	4,024	891	8,132	294	17	8,724	9,036	17,167
<b>2014 Total</b> .....	4,947	5,146	1,139	11,233	371	16	17,304	17,691	28,924
<b>2015 Total</b> .....	6,999	5,689	1,451	14,139	416	21	24,456	24,893	39,032
<b>2016 Total</b> .....	10,595	6,158	2,060	18,813	529	27	35,497	36,054	54,866
<b>2017 Total</b> .....	13,942	7,685	2,364	23,990	521	42	52,724	53,287	77,277
<b>2018 January</b> .....	921	552	146	1,619	29	2	3,288	3,319	4,938
February .....	1,007	605	155	1,766	31	3	3,863	3,896	5,663
March .....	1,393	820	221	2,434	43	4	5,009	5,056	7,490
April .....	1,592	907	241	2,740	50	4	6,002	6,057	8,796
May .....	1,753	992	267	3,011	57	5	6,788	6,849	9,860
June .....	1,788	1,003	268	3,059	62	5	7,347	7,415	10,474
July .....	1,834	1,036	277	3,146	59	5	6,691	6,755	9,901
August .....	1,756	993	268	3,017	56	5	6,634	6,695	9,712
September .....	1,539	893	242	2,674	46	4	5,911	5,961	8,635
October .....	1,385	786	220	2,392	39	4	4,926	4,970	7,361
November .....	1,108	623	174	1,905	29	3	3,711	3,743	5,648
December .....	1,029	589	157	1,775	25	2	3,083	3,110	4,885
<b>Total</b> .....	<b>17,105</b>	<b>9,798</b>	<b>2,636</b>	<b>29,539</b>	<b>525</b>	<b>47</b>	<b>63,253</b>	<b>63,825</b>	<b>93,365</b>
<b>2019 January</b> .....	1,107	629	168	1,903	30	4	3,546	3,580	5,483
February .....	1,205	676	178	2,059	34	5	3,798	3,836	5,895
March .....	1,727	933	254	2,914	50	7	5,841	5,899	8,813
April .....	1,935	1,032	278	3,245	54	8	6,690	6,752	9,997
May .....	2,130	1,110	309	3,549	58	9	7,095	7,162	10,711
June .....	2,175	1,118	311	3,604	63	10	7,898	7,971	11,575
July .....	2,268	1,171	321	3,760	69	10	8,053	8,133	11,893
August .....	2,184	1,116	311	3,611	64	9	7,803	7,877	11,488
September .....	1,930	994	281	3,205	55	8	6,754	6,817	10,022
October .....	1,697	881	255	2,833	46	7	6,040	6,093	8,926
November .....	1,346	683	198	2,228	36	5	4,323	4,364	6,592
December .....	1,210	657	179	2,047	26	4	3,423	3,453	5,500
<b>Total</b> .....	<b>20,914</b>	<b>11,002</b>	<b>3,041</b>	<b>34,957</b>	<b>587</b>	<b>85</b>	<b>71,265</b>	<b>71,937</b>	<b>106,894</b>
<b>2020 January</b> .....	1,385	736	193	2,314	37	6	4,648	4,690	7,004
February .....	1,579	835	214	2,627	44	7	5,667	5,717	8,344
March .....	2,050	1,091	295	3,435	52	8	6,374	6,434	9,869
April .....	2,312	1,200	318	3,829	64	10	7,975	8,048	11,878
May .....	2,612	1,313	351	4,277	75	13	9,646	9,734	14,011
June .....	2,613	1,319	357	4,288	72	13	9,444	9,529	13,817
July .....	2,691	1,378	372	4,442	78	14	10,287	10,379	14,821
August .....	2,550	1,330	360	4,240	68	12	9,290	9,370	13,610
September .....	2,250	1,182	324	3,756	56	11	7,690	7,757	11,514
October .....	2,090	1,019	292	3,401	52	10	7,263	7,326	10,727
November .....	1,732	812	226	2,770	42	8	5,839	5,890	8,660
<b>11-Month Total</b> .....	<b>23,864</b>	<b>12,215</b>	<b>3,301</b>	<b>39,379</b>	<b>639</b>	<b>112</b>	<b>84,124</b>	<b>84,875</b>	<b>124,255</b>
<b>2019 11-Month Total</b> .....	<b>19,704</b>	<b>10,344</b>	<b>2,862</b>	<b>32,911</b>	<b>561</b>	<b>82</b>	<b>67,841</b>	<b>68,484</b>	<b>101,394</b>
<b>2018 11-Month Total</b> .....	<b>16,076</b>	<b>9,209</b>	<b>2,479</b>	<b>27,764</b>	<b>501</b>	<b>45</b>	<b>60,170</b>	<b>60,716</b>	<b>88,480</b>

<sup>a</sup> Data are estimates for solar photovoltaic (PV) electricity generation at small-scale facilities (combined generator nameplate capacity less than 1 megawatt) connected to the electric power grid.

<sup>b</sup> See "Photovoltaic Energy" and "Solar Thermal Energy" in Glossary.

<sup>c</sup> Solar photovoltaic (PV) and solar thermal electricity net generation at utility-scale facilities (combined generator nameplate capacity of 1 megawatt or more).

<sup>d</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>e</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>f</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

NA=Not available. —=No data reported. (s)=Less than 0.5 million kilowatthours.

Notes: • Distributed (small-scale) solar generation data for all years, and

utility-scale solar energy data for the current two years, are estimates. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual and monthly data beginning in 1984.

Sources: • **Distributed Solar Generation: 1989–2013**—Calculated as distributed solar energy consumption (see Table 10.5) divided by the total fossil fuels heat rate factors (see Table A6). **2014 forward**—U.S. Energy Information Administration (EIA), *Electric Power Monthly*, monthly reports, Tables 1.1, 1.2.C, 1.2.D, and 1.2.E. • **Utility-Scale Solar Generation: 1984–1988**—EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report." **1989–1997**: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility." **2001–2003**: EIA, Form EIA-906, "Power Plant Report." **2004–2007**: EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." **2008 forward**: EIA, Form EIA-923, "Power Plant Operations Report." • **Total**: Calculated as distributed solar generation plus utility-scale solar generation.

**Note. Renewable Energy Production and Consumption.** In Tables 1.1, 1.3, and 10.1, renewable energy consumption consists of: conventional hydroelectricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6); geothermal electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), and geothermal heat pump and geothermal direct use energy; solar thermal and photovoltaic electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), and solar thermal direct use energy; wind electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6); wood and wood-derived fuels consumption; biomass waste (municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass) consumption; fuel ethanol (minus denaturant), biodiesel, and other renewable fuels consumption; and losses and co-products from the production of fuel ethanol and biodiesel. In Tables 1.1, 1.2, and 10.1, renewable energy production is assumed to equal consumption for all renewable energy sources except biofuels and wood. Biofuels production comprises biomass inputs to the production of fuel ethanol and biodiesel. Wood production is the sum of wood consumption and densified biomass exports.

### Table 10.2a Sources

#### *Residential Sector, Geothermal*

1989–2011: Annual estimates by the U.S. Energy Information Administration (EIA) based on data from Oregon Institute of Technology, Geo-Heat Center.

2012 forward: Annual estimates assumed by EIA to be equal to that of 2011.

(For 1989 forward, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

#### *Residential Sector, Solar*

1989 forward: Residential sector solar consumption is the sum of the values for "Distributed Solar Energy Consumption: Heat" (which includes solar thermal direct use energy in the residential, commercial, and industrial sectors) from Table 10.5 and "Distributed Solar Energy Consumption: Electricity, Residential Sector" from Table 10.5.

#### *Residential Sector, Wood*

1949–1979: Annual estimates are from EIA, *Estimates of U.S. Wood Energy Consumption from 1949 to 1981*, Table A2.

1980–2008: Annual estimates are based on EIA, Form EIA-457, "Residential Energy Consumption Survey"; and National Oceanic and Atmospheric Administration regional heating degree-day data.

2009 forward: Annual estimates based on EIA, Form EIA-457, "Residential Energy Consumption Survey"; and residential wood consumption growth rates from EIA's *Annual Energy Outlook* data system.

(For 1973 forward, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

#### *Residential Sector, Total Renewable Energy*

1949–1988: Residential sector total renewable energy consumption is equal to residential sector wood consumption.

1989 forward: Residential sector total renewable energy consumption is the sum of the residential sector consumption values for geothermal, solar, and wood.

#### *Commercial Sector, Hydroelectric Power*

1989 forward: Commercial sector conventional hydroelectricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," and predecessor forms, are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Commercial Sector, Geothermal Heat Pump and Direct Use Energy***

1989–2011: Annual estimates by EIA based on data from Oregon Institute of Technology, Geo-Heat Center.

2012 forward: Annual estimates assumed by EIA to be equal to that of 2011.

(For 1989 forward, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

### ***Commercial Sector, Geothermal Electricity Net Generation***

December 2018 forward: Commercial sector geothermal electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Commercial Sector, Geothermal Total***

1989–November 2018: Commercial sector geothermal total consumption is equal to commercial sector heat pump and direct use energy.

December 2018 forward: Commercial sector geothermal total consumption is the sum of the commercial sector values for geothermal heat pump and direct use energy, and geothermal electricity net generation.

### ***Commercial Sector, Solar***

1989 forward: Commercial sector solar consumption is the sum of the values for "Distributed Solar Energy Consumption: Electricity, Commercial Sector" from Table 10.5 and "Utility-Scale Solar Energy Consumption: Electricity, Commercial Sector" from Table 10.5.

### ***Commercial Sector, Wind***

2009 forward: Commercial sector wind electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Commercial Sector, Wood***

1949–1979: Annual estimates are from EIA, *Estimates of U.S. Wood Energy Consumption from 1949 to 1981*, Table A2.

1980–1983: Annual estimates are from EIA, *Estimates of U.S. Wood Energy Consumption 1980–1983*, Table ES1.

1984: Annual estimate assumed by EIA to be equal to that of 1983.

1985–1988: Annual estimates interpolated by EIA.

(For 1973–1988, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

1989 forward: Monthly/annual commercial sector combined-heat-and-power (CHP) wood consumption data are from EIA, Form EIA-923, "Power Plant Operations Report," and predecessor forms. Annual estimates for commercial sector non-CHP wood consumption are based on EIA, Form EIA-871, "Commercial Buildings Energy Consumption Survey" (for 2014–2016, the annual estimates are based on commercial sector biomass consumption growth rates from EIA's *Annual Energy Outlook* data system; for 2017 forward, annual estimates are assumed by EIA to be equal to that of 2016). For 1989 forward, monthly estimates for commercial sector non-CHP wood consumption are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. Commercial sector total wood consumption is the sum of commercial sector CHP and non-CHP wood consumption.

### ***Commercial Sector, Biomass Waste***

1989 forward: Table 7.4c.

### ***Commercial Sector, Fuel Ethanol (Minus Denaturant)***

1981 forward: The commercial sector share of motor gasoline consumption is equal to commercial sector motor gasoline consumption from Table 3.7a divided by motor gasoline product supplied from Table 3.5. Commercial sector

fuel ethanol (minus denaturant) consumption is equal to fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the commercial sector share of motor gasoline consumption. Note that there is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors; beginning in 2015, the commercial and industrial sector shares of fuel ethanol consumption are larger than in 2014, while the transportation sector share is smaller.

### ***Commercial Sector, Total Biomass***

1949–1980: Commercial sector total biomass consumption is equal to commercial sector wood consumption.

1981–1988: Commercial sector total biomass consumption is the sum of the commercial sector consumption values for wood and fuel ethanol (minus denaturant).

1989 forward: Commercial sector total biomass consumption is the sum of the commercial sector consumption values for wood, waste, and fuel ethanol (minus denaturant).

### ***Commercial Sector, Total Renewable Energy***

1949–1988: Commercial sector total renewable energy consumption is equal to commercial sector total biomass consumption.

1989–2007: Commercial sector total renewable energy consumption is the sum of the commercial sector consumption values for conventional hydroelectric power, geothermal, and total biomass.

2008: Commercial sector total renewable energy consumption is the sum of the commercial sector consumption values for conventional hydroelectric power, geothermal, solar, and total biomass.

2009 forward: Commercial sector total renewable energy is the sum of the commercial sector consumption values for conventional hydroelectric power, geothermal, solar, wind, and total biomass.

## **Table 10.2b Sources**

### ***Industrial Sector, Hydroelectric Power***

1949 forward: Industrial sector conventional hydroelectricity net generation data from Table 7.2c are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Industrial Sector, Geothermal***

1989–2009: Annual estimates by the U.S. Energy Information Administration (EIA) based on data from Oregon Institute of Technology, Geo-Heat Center.

2010 forward: Annual estimates assumed by EIA to be equal to that of 2009.

(For 1989 forward, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

### ***Industrial Sector, Solar***

1989 forward: Industrial sector solar consumption is the sum of the values for "Distributed Solar Energy Consumption: Electricity, Industrial Sector" from Table 10.5 and "Utility-Scale Solar Energy Consumption: Electricity, Industrial Sector" from Table 10.6.

### ***Industrial Sector, Wind***

2011 forward: Industrial sector wind electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Industrial Sector, Wood***

1949–1979: Annual estimates are from EIA, *Estimates of U.S. Wood Energy Consumption from 1949 to 1981*, Table A2.



1980–1983: Annual estimates are from EIA, *Estimates of U.S. Wood Energy Consumption 1980–1983*, Table ES1.

1984: Annual estimate is from EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 1.

1985 and 1986: Annual estimates interpolated by EIA.

1987: Annual estimate is from EIA, *Estimates of Biofuels Consumption in the United States During 1987*, Table 2.

1988: Annual estimate interpolated by EIA.

(For 1973–1988, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

1989 forward: Monthly/annual industrial sector combined-heat-and-power (CHP) wood consumption data are from EIA, Form EIA-923, "Power Plant Operations Report," and predecessor forms. Annual estimates for industrial sector non-CHP wood consumption are based on EIA, Form EIA-846, "Manufacturing Energy Consumption Survey" (for 2015 forward, the annual estimates are assumed by EIA to be equal to that of 2014). For 1989 forward, monthly estimates for industrial sector non-CHP wood consumption are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. Industrial sector total wood consumption is the sum of industrial sector CHP and non-CHP wood consumption.

### ***Industrial Sector, Biomass Waste***

1981: Annual estimate is calculated as total waste consumption (from EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 8) minus electric power sector waste consumption (from MER Table 10.2c).

1982 and 1983: Annual estimates are calculated as total waste consumption (based on *Estimates of U.S. Biofuels Consumption 1990*, Table 8) minus electric power sector waste consumption (from MER, Table 10.2c).

1984: Annual estimate is calculated as total waste consumption (from EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 8) minus electric power sector waste consumption (from MER, Table 10.2c).

1985 and 1986: Annual estimates interpolated by EIA.

1987: Annual estimate is calculated as total waste consumption (from EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 8) minus electric power sector waste consumption (from MER, Table 10.2c).

1988: Annual estimate interpolated by EIA.

(For 1973–1988, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

1989 forward: Monthly/annual industrial sector combined-heat-and-power (CHP) consumption data are from Table 7.4c. Annual estimates for industrial sector non-CHP waste consumption are based on information presented in Government Advisory Associates, *Resource Recovery Yearbook* and *Methane Recovery Yearbook*, and information provided by the U.S. Environmental Protection Agency, Landfill Methane Outreach Program (for 2014 forward, the annual estimates are assumed by EIA to be equal to that of 2013). For 1989 forward, monthly estimates for industrial sector non-CHP waste consumption are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. Industrial sector total waste consumption is the sum of industrial sector CHP and non-CHP waste consumption.

### ***Industrial Sector, Fuel Ethanol (Minus Denaturant)***

1981 forward: The industrial sector share of motor gasoline consumption is equal to industrial sector motor gasoline consumption from Table 3.7b divided by motor gasoline product supplied from Table 3.5. Industrial sector fuel ethanol (minus denaturant) consumption is equal to fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the industrial sector share of motor gasoline consumption. Note that there is a discontinuity in this time series between

2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors; beginning in 2015, the commercial and industrial sector shares of fuel ethanol consumption are larger than in 2014, while the transportation sector share is smaller.

#### ***Industrial Sector, Biomass Losses and Co-products***

1981 forward: Calculated as fuel ethanol losses and co-products from Table 10.3 plus biodiesel losses and co-products from Table 10.4.

#### ***Industrial Sector, Total Biomass***

1949–1980: Industrial sector total biomass consumption is equal to industrial sector wood consumption.

1981 forward: Industrial sector total biomass consumption is the sum of the industrial sector consumption values for wood, waste, fuel ethanol (minus denaturant), and biomass losses and co-products.

#### ***Industrial Sector, Total Renewable Energy***

1949–1988: Industrial sector total renewable energy consumption is the sum of the industrial sector consumption values for conventional hydroelectric power and total biomass.

1989–2009: Industrial sector total renewable energy consumption is the sum of the industrial sector consumption values for conventional hydroelectric power, geothermal, and total biomass.

2010: Industrial sector total renewable energy consumption is the sum of the industrial sector consumption values for conventional hydroelectric power, geothermal, solar, and total biomass.

2011 forward: Industrial sector total renewable energy consumption is the sum of the industrial sector consumption values for conventional hydroelectric power, geothermal, solar, wind, and total biomass.

#### ***Transportation Sector, Fuel Ethanol (Minus Denaturant)***

1981 forward: The transportation sector share of motor gasoline consumption is equal to transportation sector motor gasoline consumption from Table 3.7c divided by motor gasoline product supplied from Table 3.5. Transportation sector fuel ethanol (minus denaturant) consumption is equal to fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the transportation sector share of motor gasoline consumption. Note that there is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors; beginning in 2015, the commercial and industrial sector shares of fuel ethanol consumption are larger than in 2014, while the transportation sector share is smaller.

#### ***Transportation Sector, Biodiesel***

2001 forward: Table 10.4. Transportation sector biodiesel consumption is assumed to equal total biodiesel consumption.

#### ***Transportation Sector, Other Renewable Fuels***

2009 forward: Table 10.4.

#### ***Transportation Sector, Total Renewable Energy***

1981–2000: Transportation sector total renewable energy consumption is equal to transportation sector fuel ethanol (minus denaturant) consumption.

2001–2008: Transportation sector total renewable energy consumption is the sum of the transportation sector consumption values for fuel ethanol (minus denaturant) and biodiesel.

2009 forward: Transportation sector total renewable energy consumption is the sum of the transportation sector consumption values for fuel ethanol (minus denaturant), biodiesel, and other renewable fuels.

## Table 10.3 Sources

### *Feedstock*

1981 forward: Calculated as fuel ethanol production (in thousand barrels) minus denaturant, and then multiplied by the fuel ethanol feedstock factor—see Table A3.

### *Losses and Co-products*

1981 forward: Calculated as fuel ethanol feedstock plus denaturant minus fuel ethanol production.

### *Denaturant*

1981–2008: Data in thousand barrels for petroleum denaturant in fuel ethanol produced are estimated as 2% of fuel ethanol production; these data are converted to Btu by multiplying by 4.661 million Btu per barrel (the estimated quantity-weighted factor of natural gasoline and conventional motor gasoline used as denaturant).

2009–2019: U.S. Energy Information Administration (EIA), *Petroleum Supply Annual* (PSA), annual reports, Table 1. Data in thousand barrels for net production of natural gasoline at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 4.638 million Btu per barrel (the approximate heat content of natural gasoline). Data in thousand barrels for net production of conventional motor gasoline and motor gasoline blending components at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 5.222 million Btu per barrel (the approximate heat content of motor gasoline blending components). Total denaturant is the sum of the values for natural gasoline, conventional motor gasoline, and motor gasoline blending components.

2020: EIA, *Petroleum Supply Monthly* (PSM), monthly reports, Table 1. Data in thousand barrels for net production of natural gasoline at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 4.638 million Btu per barrel (the approximate heat content of natural gasoline). Data in thousand barrels for net production of conventional motor gasoline and motor gasoline blending components at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 5.222 million Btu per barrel (the approximate heat content of motor gasoline blending components). Total denaturant is the sum of the values for natural gasoline, conventional motor gasoline, and motor gasoline blending components.

### *Production*

1981–1992: Fuel ethanol production is assumed to equal fuel ethanol consumption—see sources for "Consumption."

1993–2004: Calculated as fuel ethanol consumption plus fuel ethanol stock change minus fuel ethanol net imports. These data differ slightly from the original production data from EIA, Form EIA-819, "Monthly Oxygenate Report," and predecessor form, which were not reconciled and updated to be consistent with the final balance.

2005–2008: EIA, Form EIA-819, "Monthly Oxygenate Report."

2009–2019: EIA, PSA, annual reports, Table 1, data for net production of fuel ethanol at renewable fuels and oxygenate plants.

2020: EIA, PSM, monthly reports, Table 1, data for net production of fuel ethanol at renewable fuels and oxygenate plants.

### *Trade, Stocks, and Stock Change*

1992–2019: EIA, PSA, annual reports, Table 1.

2020: EIA, PSM, monthly reports, Table 1.

### *Consumption*

1981–1989: EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 10; and interpolated values for 1982, 1983, 1985, 1986, and 1988.

1990–1992: EIA, *Estimates of U.S. Biomass Energy Consumption 1992*, Table D2; and interpolated value for 1991.

1993–2004: EIA, PSA, annual reports, Tables 2 and 16. Calculated as 10% of oxygenated finished motor gasoline field production (Table 2), plus fuel ethanol refinery input (Table 16).

2005–2008: EIA, PSA, annual reports, Tables 1 and 15. Calculated as motor gasoline blending components adjustments (Table 1), plus finished motor gasoline adjustments (Table 1), plus fuel ethanol refinery and blender net inputs (Table 15).

2009–2019: EIA, PSA, annual reports, Table 1. Calculated as fuel ethanol refinery and blender net inputs minus fuel ethanol adjustments.

2020: EIA, PSM, monthly reports, Table 1. Calculated as fuel ethanol refinery and blender net inputs minus fuel ethanol adjustments.

### ***Consumption Minus Denaturant***

1981 forward: Calculated as fuel ethanol consumption minus the amount of denaturant in fuel ethanol consumed. Denaturant in fuel ethanol consumed is estimated by multiplying denaturant in fuel ethanol produced by the fuel ethanol consumption-to-production ratio.

## **Table 10.4 Sources**

### ***Biodiesel Feedstock***

2001 forward: Calculated as biodiesel production in thousand barrels multiplied by 5.433 million Btu per barrel (the biodiesel feedstock factor—see "Biodiesel Feedstock" entry in the "Thermal Conversion Factor Source Documentation" at the end of Appendix A).

### ***Biodiesel Losses and Co-products***

2001 forward: Calculated as biodiesel feedstock minus biodiesel production.

### ***Biodiesel Production***

2001–2005: U.S. Department of Agriculture, Commodity Credit Corporation, Bioenergy Program records. Annual data are derived from quarterly data. Monthly data are estimated by dividing the annual data by the number of days in the year and then multiplying by the number of days in the month.

2006: U.S. Department of Commerce, U.S. Census Bureau, "M311K—Fats and Oils: Production, Consumption, and Stocks," data for soybean oil consumed in methyl esters (biodiesel). In addition, the U.S. Energy Information Administration (EIA) estimates that 14.4 million gallons of yellow grease were consumed in methyl esters (biodiesel).

2007: U.S. Department of Commerce, U.S. Census Bureau, "M311K—Fats and Oils: Production, Consumption, and Stocks," data for all fats and oils consumed in methyl esters (biodiesel).

2008: EIA, *Monthly Biodiesel Production Report*, December 2009 (release date October 2010), Table 11. Monthly data for 2008 are estimated based on U.S. Department of Commerce, U.S. Census Bureau, M311K data, multiplied by the EIA 2008 annual value's share of the M311K 2008 annual value.

2009 and 2010: EIA, *Monthly Biodiesel Production Report*, monthly reports, Table 1.

2011–2019: EIA, *Petroleum Supply Annual* (PSA), annual reports, Table 1, data for renewable fuels except fuel ethanol.

2020: EIA, *Petroleum Supply Monthly* (PSM), monthly reports, Table 1, data for renewable fuels except fuel ethanol.

### ***Biodiesel Trade***

2001–2011: For imports, U.S. Department of Agriculture, data for the following Harmonized Tariff Schedule codes: 3824.90.40.20, "Fatty Esters Animal/Vegetable Mixture" (data through June 2010); and 3824.90.40.30,

"Biodiesel/Mixes" (data for July 2010–2011). For exports, U.S. Department of Agriculture, data for the following Schedule B codes: 3824.90.40.00, "Fatty Substances Animal/Vegetable/Mixture" (data through 2010); and 3824.90.40.30, "Biodiesel <70%" (data for 2011). (The data above are converted from pounds to gallons by dividing by 7.4.) Although these categories include products other than biodiesel (such as biodiesel coprocessed with petroleum feedstocks; and products destined for soaps, cosmetics, and other items), biodiesel is the largest component. In the absence of other reliable data for biodiesel trade, EIA sees these data as good substitutes.

2012–2019: EIA, PSA, annual reports, Tables 25 and 31, data for biomass-based diesel fuel.

2020: EIA, PSM, monthly reports, Tables 37 and 49, data for biomass-based diesel fuel.

### ***Biodiesel Stocks and Stock Change***

2009–September 2020: EIA, biodiesel data from EIA-22M, "Monthly Biodiesel Production Survey"; and biomass-based diesel fuel data from EIA-810, "Monthly Refinery Report," EIA-812, "Monthly Product Pipeline Report," and EIA-815, "Monthly Bulk Terminal and Blender Report."

October 2020 forward: EIA, biodiesel data from EIA-819, "Monthly Report of Biofuels, Fuels from Non-Biogenic Wastes, Fuel Oxygenates, Isooctane, and Isooctene"; and biomass-based diesel fuel data from EIA-810, "Monthly Refinery Report," EIA-812, "Monthly Product Pipeline Report," and EIA-815, "Monthly Bulk Terminal and Blender Report."

### ***Biodiesel Consumption***

2001–2008: Calculated as biodiesel production plus biodiesel net imports.

January and February 2009: EIA, PSA, Table 1, data for refinery and blender net inputs of renewable fuels except fuel ethanol.

March 2009 forward: Calculated as biodiesel production plus biodiesel net imports minus biodiesel stock change.

### ***Other Renewable Fuels***

2009 forward: Consumption data for "Other Renewable Diesel Fuel" are set equal to refinery and blender net inputs data from EIA, EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report" (data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Consumption data for "Other Renewable Fuels" are set equal to refinery and blender net inputs data from EIA, EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report" (data are converted to Btu by multiplying by the other renewable fuels heat content factor in Table A1). "Other Renewable Fuels" in Table 10.4 is calculated as other renewable diesel fuel consumption plus other renewable fuels consumption.

## **Table 10.5 Sources**

### ***Distributed Solar Energy Consumption: Heat***

#### ***Annual Data***

1989–2009: Annual estimates by the U.S. Energy Information Administration (EIA) based on EIA, Form EIA-63A, "Annual Solar Thermal Collector/Reflector Shipments Report." Solar energy consumption by solar thermal non-electric applications (mainly in the residential sector, but with some in the commercial and industrial sectors) is based on assumptions about the stock of equipment in place and other factors.

2010 forward: Annual estimates based on commercial sector solar thermal growth rates from EIA's *Annual Energy Outlook* (AEO) data system. (Annual estimates are subject to revision when a new AEO is released.)

#### ***Monthly Data***

1989–2013: Monthly estimates for each year are obtained by allocating a given year's annual value to the months in that year. Each month's allocator is the average of that month's "Distributed Solar Energy Consumption: Electricity, Total" values in 2014 and 2015. The allocators, when rounded, are as follows: January—5%; February—6%; March—8%;

April—9%; May—10%; June—10%; July—10%; August—10%; September—9%; October—9%; November—7%; and December—7%.

2014 forward: Once all 12 months of "Distributed Solar Energy Consumption: Electricity, Total" data are available for a given year, they are used as allocators and applied to the annual estimate in order to derive monthly estimates for that year. Initial monthly estimates for the current year use the previous year's allocators.

#### ***Distributed Solar Energy Consumption: Electricity, Residential Sector***

Beginning in 2014, monthly and annual data for residential sector distributed (small-scale) solar photovoltaic generation are from EIA, *Electric Power Monthly*, Table 1.2.E. Those data are converted to consumption data in Btu by multiplying by the total fossil fuels heat rate factors in MER Table A6.

Backcasts for earlier periods are developed as follows:

#### ***Annual Data***

1989–2003: Annual growth rates are calculated based on distributed (small-scale) solar electricity consumption in all sectors. Consumption is estimated using information on shipments of solar panels from EIA, Form EIA-63B, "Annual Photovoltaic Cell/Module Shipments Report," and assumptions about the stock of equipment in place and other factors. The growth rates are applied to more recent data to create historical annual estimates.

2004–2008: Annual growth rates based on commercial sector solar photovoltaic growth rates from EIA's *Annual Energy Outlook* (AEO) data system are applied to more recent data to create historical annual estimates. (Annual estimates are subject to revision when a new AEO is released.)

2009–2013: Annual growth rates based on residential sector solar photovoltaic growth rates from EIA's *Annual Energy Outlook* (AEO) data system are applied to more recent data to create historical annual estimates. (Annual estimates are subject to revision when a new AEO is released.)

#### ***Monthly Data***

1989–2013: See "Distributed Solar Energy Consumption: Heat, Monthly Data."

#### ***Distributed Solar Energy Consumption: Electricity, Commercial Sector***

Beginning in 2014, monthly and annual data for commercial sector distributed (small-scale) solar photovoltaic generation are from EIA, *Electric Power Monthly*, Table 1.2.C. Those data are converted to consumption data in Btu by multiplying by the total fossil fuels heat rate factors in MER Table A6.

Backcasts for earlier periods are developed as follows:

#### ***Annual Data***

1989–2003: Annual growth rates based on EIA, Form EIA-63B, "Annual Photovoltaic Cell/Module Shipments Report," are applied to more recent data to create historical annual estimates. (See "Distributed Solar Energy Consumption: Electricity, Residential Sector" sources above for details.)

2004–2013: Annual growth rates based on commercial sector solar photovoltaic growth rates from EIA's *Annual Energy Outlook* (AEO) data system are applied to more recent data to create historical annual estimates. (Annual estimates are subject to revision when a new AEO is released.)

#### ***Monthly Data***

1989–2013: See "Distributed Solar Energy Consumption: Heat, Monthly Data."

#### ***Distributed Solar Energy Consumption: Electricity, Industrial Sector***

Beginning in 2014, monthly and annual data for industrial sector distributed (small-scale) solar photovoltaic generation are from EIA, *Electric Power Monthly*, Table 1.2.D. Those data are converted to consumption data in Btu by multiplying by the total fossil fuels heat rate factors in MER Table A6.

Backcasts for earlier periods are developed as follows:

### ***Annual Data***

1989–2003: Annual growth rates based on EIA, Form EIA-63B, "Annual Photovoltaic Cell/Module Shipments Report," are applied to more recent data to create historical annual estimates. (See "Distributed Solar Energy Consumption: Electricity, Residential Sector" sources above for details.)

2004–2013: Annual growth rates based on commercial sector solar photovoltaic growth rates from EIA's *Annual Energy Outlook* (AEO) data system are applied to more recent data to create historical annual estimates. (Annual estimates are subject to revision when a new AEO is released.)

### ***Monthly Data***

1989–2013: See "Distributed Solar Energy Consumption: Heat, Monthly Data."

### ***Distributed Solar Energy Consumption: Electricity, Total***

1989 forward: Distributed (small-scale) solar energy consumption for total electricity is the sum of the distributed solar energy consumption (for electricity) values for the residential, commercial, and industrial sectors.

### ***Distributed Solar Energy Consumption: Total***

1989 forward: Distributed (small-scale) solar energy consumption total is the sum of distributed solar energy consumption values for heat and total electricity.

### ***Utility-Scale Solar Energy Consumption: Electricity, Commercial Sector***

2008 forward: Commercial sector solar photovoltaic and solar thermal electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Utility-Scale Solar Energy Consumption: Electricity, Industrial Sector***

2010 forward: Industrial sector solar photovoltaic and solar thermal electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Utility-Scale Solar Energy Consumption: Electricity, Electric Power Sector***

1984 forward: Electric power sector solar photovoltaic and solar thermal electricity net generation data from Table 7.2b are converted to Btu by multiplying the total fossil fuels heat rate factors in Table A6.

### ***Utility-Scale Solar Energy Consumption: Electricity, Total***

1984 forward: Utility-scale solar energy consumption for total electricity is the sum of the utility-scale solar energy consumption (for electricity) values for the commercial, industrial, and electric power sectors.

### ***Solar Energy Consumption: Total***

1984 forward: Total solar energy consumption is the sum of the values for total distributed solar energy consumption and total utility-scale solar energy consumption.

# 11. Environment


---




**Figure 11.1 Carbon Dioxide Emissions From Energy Consumption by Source**

(Million Metric Tons of Carbon Dioxide)


Total [a], 1973–2019




Total [a], Monthly




By Major Source, 1973–2019




By Major Source, Monthly



Total [a], January–November



By Major Source, November 2020



[a] Excludes emissions from biomass energy consumption.

[b] Includes coal coke net imports.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#environment>.

Source: Table 11.1.

**Table 11.1 Carbon Dioxide Emissions From Energy Consumption by Source**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal <sup>b</sup>	Natural Gas <sup>c</sup>	Petroleum										Total	Total <sup>h,i</sup>
			Aviation Gasoline	Distillate Fuel Oil <sup>d</sup>	HGL <sup>e</sup>	Jet Fuel	Kero-sene	Lubri-cants	Motor Gasoline <sup>f</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>g</sup>		
<b>1973 Total</b> .....	1,206	1,176	6	480	80	155	32	13	911	54	510	99	2,340	4,722
<b>1975 Total</b> .....	1,181	1,044	5	442	73	146	24	11	911	51	445	94	2,202	4,426
<b>1980 Total</b> .....	1,435	1,059	4	446	78	156	24	13	900	49	455	131	2,256	4,750
<b>1985 Total</b> .....	1,637	927	3	445	82	178	17	12	930	55	217	83	2,022	4,587
<b>1990 Total</b> .....	1,821	1,027	3	470	75	223	6	13	988	70	222	115	2,185	5,040
<b>1995 Total</b> .....	1,913	1,186	3	498	90	222	8	13	1,042	77	154	107	2,214	5,323
<b>2000 Total</b> .....	2,156	1,246	3	579	106	254	10	14	1,133	84	165	107	2,454	5,867
<b>2001 Total</b> .....	2,088	1,193	2	597	96	243	11	13	1,149	90	147	125	2,472	5,765
<b>2002 Total</b> .....	2,094	1,231	2	586	98	237	6	12	1,180	100	126	122	2,471	5,809
<b>2003 Total</b> .....	2,135	1,196	2	610	96	231	8	11	1,186	99	140	134	2,517	5,860
<b>2004 Total</b> .....	2,160	1,201	2	632	96	240	10	12	1,209	113	157	136	2,606	5,979
<b>2005 Total</b> .....	2,181	1,183	2	639	92	246	10	12	1,208	111	166	135	2,623	5,999
<b>2006 Total</b> .....	2,147	1,171	2	645	86	240	8	11	1,216	104	125	147	2,584	5,914
<b>2007 Total</b> .....	2,172	1,246	2	647	90	238	5	12	1,208	98	131	143	2,573	6,003
<b>2008 Total</b> .....	2,140	1,255	2	610	89	226	2	11	1,139	92	113	126	2,410	5,817
<b>2009 Total</b> .....	1,876	1,234	2	555	86	204	3	10	1,126	85	92	107	2,271	5,392
<b>2010 Total</b> .....	1,986	1,292	2	583	85	210	3	11	1,110	82	97	115	2,296	5,585
<b>2011 Total</b> .....	1,875	1,311	2	592	79	209	2	10	1,077	79	83	114	2,247	5,446
<b>2012 Total</b> .....	1,657	1,372	2	569	76	206	1	9	1,071	79	67	110	2,189	5,229
<b>2013 Total</b> .....	1,718	1,409	2	573	85	210	1	10	1,086	77	58	116	2,218	5,356
<b>2014 Total</b> .....	1,714	1,440	2	606	86	216	1	10	1,095	78	46	108	2,249	5,413
<b>2015 Total</b> .....	1,480	1,483	1	598	87	227	1	11	1,125	79	47	112	2,288	5,263
<b>2016 Total</b> .....	1,354	1,494	1	576	83	237	1	11	1,144	78	59	120	2,311	5,171
<b>2017 Total</b> .....	1,316	1,475	1	584	86	247	1	10	1,140	72	62	126	2,328	5,131
<b>2018 January</b> .....	126	182	(s)	57	12	20	(s)	1	91	7	5	11	203	513
February .....	92	148	(s)	46	9	18	(s)	1	83	3	4	11	175	415
March .....	90	152	(s)	53	9	21	(s)	1	99	6	4	12	205	447
April .....	82	128	(s)	51	8	20	(s)	1	93	6	6	9	193	404
May .....	95	112	(s)	53	6	21	(s)	1	99	6	5	10	200	407
June .....	110	112	(s)	48	6	22	(s)	1	99	7	4	11	198	421
July .....	124	128	(s)	50	6	22	(s)	1	100	6	5	10	201	454
August .....	124	126	(s)	53	7	23	(s)	1	101	8	4	10	209	460
September .....	107	117	(s)	49	7	21	(s)	1	92	7	5	8	190	415
October .....	97	124	(s)	55	8	21	(s)	1	96	8	4	11	204	426
November .....	103	148	(s)	51	10	21	(s)	1	93	5	5	10	197	449
December .....	110	163	(s)	51	11	21	(s)	1	95	5	6	10	199	473
<b>Total</b> .....	1,260	1,639	2	618	98	250	1	10	1,141	74	57	123	2,374	5,284
<b>2019 January</b> .....	110	187	(s)	55	12	20	(s)	1	91	6	5	11	202	499
February .....	90	165	(s)	49	10	18	(s)	1	85	2	4	7	177	432
March .....	89	159	(s)	53	10	21	(s)	1	95	6	3	10	199	448
April .....	69	120	(s)	50	7	21	(s)	1	95	4	3	11	193	383
May .....	81	116	(s)	52	7	22	(s)	1	98	6	3	12	201	399
June .....	89	115	(s)	49	6	22	(s)	1	97	8	5	10	197	402
July .....	109	130	(s)	49	7	23	(s)	1	99	8	5	10	202	443
August .....	103	132	(s)	51	7	23	(s)	1	102	6	5	12	207	444
September .....	94	120	(s)	48	7	21	(s)	1	92	5	5	11	189	404
October .....	76	125	(s)	54	8	22	(s)	1	96	4	5	11	202	404
November .....	84	151	(s)	52	10	21	(s)	1	92	6	3	11	196	432
December .....	82	173	(s)	50	11	23	(s)	1	93	7	4	11	200	455
<b>Total</b> .....	1,076	1,694	2	613	103	256	1	9	1,137	69	50	127	2,365	5,146
<b>2020 January</b> .....	75	180	(s)	51	10	21	(s)	1	91	5	4	11	194	449
February .....	66	165	(s)	47	9	19	(s)	1	87	5	2	12	182	415
March .....	61	148	(s)	50	9	17	(s)	(s)	81	5	2	12	176	385
April .....	49	122	(s)	43	7	8	(s)	1	59	4	2	10	133	306
May .....	55	113	(s)	45	7	7	(s)	1	74	4	1	11	151	319
June .....	73	116	(s)	43	6	9	(s)	1	83	4	3	9	158	349
July .....	97	136	(s)	45	7	12	(s)	1	88	5	5	9	172	405
August .....	98	131	(s)	46	7	13	(s)	1	88	7	5	10	177	407
September .....	77	118	(s)	47	7	11	(s)	1	86	5	5	8	170	365
October .....	69	127	(s)	51	9	13	(s)	1	86	4	4	8	176	373
November .....	69	133	(s)	48	10	14	(s)	1	80	6	3	9	170	373
<b>11-Month Total</b> ...	788	1,489	1	515	88	144	1	8	903	54	36	108	1,858	4,146
<b>2019 11-Month Total</b> ...	994	1,521	2	563	92	233	1	9	1,045	62	45	115	2,166	4,691
<b>2018 11-Month Total</b> ...	1,150	1,476	1	567	87	230	1	9	1,046	69	52	113	2,175	4,811

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Includes coal coke net imports.

<sup>c</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>d</sup> Distillate fuel oil, excluding biodiesel.

<sup>e</sup> Hydrocarbon gas liquids.

<sup>f</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>g</sup> Aviation gasoline blending components, crude oil, motor gasoline blending components, petrochemical feedstocks, special naphthas, still gas, unfinished oils, waxes, and miscellaneous petroleum products.

<sup>h</sup> Includes electric power sector use of geothermal energy and non-biomass waste. See Table 11.6.

<sup>i</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

(s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption, plus the relatively small amount of emissions from the non-combustion use of fossil fuels. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.


**Figure 11.2 Carbon Dioxide Emissions From Energy Consumption by Sector**

(Million Metric Tons of Carbon Dioxide)


Total [a] by End-Use Sector [b], 1973–2019




Residential Sector by Major Source, 1973–2019




Commercial Sector by Major Source, 1973–2019




Industrial Sector by Major Source, 1973–2019



Transportation Sector by Major Source, 1973–2019



Electric Power Sector by Major Source, 1973–2019



[a] Excludes emissions from biomass energy consumption.

[b] Emissions from energy consumption in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total

electricity retail sales.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#environment>.

Sources: Tables 11.2–11.6.

**Table 11.2 Carbon Dioxide Emissions From Energy Consumption: Residential Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum				Retail Electricity <sup>e</sup>	Total <sup>f</sup>
			Distillate Fuel Oil <sup>c</sup>	HGL <sup>d</sup>	Kerosene	Total		
<b>1973 Total</b> .....	9	264	147	36	16	199	435	907
<b>1975 Total</b> .....	6	266	132	32	12	176	419	867
<b>1980 Total</b> .....	3	256	96	20	8	124	529	911
<b>1985 Total</b> .....	4	241	80	20	11	111	553	909
<b>1990 Total</b> .....	3	238	72	22	5	98	624	963
<b>1995 Total</b> .....	2	263	66	25	5	96	678	1,039
<b>2000 Total</b> .....	1	271	66	35	7	108	805	1,185
<b>2001 Total</b> .....	1	259	66	33	7	106	805	1,171
<b>2002 Total</b> .....	1	265	63	34	4	101	835	1,203
<b>2003 Total</b> .....	1	276	68	34	5	108	847	1,232
<b>2004 Total</b> .....	1	264	67	32	6	106	856	1,227
<b>2005 Total</b> .....	1	262	62	32	6	101	897	1,261
<b>2006 Total</b> .....	1	237	52	28	5	85	869	1,191
<b>2007 Total</b> .....	1	257	53	31	3	86	897	1,241
<b>2008 Total</b> .....	NA	266	55	35	2	91	877	1,235
<b>2009 Total</b> .....	NA	259	43	35	2	79	819	1,157
<b>2010 Total</b> .....	NA	259	41	33	2	77	874	1,210
<b>2011 Total</b> .....	NA	255	38	31	1	71	823	1,149
<b>2012 Total</b> .....	NA	225	35	25	1	61	757	1,043
<b>2013 Total</b> .....	NA	267	36	29	1	66	768	1,100
<b>2014 Total</b> .....	NA	278	39	31	1	71	766	1,115
<b>2015 Total</b> .....	NA	253	40	28	1	69	714	1,037
<b>2016 Total</b> .....	NA	239	32	27	1	60	683	982
<b>2017 Total</b> .....	NA	242	32	27	1	59	645	947
<b>2018 January</b> .....	NA	54	6	5	(s)	12	72	138
February .....	NA	38	4	4	(s)	8	48	94
March .....	NA	36	3	4	(s)	7	45	88
April .....	NA	24	3	3	(s)	6	39	69
May .....	NA	9	2	1	(s)	3	46	59
June .....	NA	7	1	1	(s)	2	60	69
July .....	NA	6	1	1	(s)	2	76	84
August .....	NA	5	1	1	(s)	2	74	81
September .....	NA	6	2	1	(s)	3	60	69
October .....	NA	14	3	2	(s)	6	48	67
November .....	NA	33	4	4	(s)	8	49	90
December .....	NA	42	6	5	(s)	10	57	110
<b>Total</b> .....	NA	275	37	32	1	70	671	1,016
<b>2019 January</b> .....	NA	53	5	5	(s)	R 10	61	124
February .....	NA	45	4	4	(s)	9	50	103
March .....	NA	38	R 4	4	(s)	8	47	93
April .....	NA	18	R 2	2	(s)	5	34	57
May .....	NA	12	2	2	(s)	4	41	56
June .....	NA	7	2	1	(s)	3	51	61
July .....	NA	6	2	1	(s)	R 2	70	79
August .....	NA	6	2	1	(s)	3	67	76
September .....	NA	6	1	1	(s)	R 2	57	65
October .....	NA	13	2	2	(s)	4	42	59
November .....	NA	32	4	4	(s)	8	44	84
December .....	NA	41	5	4	(s)	9	49	100
<b>Total</b> .....	NA	276	R 34	31	1	R 66	611	R 954
<b>2020 January</b> .....	NA	45	4	4	(s)	R 8	48	102
February .....	NA	40	3	4	(s)	R 7	42	R 89
March .....	NA	29	3	3	(s)	6	37	73
April .....	NA	21	3	3	(s)	5	33	59
May .....	NA	13	3	2	(s)	5	38	55
June .....	NA	7	2	1	(s)	3	52	63
July .....	NA	6	1	1	(s)	2	75	84
August .....	NA	6	1	1	(s)	2	71	80
September .....	NA	7	2	1	(s)	3	52	62
October .....	NA	13	2	2	(s)	4	41	59
November .....	NA	24	3	3	(s)	5	39	69
<b>11-Month Total</b> .....	NA	213	26	25	1	52	527	792
<b>2019 11-Month Total</b> .....	NA	235	30	27	1	57	564	856
<b>2018 11-Month Total</b> .....	NA	233	31	27	1	59	616	908

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Hydrocarbon gas liquids.

<sup>e</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 11.6.

<sup>f</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

R=Revised. NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption. See "Section 11 Methodology and Sources" at end of section.

• See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Table 11.3 Carbon Dioxide Emissions From Energy Consumption: Commercial Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum							Retail Electricity <sup>f</sup>	Total <sup>g</sup>
			Distillate Fuel Oil <sup>c</sup>	HGL <sup>d</sup>	Kerosene	Motor Gasoline <sup>e</sup>	Petroleum Coke	Residual Fuel Oil	Total		
1973 Total .....	15	141	47	9	5	6	NA	52	120	334	609
1975 Total .....	14	136	43	8	4	6	NA	39	100	333	583
1980 Total .....	11	141	38	6	3	8	NA	44	98	412	662
1985 Total .....	13	132	46	6	2	7	NA	18	79	480	705
1990 Total .....	12	142	39	6	1	8	0	11	73	566	793
1995 Total .....	11	164	35	7	2	1	(s)	18	56	620	851
2000 Total .....	9	173	36	9	2	3	(s)	7	58	783	1,022
2001 Total .....	9	164	37	9	2	3	(s)	6	57	797	1,027
2002 Total .....	9	170	32	9	1	3	(s)	6	52	795	1,026
2003 Total .....	8	173	36	10	1	4	(s)	9	60	796	1,037
2004 Total .....	10	170	34	10	1	3	(s)	10	58	815	1,053
2005 Total .....	9	163	33	8	2	3	(s)	9	55	841	1,069
2006 Total .....	6	154	29	8	1	3	(s)	6	47	835	1,043
2007 Total .....	7	164	28	8	1	4	(s)	6	46	861	1,078
2008 Total .....	8	171	28	10	(s)	3	(s)	6	47	849	1,075
2009 Total .....	7	169	29	9	(s)	3	(s)	6	47	784	1,007
2010 Total .....	7	168	29	9	(s)	3	(s)	5	46	804	1,025
2011 Total .....	6	171	29	9	(s)	3	(s)	4	45	768	990
2012 Total .....	4	157	26	9	(s)	3	(s)	2	40	731	932
2013 Total .....	4	179	25	10	(s)	3	(s)	2	39	736	958
2014 Total .....	4	190	26	10	(s)	4	(s)	1	41	736	970
2015 Total .....	3	176	26	9	(s)	25	(s)	(s)	61	692	932
2016 Total .....	2	171	24	9	(s)	25	(s)	(s)	59	662	894
2017 Total .....	2	174	24	10	(s)	24	(s)	(s)	58	633	867
2018 January .....	(s)	30	4	2	(s)	2	(s)	(s)	7	56	94
February .....	(s)	23	2	1	(s)	2	(s)	(s)	5	43	72
March .....	(s)	23	2	1	(s)	2	(s)	(s)	5	45	74
April .....	(s)	17	2	1	(s)	2	(s)	(s)	5	42	64
May .....	(s)	9	1	1	(s)	2	0	(s)	4	50	63
June .....	(s)	8	1	1	(s)	2	0	(s)	4	56	68
July .....	(s)	8	1	1	(s)	2	0	(s)	4	65	76
August .....	(s)	8	1	1	(s)	2	0	(s)	3	65	76
September .....	(s)	8	1	1	(s)	2	(s)	(s)	4	57	68
October .....	(s)	13	2	1	(s)	2	(s)	(s)	5	52	70
November .....	(s)	21	3	1	(s)	2	(s)	(s)	6	50	77
December .....	(s)	25	4	1	(s)	2	(s)	(s)	7	50	83
Total .....	2	193	24	11	(s)	24	(s)	(s)	59	632	886
2019 January .....	(s)	31	3	1	(s)	2	(s)	(s)	7	51	89
February .....	(s)	26	3	1	(s)	2	(s)	(s)	6	44	76
March .....	(s)	23	3	1	(s)	2	(s)	(s)	6	45	74
April .....	(s)	14	2	1	(s)	2	(s)	(s)	R 5	38	57
May .....	(s)	10	1	1	(s)	2	0	(s)	4	45	60
June .....	(s)	8	1	1	(s)	2	0	(s)	4	49	61
July .....	(s)	8	1	1	(s)	2	0	(s)	4	60	72
August .....	(s)	8	2	1	(s)	2	0	(s)	4	59	71
September .....	(s)	8	1	1	(s)	2	0	(s)	3	53	64
October .....	(s)	12	1	1	(s)	2	0	(s)	4	45	61
November .....	(s)	21	3	1	(s)	2	0	(s)	6	44	72
December .....	(s)	25	3	1	(s)	2	(s)	(s)	7	44	76
Total .....	2	193	R 24	11	(s)	24	(s)	(s)	R 60	578	R 832
2020 January .....	(s)	27	3	1	(s)	2	(s)	(s)	6	42	75
February .....	(s)	24	2	1	(s)	2	(s)	(s)	5	38	68
March .....	(s)	19	2	1	(s)	2	0	(s)	5	37	61
April .....	(s)	13	2	1	(s)	1	0	(s)	4	30	47
May .....	(s)	9	2	1	(s)	2	0	(s)	4	33	47
June .....	(s)	7	1	1	(s)	2	0	(s)	4	43	54
July .....	(s)	7	1	1	(s)	2	0	(s)	3	56	67
August .....	(s)	7	1	1	(s)	2	0	(s)	3	55	65
September .....	(s)	8	1	1	(s)	2	0	(s)	4	45	57
October .....	(s)	11	1	1	(s)	2	0	(s)	4	42	58
November .....	(s)	16	2	1	(s)	2	0	(s)	5	38	59
11-Month Total .....	1	149	18	9	(s)	19	(s)	(s)	47	461	658
2019 11-Month Total .....	1	168	21	10	(s)	22	(s)	(s)	53	533	756
2018 11-Month Total .....	2	168	20	10	(s)	22	(s)	(s)	52	581	802

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Hydrocarbon gas liquids.

<sup>e</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>f</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 11.6.

<sup>g</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

R=Revised. NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Table 11.4 Carbon Dioxide Emissions From Energy Consumption: Industrial Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Coal Coke Net Imports	Natural Gas <sup>b</sup>	Petroleum									Retail Elec- tricity <sup>g</sup>	Total <sup>h</sup>
				Distillate Fuel Oil <sup>c</sup>	HGL <sup>d</sup>	Kero- sene	Lubri- cants	Motor Gasoline <sup>e</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>f</sup>	Total		
1973 Total .....	371	-1	533	106	31	11	7	18	52	146	99	472	515	1,891
1975 Total .....	335	2	438	97	30	9	6	16	51	119	94	420	490	1,685
1980 Total .....	289	-4	428	96	52	13	7	11	48	106	131	464	601	1,777
1985 Total .....	255	-2	361	81	54	3	6	15	54	59	83	356	583	1,553
1990 Total .....	258	1	436	84	45	1	7	13	67	32	115	364	638	1,697
1995 Total .....	233	7	492	82	57	1	7	14	69	27	107	364	659	1,754
2000 Total .....	211	7	486	87	61	1	7	11	74	19	107	366	719	1,790
2001 Total .....	205	3	444	95	53	2	6	21	79	16	125	397	667	1,717
2002 Total .....	187	7	453	88	54	1	6	22	82	15	122	390	654	1,691
2003 Total .....	189	6	435	85	50	2	6	23	81	17	134	398	672	1,700
2004 Total .....	190	16	438	88	53	2	6	26	92	20	136	423	674	1,741
2005 Total .....	182	5	406	92	49	3	6	25	88	22	135	420	672	1,685
2006 Total .....	180	7	408	91	49	2	6	26	84	19	147	423	650	1,667
2007 Total .....	175	3	419	91	50	1	6	21	81	15	143	409	662	1,667
2008 Total .....	168	5	419	98	41	(s)	6	17	78	15	126	380	642	1,614
2009 Total .....	131	-3	395	78	41	(s)	5	16	72	10	107	330	550	1,403
2010 Total .....	152	-1	427	84	42	1	5	17	68	9	115	341	587	1,507
2011 Total .....	146	1	438	90	38	(s)	5	17	65	10	114	340	574	1,498
2012 Total .....	141	(s)	455	93	42	(s)	4	17	70	5	110	342	543	1,481
2013 Total .....	144	-2	472	92	46	(s)	5	17	65	4	116	345	542	1,501
2014 Total .....	143	-2	488	100	45	(s)	5	14	66	3	108	341	543	1,513
2015 Total .....	129	-2	487	85	49	(s)	5	17	67	3	112	338	502	1,455
2016 Total .....	113	-2	497	84	46	(s)	5	17	66	4	120	343	473	1,424
2017 Total .....	112	-3	510	88	48	(s)	5	18	62	4	126	350	461	1,430
2018 January .....	9	(s)	49	10	5	(s)	(s)	1	5	(s)	11	33	39	129
February .....	9	(s)	44	7	4	(s)	(s)	1	3	(s)	11	26	32	111
March .....	9	(s)	47	9	4	(s)	(s)	2	5	(s)	12	33	34	122
April .....	9	(s)	44	7	4	(s)	(s)	1	5	(s)	9	27	32	113
May .....	9	(s)	43	9	4	(s)	(s)	2	5	(s)	10	30	38	120
June .....	9	(s)	42	6	4	(s)	(s)	2	6	(s)	11	29	40	119
July .....	9	(s)	43	6	5	(s)	(s)	2	5	(s)	10	28	44	125
August .....	9	(s)	44	8	5	(s)	(s)	2	7	(s)	10	33	44	130
September .....	9	(s)	43	7	5	(s)	(s)	1	7	(s)	8	29	40	121
October .....	9	(s)	45	9	5	(s)	(s)	2	7	(s)	11	34	38	126
November .....	9	(s)	47	7	5	(s)	(s)	1	4	(s)	10	29	38	124
December .....	10	(s)	49	5	5	(s)	(s)	1	4	(s)	10	26	37	122
Total .....	110	-3	541	92	54	(s)	5	18	64	3	123	358	457	1,464
2019 January .....	9	(s)	51	10	6	(s)	(s)	1	5	(s)	11	34	38	131
February .....	9	(s)	46	R 8	5	(s)	(s)	1	1	(s)	7	24	33	111
March .....	9	(s)	48	R 8	4	(s)	(s)	1	5	(s)	10	30	34	R 121
April .....	8	(s)	44	8	4	(s)	(s)	1	4	(s)	11	R 29	30	112
May .....	9	(s)	45	8	4	(s)	(s)	2	5	(s)	R 31	34	119	
June .....	9	(s)	42	R 6	5	(s)	(s)	2	7	(s)	10	30	36	117
July .....	8	(s)	43	6	5	(s)	(s)	2	7	(s)	10	30	42	123
August .....	9	(s)	45	6	5	(s)	(s)	2	6	(s)	12	31	41	125
September .....	8	(s)	43	7	6	(s)	(s)	1	4	(s)	R 29	37	118	
October .....	9	(s)	45	9	5	(s)	(s)	R 1	4	(s)	11	32	33	119
November .....	8	(s)	48	R 7	5	(s)	(s)	1	6	(s)	R 31	34	122	
December .....	9	(s)	51	R 5	5	(s)	(s)	1	6	(s)	11	31	32	122
Total .....	104	-2	551	R 88	60	(s)	4	18	61	3	127	R 361	425	R 1,440
2020 January .....	8	(s)	51	9	4	(s)	(s)	1	4	(s)	11	30	30	R 119
February .....	8	(s)	47	R 8	4	(s)	(s)	1	4	(s)	12	30	28	R 113
March .....	8	(s)	47	R 7	5	(s)	(s)	1	4	(s)	12	30	28	113
April .....	7	(s)	43	3	3	(s)	(s)	1	3	(s)	10	R 20	23	93
May .....	6	(s)	42	R 2	4	(s)	(s)	1	4	(s)	11	23	25	96
June .....	7	(s)	40	2	4	(s)	(s)	1	3	(s)	9	21	30	98
July .....	7	(s)	43	R 3	5	(s)	(s)	1	4	(s)	9	24	36	R 109
August .....	7	(s)	43	4	5	(s)	(s)	1	6	(s)	10	R 27	37	115
September .....	7	(s)	43	R 5	5	(s)	(s)	1	5	(s)	8	26	31	R 106
October .....	8	(s)	46	7	6	(s)	(s)	1	4	(s)	R 27	32	R 112	
November .....	7	(s)	46	6	6	(s)	(s)	1	5	(s)	9	29	30	111
11-Month Total ...	80	-1	491	58	53	(s)	4	14	47	2	108	286	331	1,186
2019 11-Month Total ...	96	-2	501	83	55	(s)	4	16	54	3	115	331	392	1,317
2018 11-Month Total ...	101	-3	492	86	50	(s)	4	16	59	3	113	332	419	1,341

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Hydrocarbon gas liquids.

<sup>e</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>f</sup> Aviation gasoline blending components, crude oil, motor gasoline blending components, petrochemical feedstocks, special naphthas, still gas, unfinished oils, waxes, and miscellaneous petroleum products.

<sup>g</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 11.6.

<sup>h</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

R=Revised. (s)=Less than 0.5 million metric tons and greater than -0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption, plus the relatively small amount of emissions from the non-combustion use of fossil fuels. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Table 11.5 Carbon Dioxide Emissions From Energy Consumption: Transportation Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum							Retail Elec- tricity <sup>i</sup>	Total <sup>g</sup>	
			Aviation Gasoline	Distillate Fuel Oil <sup>c</sup>	HGL <sup>d</sup>	Jet Fuel	Lubri- cants	Motor Gasoline <sup>e</sup>	Residual Fuel Oil			Total
1973 Total .....	(s)	39	6	163	3	152	6	886	57	1,273	2	1,315
1975 Total .....	(s)	32	5	155	3	145	6	889	56	1,258	2	1,292
1980 Total .....	(h)	34	4	204	1	155	6	881	110	1,363	2	1,400
1985 Total .....	(h)	28	3	232	2	178	6	908	62	1,391	3	1,421
1990 Total .....	(h)	36	3	268	1	223	7	967	80	1,548	3	1,588
1995 Total .....	(h)	38	3	307	1	222	6	1,026	72	1,637	3	1,679
2000 Total .....	(h)	36	3	377	1	254	7	1,119	70	1,830	4	1,870
2001 Total .....	(h)	35	2	387	1	243	6	1,125	46	1,810	4	1,849
2002 Total .....	(h)	37	2	394	1	237	6	1,156	53	1,849	4	1,890
2003 Total .....	(h)	33	2	408	1	231	6	1,159	45	1,853	5	1,891
2004 Total .....	(h)	32	2	433	1	240	6	1,180	58	1,921	5	1,957
2005 Total .....	(h)	33	2	444	2	246	6	1,180	66	1,946	5	1,984
2006 Total .....	(h)	33	2	467	2	240	5	1,187	71	1,974	5	2,012
2007 Total .....	(h)	35	2	469	1	238	6	1,183	78	1,977	5	2,018
2008 Total .....	(h)	37	2	424	3	226	5	1,119	73	1,852	5	1,893
2009 Total .....	(h)	38	2	400	2	204	5	1,107	62	1,782	5	1,825
2010 Total .....	(h)	38	2	423	(s)	210	6	1,089	70	1,800	5	1,843
2011 Total .....	(h)	39	2	431	(s)	209	6	1,057	61	1,766	4	1,809
2012 Total .....	(h)	41	2	411	(s)	206	5	1,051	53	1,728	4	1,773
2013 Total .....	(h)	47	2	416	(s)	210	5	1,066	46	1,745	4	1,796
2014 Total .....	(h)	40	2	435	(s)	216	6	1,077	35	1,770	4	1,815
2015 Total .....	(h)	40	1	441	(s)	227	6	1,083	37	1,795	4	1,839
2016 Total .....	(h)	40	1	431	(s)	237	6	1,102	49	1,827	4	1,871
2017 Total .....	(h)	42	1	436	(s)	247	5	1,099	52	1,842	4	1,888
2018 January .....	(h)	6	(s)	36	(s)	20	(s)	88	3	146	(s)	152
February .....	(h)	5	(s)	32	(s)	18	(s)	80	4	134	(s)	139
March .....	(h)	5	(s)	38	(s)	21	(s)	95	3	158	(s)	163
April .....	(h)	4	(s)	38	(s)	20	(s)	89	5	153	(s)	157
May .....	(h)	3	(s)	41	(s)	21	(s)	95	4	161	(s)	165
June .....	(h)	3	(s)	39	(s)	22	(s)	95	3	161	(s)	165
July .....	(h)	4	(s)	41	(s)	22	(s)	96	5	165	(s)	169
August .....	(h)	4	(s)	43	(s)	23	(s)	98	4	168	(s)	172
September .....	(h)	4	(s)	39	(s)	21	(s)	89	4	153	(s)	157
October .....	(h)	4	(s)	41	(s)	21	(s)	93	3	158	(s)	163
November .....	(h)	5	(s)	37	(s)	21	(s)	90	4	153	(s)	158
December .....	(h)	5	(s)	36	(s)	21	(s)	92	5	154	(s)	159
Total .....	(h)	51	2	460	(s)	250	5	1,099	48	1,864	4	1,919
2019 January .....	(h)	6	(s)	36	(s)	20	(s)	88	4	149	(s)	155
February .....	(h)	5	(s)	R 34	(s)	18	(s)	82	3	R 137	(s)	R 143
March .....	(h)	5	(s)	R 38	(s)	21	(s)	92	3	R 155	(s)	160
April .....	(h)	4	(s)	38	(s)	21	1	91	2	R 154	(s)	R 158
May .....	(h)	4	(s)	R 41	(s)	22	(s)	95	2	160	(s)	164
June .....	(h)	4	(s)	R 40	(s)	22	(s)	94	4	R 160	(s)	R 164
July .....	(h)	4	(s)	R 41	(s)	23	(s)	95	4	164	(s)	R 169
August .....	(h)	4	(s)	41	(s)	23	(s)	99	4	R 168	(s)	172
September .....	(h)	4	(s)	R 39	(s)	21	(s)	89	4	R 153	(s)	157
October .....	(h)	4	(s)	41	(s)	22	(s)	93	4	160	(s)	R 165
November .....	(h)	5	(s)	37	(s)	21	(s)	89	3	R 150	(s)	155
December .....	(h)	6	(s)	36	(s)	23	(s)	89	4	152	(s)	158
Total .....	(h)	55	2	R 462	(s)	256	5	1,095	42	R 1,862	3	R 1,920
2020 January .....	(h)	6	(s)	35	(s)	21	(s)	87	3	R 148	(s)	R 154
February .....	(h)	5	(s)	33	(s)	19	(s)	84	2	R 139	(s)	144
March .....	(h)	5	(s)	37	(s)	17	(s)	78	1	134	(s)	139
April .....	(h)	4	(s)	35	(s)	8	(s)	57	1	102	(s)	R 107
May .....	(h)	4	(s)	37	(s)	7	(s)	72	1	117	(s)	121
June .....	(h)	4	(s)	37	(s)	9	(s)	80	3	R 130	(s)	R 134
July .....	(h)	4	(s)	39	(s)	12	(s)	84	R 4	141	(s)	R 146
August .....	(h)	4	(s)	40	(s)	13	(s)	85	4	142	(s)	R 147
September .....	(h)	4	(s)	R 38	(s)	11	(s)	83	4	136	(s)	140
October .....	(h)	4	(s)	R 40	(s)	13	(s)	83	4	139	(s)	R 144
November .....	(h)	4	(s)	37	(s)	14	(s)	77	3	130	(s)	135
11-Month Total .....	(h)	49	1	409	(s)	144	4	870	30	1,459	2	1,510
2019 11-Month Total .....	(h)	49	2	426	(s)	233	5	1,006	38	1,710	3	1,762
2018 11-Month Total .....	(h)	46	1	424	(s)	230	5	1,007	43	1,710	3	1,759

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Hydrocarbon gas liquids.

<sup>e</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>f</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 11.6.

<sup>g</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

<sup>h</sup> Beginning in 1978, the small amounts of coal consumed for transportation are reported as industrial sector consumption.

R=Revised. (s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption, plus the relatively small amount of emissions from the non-combustion use of fossil fuels. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973. Sources: See end of section.

**Table 11.6 Carbon Dioxide Emissions From Energy Consumption: Electric Power Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum				Geo-thermal	Non-Biomass Waste <sup>d</sup>	Total <sup>e</sup>
			Distillate Fuel Oil <sup>c</sup>	Petroleum Coke	Residual Fuel Oil	Total			
<b>1973 Total</b> .....	<b>812</b>	<b>199</b>	<b>20</b>	<b>2</b>	<b>254</b>	<b>276</b>	<b>NA</b>	<b>NA</b>	<b>1,286</b>
<b>1975 Total</b> .....	<b>824</b>	<b>172</b>	<b>17</b>	<b>(s)</b>	<b>231</b>	<b>248</b>	<b>NA</b>	<b>NA</b>	<b>1,244</b>
<b>1980 Total</b> .....	<b>1,137</b>	<b>200</b>	<b>12</b>	<b>1</b>	<b>194</b>	<b>207</b>	<b>NA</b>	<b>NA</b>	<b>1,544</b>
<b>1985 Total</b> .....	<b>1,367</b>	<b>166</b>	<b>6</b>	<b>1</b>	<b>79</b>	<b>86</b>	<b>NA</b>	<b>NA</b>	<b>1,619</b>
<b>1990 Total</b> .....	<b>1,548</b>	<b>176</b>	<b>7</b>	<b>3</b>	<b>92</b>	<b>102</b>	<b>(s)</b>	<b>6</b>	<b>1,831</b>
<b>1995 Total</b> .....	<b>1,661</b>	<b>228</b>	<b>8</b>	<b>8</b>	<b>45</b>	<b>61</b>	<b>(s)</b>	<b>10</b>	<b>1,960</b>
<b>2000 Total</b> .....	<b>1,927</b>	<b>281</b>	<b>13</b>	<b>10</b>	<b>69</b>	<b>91</b>	<b>(s)</b>	<b>10</b>	<b>2,310</b>
<b>2001 Total</b> .....	<b>1,870</b>	<b>290</b>	<b>12</b>	<b>11</b>	<b>79</b>	<b>102</b>	<b>(s)</b>	<b>11</b>	<b>2,273</b>
<b>2002 Total</b> .....	<b>1,890</b>	<b>306</b>	<b>9</b>	<b>18</b>	<b>52</b>	<b>79</b>	<b>(s)</b>	<b>13</b>	<b>2,288</b>
<b>2003 Total</b> .....	<b>1,931</b>	<b>278</b>	<b>12</b>	<b>18</b>	<b>69</b>	<b>98</b>	<b>(s)</b>	<b>11</b>	<b>2,319</b>
<b>2004 Total</b> .....	<b>1,943</b>	<b>297</b>	<b>8</b>	<b>22</b>	<b>69</b>	<b>99</b>	<b>(s)</b>	<b>11</b>	<b>2,350</b>
<b>2005 Total</b> .....	<b>1,984</b>	<b>319</b>	<b>8</b>	<b>24</b>	<b>69</b>	<b>101</b>	<b>(s)</b>	<b>11</b>	<b>2,416</b>
<b>2006 Total</b> .....	<b>1,954</b>	<b>338</b>	<b>5</b>	<b>21</b>	<b>28</b>	<b>55</b>	<b>(s)</b>	<b>12</b>	<b>2,358</b>
<b>2007 Total</b> .....	<b>1,987</b>	<b>372</b>	<b>6</b>	<b>17</b>	<b>31</b>	<b>54</b>	<b>(s)</b>	<b>11</b>	<b>2,425</b>
<b>2008 Total</b> .....	<b>1,959</b>	<b>362</b>	<b>5</b>	<b>15</b>	<b>19</b>	<b>39</b>	<b>(s)</b>	<b>12</b>	<b>2,373</b>
<b>2009 Total</b> .....	<b>1,741</b>	<b>373</b>	<b>5</b>	<b>13</b>	<b>14</b>	<b>33</b>	<b>(s)</b>	<b>11</b>	<b>2,158</b>
<b>2010 Total</b> .....	<b>1,828</b>	<b>399</b>	<b>6</b>	<b>14</b>	<b>12</b>	<b>32</b>	<b>(s)</b>	<b>11</b>	<b>2,270</b>
<b>2011 Total</b> .....	<b>1,723</b>	<b>409</b>	<b>5</b>	<b>14</b>	<b>7</b>	<b>26</b>	<b>(s)</b>	<b>11</b>	<b>2,170</b>
<b>2012 Total</b> .....	<b>1,511</b>	<b>493</b>	<b>4</b>	<b>9</b>	<b>6</b>	<b>19</b>	<b>(s)</b>	<b>11</b>	<b>2,034</b>
<b>2013 Total</b> .....	<b>1,571</b>	<b>444</b>	<b>4</b>	<b>13</b>	<b>6</b>	<b>23</b>	<b>(s)</b>	<b>11</b>	<b>2,050</b>
<b>2014 Total</b> .....	<b>1,569</b>	<b>444</b>	<b>6</b>	<b>12</b>	<b>7</b>	<b>26</b>	<b>(s)</b>	<b>11</b>	<b>2,050</b>
<b>2015 Total</b> .....	<b>1,350</b>	<b>527</b>	<b>5</b>	<b>11</b>	<b>7</b>	<b>24</b>	<b>(s)</b>	<b>11</b>	<b>1,913</b>
<b>2016 Total</b> .....	<b>1,241</b>	<b>547</b>	<b>4</b>	<b>12</b>	<b>6</b>	<b>22</b>	<b>(s)</b>	<b>11</b>	<b>1,821</b>
<b>2017 Total</b> .....	<b>1,206</b>	<b>507</b>	<b>4</b>	<b>10</b>	<b>5</b>	<b>19</b>	<b>(s)</b>	<b>11</b>	<b>1,743</b>
<b>2018 January</b> .....	<b>117</b>	<b>43</b>	<b>2</b>	<b>1</b>	<b>2</b>	<b>5</b>	<b>(s)</b>	<b>1</b>	<b>166</b>
<b>February</b> .....	<b>83</b>	<b>38</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>123</b>
<b>March</b> .....	<b>81</b>	<b>41</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>124</b>
<b>April</b> .....	<b>73</b>	<b>38</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>114</b>
<b>May</b> .....	<b>86</b>	<b>46</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>134</b>
<b>June</b> .....	<b>101</b>	<b>52</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>156</b>
<b>July</b> .....	<b>115</b>	<b>67</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>185</b>
<b>August</b> .....	<b>115</b>	<b>65</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>183</b>
<b>September</b> .....	<b>98</b>	<b>56</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>156</b>
<b>October</b> .....	<b>88</b>	<b>49</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>138</b>
<b>November</b> .....	<b>94</b>	<b>42</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>138</b>
<b>December</b> .....	<b>101</b>	<b>42</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>145</b>
<b>Total</b> .....	<b>1,151</b>	<b>579</b>	<b>6</b>	<b>10</b>	<b>6</b>	<b>22</b>	<b>(s)</b>	<b>11</b>	<b>1,764</b>
<b>2019 January</b> .....	<b>101</b>	<b>46</b>	<b>(s)</b>	<b>1</b>	<b>1</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>150</b>
<b>February</b> .....	<b>81</b>	<b>43</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>126</b>
<b>March</b> .....	<b>80</b>	<b>45</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>126</b>
<b>April</b> .....	<b>60</b>	<b>40</b>	<b>(s)</b>	<b>(s)</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>103</b>
<b>May</b> .....	<b>72</b>	<b>46</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>121</b>
<b>June</b> .....	<b>80</b>	<b>54</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>136</b>
<b>July</b> .....	<b>101</b>	<b>69</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>172</b>
<b>August</b> .....	<b>95</b>	<b>70</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>167</b>
<b>September</b> .....	<b>85</b>	<b>59</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>147</b>
<b>October</b> .....	<b>68</b>	<b>51</b>	<b>(s)</b>	<b>(s)</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>121</b>
<b>November</b> .....	<b>76</b>	<b>45</b>	<b>(s)</b>	<b>(s)</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>123</b>
<b>December</b> .....	<b>73</b>	<b>50</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>125</b>
<b>Total</b> .....	<b>973</b>	<b>618</b>	<b>4</b>	<b>8</b>	<b>5</b>	<b>16</b>	<b>(s)</b>	<b>11</b>	<b>1,618</b>
<b>2020 January</b> .....	<b>66</b>	<b>51</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>120</b>
<b>February</b> .....	<b>58</b>	<b>48</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>108</b>
<b>March</b> .....	<b>52</b>	<b>48</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>103</b>
<b>April</b> .....	<b>43</b>	<b>42</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>86</b>
<b>May</b> .....	<b>49</b>	<b>46</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>96</b>
<b>June</b> .....	<b>66</b>	<b>57</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>126</b>
<b>July</b> .....	<b>90</b>	<b>75</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>168</b>
<b>August</b> .....	<b>91</b>	<b>70</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>164</b>
<b>September</b> .....	<b>70</b>	<b>57</b>	<b>(s)</b>	<b>(s)</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>129</b>
<b>October</b> .....	<b>61</b>	<b>52</b>	<b>(s)</b>	<b>(s)</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>115</b>
<b>November</b> .....	<b>62</b>	<b>42</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>106</b>
<b>11-Month Total</b> .....	<b>709</b>	<b>588</b>	<b>3</b>	<b>8</b>	<b>4</b>	<b>14</b>	<b>(s)</b>	<b>10</b>	<b>1,321</b>
<b>2019 11-Month Total</b> .....	<b>899</b>	<b>568</b>	<b>4</b>	<b>7</b>	<b>4</b>	<b>15</b>	<b>(s)</b>	<b>10</b>	<b>1,492</b>
<b>2018 11-Month Total</b> .....	<b>1,051</b>	<b>537</b>	<b>6</b>	<b>9</b>	<b>6</b>	<b>21</b>	<b>(s)</b>	<b>10</b>	<b>1,619</b>

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Municipal solid waste from non-biogenic sources, and tire-derived fuels. Through 1994, also includes blast furnace gas, and other manufactured and waste gases derived from fossil fuels.

<sup>e</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy

consumption. See "Section 11 Methodology and Sources" at end of section.

• See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment>

(Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.



**Table 11.7 Carbon Dioxide Emissions From Biomass Energy Consumption**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	By Source					By Sector					
	Wood <sup>b</sup>	Biomass Waste <sup>c</sup>	Fuel Ethanol <sup>d</sup>	Bio-diesel	Total	Residential	Commercial <sup>e</sup>	Industrial <sup>f</sup>	Transportation	Electric Power <sup>g</sup>	Total
<b>1973 Total</b> .....	143	(s)	NA	NA	143	33	1	109	NA	(s)	143
<b>1975 Total</b> .....	140	(s)	NA	NA	141	40	1	100	NA	(s)	141
<b>1980 Total</b> .....	232	(s)	NA	NA	232	80	2	150	NA	(s)	232
<b>1985 Total</b> .....	252	14	3	NA	270	95	2	168	3	1	270
<b>1990 Total</b> .....	208	24	4	NA	237	54	8	147	4	23	237
<b>1995 Total</b> .....	222	30	8	NA	260	49	9	166	8	28	260
<b>2000 Total</b> .....	212	27	9	NA	248	39	9	161	9	29	248
<b>2001 Total</b> .....	188	33	10	(s)	231	35	9	147	10	31	231
<b>2002 Total</b> .....	187	36	12	(s)	235	36	9	144	12	35	235
<b>2003 Total</b> .....	188	36	16	(s)	240	38	9	141	16	37	240
<b>2004 Total</b> .....	199	35	20	(s)	255	38	10	151	20	36	255
<b>2005 Total</b> .....	200	37	23	1	261	40	10	150	23	37	261
<b>2006 Total</b> .....	197	36	31	2	266	36	9	151	33	38	266
<b>2007 Total</b> .....	196	37	39	3	276	39	9	146	41	39	276
<b>2008 Total</b> .....	193	39	55	3	290	44	10	139	57	40	290
<b>2009 Total</b> .....	182	41	62	3	288	47	10	125	64	41	288
<b>2010 Total</b> .....	208	42	73	2	325	51	10	149	74	42	325
<b>2011 Total</b> .....	208	42	73	8	331	49	11	151	80	40	331
<b>2012 Total</b> .....	202	42	73	8	325	41	10	153	80	42	325
<b>2013 Total</b> .....	219	45	75	13	353	54	11	158	87	43	353
<b>2014 Total</b> .....	225	47	76	13	361	54	12	158	88	49	361
<b>2015 Total</b> .....	217	47	79	14	357	48	13	157	90	48	357
<b>2016 Total</b> .....	209	46	81	20	355	R 42	14	155	98	47	355
<b>2017 Total</b> .....	205	45	82	19	R 351	40	14	152	98	47	R 351
<b>2018 January</b> .....	R 19	4	7	1	30	4	1	13	8	4	30
February .....	17	4	6	1	27	4	1	12	7	4	27
March .....	18	4	7	1	30	4	1	13	8	4	30
April .....	17	4	6	1	R 29	4	1	12	8	4	R 29
May .....	18	4	7	2	30	4	1	13	9	4	30
June .....	R 18	4	7	2	30	4	1	12	8	4	30
July .....	18	4	7	2	31	4	1	13	9	4	31
August .....	18	4	7	2	31	4	1	13	9	4	31
September .....	17	3	6	2	28	4	1	12	8	3	28
October .....	18	4	7	2	30	4	1	13	8	4	30
November .....	17	4	7	1	29	4	1	12	8	4	29
December .....	18	4	7	2	31	4	1	13	8	4	31
<b>Total</b> .....	R 213	44	82	18	R 357	49	14	151	97	46	R 357
<b>2019 January</b> .....	18	4	6	1	R 30	4	1	13	7	4	R 30
February .....	R 17	3	6	1	27	4	1	12	7	3	27
March .....	18	3	7	1	R 30	4	1	13	8	3	R 30
April .....	17	3	7	1	28	4	1	12	8	3	28
May .....	17	3	7	2	R 30	4	1	12	9	3	R 30
June .....	17	3	7	1	29	4	1	12	8	3	29
July .....	18	3	7	2	30	4	1	13	8	4	30
August .....	18	3	7	2	30	4	1	13	8	4	30
September .....	17	3	7	1	28	4	1	12	8	3	28
October .....	17	3	7	1	29	4	1	12	8	3	29
November .....	17	3	7	1	29	4	1	12	8	3	29
December .....	18	4	7	1	30	4	1	13	8	4	30
<b>Total</b> .....	R 210	40	83	17	R 350	R 51	13	148	97	41	R 350
<b>2020 January</b> .....	17	4	7	1	29	4	1	13	8	4	29
February .....	16	3	6	1	27	R 3	1	12	7	3	27
March .....	17	3	6	1	27	4	1	12	7	3	27
April .....	16	3	4	1	R 24	4	1	12	5	3	R 24
May .....	17	3	6	1	27	4	1	12	7	3	27
June .....	16	3	6	1	R 26	4	1	11	7	3	R 26
July .....	R 16	3	6	2	28	4	1	12	8	3	28
August .....	17	3	6	2	28	4	1	12	8	4	28
September .....	16	3	6	2	27	4	1	12	8	3	27
October .....	R 16	3	6	2	27	4	1	12	7	3	27
November .....	16	3	6	1	27	4	1	12	7	3	27
<b>11-Month Total</b> .....	180	36	65	16	297	39	11	132	79	36	297
<b>2019 11-Month Total</b> .....	192	37	76	16	320	47	12	135	88	38	320
<b>2018 11-Month Total</b> .....	194	40	75	16	326	45	13	138	89	42	326

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Wood and wood-derived fuels.

<sup>c</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass.

<sup>d</sup> Fuel ethanol minus denaturant.

<sup>e</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>f</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>g</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

R=Revised. NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Carbon dioxide emissions from biomass energy consumption are excluded from the energy-related carbon dioxide emissions reported in Tables 11.1–11.6. See Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Data are estimates. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment>

(Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Note 1. Emissions of Carbon Dioxide and Other Greenhouse Gases.** Greenhouse gases are those gases—such as water vapor, carbon dioxide (CO<sub>2</sub>), methane, nitrous oxide, hydrofluorocarbons (HFCs), perfluorocarbons (PFCs), and sulfur hexafluoride—that are transparent to solar (short-wave) radiation but opaque to long-wave (infrared) radiation, thus preventing long-wave radiant energy from leaving Earth's atmosphere. The net effect is a trapping of absorbed radiation and a tendency to warm the planet's surface.

The vast majority of U.S. CO<sub>2</sub> emissions come from fossil fuel combustion, with smaller amounts from the non-combustion use of fossil fuels, as well as from electricity generation using geothermal energy and non-biomass waste. Other sources of CO<sub>2</sub> emissions include industrial processes, such as cement and limestone production. Data in the U.S. Energy Information Administration's (EIA) *Monthly Energy Review* (MER) Tables 11.1–11.6 are estimates for U.S. CO<sub>2</sub> emissions from energy consumption, plus the non-combustion use of fossil fuels (excluded are estimates for CO<sub>2</sub> emissions from biomass energy consumption, which appear in MER Table 11.7).

For annual U.S. estimates of CO<sub>2</sub> emissions from all sources, as well as emissions for other greenhouse gases, see the U.S. Environmental Protection Agency's *Inventory of U.S. Greenhouse Gas Emissions and Sinks* reports at <https://www.epa.gov/ghgemissions/inventory-us-greenhouse-gas-emissions-and-sinks>.

**Note 2. Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion.** Carbon dioxide (CO<sub>2</sub>) emissions from the combustion of biomass to produce energy are excluded from the energy-related CO<sub>2</sub> emissions reported in MER Tables 11.1–11.6, but appear in MER Table 11.7. According to current international convention (see the Intergovernmental Panel on Climate Change's "2006 IPCC Guidelines for National Greenhouse Gas Inventories"), carbon released through biomass combustion is excluded from reported energy-related emissions. The release of carbon from biomass combustion is assumed to be balanced by the uptake of carbon when the feedstock is grown, resulting in zero net emissions over some period of time. (This is not to say that biomass energy is carbon-neutral. Energy inputs are required in order to grow, fertilize, and harvest the feedstock and to produce and process the biomass into fuels.)

However, analysts have debated whether increased use of biomass energy may result in a decline in terrestrial carbon stocks, leading to a net positive release of carbon rather than the zero net release assumed by its exclusion from reported energy-related emissions. For example, the clearing of forests for biofuel crops could result in an initial release of carbon that is not fully recaptured in subsequent use of the land for agriculture.

To reflect the potential net emissions, the international convention for greenhouse gas inventories is to report biomass emissions in the category "agriculture, forestry, and other land use," usually based on estimates of net changes in carbon stocks over time.

This indirect accounting of CO<sub>2</sub> emissions from biomass can potentially lead to confusion in accounting for and understanding the flow of CO<sub>2</sub> emissions within energy and non-energy systems. In recognition of this issue, reporting of CO<sub>2</sub> emissions from biomass combustion alongside other energy-related CO<sub>2</sub> emissions offers an alternative accounting treatment. It is important, however, to avoid misinterpreting emissions from fossil energy and biomass energy sources as necessarily additive. Instead, the combined total of direct CO<sub>2</sub> emissions from biomass and energy-related CO<sub>2</sub> emissions implicitly assumes that none of the carbon emitted was previously or subsequently reabsorbed in terrestrial sinks or that other emissions sources offset any such sequestration.

## Section 11 Methodology and Sources

To estimate carbon dioxide emissions from energy consumption for the *Monthly Energy Review* (MER), Tables 11.1–11.7, the U.S. Energy Information Administration (EIA) uses the following methodology and sources:

### *Step 1. Determine Fuel Consumption*

Coal—Coal sectoral (residential, commercial, coke plants, other industrial, transportation, electric power) consumption data in thousand short tons are from MER Table 6.2. Coal sectoral consumption data are converted to trillion Btu by multiplying by the coal heat content factors in MER Table A5.

Coal Coke Net Imports—Coal coke net imports data in trillion Btu are derived from coal coke imports and exports data in MER Tables 1.4a and 1.4b.

Natural Gas (excluding supplemental gaseous fuels)—Natural gas sectoral consumption data in trillion Btu are from MER Tables 2.2–2.6.

Petroleum—Total and sectoral consumption (product supplied) data in thousand barrels per day for asphalt and road oil, aviation gasoline, distillate fuel oil, hydrocarbon gas liquids (HGL), jet fuel, kerosene, lubricants, motor gasoline, petroleum coke, and residual fuel oil are from MER Tables 3.5 and 3.7a–3.7c. For the component products of HGL (ethane/ethylene, propane/propylene, normal butane/butylene, isobutane/isobutylene, and natural gasoline) and "other petroleum" (aviation gasoline blending components, crude oil, motor gasoline blending components, naphthas for petrochemical feedstock use, other oils for petrochemical feedstock use, special naphthas, still gas, unfinished oils, waxes, and miscellaneous petroleum products), consumption (product supplied) data in thousand barrels per day are from EIA's *Petroleum Supply Annual* (PSA), *Petroleum Supply Monthly* (PSM), and earlier publications (see sources for MER Table 3.5). Petroleum consumption data by product are converted to trillion Btu by multiplying by the petroleum heat content factors in MER Tables A1 and A3.

Biomass—Sectoral consumption data in trillion Btu for wood, biomass waste, fuel ethanol (minus denaturant), and biodiesel are from MER Tables 10.2a–10.2c.

### ***Step 2. Remove Biofuels From Petroleum***

Distillate Fuel Oil—Beginning in 2009, the distillate fuel oil data (for total and transportation sector) in Step 1 include biodiesel and other renewable diesel fuel, which are non-fossil renewable fuels.

2009–2011: To remove the biodiesel portion from distillate fuel oil, data for biodiesel consumption (calculated using data from EIA, EIA-22M, "Monthly Biodiesel Production Survey") and biomass-based diesel fuel data (from EIA-810, "Monthly Refinery Report," EIA-812, "Monthly Product Pipeline Report," and EIA-815, "Monthly Bulk Terminal and Blender Report") are converted to trillion Btu by multiplying by the biodiesel heat content factor in MER Table A1, and then subtracted from the distillate fuel oil consumption values. To remove the other renewable diesel fuel portion from distillate fuel oil, data for refinery and blender net inputs (from EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report") are converted to trillion Btu by multiplying by the other renewable diesel fuel heat content factor in MER Table A1, and then subtracted from the distillate fuel oil consumption values.

2012 forward: To remove the biodiesel portion from distillate fuel oil, data for biodiesel consumption (from MER Table 10.4) is subtracted from the distillate fuel oil consumption values. To remove the other renewable diesel fuel portion from distillate fuel oil, data for refinery and blender net inputs (from EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report") are converted to trillion Btu by multiplying by the other renewable diesel fuel heat content factor in MER Table A1, and then subtracted from the distillate fuel oil consumption values.

Motor Gasoline—Beginning in 1993, the motor gasoline data (for total, commercial sector, industrial sector, and transportation sector) in Step 1 include fuel ethanol, a non-fossil renewable fuel. To remove the fuel ethanol portion from motor gasoline, data in trillion Btu for fuel ethanol consumption (from MER Tables 10.2a, 10.2b, and 10.3) are subtracted from the motor gasoline consumption values. (Note that about 2% of fuel ethanol is fossil-based petroleum denaturant, to make the fuel ethanol undrinkable. For 1993–2008, petroleum denaturant is double counted in the PSA product supplied statistics, in both the original product category—e.g., natural gasoline—and also in the finished motor gasoline category; for this time period for MER Section 11, petroleum denaturant is removed along with the fuel ethanol from motor gasoline, but left in the original product. Beginning in 2009, petroleum denaturant is counted only in the PSA/PSM product supplied statistics for motor gasoline; for this time period for MER Section 11, petroleum denaturant is left in motor gasoline.)

### ***Step 3. Remove Carbon Sequestered by Non-Combustion Use***

The following fuels have industrial non-combustion uses as chemical feedstocks and other products: coal, natural gas, asphalt and road oil, distillate fuel oil, hydrocarbon gas liquids (ethane/ethylene, propane/propylene, normal butane/butylene, isobutane/isobutylene, and natural gasoline), lubricants (which have industrial and transportation non-combustion uses), naphthas for petrochemical feedstock use, other oils for petrochemical feedstock use, petroleum coke, residual fuel oil, special naphthas, still gas, waxes, and miscellaneous petroleum products. In the non-combustion use of these fuels, some of the carbon is sequestered, and is thus subtracted from the fuel consumption values in Steps 1 and 2.

Estimates of annual non-combustion use and associated carbon sequestration are developed by EIA using the methodology detailed in "Documentation for *Emissions of Greenhouse Gases in the United States 2008*" at [https://www.eia.gov/environment/archive/1605/ggrpt/documentation/pdf/0638\\_2008.pdf](https://www.eia.gov/environment/archive/1605/ggrpt/documentation/pdf/0638_2008.pdf).

To obtain monthly estimates of non-combustion use and associated carbon sequestration, monthly patterns for industrial consumption and product supplied data series are used. For coal non-combustion use, the monthly pattern for coke plants coal consumption from MER Table 6.2 is used. For natural gas, the monthly pattern for other industrial non-CHP natural gas consumption from MER Table 4.3 is used. For distillate fuel oil, petroleum coke, and residual fuel oil, the monthly patterns for industrial consumption from MER Table 3.7b are used. For the other petroleum products, the monthly patterns for product supplied from the PSA and PSM are used. See Tables 1.11a and 1.11b for estimates of fossil fuel non-combustion uses.

### ***Step 4. Determine Carbon Dioxide Emissions From Energy Consumption***

Carbon dioxide (CO<sub>2</sub>) emissions data in million metric tons are calculated by multiplying consumption values in trillion Btu from Steps 1 and 2 (minus the carbon sequestered in non-combustion use in Step 3) by the CO<sub>2</sub> emissions factors at [http://www.eia.gov/environment/archive/1605/ggrpt/excel/CO2\\_coeffs\\_09\\_v2.xls](http://www.eia.gov/environment/archive/1605/ggrpt/excel/CO2_coeffs_09_v2.xls).

Coal—CO<sub>2</sub> emissions for coal are calculated for each sector (residential, commercial, coke plants, other industrial, transportation, electric power). Total coal emissions are the sum of the sectoral coal emissions.

Coal Coke Net Imports—CO<sub>2</sub> emissions for coal coke net imports are calculated.

Natural Gas—CO<sub>2</sub> emissions for natural gas are calculated for each sector (residential, commercial, industrial, transportation, electric power). Total natural gas emissions are the sum of the sectoral natural gas emissions.

Petroleum—CO<sub>2</sub> emissions are calculated for each petroleum product. Total petroleum emissions are the sum of the product emissions. Total HGL emissions are the sum of the emissions for the component products (ethane/ethylene, propane/propylene, normal butane/butylene, isobutane/isobutylene, and natural gasoline); residential, commercial, and transportation sector HGL emissions are estimated by multiplying consumption values in trillion Btu from MER Tables 3.8a and 3.8c by the propane emissions factor; industrial sector HGL emissions are estimated as total HGL emissions minus emissions by the other sectors.

Geothermal and Non-Biomass Waste—Annual CO<sub>2</sub> emissions data for geothermal and non-biomass waste are EIA estimates based on Form EIA-923, "Power Plant Operations Report" (and predecessor forms). Monthly estimates are created by dividing the annual data by the number of days in the year and then multiplying by the number of days in the month. (Annual estimates for the current year are set equal to those of the previous year.)

Biomass—CO<sub>2</sub> emissions for wood, biomass waste, fuel ethanol (minus denaturant), and biodiesel are calculated for each sector. Total emissions for each biomass fuel are the sum of the sectoral emissions. The following factors, in million metric tons CO<sub>2</sub> per quadrillion Btu, are used: wood—93.80; biomass waste—90.70; fuel ethanol—68.44; and biodiesel—73.84. For 1973–1988, the biomass portion of waste in MER Tables 10.2a–10.2c is estimated as 67%; for 1989–2000, the biomass portion of waste is estimated as 67% in 1989 to 58% in 2000, based on the biogenic shares of total municipal solid waste shown in EIA's "Methodology for Allocating Municipal Solid Waste to Biogenic and Non-Biogenic Energy," Table 1 at <http://www.eia.gov/totalenergy/data/monthly/pdf/historical/msw.pdf>.

# Appendix A

## British Thermal Unit Conversion Factors

---

## British Thermal Unit Conversion Factors

The thermal conversion factors presented in the following tables can be used to estimate the heat content in British thermal units (Btu) of a given amount of energy measured in physical units, such as barrels or cubic feet. For example, 10 barrels of asphalt has a heat content of approximately 66.36 million Btu (10 barrels x 6.636 million Btu per barrel = 66.36 million Btu).

The heat content rates (i.e., thermal conversion factors) provided in this section represent the gross (or higher or upper) energy content of the fuels. Gross heat content rates are applied in all Btu calculations for the *Monthly Energy Review* and are commonly used in energy calculations in the United States; net (or lower) heat content rates are typically used in European energy calculations. The difference between the two rates is the amount of energy that is consumed to vaporize water that is created during the combustion process. Generally, the difference ranges from 2% to 10%, depending on the specific fuel and its hydrogen content. Some fuels, such as unseasoned wood, can be more than 40% different in their gross and net heat content rates. See "Heat Content" and "British Thermal Unit (Btu)" in the Glossary for more information.

In general, the annual thermal conversion factors presented in Tables A2 through A6 are computed from final annual data or from the best available data and labeled "preliminary." Often, the current year's factors are labeled "estimate," and are set equal to the previous year's values until data become available to calculate the factors. The source of each factor is described in the section entitled "Thermal Conversion Factor Source Documentation," which follows Table A6 in this appendix.

**Table A1. Approximate Heat Content of Petroleum and Other Liquids**  
(Million Btu per Barrel, Except as Noted)

Commodity	Heat Content	Commodity	Heat Content
Asphalt and Road Oil	6.636	Kerosene	5.670
Aviation Gasoline (Finished)	5.048	Lubricants	6.065
Aviation Gasoline Blending Components	5.048	Motor Gasoline (Finished)—see Tables A2 and A3	
Biodiesel (Biomass-Based Diesel Fuel)	5.359	Motor Gasoline Blending Components (MGBC)	
Crude Oil—see Table A2		Through 2006	5.253
Distillate Fuel Oil—see Table A3 for averages		Beginning in 2007	5.222
15 ppm sulfur and under	5.770	Other Renewable Diesel Fuel	5.494
Greater than 15 ppm to 500 ppm sulfur	5.817	Other Renewable Fuels	5.359
Greater than 500 ppm sulfur	5.825	Oxygenates (excluding Fuel Ethanol)	4.247
Fuel Ethanol—see Table A3		Petrochemical Feedstocks	
Hydrocarbon Gas Liquids		Naphtha Less Than 401°F	5.248
Natural Gas Liquids		Other Oils Equal to or Greater Than 401°F	5.825
Ethane	2.783	Petroleum Coke—see Table A3 for averages	
Propane	3.841	Total, through 2003	6.024
Normal Butane	4.353	Catalyst, beginning in 2004	<sup>a</sup> 6.287
Isobutane	4.183	Marketable, beginning in 2004	5.719
Natural Gasoline (Pentanes Plus)	4.638	Residual Fuel Oil	6.287
Refinery Olefins		Special Naphthas	5.248
Ethylene	2.436	Still Gas	
Propylene	3.835	Through 2015	<sup>b</sup> 6.000
Butylene	4.377	Beginning in 2016	<sup>a</sup> 6.287
Isobutylene	4.355	Unfinished Oils	5.825
Hydrogen	<sup>c</sup> 6.287	Waxes	5.537
Jet Fuel, Kerosene Type	5.670	Miscellaneous Products	5.796
Jet Fuel, Naphtha Type	5.355	Other Hydrocarbons	5.825

<sup>a</sup> Per residual fuel oil equivalent barrel (6.287 million Btu per barrel).

<sup>b</sup> Per fuel oil equivalent barrel (6.000 million Btu per barrel).

<sup>c</sup> Hydrogen has a gross heat content of 323.6 Btu per standard cubic foot (at 60 degrees Fahrenheit and 1 atmosphere), and 6.287 million Btu per residual fuel oil equivalent barrel. For hydrogen, barrels can be converted to standard cubic feet by multiplying by 19,426 standard cubic feet per barrel of residual fuel oil equivalent.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A2. Approximate Heat Content of Petroleum Production, Imports, and Exports**  
(Million Btu per Barrel)

	Production		Imports				Exports			
			Crude Oil <sup>a</sup>	Petroleum Products		Total <sup>d</sup>	Crude Oil <sup>a</sup>	Petroleum Products		Total <sup>d</sup>
	Crude Oil <sup>a</sup>	Natural Gas Plant Liquids <sup>b</sup>		Motor Gasoline <sup>c</sup>	Total Products <sup>d</sup>			Motor Gasoline <sup>e</sup>	Total Products <sup>d</sup>	
1950 .....	5.800	4.470	5.943	5.253	6.263	6.080	5.800	5.253	5.751	5.766
1955 .....	5.800	4.346	5.924	5.253	6.234	6.040	5.800	5.253	5.765	5.768
1960 .....	5.800	4.253	5.911	5.253	6.161	6.021	5.800	5.253	5.835	5.834
1965 .....	5.800	4.197	5.872	5.253	6.123	5.997	5.800	5.253	5.742	5.743
1970 .....	5.800	4.090	5.822	5.253	6.088	5.985	5.800	5.253	5.811	5.810
1975 .....	5.800	3.923	5.821	5.253	5.935	5.858	5.800	5.253	5.747	5.748
1980 .....	5.800	<sup>b</sup> 3.864	5.812	5.253	5.748	5.796	5.800	5.253	5.841	5.820
1981 .....	5.800	3.860	5.818	5.253	5.659	5.775	5.800	5.253	5.837	5.821
1982 .....	5.800	3.798	5.826	5.253	5.664	5.775	5.800	5.253	5.829	5.820
1983 .....	5.800	3.755	5.825	5.253	5.677	5.774	5.800	5.253	5.800	5.800
1984 .....	5.800	3.745	5.823	5.253	5.613	5.745	5.800	5.253	5.867	5.850
1985 .....	5.800	3.752	5.832	5.253	5.572	5.736	5.800	5.253	5.819	5.814
1986 .....	5.800	3.733	5.903	5.253	5.624	5.808	5.800	5.253	5.839	5.832
1987 .....	5.800	3.742	5.901	5.253	5.599	5.820	5.800	5.253	5.860	5.858
1988 .....	5.800	3.751	5.900	5.253	5.618	5.820	5.800	5.253	5.842	5.840
1989 .....	5.800	3.764	5.906	5.253	5.641	5.833	5.800	5.253	5.869	5.857
1990 .....	5.800	3.758	5.934	5.253	5.614	5.849	5.800	5.253	5.838	5.833
1991 .....	5.800	3.740	5.948	5.253	5.636	5.873	5.800	5.253	5.827	5.823
1992 .....	5.800	3.739	5.953	5.253	5.623	5.877	5.800	5.253	5.774	5.777
1993 .....	5.800	3.735	5.954	5.253	5.539	5.866	5.800	5.253	5.681	5.693
1994 .....	5.800	3.728	5.950	5.253	5.416	5.835	5.800	5.253	5.693	5.704
1995 .....	5.800	3.728	5.938	5.253	5.345	5.830	5.800	5.253	5.692	5.703
1996 .....	5.800	3.703	5.947	5.253	5.373	5.828	5.800	5.253	5.663	5.678
1997 .....	5.800	3.686	5.954	5.253	5.333	5.836	5.800	5.253	5.663	5.678
1998 .....	5.800	3.694	5.953	5.253	5.314	5.833	5.800	5.253	5.505	5.539
1999 .....	5.800	3.663	5.942	5.253	5.291	5.815	5.800	5.253	5.530	5.564
2000 .....	5.800	3.648	5.959	5.253	5.309	5.823	5.800	5.253	5.529	5.542
2001 .....	5.800	3.652	5.976	5.253	5.330	5.838	5.800	5.253	5.637	5.641
2002 .....	5.800	3.646	5.971	5.253	5.362	5.845	5.800	5.253	5.517	5.519
2003 .....	5.800	3.659	5.970	5.253	5.381	5.845	5.800	5.253	5.628	5.630
2004 .....	5.800	3.636	5.981	5.253	5.429	5.853	5.800	5.253	5.532	5.539
2005 .....	5.800	3.638	5.977	5.253	5.436	5.835	5.800	5.253	5.504	5.513
2006 .....	5.800	3.622	5.980	5.253	5.431	5.836	5.800	<sup>e</sup> 5.219	5.415	5.423
2007 .....	5.800	3.609	5.985	5.222	5.483	5.857	5.800	5.188	5.465	5.471
2008 .....	5.800	3.614	5.990	5.222	5.459	5.861	5.800	5.215	5.587	5.591
2009 .....	5.800	3.598	5.988	5.222	5.509	5.878	5.800	5.221	5.674	5.677
2010 .....	5.800	3.573	5.989	5.222	5.545	5.892	5.800	5.214	5.601	5.604
2011 .....	5.800	3.573	6.008	5.222	5.538	5.905	5.800	5.216	5.526	5.530
2012 .....	5.800	3.588	6.165	5.222	5.501	6.035	5.800	5.217	5.520	5.526
2013 .....	5.800	3.629	6.010	5.222	5.497	5.899	5.800	5.216	5.470	5.482
2014 .....	5.800	3.640	6.035	5.222	5.518	5.929	5.800	5.218	5.369	5.406
2015 .....	5.717	3.669	6.065	5.222	5.504	5.941	5.682	5.218	5.279	5.319
2016 .....	5.722	3.632	6.053	5.222	5.491	5.929	5.724	5.218	5.184	5.245
2017 .....	5.723	3.612	6.050	5.222	5.489	5.930	5.738	<sup>e</sup> 5.222	5.151	5.258
2018 .....	5.706	3.591	6.063	5.222	<sup>d</sup> 5.491	<sup>d</sup> 5.938	5.721	5.222	<sup>d</sup> 5.088	<sup>d</sup> 5.259
2019 .....	5.698	3.607	6.061	5.222	5.464	5.908	5.708	5.222	5.022	5.263
2020 .....	<sup>E</sup> 5.698	<sup>E</sup> 3.607	<sup>E</sup> 6.061	<sup>E</sup> 5.222	<sup>E</sup> 5.464	<sup>E</sup> 5.908	<sup>E</sup> 5.708	<sup>E</sup> 5.222	<sup>E</sup> 5.022	<sup>E</sup> 5.263

<sup>a</sup> Includes lease condensate.

<sup>b</sup> Natural gas processing plant production of natural gas liquids (ethane, propane, normal butane, isobutane, and natural gasoline). Through 1980, also includes natural gas processing plant production of finished petroleum products (aviation gasoline, distillate fuel oil, jet fuel, kerosene, motor gasoline, special naphthas, and miscellaneous products).

<sup>c</sup> Excludes fuel ethanol, methyl tertiary butyl ether (MTBE), and other oxygenates blended into motor gasoline.

<sup>d</sup> Through 2017, the imports and exports factors are developed using old hydrocarbon gas liquids heat content values shown in Table A1 of the September 2019 *Monthly Energy Review* (MER). Beginning in 2018, the factors are developed using heat content values shown in Table A1 of the current MER.

<sup>e</sup> For 2006–2016, includes MTBE blended into motor gasoline; excludes MTBE in other years. For all years, excludes fuel ethanol and other non-MTBE oxygenates blended into motor gasoline.

<sup>E</sup>=Estimate.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A3. Approximate Heat Content of Petroleum Consumption and Fuel Ethanol**  
(Million Btu per Barrel)

	Total Petroleum <sup>a</sup> Consumption by Sector						Distillate Fuel Oil Consumption <sup>f</sup>	Hydrocarbon Gas Liquids Consumption <sup>g</sup>	Motor Gasoline (Finished) Consumption <sup>h</sup>	Petroleum Coke Consumption <sup>i</sup>	Fuel Ethanol <sup>j</sup>	Fuel Ethanol Feedstock Factor <sup>k</sup>
	Residential	Commercial <sup>b</sup>	Industrial <sup>b</sup>	Transportation <sup>b,c</sup>	Electric Power <sup>d,e</sup>	Total <sup>b,c</sup>						
1950 .....	5.473	5.817	5.927	5.461	6.254	5.642	5.825	3.810	5.253	6.024	NA	NA
1955 .....	5.470	5.781	5.847	5.407	6.254	5.581	5.825	3.810	5.253	6.024	NA	NA
1960 .....	5.418	5.781	5.772	5.387	6.267	5.542	5.825	3.810	5.253	6.024	NA	NA
1965 .....	5.365	5.761	5.695	5.386	6.267	5.517	5.825	<sup>g</sup> 3.810	5.253	6.024	NA	NA
1970 .....	5.262	5.709	5.579	5.393	6.252	5.499	5.825	3.731	5.253	6.024	NA	NA
1975 .....	5.255	5.649	5.490	5.392	6.250	5.489	5.825	3.671	5.253	6.024	NA	NA
1980 .....	5.322	5.752	5.340	5.441	6.254	5.472	5.825	3.669	5.253	6.024	3.564	6.586
1981 .....	5.284	5.693	5.268	5.433	6.258	5.440	5.825	3.632	5.253	6.024	3.564	6.562
1982 .....	5.267	5.699	5.211	5.423	6.258	5.406	5.825	3.588	5.253	6.024	3.564	6.539
1983 .....	5.141	5.592	5.214	5.416	6.255	5.396	5.825	3.535	5.253	6.024	3.564	6.515
1984 .....	5.308	5.658	5.167	5.418	6.251	5.385	5.825	3.580	5.253	6.024	3.564	6.492
1985 .....	5.264	5.598	5.159	5.423	6.247	5.377	5.825	3.584	5.253	6.024	3.564	6.469
1986 .....	5.269	5.632	5.237	5.426	6.257	5.410	5.825	3.631	5.253	6.024	3.564	6.446
1987 .....	5.241	5.594	5.203	5.429	6.249	5.395	5.825	3.663	5.253	6.024	3.564	6.423
1988 .....	5.259	5.598	5.196	5.433	6.250	5.402	5.825	3.643	5.253	6.024	3.564	6.400
1989 .....	5.195	5.549	5.190	5.438	<sup>d</sup> 6.240	5.403	5.825	3.679	5.253	6.024	3.564	6.377
1990 .....	5.146	5.554	5.219	5.442	6.244	5.403	5.825	3.630	5.253	6.024	3.564	6.355
1991 .....	5.096	5.529	5.130	5.441	6.246	5.375	5.825	3.626	5.253	6.024	3.564	6.332
1992 .....	5.126	5.514	5.133	5.443	6.238	5.369	5.825	3.643	5.253	6.024	3.564	6.309
1993 .....	5.103	<sup>b</sup> 5.505	<sup>b</sup> 5.140	<sup>b</sup> 5.413	6.230	<sup>b</sup> 5.354	5.825	3.628	<sup>h</sup> 5.217	6.024	3.564	6.287
1994 .....	5.097	5.513	5.115	5.413	6.213	5.344	<sup>f</sup> 5.820	3.657	5.214	6.024	3.564	6.264
1995 .....	5.062	5.476	5.084	5.409	6.187	5.326	5.820	3.641	5.204	6.024	3.564	6.242
1996 .....	4.997	5.431	5.076	5.416	6.194	5.323	5.820	3.629	5.211	6.024	3.564	6.220
1997 .....	4.988	5.389	5.083	5.410	6.198	5.322	5.820	3.627	5.205	6.024	3.564	6.198
1998 .....	4.974	5.363	5.101	5.406	6.210	5.335	5.819	3.619	5.203	6.024	3.564	6.176
1999 .....	4.902	5.289	5.052	5.406	6.204	5.313	5.819	3.628	5.202	6.024	3.564	6.167
2000 .....	4.908	5.313	5.015	5.415	6.188	5.311	5.819	3.610	5.201	6.024	3.564	6.159
2001 .....	4.936	5.323	5.104	5.405	6.199	5.331	5.819	3.604	5.201	6.024	3.564	6.151
2002 .....	4.885	5.291	5.053	5.404	6.172	5.309	5.819	3.588	5.199	6.024	3.564	6.143
2003 .....	4.920	5.313	5.108	5.400	6.182	5.326	5.819	3.610	5.197	6.024	3.564	6.106
2004 .....	4.952	5.324	5.106	5.407	6.134	5.330	5.818	3.591	<sup>i</sup> 5.196	<sup>i</sup> 5.982	3.564	6.069
2005 .....	4.915	5.360	5.143	5.408	6.126	5.342	5.818	3.589	5.192	5.982	3.564	6.032
2006 .....	4.886	5.296	5.120	5.405	6.038	5.323	5.803	3.551	5.185	5.987	3.564	5.995
2007 .....	4.833	5.270	5.079	5.376	6.064	5.293	5.784	3.544	5.142	5.996	3.564	5.959
2008 .....	4.772	5.156	5.103	5.342	6.013	5.268	5.780	3.549	5.106	5.992	3.564	5.922
2009 .....	4.664	5.217	4.959	<sup>c</sup> 5.320	5.987	<sup>c</sup> 5.218	5.781	3.487	5.090	6.017	3.564	5.901
2010 .....	4.664	5.195	4.921	5.316	5.956	5.204	5.778	3.489	5.067	6.059	3.562	5.880
2011 .....	4.657	5.176	4.887	5.315	5.900	5.193	5.776	3.423	5.063	6.077	3.561	5.859
2012 .....	4.714	5.126	4.844	5.306	5.925	5.176	5.774	3.440	5.062	6.084	3.560	5.838
2013 .....	4.648	5.053	4.801	5.302	5.892	5.157	5.774	3.468	5.060	6.089	3.560	5.817
2014 .....	4.664	5.016	4.804	5.300	5.906	5.161	5.773	3.439	5.059	6.100	3.559	5.797
2015 .....	4.721	5.050	4.767	5.302	5.915	5.154	5.773	3.461	5.057	6.085	3.558	5.776
2016 .....	4.631	5.022	4.798	5.303	5.885	5.161	5.773	3.424	5.055	6.104	3.558	5.755
2017 .....	4.623	5.006	4.768	5.305	5.893	5.153	5.772	3.400	5.053	6.132	3.556	5.735
2018 .....	4.620	4.971	4.664	5.310	5.896	5.122	5.772	3.381	5.054	6.122	3.553	5.715
2019 .....	RE 4.598	RE 4.979	RE 4.637	RE 5.307	5.900	5.111	5.771	3.401	5.052	6.132	3.555	5.694
2020 .....	RE 4.598	RE 4.979	RE 4.637	RE 5.307	E 5.900	RE 5.066	E 5.771	E 3.401	E 5.052	E 6.132	E 3.555	5.674

<sup>a</sup> Petroleum products supplied, including natural gas plant liquids and crude oil burned directly as fuel. Quantity-weighted averages of the petroleum products included in each category are calculated by using heat content values for individual products shown in Tables A1 and A3.

<sup>b</sup> Beginning in 1993, includes fuel ethanol blended into motor gasoline.

<sup>c</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>d</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>e</sup> Electric power sector factors are weighted average heat contents for distillate fuel oil, petroleum coke, and residual fuel oil; they exclude other liquids.

<sup>f</sup> There is a discontinuity in this time series between 1993 and 1994; beginning in 1994, the single constant factor is replaced by a quantity-weighted factor.

Quantity-weighted averages of the sulfur-content categories of distillate fuel oil are calculated by using heat content values shown in Table A1. Excludes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>g</sup> Quantity-weighted averages of the major components of hydrocarbon gas liquids are calculated by using heat content values shown in Table A1. The factor for 1967 is used as the estimated factor for 1949–1966.

<sup>h</sup> Through 1992, excludes oxygenates. Beginning in 1993, includes fuel ethanol blended into motor gasoline; and for 1993–2006, also includes methyl tertiary butyl ether (MTBE) and other oxygenates blended into motor gasoline.

<sup>i</sup> There is a discontinuity in this time series between 2003 and 2004; beginning in 2004, the single constant factor is replaced by a quantity-weighted factor.

Quantity-weighted averages of the two categories of petroleum coke are calculated by using heat content values shown in Table A1.

<sup>j</sup> Includes denaturant (petroleum added to ethanol to make it undrinkable). Fuel ethanol factors are weighted average heat contents for undenatured ethanol (3.539 million Btu per barrel) and products used as denaturant (natural gasoline, finished motor gasoline, and motor gasoline blending components—see Tables A1 and A3 for factors). The factor for 2009 is used as the estimated factor for 1980–2008.

<sup>k</sup> Corn input to the production of undenatured ethanol (million Btu corn per barrel undenatured ethanol), used as the factor to estimate total biomass inputs to the production of undenatured ethanol. Observed ethanol yields (gallons undenatured ethanol per bushel of corn) are 2.5 in 1980, 2.666 in 1998, 2.68 in 2002, 2.78 in 2008, and 2.82 in 2012; yields in other years are estimated. Corn is assumed to have a gross heat content of 0.392 million Btu per bushel. Undenatured ethanol is assumed to have a gross heat content of 3.539 million Btu per barrel.

R=Revised. E=Estimate. NA=Not available.

Note: The heat content values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.



**Table A4. Approximate Heat Content of Natural Gas**  
(Btu per Cubic Foot)

	Production		Consumption <sup>a</sup>			Imports	Exports
	Marketed	Dry	End-Use Sectors <sup>b</sup>	Electric Power Sector <sup>c</sup>	Total		
1950 .....	1,119	1,035	1,035	1,035	1,035	--	1,035
1955 .....	1,120	1,035	1,035	1,035	1,035	1,035	1,035
1960 .....	1,107	1,035	1,035	1,035	1,035	1,035	1,035
1965 .....	1,101	1,032	1,032	1,032	1,032	1,032	1,032
1970 .....	1,102	1,031	1,031	1,031	1,031	1,031	1,031
1975 .....	1,095	1,021	1,020	1,026	1,021	1,026	1,014
1980 .....	1,098	1,026	1,024	1,035	1,026	1,022	1,013
1981 .....	1,103	1,027	1,025	1,035	1,027	1,014	1,011
1982 .....	1,107	1,028	1,026	1,036	1,028	1,018	1,011
1983 .....	1,115	1,031	1,031	1,030	1,031	1,024	1,010
1984 .....	1,109	1,031	1,030	1,035	1,031	1,005	1,010
1985 .....	1,112	1,032	1,031	1,038	1,032	1,002	1,011
1986 .....	1,110	1,030	1,029	1,034	1,030	997	1,008
1987 .....	1,112	1,031	1,031	1,032	1,031	999	1,011
1988 .....	1,109	1,029	1,029	1,028	1,029	1,002	1,018
1989 .....	1,107	1,031	1,032	<sup>c</sup> 1,028	1,031	1,004	1,019
1990 .....	1,105	1,029	1,029	1,027	1,029	1,012	1,018
1991 .....	1,108	1,030	1,031	1,025	1,030	1,014	1,022
1992 .....	1,110	1,030	1,031	1,025	1,030	1,011	1,018
1993 .....	1,106	1,027	1,027	1,025	1,027	1,020	1,016
1994 .....	1,105	1,028	1,029	1,025	1,028	1,022	1,011
1995 .....	1,106	1,026	1,027	1,021	1,026	1,021	1,011
1996 .....	1,109	1,026	1,027	1,020	1,026	1,022	1,011
1997 .....	1,107	1,026	1,027	1,020	1,026	1,023	1,011
1998 .....	1,109	1,031	1,033	1,024	1,031	1,023	1,011
1999 .....	1,107	1,027	1,028	1,022	1,027	1,022	1,006
2000 .....	1,107	1,025	1,026	1,021	1,025	1,023	1,006
2001 .....	1,105	1,028	1,029	1,026	1,028	1,023	1,010
2002 .....	1,103	1,024	1,025	1,020	1,024	1,022	1,008
2003 .....	1,103	1,028	1,029	1,025	1,028	1,025	1,009
2004 .....	1,104	1,026	1,026	1,027	1,026	1,025	1,009
2005 .....	1,104	1,028	1,028	1,028	1,028	1,025	1,009
2006 .....	1,103	1,028	1,028	1,028	1,028	1,025	1,009
2007 .....	1,102	1,027	1,027	1,027	1,027	1,025	1,009
2008 .....	1,100	1,027	1,027	1,027	1,027	1,025	1,009
2009 .....	1,101	1,025	1,025	1,025	1,025	1,025	1,009
2010 .....	1,098	1,023	1,023	1,022	1,023	1,025	1,009
2011 .....	1,142	1,022	1,022	1,021	1,022	1,025	1,009
2012 .....	1,091	1,024	1,025	1,022	1,024	1,025	1,009
2013 .....	1,101	1,027	1,028	1,025	1,027	1,025	1,009
2014 .....	1,116	1,032	1,033	1,029	1,032	1,025	1,009
2015 .....	1,124	1,037	1,038	1,035	1,037	1,025	1,009
2016 .....	1,128	1,037	1,039	1,034	1,037	1,025	1,009
2017 .....	1,129	1,036	1,037	1,034	1,036	1,025	1,009
2018 .....	1,134	1,036	1,038	1,033	1,036	1,025	1,009
2019 .....	1,140	1,038	1,040	1,034	1,038	1,025	1,009
2020 .....	<sup>E</sup> 1,140	<sup>E</sup> 1,038	<sup>E</sup> 1,040	<sup>E</sup> 1,034	<sup>E</sup> 1,038	<sup>E</sup> 1,025	<sup>E</sup> 1,009

<sup>a</sup> Consumption factors are for natural gas, plus a small amount of supplemental gaseous fuels.

<sup>b</sup> Residential, commercial, industrial, and transportation sectors.

<sup>c</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>E</sup>=Estimate. -- =Not applicable.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A5. Approximate Heat Content of Coal and Coal Coke**  
(Million Btu per Short Ton)

	Coal									Coal Coke
	Production <sup>a</sup>	Waste Coal Supplied <sup>b</sup>	Consumption					Imports	Exports	Imports and Exports
			Residential and Commercial Sectors <sup>c</sup>	Industrial Sector		Electric Power Sector <sup>e,f</sup>	Total			
				Coke Plants	Other <sup>d</sup>					
1950 .....	25.090	NA	24.461	26.798	24.820	23.937	24.989	25.020	26.788	24.800
1955 .....	25.201	NA	24.373	26.794	24.821	24.056	24.982	25.000	26.907	24.800
1960 .....	24.906	NA	24.226	26.791	24.609	23.927	24.713	25.003	26.939	24.800
1965 .....	24.775	NA	24.028	26.787	24.385	23.780	24.537	25.000	26.973	24.800
1970 .....	23.842	NA	23.203	26.784	22.983	22.573	23.440	25.000	26.982	24.800
1975 .....	22.897	NA	22.261	26.782	22.436	21.642	22.506	25.000	26.562	24.800
1980 .....	22.415	NA	22.543	26.790	22.690	21.295	21.947	25.000	26.384	24.800
1981 .....	22.308	NA	22.474	26.794	22.585	21.085	21.713	25.000	26.160	24.800
1982 .....	22.239	NA	22.695	26.797	22.712	21.194	21.674	25.000	26.223	24.800
1983 .....	22.052	NA	22.775	26.798	22.691	21.133	21.576	25.000	26.291	24.800
1984 .....	22.010	NA	22.844	26.799	22.543	21.101	21.573	25.000	26.402	24.800
1985 .....	21.870	NA	22.646	26.798	22.020	20.959	21.366	25.000	26.307	24.800
1986 .....	21.913	NA	22.947	26.798	22.198	21.084	21.462	25.000	26.292	24.800
1987 .....	21.922	NA	23.404	26.799	22.381	21.136	21.517	25.000	26.291	24.800
1988 .....	21.823	NA	23.571	26.799	22.360	20.900	21.328	25.000	26.299	24.800
1989 .....	21.765	<sup>b</sup> 10.391	23.650	26.800	22.347	<sup>e</sup> 20.898	21.307	25.000	26.160	24.800
1990 .....	21.822	9.303	23.137	26.799	22.457	20.779	21.197	25.000	26.202	24.800
1991 .....	21.681	10.758	23.114	26.799	22.460	20.730	21.120	25.000	26.188	24.800
1992 .....	21.682	10.396	23.105	26.799	22.250	20.709	21.068	25.000	26.161	24.800
1993 .....	21.418	10.638	22.994	26.800	22.123	20.677	21.010	25.000	26.335	24.800
1994 .....	21.394	11.097	23.112	26.800	22.068	20.589	20.929	25.000	26.329	24.800
1995 .....	21.326	11.722	23.118	26.800	21.950	20.543	20.880	25.000	26.180	24.800
1996 .....	21.322	12.147	23.011	26.800	22.105	20.547	20.870	25.000	26.174	24.800
1997 .....	21.296	12.158	22.494	26.800	22.172	20.518	20.830	25.000	26.251	24.800
1998 .....	21.418	12.639	21.620	27.426	23.164	20.516	20.881	25.000	26.800	24.800
1999 .....	21.070	12.552	23.880	27.426	22.489	20.490	20.818	25.000	26.081	24.800
2000 .....	21.072	12.360	25.020	27.426	22.433	20.511	20.828	25.000	26.117	24.800
2001 .....	<sup>a</sup> 20.772	12.169	24.909	27.426	22.622	20.337	20.671	25.000	25.998	24.800
2002 .....	20.673	12.165	22.962	27.426	22.562	20.238	20.541	25.000	26.062	24.800
2003 .....	20.499	12.360	22.242	27.425	22.468	20.082	20.387	25.000	25.972	24.800
2004 .....	20.424	12.266	22.324	27.426	22.473	19.980	20.290	25.000	26.108	24.800
2005 .....	20.348	12.093	22.342	26.279	22.178	19.988	20.246	25.000	25.494	24.800
2006 .....	20.310	12.080	22.066	26.271	22.050	19.931	20.181	25.000	25.453	24.800
2007 .....	20.340	12.090	22.069	26.329	22.371	19.909	20.168	25.000	25.466	24.800
2008 .....	20.208	12.121	<sup>c</sup> 23.035	26.281	22.304	19.713	19.979	25.000	25.399	24.800
2009 .....	19.963	12.076	22.852	26.334	21.823	19.521	19.741	25.000	25.633	24.800
2010 .....	20.173	11.960	22.611	26.295	21.846	19.623	19.870	25.000	25.713	24.800
2011 .....	20.142	11.604	22.099	26.299	21.568	19.341	19.600	25.000	25.645	24.800
2012 .....	20.215	11.539	21.300	28.636	21.449	19.211	19.544	23.128	24.551	24.800
2013 .....	20.182	11.103	21.233	28.705	21.600	19.174	19.513	22.379	24.605	24.800
2014 .....	20.146	11.474	21.307	28.458	21.525	19.290	19.611	22.187	25.032	24.800
2015 .....	19.880	11.527	20.699	28.526	21.258	19.146	19.482	22.633	25.048	24.800
2016 .....	19.977	11.496	20.078	28.608	21.055	19.153	19.459	22.327	25.655	24.800
2017 .....	20.025	11.438	19.467	28.673	20.802	18.981	19.303	21.489	24.628	24.800
2018 .....	20.160	11.419	19.269	28.608	20.739	18.915	19.258	20.415	24.294	24.800
2019 .....	20.053	11.513	19.084	28.629	20.721	18.903	19.292	20.558	24.584	24.800
2020 .....	<sup>E</sup> 20.053	<sup>E</sup> 11.513	<sup>E</sup> 19.084	<sup>E</sup> 28.629	<sup>E</sup> 20.721	<sup>E</sup> 18.903	<sup>E</sup> 19.292	<sup>E</sup> 20.558	<sup>E</sup> 24.584	<sup>E</sup> 24.800

<sup>a</sup> Beginning in 2001, includes a small amount of refuse recovery (coal recaptured from a refuse mine, and cleaned to reduce the concentration of noncombustible materials).

<sup>b</sup> Waste coal (including fine coal, coal obtained from a refuse bank or slurry dam, anthracite culm, bituminous gob, and lignite waste) consumed by the electric power and industrial sectors. Beginning in 1989, waste coal supplied is counted as a supply-side item to balance the same amount of waste coal included in "Consumption."

<sup>c</sup> Through 2007, used as the thermal conversion factor for coal consumption by the residential and commercial sectors. Beginning in 2008, used as the thermal conversion factor for coal consumption by the commercial sector only.

<sup>d</sup> Includes transportation. Excludes coal synfuel plants.

<sup>e</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>f</sup> Electric power sector factors are for anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and, beginning in 1998, coal synfuel.

E=Estimate. NA=Not available.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A6. Approximate Heat Rates for Electricity, and Heat Content of Electricity**  
(Btu per Kilowatthour)

	Approximate Heat Rates <sup>a</sup> for Electricity Net Generation						Heat Content <sup>j</sup> of Electricity <sup>k</sup>
	Fossil Fuels <sup>b</sup>				Nuclear <sup>h</sup>	Noncombustible Renewable Energy <sup>g,i</sup>	
	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Total Fossil Fuels <sup>f,g</sup>			
1950 .....	NA	NA	NA	14,030	--	14,030	3,412
1955 .....	NA	NA	NA	11,699	--	11,699	3,412
1960 .....	NA	NA	NA	10,760	11,629	10,760	3,412
1965 .....	NA	NA	NA	10,453	11,804	10,453	3,412
1970 .....	NA	NA	NA	10,494	10,977	10,494	3,412
1975 .....	NA	NA	NA	10,406	11,013	10,406	3,412
1980 .....	NA	NA	NA	10,388	10,908	10,388	3,412
1981 .....	NA	NA	NA	10,453	11,030	10,453	3,412
1982 .....	NA	NA	NA	10,454	11,073	10,454	3,412
1983 .....	NA	NA	NA	10,520	10,905	10,520	3,412
1984 .....	NA	NA	NA	10,440	10,843	10,440	3,412
1985 .....	NA	NA	NA	10,447	10,622	10,447	3,412
1986 .....	NA	NA	NA	10,446	10,579	10,446	3,412
1987 .....	NA	NA	NA	10,419	10,442	10,419	3,412
1988 .....	NA	NA	NA	10,324	10,602	10,324	3,412
1989 .....	NA	NA	NA	10,432	10,583	10,432	3,412
1990 .....	NA	NA	NA	10,402	10,582	10,402	3,412
1991 .....	NA	NA	NA	10,436	10,484	10,436	3,412
1992 .....	NA	NA	NA	10,342	10,471	10,342	3,412
1993 .....	NA	NA	NA	10,309	10,504	10,309	3,412
1994 .....	NA	NA	NA	10,316	10,452	10,316	3,412
1995 .....	NA	NA	NA	10,312	10,507	10,312	3,412
1996 .....	NA	NA	NA	10,340	10,503	10,340	3,412
1997 .....	NA	NA	NA	10,213	10,494	10,213	3,412
1998 .....	NA	NA	NA	10,197	10,491	10,197	3,412
1999 .....	NA	NA	NA	10,226	10,450	10,226	3,412
2000 .....	NA	NA	NA	10,201	10,429	10,201	3,412
2001 .....	10,378	10,742	10,051	<sup>b</sup> 10,333	10,443	10,333	3,412
2002 .....	10,314	10,641	9,533	10,173	10,442	10,173	3,412
2003 .....	10,297	10,610	9,207	10,125	10,422	10,125	3,412
2004 .....	10,331	10,571	8,647	10,016	10,428	10,016	3,412
2005 .....	10,373	10,631	8,551	9,999	10,436	9,999	3,412
2006 .....	10,351	10,809	8,471	9,919	10,435	9,919	3,412
2007 .....	10,375	10,794	8,403	9,884	10,489	9,884	3,412
2008 .....	10,378	11,015	8,305	9,854	10,452	9,854	3,412
2009 .....	10,414	10,923	8,160	9,760	10,459	9,760	3,412
2010 .....	10,415	10,984	8,185	9,756	10,452	9,756	3,412
2011 .....	10,444	10,829	8,152	9,716	10,464	9,716	3,412
2012 .....	10,498	10,991	8,039	9,516	10,479	9,516	3,412
2013 .....	10,459	10,713	7,948	9,541	10,449	9,541	3,412
2014 .....	10,428	10,814	7,907	9,510	10,459	9,510	3,412
2015 .....	10,495	10,687	7,878	9,319	10,458	9,319	3,412
2016 .....	10,493	10,811	7,870	9,232	10,459	9,232	3,412
2017 .....	10,465	10,834	7,812	9,213	10,459	9,213	3,412
2018 .....	10,481	11,095	7,821	9,104	10,455	9,104	3,412
2019 .....	10,551	11,135	7,732	8,904	10,442	8,904	3,412
2020 .....	<sup>E</sup> 10,551	<sup>E</sup> 11,135	<sup>E</sup> 7,732	<sup>E</sup> 8,904	<sup>E</sup> 10,442	<sup>E</sup> 8,904	3,412

<sup>a</sup> The values in columns 1–6 of this table are for net heat rates. See "Heat Rate" in Glossary.

<sup>b</sup> Through 2000, heat rates are for fossil-fueled steam-electric plants at electric utilities. Beginning in 2001, heat rates are for all fossil-fueled plants at electric utilities and electricity-only independent power producers.

<sup>c</sup> Includes anthracite, bituminous coal, subbituminous coal, lignite, and, beginning in 2002, waste coal and coal synfuel.

<sup>d</sup> Includes distillate fuel oil, residual fuel oil, jet fuel, kerosene, petroleum coke, and waste oil.

<sup>e</sup> Includes natural gas and supplemental gaseous fuels.

<sup>f</sup> Includes coal, petroleum, natural gas, and, beginning in 2001, other gases (blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels).

<sup>g</sup> The fossil-fuels heat rate is used as the thermal conversion factor for electricity net generation from noncombustible renewable energy (hydro, geothermal, solar thermal, photovoltaic, and wind) to approximate the quantity of fossil fuels replaced by these sources. Through 2000, also used as the thermal conversion factor for wood and waste electricity net generation at electric utilities; beginning in 2001, Btu data for wood and waste at electric utilities are available from surveys.

<sup>h</sup> Used as the thermal conversion factor for nuclear electricity net generation.

<sup>i</sup> Technology-based geothermal heat rates are no longer used in Btu calculations in this report. For technology-based geothermal heat rates for 1960–2010, see the *Annual Energy Review 2010*, Table A6.

<sup>j</sup> See "Heat Content" in Glossary.

<sup>k</sup> The value of 3,412 Btu per kilowatthour is a constant. It is used as the thermal conversion factor for electricity retail sales, and electricity imports and exports.

<sup>E</sup>=Estimate. NA=Not available. -- =Not applicable.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: See "Thermal Conversion Factor Source Documentation," which follows this table.

## Approximate Heat Content of Petroleum and Natural Gas Liquids

**Asphalt.** The U.S. Energy Information Administration (EIA) adopted the thermal conversion factor of 6.636 million British thermal units (Btu) per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

**Aviation Gasoline Blending Components.** Assumed by EIA to be 5.048 million Btu per barrel or equal to the thermal conversion factor for **Aviation Gasoline (Finished)**.

**Aviation Gasoline (Finished).** EIA adopted the thermal conversion factor of 5.048 million Btu per barrel as adopted by the Bureau of Mines from the Texas Eastern Transmission Corporation publication *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics.

**Butylene.** EIA estimated the thermal conversion factor to be 4.377 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook, NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Crude Oil Exports.** • 1949–2014: Assumed by EIA to be 5.800 million Btu per barrel or equal to the thermal conversion factor for crude oil produced in the United States. See **Crude Oil Production**. • 2015 forward: Calculated annually by EIA based on conversion of American Petroleum Institute (API) gravity ranges of crude oil exports as reported in trade data from the U.S. Census Bureau. Specific gravity (SG) =  $141.5 / (131.5 + \text{API gravity})$ . The higher heating value (HHV) in million Btu per barrel =  $\text{SG} * (7.801796 - 1.3213 * \text{SG}^2)$ .

**Crude Oil Imports.** Calculated annually by EIA as the average of the thermal conversion factors for each type of crude oil imported weighted by the quantities imported. Thermal conversion factors for each type were calculated on a foreign country basis, by determining the average American Petroleum Institute (API) gravity of crude oil imported from each foreign country from Form ERA-60 in 1977 and converting average API gravity to average Btu content by using National Bureau of Standards, Miscellaneous Publication No. 97, *Thermal Properties of Petroleum Products*, 1933.

**Crude Oil Production.** • 1949–2014: EIA adopted the thermal conversion factor of 5.800 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.” • 2015 forward: Calculated annually by EIA based on conversion of American Petroleum Institute (API) gravity ranges of crude oil production as reported on Form EIA-914, “Monthly Crude Oil, Lease Condensate, and Natural Gas Production Report.” Specific gravity (SG) =  $141.5 / (131.5 + \text{API gravity})$ . The higher heating value (HHV) in million Btu per barrel =  $\text{SG} * (7.801796 - 1.3213 * \text{SG}^2)$ .

**Distillate Fuel Oil Consumption.** • 1949–1993: EIA adopted the Bureau of Mines thermal conversion factor of 5.825 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.” • 1994 forward: Calculated by EIA as the annual quantity-weighted average of the conversion factors for **Distillate Fuel Oil, 15 ppm Sulfur and Under** (5.770 million Btu per barrel), **Distillate Fuel Oil, Greater Than 15 ppm to 500 ppm Sulfur** (5.817 million Btu per barrel), and **Distillate Fuel Oil, Greater Than 500 ppm Sulfur** (5.825 million Btu per barrel).

**Distillate Fuel Oil, 15 ppm Sulfur and Under.** EIA adopted the thermal conversion factor of 5.770 million Btu per barrel (137,380 Btu per gallon) for U.S. conventional diesel from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Distillate Fuel Oil, Greater Than 15 ppm to 500 ppm Sulfur.** EIA adopted the thermal conversion factor of 5.817 million Btu per barrel (138,490 Btu per gallon) for low-sulfur diesel from U.S. Department of Energy, Argonne Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Distillate Fuel Oil, Greater Than 500 ppm Sulfur.** EIA adopted the Bureau of Mines thermal conversion factor of 5.825 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.”

**Ethane.** EIA estimated the thermal conversion factor to be 2.783 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook, NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Ethylene.** EIA adopted the thermal conversion factor of 2.436 million Btu per barrel (0.058 million Btu per gallon) as published in the Federal Register EPA; 40 CFR part 98; e-CRF; Table C1; April 5, 2019. The ethylene higher heating value is determined at 41 degrees Fahrenheit at saturation pressure.

**Hydrocarbon Gas Liquids.** • 1949–1966: EIA used the 1967 factor. • 1967 forward: Calculated annually by EIA as the average of the thermal conversion factors for all hydrocarbon gas liquids consumed (see Table A1) weighted by the quantities consumed. The component products of hydrocarbon gas liquids are ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). For 1967–1980, quantities consumed are from EIA, Energy Data Reports, “Petroleum Statement, Annual.” For 1981 forward, quantities consumed are from EIA, *Petroleum Supply Annual*.

**Hydrogen.** EIA estimated a thermal conversion factor of 323.6 Btu per standard cubic foot (at 60 degrees Fahrenheit and 1 atmosphere), based on data published by the National Research Council and National Academy of Engineering, in Appendix H of *The Hydrogen Economy: Opportunities, Costs, Barriers, and R&D Needs*, 2004. EIA also assumed a thermal conversion factor of 6.287 million Btu per residual fuel oil equivalent barrel or equal to the thermal conversion factor for **Residual Fuel Oil**.

**Isobutane.** EIA estimated the thermal conversion factor to be 4.183 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook, NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Isobutylene.** EIA estimated the thermal conversion factor to be 4.355 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook, NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Jet Fuel, Kerosene-Type.** EIA adopted the Bureau of Mines thermal conversion factor of 5.670 million Btu per barrel for “Jet Fuel, Commercial” as published by the Texas Eastern Transmission Corporation in the report *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics.

**Jet Fuel, Naphtha-Type.** EIA adopted the Bureau of Mines thermal conversion factor of 5.355 million Btu per barrel for “Jet Fuel, Military” as published by the Texas Eastern Transmission Corporation in the report *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics.

**Kerosene.** EIA adopted the Bureau of Mines thermal conversion factor of 5.670 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.”

**Lubricants.** EIA adopted the thermal conversion factor of 6.065 million Btu per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

**Miscellaneous Products.** EIA adopted the thermal conversion factor of 5.796 million Btu per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

**Motor Gasoline Blending Components.** • 1949–2006: EIA adopted the Bureau of Mines thermal conversion factor of 5.253 million Btu per barrel for “Gasoline, Motor Fuel” as published by the Texas Eastern Transmission Corporation in Appendix V of *Competition and Growth in American Markets 1947–1985*, a 1968 release of historical and projected statistics. • 2007 forward: EIA adopted the thermal conversion factor of 5.222 million Btu per barrel (124,340 Btu per gallon) for gasoline blendstock from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Motor Gasoline Exports.** • 1949–2005: EIA adopted the Bureau of Mines thermal conversion factor of 5.253 million Btu per barrel for “Gasoline, Motor Fuel” as published by the Texas Eastern Transmission Corporation in Appendix V of *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics. • 2006 forward: Calculated by EIA as the annual quantity-weighted average of the conversion factors for gasoline blendstock and the methyl tertiary butyl ether (MTBE) blended into motor gasoline exports. The factor for gasoline

blendstock is 5.253 million Btu per barrel in 2006 and 5.222 million Btu per barrel beginning in 2007 (see **Motor Gasoline Blending Components**). For MTBE, EIA adopted the thermal conversion factor of 4.247 million Btu per barrel (101,130 Btu per gallon) from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Motor Gasoline (Finished) Consumption.** • 1949–1992: EIA adopted the Bureau of Mines thermal conversion factor of 5.253 million Btu per barrel for “Gasoline, Motor Fuel” as published by the Texas Eastern Transmission Corporation in Appendix V of *Competition and Growth in American Markets 1947-1985*, a 1968 release of historical and projected statistics. • 1993–2006: Calculated by EIA as the annual quantity-weighted average of the conversion factors for gasoline blendstock and the oxygenates blended into motor gasoline. The factor for gasoline blendstock is 5.253 million Btu per barrel (the motor gasoline factor used for previous years). The factors for fuel ethanol are shown in Table A3 (see **Fuel Ethanol, Denatured**). The following factors for other oxygenates are from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013—methyl tertiary butyl ether (MTBE): 4.247 million Btu per barrel (101,130 Btu per gallon); tertiary amyl methyl ether (TAME): 4.560 million Btu per barrel (108,570 Btu per gallon); ethyl tertiary butyl ether (ETBE): 4.390 million Btu per barrel (104,530 Btu per gallon); methanol: 2.738 million Btu per barrel (65,200 Btu per gallon); and butanol: 4.555 million Btu per barrel (108,458 Btu per gallon). • 2007 forward: Calculated by EIA as the annual quantity-weighted average of the conversion factors for gasoline blendstock and fuel ethanol blended into motor gasoline. The factor for gasoline blendstock is 5.222 million Btu per barrel (124,340 Btu per gallon), which is from the GREET model (see above). The factors for fuel ethanol are shown in Table A3 (see **Fuel Ethanol, Denatured**).

**Motor Gasoline Imports.** • 1949–2006: EIA adopted the Bureau of Mines thermal conversion factor of 5.253 million Btu per barrel for “Gasoline, Motor Fuel” as published by the Texas Eastern Transmission Corporation in Appendix V of *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics. • 2007 forward: EIA adopted the thermal conversion factor of 5.222 million Btu per barrel (124,340 Btu per gallon) for gasoline blendstock from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Natural Gas Plant Liquids Production.** Calculated annually by EIA as the average of the thermal conversion factors for each natural gas plant liquid produced weighted by the quantities produced.

**Natural Gasoline.** EIA estimated the thermal conversion factor to be 4.638 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook*, *NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute. EIA assumes a natural gasoline ratio of 29% isopentane, 29% neopentane, 20% normal pentane, 13% normal hexane, 4% cyclohexane, 3% benzene, and 2% toluene in these calculations.

**Normal Butane.** EIA estimated the thermal conversion factor to be 4.353 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook*, *NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Other Hydrocarbons.** Assumed by EIA to be 5.825 million Btu per barrel or equal to the thermal conversion factor for **Unfinished Oils**.

**Oxygenates (Excluding Fuel Ethanol).** EIA adopted the thermal conversion factor of 4.247 million Btu per barrel (101,130 Btu per gallon) for methyl tertiary butyl ether (MTBE) from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Petrochemical Feedstocks, Naphtha Less Than 401 Degrees Fahrenheit.** Assumed by EIA to be 5.248 million Btu per barrel or equal to the thermal conversion factor for **Special Naphthas**.

**Petrochemical Feedstocks, Other Oils Equal to or Greater Than 401 Degrees Fahrenheit.** Assumed by EIA to be 5.825 million Btu per barrel or equal to the thermal conversion factor for **Distillate Fuel Oil**.

**Petrochemical Feedstocks, Still Gas.** Assumed by EIA to be equal to the thermal conversion factor for **Still Gas**.

**Petroleum Coke, Catalyst.** Assumed by EIA to be 6.287 million Btu per barrel or equal to the thermal conversion factor for **Residual Fuel Oil**.

**Petroleum Coke, Marketable.** EIA adopted the thermal conversion factor of 5.719 million Btu per barrel, calculated by dividing 28,595,925 Btu per short ton for petroleum coke (from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_October 2013) by 5.0 barrels per short ton (as given in the Bureau of Mines Form 6-1300-M and successor EIA forms).

**Petroleum Coke, Total.** • 1949–2003: EIA adopted the thermal conversion factor of 6.024 million Btu per barrel as reported in Btu per short ton in the Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.” The Bureau of Mines calculated this factor by dividing 30.120 million Btu per short ton, as given in the referenced Bureau of Mines internal memorandum, by 5.0 barrels per short ton, as given in the Bureau of Mines Form 6-1300-M and successor EIA forms. • 2004 forward: Calculated by EIA as the annual quantity-weighted average of the conversion factors for **Petroleum Coke, Catalyst** (6.287 million Btu per barrel) and **Petroleum Coke, Marketable** (5.719 million Btu per barrel).

**Petroleum Consumption, Commercial Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the commercial sector weighted by the estimated quantities consumed by the commercial sector. The quantities of petroleum products consumed by the commercial sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_petrol.pdf).

**Petroleum Consumption, Electric Power Sector.** Calculated annually by EIA as the average of the thermal conversion factors for distillate fuel oil, petroleum coke, and residual fuel oil consumed by the electric power sector weighted by the quantities consumed by the electric power sector. Data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

**Petroleum Consumption, Industrial Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the industrial sector weighted by the estimated quantities consumed by the industrial sector. The quantities of petroleum products consumed by the industrial sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_petrol.pdf).

**Petroleum Consumption, Residential Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the residential sector weighted by the estimated quantities consumed by the residential sector. The quantities of petroleum products consumed by the residential sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_petrol.pdf).

**Petroleum Consumption, Total.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed weighted by the quantities consumed.

**Petroleum Consumption, Transportation Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the transportation sector weighted by the estimated quantities consumed by the transportation sector. The quantities of petroleum products consumed by the transportation sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_petrol.pdf).

**Petroleum Products Exports.** Calculated annually by EIA as the average of the thermal conversion factors for each petroleum product exported weighted by the quantities exported.

**Petroleum Products Imports.** Calculated annually by EIA as the average of the thermal conversion factors for each petroleum product imported weighted by the quantities imported.

**Plant Condensate.** • 1973–1983: Estimated to be 5.418 million Btu per barrel by EIA from data provided by McClanahan Consultants, Inc., Houston, Texas.

**Propane.** EIA estimated the thermal conversion factor to be 3.841 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook*, *NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Propylene.** EIA estimated the thermal conversion factor to be 3.835 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook*, *NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Renewable Fuels Except Fuel Ethanol.** For “Biomass-Based Diesel Fuel” and “Other Renewable Fuels,” EIA assumed the thermal conversion factor to be 5.359 million Btu per barrel or equal to the thermal conversion factor for **Biodiesel**. For “Other Renewable Diesel Fuel,” EIA adopted the thermal conversion factor of 5.494 million Btu per barrel (130,817 Btu per gallon) for renewable diesel II (UOP-HDO) from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Residual Fuel Oil.** EIA adopted the thermal conversion factor of 6.287 million Btu per barrel as reported in the Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.”

**Road Oil.** EIA adopted the Bureau of Mines thermal conversion factor of 6.636 million Btu per barrel, which was assumed to be equal to that of **Asphalt** and was first published by the Bureau of Mines in the *Petroleum Statement, Annual, 1970*.

**Special Naphthas.** EIA adopted the Bureau of Mines thermal conversion factor of 5.248 million Btu per barrel, which was assumed to be equal to that of the total gasoline (aviation and motor) factor and was first published in the *Petroleum Statement, Annual, 1970*.

**Still Gas.** • 1949–2015: EIA adopted the Bureau of Mines estimated thermal conversion factor of 6.000 million Btu per barrel, first published in the *Petroleum Statement, Annual, 1970*. • 2016 forward: Assumed by EIA to be 6.287 million Btu per barrel or equal to the thermal conversion factor for **Residual Fuel Oil**.

**Total Petroleum Exports.** Calculated annually by EIA as the average of the thermal conversion factors for crude oil and each petroleum product exported weighted by the quantities exported. See **Crude Oil Exports** and **Petroleum Products Exports**.

**Total Petroleum Imports.** Calculated annually by EIA as the average of the thermal conversion factors for each type of crude oil and petroleum product imported weighted by the quantities imported. See **Crude Oil Imports** and **Petroleum Products Imports**.

**Unfinished Oils.** EIA assumed the thermal conversion factor to be 5.825 million Btu per barrel, the average of all natural gas or equal to that for **Distillate Fuel Oil** and first published it in EIA’s *Annual Report to Congress, Volume 3, 1977*.

**Unfractionated Stream.** • 1979–1982: EIA assumed the thermal conversion factor to be 3.800 million Btu per barrel, the average of all natural gas plant liquids calculated on their contribution to total barrels produced.

**Waxes.** EIA adopted the thermal conversion factor of 5.537 million Btu per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

## Approximate Heat Content of Biofuels

**Biodiesel.** EIA estimated the thermal conversion factor for biodiesel to be 5.359 million Btu per barrel, or 17,253 Btu per pound.

**Biodiesel Feedstock.** EIA used soybean oil input to the production of biodiesel (million Btu soybean oil per barrel biodiesel) as the factor to estimate total biomass inputs to the production of biodiesel. EIA assumed that 7.65 pounds of soybean oil are needed to produce one gallon of biodiesel, and 5.433 million Btu of soybean oil are needed to produce one barrel of biodiesel. EIA also assumed that soybean oil has a gross heat content of 16,909 Btu per pound, or 5.483 million Btu per barrel.

**Ethanol (Undenatured).** EIA adopted the thermal conversion factor of 3.539 million Btu per barrel published in “Oxygenate Flexibility for Future Fuels,” a paper presented by William J. Piel of the ARCO Chemical Company at the National Conference on Reformulated Gasolines and Clean Air Act Implementation, Washington, DC, October 1991.

**Fuel Ethanol (Denatured).** • 1981–2008: EIA used the 2009 factor. • 2009 forward: Calculated by EIA as the annual quantity-weighted average of the thermal conversion factors for undenatured ethanol (3.539 million Btu per barrel), natural gasoline used as denaturant (4.638 million Btu per barrel), and conventional motor gasoline and motor gasoline blending components used as denaturant (5.253 million Btu per barrel). The quantity of ethanol consumed is from EIA’s *Petroleum Supply Annual* (PSA) and *Petroleum Supply Monthly* (PSM), Table 1, data for renewable fuels and oxygenate plant net production of fuel ethanol. The quantity of natural gasoline used as denaturant is from PSA/PSM, Table 1, data for renewable fuels and oxygenate plant net production of natural gasoline, multiplied by -1. The



quantity of conventional motor gasoline and motor gasoline blending components used as denaturant is from PSA/PSM, Table 1, data for renewable fuels and oxygenate plant net production of conventional motor gasoline and motor gasoline blending components, multiplied by -1.

**Fuel Ethanol Feedstock.** EIA used corn input to the production of undenatured ethanol (million Btu corn per barrel undenatured ethanol) as the annual factor to estimate total biomass inputs to the production of undenatured ethanol. EIA used the following observed ethanol yields (in gallons undenatured ethanol per bushel of corn) from U.S. Department of Agriculture: 2.5 in 1980, 2.666 in 1998, 2.68 in 2002; and from University of Illinois at Chicago, Energy Resources Center, “2012 Corn Ethanol: Emerging Plant Energy and Environmental Technologies”: 2.78 in 2008, and 2.82 in 2012. EIA estimated the ethanol yields in other years. EIA also assumed that corn has a gross heat content of 0.392 million Btu per bushel.

## Approximate Heat Content of Natural Gas

**Natural Gas Consumption, Electric Power Sector.** Calculated annually by EIA by dividing the heat content of natural gas consumed by the electric power sector by the quantity consumed. Data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

**Natural Gas Consumption, End-Use Sectors.** Calculated annually by EIA by dividing the heat content of natural gas consumed by the end-use sectors (residential, commercial, industrial, and transportation) by the quantity consumed. The heat content of natural gas consumed by the end-use sectors is calculated as the total heat content of natural gas consumed minus the heat content of natural gas consumed by the electric power sector. The quantity of natural gas consumed by the end-use sectors is calculated as the total quantity of natural gas consumed minus the quantity of natural gas consumed by the electric power sector. Data are from Form EIA-176, “Annual Report of Natural and Supplemental Gas Supply and Disposition”; and Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

**Natural Gas Consumption, Total.** • 1949–1962: EIA adopted the thermal conversion factor of 1,035 Btu per cubic foot as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*. • 1963–1979: EIA adopted the thermal conversion factor calculated annually by the American Gas Association (AGA) and published in *Gas Facts*, an AGA annual publication. • 1980 forward: Calculated annually by EIA by dividing the total heat content of natural gas consumed by the total quantity consumed.

**Natural Gas Exports.** • 1949–1972: Assumed by EIA to be equal to the thermal conversion factor for dry natural gas consumed (see **Natural Gas Consumption, Total**). • 1973 forward: Calculated annually by EIA by dividing the heat content of natural gas exported by the quantity exported. For 1973–1995, data are from Form FPC-14, “Annual Report for Importers and Exporters of Natural Gas.” Beginning in 1996, data are from U.S. Department of Energy, Office of Fossil Energy, *Natural Gas Imports and Exports*.

**Natural Gas Imports.** • 1949–1972: Assumed by EIA to be equal to the thermal conversion factor for dry natural gas consumed (see **Natural Gas Consumption, Total**). • 1973 forward: Calculated annually by EIA by dividing the heat content of natural gas imported by the quantity imported. For 1973–1995, data are from Form FPC-14, “Annual Report for Importers and Exporters of Natural Gas.” Beginning in 1996, data are from U.S. Department of Energy, Office of Fossil Energy, *Natural Gas Imports and Exports*.

**Natural Gas Production, Dry.** Assumed by EIA to be equal to the thermal conversion factor for dry natural gas consumed. See **Natural Gas Consumption, Total**.

**Natural Gas Production, Marketed.** Calculated annually by EIA by dividing the heat content of dry natural gas produced (see **Natural Gas Production, Dry**) and natural gas liquids produced (see **Natural Gas Liquids Production**) by the total quantity of marketed natural gas produced.

## Approximate Heat Content of Coal and Coal Coke

**Coal Coke Imports and Exports.** EIA adopted the Bureau of Mines estimate of 24,800 million Btu per short ton.

**Coal Consumption, Electric Power Sector.** Calculated annually by EIA by dividing the heat content of coal consumed by the electric power sector by the quantity consumed. Data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

**Coal Consumption, Industrial Sector, Coke Plants.** • 1949–2011: Calculated annually by EIA based on the reported volatility (low, medium, or high) of coal received by coke plants. (For 2011, EIA used the following volatility factors, in million Btu per short ton: low volatile—26.680; medium volatile—27.506; and high volatile—25.652.) Data are from Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants,” and predecessor forms. • 2012 forward: Calculated annually by EIA by dividing the heat content of coal received by coke plants by the quantity received. Through June 2014, data are from Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants”; beginning in July 2014, data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”).

**Coal Consumption, Industrial Sector, Other.** • 1949–2007: Calculated annually by EIA by dividing the heat content of coal received by manufacturing plants by the quantity received. Data are from Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms. • 2008 forward: Calculated annually by EIA by dividing the heat content of coal received by manufacturing, gasification, and liquefaction plants by the quantity received. Data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”).

**Coal Consumption, Residential and Commercial Sectors.** • 1949–1999: Calculated annually by EIA by dividing the heat content of coal received by the residential and commercial sectors by the quantity received. Data are from Form EIA-6, “Coal Distribution Report,” and predecessor forms. • 2000–2007: Calculated annually by EIA by dividing the heat content of coal consumed by commercial combined-heat-and-power (CHP) plants by the quantity consumed. Data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms. • 2008 forward: Calculated annually by EIA by dividing the heat content of coal received by commercial and institutional users by the quantity received. Data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”).

**Coal Consumption, Total.** Calculated annually by EIA by dividing the total heat content of coal consumed by all sectors by the total quantity consumed.

**Coal Exports.** • 1949–2011: Calculated annually by EIA by dividing the heat content of steam coal and metallurgical coal exported by the quantity exported. Data are from U.S. Department of Commerce, U.S. Census Bureau, “Monthly Report EM 545,” and predecessor forms. • 2012 forward: Calculated annually by EIA by dividing the heat content of steam coal and metallurgical coal exported by the quantity exported. The average heat content of steam coal is derived from receipts data from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”), and Form EIA-923, “Power Plant Operations Report.” Through June 2014, the average heat content of metallurgical coal is derived from receipts data from Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants”; beginning in July 2014, the average heat content of metallurgical coal is derived from receipts data from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”). Data for export quantities are from U.S. Department of Commerce, U.S. Census Bureau, “Monthly Report EM 545.”

**Coal Imports.** • 1949–1963: Calculated annually by EIA by dividing the heat content of coal imported by the quantity imported. Data are from U.S. Department of Commerce, U.S. Census Bureau, “Monthly Report IM 145,” and predecessor forms. • 1964–2011: Assumed by EIA to be 25.000 million Btu per short ton. • 2012 forward: Calculated annually by EIA by dividing the heat content of coal imported (received) by the quantity imported (received). Data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”); Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants” (data through June 2014); and Form EIA-923, “Power Plant Operations Report.”

**Coal Production.** • 1949–2011: Calculated annually by EIA by dividing the heat content of domestic coal (excluding waste coal) received by the quantity received. Data are from Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing and Transformation/Processing Coal Plants and Commercial and Institutional Users”; Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants”; Form EIA-923, “Power Plant Operations Report”; and predecessor forms. • 2012 forward: Calculated annually by EIA by dividing the heat content of domestic coal (excluding waste coal) received and exported by the quantity received and exported. Data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”); Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants” (data through June 2014); Form EIA-

923, “Power Plant Operations Report”; U.S. Department of Commerce, U.S. Census Bureau, “Monthly Report EM 545”; and predecessor forms.

**Waste Coal Supplied.** • 1989–2000: Calculated annually by EIA by dividing the heat content of waste coal consumed by the quantity consumed. Data are from Form EIA-860B, “Annual Electric Generator Report—Nonutility,” and predecessor form. • 2001 forward: Calculated by EIA by dividing the heat content of waste coal received (or consumed) by the quantity received (or consumed). Receipts data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”), and predecessor forms. Consumption data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

## Approximate Heat Rates for Electricity

**Electricity Net Generation, Coal.** • 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for all electric utilities and electricity-only independent power producers using anthracite, bituminous coal, subbituminous coal, lignite, and beginning in 2002, waste coal and coal synfuel.

**Electricity Net Generation, Natural Gas.** • 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for all electric utilities and electricity-only independent power producers using natural gas and supplemental gaseous fuels.

**Electricity Net Generation, Noncombustible Renewable Energy.** There is no generally accepted practice for measuring the thermal conversion rates for power plants that generate electricity from hydro, geothermal, solar thermal, photovoltaic, and wind energy sources. Therefore, EIA calculates a rate factor that is equal to the annual average heat rate factor for fossil-fueled power plants in the United States (see “Electricity Net Generation, Total Fossil Fuels”). By using that factor it is possible to evaluate fossil fuel requirements for replacing those sources during periods of interruption, such as droughts. See Appendix E for more information.

**Electricity Net Generation, Nuclear.** • 1957–1984: Calculated annually by dividing the total heat content consumed in nuclear generating units by the total (net) electricity generated by nuclear generating units. The heat content and electricity generation were reported on Form FERC-1, “Annual Report of Major Electric Utilities, Licensees, and Others”; Form EIA-412, “Annual Report of Public Electric Utilities”; and predecessor forms. For 1982, the factors were published in EIA, *Historical Plant Cost and Annual Production Expenses for Selected Electric Plants 1982*, page 215. For 1983 and 1984, the factors were published in EIA, *Electric Plant Cost and Power Production Expenses 1991*, Table 13. • 1985 forward: Calculated annually by EIA by using the heat rate data reported on Form EIA-860, “Annual Electric Generator Report,” and predecessor forms.

**Electricity Net Generation, Petroleum.** • 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for all electric utilities and electricity-only independent power producers using distillate fuel oil, residual fuel oil, jet fuel, kerosene, petroleum coke, and waste oil.

**Electricity Net Generation, Total Fossil Fuels.** • 1949–1955: The weighted annual average heat rate for fossil-fueled steam-electric power plants in the United States, as published by EIA in *Thermal-Electric Plant Construction Cost and Annual Production Expenses—1981* and *Steam-Electric Plant Construction Cost and Annual Production Expenses—1978*. • 1956–1988: The weighted annual average heat rate for fossil-fueled steam-electric power plants in the United States, as published in EIA, *Electric Plant Cost and Power Production Expenses 1991*, Table 9. • 1989–2000: Calculated annually by EIA by using heat rate data reported on Form EIA-860, “Annual Electric Generator Report,” and predecessor forms; and net generation data reported on Form EIA-759, “Monthly Power Plant Report.” The computation includes data for all electric utility steam-electric plants using fossil fuels. • 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for all electric utilities and electricity-only independent power producers using coal, petroleum, natural gas, and other gases (blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels).

# Appendix B

## Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors

---

## Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors

---

Data presented in the *Monthly Energy Review* and in other U.S. Energy Information Administration publications are expressed predominately in units that historically have been used in the United States, such as British thermal units, barrels, cubic feet, and short tons. The metric conversion factors presented in Table B1 can be used to calculate the metric-unit equivalents of values expressed in U.S. Customary units. For example, 500 short tons are the equivalent of 453.6 metric tons (500 short tons x 0.9071847 metric tons/short ton = 453.6 metric tons).

In the metric system of weights and measures, the names of multiples and subdivisions of any unit may be derived by combining the name of the unit with prefixes, such as deka, hecto, and kilo, meaning, respectively, 10, 100, 1,000, and deci, centi, and milli, meaning, respectively, one-tenth, one-hundredth, and one-thousandth. Common metric prefixes can be found in Table B2.

The conversion factors presented in Table B3 can be used to calculate equivalents in various physical units commonly used in energy analyses. For example, 10 barrels are the equivalent of 420 U.S. gallons (10 barrels x 42 gallons/barrel = 420 gallons).

**Table B1. Metric Conversion Factors**

Type of Unit	U.S. Unit		Equivalent in	Metric Units
<b>Mass</b>	1 short ton (2,000 lb)	=	0.907 184 7	metric tons (t)
	1 long ton	=	1.016 047	metric tons (t)
	1 pound (lb)	=	0.453 592 37 <sup>a</sup>	kilograms (kg)
	1 pound uranium oxide (lb U <sub>3</sub> O <sub>8</sub> )	=	0.384 647 <sup>b</sup>	kilograms uranium (kgU)
	1 ounce, avoirdupois (avdp oz)	=	28.349 52	grams (g)
<b>Volume</b>	1 barrel of oil (bbl)	=	0.158 987 3	cubic meters (m <sup>3</sup> )
	1 cubic yard (yd <sup>3</sup> )	=	0.764 555	cubic meters (m <sup>3</sup> )
	1 cubic foot (ft <sup>3</sup> )	=	0.028 316 85	cubic meters (m <sup>3</sup> )
	1 U.S. gallon (gal)	=	3.785 412	liters (L)
	1 ounce, fluid (fl oz)	=	29.573 53	milliliters (mL)
	1 cubic inch (in <sup>3</sup> )	=	16.387 06	milliliters (mL)
<b>Length</b>	1 mile (mi)	=	1.609 344 <sup>a</sup>	kilometers (km)
	1 yard (yd)	=	0.914 4 <sup>a</sup>	meters (m)
	1 foot (ft)	=	0.304 8 <sup>a</sup>	meters (m)
	1 inch (in)	=	2.54 <sup>a</sup>	centimeters (cm)
<b>Area</b>	1 acre	=	0.404 69	hectares (ha)
	1 square mile (mi <sup>2</sup> )	=	2.589 988	square kilometers (km <sup>2</sup> )
	1 square yard (yd <sup>2</sup> )	=	0.836 127 4	square meters (m <sup>2</sup> )
	1 square foot (ft <sup>2</sup> )	=	0.092 903 04 <sup>a</sup>	square meters (m <sup>2</sup> )
	1 square inch (in <sup>2</sup> )	=	6.451 6 <sup>a</sup>	square centimeters (cm <sup>2</sup> )
<b>Energy</b>	1 British thermal unit (Btu) <sup>c</sup>	=	1,055.055 852 62 <sup>a</sup>	joules (J)
	1 calorie (cal)	=	4.186 8 <sup>a</sup>	joules (J)
	1 kilowatthour (kWh)	=	3.6 <sup>a</sup>	megajoules (MJ)
<b>Temperature<sup>d</sup></b>	32 degrees Fahrenheit (°F)	=	0 <sup>a</sup>	degrees Celsius (°C)
	212 degrees Fahrenheit (°F)	=	100 <sup>a</sup>	degrees Celsius (°C)

[a] Exact conversion.

[b] Calculated by the U.S. Energy Information Administration.

[c] The Btu used in this table is the International Table Btu adopted by the Fifth International Conference on Properties of Steam, London, 1956.

[d] To convert degrees Fahrenheit (°F) to degrees Celsius (°C) exactly, subtract 32, then multiply by 5/9.

Notes: • Spaces have been inserted after every third digit to the right of the decimal for ease of reading. • Most metric units belong to the International System of Units (SI), and the liter, hectare, and metric ton are accepted for use with the SI units. For more information about the SI units, see <http://physics.nist.gov/cuu/Units/index.html>.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: • General Services Administration, Federal Standard 376B, *Preferred Metric Units for General Use by the Federal Government* (Washington, DC, January 1993), pp. 9–11, 13, and 16. • U.S. Department of Commerce, National Institute of Standards and Technology, *Special Publications 330, 811, and 814*. • American National Standards Institute/Institute of Electrical and Electronic Engineers, ANSI/IEEE Std268-1992, pp. 28 and 29.

**Table B2. Metric Prefixes**

Unit Multiple	Prefix	Symbol	Unit Subdivision	Prefix	Symbol
10 <sup>1</sup>	deka	da	10 <sup>-1</sup>	deci	d
10 <sup>2</sup>	hecto	h	10 <sup>-2</sup>	centi	c
10 <sup>3</sup>	kilo	k	10 <sup>-3</sup>	milli	m
10 <sup>6</sup>	mega	M	10 <sup>-6</sup>	micro	μ
10 <sup>9</sup>	giga	G	10 <sup>-9</sup>	nano	n
10 <sup>12</sup>	tera	T	10 <sup>-12</sup>	pico	p
10 <sup>15</sup>	peta	P	10 <sup>-15</sup>	femto	f
10 <sup>18</sup>	exa	E	10 <sup>-18</sup>	atto	a
10 <sup>21</sup>	zetta	Z	10 <sup>-21</sup>	zepto	z
10 <sup>24</sup>	yotta	Y	10 <sup>-24</sup>	yocto	y

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: U.S. Department of Commerce, National Institute of Standards and Technology, *The International System of Units (SI)*, NIST Special Publication 330, 1991 Edition (Washington, DC, August 1991), p.10.

**Table B3. Other Physical Conversion Factors**

Energy Source	Original Unit		Equivalent in Final Units
<b>Petroleum</b>	1 barrel (bbl)	=	42 <sup>a</sup> U.S. gallons (gal)
<b>Coal</b>	1 short ton	=	2,000 <sup>a</sup> pounds (lb)
	1 long ton	=	2,240 <sup>a</sup> pounds (lb)
	1 metric ton (t)	=	1,000 <sup>a</sup> kilograms (kg)
<b>Wood</b>	1 cord (cd)	=	1.25 <sup>b</sup> shorts tons
	1 cord (cd)	=	128 <sup>a</sup> cubic feet (ft <sup>3</sup> )

[a] Exact conversion.

[b] Calculated by the U.S. Energy Information Administration.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: U.S. Department of Commerce, National Institute of Standards and Technology, *Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices*, NIST Handbook 44, 1994 Edition (Washington, DC, October 1993), pp. B-10, C-17, and C-21.

# Appendix C

**Population, U.S. Gross Domestic Product, and U.S. Gross Output**

---



# Population, U.S. Gross Domestic Product, and U.S. Gross Output

**Table C1. Population, U.S. Gross Domestic Product, and U.S. Gross Output**

	Population			U.S. Gross Domestic Product			U.S. Gross Output <sup>a</sup>
	United States <sup>b</sup>	World	United States as Share of World	Billion Nominal Dollars <sup>d</sup>	Billion Chained (2012) Dollars <sup>e</sup>	Implicit Price Deflator <sup>c</sup> (2012 = 1.00000)	Billion Nominal Dollars <sup>d</sup>
	Million People		Percent				
1950 .....	152.3	2,557.6	6.0	299.8	2,289.5	0.13095	577.8
1955 .....	165.9	2,782.1	6.0	425.5	2,871.2	.14819	802.6
1960 .....	180.7	3,043.0	5.9	542.4	3,260.0	.16638	1,006.0
1965 .....	194.3	3,350.8	5.8	742.3	4,170.8	.17798	1,356.0
1970 .....	205.1	3,713.5	5.5	1,073.3	4,951.3	.21677	1,903.0
1975 .....	216.0	<sup>R</sup> 4,089.0	5.3	1,684.9	5,644.8	.29849	3,055.3
1980 .....	227.2	<sup>R</sup> 4,445.0	5.1	2,857.3	6,759.2	.42273	5,462.0
1981 .....	229.5	<sup>R</sup> 4,526.3	5.1	3,207.0	6,930.7	.46273	6,033.5
1982 .....	231.7	<sup>R</sup> 4,606.5	5.0	3,343.8	6,805.8	.49132	6,175.0
1983 .....	233.8	<sup>R</sup> 4,687.7	5.0	3,634.0	7,117.7	.51056	6,631.0
1984 .....	235.8	<sup>R</sup> 4,766.5	4.9	4,037.6	7,632.8	.52898	7,313.8
1985 .....	237.9	<sup>R</sup> 4,848.4	4.9	4,339.0	7,951.1	.54571	7,775.7
1986 .....	240.1	<sup>R</sup> 4,932.4	4.9	4,579.6	8,226.4	.55670	8,031.0
1987 .....	242.3	<sup>R</sup> 5,019.0	4.8	4,855.2	8,511.0	.57046	8,707.5
1988 .....	244.5	<sup>R</sup> 5,106.4	4.8	5,236.4	8,866.5	.59059	9,434.2
1989 .....	246.8	<sup>R</sup> 5,193.4	<sup>R</sup> 4.8	5,641.6	9,192.1	.61374	10,069.8
1990 .....	249.6	<sup>R</sup> 5,282.0	4.7	5,963.1	9,365.5	.63671	10,624.6
1991 .....	253.0	<sup>R</sup> 5,365.3	4.7	6,158.1	9,355.4	.65825	10,808.0
1992 .....	256.5	<sup>R</sup> 5,449.4	4.7	6,520.3	9,684.9	.67325	11,381.0
1993 .....	259.9	<sup>R</sup> 5,530.9	4.7	6,858.6	9,951.5	.68920	12,024.4
1994 .....	263.1	<sup>R</sup> 5,610.7	4.7	7,287.2	10,352.4	.70392	12,826.8
1995 .....	266.3	<sup>R</sup> 5,691.8	4.7	7,639.7	10,630.3	.71868	13,653.2
1996 .....	269.4	<sup>R</sup> 5,772.0	4.7	8,073.1	11,031.4	.73183	14,463.4
1997 .....	272.6	5,850.7	4.7	8,577.6	11,521.9	.74445	15,393.3
1998 .....	275.9	<sup>R</sup> 5,928.2	<sup>R</sup> 4.7	9,062.8	12,038.3	.75283	16,216.8
1999 .....	279.0	<sup>R</sup> 6,005.1	4.6	9,630.7	12,610.5	.76370	17,272.3
2000 .....	282.2	<sup>R</sup> 6,081.9	4.6	10,252.3	13,131.0	.78078	18,623.9
2001 .....	285.0	<sup>R</sup> 6,159.1	4.6	10,581.8	13,262.1	.79790	18,888.3
2002 .....	287.6	<sup>R</sup> 6,236.7	4.6	10,936.4	13,493.1	.81052	19,178.3
2003 .....	290.1	<sup>R</sup> 6,314.7	4.6	11,458.2	13,879.1	.82557	20,141.2
2004 .....	292.8	<sup>R</sup> 6,393.1	4.6	12,213.7	14,406.4	.84780	21,690.2
2005 .....	295.5	<sup>R</sup> 6,471.5	4.6	13,036.6	14,912.5	.87421	23,512.9
2006 .....	298.4	<sup>R</sup> 6,551.9	4.6	13,814.6	15,338.3	.90066	24,931.4
2007 .....	301.2	<sup>R</sup> 6,634.4	4.5	14,451.9	15,626.0	.92486	26,238.5
2008 .....	304.1	<sup>R</sup> 6,718.3	4.5	14,712.8	15,604.7	.94285	26,989.2
2009 .....	306.8	<sup>R</sup> 6,801.8	4.5	14,448.9	15,208.8	.95004	24,919.5
2010 .....	309.3	<sup>R</sup> 6,884.0	4.5	14,992.1	15,598.8	.96111	26,422.4
2011 .....	311.6	<sup>R</sup> 6,965.9	4.5	15,542.6	15,840.7	.98118	27,999.5
2012 .....	<sup>R</sup> 313.9	<sup>R</sup> 7,047.8	4.5	16,197.0	16,197.0	1.00000	29,186.8
2013 .....	<sup>R</sup> 316.1	<sup>R</sup> 7,130.5	4.4	16,784.9	16,495.4	1.01755	30,291.3
2014 .....	<sup>R</sup> 318.4	<sup>R</sup> 7,212.9	4.4	17,527.3	16,912.0	1.03638	31,740.0
2015 .....	<sup>R</sup> 320.7	<sup>R</sup> 7,294.3	4.4	18,238.3	17,432.2	1.04624	32,222.3
2016 .....	<sup>R</sup> 323.1	<sup>R</sup> 7,375.3	4.4	18,745.1	17,730.5	1.05722	32,882.2
2017 .....	<sup>R</sup> 325.1	<sup>R</sup> 7,455.1	4.4	19,543.0	18,144.1	1.07710	34,474.7
2018 .....	<sup>R</sup> 326.8	<sup>R</sup> 7,533.7	4.3	20,611.9	18,687.8	1.10296	36,603.4
2019 .....	<sup>R</sup> 328.3	<sup>R</sup> 7,612.1	4.3	21,433.2	19,091.7	1.12265	37,817.0
2020 .....	329.5	7,693.3	4.3	20,932.8	18,422.6	1.13626	NA

<sup>a</sup> Gross output is the value of gross domestic product (GDP) plus the value of intermediate inputs used to produce GDP.

<sup>b</sup> Resident population of the 50 states and the District of Columbia estimated for July 1 of each year.

<sup>c</sup> The gross domestic product implicit price deflator is used to convert nominal dollars to chained (2012) dollars.

<sup>d</sup> See "Nominal Dollars" in Glossary.

<sup>e</sup> See "Chained Dollars" in Glossary.

R=Revised. NA=Not available.

Notes: • Data are estimates. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **United States Population: 1949–1989**—U.S. Department of

Commerce (DOC), U.S. Census Bureau, Current Population Reports Series P-25 (June 2000). **1990–1999**—DOC, U.S. Census Bureau, "Time Series of Intercensal State Population Estimates" (April 2002). **2000–2009**—DOC, U.S. Census Bureau, "Intercensal Estimates of the Resident Population for the United States, Regions, States, and Puerto Rico" (September 2011). **2010 forward**—DOC, U.S. Census Bureau, "Annual Estimates of the Resident Population for the United States, Regions, States, and Puerto Rico" (December 2020). • **World Population: 1950 forward**—DOC, U.S. Census Bureau, International Database (December 2020). • **United States as Share of World Population:** Calculated as U.S. population divided by world population. • **U.S. Gross Domestic Product: 1949 forward**—DOC, Bureau of Economic Analysis (BEA), National Income and Product Accounts (August 2020), Tables 1.1.5, 1.1.6, and 1.1.9. • **U.S. Gross Output: 1949–1996**—DOC, BEA, GDP by industry (Historical) data (October 2019). **1997 forward**—DOC, BEA, GDP by Industry data (January 2021).

# Appendix D

Estimated Primary Energy Consumption in the  
United States, Selected Years, 1635-1945

---

# Estimated Primary Energy Consumption in the United States, Selected Years, 1635-1945

**Table D1. Estimated Primary Energy Consumption in the United States, Selected Years, 1635–1945** (Quadrillion Btu)

	Fossil Fuels				Renewable Energy			Electricity Net Imports <sup>b</sup>	Total
	Coal	Natural Gas	Petroleum	Total	Conventional Hydroelectric Power	Biomass	Total		
						Wood <sup>a</sup>			
1635 .....	NA	--	--	NA	--	(s)	(s)	--	(s)
1645 .....	NA	--	--	NA	--	0.001	0.001	--	0.001
1655 .....	NA	--	--	NA	--	.002	.002	--	.002
1665 .....	NA	--	--	NA	--	.005	.005	--	.005
1675 .....	NA	--	--	NA	--	.007	.007	--	.007
1685 .....	NA	--	--	NA	--	.009	.009	--	.009
1695 .....	NA	--	--	NA	--	.014	.014	--	.014
1705 .....	NA	--	--	NA	--	.022	.022	--	.022
1715 .....	NA	--	--	NA	--	.037	.037	--	.037
1725 .....	NA	--	--	NA	--	.056	.056	--	.056
1735 .....	NA	--	--	NA	--	.080	.080	--	.080
1745 .....	NA	--	--	NA	--	.112	.112	--	.112
1755 .....	NA	--	--	NA	--	.155	.155	--	.155
1765 .....	NA	--	--	NA	--	.200	.200	--	.200
1775 .....	NA	--	--	NA	--	.249	.249	--	.249
1785 .....	NA	--	--	NA	--	.310	.310	--	.310
1795 .....	NA	--	--	NA	--	.402	.402	--	.402
1805 .....	NA	--	--	NA	--	.537	.537	--	.537
1815 .....	NA	--	--	NA	--	.714	.714	--	.714
1825 .....	NA	--	--	NA	--	.960	.960	--	.960
1835 .....	NA	--	--	NA	--	1.305	1.305	--	1.305
1845 .....	NA	--	--	NA	--	1.757	1.757	--	1.757
1850 .....	0.219	--	--	0.219	--	2.138	2.138	--	2.357
1855 .....	.421	--	--	.421	--	2.389	2.389	--	2.810
1860 .....	.518	--	0.003	.521	--	2.641	2.641	--	3.162
1865 .....	.632	--	.010	.642	--	2.767	2.767	--	3.409
1870 .....	1.048	--	.011	1.059	--	2.893	2.893	--	3.952
1875 .....	1.440	--	.011	1.451	--	2.872	2.872	--	4.323
1880 .....	2.054	--	.096	2.150	--	2.851	2.851	--	5.001
1885 .....	2.840	0.082	.040	2.962	--	2.683	2.683	--	5.645
1890 .....	4.062	.257	.156	4.475	0.022	2.515	2.537	--	7.012
1895 .....	4.950	.147	.168	5.265	.090	2.306	2.396	--	7.661
1900 .....	6.841	.252	.229	7.322	.250	2.015	2.265	--	9.587
1905 .....	10.001	.372	.610	10.983	.386	1.843	2.229	--	13.212
1910 .....	12.714	.540	1.007	14.261	.539	1.765	2.304	--	16.565
1915 .....	13.294	.673	1.418	15.385	.659	1.688	2.347	0.002	17.734
1920 .....	15.504	.813	2.676	18.993	.738	1.610	2.348	.003	21.344
1925 .....	14.706	1.191	4.280	20.177	.668	1.533	2.201	.004	22.382
1930 .....	13.639	1.932	5.897	21.468	.752	1.455	2.207	.005	23.680
1935 .....	10.634	1.919	5.675	18.228	.806	1.397	2.203	.005	20.436
1940 .....	12.535	2.665	7.760	22.960	.880	1.358	2.238	.007	25.205
1945 .....	15.972	3.871	10.110	29.953	1.442	<sup>a</sup> 1.261	2.703	.009	32.665

<sup>a</sup> There is a discontinuity in the "Wood" time series between 1945 (in this table) and 1949 (in Table 10.1). Through 1945, data are for fuelwood only; beginning in 1949, data are for wood and wood-derived fuels.

<sup>b</sup> Electricity transmitted across U.S. borders. Net imports equal imports minus exports.

NA=Not available. -- =Not applicable. (s)=Less than 0.5 trillion Btu.

Notes: • For years not shown, data are not available. • See Tables 1.3 and 10.1 for continuation of these data series beginning in 1949. • See Note, "Geographic Coverage of Statistics for 1635–1945," at end of section.

Sources: • **Fossil Fuels:** *Energy in the American Economy, 1850–1975*, Table VII. • **Conventional Hydroelectric Power:** *Energy in the American Economy, 1850–1975*, Table II. • **Wood:** 1635–1845—U.S. Department of Agriculture,

Circular No. 641, *Fuel Wood Used in the United States 1630–1930*, February 1942. This source estimates fuelwood consumption in cords per decade, which were converted to Btu using the conversion factor of 20 million Btu per cord. The annual average value for each decade was assigned to the fifth year of the decade on the assumption that annual use was likely to increase during any given decade and the average annual value was more likely to reflect mid-decade yearly consumption than use at either the beginning or end of the decade. Values thus begin in 1635 and are plotted at 10-year intervals. 1850–1945—*Energy in the American Economy, 1850–1975*, Table VII. • **Electricity Net Imports:** *Energy in the American Economy, 1850–1975*, Tables I and VI. Electricity net imports are assumed to equal hydroelectric consumption minus hydroelectric production (data are converted to Btu by multiplying by 3,412 Btu per kilowatthour).

**Note. Geographic Coverage of Statistics for 1635–1945.**

Table D1 presents estimates of U.S. energy consumption by energy source for a period that begins a century and a half before the original 13 colonies formed a political union and continues through the decades during which the United States was still expanding territorially. The question thus arises, what exactly is meant by “U.S. consumption” of an energy source for those years when the United States did not formally exist or consisted of less territory than is now encompassed by the 50 states and the District of Columbia?

The documents used to assemble the estimates, and (as far as possible) the sources of those documents, were reviewed carefully for clues to geographic coverage. For most energy sources, the extent of coverage expanded more rapidly than the nation, defined as all the official states and the District of Columbia. Estimates or measurements of consumption of each energy source generally appear to follow settlement patterns. That is, they were made for areas of the continent that were settled enough to have economically significant consumption even though those areas were not to become states for years. The wood data series, for example, begins in 1635 and includes 12 of the original colonies (excepting Georgia), as well as Maine, Vermont, and the area that would become the District of Columbia. By the time the series reaches 1810, the rest of the continental states are all included, although the last of the 48 states to achieve statehood did not do so until 1912. Likewise, the coal data series begins in 1850 but includes consumption in areas, such as Utah and Washington (state), which were significant coal producing regions but had not yet attained statehood. (Note: No data were available on state-level historical coal consumption. The coal data shown in Table D1 through 1945 describe *apparent* consumption, i.e., production plus imports minus exports. The geographic coverage for coal was therefore based on a tally of coal-*producing* states listed in various historical issues of *Minerals Yearbook*. It is likely that coal was consumed in states where it was not mined in significant quantities.)

By energy source, the extent of coverage can be summarized as follows:

- Coal—35 coal-producing states by 1885.
- Natural Gas—All 48 contiguous states, the District of Columbia, and Alaska by 1885.
- Petroleum—All 48 contiguous states, the District of Columbia, and Alaska by 1885.
- Conventional Hydroelectric Power—Coverage for 1890 and 1895 is uncertain, but probably the 48 contiguous states and the District of Columbia. Coverage for 1900–1945 is the 48 contiguous states, and the District of Columbia.
- Wood—All 48 contiguous states and the District of Columbia by 1810.

# **Appendix E**

## **Alternative Approaches for Deriving Energy Contents of Noncombustible Renewables**

---

# Alternative Approaches for Deriving Energy Contents of Noncombustible Renewables

EIA compiles data on most energy sources in physical units, such as barrels and cubic feet, in order to calculate total primary energy consumption. To sum data for different energy sources, EIA converts the data to the common unit of British thermal units (Btu), a measure that is based on the thermal conversion of energy resources to heat and power.

Noncombustible renewables are resources from which energy is extracted without burning or combusting fuel. They include hydroelectric, geothermal, solar, and wind energy. When noncombustible renewables are used to generate electricity, there is no fuel combustion and, therefore, no set Btu conversion factors for the energy sources.<sup>1</sup> However, there are several possible approaches for converting that electricity to Btu. Three of these approaches are described below.

## *Fossil Fuel Equivalency Approach*

In Sections 1, 2, and 10 of the *Monthly Energy Review*, EIA calculates total primary energy consumption for noncombustible renewable electricity in Btu by applying a fossil fuel equivalency factor. Under that approach, the primary energy consumption of noncombustible renewable electricity can be viewed as the sum of captured energy "transformed into electricity" and an "adjustment for fossil fuel equivalency."

The adjustment for fossil fuel equivalency is equal to the difference between total primary consumption of noncombustible renewables for electricity generation in Btu (calculated using the fossil fuels heat rate in Table A6) and the captured energy of that electricity (calculated using the constant conversion factor of 3,412 Btu per kWh). The fossil fuels heat rate is equal to the thermal efficiency across fossil fuel-fired generating stations based on net generation. The fossil fuel equivalency adjustment represents the energy that would have been consumed if electricity had been generated by fossil fuels. By using that factor, it is possible, for example, to evaluate fossil fuel requirements for replacing electricity generation during periods of interruptions, such as droughts.

## *Captured Energy Approach*

Captured energy (Tables E1a and E1b) reflects the primary energy captured for economic use and does not include losses. Thus, it is the net energy available for direct consumption after transformation of a noncombustible renewable into electricity. In other words, captured energy is the energy measured as the "output" of a generating unit, such as electricity from a wind turbine or solar plant. The captured energy approach is often used to show the economically significant energy transformations in the United States. There is no market for the resource-specific energy apart from its immediate, site-specific energy conversion, and there is no substantive opportunity cost to its continued exploitation.<sup>2</sup>

## *Incident Energy Approach*

Incident energy is the mechanical, radiation, or thermal energy that is measurable as the "input" of the device. EIA defines "incident energy" for noncombustible renewables as the gross energy that first strikes an energy conversion device:

- For hydroelectric, the energy contained in the water passing through the penstock (a closed conduit for carrying water to the turbines)
- For geothermal, the energy contained in the hot fluid at the surface of the wellbore
- For wind, the energy contained in the wind that passes through the rotor disc
- For solar, the energy contained in the sunlight that strikes the panel or collector mirror

The incident energy approach to converting noncombustible renewable electricity to Btu could, in theory, be used to account for “losses” that are due to the inability to convert 100% of incident energy to a useful form of energy. EIA does not publish total primary energy consumption estimates based on the incident energy approach because it would be difficult to obtain accurate estimates of input energy without creating undue burden on survey respondents. Few renewable electricity power plants track cumulative input energy due to its lack of economic significance or other purpose. In addition, estimated energy efficiencies of renewable conversion technologies vary significantly across technologies, site-specific configurations, and environmental factors.<sup>3</sup>

---

<sup>1</sup>Direct use of noncombustible renewables in the form of heat (e.g., solar thermal heating) is estimated separately and is measured in Btu.

<sup>2</sup>There is an initial opportunity cost when a facility is first built: water behind a dam might flood land that could have been used for other purposes, or a solar panel might shade an area that could have used the sunlight. But that is a “fixed” opportunity cost that does not change during the operation of the plant.

<sup>3</sup>Based on EIA research conducted in 2016, engineering estimates of conversion efficiencies for noncombustible renewables range from less than 20% for solar photovoltaics and geothermal to 90% for large-scale hydroelectricity plants. Those estimates are notional indications of the energy output as a percent of energy input at each technology based on typical equipment operating within the normal operating range for that technology.

**Table E1a. Noncombustible Renewable Primary Energy Consumption: Conventional Hydroelectric Power, Geothermal, and Wind** (Trillion Btu)

	Conventional Hydroelectric Power <sup>a</sup>			Geothermal <sup>b</sup>				Wind <sup>c</sup>		
	Trans- formed Into Electricity <sup>d,e</sup>	Adjustment for Fossil Fuel Equivalence <sup>f</sup>	Total Primary Energy <sup>g</sup>	Direct Consump- tion <sup>h</sup>	Trans- formed Into Electricity <sup>d,i</sup>	Adjustment for Fossil Fuel Equivalence <sup>f</sup>	Total Primary Energy <sup>j</sup>	Trans- formed Into Electricity <sup>d,i</sup>	Adjustment for Fossil Fuel Equivalence <sup>f</sup>	Total Primary Energy <sup>g</sup>
1950 .....	344	1,071	1,415	NA	NA	NA	NA	NA	NA	NA
1955 .....	397	963	1,360	NA	NA	NA	NA	NA	NA	NA
1960 .....	510	1,098	1,608	NA	(s)	(s)	(s)	NA	NA	NA
1965 .....	672	1,387	2,059	NA	1	1	2	NA	NA	NA
1970 .....	856	1,777	2,634	NA	2	4	6	NA	NA	NA
1975 .....	1,034	2,120	3,155	NA	11	23	34	NA	NA	NA
1980 .....	953	1,948	2,900	NA	17	35	53	NA	NA	NA
1981 .....	900	1,858	2,758	NA	19	40	59	NA	NA	NA
1982 .....	1,066	2,200	3,266	NA	17	34	51	NA	NA	NA
1983 .....	1,144	2,383	3,527	NA	21	43	64	(s)	(s)	(s)
1984 .....	1,107	2,279	3,386	NA	26	54	81	(s)	(s)	(s)
1985 .....	970	2,000	2,970	NA	32	66	97	(s)	(s)	(s)
1986 .....	1,003	2,068	3,071	NA	35	73	108	(s)	(s)	(s)
1987 .....	863	1,772	2,635	NA	37	76	112	(s)	(s)	(s)
1988 .....	771	1,563	2,334	NA	35	71	106	(s)	(s)	(s)
1989 .....	<sup>e</sup> 928	1,909	2,837	9	<sup>i</sup> 50	102	162	<sup>j</sup> 7	15	22
1990 .....	999	2,047	3,046	10	53	108	171	10	19	29
1991 .....	986	2,030	3,016	11	54	112	178	10	21	31
1992 .....	864	1,754	2,617	12	55	112	179	10	20	30
1993 .....	957	1,935	2,892	13	57	116	186	10	21	31
1994 .....	888	1,796	2,683	13	53	107	173	12	24	36
1995 .....	1,061	2,145	3,205	14	46	92	152	11	22	33
1996 .....	1,185	2,405	3,590	15	49	99	163	11	22	33
1997 .....	1,216	2,424	3,640	16	50	100	167	11	22	34
1998 .....	1,103	2,194	3,297	18	50	100	168	10	21	31
1999 .....	1,090	2,177	3,268	19	51	101	171	15	31	46
2000 .....	940	1,871	2,811	21	48	96	164	19	38	57
2001 .....	740	1,502	2,242	22	47	95	164	23	47	70
2002 .....	902	1,787	2,689	24	49	98	171	35	70	105
2003 .....	941	1,851	2,793	27	49	97	173	38	75	113
2004 .....	916	1,773	2,688	30	51	98	178	48	93	142
2005 .....	922	1,781	2,703	34	50	97	181	61	117	178
2006 .....	987	1,882	2,869	37	50	95	181	91	173	264
2007 .....	845	1,602	2,446	41	50	95	186	118	223	341
2008 .....	869	1,642	2,511	46	51	96	192	189	357	546
2009 .....	933	1,736	2,669	54	51	95	200	252	469	721
2010 .....	888	1,651	2,539	60	52	97	208	323	600	923
2011 .....	1,090	2,013	3,103	64	52	97	212	410	758	1,168
2012 .....	943	1,686	2,629	64	53	95	212	480	860	1,340
2013 .....	916	1,646	2,562	64	54	97	214	573	1,029	1,601
2014 .....	885	1,582	2,467	64	54	97	214	620	1,108	1,728
2015 .....	850	1,471	2,321	64	54	94	212	651	1,127	1,777
2016 .....	914	1,559	2,472	64	54	92	210	774	1,321	2,096
2017 .....	1,025	1,742	2,767	64	54	92	210	868	1,475	2,343
2018 .....	998	1,665	2,663	64	54	91	209	930	1,552	2,482
2019 .....	982	1,581	2,563	64	53	85	201	1,006	1,620	2,626

<sup>a</sup> Conventional hydroelectricity net generation. Through 1989, also includes hydroelectric pumped storage.

<sup>b</sup> Geothermal heat pump and direct use energy; and geothermal electricity net generation.

<sup>c</sup> Wind electricity net generation.

<sup>d</sup> Electricity net generation in kilowatthours (kWh) multiplied by 3,412 Btu/kWh, the heat content of electricity (see Table A6).

<sup>e</sup> Through 1988, data are for electric utilities and industrial plants. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

<sup>f</sup> Equals the difference between the fossil-fuel equivalent value of electricity and the captured energy consumed as electricity. The fossil-fuel equivalent value of electricity equals electricity net generation in kilowatthours multiplied by the total fossil fuels heat rate factors (see Table A6). The captured energy consumed as electricity equals electricity net generation in kilowatthours multiplied by 3,412 Btu/kWh, the heat content of electricity (see Table A6).

<sup>g</sup> Electricity net generation in kilowatthours multiplied by the total fossil fuels

heat rate factors (see Table A6).

<sup>h</sup> Geothermal heat pump and direct use energy.

<sup>i</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

<sup>j</sup> Direct consumption of energy; and energy used to generate electricity, calculated as electricity net generation in kilowatthours multiplied by the total fossil fuels heat rate factors (see Table A6).

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Geothermal direct consumption data are estimates. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **Conventional Hydroelectric Power** and **Wind**: Tables 7.2a, 10.1, and A6. • **Geothermal**: Tables 7.2a, 10.1, 10.2a, 10.2b, and A6.



**Table E1b. Noncombustible Renewable Primary Energy Consumption: Solar and Total**  
(Trillion Btu)

	Solar <sup>a</sup>						Total <sup>b</sup>		
	Distributed <sup>c</sup>			Utility-Scale <sup>d</sup>		Total Primary Energy <sup>i</sup>	Captured Energy <sup>j</sup>	Adjustment for Fossil Fuel Equivalence <sup>g</sup>	Total Primary Energy <sup>i</sup>
	Direct Consumption <sup>e</sup>	Transformed Into Electricity <sup>f</sup>	Adjustment for Fossil Fuel Equivalence <sup>g</sup>	Transformed Into Electricity <sup>f,h</sup>	Adjustment for Fossil Fuel Equivalence <sup>g</sup>				
1950 .....	NA	NA	NA	NA	NA	NA	344	1,071	1,415
1955 .....	NA	NA	NA	NA	NA	NA	397	963	1,360
1960 .....	NA	NA	NA	NA	NA	NA	510	1,098	1,608
1965 .....	NA	NA	NA	NA	NA	NA	673	1,388	2,061
1970 .....	NA	NA	NA	NA	NA	NA	858	1,781	2,639
1975 .....	NA	NA	NA	NA	NA	NA	1,045	2,143	3,188
1980 .....	NA	NA	NA	NA	NA	NA	970	1,983	2,953
1981 .....	NA	NA	NA	NA	NA	NA	920	1,898	2,817
1982 .....	NA	NA	NA	NA	NA	NA	1,082	2,234	3,316
1983 .....	NA	NA	NA	NA	NA	NA	1,165	2,426	3,591
1984 .....	NA	NA	NA	(s)	(s)	(s)	1,133	2,334	3,467
1985 .....	NA	NA	NA	(s)	(s)	(s)	1,002	2,066	3,068
1986 .....	NA	NA	NA	(s)	(s)	(s)	1,038	2,141	3,179
1987 .....	NA	NA	NA	(s)	(s)	(s)	900	1,847	2,747
1988 .....	NA	NA	NA	(s)	(s)	(s)	807	1,634	2,441
1989 .....	52	(s)	(s)	<sup>h</sup> 1	2	54	1,047	2,029	3,075
1990 .....	55	(s)	(s)	1	3	59	1,128	2,177	3,305
1991 .....	56	(s)	(s)	2	3	62	1,120	2,166	3,286
1992 .....	58	(s)	(s)	1	3	63	1,000	1,889	2,889
1993 .....	60	(s)	(s)	2	3	65	1,099	2,075	3,173
1994 .....	62	(s)	(s)	2	3	67	1,029	1,931	2,960
1995 .....	63	(s)	(s)	2	3	68	1,196	2,263	3,458
1996 .....	63	(s)	(s)	2	4	69	1,325	2,531	3,856
1997 .....	62	(s)	1	2	3	68	1,358	2,551	3,909
1998 .....	61	(s)	1	2	3	67	1,245	2,319	3,564
1999 .....	60	(s)	1	2	3	66	1,237	2,313	3,550
2000 .....	57	(s)	1	2	3	63	1,087	2,009	3,096
2001 .....	55	(s)	1	2	4	62	890	1,648	2,538
2002 .....	53	1	1	2	4	60	1,066	1,960	3,025
2003 .....	51	1	1	2	4	58	1,109	2,028	3,138
2004 .....	50	1	2	2	4	58	1,097	1,969	3,067
2005 .....	49	1	2	2	4	58	1,119	2,001	3,120
2006 .....	51	2	3	2	3	61	1,218	2,157	3,375
2007 .....	53	2	5	2	4	66	1,110	1,928	3,038
2008 .....	54	4	7	3	6	74	1,217	2,107	3,323
2009 .....	55	5	10	3	6	78	1,353	2,315	3,668
2010 .....	56	8	15	4	8	91	1,390	2,371	3,761
2011 .....	58	13	24	6	11	112	1,692	2,903	4,595
2012 .....	59	21	38	15	26	159	1,635	2,705	4,339
2013 .....	61	28	50	31	55	225	1,726	2,877	4,602
2014 .....	62	38	68	60	108	338	1,784	2,963	4,746
2015 .....	63	48	84	85	147	427	1,815	2,922	4,737
2016 .....	64	64	109	123	210	570	2,057	3,291	5,348
2017 .....	65	82	139	182	309	777	2,339	3,758	6,097
2018 .....	66	101	168	218	363	916	2,430	3,839	6,270
2019 .....	66	119	192	245	395	1,018	2,536	3,873	6,408

<sup>a</sup> Solar thermal direct use energy; and solar photovoltaic (PV) and solar thermal electricity net generation.

<sup>b</sup> Conventional hydroelectricity net generation; geothermal heat pump and direct use energy; geothermal electricity net generation; wind electricity net generation; solar thermal direct use energy; and solar photovoltaic (PV) and solar thermal electricity net generation.

<sup>c</sup> Distributed (small-scale) facilities (electric generators have a combined generator nameplate capacity of less than 1 megawatt).

<sup>d</sup> Utility-scale facilities (combined generator nameplate capacity of 1 megawatt or more).

<sup>e</sup> Solar thermal direct use energy.

<sup>f</sup> Electricity net generation in kilowatthours (kWh) multiplied by 3,412 Btu/kWh, the heat content of electricity (see Table A6).

<sup>g</sup> Equals the difference between the fossil-fuel equivalent value of electricity and the captured energy consumed as electricity. The fossil-fuel equivalent value of electricity equals electricity net generation in kilowatthours multiplied by the total fossil fuels heat rate factors (see Table A6). The captured energy consumed as electricity equals electricity net generation in kilowatthours multiplied by 3,412 Btu/kWh, the heat content of electricity (see Table A6).

<sup>h</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

<sup>i</sup> Direct consumption of energy; and energy used to generate electricity, calculated as electricity net generation in kilowatthours multiplied by the total fossil fuels heat rate factors (see Table A6).

<sup>j</sup> Direct consumption of energy plus captured energy consumed as electricity, which is calculated as electricity net generation in kilowatthours (kWh) multiplied by 3,412 Btu/kWh, the heat content of electricity (see Table A6).

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Beginning in 1989, data for distributed solar and total captured energy are estimates. For the current year, data for utility-scale solar are estimates.

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices>

(Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **Solar:** Tables 10.5, 10.6, and A6. • **Total:** Tables 7.2a, 10.1, 10.2a, 10.2b, 10.5, 10.6, and A6.

# Glossary

---

**Alcohol:** The family name of a group of organic chemical compounds composed of carbon, hydrogen, and oxygen. The series of molecules vary in chain length and are composed of a **hydrocarbon** plus a hydroxyl group;  $\text{CH}_3\text{-(CH}_2\text{)}_n\text{-OH}$  (e.g., **methanol**, **ethanol**, and tertiary butyl alcohol). See **Fuel ethanol**.

**Alternative fuel:** Alternative fuels, for transportation applications, include the following: **methanol**; denatured **ethanol**, and other **alcohols**; fuel mixtures containing 85 percent or more by volume of methanol, denatured ethanol, and other alcohols with **motor gasoline** or other fuels; **natural gas**; **liquefied petroleum gas (propane)**; **hydrogen**; **coal-derived liquid fuels**; fuels (other than alcohol) derived from biological materials (**biofuels** such as soy **diesel fuel**); **electricity** (including electricity from **solar energy**); and "... any other fuel the Secretary determines, by rule, is substantially not **petroleum** and would yield substantial energy security benefits and substantial environmental benefits." The term "alternative fuel" does not include alcohol or other blended portions of primarily petroleum-based fuels used as **oxygenates** or extenders, i.e., **MTBE**, **ETBE**, other ethers, and the 10-percent ethanol portion of **gasohol**.

**Alternative-fuel vehicle (AFV):** A vehicle designed to operate on an **alternative fuel** (e.g., compressed **natural gas**, **methane** blend, or **electricity**). The vehicle could be either a dedicated vehicle designed to operate exclusively on alternative fuel or a nondedicated vehicle designed to operate on alternative fuel and/or a traditional fuel.

**Anthracite:** The highest rank of **coal**; used primarily for residential and commercial space heating. It is a hard, brittle, and black lustrous coal, often referred to as hard coal, containing a high percentage of fixed carbon and a low percentage of volatile matter. The moisture content of fresh-mined anthracite generally is less than 15 percent. The heat content of anthracite ranges from 22 to 28 million **Btu** per **short ton** on a moist, mineral-matter-free basis. The heat content of anthracite coal consumed in the United States averages 25 million Btu per short ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter). **Note:** Since the 1980's, anthracite refuse or mine waste has been used for steam-electric power generation. This fuel typically has a heat content of 15 million Btu per ton or less.

**Anthropogenic:** Made or generated by a human or caused by human activity. The term is used in the context of global **climate change** to refer to gaseous emissions that are the result of human activities, as well as other potentially climate-altering activities, such as deforestation.

**Asphalt:** A dark brown-to-black cement-like material obtained by **petroleum** processing and containing bitumens as the predominant component; used primarily for road construction. It includes crude asphalt as well as the following finished products: cements, fluxes, the asphalt content of emulsions (exclusive of water), and petroleum distillates blended with asphalt to make cutback asphalts. **Note:** The conversion factor for asphalt is 5.5 barrels per short ton.

**ASTM:** The American Society for Testing and Materials.

**Aviation gasoline blending components:** **Naphthas** that will be used for blending or compounding into finished aviation gasoline (e.g., straight run gasoline, alkylate, reformate, benzene, toluene, and xylene). Excludes **oxygenates (alcohols, ethers)**, **butane**, and **natural gasoline**. Oxygenates are reported as **other hydrocarbons**, **hydrogen**, and oxygenates. See **Aviation gasoline, finished**.

**Aviation gasoline, finished:** A complex mixture of relatively volatile hydrocarbons with or without small quantities of additives, blended to form a fuel suitable for use in aviation reciprocating engines. Fuel specifications are provided in ASTM Specification D 910 and Military Specification MIL-G-5572. **Note:** Data on blending components are not counted in data on finished aviation gasoline.

**Barrel (petroleum):** A unit of volume equal to 42 U.S. Gallons.

**Base gas:** The quantity of **natural gas** needed to maintain adequate reservoir pressures and deliverability rates throughout the withdrawal season. Base gas usually is not withdrawn and remains in the reservoir. All natural gas native to a depleted reservoir is included in the base gas volume.

**Biodiesel:** A fuel typically made from soybean, canola, or other vegetable oils; animal fats; and recycled grease. It can serve as a substitute for **petroleum-derived diesel fuel** or **distillate fuel oil**. For U.S. Energy Information Administration

reporting, it is a fuel composed of mono-alkyl esters of long chain fatty acids derived from vegetable oils or animal fats, designated B100, and meeting the requirements of ASTM (American Society for Testing & Materials) D 6751.

**Biofuels:** Liquid fuels and blending components produced from **biomass** (plant) feedstocks, used primarily for transportation. See **Biodiesel** and **Fuel ethanol**.

**Biogenic:** Produced by biological processes of living organisms. **Note:** EIA uses the term “biogenic” to refer only to organic nonfossil material of biological origin.

**Biomass:** Organic nonfossil material of biological origin constituting a renewable energy source. See **Biodiesel**, **Biofuels**, **Biomass waste**, **Densified biomass**, **Fuel ethanol**, and **Wood and wood-derived fuels**.

**Biomass-based diesel fuel:** Biodiesel and other renewable **diesel fuel** or diesel fuel blending components derived from **biomass**, but excluding renewable diesel fuel coprocessed with petroleum feedstocks. See **Renewable diesel fuel (other)**.

**Biomass waste:** Organic non-fossil material of biological origin that is a byproduct or a discarded product. “Biomass waste” includes municipal solid waste from **biogenic** sources, landfill gas, sludge waste, agricultural crop byproducts, straw, and other **biomass** solids, liquids, and gases; but excludes **wood and wood-derived fuels** (including **black liquor**), **biofuels** feedstock, **biodiesel**, and **fuel ethanol**. **Note:** EIA “biomass waste” data also include energy crops grown specifically for energy production, which would not normally constitute waste.

**Bituminous coal:** A dense **coal**, usually black, sometimes dark brown, often with well-defined bands of bright and dull material, used primarily as fuel in steam-electric power generation, with substantial quantities also used for heat and power applications in manufacturing and to make **coke**. Bituminous coal is the most abundant coal in active U.S. mining regions. Its moisture content usually is less than 20 percent. The heat content of bituminous coal ranges from 21 to 30 million **Btu** per **short ton** on a moist, mineral-matter-free basis. The heat content of bituminous coal consumed in the United States averages 24 million Btu per short ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter).

**Black liquor:** A byproduct of the paper production process, alkaline spent liquor that can be used as a source of energy. Alkaline spent liquor is removed from the digesters in the process of chemically pulping wood. After evaporation, the residual “black” liquor is burned as a fuel in a recovery furnace that permits the recovery of certain basic chemicals.

**British thermal unit (Btu):** The quantity of heat required to raise the temperature of 1 pound of liquid water by 1 degree Fahrenheit at the temperature at which water has its greatest density (approximately 39 degrees Fahrenheit). See **Heat content**.

**Btu:** See **British thermal unit**.

**Btu conversion factor:** A factor for converting **energy** data between one unit of measurement and **British thermal units (Btu)**. Btu conversion factors are generally used to convert energy data from physical units of measure (such as **barrels**, **cubic feet**, or **short tons**) into the energy-equivalent measure of Btu. (See <http://www.eia.gov/totalenergy/data/monthly/#appendices> for further information on Btu conversion factors.)

**Butane (C<sub>4</sub>H<sub>10</sub>):** A straight-chain or branch-chain **hydrocarbon** extracted from **natural gas** or **refinery gas** streams, which is gaseous at standard temperature and pressure. It includes **isobutane** and **normal butane** and is designated in ASTM Specification D1835 and Gas Processors Association specifications for commercial butane.

**Butylene (C<sub>4</sub>H<sub>8</sub>):** An olefinic **hydrocarbon** recovered from refinery or petrochemical processes, which is gaseous at standard temperature and pressure. Butylene is used in the production of gasoline and various petrochemical products. See **Olefinic hydrocarbons (olefins)**.

**Capacity factor:** The ratio of the electrical energy produced by a generating unit for a given period of time to the electrical energy that could have been produced at continuous full-power operation during the same period.

**Carbon dioxide (CO<sub>2</sub>):** A colorless, odorless, non-poisonous gas that is a normal part of Earth's atmosphere. Carbon dioxide is a product of **fossil-fuel** combustion as well as other processes. It is considered a **greenhouse gas** as it traps

heat (infrared energy) radiated by the Earth into the atmosphere and thereby contributes to the potential for **global warming**. The **global warming potential** (GWP) of other greenhouse gases is measured in relation to that of carbon dioxide, which by international scientific convention is assigned a value of one (1).

**Chained dollars:** A measure used to express **real prices**. Real prices are those that have been adjusted to remove the effect of changes in the purchasing power of the dollar; they usually reflect buying power relative to a reference year. Prior to 1996, real prices were expressed in constant dollars, a measure based on the weights of goods and services in a single year, usually a recent year. In 1996, the U.S. Department of Commerce introduced the chained-dollar measure. The new measure is based on the average weights of goods and services in successive pairs of years. It is "chained" because the second year in each pair, with its weights, becomes the first year of the next pair. The advantage of using the chained-dollar measure is that it is more closely related to any given period and is therefore subject to less distortion over time.

**CIF:** See **Cost, insurance, freight**.

**Citygate:** A point or measuring station at which a distribution gas utility receives gas from a **natural gas** pipeline company or transmission system.

**Climate change:** A term used to refer to all forms of climatic inconsistency, but especially to significant change from one prevailing climatic condition to another. In some cases, "climate change" has been used synonymously with the term "**global warming**"; scientists, however, tend to use the term in a wider sense inclusive of natural changes in climate, including climatic cooling.

**Coal:** A readily combustible black or brownish-black rock whose composition, including inherent moisture, consists of more than 50 percent by weight and more than 70 percent by volume of carbonaceous material. It is formed from plant remains that have been compacted, hardened, chemically altered, and metamorphosed by heat and pressure over geologic time. See **Anthracite, Bituminous coal, Lignite, Subbituminous coal, Waste coal, and Coal synfuel**.

**Coal coke:** A solid carbonaceous residue derived from low-ash, low-sulfur **bituminous coal** from which the volatile constituents are driven off by baking in an oven at temperatures as high as 2,000 degrees Fahrenheit so that the fixed carbon and residual ash are fused together. Coke is used as a fuel and as a reducing agent in smelting iron ore in a blast furnace. Coke from coal is grey, hard, and porous and has a heating value of 24.8 million Btu per ton.

**Coal stocks:** Coal quantities that are held in storage for future use and disposition. **Note:** When coal data are collected for a particular reporting period (month, quarter, or year), coal stocks are commonly measured as of the last day of the period.

**Coal synfuel:** Coal-based solid fuel that has been processed by a **coal synfuel plant**; and coal-based fuels such as briquettes, pellets, or extrusions, which are formed from fresh or recycled coal and binding materials.

**Coal synfuel plant:** A plant engaged in the chemical transformation of **coal** into **coal synfuel**.

**Coke:** See **Coal coke** and **Petroleum coke**.

**Coking coal:** Bituminous coal suitable for making coke. See **Coal coke**.

**Combined heat and power (CHP) plant:** A plant designed to produce both heat and electricity from a single heat source. **Note:** This term is being used in place of the term "cogenerator" that was used by EIA in the past. CHP better describes the facilities because some of the plants included do not produce heat and power in a sequential fashion and, as a result, do not meet the legal definition of cogeneration specified in the Public Utility Regulatory Policies Act (PURPA).

**Commercial sector:** An energy-consuming sector that consists of service-providing facilities and equipment of: businesses; federal, state, and local governments; and other private and public organizations, such as religious, social, or fraternal groups. The commercial sector includes institutional living quarters. It also includes sewage treatment facilities. Common uses of energy associated with this sector include space heating, water heating, air conditioning, lighting, refrigeration, cooking, and running a wide variety of other equipment. **Note:** This sector includes generators that produce electricity and/or useful thermal output primarily to support the activities of the above-mentioned commercial establishments. See **End-use sectors** and **Energy-use sectors**.

**Completion:** The installation of permanent equipment for the production of oil or gas. If a well is equipped to produce only oil or gas from one zone or reservoir, the definition of a well (classified as an oil well or gas well) and the definition of a completion are identical. However, if a well is equipped to produce oil and/or gas separately from more than one reservoir, a well is not synonymous with a completion.

**Conventional hydroelectric power:** Hydroelectric power generated from flowing water that is not created by hydroelectric pumped storage.

**Conventional motor gasoline:** See **Motor gasoline conventional**.

**Conversion factor:** A factor for converting data between one unit of measurement and another (such as between **short tons** and **British thermal units**, or between **barrels** and gallons).

(See <http://www.eia.gov/totalenergy/data/monthly/#appendices>. See **Btu conversion factor** and **Thermal conversion factor**.)

**Cost, insurance, freight (CIF):** A sales transaction in which the seller pays for the transportation and insurance of the goods to the port of destination specified by the buyer.

**Crude oil:** A mixture of hydrocarbons that exists in liquid phase in natural underground reservoirs and remains liquid at atmospheric pressure after passing through surface separating facilities. Depending upon the characteristics of the crude stream, it may also include: (1) small amounts of hydrocarbons that exist in gaseous phase in natural underground reservoirs but are liquid at atmospheric pressure after being recovered from oil well (casing head) gas in lease separators and are subsequently commingled with the crude stream without being separately measured. Lease condensate recovered as a liquid from natural gas wells in lease or field separation facilities and later mixed into the crude stream is also included; (2) small amounts of nonhydrocarbons produced with the oil, such as sulfur and various metals; and (3) drip gases, and liquid hydrocarbons produced from tar sands, oil sands, gilsonite, and oil shale. Liquids produced at natural gas processing plants are excluded. Crude oil is refined to produce a wide array of petroleum products, including heating oils; gasoline, diesel and jet fuels; lubricants; asphalt; ethane, propane, and butane; and many other products used for their energy or chemical content.

**Crude oil f.o.b. price:** The crude oil price actually charged at the oil-producing country's port of loading. Includes deductions for any rebates and discounts or additions of premiums, where applicable. It is the actual price paid with no adjustment for credit terms.

**Crude oil (including lease condensate):** A mixture of hydrocarbons that exists in liquid phase in underground reservoirs and remains liquid at atmospheric pressure after passing through surface separating facilities. Included are lease condensate and liquid hydrocarbons produced from tar sands, gilsonite, and oil shale. Drip gases are also included, but topped crude oil (residual oil) and other unfinished oils are excluded. Where identifiable, liquids produced at natural gas processing plants and mixed with crude oil are likewise excluded.

**Crude oil landed cost:** The price of crude oil at the port of discharge, including charges associated with the purchase, transporting, and insuring of a cargo from the purchase point to the port of discharge. The cost does not include charges incurred at the discharge port (e.g., import tariffs or fees, wharfage charges, and demurrage).

**Crude oil refinery input:** The total crude oil put into processing units at refineries.

**Crude oil stocks:** Stocks of crude oil and lease condensate held at refineries, in pipelines, at pipeline terminals, and on leases.

**Crude oil used directly:** Crude oil consumed as fuel by crude oil pipelines and on crude oil leases.

**Crude oil well:** A well completed for the production of crude oil from one or more oil zones or reservoirs. Wells producing both crude oil and natural gas are classified as oil wells.

**Cubic foot (natural gas):** The amount of **natural gas** contained at standard temperature and pressure (60 degrees Fahrenheit and 14.73 pounds standard per square inch) in a cube whose edges are one foot long.

**Degree Day Normals:** Simple arithmetic averages of monthly or annual degree days over a long period of time (usually the 30-year period 1961–1990). The averages may be simple degree day normals or population-weighted degree day normals.

**Degree Days, Cooling (CDD):** A measure of how warm a location is over a period of time relative to a base temperature, most commonly specified as 65 degrees Fahrenheit. The measure is computed for each day by subtracting the base temperature (65 degrees) from the average of the day's high and low temperatures, with negative values set equal to zero. Each day's cooling degree days are summed to create a cooling degree day measure for a specified reference period. Cooling degree days are used in energy analysis as an indicator of air conditioning energy requirements or use.

**Degree Days, Heating (HDD):** A measure of how cold a location is over a period of time relative to a base temperature, most commonly specified as 65 degrees Fahrenheit. The measure is computed for each day by subtracting the average of the day's high and low temperatures from the base temperature (65 degrees), with negative values set equal to zero. Each day's heating degree days are summed to create a heating degree day measure for a specified reference period. Heating degree days are used in energy analysis as an indicator of space heating energy requirements or use.

**Degree Days, Population-weighted:** Heating or cooling degree days weighted by the population of the area in which the degree days are recorded. To compute state population-weighted degree days, each state is divided into from one to nine climatically homogeneous divisions, which are assigned weights based on the ratio of the population of the division to the total population of the state. Degree day readings for each division are multiplied by the corresponding population weight for each division and those products are then summed to arrive at the state population-weighted degree day figure. To compute national population-weighted degree days, the nation is divided into nine Census regions, each comprising from three to eight states, which are assigned weights based on the ratio of the population of the region to the total population of the nation. Degree day readings for each region are multiplied by the corresponding population weight for each region and those products are then summed to arrive at the national population-weighted degree day figure.

**Denaturant:** Petroleum, typically **natural gasoline** or **conventional motor gasoline**, added to **fuel ethanol** to make it unfit for human consumption. Fuel ethanol is denatured, usually prior to transport from the ethanol production facility, by adding 2 to 5 volume percent denaturant. See **Fuel ethanol** and **Fuel ethanol minus denaturant**.

**Densified biomass fuel:** Raw biomass, primarily wood, that has been condensed into a homogenously sized, energy-dense product, such as wood pellets, intended for use as fuel. It is mainly used for residential and commercial space heating and electricity generation.

**Design electrical rating, net:** The nominal net electrical output of a nuclear unit as specified by the electric utility for the purpose of plant design.

**Development well:** A well drilled within the proved area of an oil or gas reservoir to the depth of a stratigraphic horizon known to be productive.

**Diesel fuel:** A fuel composed of **distillate fuel oils** obtained in petroleum refining operation or blends of such distillate fuel oils with **residual fuel oil** used in motor vehicles. The boiling point and specific gravity are higher for diesel fuels than for gasoline.

**Direct use:** Use of electricity that (1) is self-generated, (2) is produced by either the same entity that consumes the power or an affiliate, and (3) is used in direct support of a service or industrial process located within the same facility or group of facilities that house the generating equipment. Direct use is exclusive of **station use**.

**Distillate fuel oil:** A general classification for one of the **petroleum** fractions produced in conventional distillation operations. It includes **diesel fuels** and fuel oils. Products known as No. 1, No. 2, and No. 4 diesel fuel are used in on-highway diesel engines, such as those in trucks and automobiles, as well as off-highway engines, such as those in railroad locomotives and agricultural machinery. Products known as No. 1, No. 2, and No. 4 fuel oils are used primarily for space heating and **electricity generation**.

**Dry hole:** An exploratory or development well found to be incapable of producing either oil or gas in sufficient quantities to justify completion as an oil or gas well.

**Dry natural gas production:** See **Natural gas (dry) production**.

**E85:** A fuel containing a mixture of 85 percent **ethanol** and 15 percent **motor gasoline**.

**Electric power plant:** A station containing prime movers, electric generators, and auxiliary equipment for converting mechanical, chemical, and/or fission energy into electric energy.

**Electric power sector:** An energy-consuming sector that consists of electricity-only and combined-heat-and-power (CHP) plants whose primary business is to sell electricity, or electricity and heat, to the public—i.e., North American Industry Classification System 22 plants. See also **Combined heat and power (CHP) plant**, **Electricity-only plant**, **Electric utility**, and **Independent power producer**.

**Electric utility:** Any entity that generates, transmits, or distributes **electricity** and recovers the cost of its generation, transmission or distribution assets and operations, either directly or indirectly, through cost-based rates set by a separate regulatory authority (e.g., State Public Service Commission), or is owned by a governmental unit or the consumers that the entity serves. Examples of these entities include: investor-owned entities, public power districts, public utility districts, municipalities, rural electric cooperatives, and state and federal agencies. Electric utilities may have Federal Energy Regulatory Commission approval for interconnection agreements and wholesale trade tariffs covering either cost-of-service and/or market-based rates under the authority of the Federal Power Act. See **Electric power sector**.

**Electrical system energy losses:** The amount of energy lost during generation, transmission, and distribution of electricity, including plant and unaccounted-for uses.

**Electricity:** A form of energy characterized by the presence and motion of elementary charged particles generated by friction, induction, or chemical change.

**Electricity generation:** The process of producing electric energy, or the amount of electric energy produced by transforming other forms of energy, commonly expressed in **kilowatthours** (kWh) or megawatthours (MWh).

**Electricity generation, gross:** The total amount of electric energy produced by generating units and measured at the generating terminal in **kilowatthours** (kWh) or megawatthours (MWh).

**Electricity generation, net:** The amount of **gross electricity generation** less **station use** (the **electric energy** consumed at the generating station(s) for station service or auxiliaries). **Note:** Electricity required for pumping at **hydroelectric pumped-storage** plants is regarded as electricity for station service and is deducted from gross generation.

**Electricity only plant:** A plant designed to produce electricity only. See also **Combined heat and power (CHP) plant**.

**Electricity retail sales:** The amount of electricity sold to customers purchasing electricity for their own use and not for resale.

**End use sectors:** The **residential**, **commercial**, **industrial**, and **transportation** sectors of the economy.

**Energy:** The capacity for doing work as measured by the capability of doing work (potential energy) or the conversion of this capability to motion (kinetic energy). Energy has several forms, some of which are easily convertible and can be changed to another form useful for work. Most of the world's convertible energy comes from fossil fuels that are burned to produce heat that is then used as a transfer medium to mechanical or other means in order to accomplish tasks. Electrical energy is usually measured in kilowatthours, while heat energy is usually measured in British thermal units.

**Energy consumption:** The use of energy as a source of heat or power or as an input in the manufacturing process.

**Energy service provider:** An energy entity that provides service to a retail or end-use customer.

**Energy use sectors:** A group of major energy-consuming components of U.S. society developed to measure and analyze energy use. The sectors most commonly referred to in EIA are: **residential**, **commercial**, **industrial**, **transportation**, and **electric power**.



**Ethane (C<sub>2</sub>H<sub>6</sub>):** A straight-chain saturated (paraffinic) **hydrocarbon** extracted predominantly from the natural gas stream, which is gaseous at standard temperature and pressure. It is a colorless gas that boils at a temperature of -127 degrees Fahrenheit. See **Paraffinic hydrocarbons**.

**Ethanol (C<sub>2</sub>H<sub>5</sub>OH):** A clear, colorless, flammable **alcohol**. Ethanol is typically produced biologically from **biomass** feedstocks such as agricultural crops and cellulosic residues from agricultural crops or wood. Ethanol can also be produced chemically from **ethylene**. See **Biomass**, **Fuel ethanol**, and **Fuel ethanol minus denaturant**.

**Ether:** A generic term applied to a group of organic chemical compounds composed of carbon, **hydrogen**, and oxygen, characterized by an oxygen atom attached to two carbon atoms (e.g., **methyl tertiary butyl ether**).

**Ethylene (C<sub>2</sub>H<sub>4</sub>):** An olefinic **hydrocarbon** recovered from refinery or petrochemical processes, which is gaseous at standard temperature and pressure. Ethylene is used as a petrochemical feedstock for many chemical applications and the production of consumer goods. See **Olefinic hydrocarbons (olefins)**.

**Exploratory well:** A well drilled to find and produce oil or gas in an area previously considered an unproductive area, to find a new reservoir in a known field (i.e., one previously found to be producing oil or gas in another reservoir), or to extend the limit of a known oil or gas reservoir.

**Exports:** Shipments of goods from within the 50 states and the District of Columbia to U.S. possessions and territories or to foreign countries.

**Federal Energy Administration (FEA):** A predecessor of the U.S. Energy Information Administration.

**Federal Energy Regulatory Commission (FERC):** The Federal agency with jurisdiction over interstate electricity sales, wholesale electric rates, hydroelectric licensing, natural gas pricing, oil pipeline rates, and gas pipeline certification. FERC is an independent regulatory agency within the U.S. Department of Energy and is the successor to the Federal Power Commission.

**Federal Power Commission (FPC):** The predecessor agency of the Federal Energy Regulatory Commission. The Federal Power Commission was created by an Act of Congress under the Federal Water Power Act on June 10, 1920. It was charged originally with regulating the electric power and natural gas industries. It was abolished on September 30, 1977, when the U.S. Department of Energy was created. Its functions were divided between the U.S. Department of Energy and the Federal Energy Regulatory Commission, an independent regulatory agency.

**First purchase price:** The price for domestic crude oil reported by the company that owns the crude oil the first time it is removed from the lease boundary.

**Flared natural gas:** Natural gas burned in flares on the base site or at gas processing plants.

**F.O.B. (free on board):** A sales transaction in which the seller makes the product available for pick up at a specified port or terminal at a specified price and the buyer pays for the subsequent transportation and insurance.

**Footage drilled:** Total footage for wells in various categories, as reported for any specified period, includes (1) the deepest total depth (length of well bores) of all wells drilled from the surface, (2) the total of all bypassed footage drilled in connection with reported wells, and (3) all new footage drilled for directional sidetrack wells. Footage reported for directional sidetrack wells does not include footage in the common bore, which is reported as footage for the original well. In the case of old wells drilled deeper, the reported footage is that which was drilled below the total depth of the old well.

**Former U.S.S.R.:** See **Union of Soviet Socialist Republics (U.S.S.R.)**.

**Fossil fuel:** An energy source formed in the Earth's crust from decayed organic material, such as **petroleum**, **coal**, and **natural gas**.

**Fossil fueled steam electric power plant:** An electricity generation plant in which the prime mover is a turbine rotated by high-pressure steam produced in a boiler by heat from burning fossil fuels.

**Fuel ethanol:** Ethanol intended for fuel use. Fuel ethanol in the United States must be anhydrous (less than 1 percent water). Fuel ethanol is denatured (made unfit for human consumption), usually prior to transport from the ethanol production facility, by adding 2 to 5 volume percent petroleum, typically **natural gasoline** or **conventional motor gasoline**. Fuel ethanol is used principally for blending in low concentrations with **motor gasoline** as an **oxygenate** or octane enhancer. In high concentrations, it is used to fuel **alternative-fuel vehicles** specially designed for its use. See **Alternative-fuel vehicle**, **Denaturant**, **E85**, **Ethanol**, **Fuel ethanol minus denaturant**, and **Oxygenates**.

**Fuel ethanol minus denaturant:** An unobserved quantity of anhydrous, **biomass**-derived, undenatured **ethanol** for fuel use. The quantity is obtained by subtracting the estimated **denaturant** volume from **fuel ethanol** volume. Fuel ethanol minus denaturant is counted as **renewable energy**, while denaturant is counted as **nonrenewable fuel**. See **Denaturant**, **Ethanol**, **Fuel ethanol**, **Nonrenewable fuels**, **Oxygenates**, and **Renewable energy**.

**Full power operation:** Operation of a nuclear generating unit at 100 percent of its design capacity. Full-power operation precedes commercial operation.

**Gasohol:** A blend of finished motor gasoline containing alcohol (generally ethanol but sometimes methanol) at a concentration between 5.7 percent and 10 percent by volume. See **Motor gasoline**, **oxygenated**.

**Gas well:** A well completed for production of natural gas from one or more gas zones or reservoirs. Such wells contain no completions for the production of crude oil.

**Geothermal energy:** Hot water or steam extracted from geothermal reservoirs in the earth's crust and used for geothermal heat pumps, water heating, or electricity generation.

**Global warming:** An increase in the near-surface temperature of the Earth. Global warming has occurred in the distant past as the result of natural influences, but the term is today most often used to refer to the warming some scientists predict will occur as a result of increased anthropogenic emissions of **greenhouse gases**. See **Climate change**.

**Global warming potential (GWP):** An index used to compare the relative radiative forcing of different gases without directly calculating the changes in atmospheric concentrations. GWPs are calculated as the ratio of the radiative forcing that would result from the emission of one kilogram of a **greenhouse gas** to that from the emission of one kilogram of **carbon dioxide** over a fixed period of time, such as 100 years.

**Greenhouse gases:** Those gases, such as water vapor, **carbon dioxide**, nitrous oxide, **methane**, hydrofluorocarbons (HFCs), perfluorocarbons (PFCs) and sulfur hexafluoride, that are transparent to solar (short-wave) radiation but opaque to long-wave (infrared) radiation, thus preventing long-wave radiant energy from leaving Earth's atmosphere. The net effect is a trapping of absorbed radiation and a tendency to warm the planet's surface.

**Gross domestic product (GDP):** The total value of goods and services produced by labor and property located in the United States. As long as the labor and property are located in the United States, the supplier (that is, the workers and, for property, the owners) may be either U.S. residents or residents of foreign countries.

**GT/IC:** Gas turbine and internal combustion plants.

**Heat content:** The amount of heat energy available to be released by the transformation or use of a specified physical unit of an energy form (e.g., a ton of coal, a barrel of oil, a kilowatthour of electricity, a cubic foot of natural gas, or a pound of steam). The amount of heat energy is commonly expressed in **British thermal units (Btu)**. **Note:** Heat content of combustible energy forms can be expressed in terms of either gross heat content (higher or upper heating value) or net heat content (lower heating value), depending upon whether or not the available heat energy includes or excludes the energy used to vaporize water (contained in the original energy form or created during the combustion process). The U.S. Energy Information Administration typically uses gross heat content values.

**Heat rate:** A measure of generating station thermal efficiency commonly stated as **Btu per kilowatthour**. **Note:** Heat rates can be expressed as either gross or net heat rates, depending whether the electricity output is gross or net generation. Heat rates are typically expressed as net heat rates.

**Hydrocarbon:** An organic chemical compound of **hydrogen** and carbon in the gaseous, liquid, or solid phase. The molecular structure of hydrocarbon compounds varies from the simplest (methane, the primary constituent of **natural gas**) to the very heavy and very complex.

**Hydrocarbon gas liquids (HGL):** A group of **hydrocarbons** including **ethane, propane, normal butane, isobutane**, and **natural gasoline**, and their associated **olefins**, including **ethylene, propylene, butylene**, and **isobutylene**. As marketed products, HGL represents all **natural gas liquids** (NGL) and olefins. EIA reports production of HGL from refineries (**liquefied refinery gases**, or LRG) and natural gas plants (**natural gas plant liquids**, or NGPL). Excludes liquefied natural gas (LNG). See **Olefinic hydrocarbons (olefins)**.

**Hydroelectric power:** The production of electricity from the kinetic energy of falling water.

**Hydroelectric power plant:** A plant in which the turbine generators are driven by falling water.

**Hydroelectric pumped storage:** Hydroelectricity that is generated during peak load periods by using water previously pumped into an elevated storage reservoir during off-peak periods when excess generating capacity is available to do so. When additional generating capacity is needed, the water can be released from the reservoir through a conduit to turbine generators located in a power plant at a lower level.

**Hydrogen (H):** The lightest of all gases, hydrogen occurs chiefly in combination with oxygen in water. It also exists in acids, bases, **alcohols, petroleum**, and **other hydrocarbons**.

**Imports:** Receipts of goods into the 50 states and the District of Columbia from U.S. possessions and territories or from foreign countries.

**Independent power producer:** A corporation, person, agency, authority, or other legal entity or instrumentality that owns or operates facilities for the generation of electricity for use primarily by the public, and that is not an **electric utility**.

**Industrial sector:** An **energy**-consuming sector that consists of all facilities and equipment used for producing, processing, or assembling goods. The industrial sector encompasses the following types of activity: manufacturing (**NAICS** codes 31-33); agriculture, forestry, fishing and hunting (NAICS code 11); mining, including oil and gas extraction (NAICS code 21); and construction (NAICS code 23). Overall energy use in this sector is largely for process heat and cooling and powering machinery, with lesser amounts used for facility heating, air conditioning, and lighting. Fossil fuels are also used as raw material inputs to manufactured products. **Note:** This sector includes **generators** that produce **electricity** and/or **useful thermal output** primarily to support the above-mentioned industrial activities. See **End use sectors** and **Energy use sectors**.

**Injections (natural gas):** **Natural gas** injected into storage reservoirs.

**Isobutane (C<sub>4</sub>H<sub>10</sub>):** A branch-chain saturated (paraffinic) **hydrocarbon** extracted from both **natural gas** and **refinery gas** streams, which is gaseous at standard temperature and pressure. It is a colorless gas that boils at a temperature of 11 degrees Fahrenheit. See **Paraffinic hydrocarbons**.

**Isobutylene (C<sub>4</sub>H<sub>8</sub>):** A branch-chain olefinic **hydrocarbon** recovered from refinery or petrochemical processes, which is gaseous at standard temperature and pressure. Isobutylene is used in the production of gasoline and various petrochemical products. See **Olefinic hydrocarbons (olefins)**.

**Isopentane (C<sub>5</sub>H<sub>12</sub>):** A saturated branched-chain **hydrocarbon** obtained by fractionation of **natural gasoline** or isomerization of normal pentane.

**Jet fuel:** A refined **petroleum** product used in jet aircraft engines. See **Jet fuel, Kerosene-type**, and **Jet fuel, Naphtha-type**.

**Jet fuel, kerosene-type:** A **kerosene**-based product having a maximum distillation temperature of 400 degrees Fahrenheit at the 10-percent recovery point and a final maximum boiling point of 572 degrees Fahrenheit and meeting ASTM Specification D 1655 and Military Specifications MIL-T-5624P and MIL-T-83133D (Grades JP-5 and JP-8). It is used for commercial and military turbo jet and turbo prop aircraft engines.

**Jet fuel, naphtha-type:** A fuel in the heavy **naphtha** boiling range having an average gravity of 52.8 degrees API, 20% to 90% distillation temperatures of 290 degrees to 470 degrees Fahrenheit, and meeting Military Specification MIL-T-5624L (Grade JP-4). It is used primarily for military turbojet and turboprop aircraft engines because it has a lower freeze point than other aviation fuels and meets engine requirements at high altitudes and speeds.

**Kerosene:** A light **petroleum** distillate that is used in space heaters, cook stoves, and water heaters and is suitable for use as a light source when burned in wick-fed lamps. Kerosene has a maximum distillation temperature of 400 degrees Fahrenheit at the 10-percent recovery point, a final boiling point of 572 degrees Fahrenheit, and a minimum flash point of 100 degrees Fahrenheit. Included are No. 1-K and No. 2-K, the two grades recognized by ASTM Specification D 3699 as well as all other grades of kerosene called range or stove oil, which have properties similar to those of No. 1 fuel oil. See **Jet fuel, kerosene-type**.

**Kilowatt:** A unit of electrical power equal to 1,000 **watts**.

**Kilowatthour (kWh):** A measure of electricity defined as a unit of work or energy, measured as 1 **kilowatt** (1,000 watts) of power expended for 1 hour. One kilowatthour is equivalent to 3,412 Btu. See **Watthour**.

**Landed costs:** The dollar-per-barrel price of crude oil at the port of discharge. Included are the charges associated with the purchase, transporting, and insuring of a cargo from the purchase point to the port of discharge. Not included are charges incurred at the discharge port (e.g., import tariffs or fees, wharfage charges, and demurrage charges).

**Lease and plant fuel:** **Natural gas** used in well, field, and lease operations (such as gas used in drilling operations, heaters, dehydrators, and field compressors) and used as fuel in natural gas processing plants.

**Lease condensate:** Light liquid **hydrocarbons** recovered from lease separators or field facilities at associated and non-associated **natural gas** wells. Mostly pentanes and heavier hydrocarbons. Normally enters the **crude oil** stream after production.

**Lignite:** The lowest rank of coal, often referred to as brown **coal**, used almost exclusively as fuel for steam-electric power generation. It is brownish-black and has a high inherent moisture content, sometimes as high as 45 percent. The heat content of lignite ranges from 9 to 17 million **Btu** per **short ton** on a moist, mineral-matter-free basis. The heat content of lignite consumed in the United States averages 13 million Btu per short ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter).

**Liquefied natural gas (LNG):** **Natural gas** (primarily methane) that has been liquefied by reducing its temperature to -260 degrees Fahrenheit at atmospheric pressure.

**Liquefied petroleum gases (LPG):** A group of **hydrocarbon** gases, primarily **propane**, **normal butane**, and **isobutane**, derived from crude oil refining or **natural gas** processing. These gases may be marketed individually or mixed. They can be liquefied through pressurization (without requiring cryogenic refrigeration) for convenience of transportation or storage. Excludes **ethane** and **olefins**. **Note:** In some EIA publications, LPG includes ethane and marketed refinery olefin streams, in accordance with definitions used prior to January 2014.

**Liquefied refinery gases (LRG):** **Hydrocarbon gas liquids** produced in refineries from processing of **crude oil** and **unfinished oils**. They are retained in the liquid state through pressurization and/or refrigeration. The reported categories include **ethane**, **propane**, **normal butane**, **isobutane**, and refinery **olefins** (**ethylene**, **propylene**, **butylene**, and **isobutylene**).

**Low power testing:** The period of time between a nuclear generating unit's initial fuel loading date and the issuance of its operating (full-power) license. The maximum level of operation during that period is 5 percent of the unit's design thermal rating.

**Lubricants:** Substances used to reduce friction between bearing surfaces or as process materials either incorporated into other materials used as processing aids in the manufacturing of other products or as carriers of other materials. Petroleum lubricants may be produced either from distillates or residues. Other substances may be added to impart or improve certain required properties. Excluded are byproducts of lubricating oil refining, such as aromatic extracts derived from solvent extraction or tars derived from deasphalting. Included are all grades of lubricating oils from spindle oil to cylinder oil and those used in greases. Lubricant categories are paraffinic and naphthenic.

**Marketed production (natural gas):** See **Natural gas marketed production**.

**Methane (CH<sub>4</sub>):** A colorless, flammable, odorless **hydrocarbon** gas which is the major component of **natural gas**. It is also an important source of hydrogen in various industrial processes. Methane is a greenhouse gas. See **Greenhouse gases**.

**Methanol (CH<sub>3</sub>OH):** A light, volatile alcohol eligible for gasoline blending. See **Motor gasoline blending** and **Oxygenates**.

**Methyl tertiary butyl ether (MTBE) ((CH<sub>3</sub>)<sub>3</sub>COCH<sub>3</sub>):** An **ether** intended for gasoline blending. See **Motor gasoline blending** and **Oxygenates**.

**Miscellaneous petroleum products:** All finished petroleum products not classified elsewhere—for example, petrolatum, lube refining byproducts (aromatic extracts and tars), absorption oils, ram-jet fuel, petroleum rocket fuels, synthetic natural gas feedstocks, and specialty oils.

**Motor gasoline blending components:** Naphtha (e.g., straight-run gasoline, alkylate, reformate, benzene, toluene, xylene) used for blending or compounding into finished motor gasoline. These components include reformulated gasoline blendstock (RBOB) but exclude oxygenates (alcohols, ethers), butane, and natural gasoline. **Note:** Oxygenates are reported as individual components and are included in the total for other hydrocarbons, hydrogens, and oxygenates.

**Motor gasoline, conventional:** **Finished motor gasoline** not included in the **oxygenated** or **reformulated** motor gasoline categories. **Note:** This category excludes reformulated gasoline blendstock for oxygenate blending (RBOB) as well as other blendstock. Conventional motor gasoline can be leaded or unleaded; regular, midgrade, or premium. See **Motor gasoline grades**.

**Motor gasoline (finished):** A complex mixture of relatively volatile **hydrocarbons** with or without small quantities of additives, blended to form a fuel suitable for use in spark-ignition engines. Motor gasoline, as defined in ASTM Specification D 4814 or Federal Specification VV-G-1690C, is characterized as having a boiling range of 122 to 158 degrees Fahrenheit at the 10 percent recovery point to 365 to 374 degrees Fahrenheit at the 90 percent recovery point. Motor gasoline includes conventional gasoline; all types of oxygenated gasoline, including **gasohol**; and reformulated gasoline, but excludes aviation gasoline. **Note:** Volumetric data on blending components, such as **oxygenates**, are not counted in data on finished motor gasoline until the blending components are blended into the gasoline. See **Motor gasoline, conventional**; **Motor gasoline, oxygenated**; and **Motor gasoline, reformulated**.

**Motor gasoline grades:** The classification of gasoline by octane ratings. Each type of gasoline (conventional, oxygenated, and reformulated) is classified by three grades: regular, midgrade, and premium. **Note:** Gasoline sales are reported by grade in accordance with their classification at the time of sale. In general, automotive octane requirements are lower at high altitudes. Therefore, in some areas of the United States, such as the Rocky Mountain States, the octane ratings for the gasoline grades may be 2 or more octane points lower.

**Regular Gasoline:** Gasoline having an antiknock index, i.e., octane rating, greater than or equal to 85 and less than **88**. **Note:** Octane requirements may vary by altitude. See **Motor gasoline grades**.

**Midgrade Gasoline:** Gasoline having an antiknock index, i.e., octane rating, greater than or equal to **88** and less than or equal to 90. **Note:** Octane requirements may vary by altitude. See **Motor gasoline grades**.

**Premium Gasoline:** Gasoline having an antiknock index, i.e., octane rating, greater than 90. **Note:** Octane requirements may vary by altitude. See **Motor gasoline grades**.

**Motor gasoline, oxygenated:** Finished motor gasoline, other than reformulated gasoline, having an oxygen content of 2.7 percent or higher by weight and required by the U.S. Environmental Protection Agency (EPA) to be sold in areas designated by EPA as carbon monoxide (CO) nonattainment areas. **Note:** Oxygenated gasoline excludes oxygenated fuels program reformulated gasoline (OPRG) and reformulated gasoline blendstock for oxygenate blending (RBOB). Data on gasohol that has at least 2.7 percent oxygen, by weight, and is intended for sale inside CO nonattainment areas are included in data on oxygenated gasoline. Other data on gasohol are included in data on conventional gasoline.

**Motor gasoline, reformulated:** Finished motor gasoline formulated for use in motor vehicles, the composition and properties of which meet the requirements of the reformulated gasoline regulations promulgated by the U.S. Environmental Protection Agency under Section 211(k) of the Clean Air Act. **Note:** This category includes oxygenated fuels program reformulated gasoline (OPRG) but excludes reformulated gasoline blendstock for oxygenate blending (RBOB).

**Motor gasoline retail prices:** Motor gasoline prices calculated each month by the Bureau of Labor Statistics (BLS) in conjunction with the construction of the Consumer Price Index (CPI). Those prices are collected in 85 urban areas selected to represent all urban consumers-about 80 percent of the total U.S. population. The service stations are selected initially, and on a replacement basis, in such a way that they represent the purchasing habits of the CPI population. Service stations in the current sample include those providing all types of service (i.e., full-, mini-, and self-service).

**Motor gasoline (total):** For stock level data, a sum including finished motor gasoline stocks plus stocks of motor gasoline blending components but excluding stocks of oxygenates.

**MTBE:** See **Methyl tertiary butyl ether**.

**NAICS (North American Industry Classification System):** A coding system developed jointly by the United States, Canada, and Mexico to classify businesses and industries according to the type of economic activity in which they are engaged. NAICS replaces the Standard Industrial Classification (SIC) codes. For additional information on NAICS, go to <http://www.census.gov/eos/www/naics/>.

**Naphtha:** A generic term applied to a refined or partially refined **petroleum** fraction with an approximate boiling range between 122 degrees and 400 degrees Fahrenheit.

**Natural Gas:** A gaseous mixture of **hydrocarbon** compounds, primarily **methane**, used as a fuel for **electricity generation** and in a variety of ways in buildings, and as raw material input and fuel for industrial processes.

**Natural gas, dry:** **Natural gas** which remains after: (1) the liquefiable **hydrocarbon** portion has been removed from the gas stream (i.e., gas after lease, field, and/or plant separation); and (2) any volumes of **nonhydrocarbon gases** have been removed where they occur in sufficient quantity to render the gas unmarketable. **Note:** Dry natural gas is also known as consumer-grade natural gas. The parameters for measurement are cubic feet at 60 degrees Fahrenheit and 14.73 pounds per square inch absolute.

**Natural gas (dry) production:** The process of producing consumer-grade **natural gas**. Natural gas withdrawn from reservoirs is reduced by volumes used at the production (lease) site and by processing losses. Volumes used at the production site include (1) the volume returned to reservoirs in cycling, **repressuring** of oil reservoirs, and conservation operations; and (2) **vented natural gas** and **flared natural gas**. Processing losses include (1) **nonhydrocarbon gases** (e.g., water vapor, carbon dioxide, helium, hydrogen sulfide, and nitrogen) removed from the gas stream; and (2) gas converted to liquid form, such as **lease condensate** and **natural gas plant liquids**. Volumes of dry gas withdrawn from gas storage reservoirs are not considered part of production. Dry natural gas production equals **natural gas marketed production** less **natural gas plant liquids** production.

**Natural gas liquids (NGL):** A group of **hydrocarbons** including **ethane**, **propane**, **normal butane**, **isobutane**, and **natural gasoline**. Generally include **natural gas plant liquids** and all **liquefied refinery gases** except **olefins**. See **Paraffinic hydrocarbons**.

**Natural gas marketed production:** Gross withdrawals of **natural gas** from production reservoirs, less gas used for reservoir **repressuring**; **nonhydrocarbon gases** removed in treating and processing operations; and quantities of **vented natural gas** and **flared natural gas**.

**Natural gas plant liquids (NGPL):** Those **hydrocarbons** in **natural gas** that are separated as liquids at natural gas processing, fractionating, and cycling plants. Products obtained include **ethane**, **liquefied petroleum gases** (**propane**, **normal butane** and **isobutane**), and **natural gasoline**. Component products may be fractionated or mixed. **Lease condensate** and **plant condensate** are excluded. **Note:** Some EIA publications categorize NGPL production as field production, in accordance with definitions used prior to January 2014.

**Natural gas wellhead price:** The **wellhead price** of **natural gas** is calculated by dividing the total reported value at the wellhead by the total quantity produced as reported by the appropriate agencies of individual producing states and the U.S. Minerals Management Service. The price includes all costs prior to shipment from the lease, including gathering and compression costs, in addition to state production, severance, and similar charges.

**Natural gasoline:** A commodity product commonly traded in **natural gas liquids** (NGL) markets that comprises liquid **hydrocarbons** (mostly pentanes and hexanes) and generally remains liquid at ambient temperatures and atmospheric pressure. Natural gasoline is equivalent to **pentanes plus**.

**Net summer capacity:** The maximum output, commonly expressed in **kilowatts** (kW) or megawatts (MW), that generating equipment can supply to system load, as demonstrated by a multi-hour test, at the time of summer peak demand (period of June 1 through September 30). This output reflects a reduction in capacity due to electricity use for station service or auxiliaries.

**Neutral zone:** A 6,200 square-mile area shared equally between Kuwait and Saudi Arabia under a 1992 agreement. The Neutral zone contains an estimated 5 billion barrels of oil and 8 trillion cubic feet of natural gas.

**Nominal dollars:** A measure used to express **nominal price**.

**Nominal price:** The price paid for a product or service at the time of the transaction. Nominal prices are those that have not been adjusted to remove the effect of changes in the purchasing power of the dollar; they reflect buying power in the year in which the transaction occurred.

**Non-biomass waste:** Material of non-biological origin that is a byproduct or a discarded product. "Non-biomass waste" includes municipal solid waste from non-biogenic sources, such as plastics, and tire-derived fuels.

**Non-combustion use:** Fossil fuels (coal, natural gas, and petroleum products) that are not burned to release energy and instead used directly as construction materials, chemical, feedstocks, lubricants, solvents, waxes, and other products.

**Nonhydrocarbon gases:** Typical nonhydrocarbon gases that may be present in reservoir **natural gas** are **carbon dioxide**, helium, hydrogen sulfide, and nitrogen.

**Nonrenewable fuels:** Fuels that cannot be easily made or "renewed," such as **crude oil**, **natural gas**, and **coal**.

**Normal butane (C<sub>4</sub>H<sub>10</sub>):** A straight-chain saturated (paraffinic) **hydrocarbon** extracted from both **natural gas** and **refinery gas** streams, which is gaseous at standard temperature and pressure. It is a colorless gas that boils at a temperature of 31 degrees Fahrenheit. See **Paraffinic hydrocarbons**.

**Nuclear electric power (nuclear power):** Electricity generated by the use of the thermal energy released from the fission of nuclear fuel in a reactor.

**Nuclear electric power plant:** A single-unit or multiunit facility in which heat produced in one or more reactors by the fissioning of nuclear fuel is used to drive one or more steam turbines.

**Nuclear reactor:** An apparatus in which a nuclear fission chain reaction can be initiated, controlled, and sustained at a specific rate. A reactor includes fuel (fissionable material), moderating material to control the rate of fission, a heavy-walled pressure vessel to house reactor components, shielding to protect personnel, a system to conduct heat away from the reactor, and instrumentation for monitoring and controlling the reactor's systems.

**OECD:** See **Organization for Economic Cooperation and Development**.

**Offshore:** That geographic area that lies seaward of the coastline. In general, the coastline is the line of ordinary low water along with that portion of the coast that is in direct contact with the open sea or the line marking the seaward limit of inland water.

**Oil:** See **Crude oil**.

**Olefinic hydrocarbons (olefins):** Unsaturated **hydrocarbon** compounds with the general formula C<sub>n</sub>H<sub>2n</sub> containing at least one carbon-to-carbon double-bond. Olefins are produced at crude oil refineries and petrochemical plants and are

not naturally occurring constituents of oil and natural gas. Sometimes referred to as alkenes or unsaturated hydrocarbons. Excludes aromatics.

**Olefins:** See **Olefinic hydrocarbons (olefins)**.

**OPEC:** See **Organization of the Petroleum Exporting Countries**.

**Operable unit (nuclear):** In the United States, a nuclear generating unit that has completed low-power testing and been issued a full-power operating license by the Nuclear Regulatory Commission, or equivalent permission to operate.

**Organization for Economic Cooperation and Development (OECD):** An international organization helping governments tackle the economic, social and governance challenges of a globalized economy. Its membership comprises about 30 member countries. With active relationships with some 70 other countries, non-governmental organizations (NGOs) and civil society, it has a global reach. For details about the organization, see <http://www.oecd.org>.

**Organization of the Petroleum Exporting Countries (OPEC):** An intergovernmental organization whose stated objective is to "coordinate and unify the petroleum policies of member countries." It was created at the Baghdad Conference on September 10–14, 1960. Current and former members (with years of membership) include Algeria (1969 forward), Angola (2007 forward), Congo-Brazzaville (2018 forward), Ecuador (1973–1992 and 2007–2019), Equatorial Guinea (2017 forward), Gabon (1974–1994 and 2016 forward), Indonesia (1962–2008 and 2016), Iran (1960 forward), Iraq (1960 forward), Kuwait (1960 forward), Libya (1962 forward), Nigeria (1971 forward), Qatar (1961–2018), Saudi Arabia (1960 forward), United Arab Emirates (1967 forward), and Venezuela (1960 forward).

**Other energy losses:** Energy losses throughout the energy system as they are consumed, usually in the form of heat, that are not separately identified by U.S. Energy Information Administration. Examples include heat lost in the process of burning motor gasoline to move vehicles or in electricity used to power a lightbulb.

**Other hydrocarbons:** Materials received by a refinery and consumed as a raw material. Includes hydrogen, coal tar derivatives, gilsonite. Excludes **natural gas** used for fuel or **hydrogen** feedstock.

**Oxygenates:** Substances which, when added to gasoline, increase the amount of oxygen in that gasoline blend. **Ethanol**, **Methyl Tertiary Butyl Ether (MTBE)**, Ethyl Tertiary Butyl Ether (ETBE), and methanol are common oxygenates.

**PAD Districts or PADD:** Petroleum Administration for Defense Districts. Geographic aggregations of the 50 states and the District of Columbia into five districts for the Petroleum Administration for Defense in 1950. The districts were originally instituted for economic and geographic reasons as Petroleum Administration for War (PAW) Districts, which were established in 1942.

**Petroleum Administration for Defense District (PADD):** The 50 U.S. states and the District of Columbia are divided into five districts, with PADD 1 further split into three subdistricts. PADDs 6 and 7 encompass U.S. territories. The PADDs include the states and territories listed below:

**PADD 1 (East Coast).**

**PADD 1A (New England):** Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, and Vermont.

**PADD 1B (Central Atlantic):** Delaware, District of Columbia, Maryland, New Jersey, New York, and Pennsylvania.

**PADD 1C (Lower Atlantic):** Florida, Georgia, North Carolina, South Carolina, Virginia, and West Virginia.

**PADD 2 (Midwest):** Illinois, Indiana, Iowa, Kansas, Kentucky, Michigan, Minnesota, Missouri, Nebraska, North Dakota, Ohio, Oklahoma, South Dakota, Tennessee, and Wisconsin.

**PADD 3 (Gulf Coast):** Alabama, Arkansas, Louisiana, Mississippi, New Mexico, and Texas.

**PADD 4 (Rocky Mountain):** Colorado, Idaho, Montana, Utah, and Wyoming.

**PADD 5 (West Coast):** Alaska, Arizona, California, Hawaii, Nevada, Oregon, and Washington.

**PADD 6:** U.S. Virgin Islands and Puerto Rico.

**PADD 7:** Guam, American Samoa and the Northern Mariana Islands Territory.

**Paraffinic hydrocarbons:** Saturated **hydrocarbon** compounds with the general formula  $C_nH_{2n+2}$  containing only single bonds. Sometimes referred to as alkanes or **natural gas liquids**.

**Pentanes plus:** A mixture of liquid **hydrocarbons**, mostly pentanes and heavier, extracted from **natural gas** in a gas processing plant. Pentanes plus is equivalent to **natural gasoline**.



**Petrochemical feedstocks:** Chemical feedstocks derived from refined or partially refined **petroleum** fractions, principally for use in the manufacturing of chemicals, synthetic rubber, and a variety of plastics.

**Petroleum:** A broadly defined class of liquid hydrocarbon mixtures. Included are crude oil, lease condensate, unfinished oils, refined products obtained from the processing of crude oil, and natural gas plant liquids. **Note:** Volumes of finished petroleum products include nonhydrocarbon compounds, such as additives and detergents, after they have been blended into the products.

**Petroleum coke:** A residue high in carbon content and low in **hydrogen** that is the final product of thermal decomposition in the condensation process in cracking. This product is reported as marketable coke or catalyst coke. The conversion is 5 barrels (of 42 U.S. gallons each) per short ton. See **Petroleum coke, Catalyst** and **Petroleum coke, marketable**.

**Petroleum coke, catalyst:** The carbonaceous residue that is deposited on the catalyst used in many catalytic operations (e.g., catalytic cracking). Carbon is deposited on the catalyst, thus deactivating the catalyst. The catalyst is reactivated by burning off the carbon producing heat and **carbon dioxide (CO<sub>2</sub>)**. The carbonaceous residue is not recoverable as a product. See **Petroleum coke**.

**Petroleum coke, marketable:** Those grades of coke produced in delayed or fluid cokers that may be recovered as relatively pure carbon. Marketable petroleum coke may be sold as is or further purified by calcining. See **Petroleum coke**.

**Petroleum consumption:** See **Products supplied (petroleum)**.

**Petroleum imports:** Imports of petroleum into the 50 states and the District of Columbia from foreign countries and from Puerto Rico, the Virgin Islands, and other U.S. territories and possessions. Included are imports for the Strategic Petroleum Reserve and withdrawals from bonded warehouses for onshore consumption, offshore bunker use, and military use. Excluded are receipts of foreign petroleum into bonded warehouses and into U.S. territories and U.S. Foreign Trade Zones.

**Petroleum products:** Products obtained from the processing of crude oil (including lease condensate), natural gas, and other hydrocarbon compounds. Petroleum products include unfinished oils, hydrocarbon gas liquids, aviation gasoline, motor gasoline, naphtha-type jet fuel, kerosene-type jet fuel, kerosene, distillate fuel oil, residual fuel oil, petrochemical feedstocks, special naphthas, lubricants, waxes, petroleum coke, asphalt, road oil, still gas, and miscellaneous products.

**Petroleum stocks, primary:** For individual products, quantities that are held at refineries, in pipelines, and at bulk terminals that have a capacity of 50,000 barrels or more, or that are in transit thereto. Stocks held by product retailers and resellers, as well as tertiary stocks held at the point of consumption, are excluded. Stocks of individual products held at gas processing plants are excluded from individual product estimates but are included in other oils estimates and total.

**Pipeline fuel:** Gas consumed in the operation of pipelines, primarily in compressors.

**Plant condensate:** Liquid **hydrocarbons** recovered at inlet separators or scrubbers in **natural gas** processing plants at atmospheric pressure and ambient temperatures. Mostly pentanes and heavier hydrocarbons.

**Primary energy:** **Energy** in the form that it is first accounted for in a statistical energy balance, before any transformation to secondary or tertiary forms of energy. For example, **coal** can be converted to synthetic gas, which can be converted to **electricity**; in this example, coal is primary energy, synthetic gas is secondary energy, and electricity is tertiary energy. See **Primary energy production** and **Primary energy consumption**.

**Primary energy consumption:** Consumption of **primary energy**. The U.S. Energy Information Administration includes the following in U.S. primary energy consumption: coal consumption; coal coke net imports; **petroleum consumption (petroleum products supplied)**; **dry natural gas**—excluding **supplemental gaseous fuels**—consumption; **nuclear electricity net generation** (converted to Btu using the nuclear plants **heat rate**); **conventional hydroelectricity** net generation (converted to Btu using the average heat rate of fossil-fuel fired plants); **geothermal** electricity net generation (converted to Btu using the average annual heat rate of fossil-fueled fired plants ), geothermal heat pump energy and geothermal direct-use energy; **solar thermal** and **photovoltaic** electricity net generation (converted to Btu

using the average annual heat rate of fossil-fueled fired plants), and solar thermal direct-use energy; wind electricity net generation (converted to Btu using the average annual heat rate of fossil-fueled fired plants); **wood and wood-derived fuels** consumption; **biomass waste** consumption; **fuel ethanol** and **biodiesel** consumption; losses and co-products from the production of fuel ethanol and biodiesel; and electricity net imports (converted to Btu using the electricity heat content of 3,412 Btu per kilowatthour). Primary energy consumption includes all non-combustion use of fossil fuels. Primary energy consumption also includes **other energy losses** throughout the energy system. See **Total energy consumption**. Energy sources produced from other energy sources—e.g. Coal coke from coal—are included in primary energy consumption only if their energy content has not already been included as part of the original energy source. As a result, U.S. primary energy consumption does include net imports of coal coke, but it does not include the coal coke produced from domestic coal.

**Primary energy production:** Production of **primary energy**. The U.S. Energy Information Administration includes the following in U.S. primary energy production: **coal** production, **waste coal** supplied, and coal refuse recovery; **crude oil** and **lease condensate** production; **natural gas plant liquids** production; **dry natural gas**—excluding **supplemental gaseous fuels**— production; **nuclear electricity net generation** (converted to **Btu** using the nuclear plants **heat rate**); **conventional hydroelectricity** net generation (converted to Btu using the fossil-fueled plants heat rate); **geothermal** electricity net generation (converted to Btu using the fossil-fueled plants heat rate), and geothermal heat pump energy and geothermal direct use energy; **solar thermal** and **photovoltaic** electricity net generation (converted to Btu using the fossil-fueled plants heat rate), and solar thermal direct use energy; **wind** electricity net generation (converted to Btu using the fossil-fueled plants heat rate); **wood and wood-derived fuels** production; **biomass waste** consumption; and **biofuels** feedstock.

**Prime mover:** The engine, turbine, water wheel, or similar machine that drives an electric generator; or, for reporting purposes, a device that converts energy to electricity directly.

**Product supplied (petroleum):** Approximately represents consumption of petroleum products because it measures the disappearance of these products from primary sources, i.e., refineries, natural gas-processing plants, blending plants, pipelines, and bulk terminals. In general, product supplied of each product in any given period is computed as follows: field production, plus refinery production, plus imports, plus unaccounted-for crude oil (plus net receipts when calculated on a PAD District basis) minus stock change, minus crude oil losses, minus refinery inputs, and minus exports.

**Propane (C<sub>3</sub>H<sub>8</sub>):** A straight-chain saturated (paraffinic) **hydrocarbon** extracted from **natural gas** or **refinery gas** streams, which is gaseous at standard temperature and pressure. It is a colorless gas that boils at a temperature of -44 degrees Fahrenheit. It includes all products designated in ASTM Specification D1835 and Gas Processors Association specifications for commercial (HD-5) propane. See **Paraffinic hydrocarbons**.

**Propylene (C<sub>3</sub>H<sub>6</sub>):** An olefinic **hydrocarbon** recovered from refinery or petrochemical processes, which is gaseous at standard temperature and pressure. Propylene is an important petrochemical feedstock. See **Olefinic hydrocarbons (olefins)**.

**Real dollars:** These are dollars that have been adjusted for inflation.

**Real price:** A price that has been adjusted to remove the effect of changes in the purchasing power of the dollar. Real prices, which are expressed in constant dollars, usually reflect buying power relative to a base year.

**Refiner acquisition cost of crude oil:** The cost of crude oil to the refiner, including transportation and fees. The composite cost is the weighted average of domestic and imported crude oil costs.

**Refinery and blender net inputs:** Raw materials, **unfinished oils**, and blending components processed at refineries, or blended at refineries or petroleum storage terminals to produce finished **petroleum products**. Included are gross inputs of **crude oil**, **natural gas liquids**, other **hydrocarbon** raw materials, **hydrogen**, **oxygenates** (excluding **fuel ethanol**), and renewable fuels (including fuel ethanol). Also included are net inputs of unfinished oils, **motor gasoline blending components**, and **aviation gasoline blending components**. Net inputs are calculated as gross inputs minus gross production. Negative net inputs indicate gross inputs are less than gross production. Examples of negative net inputs include reformulated gasoline blendstock for oxygenate blending (RBOB) produced at refineries for shipment to

blending terminals, and unfinished oils produced and added to inventory in advance of scheduled maintenance of a refinery crude oil distillation unit.

**Refinery and blender net production:** Liquefied refinery gases, and finished **petroleum products** produced at a **refinery** or petroleum storage terminal blending facility. Net production equals gross production minus gross inputs. Negative net production indicates gross production is less than gross inputs for a finished petroleum product. Examples of negative net production include reclassification of one finished product to another finished product, or reclassification of a finished product to **unfinished oils** or blending components.

**Refinery gas:** **Still gas** consumed as refinery fuel.

**Refinery (petroleum):** An installation that manufactures finished petroleum products from crude oil, unfinished oils, natural gas liquids, other hydrocarbons, and alcohol.

**Refuse mine:** A surface site where **coal** is recovered from previously mined coal. It may also be known as a silt bank, culm bank, refuse bank, slurry dam, or dredge operation.

**Refuse recovery:** The recapture of **coal** from a **refuse mine** or the coal recaptured by that process. The resulting product has been cleaned to reduce the concentration of noncombustible materials.

**Renewable diesel fuel:** See **Biomass-based diesel fuel** and **Renewable diesel fuel (other)**.

**Renewable diesel fuel (other):** **Diesel fuel** and diesel fuel blending components produced from renewable sources that are coprocessed with **petroleum** feedstocks and meet requirements of advanced biofuels. **Note:** This category "other" pertains to the petroleum supply data system. See **Biomass-based diesel fuel**.

**Renewable energy:** Energy obtained from sources that are essentially inexhaustible (unlike, for example, the **fossil fuels**, of which there is a finite supply). Renewable sources of energy include **conventional hydroelectric power**, **biomass**, **geothermal**, **solar**, and **wind**.

**Renewable fuels except fuel ethanol:** See **Biomass-based diesel fuel**, **Renewable diesel fuel (other)**, and **Renewable fuels (other)**.

**Renewable fuels (other):** Fuels and fuel blending components, except **biomass-based diesel fuel**, **renewable diesel fuel (other)**, and **fuel ethanol**, produced from renewable biomass. **Note:** This category "other" pertains to the petroleum supply data system.

**Repressuring:** The injection of a pressurized fluid (such as air, gas, or water) into oil and gas reservoir formations to effect greater ultimate recovery.

**Residential sector:** An energy-consuming sector that consists of living quarters for private households. Common uses of energy associated with this sector include space heating, water heating, air conditioning, and lighting, refrigeration, cooking, and running a variety of other appliances. The residential sector excludes institutional living quarters. See **End-use sectors** and **Energy-use sectors**.

**Residual fuel oil:** A general classification for the heavier oils, known as No. 5 and No. 6 fuel oils, that remain after the **distillate fuel oils** and lighter **hydrocarbons** are distilled away in refinery operations. It conforms to ASTM Specifications D 396 and D 975 and Federal Specification VV-F-815C. No. 5, a residual fuel oil of medium viscosity, is also known as Navy Special and is defined in Military Specification MIL-F-859E, including Amendment 2 (NATO Symbol F-770). It is used in steam-powered vessels in government service and inshore power plants. No. 6 fuel oil includes Bunker C fuel oil and is used for the production of electric power, space heating, vessel bunkering, and various industrial purposes.

**Road oil:** Any heavy petroleum oil, including residual asphaltic oil used as a dust palliative and surface treatment on roads and highways. It is generally produced in six grades, from 0, the most liquid, to 5, the most viscous.

**Rotary rig:** A machine used for drilling wells that employs a rotating tube attached to a bit for boring holes through rock.

**Short ton (coal):** A unit of weight equal to 2,000 pounds.

**SIC (Standard Industrial Classification):** A set of codes developed by the U.S. Office of Management and Budget which categorizes industries into groups with similar economic activities. Replaced by **NAICS (North American Industry Classification System)**.

**Small-scale:** Generators at a site that has a total generating nameplate capacity of less than 1 megawatt (MW).

**Solar energy:** See **Solar photovoltaic (PV) energy** and **Solar thermal energy**.

**Solar photovoltaic (PV) energy:** **Energy**, radiated by the sun that is converted into direct-current electricity by solar photovoltaic cells. Examples of solar PV technologies include solar panels on residential and commercial rooftops (generally small-scale solar PV energy) and mirrors or dishes that concentrate solar rays onto solar PV panels (concentrating PV or CPV). Utility-scale solar PV electric generation typically relies on installations of solar PV panels on or near the ground (solar farms).

**Solar thermal energy:** Energy, radiated by the sun that is converted into electricity or heat by means of solar concentrating collectors. Examples of solar thermal energy technologies include pool heaters, dark water bladders, or thermal panels (generally small-scale solar thermal energy). Utility-scale solar thermal electric generation typically relies on a large array of mirrors to heat fluids and turn a turbine, which generates electricity.

**Special naphthas:** All finished products within the naphtha boiling range that are used as paint thinners, cleaners, or solvents. These products are refined to a specified flash point. Special naphthas include all commercial hexane and cleaning solvents conforming to ASTM Specification D1836 and D484, respectively. Naphthas to be blended or marketed as motor gasoline or aviation gasoline, or that are to be used as petrochemical and synthetic natural gas (SNG) feedstocks are excluded.

**Station use:** Energy that is used to operate an **electric power plant**. It includes energy consumed for plant lighting, power, and auxiliary facilities, regardless of whether the energy is produced at the plant or comes from another source.

**Steam coal:** All nonmetallurgical coal.

**Steam-electric power plant:** A plant in which the prime mover is a steam turbine. The steam used to drive the turbine is produced in a boiler where fossil fuels are burned.

**Still gas:** Any form or mixture of gases produced in refineries by distillation, cracking, reforming, and other processes. The principal constituents are **methane** and **ethane**. May contain **hydrogen** and small/trace amounts of other gases. Still gas is typically consumed as refinery fuel or used as petrochemical feedstock. Still gas burned for refinery fuel may differ in composition from marketed still gas sold to other users. See **Refinery gas**.

**Stocks:** See **Coal stocks**, **Crude oil stocks**, or **Petroleum stocks, primary**.

**Strategic Petroleum Reserve (SPR):** Petroleum stocks maintained by the federal Government for use during periods of major supply interruption.

**Subbituminous coal:** A **coal** whose properties range from those of **lignite** to those of **bituminous coal** and used primarily as fuel for steam-electric power generation. It may be dull, dark brown to black, soft and crumbly, at the lower end of the range, to bright, jet black, hard, and relatively strong, at the upper end. Subbituminous coal contains 20 to 30 percent inherent moisture by weight. The heat content of subbituminous coal ranges from 17 to 24 million **Btu** per **short ton** on a moist, mineral-matter-free basis. The heat content of subbituminous coal consumed in the United States averages 17 to 18 million Btu per ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter).

**Supplemental gaseous fuels:** Synthetic **natural gas**, **propane**-air, coke oven gas, **still gas (refinery gas)**, **biomass** gas, air injected for Btu stabilization, and manufactured gas commingled and distributed with natural gas.

**Synthetic natural gas (SNG):** (Also referred to as substitute natural gas) A manufactured product, chemically similar in most respects to **natural gas**, resulting from the conversion or reforming of **hydrocarbons** that may easily be substituted for or interchanged with pipeline-quality natural gas.

**Thermal conversion factor:** A factor for converting data between physical units of measure (such as **barrels**, **cubic feet**, or **short tons**) and thermal units of measure (such as **British thermal units**, calories, or joules); or for converting data between different thermal units of measure. See **Btu conversion factor**.

**Total energy consumption:** **Primary energy consumption** in the **end-use sectors**, plus **electricity retail sales** and **electrical system energy losses**. Also includes **other energy losses** throughout the energy system.

**Transportation sector:** An energy-consuming sector that consists of all vehicles whose primary purpose is transporting people and/or goods from one physical location to another. Included are automobiles; trucks; buses; motorcycles; trains, subways, and other rail vehicles; aircraft; and ships, barges, and other waterborne vehicles. Vehicles whose primary purpose is not transportation (e.g., construction cranes and bulldozers, farming vehicles, and warehouse tractors and forklifts) are classified in the sector of their primary use. See **End-use sectors** and **Energy-use sectors**.

**Underground storage:** The storage of **natural gas** in underground reservoirs at a different location from which it was produced.

**Unfinished oils:** All oils requiring further processing, except those requiring only mechanical blending. Unfinished oils are produced by partial refining of **crude oil** and include **naphthas** and lighter oils, **kerosene** and light gas oils, heavy gas oils, and residuum.

**Unfractionated streams:** Mixtures of unsegregated **natural gas liquids** components, excluding those in **plant condensate**. This product is extracted from **natural gas**.

**Union of Soviet Socialist Republics (U.S.S.R.):** A political entity that consisted of 15 constituent republics: Armenia, Azerbaijan, Belarus, Estonia, Georgia, Kazakhstan, Kyrgyzstan, Latvia, Lithuania, Moldova, Russia, Tajikistan, Turkmenistan, Ukraine, and Uzbekistan. The U.S.S.R. ceased to exist as of December 31, 1991.

**United States:** The 50 states and the District of Columbia. **Note:** The United States has varying degrees of jurisdiction over a number of territories and other political entities outside the 50 states and the District of Columbia, including Puerto Rico, the U.S. Virgin Islands, Guam, American Samoa, Johnston Atoll, Midway Islands, Wake Island, and the Northern Mariana Islands. EIA data programs may include data from some or all of these areas in U.S. totals. For these programs, data products will contain notes explaining the extent of geographic coverage included under the term "United States."

**Uranium:** A heavy, naturally radioactive, metallic element (atomic number 92). Its two principally occurring isotopes are uranium-235 and uranium-238. Uranium-235 is indispensable to the nuclear industry because it is the only isotope existing in nature, to any appreciable extent, that is fissionable by thermal neutrons. Uranium-238 is also important because it absorbs neutrons to produce a radioactive isotope that subsequently decays to the isotope plutonium-239, which also is fissionable by thermal neutrons.

**Uranium concentrate:** A yellow or brown powder obtained by the milling of uranium ore, processing of in situ leach mining solutions, or as a byproduct of phosphoric acid production. See **Uranium oxide**.

**Uranium ore:** Rock containing uranium mineralization in concentrations that can be mined economically, typically one to four pounds of uranium oxide (U<sub>3</sub>O<sub>8</sub>) per ton or 0.05 percent to 0.2 percent U<sub>3</sub>O<sub>8</sub>.

**Uranium oxide (U<sub>3</sub>O<sub>8</sub>):** **Uranium concentrate** or **yellowcake**.

**Useful thermal output:** The thermal energy made available in a combined-heat-and-power system for use in any industrial or commercial process, heating or cooling application, or delivered to other end users, i.e., total thermal energy made available for processes and applications other than electrical generation.

**U.S.S.R.:** See **Union of Soviet Socialist Republics (U.S.S.R.)**.

**Utility-scale:** Generators at a site that has a total generating nameplate capacity of 1 megawatt (MW) or more.

**Vented natural gas:** **Natural gas** released into the air on the production site or at processing plants.

**Vessel bunkering:** Includes sales for the fueling of commercial or private boats, such as pleasure craft, fishing boats, tugboats, and ocean-going vessels, including vessels operated by oil companies. Excluded are volumes sold to the U.S. Armed Forces.

**Waste:** See **Biomass waste** and **Non-biomass waste**.

**Waste coal:** Usable material that is a byproduct of previous **coal** processing operations. Waste coal is usually composed of mixed coal, soil, and rock (mine waste). Most waste coal is burned as-is in unconventional fluidized-bed combustors. For some uses, waste coal may be partially cleaned by removing some extraneous noncombustible constituents. Examples of waste coal include fine coal, coal obtained from a refuse bank or slurry dam, anthracite culm, bituminous gob, and lignite waste.

**Watt (W):** The unit of electrical power equal to one ampere under a pressure of one volt. A watt is equal to 1/746 horsepower.

**Watthour (Wh):** The electrical energy unit of measure equal to one watt of power supplied to, or taken from, an electric circuit steadily for one hour.

**Wax:** A solid or semi-solid material consisting of a mixture of **hydrocarbons** obtained or derived from **petroleum** fractions, or through a Fischer-Tropsch type process, in which the straight-chained paraffin series predominates. This includes all marketable wax, whether crude or refined, with a congealing point (ASTM D 938) between 100 and 200 degrees Fahrenheit and a maximum oil content (ASTM D 3235) of 50 weight percent.

**Wellhead price:** The value of **crude oil** or **natural gas** at the mouth of the well.

**Wind energy:** Kinetic energy present in wind motion that can be converted to mechanical energy for driving pumps, mills, and electric power generators.

**Wood and wood-derived fuels:** Wood and products derived from wood that are used as fuel, including round wood (cord wood), limb wood, wood chips, bark, sawdust, forest residues, charcoal, paper pellets, railroad ties, utility poles, **black liquor**, red liquor, sludge wood, spent sulfite liquor, **densified biomass** (including wood pellets), and other wood-based solids and liquids.

**Working gas:** The quantity of **natural gas** in the reservoir that is in addition to the cushion or **base gas**. It may or may not be completely withdrawn during any particular withdrawal season. Conditions permitting, the total working capacity could be used more than once during any season. Volumes of working gas are reported in thousand cubic feet at standard temperature and pressure.

THIS PAGE INTENTIONALLY LEFT BLANK