


May 2021

# Monthly Energy Review



*Independent Statistics & Analysis*

U.S. Energy Information  
Administration

[www.eia.gov/mer](http://www.eia.gov/mer)

# Monthly Energy Review

---

The *Monthly Energy Review* (MER) is the U.S. Energy Information Administration's (EIA) primary report of recent and historical energy statistics. Included are statistics on total energy production, consumption, stocks, trade, and energy prices; overviews of petroleum, natural gas, coal, electricity, nuclear energy, and renewable energy; carbon dioxide emissions; and data unit conversions.

Release of the MER is in keeping with responsibilities given to EIA in Public Law 95–91 (Department of Energy Organization Act), which states, in part, in Section 205(a)(2):

*“The Administrator shall be responsible for carrying out a central, comprehensive, and unified energy data and information program which will collect, evaluate, assemble, analyze, and disseminate data and information...”*

The MER is intended for use by members of Congress, federal and state agencies, energy analysts, and the general public. EIA welcomes suggestions from readers regarding MER content and other EIA publications.

**Related monthly publications:** Other monthly EIA reports are Petroleum Supply Monthly, Petroleum Marketing Monthly, Natural Gas Monthly, and Electric Power Monthly. For more information, contact EIA's Office of Communications via email at [infoctr@eia.gov](mailto:infoctr@eia.gov).

## Important notes about the data

**Data displayed:** For tables beginning in 1949, annual data are usually displayed only in 5-year increments between 1950 and 2000 in the tables in Portable Document Format (PDF) files; however, all annual data are shown in the Excel files, comma-separated values (CSV) files, application programming interface (API) files, and in the data browser. Also, only two to three years of monthly data are displayed in the PDF files; however, for many series, monthly data beginning with January 1973 are available in the Excel files, CSV files, API files, and in the data browser.

**Comprehensive changes:** Each month, most MER tables and figures present data for a new month. These data are usually preliminary (and sometimes estimated or forecasted) and likely to be revised the following month. The first dissemination of most annual data is also preliminary. It is often based on monthly estimates and is likely to be revised later that year after final data are published from sources, according to source data revision policies and publication schedules. In addition, EIA may revise historical data when a major revision in a source publication is needed, when new data sources become available, or when estimation methodologies are improved. A record of current and historical changes to MER data is available at <https://www.eia.gov/totalenergy/data/monthly/whatsnew.php>.

**Annual data from 1949:** In 2013, EIA expanded the MER to incorporate annual data as far back as 1949 in those data tables that were previously published in both the Annual Energy Review and MER.

## Electronic access

The MER is available on EIA's website in various formats at <http://www.eia.gov/totalenergy/data/monthly>.

- Full report and report tables: PDF files
- Table data (unrounded): Excel files, CSV files, API files, and data browser
- Graphs: PDF files and data browser

Note: PDF files display selected annual and monthly data; Excel files, CSV files, API files, and data browser display all available annual and monthly data, often with greater precision than the PDF files.

**Timing of release:** The MER is posted at <http://www.eia.gov/totalenergy/data/monthly> no later than the last work day of the month.

**Released:** May 25, 2021

# **Monthly Energy Review**

## **May 2021**

**U.S. Energy Information Administration**  
Office of Energy Statistics  
U.S. Department of Energy  
Washington, DC 20585

This report was prepared by the U.S. Energy Information Administration (EIA), the statistical and analytical agency within the U.S. Department of Energy. By law, EIA's data, analyses, and forecasts are independent of approval by any other officer or employee of the United States Government. The views in this report therefore should not be construed as representing those of the Department of Energy or other federal agencies.

# Contacts

The *Monthly Energy Review* is prepared by the U.S. Energy Information Administration, Office of Energy Statistics, Office of Energy Demand and Integrated Statistics, Integrated Statistics Team, under the direction of Ryan Repice, 202-586-5828 (ryan.repice@eia.gov). Questions and comments specifically related to the *Monthly Energy Review* may be addressed to Alexander Sun, 202-287-5948 (alexander.sun@eia.gov).

For assistance in acquiring data, please contact EIA's Office of Communications at 202-586-8800 (infoctr@eia.gov). Questions about the collection, processing, or interpretation of the information may be directed to the following subject specialists:

<b>Section 1. Energy Overview</b>	Dianne R. Dunn	202-586-2792 dianne.dunn@eia.gov
<b>Section 2. Energy Consumption by Sector</b>	Dianne R. Dunn	202-586-2792 dianne.dunn@eia.gov
<b>Section 3. Petroleum</b>	Javed Zaidi	202-586-1155 javed.zaidi@doe.gov
<b>Section 4. Natural Gas</b>	Michael Kopalek	202-586-4001 michael.kopalek@eia.gov
<b>Section 5. Crude Oil and Natural Gas Resource Development</b>	Gary Long	202-586-3467 gary.long@eia.gov
<b>Section 6. Coal</b>	Rosalyn Berry	202-586-6393 rosalyn.berry@eia.gov
<b>Section 7. Electricity</b>	Glenn McGrath	202-586-4325 glenn.mcgrath@eia.gov
<b>Section 8. Nuclear Energy</b>	Tim Shear	202-586-0403 tim.shear@eia.gov
<b>Section 9. Energy Prices</b>		
Petroleum	Maureen Klein	202-586-8013 maureen.klein@eia.gov
Natural Gas	Michael Kopalek	202-586-4001 michael.kopalek@eia.gov
Average Retail Prices of Electricity	Peter Wong	202-586-7574 peter.wong@eia.gov
Cost of Fuel at Electric Generating Plants	Eric Harrison	202-586-1158 eric.harrison@eia.gov
<b>Section 10. Renewable Energy</b>	Lolita Jamison	202-586-9567 lolita.jamison@eia.gov
<b>Section 11. Environment</b>	Perry Lindstrom	202-586-0934 perry.lindstrom@eia.gov

# Contents

	Page
Section 1. Energy Overview .....	1
Section 2. Energy Consumption by Sector .....	35
Section 3. Petroleum.....	57
Section 4. Natural Gas .....	99
Section 5. Crude Oil and Natural Gas Resource Development .....	109
Section 6. Coal .....	115
Section 7. Electricity .....	125
Section 8. Nuclear Energy .....	149
Section 9. Energy Prices.....	155
Section 10. Renewable Energy .....	175
Section 11. Environment .....	195
Appendix A. British Thermal Unit Conversion Factors.....	209
Appendix B. Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors.....	225
Appendix C. Population, U.S. Gross Domestic Product, and U.S. Gross Output.....	229
Appendix D. Estimated Primary Energy Consumption in the United States, Selected Years, 1635–1945 .....	231
Appendix E. Alternative Approaches for Deriving Energy Contents of Noncombustible Renewables.....	235
Glossary.....	241

# Tables

## Page

<b>Section 1.</b>	<b>Energy Overview</b>	
1.1	Primary Energy Overview.....	3
1.2	Primary Energy Production by Source.....	5
1.3	Primary Energy Consumption by Source.....	7
1.4a	Primary Energy Imports by Source Overview.....	9
1.4b	Primary Energy Exports by Source.....	11
1.4c	Primary Energy Net Imports by Source.....	13
1.5	Merchandise Trade Value.....	15
1.6	Cost of Fuels to End Users in Real (1982–1984) Dollars.....	17
1.7	Primary Energy Consumption, Energy Expenditures, and Carbon Dioxide Emissions Indicators.....	19
1.8	Motor Vehicle Mileage, Fuel Consumption, and Fuel Economy.....	21
1.9	Heating Degree Days by Census Division.....	22
1.10	Cooling Degree Days by Census Division.....	23
1.11a	Non-Combustion Use of Fossil Fuels in Physical Units.....	24
1.11b	Heat Content of Non-Combustion Use of Fossil Fuels.....	25
<b>Section 2.</b>	<b>Energy Consumption by Sector</b>	
2.1	Energy Consumption by Sector.....	37
2.2	Residential Sector Energy Consumption.....	39
2.3	Commercial Sector Energy Consumption.....	41
2.4	Industrial Sector Energy Consumption.....	43
2.5	Transportation Sector Energy Consumption.....	45
2.6	Electric Power Sector Energy Consumption.....	47
2.7	U.S. Government Energy Consumption by Agency, Fiscal Years.....	48
2.8	U.S. Government Energy Consumption by Source, Fiscal Years.....	49
<b>Section 3.</b>	<b>Petroleum</b>	
3.1	Petroleum Overview.....	59
3.2	Refinery and Blender Net Inputs and Net Production.....	61
3.3	Petroleum Trade	
3.3a	Overview.....	63
3.3b	Imports by Type.....	65
3.3c	Imports From OPEC Countries.....	66
3.3d	Imports From Non-OPEC Countries.....	67
3.3e	Exports by Type.....	68
3.3f	Exports by Country of Destination.....	69
3.4	Petroleum Stocks.....	71
3.5	Petroleum Products Supplied by Type.....	73
3.6	Heat Content of Petroleum Products Supplied by Type.....	75
3.7	Petroleum Consumption	
3.7a	Residential and Commercial Sectors.....	77
3.7b	Industrial Sector.....	78
3.7c	Transportation and Electric Power Sectors.....	79
3.8	Heat Content of Petroleum Consumption	
3.8a	Residential and Commercial Sectors.....	82
3.8b	Industrial Sector.....	83
3.8c	Transportation and Electric Power Sectors.....	84
<b>Section 4.</b>	<b>Natural Gas</b>	
4.1	Natural Gas Overview.....	101
4.2	Natural Gas Trade by Country.....	102
4.3	Natural Gas Consumption by Sector.....	103
4.4	Natural Gas in Underground Storage.....	104

# Tables

Page

<b>Section 5.</b>	<b>Crude Oil and Natural Gas Resource Development</b>	
5.1	Crude Oil and Natural Gas Drilling Activity Measurements .....	111
5.2	Crude Oil and Natural Gas Exploratory and Development Wells.....	112
<b>Section 6.</b>	<b>Coal</b>	
6.1	Coal Overview .....	117
6.2	Coal Consumption by Sector.....	118
6.3	Coal Stocks by Sector .....	119
<b>Section 7.</b>	<b>Electricity</b>	
7.1	Electricity Overview .....	127
7.2	Electricity Net Generation	
7.2a	Total (All Sectors) .....	129
7.2b	Electric Power Sector.....	130
7.2c	Commercial and Industrial Sectors.....	131
7.3	Consumption of Combustible Fuels for Electricity Generation	
7.3a	Total (All Sectors) .....	133
7.3b	Electric Power Sector.....	134
7.3c	Commercial and Industrial Sectors (Selected Fuels) .....	135
7.4	Consumption of Combustible Fuels for Electricity Generation and Useful Thermal Output	
7.4a	Total (All Sectors) .....	137
7.4b	Electric Power Sector.....	138
7.4c	Commercial and Industrial Sectors (Selected Fuels) .....	139
7.5	Stocks of Coal and Petroleum: Electric Power Sector .....	141
7.6	Electricity End Use .....	143
<b>Section 8.</b>	<b>Nuclear Energy</b>	
8.1	Nuclear Energy Overview.....	151
8.2	Uranium Overview.....	153
<b>Section 9.</b>	<b>Energy Prices</b>	
9.1	Crude Oil Price Summary .....	157
9.2	F.O.B. Costs of Crude Oil Imports From Selected Countries .....	158
9.3	Landed Costs of Crude Oil Imports From Selected Countries.....	159
9.4	Retail Motor Gasoline and On-Highway Diesel Fuel Prices.....	160
9.5	Refiner Prices of Residual Fuel Oil.....	161
9.6	Refiner Prices of Petroleum Products for Resale .....	162
9.7	Refiner Prices of Petroleum Products to End Users.....	163
9.8	Average Retail Prices of Electricity .....	165
9.9	Cost of Fossil-Fuel Receipts at Electric Generating Plants.....	167
9.10	Natural Gas Prices.....	169
<b>Section 10.</b>	<b>Renewable Energy</b>	
10.1	Renewable Energy Production and Consumption by Source.....	177
10.2	Renewable Energy Consumption	
10.2a	Residential and Commercial Sectors .....	178
10.2b	Industrial and Transportation Sectors .....	179
10.2c	Electric Power Sector .....	180
10.3	Fuel Ethanol Overview .....	181
10.4	Biodiesel and Other Renewable Fuels Overview.....	182
10.5	Solar Energy Consumption .....	183
10.6	Solar Electricity Net Generation .....	184

# Tables

Page

## Section 11. Environment

11.1	Carbon Dioxide Emissions From Energy Consumption by Source .....	197
11.2	Carbon Dioxide Emissions From Energy Consumption: Residential Sector .....	199
11.3	Carbon Dioxide Emissions From Energy Consumption: Commercial Sector .....	200
11.4	Carbon Dioxide Emissions From Energy Consumption: Industrial Sector.....	201
11.5	Carbon Dioxide Emissions From Energy Consumption: Transportation Sector.....	202
11.6	Carbon Dioxide Emissions From Energy Consumption: Electric Power Sector .....	203
11.7	Carbon Dioxide Emissions From Biomass Energy Consumption.....	204

## Appendix A. British Thermal Unit Conversion Factors

A1	Approximate Heat Content of Petroleum and Other Liquids .....	210
A2	Approximate Heat Content of Petroleum Production, Imports, and Exports .....	211
A3	Approximate Heat Content of Petroleum Consumption and Fuel Ethanol .....	212
A4	Approximate Heat Content of Natural Gas .....	213
A5	Approximate Heat Content of Coal and Coal Coke .....	214
A6	Approximate Heat Rates for Electricity, and Heat Content of Electricity .....	215

## Appendix B. Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors

B1	Metric Conversion Factors .....	227
B2	Metric Prefixes .....	228
B3	Other Physical Conversion Factors .....	228

## Appendix C. Population, U.S. Gross Domestic Product, and U.S. Gross Output

C1	Population, U.S. Gross Domestic Product, and U.S. Gross Output .....	230
----	--	-----

## Appendix D. Estimated Primary Energy Consumption in the United States, Selected Years, 1635–1945

D1	Estimated Primary Energy Consumption in the United States, Selected Years, 1635–1945 .....	232
----	--	-----

## Appendix E. Alternative Approaches for Deriving Energy Contents of Noncombustible Renewables

E1	Noncombustible Renewable Primary Energy Consumption:	
E.1a	Conventional Hydroelectric Power, Geothermal, and Wind.....	238
E.1b	Solar and Total.....	239



# Figures

## Page

<b>Section 1. Energy Overview</b>	
1.1 Primary Energy Overview .....	2
1.2 Primary Energy Production .....	4
1.3 Primary Energy Consumption .....	6
1.4a Primary Energy Imports .....	8
1.4b Primary Energy Exports .....	10
1.4c Primary Energy Net Imports .....	12
1.5 Merchandise Trade Value .....	14
1.6 Cost of Fuels to End Users in Real (1982–1984) Dollars .....	16
1.7 Primary Energy Consumption and Energy Expenditures Indicators .....	18
1.8 Motor Vehicle Mileage, Fuel Consumption, and Fuel Economy, 1949–2019 .....	20
<b>Section 2. Energy Consumption by Sector</b>	
2.1 Energy Consumption by Sector .....	36
2.2 Residential Sector Energy Consumption .....	38
2.3 Commercial Sector Energy Consumption .....	40
2.4 Industrial Sector Energy Consumption .....	42
2.5 Transportation Sector Energy Consumption .....	44
2.6 Electric Power Sector Energy Consumption .....	46
<b>Section 3. Petroleum</b>	
3.1 Petroleum Overview .....	58
3.2 Refinery and Blender Net Inputs and Net Production .....	60
3.3 Petroleum Trade	
3.3a Overview .....	62
3.3b Imports and Exports by Type .....	64
3.4 Petroleum Stocks .....	70
3.5 Petroleum Products Supplied by Type .....	72
3.6 Heat Content of Petroleum Products Supplied by Type .....	74
3.7 Petroleum Consumption by Sector .....	76
3.8a Heat Content of Petroleum Consumption by End-User Sector, 1949–2018 .....	80
3.8b Heat Content of Petroleum Consumption by End-User Sector, Monthly .....	81
<b>Section 4. Natural Gas</b>	
4.1 Natural Gas .....	100
<b>Section 5. Crude Oil and Natural Gas Resource Development</b>	
5.1 Crude Oil and Natural Gas Resource Development Indicators .....	110
<b>Section 6. Coal</b>	
6.1 Coal .....	116
<b>Section 7. Electricity</b>	
7.1 Electricity Overview .....	126
7.2 Electricity Net Generation .....	128
7.3 Consumption of Selected Combustible Fuels for Electricity Generation .....	132
7.4 Consumption of Selected Combustible Fuels for Electricity Generation and Useful Thermal Output .....	136
7.5 Stocks of Coal and Petroleum: Electric Power Sector .....	140
7.6 Electricity End Use .....	142

# Figures

## Page

### Section 8. Nuclear Energy

8.1	Nuclear Energy Overview .....	150
8.2	Uranium Overview .....	152

### Section 9. Energy Prices

9.1	Petroleum Prices .....	156
9.2	Average Retail Prices of Electricity .....	164
9.3	Cost of Fossil-Fuel Receipts at Electric Generating Plants .....	166
9.4	Natural Gas Prices .....	168

### Section 10. Renewable Energy

10.1	Renewable Energy Consumption .....	176
------	------------------------------------	-----

### Section 11. Environment

11.1	Carbon Dioxide Emissions From Energy Consumption by Source .....	196
11.2	Carbon Dioxide Emissions From Energy Consumption by Sector .....	198


# 1. Energy Overview

---


**Figure 1.1 Primary Energy Overview**

(Quadrillion Btu)


Overview, 1949–2020




Overview, Monthly



Overview, February 2021



Net Imports, January–February



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.1.

**Table 1.1 Primary Energy Overview**  
(Quadrillion Btu)

	Production				Trade			Stock Change and Other <sup>d</sup>	Consumption			
	Fossil Fuels <sup>a</sup>	Nuclear Electric Power	Renewable Energy <sup>b</sup>	Total	Imports	Exports	Net Imports <sup>c</sup>		Fossil Fuels <sup>e</sup>	Nuclear Electric Power	Renewable Energy <sup>b</sup>	Total <sup>f</sup>
1950 Total .....	32.553	0.000	2.978	35.531	1.913	1.465	0.448	-1.380	31.615	0.000	2.978	34.599
1955 Total .....	37.347	.000	2.784	40.131	2.790	2.286	.504	-.457	37.380	.000	2.784	40.178
1960 Total .....	39.855	.006	2.928	42.789	4.188	1.477	2.710	-.458	42.091	.006	2.928	45.041
1965 Total .....	47.205	.043	3.396	50.644	5.892	1.829	4.063	-.754	50.515	.043	3.396	53.953
1970 Total .....	59.152	.239	4.070	63.462	8.342	2.632	5.709	-1.354	63.501	.239	4.070	67.817
1975 Total .....	54.697	1.900	4.687	61.284	14.032	2.323	11.709	-1.062	65.323	1.900	4.687	71.931
1980 Total .....	58.979	2.739	5.428	67.147	15.796	3.695	12.101	-1.227	69.782	2.739	5.428	78.021
1985 Total .....	57.502	4.076	6.084	67.661	11.781	4.196	7.584	1.088	66.035	4.076	6.084	76.334
1990 Total .....	58.523	6.104	6.040	70.668	18.817	4.752	14.065	-.299	72.281	6.104	6.040	84.433
1995 Total .....	57.496	7.075	6.557	71.129	22.180	4.496	17.684	2.118	77.162	7.075	6.559	90.931
2000 Total .....	57.307	7.862	6.102	71.271	28.865	3.962	24.904	2.528	84.620	7.862	6.104	98.702
2005 Total .....	54.995	8.161	6.221	69.377	34.659	4.462	30.197	.527	85.623	8.161	6.234	100.102
2006 Total .....	55.877	8.215	6.586	70.678	34.649	4.727	29.921	-1.207	84.477	8.215	6.637	99.392
2007 Total .....	56.369	8.459	6.510	71.338	34.679	5.338	29.341	.215	85.805	8.459	6.523	100.893
2008 Total .....	57.527	8.426	7.192	73.145	32.970	6.949	26.021	-.412	83.041	8.426	7.175	98.754
2009 Total .....	56.612	8.355	7.625	72.592	29.690	6.920	22.770	-1.420	77.862	8.355	7.608	93.942
2010 Total .....	58.159	8.434	8.314	74.907	29.866	8.176	21.690	.916	80.723	8.434	8.267	97.513
2011 Total .....	60.515	8.269	9.300	78.083	28.748	10.373	18.375	.404	79.263	8.269	9.204	96.863
2012 Total .....	62.291	8.062	8.886	79.239	27.068	11.267	15.801	-.666	77.304	8.062	8.847	94.374
2013 Total .....	64.177	8.244	9.418	81.839	24.623	11.788	12.835	2.443	79.224	8.244	9.451	97.117
2014 Total .....	69.616	8.338	9.766	87.720	23.241	12.270	10.971	-.415	80.017	8.338	9.740	98.276
2015 Total .....	70.201	8.337	9.729	88.267	23.794	12.902	10.892	-1.783	79.090	8.337	9.720	97.375
2016 Total .....	65.445	8.427	10.425	84.297	25.378	14.119	11.259	1.781	78.319	8.427	10.365	97.337
2017 Total .....	68.478	8.419	11.200	88.096	25.458	17.946	7.512	1.990	77.907	8.419	11.080	97.599
2018 Total .....	75.807	8.438	11.509	95.754	24.833	21.224	3.610	1.798	81.271	8.438	11.302	101.162
2019 January .....	6.814	.770	.945	8.529	2.122	1.910	.212	.791	7.830	.770	.921	9.532
February .....	6.134	.676	.875	7.684	1.700	1.725	-.024	.717	6.829	.676	.862	8.377
March .....	6.679	.680	.992	8.351	1.925	1.912	.013	.329	7.025	.680	.980	8.692
April .....	6.660	.633	1.032	8.324	1.925	1.893	.032	-.694	6.007	.633	1.015	7.662
May .....	6.888	.701	1.065	8.654	2.046	1.954	.092	-.809	6.171	.701	1.054	7.937
June .....	6.597	.718	1.002	8.317	1.889	1.940	-.051	-.360	6.186	.718	.989	7.906
July .....	6.783	.754	.989	8.526	2.021	1.889	.132	-.109	6.807	.754	.975	8.548
August .....	7.064	.751	.946	8.761	1.975	1.969	.006	-.215	6.857	.751	.930	8.552
September .....	6.804	.690	.904	8.398	1.789	1.977	-.188	-.357	6.260	.690	.891	7.854
October .....	7.052	.648	.932	8.632	1.816	2.088	-.272	-.432	6.351	.648	.922	7.929
November .....	6.849	.670	.903	8.422	1.688	2.028	-.340	.296	6.807	.670	.889	8.378
December .....	7.015	.763	.942	8.720	1.969	2.190	-.221	.427	7.227	.763	.922	8.926
<b>Total .....</b>	<b>81.339</b>	<b>8.452</b>	<b>11.527</b>	<b>101.317</b>	<b>22.865</b>	<b>23.474</b>	<b>-.609</b>	<b>-.415</b>	<b>80.358</b>	<b>8.452</b>	<b>11.350</b>	<b>100.293</b>
2020 January .....	6.992	.774	.994	8.760	1.873	2.164	-.291	.487	7.201	.774	.970	8.956
February .....	6.417	.689	.994	8.100	1.726	2.154	-.428	.633	6.634	.689	.973	8.305
March .....	6.792	.668	.995	8.456	1.782	2.245	-.463	-.153	6.193	.668	.964	7.839
April .....	6.254	.618	.917	7.789	1.509	1.897	-.388	-.889	4.974	.618	.908	6.511
May .....	5.857	.672	1.033	7.562	1.652	1.643	.009	-.720	5.132	.672	1.035	6.851
June .....	5.877	.702	1.044	7.623	1.708	1.671	.037	-.388	5.520	.702	1.037	7.272
July .....	6.285	.725	.999	8.008	1.693	1.861	-.168	.250	6.357	.725	.991	8.091
August .....	6.312	.720	.960	7.992	1.618	1.865	-.247	.265	6.323	.720	.946	8.010
September .....	6.115	.686	.891	7.692	1.545	1.861	-.316	-.059	5.738	.686	.879	7.317
October .....	<sup>R</sup> 6.192	.620	.941	7.753	1.580	1.973	-.393	.129	5.935	.620	.921	7.489
November .....	<sup>R</sup> 6.230	.645	.999	<sup>R</sup> 7.874	1.599	1.941	-.342	<sup>R</sup> .064	5.962	.645	.978	7.596
December .....	<sup>R</sup> 6.393	.730	1.008	<sup>R</sup> 8.131	1.721	2.192	-.472	<sup>R</sup> 1.047	6.975	.730	.988	8.707
<b>Total .....</b>	<b><sup>R</sup> 75.715</b>	<b>8.248</b>	<b>11.777</b>	<b><sup>R</sup> 95.740</b>	<b>20.006</b>	<b>23.469</b>	<b>-3.463</b>	<b><sup>R</sup> .666</b>	<b>72.944</b>	<b>8.248</b>	<b>11.590</b>	<b>92.943</b>
2021 January .....	<sup>R</sup> 6.467	.750	<sup>R</sup> 1.005	<sup>R</sup> 8.223	1.775	2.135	-.359	<sup>R</sup> 1.001	<sup>R</sup> 7.123	.750	.976	<sup>R</sup> 8.865
February .....	5.309	.657	.885	6.852	1.566	1.751	-.185	1.371	6.500	.657	.877	8.037
<b>2-Month Total .....</b>	<b>11.777</b>	<b>1.407</b>	<b>1.890</b>	<b>15.074</b>	<b>3.341</b>	<b>3.885</b>	<b>-.544</b>	<b>2.372</b>	<b>13.623</b>	<b>1.407</b>	<b>1.853</b>	<b>16.902</b>
2020 2-Month Total .....	13.409	1.463	1.988	16.860	3.599	4.318	-.719	1.120	13.834	1.463	1.943	17.261
2019 2-Month Total .....	12.948	1.445	1.820	16.213	3.822	3.635	.187	1.509	14.659	1.445	1.783	17.909

<sup>a</sup> Coal, natural gas (dry), crude oil, and natural gas plant liquids.  
<sup>b</sup> See Tables 10.1–10.2c for notes on series components and estimation; and see Note, "Renewable Energy Production and Consumption," at end of Section 10.  
<sup>c</sup> Net imports equal imports minus exports.  
<sup>d</sup> Includes petroleum stock change and adjustments; natural gas net storage withdrawals and balancing item; coal stock change, losses, and unaccounted for; fuel ethanol stock change; and biodiesel stock change and balancing item.  
<sup>e</sup> Coal, coal coke net imports, natural gas, and petroleum.  
<sup>f</sup> Also includes electricity net imports.  
<sup>R</sup>=Revised.

Notes: • See "Primary Energy," "Primary Energy Production," and "Primary Energy Consumption," in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **Production:** Table 1.2. • **Trade:** Tables 1.4a and 1.4b. • **Stock Change and Other:** Calculated as consumption minus production and net imports. • **Consumption:** Table 1.3.


**Figure 1.2 Primary Energy Production**

(Quadrillion Btu)


By Source, 1949–2020




By Source, Monthly



Total, January–February



By Source, February 2021



[a] National gas plant liquids.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.2.

**Table 1.2 Primary Energy Production by Source**  
(Quadrillion Btu)

	Fossil Fuels					Nuclear Electric Power	Renewable Energy <sup>a</sup>						Total
	Coal <sup>b</sup>	Natural Gas (Dry)	Crude Oil <sup>c</sup>	NGPL <sup>d</sup>	Total		Hydro- electric Power <sup>e</sup>	Geo- thermal	Solar	Wind	Bio- mass	Total	
<b>1950 Total</b> .....	14.060	6.233	11.447	0.813	32.553	0.000	1.415	NA	NA	NA	1.562	2.978	35.531
<b>1955 Total</b> .....	12.370	9.345	14.410	1.223	37.347	.000	1.360	NA	NA	NA	1.424	2.784	40.131
<b>1960 Total</b> .....	10.817	12.656	14.935	1.447	39.855	.006	1.608	(s)	NA	NA	1.320	2.928	42.789
<b>1965 Total</b> .....	13.055	15.775	16.521	1.853	47.205	.043	2.059	.002	NA	NA	1.335	3.396	50.644
<b>1970 Total</b> .....	14.607	21.666	20.401	2.478	59.152	.239	2.634	.006	NA	NA	1.431	4.070	63.462
<b>1975 Total</b> .....	14.989	19.640	17.729	2.338	54.697	1.900	3.155	.034	NA	NA	1.499	4.687	61.284
<b>1980 Total</b> .....	18.598	19.908	18.249	2.225	58.979	2.739	2.900	.053	NA	NA	2.475	5.428	67.147
<b>1985 Total</b> .....	19.325	16.980	18.992	2.204	57.502	4.076	2.970	.097	(s)	(s)	3.016	6.084	67.661
<b>1990 Total</b> .....	22.488	18.326	15.571	2.138	58.523	6.104	3.046	.171	.059	.029	2.735	6.040	70.668
<b>1995 Total</b> .....	22.130	19.082	13.887	2.398	57.496	7.075	3.205	.152	.068	.033	3.099	6.557	71.129
<b>2000 Total</b> .....	22.735	19.662	12.358	2.551	57.307	7.862	2.811	.164	.063	.057	3.006	6.102	71.271
<b>2005 Total</b> .....	23.185	18.556	10.974	2.280	54.995	8.161	2.703	.181	.058	.178	3.101	6.221	69.377
<b>2006 Total</b> .....	23.790	19.022	10.767	2.299	55.877	8.215	2.869	.181	.061	.264	3.212	6.586	70.678
<b>2007 Total</b> .....	23.493	19.786	10.741	2.349	56.369	8.459	2.446	.186	.066	.341	3.472	6.510	71.338
<b>2008 Total</b> .....	23.851	20.703	10.613	2.359	57.527	8.426	2.511	.192	.074	.546	3.868	7.192	73.145
<b>2009 Total</b> .....	21.624	21.139	11.340	2.508	56.612	8.355	2.669	.200	.078	.721	3.957	7.625	72.592
<b>2010 Total</b> .....	22.038	21.806	11.610	2.705	58.159	8.434	2.539	.208	.091	.923	4.553	8.314	74.907
<b>2011 Total</b> .....	22.221	23.406	11.998	2.890	60.515	8.269	3.103	.212	.112	1.168	4.704	9.300	78.083
<b>2012 Total</b> .....	20.677	24.610	13.842	3.162	62.291	8.062	2.629	.212	.159	1.340	4.547	8.886	79.239
<b>2013 Total</b> .....	20.001	24.859	15.865	3.451	64.177	8.244	2.562	.214	.225	1.601	4.816	9.418	81.839
<b>2014 Total</b> .....	20.286	26.718	18.607	4.005	69.616	8.338	2.467	.214	.337	1.728	5.020	9.766	87.720
<b>2015 Total</b> .....	17.946	28.067	19.712	4.476	70.201	8.337	2.321	.212	.427	1.777	4.992	9.729	88.267
<b>2016 Total</b> .....	14.667	27.576	18.537	4.665	65.445	8.427	2.472	.210	.570	2.096	5.077	10.425	84.297
<b>2017 Total</b> .....	15.625	28.289	19.576	4.987	68.478	8.419	2.767	.210	.777	2.343	5.103	11.200	88.096
<b>2018 Total</b> .....	15.363	31.882	22.835	5.727	75.807	8.438	2.663	.209	.915	2.482	5.239	11.509	95.754
<b>2019 January</b> .....	1.331	2.878	2.096	.509	6.814	.770	.221	.018	.052	.216	.437	.945	8.529
<b>February</b> .....	1.179	2.616	1.863	.476	6.134	.676	.204	.016	.056	.201	.397	.875	7.684
<b>March</b> .....	1.126	2.915	2.109	.529	6.679	.680	.235	.018	.084	.230	.426	.992	8.351
<b>April</b> .....	1.234	2.833	2.074	.518	6.660	.633	.248	.016	.095	.257	.415	1.032	8.324
<b>May</b> .....	1.248	2.950	2.148	.541	6.888	.701	.285	.017	.102	.230	.432	1.065	8.654
<b>June</b> .....	1.145	2.866	2.066	.519	6.597	.718	.250	.017	.110	.200	.425	1.002	8.317
<b>July</b> .....	1.191	2.978	2.088	.526	6.783	.754	.222	.018	.113	.197	.440	.989	8.526
<b>August</b> .....	1.286	3.051	2.195	.533	7.064	.751	.201	.018	.109	.178	.440	.946	8.761
<b>September</b> .....	1.180	2.949	2.136	.540	6.804	.690	.165	.017	.095	.218	.408	.904	8.398
<b>October</b> .....	1.162	3.090	2.238	.562	7.052	.648	.163	.016	.085	.246	.423	.932	8.632
<b>November</b> .....	1.098	3.012	2.198	.540	6.849	.670	.180	.014	.063	.224	.422	.903	8.422
<b>December</b> .....	1.075	3.121	2.261	.558	7.015	.763	.191	.016	.053	.237	.444	.942	8.720
<b>Total</b> .....	14.256	35.258	25.473	6.352	81.339	8.452	2.564	.201	1.017	2.635	5.110	11.527	101.317
<b>2020 January</b> .....	1.111	E 3.057	E 2.250	.573	6.992	.774	.226	.017	.066	.254	.432	.994	8.760
<b>February</b> .....	.948	E 2.848	E 2.104	.517	6.417	.689	.235	.016	.078	.262	.403	.994	8.100
<b>March</b> .....	.920	E 3.040	E 2.247	.585	6.792	.668	.210	.019	.094	.263	.410	.995	8.456
<b>April</b> .....	.780	E 2.891	E 2.050	.532	6.254	.618	.197	.018	.112	.262	.328	.917	7.789
<b>May</b> .....	.739	E 2.822	E 1.768	.528	5.857	.672	.271	.018	.132	.252	.360	1.033	7.562
<b>June</b> .....	.786	E 2.749	E 1.783	.560	5.877	.702	.259	.017	.130	.263	.374	1.044	7.623
<b>July</b> .....	.865	E 2.886	E 1.936	.598	6.285	.725	.246	.018	.139	.198	.397	.999	8.008
<b>August</b> .....	.951	E 2.901	E 1.867	.593	6.312	.720	.214	.018	.129	.200	.399	.960	7.992
<b>September</b> .....	.903	E 2.783	E 1.856	.572	6.115	.686	.171	.018	.109	.205	.388	.891	7.692
<b>October</b> .....	.901	RE 2.859	E 1.842	.590	R 6.192	.620	.163	.018	.101	.257	.402	.941	7.753
<b>November</b> .....	.888	E 2.862	E 1.907	.574	R 6.230	.645	.194	.018	.081	.300	.405	.999	R 7.874
<b>December</b> .....	.899	RE 2.975	RE 1.956	.564	R 6.393	.730	.206	.019	.074	.289	.421	1.008	R 8.131
<b>Total</b> .....	10.690	RE 34.673	RE 23.565	6.787	R 75.715	8.248	2.592	.214	1.246	3.006	4.719	11.777	R 95.740
<b>2021 January</b> .....	.971	RE 2.967	RE 1.951	.578	R 6.467	.750	.233	.018	.079	.271	R .404	R 1.005	R 8.223
<b>February</b> .....	.807	E 2.507	E 1.571	.424	5.309	.657	.197	.017	.088	.238	.345	.885	6.852
<b>2-Month Total</b> ...	1.778	E 5.474	E 3.523	1.002	11.777	1.407	.430	.035	.167	.508	.750	1.890	15.074
<b>2020 2-Month Total</b> ...	2.059	E 5.905	E 4.354	1.090	13.409	1.463	.460	.033	.144	.516	.835	1.988	16.860
<b>2019 2-Month Total</b> ...	2.510	5.493	3.959	.985	12.948	1.445	.425	.034	.109	.418	.834	1.820	16.213

<sup>a</sup> Most data are estimates. See Tables 10.1–10.2c for notes on series components and estimation; and see Note, "Renewable Energy Production and Consumption," at end of Section 10.

<sup>b</sup> Beginning in 1989, includes waste coal supplied. Beginning in 2001, also includes a small amount of refuse recovery. See Table 6.1.

<sup>c</sup> Includes lease condensate.

<sup>d</sup> Natural gas processing plant production of natural gas liquids (ethane, propane, normal butane, isobutane, and natural gasoline). Through 1980, also includes natural gas processing plant production of finished petroleum products (aviation gasoline, distillate fuel oil, jet fuel, kerosene, motor gasoline, special

naphthas, and miscellaneous products).

<sup>e</sup> Conventional hydroelectric power.

R=Revised. E=Estimate. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy Production" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 1.3 Primary Energy Consumption**

(Quadrillion Btu)


By Source, [a] 1949–2020




By Source, [a] Monthly



Total, January–February



By Source, [a] February 2021



[a] Small quantities of net imports of coal coke and electricity are not shown.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.3.



**Table 1.3 Primary Energy Consumption by Source**  
(Quadrillion Btu)

	Fossil Fuels <sup>a</sup>				Nuclear Electric Power	Renewable Energy <sup>b</sup>						Total <sup>g</sup>
	Coal	Natural Gas <sup>c</sup>	Petroleum <sup>d</sup>	Total <sup>e</sup>		Hydro-electric Power <sup>f</sup>	Geo-thermal	Solar	Wind	Bio-mass	Total	
1950 Total .....	12.347	5.968	13.298	31.615	0.000	1.415	NA	NA	NA	1.562	2.978	34.599
1955 Total .....	11.167	8.998	17.225	37.380	.000	1.360	NA	NA	NA	1.424	2.784	40.178
1960 Total .....	9.838	12.385	19.874	42.091	.006	1.608	(s)	NA	NA	1.320	2.928	45.041
1965 Total .....	11.581	15.769	23.184	50.515	.043	2.059	.002	NA	NA	1.335	3.396	53.953
1970 Total .....	12.265	21.795	29.499	63.501	.239	2.634	.006	NA	NA	1.431	4.070	67.817
1975 Total .....	12.663	19.948	32.699	65.323	1.900	3.155	.034	NA	NA	1.499	4.687	71.931
1980 Total .....	15.423	20.235	34.159	69.782	2.739	2.900	.053	NA	NA	2.475	5.428	78.021
1985 Total .....	17.478	17.703	30.866	66.035	4.076	2.970	.097	(s)	(s)	3.016	6.084	76.334
1990 Total .....	19.173	19.603	33.500	72.281	6.104	3.046	.171	.059	.029	2.735	6.040	84.433
1995 Total .....	20.089	22.671	34.341	77.162	7.075	3.205	.152	.068	.033	3.101	6.559	90.931
2000 Total .....	22.580	23.824	38.152	84.620	7.862	2.811	.164	.063	.057	3.008	6.104	98.702
2005 Total .....	22.797	22.565	40.217	85.623	8.161	2.703	.181	.058	.178	3.114	6.234	100.102
2006 Total .....	22.447	22.239	39.731	84.477	8.215	2.869	.181	.061	.264	3.262	6.637	99.392
2007 Total .....	22.749	23.663	39.368	85.805	8.459	2.446	.186	.066	.341	3.485	6.523	100.893
2008 Total .....	22.387	23.843	36.769	83.041	8.426	2.511	.192	.074	.546	3.851	7.175	98.754
2009 Total .....	19.691	23.416	34.779	77.862	8.355	2.669	.200	.078	.721	3.940	7.608	93.942
2010 Total .....	20.834	24.575	35.321	80.723	8.434	2.539	.208	.091	.923	4.506	8.267	97.513
2011 Total .....	19.658	24.955	34.639	79.263	8.269	3.103	.212	.112	1.168	4.609	9.204	96.863
2012 Total .....	17.378	26.089	33.833	77.304	8.062	2.629	.212	.159	1.340	4.508	8.847	94.374
2013 Total .....	18.039	26.805	34.398	79.224	8.244	2.562	.214	.225	1.601	4.848	9.451	97.117
2014 Total .....	17.998	27.383	34.658	80.017	8.338	2.467	.214	.337	1.728	4.994	9.740	98.276
2015 Total .....	15.549	28.191	35.368	79.090	8.337	2.321	.212	.427	1.777	4.983	9.720	97.375
2016 Total .....	14.226	28.400	35.712	78.319	8.427	2.472	.210	.570	2.096	5.017	10.365	97.337
2017 Total .....	13.837	28.055	36.043	77.907	8.419	2.767	.210	.777	2.343	4.983	11.080	97.599
2018 Total .....	13.252	31.153	36.892	81.271	8.438	2.663	.209	.915	2.482	5.032	11.302	101.162
2019 January .....	1.161	3.542	3.130	7.830	.770	.221	.018	.052	.216	.413	.921	9.532
February .....	.949	3.123	2.757	6.829	.676	.204	.016	.056	.201	.384	.862	8.377
March .....	.933	3.028	3.065	7.025	.680	.235	.018	.084	.230	.414	.980	8.692
April .....	.719	2.288	3.001	6.007	.633	.248	.016	.095	.257	.398	1.015	7.662
May .....	.850	2.207	3.116	6.171	.701	.285	.017	.102	.230	.421	1.054	7.937
June .....	.931	2.192	3.065	6.186	.718	.250	.017	.110	.200	.412	.989	7.906
July .....	1.154	2.476	3.179	6.807	.754	.222	.018	.113	.197	.426	.975	8.548
August .....	1.086	2.517	3.255	6.857	.751	.201	.018	.109	.178	.424	.930	8.552
September .....	.986	2.282	2.995	6.260	.690	.165	.017	.095	.218	.396	.891	7.854
October .....	.801	2.387	3.165	6.351	.648	.163	.016	.085	.246	.413	.922	7.929
November .....	.885	2.878	3.046	6.807	.670	.180	.014	.063	.224	.408	.889	8.378
December .....	.860	3.278	3.093	7.227	.763	.191	.016	.053	.237	.425	.922	8.926
Total .....	11.316	32.197	36.866	80.358	8.452	2.564	.201	1.017	2.635	4.933	11.350	100.293
2020 January .....	.783	3.412	3.007	7.201	.774	.226	.017	.066	.254	.408	.970	8.956
February .....	.692	3.139	2.805	6.634	.689	.235	.016	.078	.262	.382	.973	8.305
March .....	.631	2.803	2.761	6.193	.668	.210	.019	.094	.263	.379	.964	7.839
April .....	.514	2.322	2.140	4.974	.618	.197	.018	.112	.262	.319	.908	6.511
May .....	.574	2.143	2.416	5.132	.672	.271	.018	.132	.252	.361	1.035	6.851
June .....	.768	2.209	2.544	5.520	.702	.259	.017	.130	.263	.367	1.037	7.272
July .....	1.019	2.579	2.759	6.357	.725	.246	.018	.139	.198	.388	.991	8.091
August .....	1.033	2.490	2.801	6.323	.720	.214	.018	.129	.200	.386	.946	8.010
September .....	.806	2.250	2.683	5.738	.686	.171	.018	.109	.205	.376	.879	7.317
October .....	.721	2.404	2.811	5.935	.620	.163	.018	.101	.257	.382	.921	7.489
November .....	.732	2.525	2.707	5.962	.645	.194	.018	.081	.300	.383	.978	7.596
December .....	.910	3.269	2.797	6.975	.730	.206	.019	.074	.289	.400	.988	8.707
Total .....	9.182	31.544	32.231	72.944	8.248	2.592	.214	1.246	3.006	4.532	11.590	92.943
2021 January .....	.946	R 3.402	2.777	R 7.123	.750	.233	.018	.079	.271	.375	.976	R 8.865
February .....	.972	3.143	2.387	6.500	.657	.197	.017	.088	.238	.337	.877	8.037
2-Month Total .....	1.919	6.546	5.164	13.623	1.407	.430	.035	.167	.508	.712	1.853	16.902
2020 2-Month Total .....	1.475	6.551	5.811	13.834	1.463	.460	.033	.144	.516	.790	1.943	17.261
2019 2-Month Total .....	2.111	6.665	5.887	14.659	1.445	.425	.034	.109	.418	.797	1.783	17.909

<sup>a</sup> Includes non-combustion use of fossil fuels.

<sup>b</sup> Most data are estimates. See Tables 10.1–10.2c for notes on series components and estimation; and see Note, "Renewable Energy Production and Consumption," at end of Section 10.

<sup>c</sup> Natural gas only; excludes supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.

<sup>d</sup> Petroleum products supplied; excludes biofuels Biofuels are included in "Biomass."

<sup>e</sup> Includes coal coke net imports. See Tables 1.4c.

<sup>f</sup> Conventional hydroelectric power.

<sup>g</sup> Includes coal coke net imports and electricity net imports, which are not

separately displayed. See Tables 1.4c.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy Consumption" in Glossary.

• See Table D1 for estimated energy consumption for 1635–1945. • Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 1.4a Primary Energy Imports**

(Quadrillion Btu)


By Source, 1949–2020




By Source, Monthly



Total, January–February



Total, Monthly



[a] Crude oil and lease condensate, includes imports into the Strategic Petroleum Reserve, which began in 1977.

[b] Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

[c] Coal, coal coke, biomass, and electricity.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.4a.

**Table 1.4a Primary Energy Imports by Source**  
(Quadrillion Btu)

	Imports								
	Coal	Coal Coke	Natural Gas	Petroleum			Biomass <sup>c</sup>	Electricity	Total
				Crude Oil <sup>a</sup>	Petroleum Products <sup>b</sup>	Total			
1950 Total .....	0.009	0.011	0.000	1.056	0.830	1.886	NA	0.007	1.913
1955 Total .....	.008	.003	.011	1.691	1.061	2.752	NA	.016	2.790
1960 Total .....	.007	.003	.161	2.196	1.802	3.999	NA	.018	4.188
1965 Total .....	.005	.002	.471	2.654	2.748	5.402	NA	.012	5.892
1970 Total .....	.001	.004	.846	2.814	4.656	7.470	NA	.021	8.342
1975 Total .....	.024	.045	.978	8.721	4.227	12.948	NA	.038	14.032
1980 Total .....	.030	.016	1.006	11.195	3.463	14.658	NA	.085	15.796
1985 Total .....	.049	.014	.952	6.814	3.796	10.609	NA	.157	11.781
1990 Total .....	.067	.019	1.551	12.766	4.351	17.117	NA	.063	18.817
1995 Total .....	.237	.095	2.901	15.669	3.131	18.800	.001	.146	22.180
2000 Total .....	.313	.094	3.869	19.783	4.641	24.424	(s)	.166	28.865
2005 Total .....	.762	.088	4.450	22.091	7.108	29.198	.012	.150	34.659
2006 Total .....	.906	.101	4.291	22.085	7.054	29.139	.066	.146	34.649
2007 Total .....	.909	.061	4.723	21.914	6.842	28.756	.055	.175	34.679
2008 Total .....	.855	.089	4.084	21.448	6.214	27.662	.085	.195	32.970
2009 Total .....	.566	.009	3.845	19.699	5.367	25.066	.027	.178	29.690
2010 Total .....	.484	.030	3.834	20.140	5.219	25.359	.004	.154	29.866
2011 Total .....	.327	.035	3.555	19.595	5.038	24.633	.019	.178	28.748
2012 Total .....	.212	.028	3.216	19.239	4.122	23.361	.049	.202	27.068
2013 Total .....	.199	.003	2.955	16.957	4.169	21.126	.102	.236	24.623
2014 Total .....	.252	.002	2.763	16.178	3.773	19.951	.046	.227	23.241
2015 Total .....	.256	.003	2.786	16.299	4.111	20.410	.079	.259	23.794
2016 Total .....	.220	.006	3.082	17.392	4.309	21.700	.123	.248	25.378
2017 Total .....	.168	.001	3.109	17.597	4.277	21.874	.081	.224	25.458
2018 Total .....	.122	.003	2.961	17.192	4.309	21.501	.048	.199	24.833
2019 January .....	.013	(s)	.298	1.420	.370	1.790	.005	.016	2.122
February .....	.007	(s)	.239	1.132	.303	1.435	.003	.016	1.700
March .....	.015	(s)	.259	1.274	.353	1.628	.006	.017	1.925
April .....	.011	.001	.212	1.273	.409	1.681	.006	.015	1.925
May .....	.008	(s)	.213	1.344	.459	1.803	.005	.016	2.046
June .....	.014	(s)	.206	1.300	.345	1.645	.007	.018	1.889
July .....	.011	(s)	.236	1.304	.444	1.748	.007	.019	2.021
August .....	.011	.001	.226	1.305	.408	1.713	.006	.020	1.975
September .....	.013	(s)	.213	1.179	.358	1.537	.007	.018	1.789
October .....	.015	(s)	.216	1.173	.392	1.565	.007	.012	1.816
November .....	.010	.001	.229	1.058	.368	1.426	.006	.017	1.688
December .....	.011	(s)	.262	1.284	.387	1.671	.007	.018	1.969
Total .....	.138	.003	2.810	15.045	4.596	19.641	.072	.201	22.865
2020 January .....	.011	(s)	.269	1.208	.364	1.572	.006	.016	1.873
February .....	.007	(s)	.244	1.149	.305	1.454	.005	.015	1.726
March .....	.009	(s)	.219	1.187	.345	1.532	.005	.017	1.782
April .....	.007	(s)	.195	1.007	.277	1.284	.007	.016	1.509
May .....	.010	.001	.191	1.147	.280	1.427	.005	.018	1.652
June .....	.006	(s)	.192	1.167	.320	1.487	.006	.018	1.708
July .....	.010	(s)	.216	1.113	.327	1.440	.005	.023	1.693
August .....	.006	(s)	.217	1.024	.341	1.365	.007	.023	1.618
September .....	.010	.001	.179	.984	.349	1.333	.006	.016	1.545
October .....	.005	.002	.204	.997	.348	1.345	.007	.016	1.580
November .....	.013	(s)	.217	1.016	.331	1.347	.007	.014	1.599
December .....	.009	(s)	.273	1.077	.337	1.413	.008	.018	1.721
Total .....	.104	.004	2.616	13.075	3.924	16.999	.074	.210	20.006
2021 January .....	.011	(s)	.291	1.090	.359	1.449	.005	.019	1.775
February .....	.006	(s)	.279	.951	.312	1.264	.005	.012	1.566
2-Month Total .....	.017	(s)	.570	2.041	.671	2.713	.011	.031	3.341
2020 2-Month Total .....	.018	(s)	.513	2.357	.669	3.026	.010	.031	3.599
2019 2-Month Total .....	.020	(s)	.537	2.552	.673	3.225	.008	.032	3.822

<sup>a</sup> Crude oil and lease condensate. Includes imports into the Strategic Petroleum Reserve, which began in 1977.

<sup>b</sup> Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

<sup>c</sup> Beginning in 1993, includes fuel ethanol (minus denaturant). Beginning in 2001, also includes biodiesel. From 2009-2011, also includes other renewable fuels. Beginning in 2012, also includes other renewable diesel fuel.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 1.4b Primary Energy Exports**

(Quadrillion Btu)


By Source, 1949-2020




By Source, Monthly



Total, January–February



Total, Monthly



[a] Crude oil and lease condensate.

[b] Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

[c] Includes coal coke.

[d] Biomass and electricity

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.4b.

**Table 1.4b Primary Energy Exports by Source**  
(Quadrillion Btu)

	Exports								
	Coal	Coal Coke	Natural Gas	Petroleum			Biomass <sup>c</sup>	Electricity	Total
				Crude Oil <sup>a</sup>	Petroleum Products <sup>b</sup>	Total			
<b>1950 Total</b> .....	<b>0.786</b>	<b>0.010</b>	<b>0.027</b>	<b>0.202</b>	<b>0.440</b>	<b>0.642</b>	<b>NA</b>	<b>0.001</b>	<b>1.465</b>
<b>1955 Total</b> .....	<b>1.465</b>	<b>.013</b>	<b>.032</b>	<b>.067</b>	<b>.707</b>	<b>.774</b>	<b>NA</b>	<b>.002</b>	<b>2.286</b>
<b>1960 Total</b> .....	<b>1.023</b>	<b>.009</b>	<b>.012</b>	<b>.018</b>	<b>.413</b>	<b>.431</b>	<b>NA</b>	<b>.003</b>	<b>1.477</b>
<b>1965 Total</b> .....	<b>1.376</b>	<b>.021</b>	<b>.027</b>	<b>.006</b>	<b>.386</b>	<b>.392</b>	<b>NA</b>	<b>.013</b>	<b>1.829</b>
<b>1970 Total</b> .....	<b>1.936</b>	<b>.061</b>	<b>.072</b>	<b>.029</b>	<b>.520</b>	<b>.549</b>	<b>NA</b>	<b>.014</b>	<b>2.632</b>
<b>1975 Total</b> .....	<b>1.761</b>	<b>.032</b>	<b>.074</b>	<b>.012</b>	<b>.427</b>	<b>.439</b>	<b>NA</b>	<b>.017</b>	<b>2.323</b>
<b>1980 Total</b> .....	<b>2.421</b>	<b>.051</b>	<b>.049</b>	<b>.609</b>	<b>.551</b>	<b>1.160</b>	<b>NA</b>	<b>.014</b>	<b>3.695</b>
<b>1985 Total</b> .....	<b>2.438</b>	<b>.028</b>	<b>.056</b>	<b>.432</b>	<b>1.225</b>	<b>1.657</b>	<b>NA</b>	<b>.017</b>	<b>4.196</b>
<b>1990 Total</b> .....	<b>2.772</b>	<b>.014</b>	<b>.087</b>	<b>.230</b>	<b>1.594</b>	<b>1.824</b>	<b>NA</b>	<b>.055</b>	<b>4.752</b>
<b>1995 Total</b> .....	<b>2.318</b>	<b>.034</b>	<b>.156</b>	<b>.200</b>	<b>1.776</b>	<b>1.976</b>	<b>NA</b>	<b>.012</b>	<b>4.496</b>
<b>2000 Total</b> .....	<b>1.528</b>	<b>.028</b>	<b>.245</b>	<b>.106</b>	<b>2.003</b>	<b>2.110</b>	<b>NA</b>	<b>.051</b>	<b>3.962</b>
<b>2005 Total</b> .....	<b>1.273</b>	<b>.043</b>	<b>.735</b>	<b>.067</b>	<b>2.276</b>	<b>2.344</b>	<b>(s)</b>	<b>.065</b>	<b>4.462</b>
<b>2006 Total</b> .....	<b>1.264</b>	<b>.040</b>	<b>.730</b>	<b>.052</b>	<b>2.554</b>	<b>2.606</b>	<b>(s)</b>	<b>.083</b>	<b>4.727</b>
<b>2007 Total</b> .....	<b>1.507</b>	<b>.036</b>	<b>.830</b>	<b>.058</b>	<b>2.803</b>	<b>2.861</b>	<b>.036</b>	<b>.069</b>	<b>5.338</b>
<b>2008 Total</b> .....	<b>2.071</b>	<b>.049</b>	<b>.972</b>	<b>.061</b>	<b>3.626</b>	<b>3.686</b>	<b>.089</b>	<b>.083</b>	<b>6.949</b>
<b>2009 Total</b> .....	<b>1.515</b>	<b>.032</b>	<b>1.082</b>	<b>.093</b>	<b>4.101</b>	<b>4.194</b>	<b>.035</b>	<b>.062</b>	<b>6.920</b>
<b>2010 Total</b> .....	<b>2.101</b>	<b>.036</b>	<b>1.147</b>	<b>.088</b>	<b>4.691</b>	<b>4.780</b>	<b>.047</b>	<b>.065</b>	<b>8.176</b>
<b>2011 Total</b> .....	<b>2.751</b>	<b>.024</b>	<b>1.519</b>	<b>.100</b>	<b>5.820</b>	<b>5.919</b>	<b>.108</b>	<b>.051</b>	<b>10.373</b>
<b>2012 Total</b> .....	<b>3.087</b>	<b>.024</b>	<b>1.633</b>	<b>.143</b>	<b>6.261</b>	<b>6.404</b>	<b>.078</b>	<b>.041</b>	<b>11.267</b>
<b>2013 Total</b> .....	<b>2.895</b>	<b>.021</b>	<b>1.587</b>	<b>.284</b>	<b>6.886</b>	<b>7.170</b>	<b>.076</b>	<b>.039</b>	<b>11.788</b>
<b>2014 Total</b> .....	<b>2.435</b>	<b>.023</b>	<b>1.528</b>	<b>.744</b>	<b>7.414</b>	<b>8.158</b>	<b>.081</b>	<b>.045</b>	<b>12.270</b>
<b>2015 Total</b> .....	<b>1.852</b>	<b>.021</b>	<b>1.800</b>	<b>.964</b>	<b>8.153</b>	<b>9.118</b>	<b>.080</b>	<b>.031</b>	<b>12.902</b>
<b>2016 Total</b> .....	<b>1.546</b>	<b>.025</b>	<b>2.356</b>	<b>1.238</b>	<b>8.752</b>	<b>9.990</b>	<b>.181</b>	<b>.021</b>	<b>14.119</b>
<b>2017 Total</b> .....	<b>2.388</b>	<b>.030</b>	<b>3.182</b>	<b>2.424</b>	<b>9.684</b>	<b>12.108</b>	<b>.206</b>	<b>.032</b>	<b>17.946</b>
<b>2018 Total</b> .....	<b>2.824</b>	<b>.029</b>	<b>3.640</b>	<b>4.277</b>	<b>10.158</b>	<b>14.434</b>	<b>.249</b>	<b>.047</b>	<b>21.224</b>
<b>2019 January</b> .....	<b>.229</b>	<b>.003</b>	<b>.368</b>	<b>.468</b>	<b>.820</b>	<b>1.287</b>	<b>.018</b>	<b>.005</b>	<b>1.910</b>
February .....	.166	.001	.333	.466	.737	1.203	.017	.005	1.725
March .....	.225	.001	.377	.473	.806	1.279	.022	.009	1.912
April .....	.212	.002	.341	.498	.810	1.309	.022	.007	1.893
May .....	.221	.002	.372	.524	.811	1.335	.019	.006	1.954
June .....	.204	.002	.363	.531	.813	1.344	.021	.005	1.940
July .....	.159	.002	.397	.479	.825	1.304	.020	.007	1.889
August .....	.190	.002	.388	.487	.873	1.360	.022	.006	1.969
September .....	.190	.003	.398	.530	.831	1.360	.019	.006	1.977
October .....	.162	.003	.430	.604	.866	1.470	.018	.005	2.088
November .....	.186	.002	.445	.527	.844	1.372	.018	.004	2.028
December .....	.160	.003	.485	.626	.889	1.515	.023	.004	2.190
<b>Total</b> .....	<b>2.305</b>	<b>.024</b>	<b>4.698</b>	<b>6.212</b>	<b>9.926</b>	<b>16.139</b>	<b>.240</b>	<b>.068</b>	<b>23.474</b>
<b>2020 January</b> .....	<b>.156</b>	<b>.002</b>	<b>.515</b>	<b>.575</b>	<b>.892</b>	<b>1.467</b>	<b>.020</b>	<b>.005</b>	<b>2.164</b>
February .....	.171	.002	.458	.614	.879	1.493	.025	.006	2.154
March .....	.173	.001	.502	.630	.913	1.542	.023	.004	2.245
April .....	.137	.001	.425	.527	.782	1.309	.020	.005	1.897
May .....	.118	.001	.399	.518	.585	1.103	.016	.005	1.643
June .....	.114	(s)	.342	.472	.720	1.192	.019	.004	1.671
July .....	.134	.001	.352	.578	.777	1.355	.015	.004	1.861
August .....	.113	.001	.362	.584	.782	1.366	.020	.003	1.865
September .....	.134	.001	.399	.555	.750	1.305	.019	.003	1.861
October .....	.126	.003	.486	.519	.816	1.336	.020	.003	1.973
November .....	.175	.002	.532	.467	.743	1.210	.019	.003	1.941
December .....	.175	.001	.557	.597	.839	1.436	.021	.003	2.192
<b>Total</b> .....	<b>1.726</b>	<b>.017</b>	<b>5.329</b>	<b>6.636</b>	<b>9.478</b>	<b>16.114</b>	<b>.235</b>	<b>.048</b>	<b>23.469</b>
<b>2021 January</b> .....	<b>.143</b>	<b>.003</b>	<b>.567</b>	<b>.560</b>	<b>.834</b>	<b>1.394</b>	<b>R .023</b>	<b>.003</b>	<b>2.135</b>
February .....	.185	.003	.430	.432	.674	1.106	.018	.009	1.751
<b>2-Month Total</b> .....	<b>.328</b>	<b>.006</b>	<b>.998</b>	<b>.992</b>	<b>1.508</b>	<b>2.501</b>	<b>.042</b>	<b>.012</b>	<b>3.885</b>
<b>2020 2-Month Total</b> .....	<b>.326</b>	<b>.003</b>	<b>.973</b>	<b>1.189</b>	<b>1.771</b>	<b>2.960</b>	<b>.045</b>	<b>.011</b>	<b>4.318</b>
<b>2019 2-Month Total</b> .....	<b>.395</b>	<b>.004</b>	<b>.701</b>	<b>.934</b>	<b>1.557</b>	<b>2.490</b>	<b>.035</b>	<b>.010</b>	<b>3.635</b>

<sup>a</sup> Crude oil and lease condensate.

<sup>b</sup> Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

<sup>c</sup> Beginning in 2001, includes biodiesel. Beginning in 2010, also includes fuel ethanol (minus denaturant). Beginning in 2016, also includes wood and wood-derived fuels.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 1.4c Primary Energy Net Imports**

(Quadrillion Btu)


Total, 1949–2020




By Major Source, 1949–2020



Total, Monthly



By Major Source, Monthly



[a] Crude oil and lease condensate. Includes imports into the Strategic Petroleum Reserve, which began in 1977.

[b] Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

[c] Includes coal coke.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.4c.

**Table 1.4c Primary Energy Net Imports by Source**  
(Quadrillion Btu)

	Net Imports <sup>a</sup>								
	Coal	Coal Coke	Natural Gas	Petroleum			Biomass <sup>d</sup>	Electricity	Total
				Crude Oil <sup>b</sup>	Petroleum Products <sup>c</sup>	Total			
<b>1950 Total</b> .....	-0.777	0.001	-0.027	0.854	0.390	1.244	NA	0.006	0.448
<b>1955 Total</b> .....	-1.456	-.010	-.021	1.624	.354	1.978	NA	.014	.504
<b>1960 Total</b> .....	-1.017	-.006	.149	2.178	1.389	3.568	NA	.015	2.710
<b>1965 Total</b> .....	-1.372	-.018	.444	2.648	2.362	5.010	NA	(s)	4.063
<b>1970 Total</b> .....	-1.935	-.058	.774	2.785	4.136	6.921	NA	.007	5.709
<b>1975 Total</b> .....	-1.738	.014	.904	8.708	3.800	12.508	NA	.021	11.709
<b>1980 Total</b> .....	-2.391	-.035	.957	10.586	2.912	13.499	NA	.071	12.101
<b>1985 Total</b> .....	-2.389	-.013	.896	6.381	2.570	8.952	NA	.140	7.584
<b>1990 Total</b> .....	-2.705	.005	1.464	12.536	2.757	15.293	NA	.008	14.065
<b>1995 Total</b> .....	-2.081	.061	2.745	15.469	1.355	16.824	NA	.134	17.684
<b>2000 Total</b> .....	-1.215	.065	3.623	19.676	2.638	22.314	NA	.115	24.904
<b>2005 Total</b> .....	-.512	.044	3.714	22.023	4.831	26.855	.011	.085	30.197
<b>2006 Total</b> .....	-.358	.061	3.560	22.032	4.501	26.533	.062	.063	29.921
<b>2007 Total</b> .....	-.598	.025	3.893	21.855	4.040	25.895	.019	.107	29.341
<b>2008 Total</b> .....	-1.215	.041	3.112	21.388	2.588	23.976	-.004	.112	26.021
<b>2009 Total</b> .....	-.949	-.024	2.763	19.606	1.266	20.872	-.009	.116	22.770
<b>2010 Total</b> .....	-1.617	-.006	2.687	20.052	.528	20.580	-.042	.089	21.690
<b>2011 Total</b> .....	-2.423	.011	2.036	19.495	-.781	18.714	-.089	.127	18.375
<b>2012 Total</b> .....	-2.875	.004	1.583	19.096	-2.139	16.957	-.029	.161	15.801
<b>2013 Total</b> .....	-2.696	-.017	1.369	16.673	-2.717	13.956	.026	.197	12.835
<b>2014 Total</b> .....	-2.183	-.022	1.235	15.434	-3.641	11.793	-.034	.182	10.971
<b>2015 Total</b> .....	-1.596	-.018	.986	15.335	-4.042	11.292	-.001	.227	10.892
<b>2016 Total</b> .....	-1.326	-.019	.725	16.154	-4.443	11.710	-.058	.227	11.259
<b>2017 Total</b> .....	-2.220	-.029	-.073	15.173	-5.407	9.766	-.124	.192	7.512
<b>2018 Total</b> .....	-2.702	-.026	-.679	12.915	-5.849	7.066	-.201	.152	3.610
<b>2019 January</b> .....	-.217	-.003	-.070	.952	-.450	.503	-.013	.011	.212
February .....	-.159	-.001	-.094	.666	-.434	.232	-.014	.011	-.024
March .....	-.210	-.001	-.118	.801	-.453	.349	-.016	.008	.013
April .....	-.201	-.001	-.130	.774	-.402	.373	-.017	.008	.032
May .....	-.212	-.002	-.159	.821	-.352	.468	-.013	.010	.092
June .....	-.191	-.002	-.157	.770	-.469	.301	-.014	.012	-.051
July .....	-.149	-.002	-.161	.825	-.381	.444	-.014	.013	.132
August .....	-.180	-.001	-.163	.817	-.465	.353	-.017	.014	.006
September .....	-.177	-.002	-.185	.649	-.473	.176	-.012	.012	-.188
October .....	-.147	-.002	-.214	.569	-.474	.095	-.011	.007	-.272
November .....	-.177	-.002	-.216	.530	-.476	.055	-.012	.012	-.340
December .....	-.149	-.003	-.223	.658	-.502	.156	-.016	.014	-.221
<b>Total</b> .....	<b>-2.167</b>	<b>-.021</b>	<b>-1.888</b>	<b>8.833</b>	<b>-5.331</b>	<b>3.502</b>	<b>-.168</b>	<b>.133</b>	<b>-.609</b>
<b>2020 January</b> .....	-.145	-.001	-.246	.632	-.527	.105	-.014	.011	-.291
February .....	-.164	-.002	-.214	.535	-.574	-.039	-.020	.010	-.428
March .....	-.163	-.001	-.283	.557	-.567	-.011	-.018	.013	-.463
April .....	-.129	-.001	-.230	.479	-.505	-.026	-.013	.011	-.388
May .....	-.108	(s)	-.208	.629	-.305	.324	-.011	.012	.009
June .....	-.109	(s)	-.149	.695	-.400	.295	-.013	.013	.037
July .....	-.124	(s)	-.137	.535	-.450	.085	-.011	.019	-.168
August .....	-.107	-.001	-.146	.440	-.441	-.001	-.013	.020	-.247
September .....	-.124	-.001	-.220	.430	-.401	.028	-.013	.013	-.316
October .....	-.121	-.001	-.282	.478	-.468	.010	-.012	.013	-.393
November .....	-.162	-.002	-.315	.549	-.412	.137	-.011	.012	-.342
December .....	-.166	-.001	-.284	.480	-.502	-.022	-.013	.015	-.472
<b>Total</b> .....	<b>-1.622</b>	<b>-.013</b>	<b>-2.713</b>	<b>6.439</b>	<b>-5.554</b>	<b>.885</b>	<b>-.162</b>	<b>.161</b>	<b>-3.463</b>
<b>2021 January</b> .....	-.132	-.003	-.276	.530	-.475	.055	-.018	.016	-.359
February .....	-.179	-.003	-.152	.519	-.362	.157	-.013	.003	-.185
<b>2-Month Total</b> .....	<b>-.311</b>	<b>-.006</b>	<b>-.428</b>	<b>1.049</b>	<b>-.837</b>	<b>.212</b>	<b>-.031</b>	<b>.019</b>	<b>-.544</b>
<b>2020 2-Month Total</b> .....	<b>-.309</b>	<b>-.003</b>	<b>-.460</b>	<b>1.168</b>	<b>-1.101</b>	<b>.066</b>	<b>-.034</b>	<b>.021</b>	<b>-.719</b>
<b>2019 2-Month Total</b> .....	<b>-.375</b>	<b>-.004</b>	<b>-.164</b>	<b>1.619</b>	<b>-.884</b>	<b>.735</b>	<b>-.027</b>	<b>.022</b>	<b>.187</b>

<sup>a</sup> Net imports equal imports minus exports.

<sup>b</sup> Crude oil and lease condensate. Includes imports into the Strategic Petroleum Reserve, which began in 1977.

<sup>c</sup> Petroleum products, unfinished oils, natural gasoline, and gasoline blending components. Does not include biofuels.

<sup>d</sup> Beginning in 1993, includes fuel ethanol (minus denaturant) imports. Beginning in 2001, also includes biodiesel imports and exports. From 2009-2011, also includes other renewable fuels imports. Beginning in 2010, also includes fuel ethanol (minus denaturant) exports. Beginning in 2012, also includes other renewable diesel fuel imports. Beginning in 2016, also includes wood and

wood-derived fuels exports.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: Tables 1.4a and 1.4b.


**Figure 1.5 Merchandise Trade Value**

(Billion Dollars[a])

Imports and Exports, 1974–2020




Imports and Exports, Monthly



Trade Balance, 1974–2020



Trade Balance, Monthly



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.5.



**Table 1.5 Merchandise Trade Value**  
(Million Dollars<sup>a</sup>)

	Petroleum <sup>b</sup>			Energy <sup>c</sup>			Non-Energy Balance	Total Merchandise		
	Exports	Imports	Balance	Exports	Imports	Balance		Exports	Imports	Balance
<b>1974 Total</b> .....	792	24,668	-23,876	3,444	25,454	-22,010	18,126	99,437	103,321	-3,884
<b>1975 Total</b> .....	907	25,197	-24,289	4,470	26,476	-22,006	31,557	108,856	99,305	9,551
<b>1980 Total</b> .....	2,833	78,637	-75,803	7,982	82,924	-74,942	55,246	225,566	245,262	-19,696
<b>1985 Total</b> .....	4,707	50,475	-45,768	9,971	53,917	-43,946	-73,765	218,815	336,526	-117,712
<b>1990 Total</b> .....	6,901	61,583	-54,682	12,233	64,661	-52,428	-50,068	393,592	496,088	-102,496
<b>1995 Total</b> .....	6,321	54,368	-48,047	10,358	59,109	-48,751	-110,050	584,742	743,543	-158,801
<b>2000 Total</b> .....	8,569	102,663	-94,094	11,541	115,748	-104,207	-364,056	693,103	1,161,366	-468,263
<b>2005 Total</b> .....	19,155	250,068	-230,913	26,488	289,723	-263,235	-504,242	905,978	1,673,455	-767,477
<b>2006 Total</b> .....	28,171	299,714	-271,543	34,711	332,500	-297,789	-519,515	1,036,635	1,853,938	-817,304
<b>2007 Total</b> .....	33,293	327,620	-294,327	41,725	364,987	-323,262	-485,501	1,148,199	1,956,962	-808,763
<b>2008 Total</b> .....	61,695	449,847	-388,152	76,075	491,885	-415,810	-400,389	1,287,442	2,103,641	-816,199
<b>2009 Total</b> .....	44,509	251,833	-207,324	54,536	271,739	-217,203	-286,379	1,056,043	1,559,625	-503,582
<b>2010 Total</b> .....	64,753	333,472	-268,719	80,625	354,982	-274,357	-361,005	1,278,495	1,913,857	-635,362
<b>2011 Total</b> .....	<sup>b</sup> 102,180	<sup>b</sup> 431,866	<sup>b</sup> -329,686	128,989	453,839	-324,850	-400,597	1,482,508	2,207,954	-725,447
<b>2012 Total</b> .....	111,949	408,509	-296,560	136,054	423,860	-287,806	-442,640	1,545,821	2,276,267	-730,446
<b>2013 Total</b> .....	123,244	363,141	-239,897	147,572	379,758	-232,186	-457,284	1,578,517	2,267,987	-689,470
<b>2014 Total</b> .....	127,818	326,709	-198,891	154,498	347,474	-192,976	-541,506	1,621,874	2,356,356	-734,482
<b>2015 Total</b> .....	85,890	177,455	-91,565	103,612	190,501	-86,889	-658,594	1,503,328	2,248,811	-745,483
<b>2016 Total</b> .....	74,921	142,920	-67,999	92,971	153,800	-60,829	-674,497	1,451,460	2,186,786	-735,326
<b>2017 Total</b> .....	104,975	181,672	-76,697	137,920	194,790	-56,870	-735,526	1,547,195	2,339,591	-792,396
<b>2018 Total</b> .....	149,661	219,489	-69,828	190,843	232,741	-41,898	-830,143	1,665,688	2,537,729	-872,041
<b>2019 January</b> .....	11,965	14,077	-2,112	15,609	15,674	-65	-74,915	129,608	204,587	-74,980
February .....	11,642	12,273	-631	14,555	13,581	974	-56,750	129,919	185,694	-55,776
March .....	12,896	15,335	-2,439	16,389	16,707	-318	-59,179	148,472	207,969	-59,497
April .....	12,953	17,808	-4,855	16,746	18,631	-1,885	-72,450	134,838	209,174	-74,335
May .....	13,369	20,087	-6,718	16,948	20,860	-3,912	-74,442	142,237	220,591	-78,354
June .....	12,771	16,978	-4,207	16,142	17,657	-1,515	-67,782	137,870	207,167	-69,297
July .....	12,669	18,265	-5,596	16,000	19,036	-3,036	-82,634	133,129	218,799	-85,670
August .....	13,196	16,240	-3,044	16,122	17,009	-887	-76,449	138,310	215,647	-77,336
September .....	12,912	14,396	-1,484	16,289	15,131	1,158	-73,721	134,162	206,725	-72,563
October .....	13,925	15,027	-1,102	17,376	15,804	1,572	-78,569	142,418	219,414	-76,997
November .....	13,187	13,281	-94	16,798	14,279	2,519	-65,055	136,940	199,476	-62,536
December .....	15,069	15,307	-238	18,863	16,531	2,332	-69,364	135,258	202,289	-67,032
<b>Total</b> .....	<b>156,553</b>	<b>189,075</b>	<b>-32,522</b>	<b>197,836</b>	<b>200,900</b>	<b>-3,064</b>	<b>-851,307</b>	<b>1,643,161</b>	<b>2,497,531</b>	<b>-854,371</b>
<b>2020 January</b> .....	14,000	14,873	-873	17,912	15,914	1,998	-69,402	128,993	196,397	-67,404
February .....	14,074	12,543	1,531	17,509	13,286	4,223	-50,326	132,182	178,285	-46,103
March .....	12,407	11,023	1,384	15,863	11,628	4,235	-64,057	134,560	194,382	-59,822
April .....	7,904	5,966	1,938	10,749	6,485	4,264	-73,916	95,799	165,452	-69,652
May .....	4,960	5,907	-947	7,559	6,518	1,041	-74,423	90,549	163,931	-73,382
June .....	6,722	7,555	-833	9,275	8,108	1,167	-75,820	105,056	179,709	-74,653
July .....	8,712	8,644	68	11,391	9,348	2,043	-90,055	112,827	200,839	-88,012
August .....	9,177	9,445	-268	11,946	10,230	1,716	-87,131	118,044	203,459	-85,415
September .....	8,878	9,156	-278	11,836	9,833	2,003	-86,929	121,469	206,395	-84,926
October .....	8,603	8,927	-324	12,197	9,715	2,482	-89,413	132,571	219,502	-86,931
November .....	8,027	8,716	-689	12,294	9,717	2,577	-88,299	127,024	212,746	-85,722
December .....	10,246	9,981	265	14,966	11,254	3,712	-86,640	132,537	215,465	-82,928
<b>Total</b> .....	<b>113,711</b>	<b>112,736</b>	<b>975</b>	<b>153,497</b>	<b>122,036</b>	<b>31,461</b>	<b>-936,412</b>	<b>1,431,610</b>	<b>2,336,561</b>	<b>-904,951</b>
<b>2021 January</b> .....	10,253	10,941	-688	15,148	12,051	3,097	-80,055	127,860	204,818	-76,958
February .....	8,965	10,696	-1,731	16,061	12,611	3,450	<sup>R</sup> -73,253	<sup>R</sup> 124,010	<sup>R</sup> 193,813	<sup>R</sup> -69,803
March .....	10,317	14,638	-4,321	15,977	15,835	142	-85,836	151,600	237,293	-85,694
<b>3-Month Total</b> .....	<b>29,535</b>	<b>36,275</b>	<b>-6,740</b>	<b>47,185</b>	<b>40,497</b>	<b>6,689</b>	<b>-239,144</b>	<b>403,469</b>	<b>635,924</b>	<b>-232,454</b>
<b>2020 3-Month Total</b> .....	<b>40,481</b>	<b>38,439</b>	<b>2,042</b>	<b>51,284</b>	<b>40,828</b>	<b>10,456</b>	<b>-183,785</b>	<b>395,735</b>	<b>569,064</b>	<b>-173,330</b>
<b>2019 3-Month Total</b> .....	<b>36,503</b>	<b>41,685</b>	<b>-5,182</b>	<b>46,553</b>	<b>45,962</b>	<b>591</b>	<b>-190,844</b>	<b>407,998</b>	<b>598,250</b>	<b>-190,252</b>

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> Through 2010, data are for crude oil, petroleum preparations, liquefied propane and butane, and other mineral fuels. Beginning in 2011, data are for petroleum products and preparations.

<sup>c</sup> Petroleum, coal, natural gas, and electricity.

R=Revised.

Notes: • Monthly data are not adjusted for seasonal variations. • See Note 1, "Merchandise Trade Value," at end of section. • Totals may not equal sum of


components due to independent rounding. • The U.S. import statistics reflect both government and nongovernment imports of merchandise from foreign countries into the U.S. customs territory, which comprises the 50 states, the District of Columbia, Puerto Rico, and the Virgin Islands.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual and monthly data beginning in 1974.


Sources: See end of section.

**Figure 1.6 Cost of Fuels to End Users In Real (1982-1984) Dollars**


Costs, 1960–2020




Costs, February 2021




Residential Electricity, [a] Monthly



Motor Gasoline, [a] Monthly



Residential Natural Gas, [a] Monthly



[a] Includes Taxes.

[b] Excludes Taxes.

Note: See "Real Dollars" in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Tables 1.6.

**Table 1.6 Cost of Fuels to End Users in Real (1982–1984) Dollars**

	Consumer Price Index, All Urban Consumers <sup>a</sup>	Motor Gasoline <sup>b</sup>		Residential Heating Oil <sup>c</sup>		Residential Natural Gas <sup>b</sup>		Residential Electricity <sup>b</sup>	
	Index 1982–1984=100	Dollars per Gallon	Dollars per Million Btu	Dollars per Gallon	Dollars per Million Btu	Dollars per Thousand Cubic Feet	Dollars per Million Btu	Cents per Kilowatthour	Dollars per Million Btu
<b>1960 Average</b> .....	<b>29.6</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>8.8</b>	<b>25.74</b>
<b>1965 Average</b> .....	<b>31.5</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>7.6</b>	<b>22.33</b>
<b>1970 Average</b> .....	<b>38.8</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>2.81</b>	<b>2.72</b>	<b>5.7</b>	<b>16.62</b>
<b>1975 Average</b> .....	<b>53.8</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>3.18</b>	<b>3.12</b>	<b>6.5</b>	<b>19.07</b>
<b>1981 Average</b> .....	<b>90.9</b>	<b>1.488</b>	<b>11.90</b>	<b>1.314</b>	<b>9.47</b>	<b>4.72</b>	<b>4.60</b>	<b>6.8</b>	<b>19.99</b>
<b>1986 Average</b> .....	<b>109.6</b>	<b>0.849</b>	<b>6.79</b>	<b>0.763</b>	<b>5.50</b>	<b>5.32</b>	<b>5.17</b>	<b>6.77</b>	<b>19.84</b>
<b>1991 Average</b> .....	<b>136.2</b>	<b>0.878</b>	<b>7.02</b>	<b>0.748</b>	<b>5.39</b>	<b>4.27</b>	<b>4.14</b>	<b>5.90</b>	<b>17.30</b>
<b>1996 Average</b> .....	<b>156.9</b>	<b>0.821</b>	<b>6.62</b>	<b>0.630</b>	<b>4.54</b>	<b>4.04</b>	<b>3.94</b>	<b>5.33</b>	<b>15.62</b>
<b>2001 Average</b> .....	<b>177.1</b>	<b>0.864</b>	<b>6.98</b>	<b>0.706</b>	<b>5.09</b>	<b>5.44</b>	<b>5.28</b>	<b>4.84</b>	<b>14.20</b>
<b>2002 Average</b> .....	<b>179.9</b>	<b>0.801</b>	<b>6.47</b>	<b>0.628</b>	<b>4.52</b>	<b>4.39</b>	<b>4.28</b>	<b>4.69</b>	<b>13.75</b>
<b>2003 Average</b> .....	<b>184.0</b>	<b>0.890</b>	<b>7.19</b>	<b>0.736</b>	<b>5.31</b>	<b>5.23</b>	<b>5.09</b>	<b>4.74</b>	<b>13.89</b>
<b>2004 Average</b> .....	<b>188.9</b>	<b>1.018</b>	<b>8.23</b>	<b>0.819</b>	<b>5.91</b>	<b>5.69</b>	<b>5.55</b>	<b>4.74</b>	<b>13.89</b>
<b>2005 Average</b> .....	<b>195.3</b>	<b>1.197</b>	<b>9.68</b>	<b>1.051</b>	<b>7.58</b>	<b>6.50</b>	<b>6.33</b>	<b>4.84</b>	<b>14.18</b>
<b>2006 Average</b> .....	<b>201.6</b>	<b>1.307</b>	<b>10.59</b>	<b>1.173</b>	<b>8.46</b>	<b>6.81</b>	<b>6.63</b>	<b>5.16</b>	<b>15.12</b>
<b>2007 Average</b> .....	<b>207.3</b>	<b>1.374</b>	<b>11.22</b>	<b>1.250</b>	<b>9.01</b>	<b>6.31</b>	<b>6.14</b>	<b>5.14</b>	<b>15.05</b>
<b>2008 Average</b> .....	<b>215.303</b>	<b>1.541</b>	<b>12.67</b>	<b>1.495</b>	<b>10.78</b>	<b>6.45</b>	<b>6.28</b>	<b>5.23</b>	<b>15.33</b>
<b>2009 Average</b> .....	<b>214.537</b>	<b>1.119</b>	<b>9.23</b>	<b>1.112</b>	<b>8.02</b>	<b>5.66</b>	<b>5.52</b>	<b>5.37</b>	<b>15.72</b>
<b>2010 Average</b> .....	<b>218.056</b>	<b>1.301</b>	<b>10.78</b>	<b>1.283</b>	<b>9.25</b>	<b>5.22</b>	<b>5.11</b>	<b>5.29</b>	<b>15.51</b>
<b>2011 Average</b> .....	<b>224.939</b>	<b>1.590</b>	<b>13.19</b>	<b>NA</b>	<b>NA</b>	<b>4.90</b>	<b>4.80</b>	<b>5.21</b>	<b>15.27</b>
<b>2012 Average</b> .....	<b>229.594</b>	<b>1.609</b>	<b>13.35</b>	<b>NA</b>	<b>NA</b>	<b>4.64</b>	<b>4.53</b>	<b>5.17</b>	<b>15.17</b>
<b>2013 Average</b> .....	<b>232.957</b>	<b>1.538</b>	<b>12.77</b>	<b>NA</b>	<b>NA</b>	<b>4.43</b>	<b>4.31</b>	<b>5.21</b>	<b>15.26</b>
<b>2014 Average</b> .....	<b>236.736</b>	<b>1.447</b>	<b>12.01</b>	<b>NA</b>	<b>NA</b>	<b>4.63</b>	<b>4.49</b>	<b>5.29</b>	<b>15.50</b>
<b>2015 Average</b> .....	<b>237.017</b>	<b>1.059</b>	<b>8.80</b>	<b>NA</b>	<b>NA</b>	<b>4.38</b>	<b>4.22</b>	<b>5.34</b>	<b>15.64</b>
<b>2016 Average</b> .....	<b>240.007</b>	<b>0.918</b>	<b>7.63</b>	<b>NA</b>	<b>NA</b>	<b>4.19</b>	<b>4.03</b>	<b>5.23</b>	<b>15.33</b>
<b>2017 Average</b> .....	<b>245.120</b>	<b>1.007</b>	<b>8.37</b>	<b>NA</b>	<b>NA</b>	<b>4.45</b>	<b>4.29</b>	<b>5.26</b>	<b>15.41</b>
<b>2018 Average</b> .....	<b>251.107</b>	<b>1.113</b>	<b>9.25</b>	<b>NA</b>	<b>NA</b>	<b>4.18</b>	<b>4.03</b>	<b>5.13</b>	<b>15.02</b>
<b>2019</b>									
January .....	251.712	0.934	7.77	NA	NA	3.72	3.58	4.95	14.52
February .....	252.776	0.954	7.93	NA	NA	3.72	3.58	5.03	14.75
March .....	254.202	1.031	8.57	NA	NA	3.71	3.56	5.05	14.80
April .....	255.548	1.132	9.41	NA	NA	4.25	4.08	5.18	15.20
May .....	256.092	1.157	9.62	NA	NA	4.98	4.79	5.20	15.23
June .....	256.143	1.099	9.13	NA	NA	6.07	5.84	5.20	15.24
July .....	256.571	1.105	9.19	NA	NA	6.91	6.65	5.17	15.15
August .....	256.558	1.059	8.80	NA	NA	7.16	6.89	5.18	15.19
September .....	256.759	1.049	8.72	NA	NA	6.86	6.59	5.13	15.02
October .....	257.346	1.065	8.85	NA	NA	4.86	4.67	4.98	14.59
November .....	257.208	1.045	8.68	NA	NA	3.63	3.49	5.07	14.85
December .....	256.974	1.032	8.58	NA	NA	3.62	3.48	4.93	14.46
<b>Average</b> .....	<b>255.657</b>	<b>1.055</b>	<b>8.77</b>	<b>NA</b>	<b>NA</b>	<b>4.11</b>	<b>3.95</b>	<b>5.09</b>	<b>14.91</b>
<b>2020</b>									
January .....	257.971	1.020	8.48	NA	NA	3.69	3.55	4.96	14.53
February .....	258.678	0.978	8.13	NA	NA	3.53	3.39	4.97	14.56
March .....	258.115	0.904	7.52	NA	NA	3.82	3.67	5.07	14.85
April .....	256.389	0.759	6.31	NA	NA	4.16	4.00	5.18	15.18
May .....	256.394	0.759	6.31	NA	NA	4.62	4.45	5.13	15.03
June .....	257.797	0.830	6.90	NA	NA	5.96	5.74	5.15	15.09
July .....	259.101	0.866	7.20	NA	NA	6.80	6.55	5.11	14.99
August .....	259.918	0.864	7.18	NA	NA	7.09	6.82	5.12	15.01
September .....	260.280	0.868	7.22	NA	NA	6.53	6.28	5.20	15.25
October .....	260.388	0.856	7.11	NA	NA	4.75	4.57	5.26	15.42
November .....	260.229	0.830	6.90	NA	NA	4.25	4.09	5.13	15.04
December .....	260.474	0.858	7.13	NA	NA	3.77	3.62	4.91	14.40
<b>Average</b> .....	<b>258.811</b>	<b>0.866</b>	<b>7.20</b>	<b>NA</b>	<b>NA</b>	<b>4.19</b>	<b>4.03</b>	<b>5.10</b>	<b>14.95</b>
<b>2021</b>									
January .....	261.582	0.914	7.60	NA	NA	3.72	3.58	4.85	14.22
February .....	263.014	0.973	8.09	NA	NA	R 3.63	R 3.49	R 5.07	R 14.87
March .....	264.877	1.078	8.96	NA	NA	NA	NA	NA	NA
April .....	267.054	1.089	9.05	NA	NA	NA	NA	NA	NA

<sup>a</sup> Data are U.S. city averages for all items, and are not seasonally adjusted.

<sup>b</sup> Includes taxes.

<sup>c</sup> Excludes taxes.

R=Revised. NA=Not available.


Notes: • See "Real Dollars" in Glossary. • Fuel costs are calculated by using the Urban Consumer Price Index (CPI) developed by the Bureau of Labor Statistics. • Annual averages may not equal average of months due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1960 and monthly data beginning in 1995.


Sources: • **Fuel Prices:** Tables 9.4 (All Grades), 9.8, and 9.10, adjusted by the CPI; and *Monthly Energy Review*, September 2012, Table 9.8c. • **Consumer Price Index, All Urban Consumers:** U.S. Department of Labor, Bureau of Labor Statistics, series ID CUUR0000SA0. • **Conversion Factors:** Tables A1, A3, A4, and A6.

**Figure 1.7 Primary Energy Consumption and Energy Expenditures Indicators**


Energy Consumption per Capita, 1949–2020



Primary Energy Consumption per Real Dollar [a] of Gross Domestic Product, 1949–2020



Energy Expenditures as Share of Gross Domestic Product and Gross Output,[b] 1970–2018



[a] See “Chained Dollars” and “Real Dollars” in Glossary.

[b] Gross output is the value of gross domestic product (GDP) plus the value of intermediate inputs used to produce GDP.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.7.

**Table 1.7 Primary Energy Consumption, Energy Expenditures, and Carbon Dioxide Emissions Indicators**

	Primary Energy Consumption <sup>a</sup>			Energy Expenditures <sup>b</sup>				Carbon Dioxide Emissions <sup>c</sup>		
	Consumption	Consumption per Capita	Consumption per Real Dollar <sup>d</sup> of GDP <sup>e</sup>	Expenditures	Expenditures per Capita	Expenditures as Share of GDP <sup>e</sup>	Expenditures as Share of Gross Output <sup>f</sup>	Emissions	Emissions per Capita	Emissions per Real Dollar <sup>d</sup> of GDP <sup>e</sup>
	Quadrillion Btu	Million Btu	Thousand Btu per Chained (2012) Dollar <sup>d</sup>	Million Nominal Dollars <sup>g</sup>	Nominal Dollars <sup>g</sup>	Percent	Percent	Million Metric Tons Carbon Dioxide	Metric Tons Carbon Dioxide	Metric Tons Carbon Dioxide per Million Chained (2012) Dollars <sup>d</sup>
1950 .....	34.599	227	15.11	NA	NA	NA	NA	2,382	15.6	1,040
1955 .....	40.178	242	13.99	NA	NA	NA	NA	2,685	16.2	935
1960 .....	45.041	249	13.82	NA	NA	NA	NA	2,914	16.1	894
1965 .....	53.953	278	12.94	NA	NA	NA	NA	3,462	17.8	830
1970 .....	67.817	331	13.70	82,875	404	7.7	4.4	4,261	20.8	861
1975 .....	71.931	333	12.74	171,854	796	10.2	5.6	4,428	20.5	784
1980 .....	78.021	343	11.54	374,350	1,647	13.1	6.9	4,752	20.9	703
1981 .....	76.057	331	10.97	427,901	1,865	13.3	7.1	4,628	20.2	668
1982 .....	73.046	315	10.73	426,482	1,841	12.8	6.9	4,395	19.0	646
1983 .....	72.915	312	10.24	417,622	1,786	11.5	6.3	4,372	18.7	614
1984 .....	76.571	325	10.03	435,313	1,846	10.8	6.0	4,597	19.5	602
1985 .....	76.334	321	9.60	438,343	1,842	10.1	5.6	4,588	19.3	577
1986 .....	76.599	319	9.31	384,091	1,599	8.4	4.8	4,600	19.2	559
1987 .....	79.008	326	9.28	397,627	1,641	8.2	4.6	4,758	19.6	559
1988 .....	82.659	338	9.32	411,568	1,683	7.9	4.4	4,982	20.4	562
1989 .....	84.740	343	9.22	439,051	1,779	7.8	4.4	5,069	20.5	551
1990 .....	84.433	338	9.02	474,652	1,901	8.0	4.5	5,041	20.2	538
1991 .....	84.380	334	9.02	472,440	1,867	7.7	4.4	4,996	19.7	534
1992 .....	85.725	334	8.85	476,845	1,859	7.3	4.2	5,097	19.9	526
1993 .....	87.266	336	8.77	492,275	1,894	7.2	4.1	5,187	20.0	521
1994 .....	88.983	338	8.60	504,856	1,919	6.9	3.9	5,264	20.0	508
1995 .....	90.931	341	8.55	514,624	1,933	6.7	3.8	5,324	20.0	501
1996 .....	93.935	349	8.52	560,293	2,080	6.9	3.9	5,513	20.5	500
1997 .....	94.507	347	8.20	567,962	2,083	6.6	3.7	5,583	20.5	485
1998 .....	94.920	344	7.88	526,283	1,908	5.8	3.2	5,633	20.4	468
1999 .....	96.545	346	7.66	558,627	2,002	5.8	3.2	5,694	20.4	452
2000 .....	98.702	350	7.52	687,711	2,437	6.7	3.7	5,868	20.8	447
2001 .....	96.064	337	7.24	696,242	2,443	6.6	3.7	5,766	20.2	435
2002 .....	97.535	339	7.23	663,964	2,308	6.1	3.5	5,808	20.2	430
2003 .....	97.835	337	7.05	755,070	2,603	6.6	3.7	5,858	20.2	422
2004 .....	100.002	342	6.94	871,210	2,975	7.1	4.0	5,977	20.4	415
2005 .....	100.102	339	6.71	1,045,730	3,539	8.0	4.4	5,998	20.3	402
2006 .....	99.392	333	6.48	1,158,821	3,884	8.4	4.6	5,915	19.8	386
2007 .....	100.893	335	6.46	1,233,869	4,096	8.5	4.7	6,005	19.9	384
2008 .....	98.754	325	6.33	1,408,759	4,633	9.6	5.2	5,818	19.1	373
2009 .....	93.942	306	6.18	1,066,293	3,476	7.4	4.3	5,393	17.6	355
2010 .....	97.513	315	6.25	1,214,045	3,925	8.1	4.6	5,584	18.1	358
2011 .....	96.863	311	6.11	1,391,711	4,467	9.0	5.0	5,445	17.5	344
2012 .....	94.374	301	5.83	1,355,033	4,317	8.4	4.6	5,228	16.7	323
2013 .....	97.117	307	5.89	1,376,142	4,354	8.2	4.5	5,355	16.9	325
2014 .....	98.276	309	5.81	1,394,926	4,381	8.0	4.4	5,412	17.0	320
2015 .....	97.375	304	5.59	1,128,068	3,517	6.2	3.5	5,262	16.4	302
2016 .....	97.337	301	5.49	1,038,272	3,214	5.5	3.2	5,169	16.0	292
2017 .....	97.599	300	5.38	1,136,189	3,495	5.8	3.3	5,130	15.8	283
2018 .....	101.162	310	5.41	1,271,064	3,889	6.2	3.5	5,275	16.1	282
2019 .....	100.293	305	5.25	NA	NA	NA	NA	5,140	15.7	269
2020 .....	92.943	282	5.05	NA	NA	NA	NA	4,571	13.9	248

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> Expenditures include taxes where data are available.

<sup>c</sup> Carbon dioxide emissions from energy consumption. See Table 11.1.

<sup>d</sup> See "Chained Dollars" and "Real Dollars" in Glossary.

<sup>e</sup> See "Gross Domestic Product (GDP)" in Glossary.

<sup>f</sup> Gross output is the value of GDP plus the value of intermediate inputs used to produce GDP. Through 1996, data have been adjusted by EIA based on DOC/BEA's 2012 comprehensive revision.

<sup>g</sup> See "Nominal Dollars" in Glossary.

NA=Not available.

Notes: • Data are estimates. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **Consumption:** Table 1.3. • **Consumption per Capita:**

Calculated as energy consumption divided by U.S. population (see Table C1).

• **Consumption per Real Dollar of GDP:** Calculated as energy consumption divided by U.S. gross domestic product in chained (2012) dollars (see Table C1).

• **Expenditures:** U.S. Energy Information Administration, "State Energy Price and Expenditure Estimates, 1970 Through 2018" (June 2020), U.S. Table ET1.


• **Expenditures per Capita:** Calculated as energy expenditures divided by U.S. population (see Table C1). • **Expenditures as Share of GDP:** Calculated as energy expenditures divided by U.S. gross domestic product in nominal dollars (see Table C1).

• **Expenditures as Share of Gross Output:** Calculated as energy expenditures divided by U.S. gross output (see Table C1). • **Emissions:**

1949–1972—U.S. Energy Information Administration, *Annual Energy Review 2011*, Table 11.1. 1973 forward—Table 11.1. • **Emissions per Capita:** Calculated as carbon dioxide emissions divided by U.S. population (see Table C1).

• **Emissions per Real Dollar of GDP:** Calculated as carbon dioxide emissions divided by U.S. gross domestic product in chained (2012) dollars (see Table C1).

**Figure 1.8 Motor Vehicle Mileage, Fuel Consumption, and Fuel Economy, 1949-2019**



[a] Through 1989, data are for passenger cars and motorcycles. For 1990–2006, data are for passenger cars only. Beginning in 2007, data are for light-duty vehicles (passenger cars, light trucks, vans, and sport utility vehicles) with a wheelbase less than or equal to 121 inches.

[b] For 1966–2000, data are for vans, pickup trucks, and sport utility vehicles. Beginning in 2007, data are for light-duty vehicles (passenger cars, light trucks, vans, and sport utility vehicles) with a wheelbase greater than 121 inches.

[c] For 1949–1965, data are for single-unit trucks with 2 axles and 6 or more

tires, combination trucks, and other vehicles with 2 axles and 4 tires that are not passenger cars. For 1966–2006 data are for single-unit truck with 2 axles and 6 or more tires, and combination trucks. Beginning in 2007, data are for single-unit trucks with 2 axles and 6 or more tires (or a gross vehicle weight rating exceeding 10,000 pounds), and combination trucks. Note: Through 1965, “Light-Duty Vehicles, Long Wheelbase” data are included in “Heavy-Duty Trucks.”

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.8.

**Table 1.8 Motor Vehicle Mileage, Fuel Consumption, and Fuel Economy**

	Light-Duty Vehicles, Short Wheelbase <sup>a</sup>			Light-Duty Vehicles, Long Wheelbase <sup>b</sup>			Heavy-Duty Trucks <sup>c</sup>			All Motor Vehicles <sup>d</sup>		
	Mileage	Fuel Consumption	Fuel Economy	Mileage	Fuel Consumption	Fuel Economy	Mileage	Fuel Consumption	Fuel Economy	Mileage	Fuel Consumption	Fuel Economy
	Miles per Vehicle	Gallons per Vehicle	Miles per Gallon	Miles per Vehicle	Gallons per Vehicle	Miles per Gallon	Miles per Vehicle	Gallons per Vehicle	Miles per Gallon	Miles per Vehicle	Gallons per Vehicle	Miles per Gallon
1950 .....	9,060	603	15.0	( <sup>e</sup> )	( <sup>e</sup> )	( <sup>e</sup> )	10,316	1,229	8.4	9,321	725	12.8
1955 .....	9,447	645	14.6	( <sup>e</sup> )	( <sup>e</sup> )	( <sup>e</sup> )	10,576	1,293	8.2	9,661	761	12.7
1960 .....	9,518	668	14.3	( <sup>e</sup> )	( <sup>e</sup> )	( <sup>e</sup> )	10,693	1,333	8.0	9,732	784	12.4
1965 .....	9,603	661	14.5	( <sup>e</sup> )	( <sup>e</sup> )	( <sup>e</sup> )	10,851	1,387	7.8	9,826	787	12.5
1970 .....	9,989	737	13.5	8,676	866	10.0	13,565	2,467	5.5	9,976	830	12.0
1975 .....	9,309	665	14.0	9,829	934	10.5	15,167	2,722	5.6	9,627	790	12.2
1980 .....	8,813	551	16.0	10,437	854	12.2	18,736	3,447	5.4	9,458	712	13.3
1981 .....	8,873	538	16.5	10,244	819	12.5	19,016	3,565	5.3	9,477	697	13.6
1982 .....	9,050	535	16.9	10,276	762	13.5	19,931	3,647	5.5	9,644	686	14.1
1983 .....	9,118	534	17.1	10,497	767	13.7	21,083	3,769	5.6	9,760	686	14.2
1984 .....	9,248	530	17.4	11,151	797	14.0	22,550	3,967	5.7	10,017	691	14.5
1985 .....	9,419	538	17.5	10,506	735	14.3	20,597	3,570	5.8	10,020	685	14.6
1986 .....	9,464	543	17.4	10,764	738	14.6	22,143	3,821	5.8	10,143	692	14.7
1987 .....	9,720	539	18.0	11,114	744	14.9	23,349	3,937	5.9	10,453	694	15.1
1988 .....	9,972	531	18.8	11,465	745	15.4	22,485	3,736	6.0	10,721	688	15.6
1989 .....	10,157	533	19.0	11,676	724	16.1	22,926	3,776	6.1	10,932	688	15.9
1990 .....	10,504	520	20.2	11,902	738	16.1	23,603	3,953	6.0	11,107	677	16.4
1991 .....	10,571	501	21.1	12,245	721	17.0	24,229	4,047	6.0	11,294	669	16.9
1992 .....	10,857	517	21.0	12,381	717	17.3	25,373	4,210	6.0	11,558	683	16.9
1993 .....	10,804	527	20.5	12,430	714	17.4	26,262	4,309	6.1	11,595	693	16.7
1994 .....	10,992	531	20.7	12,156	701	17.3	25,838	4,202	6.1	11,683	698	16.7
1995 .....	11,203	530	21.1	12,018	694	17.3	26,514	4,315	6.1	11,793	700	16.8
1996 .....	11,330	534	21.2	11,811	685	17.2	26,092	4,221	6.2	11,813	700	16.9
1997 .....	11,581	539	21.5	12,115	703	17.2	27,032	4,218	6.4	12,107	711	17.0
1998 .....	11,754	544	21.6	12,173	707	17.2	25,397	4,135	6.1	12,211	721	16.9
1999 .....	11,848	553	21.4	11,957	701	17.0	26,014	4,352	6.0	12,206	732	16.7
2000 .....	11,976	547	21.9	11,672	669	17.4	25,617	4,391	5.8	12,164	720	16.9
2001 .....	11,831	534	22.1	11,204	636	17.6	26,602	4,477	5.9	11,887	695	17.1
2002 .....	12,202	555	22.0	11,364	650	17.5	27,071	4,642	5.8	12,171	719	16.9
2003 .....	12,325	556	22.2	11,287	697	16.2	28,093	4,215	6.7	12,208	718	17.0
2004 .....	12,460	553	22.5	11,184	690	16.2	27,023	4,057	6.7	12,200	714	17.1
2005 .....	12,510	567	22.1	10,920	617	17.7	26,235	4,385	6.0	12,082	706	17.1
2006 .....	12,485	554	22.5	10,920	612	17.8	25,231	4,304	5.9	12,017	698	17.2
2007 .....	<sup>a</sup> 10,710	<sup>a</sup> 468	<sup>a</sup> 22.9	<sup>b</sup> 14,970	<sup>b</sup> 877	<sup>b</sup> 17.1	<sup>c</sup> 28,290	<sup>c</sup> 4,398	6.4	11,915	693	17.2
2008 .....	10,290	435	23.7	15,256	880	17.3	28,573	4,387	6.5	11,631	667	17.4
2009 .....	10,391	442	23.5	15,252	882	17.3	26,274	4,037	6.5	11,631	661	17.6
2010 .....	10,650	456	23.3	15,474	901	17.2	26,604	4,180	6.4	11,866	681	17.4
2011 .....	11,150	481	23.2	12,007	702	17.1	26,054	4,128	6.3	11,652	665	17.5
2012 .....	11,262	484	23.3	11,885	694	17.1	25,255	3,973	6.4	11,707	665	17.6
2013 .....	11,244	480	23.4	11,712	683	17.2	25,951	4,086	6.4	11,679	663	17.6
2014 .....	11,048	476	23.2	12,138	710	17.1	25,594	4,036	6.3	11,621	666	17.5
2015 .....	11,327	475	23.9	11,855	684	17.3	24,979	3,904	6.4	11,742	656	17.9
2016 .....	11,370	475	24.0	11,991	689	17.4	25,037	3,904	6.4	11,810	658	17.9
2017 .....	11,467	474	24.2	11,543	659	17.5	24,335	3,758	6.5	11,789	653	18.1
2018 .....	11,576	475	24.4	11,486	643	17.9	23,037	3,507	6.6	11,843	651	18.2
2019 .....	11,599	481	24.1	11,263	640	17.6	22,930	3,488	6.6	11,797	651	18.1

<sup>a</sup> Through 1989, data are for passenger cars and motorcycles. For 1990–2006, data are for passenger cars only. Beginning in 2007, data are for light-duty vehicles (passenger cars, light trucks, vans, and sport utility vehicles) with a wheelbase less than or equal to 121 inches.

<sup>b</sup> For 1966–2006, data are for vans, pickup trucks, and sport utility vehicles. Beginning in 2007, data are for light-duty vehicles (passenger cars, light trucks, vans, and sport utility vehicles) with a wheelbase greater than 121 inches.

<sup>c</sup> For 1949–1965, data are for single-unit trucks with 2 axles and 6 or more tires, combination trucks, and other vehicles with 2 axles and 4 tires that are not passenger cars. For 1966–2006, data are for single-unit trucks with 2 axles and 6 or more tires, and combination trucks. Beginning in 2007, data are for single-unit trucks with 2 axles and 6 or more tires (or a gross vehicle weight rating exceeding

10,000 pounds), and combination trucks.

<sup>d</sup> Includes buses and motorcycles, which are not separately displayed.

<sup>e</sup> Included in "Heavy-Duty Trucks."

Note: Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **Light-Duty Vehicles, Short Wheelbase: 1990–1994**—U.S. Department of Transportation, Bureau of Transportation Statistics, *National Transportation Statistics 1998*, Table 4-13. • **All Other Data: 1949–1994**—Federal Highway Administration (FHWA), *Highway Statistics Summary to 1995*, Table VM-201A. **1995 forward**—FHWA, *Highway Statistics*, annual reports, Table VM-1.

**Table 1.9 Heating Degree Days by Census Division**

	New England <sup>a</sup>	Middle Atlantic <sup>b</sup>	East North Central <sup>c</sup>	West North Central <sup>d</sup>	South Atlantic <sup>e</sup>	East South Central <sup>f</sup>	West South Central <sup>g</sup>	Mountain <sup>h</sup>	Pacific <sup>i</sup>	United States
<b>1950 Total</b> .....	6,794	6,324	7,027	7,455	3,521	3,547	2,277	6,341	3,906	5,367
<b>1955 Total</b> .....	6,872	6,231	6,486	6,912	3,508	3,513	2,294	6,704	4,320	5,246
<b>1960 Total</b> .....	6,828	6,391	6,908	7,184	3,780	4,134	2,767	6,281	3,799	5,404
<b>1965 Total</b> .....	7,029	6,393	6,587	6,932	3,372	3,501	2,237	6,086	3,819	5,146
<b>1970 Total</b> .....	7,022	6,388	6,721	7,090	3,452	3,823	2,558	6,119	3,726	5,218
<b>1975 Total</b> .....	6,547	5,892	6,406	6,880	2,970	3,437	2,312	6,260	4,117	4,905
<b>1980 Total</b> .....	7,071	6,477	6,975	6,836	3,378	3,964	2,494	5,554	3,539	5,080
<b>1985 Total</b> .....	6,749	5,971	6,668	7,262	2,899	3,660	2,535	6,059	3,935	4,889
<b>1990 Total</b> .....	5,987	5,252	5,780	6,137	2,307	2,942	1,968	5,391	3,603	4,180
<b>1995 Total</b> .....	6,684	6,093	6,740	6,911	2,988	3,648	2,147	5,101	3,269	4,640
<b>2000 Total</b> .....	6,625	5,999	6,315	6,500	2,905	3,551	2,153	4,971	3,460	4,494
<b>2005 Total</b> .....	6,644	5,950	6,222	6,213	2,775	3,380	1,985	4,896	3,377	4,348
<b>2006 Total</b> .....	5,885	5,211	5,703	5,821	2,475	3,211	1,802	4,915	3,557	4,040
<b>2007 Total</b> .....	6,537	5,756	6,074	6,384	2,525	3,187	2,105	4,939	3,506	4,268
<b>2008 Total</b> .....	6,434	5,782	6,677	7,118	2,712	3,600	2,125	5,233	3,566	4,494
<b>2009 Total</b> .....	6,644	5,922	6,512	6,841	2,812	3,536	2,152	5,139	3,538	4,481
<b>2010 Total</b> .....	5,934	5,553	6,185	6,565	3,167	3,948	2,449	5,082	3,624	4,463
<b>2011 Total</b> .....	6,114	5,483	6,172	6,565	2,565	3,343	2,114	5,322	3,818	4,312
<b>2012 Total</b> .....	5,561	4,970	5,356	5,515	2,306	2,876	1,650	4,574	3,411	3,769
<b>2013 Total</b> .....	6,426	5,838	6,621	7,135	2,736	3,648	2,326	5,273	3,362	4,465
<b>2014 Total</b> .....	6,675	6,203	7,194	7,304	2,951	3,932	2,422	4,744	2,774	4,550
<b>2015 Total</b> .....	6,521	5,777	6,165	6,088	2,487	3,222	2,087	4,602	2,898	4,087
<b>2016 Total</b> .....	5,929	5,353	5,701	5,786	2,456	3,094	1,752	4,619	3,031	3,878
<b>2017 Total</b> .....	6,038	5,333	5,684	5,997	2,232	2,835	1,582	4,568	3,187	3,828
<b>2018 Total</b> .....	6,326	5,784	6,433	6,968	2,628	3,478	2,252	4,803	3,170	4,279
<b>2019</b>										
January .....	1,221	1,153	1,303	1,359	582	748	545	893	542	859
February .....	1,030	942	1,062	1,284	377	459	357	866	656	719
March .....	976	890	961	1,002	375	505	305	667	491	632
April .....	527	413	475	454	109	166	78	374	275	288
May .....	313	188	236	272	16	24	11	314	241	158
June .....	55	32	49	45	2	3	0	97	60	34
July .....	2	1	1	8	0	0	0	15	20	5
August .....	16	10	20	32	0	0	0	17	12	10
September .....	118	58	43	67	2	1	0	95	64	41
October .....	389	303	390	526	78	128	84	477	239	254
November .....	831	790	913	924	392	573	346	617	372	589
December .....	1,061	972	975	1,098	449	573	418	870	576	715
<b>Total</b> .....	<b>6,539</b>	<b>5,752</b>	<b>6,427</b>	<b>7,074</b>	<b>2,383</b>	<b>3,181</b>	<b>2,146</b>	<b>5,301</b>	<b>3,548</b>	<b>4,305</b>
<b>2020</b>										
January .....	R 1,033	R 958	R 1,052	1,224	481	634	R 431	R 849	R 564	739
February .....	R 926	842	1,002	1,069	396	R 556	R 402	R 762	448	652
March .....	R 779	R 670	R 733	744	230	R 294	R 140	R 598	R 525	483
April .....	R 654	568	567	R 533	176	249	90	412	R 308	358
May .....	289	251	R 257	246	R 74	86	13	186	R 148	156
June .....	29	R 18	23	21	2	3	0	73	69	25
July .....	1	0	1	6	0	0	0	14	R 18	5
August .....	R 10	4	13	18	0	0	0	9	R 15	7
September .....	104	81	R 112	143	17	20	R 8	103	30	58
October .....	R 398	R 338	R 465	R 554	95	156	83	323	R 132	247
November .....	R 615	R 548	R 600	R 661	225	344	R 176	R 561	412	421
December .....	986	R 946	1,036	1,096	R 555	R 727	R 478	R 883	R 539	749
<b>Total</b> .....	<b>R 5,822</b>	<b>R 5,224</b>	<b>R 5,861</b>	<b>R 6,316</b>	<b>R 2,252</b>	<b>R 3,069</b>	<b>R 1,822</b>	<b>R 4,773</b>	<b>R 3,208</b>	<b>R 3,903</b>
<b>2021</b>										
January .....	1,122	R 1,068	1,148	R 1,179	R 576	737	R 514	R 873	R 547	802
February .....	1,054	1,016	1,249	1,375	481	718	582	779	491	791
<b>2-Month Total</b> .....	<b>2,176</b>	<b>2,084</b>	<b>2,398</b>	<b>2,554</b>	<b>1,057</b>	<b>1,456</b>	<b>1,097</b>	<b>1,652</b>	<b>1,038</b>	<b>1,593</b>
<b>2020 2-Month Total</b> .....	<b>1,959</b>	<b>1,800</b>	<b>2,054</b>	<b>2,293</b>	<b>877</b>	<b>1,190</b>	<b>833</b>	<b>1,611</b>	<b>1,012</b>	<b>1,391</b>
<b>2019 2-Month Total</b> .....	<b>2,251</b>	<b>2,095</b>	<b>2,364</b>	<b>2,644</b>	<b>959</b>	<b>1,207</b>	<b>902</b>	<b>1,759</b>	<b>1,198</b>	<b>1,578</b>

<sup>a</sup> Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, and Vermont.

<sup>b</sup> New Jersey, New York, and Pennsylvania.

<sup>c</sup> Illinois, Indiana, Michigan, Ohio, and Wisconsin.

<sup>d</sup> Iowa, Kansas, Minnesota, Missouri, Nebraska, North Dakota, and South Dakota.

<sup>e</sup> Delaware, Florida, Georgia, Maryland (and the District of Columbia), North Carolina, South Carolina, Virginia, and West Virginia.

<sup>f</sup> Alabama, Kentucky, Mississippi, and Tennessee.

<sup>g</sup> Arkansas, Louisiana, Oklahoma, and Texas.

<sup>h</sup> Arizona, Colorado, Idaho, Montana, Nevada, New Mexico, Utah, and Wyoming.

<sup>i</sup> Alaska, California, Hawaii, Oregon, and Washington.

R=Revised.

Notes: • Degree days are relative measurements of outdoor air temperature used as an index for heating and cooling energy requirements. Heating degree days are the number of degrees that the daily average temperature falls below 65 degrees Fahrenheit (°F). Cooling degree days are the number of degrees that the

daily average temperature rises above 65°F. The daily average temperature is the mean of the maximum and minimum temperatures in a 24-hour period. For example, a weather station recording an average daily temperature of 40°F would report 25 heating degree days for that day (and 0 cooling degree days). If a weather station recorded an average daily temperature of 78°F, cooling degree days for that station would be 13 (and 0 heating degree days). • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: State-level degree day data are from U.S. Department of Commerce, National Oceanic and Atmospheric Administration, National Centers for Environmental Information. Using these state-level data, the U.S. Energy Information Administration calculates population-weighted census-division and U.S. degree day averages using state populations from the same year the degree days are measured. See methodology at [http://www.eia.gov/forecasts/steo/special/pdf/2012\\_sp\\_04.pdf](http://www.eia.gov/forecasts/steo/special/pdf/2012_sp_04.pdf).



**Table 1.10 Cooling Degree Days by Census Division**

	New England <sup>a</sup>	Middle Atlantic <sup>b</sup>	East North Central <sup>c</sup>	West North Central <sup>d</sup>	South Atlantic <sup>e</sup>	East South Central <sup>f</sup>	West South Central <sup>g</sup>	Mountain <sup>h</sup>	Pacific <sup>i</sup>	United States
<b>1950 Total</b> .....	295	401	505	647	1,414	1,420	2,282	682	629	871
<b>1955 Total</b> .....	532	761	922	1,139	1,636	1,674	2,508	780	558	1,144
<b>1960 Total</b> .....	318	487	626	871	1,583	1,532	2,367	974	796	1,000
<b>1965 Total</b> .....	310	498	618	832	1,613	1,552	2,461	780	577	979
<b>1970 Total</b> .....	423	615	747	980	1,744	1,571	2,282	971	734	1,079
<b>1975 Total</b> .....	422	584	721	937	1,791	1,440	2,162	903	597	1,049
<b>1980 Total</b> .....	438	680	769	1,158	1,911	1,754	2,651	1,071	653	1,214
<b>1985 Total</b> .....	324	509	602	780	1,878	1,522	2,519	1,095	761	1,121
<b>1990 Total</b> .....	429	562	602	913	2,054	1,563	2,526	1,212	838	1,200
<b>1995 Total</b> .....	471	704	877	928	2,028	1,613	2,398	1,213	794	1,261
<b>2000 Total</b> .....	279	458	632	983	1,925	1,674	2,775	1,480	772	1,232
<b>2005 Total</b> .....	598	892	944	1,063	2,098	1,676	2,647	1,372	777	1,388
<b>2006 Total</b> .....	485	693	734	1,034	2,053	1,648	2,786	1,466	922	1,360
<b>2007 Total</b> .....	447	694	881	1,102	2,219	1,892	2,475	1,564	828	1,392
<b>2008 Total</b> .....	462	667	883	818	1,993	1,537	2,501	1,385	918	1,282
<b>2009 Total</b> .....	350	524	534	698	2,029	1,479	2,590	1,393	894	1,241
<b>2010 Total</b> .....	635	908	964	1,096	2,269	1,977	2,757	1,358	674	1,456
<b>2011 Total</b> .....	554	836	859	1,074	2,259	1,727	3,112	1,450	736	1,470
<b>2012 Total</b> .....	565	815	974	1,221	2,162	1,762	2,915	1,573	917	1,495
<b>2013 Total</b> .....	540	683	690	892	2,000	1,441	2,536	1,462	892	1,306
<b>2014 Total</b> .....	420	596	610	814	2,009	1,493	2,474	1,431	1,068	1,299
<b>2015 Total</b> .....	555	804	729	942	2,405	1,718	2,741	1,478	1,068	1,488
<b>2016 Total</b> .....	626	888	958	1,073	2,412	1,957	2,882	1,497	928	1,559
<b>2017 Total</b> .....	450	661	709	911	2,254	1,585	2,718	1,548	1,053	1,428
<b>2018 Total</b> .....	667	885	972	1,134	2,418	1,928	2,856	1,573	1,002	1,585
<b>2019</b> January .....	0	0	0	0	29	5	12	0	8	9
February .....	0	0	0	0	67	14	24	0	5	18
March .....	0	0	0	0	56	10	36	10	8	18
April .....	0	0	1	6	101	31	91	51	26	42
May .....	3	31	47	42	293	220	291	57	24	130
June .....	63	112	127	175	361	300	439	233	116	227
July .....	274	325	320	320	481	428	549	395	209	373
August .....	166	218	195	224	441	408	625	386	246	336
September .....	28	88	135	183	375	382	523	207	131	243
October .....	0	8	7	2	204	80	139	49	40	75
November .....	0	0	0	0	53	1	16	11	16	16
December .....	0	0	0	0	51	5	13	0	10	14
<b>Total</b> .....	<b>535</b>	<b>783</b>	<b>831</b>	<b>952</b>	<b>2,513</b>	<b>1,886</b>	<b>2,758</b>	<b>1,399</b>	<b>840</b>	<b>1,502</b>
<b>2020</b> January .....	0	0	0	0	47	13	R 29	0	9	15
February .....	0	0	0	0	46	4	14	2	8	13
March .....	0	0	2	6	103	55	R 131	8	8	43
April .....	0	0	0	1	109	20	R 105	43	R 20	43
May .....	3	11	32	37	R 166	105	R 278	R 158	R 65	R 105
June .....	R 99	145	R 185	R 256	R 343	297	R 457	R 264	R 113	R 247
July .....	R 292	R 362	336	R 343	503	R 462	R 600	415	213	398
August .....	215	R 261	219	247	R 455	387	R 575	R 442	R 295	357
September .....	35	58	55	72	274	210	324	R 230	R 214	181
October .....	0	4	2	3	R 185	66	R 133	103	R 104	R 84
November .....	0	0	0	0	R 94	12	69	15	15	32
December .....	0	0	0	0	21	1	7	0	10	7
<b>Total</b> .....	<b>R 643</b>	<b>R 842</b>	<b>R 830</b>	<b>R 965</b>	<b>R 2,345</b>	<b>R 1,634</b>	<b>R 2,722</b>	<b>R 1,679</b>	<b>R 1,073</b>	<b>R 1,525</b>
<b>2021</b> January .....	0	0	0	0	R 30	R 5	15	0	9	10
February .....	0	0	0	0	50	1	4	3	7	12
<b>2-Month Total</b> .....	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>80</b>	<b>6</b>	<b>19</b>	<b>3</b>	<b>16</b>	<b>22</b>
<b>2020 2-Month Total</b> .....	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>94</b>	<b>17</b>	<b>43</b>	<b>2</b>	<b>16</b>	<b>28</b>
<b>2019 2-Month Total</b> .....	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>96</b>	<b>19</b>	<b>36</b>	<b>0</b>	<b>14</b>	<b>27</b>

<sup>a</sup> Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, and Vermont.

<sup>b</sup> New Jersey, New York, and Pennsylvania.

<sup>c</sup> Illinois, Indiana, Michigan, Ohio, and Wisconsin.

<sup>d</sup> Iowa, Kansas, Minnesota, Missouri, Nebraska, North Dakota, and South Dakota.

<sup>e</sup> Delaware, Florida, Georgia, Maryland (and the District of Columbia), North Carolina, South Carolina, Virginia, and West Virginia.

<sup>f</sup> Alabama, Kentucky, Mississippi, and Tennessee.

<sup>g</sup> Arkansas, Louisiana, Oklahoma, and Texas.

<sup>h</sup> Arizona, Colorado, Idaho, Montana, Nevada, New Mexico, Utah, and Wyoming.

<sup>i</sup> Alaska, California, Hawaii, Oregon, and Washington.

R=Revised.

Notes: • Degree days are relative measurements of outdoor air temperature used as an index for heating and cooling energy requirements. Cooling degree days are the number of degrees that the daily average temperature rises above 65 degrees Fahrenheit (°F). Heating degree days are the number of degrees that the

daily average temperature falls below 65°F. The daily average temperature is the mean of the maximum and minimum temperatures in a 24-hour period. For example, if a weather station recorded an average daily temperature of 78°F, cooling degree days for that station would be 13 (and 0 heating degree days). A weather station recording an average daily temperature of 40°F would report 25 heating degree days for that day (and 0 cooling degree days).

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: State-level degree day data are from U.S. Department of Commerce, National Oceanic and Atmospheric Administration, National Centers for Environmental Information. Using these state-level data, the U.S. Energy Information Administration calculates population-weighted census-division and U.S. degree day averages using state populations from the same year the degree days are measured. See methodology at [http://www.eia.gov/forecasts/steo/special/pdf/2012\\_sp\\_04.pdf](http://www.eia.gov/forecasts/steo/special/pdf/2012_sp_04.pdf).

Table 1.11a Non-Combustion Use of Fossil Fuels in Physical Units

	Coal	Natural Gas	Petroleum							
			Asphalt and Road Oil	Hydrocarbon Gas Liquids <sup>a</sup>	Lubricants	Petrochemical Feedstocks <sup>b</sup>	Petroleum Coke	Special Naphthas	Other <sup>c</sup>	Total
	Thousand Short Tons	Billion Cubic Feet	Thousand Barrels per Day							
1973 Total .....	3,523	898	522	684	162	356	45	88	88	1,945
1975 Total .....	3,105	761	419	654	137	320	43	75	122	1,770
1980 Total .....	2,612	759	396	890	159	692	41	100	143	2,422
1985 Total .....	1,536	642	425	982	145	395	46	83	95	2,173
1990 Total .....	758	675	483	1,071	164	546	57	56	85	2,462
1995 Total .....	921	868	486	1,357	156	590	58	37	70	2,754
1996 Total .....	884	896	484	1,413	151	592	60	39	70	2,809
1997 Total .....	842	909	505	1,447	160	686	58	38	72	2,966
1998 Total .....	656	938	521	1,441	168	690	84	56	83	3,043
1999 Total .....	654	906	547	1,578	169	651	92	76	77	3,190
2000 Total .....	937	836	512	1,474	151	628	100	53	85	3,003
2005 Total .....	929	761	546	1,369	141	729	106	33	75	2,997
2006 Total .....	562	573	521	1,424	137	726	111	37	86	3,041
2007 Total .....	556	587	494	1,444	142	664	108	41	82	2,974
2008 Total .....	541	597	417	1,279	131	574	103	44	85	2,634
2009 Total .....	375	513	360	1,401	118	507	95	24	85	2,591
2010 Total .....	719	654	362	1,597	131	539	42	14	89	2,773
2011 Total .....	730	680	355	1,639	125	520	40	12	91	2,781
2012 Total .....	707	706	340	1,747	114	444	43	8	88	2,785
2013 Total .....	732	721	323	1,870	121	448	40	52	93	2,948
2014 Total .....	562	725	327	1,780	126	410	20	55	97	2,817
2015 Total .....	520	703	343	1,918	138	378	21	52	99	2,948
2016 Total .....	435	727	351	1,943	130	371	20	49	100	2,965
2017 Total .....	463	746	351	2,023	121	394	19	52	103	3,062
2018 Total .....	531	1,118	327	2,309	117	393	22	48	103	3,320
2019 January .....	44	108	195	2,490	114	354	19	39	104	3,315
February .....	40	97	201	2,454	105	344	6	48	94	3,252
March .....	45	101	232	2,200	97	323	20	42	93	3,009
April .....	42	90	318	2,241	156	357	17	55	91	3,236
May .....	47	89	369	2,206	107	345	22	48	89	3,187
June .....	46	83	413	2,271	104	355	29	51	90	3,314
July .....	43	84	510	2,436	129	348	28	63	98	3,613
August .....	43	87	507	2,365	115	386	23	51	97	3,543
September .....	43	84	480	2,488	96	365	18	51	91	3,589
October .....	43	90	438	2,448	130	285	18	53	90	3,462
November .....	40	98	310	2,427	105	338	26	49	92	3,347
December .....	44	104	198	2,431	94	387	26	47	97	3,281
Total .....	520	1,115	348	2,371	113	349	21	50	94	3,346
2020 January .....	42	105	191	2,403	123	367	17	46	102	3,249
February .....	42	98	191	2,265	108	292	18	52	97	3,023
March .....	41	96	204	2,470	62	325	17	47	95	3,220
April .....	35	85	292	2,227	82	315	12	55	86	3,069
May .....	31	82	365	2,358	83	299	14	38	79	3,237
June .....	35	79	511	2,343	104	291	14	47	83	3,394
July .....	30	83	491	2,593	116	306	16	42	93	3,656
August .....	31	85	479	2,419	94	319	26	41	81	3,458
September .....	31	86	422	2,370	103	303	21	40	85	3,344
October .....	33	92	401	2,624	110	310	17	52	84	3,597
November .....	34	95	318	2,824	111	312	22	41	83	3,710
December .....	35	105	237	2,820	110	345	17	39	86	3,653
Total .....	418	1,090	342	2,478	100	315	18	45	88	3,386
2021 January .....	36	106	239	2,791	110	307	17	44	87	3,596
February .....	4	91	201	1,775	113	248	9	29	75	2,451
2-Month Total .....	40	196	221	2,309	112	279	13	37	82	3,053
2020 2-Month Total .....	83	203	191	2,336	116	331	17	49	100	3,140
2019 2-Month Total .....	84	204	198	2,473	109	349	13	44	99	3,285

<sup>a</sup> Ethane, propane, normal butane, isobutane, natural gasoline, and refinery olefins (ethylene, propylene, butylene, and isobutylene).

<sup>b</sup> Includes still gas not burned as refinery fuel.

<sup>c</sup> Distillate fuel oil, residual fuel oil, waxes, and miscellaneous products.

R=Revised.

Notes: • Data are estimates. • Non-combustion use estimates are included in total energy consumption. See Table 1.3. • Non-combustion estimates are all for industrial sector consumption, except for some lubricants consumed by the

transportation sector. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia. • See Note 2, "Non-Combustion Use of Fossil Fuels," at end of section.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all available annual and monthly data beginning in 1973.

Sources: • See Note 2, "Non-Combustion Use of Fossil Fuels," at end of section.

**Table 1.11b Heat Content of Non-Combustion Use of Fossil Fuels**  
(Quadrillion Btu)

	Coal	Natural Gas	Petroleum							Total	Percent of Total Energy Consumption	
			Asphalt and Road Oil	Hydro-carbon Gas Liquids <sup>a</sup>	Lubri-cants	Petro-chemical Feed-stocks <sup>b</sup>	Petro-leum Coke	Special Naphthas	Other <sup>c</sup>			
1973 Total .....	0.113	0.916	1.264	0.872	0.359	0.726	0.093	0.169	0.185	3.668	4.696	6.2
1975 Total .....	.099	.777	1.014	.822	.304	.652	.090	.144	.256	3.283	4.159	5.8
1980 Total .....	.084	.777	.962	1.128	.354	1.426	.086	.193	.303	4.451	5.312	6.8
1985 Total .....	.049	.662	1.029	1.194	.322	.817	.096	.159	.201	3.818	4.529	5.9
1990 Total .....	.024	.695	1.170	1.345	.362	1.123	.119	.107	.179	4.406	5.125	6.1
1995 Total .....	.029	.892	1.178	1.716	.346	1.214	.120	.071	.145	4.790	5.711	6.3
1996 Total .....	.028	.921	1.176	1.779	.335	1.209	.126	.075	.146	4.846	5.795	6.2
1997 Total .....	.027	.933	1.224	1.821	.354	1.400	.121	.072	.150	5.142	6.102	6.5
1998 Total .....	.021	.969	1.263	1.819	.371	1.403	.176	.107	.174	5.312	6.302	6.6
1999 Total .....	.021	.932	1.324	1.989	.375	1.329	.192	.145	.161	5.516	6.469	6.7
2000 Total .....	.030	.856	1.240	1.831	.334	1.272	.209	.102	.178	5.167	6.054	6.2
2005 Total .....	.030	.782	1.323	1.701	.312	1.474	.221	.063	.157	5.250	6.062	6.1
2006 Total .....	.018	.589	1.261	1.754	.303	1.477	.232	.070	.180	5.278	5.885	5.9
2007 Total .....	.018	.603	1.197	1.768	.313	1.351	.225	.078	.173	5.106	5.726	5.7
2008 Total .....	.017	.613	1.012	1.564	.291	1.172	.216	.085	.180	4.520	5.150	5.2
2009 Total .....	.012	.526	.873	1.676	.262	1.031	.199	.046	.179	4.265	4.804	5.1
2010 Total .....	.023	.669	.878	1.931	.291	1.096	.087	.026	.188	4.496	5.187	5.3
2011 Total .....	.023	.695	.859	1.947	.276	1.057	.083	.023	.193	4.437	5.156	5.3
2012 Total .....	.023	.724	.827	2.109	.254	.901	.090	.015	.187	4.382	5.128	5.4
2013 Total .....	.023	.741	.783	2.269	.268	.901	.083	.100	.197	4.601	5.366	5.5
2014 Total .....	.018	.749	.793	2.125	.280	.827	.043	.106	.205	4.379	5.146	5.2
2015 Total .....	.017	.730	.832	2.316	.305	.760	.043	.099	.208	4.563	5.310	5.5
2016 Total .....	.014	.755	.853	2.330	.289	.754	.043	.094	.212	4.574	5.344	5.5
2017 Total .....	.015	.774	.849	2.393	.267	.797	.040	.100	.217	4.663	5.452	5.6
2018 Total .....	.017	1.160	.793	2.709	.259	.794	.046	.092	.218	4.911	6.088	6.0
2019 January .....	.001	.112	.040	.248	.021	.061	.003	.006	.019	.399	.512	5.4
February .....	.001	.101	.037	.219	.018	.053	.001	.007	.015	.350	.452	5.4
March .....	.001	.105	.048	.215	.018	.055	.004	.007	.017	.363	.469	5.4
April .....	.001	.094	.063	.211	.028	.059	.003	.009	.016	.390	.485	6.3
May .....	.002	.093	.076	.218	.020	.059	.004	.008	.016	.401	.495	6.2
June .....	.001	.086	.082	.222	.019	.059	.005	.008	.016	.411	.498	6.3
July .....	.001	.087	.105	.247	.024	.060	.005	.010	.018	.469	.558	6.5
August .....	.001	.091	.104	.240	.022	.066	.004	.008	.017	.462	.554	6.5
September .....	.001	.087	.096	.244	.018	.060	.003	.008	.016	.445	.533	6.8
October .....	.001	.094	.090	.249	.025	.049	.003	.009	.016	.440	.536	6.8
November .....	.001	.102	.062	.233	.019	.056	.004	.008	.016	.398	.502	6.0
December .....	.001	.108	.041	.240	.018	.066	.005	.008	.017	.394	.504	5.6
Total .....	.017	1.159	.844	2.786	.250	.704	.044	.096	.198	4.922	6.098	6.1
2020 January .....	.001	.110	.039	.232	.023	.063	.003	.007	.018	.386	.497	5.6
February .....	.001	.102	.037	.202	.019	.047	.003	.008	.016	.332	.434	5.2
March .....	.001	.099	.042	.242	.012	.056	.003	.008	.017	.379	.480	6.1
April .....	.001	.088	.058	.206	.015	.053	.002	.009	.015	.358	.447	6.9
May .....	.001	.085	.075	.231	.016	.052	.003	.006	.014	.396	.482	7.0
June .....	.001	.082	.102	.221	.019	.048	.002	.007	.014	.414	.497	6.8
July .....	.001	.086	.101	.252	.022	.052	.003	.007	.017	.453	.540	6.7
August .....	.001	.088	.098	.240	.018	.054	.005	.007	.015	.436	.525	6.6
September .....	.001	.089	.084	.231	.019	.050	.004	.006	.015	.408	.499	6.8
October .....	.001	.096	.082	.265	.021	.053	.003	.008	.015	.447	.544	7.3
November .....	.001	.099	.063	.271	.020	.052	.004	.006	.014	.431	.531	7.0
December .....	.001	.109	.049	.281	.021	.059	.003	.006	.015	.434	.544	6.3
Total .....	.013	1.132	.831	2.873	.223	.638	.037	.086	.186	4.875	6.021	6.5
2021 January .....	.001	.110	.049	.278	.021	.053	.003	.007	.016	.426	.537	6.1
February .....	(s)	.094	.037	.158	.019	.039	.001	.004	.012	.272	.366	4.6
2-Month Total .....	.001	.204	.087	.436	.040	.091	.004	.011	.028	.698	.903	5.3
2020 2-Month Total .....	.003	.211	.076	.434	.042	.110	.006	.015	.035	.718	.932	5.4
2019 2-Month Total .....	.003	.212	.077	.467	.039	.114	.004	.013	.034	.749	.964	5.4

<sup>a</sup> Ethane, propane, normal butane, isobutane, natural gasoline, and refinery olefins (ethylene, propylene, butylene, and isobutylene).

<sup>b</sup> Includes still gas not burned as refinery fuel.

<sup>c</sup> Distillate fuel oil, residual fuel oil, waxes, and miscellaneous products.

(s)=Less than 0.5 trillion Btu.

Notes: • Data are estimates. • Non-combustion use estimates are included in total energy consumption. See Table 1.3. • Non-combustion estimates are all for industrial sector consumption, except for some lubricants consumed by the transportation sector. • Totals may not equal sum of components due to

independent rounding. • Geographic coverage is the 50 states and the District of Columbia. • See Note 2, "Non-Combustion Use of Fossil Fuels," at end of section.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all available annual and monthly data beginning in 1973.

Sources: • See Note 2, "Non-Combustion Use of Fossil Fuels," at end of section. • **Percent of Total Energy Consumption:** Calculated as total non-combustion use of fossil fuels divided by total primary energy consumption (see Table 1.3).

**Note 1. Merchandise Trade Value.** Imports data presented are based on the customs values. Those values do not include insurance and freight and are consequently lower than the cost, insurance, and freight (CIF) values, which are also reported by the Bureau of the Census. All exports data, and imports data through 1980, are on a free alongside ship (f.a.s.) basis.

“Balance” is exports minus imports; a positive balance indicates a surplus trade value and a negative balance indicates a deficit trade value. “Energy” includes mineral fuels, lubricants, and related material. “Non-Energy Balance” and “Total Merchandise” include foreign exports (i.e., re-exports) and nonmonetary gold and U.S. Department of Defense Grant-Aid shipments. The “Non-Energy Balance” is calculated by subtracting the “Energy” from the “Total Merchandise Balance.”

“Imports” consist of government and nongovernment shipments of merchandise into the 50 states, the District of Columbia, Puerto Rico, the U.S. Virgin Islands, and the U.S. Foreign Trade Zones. They reflect the total arrival from foreign countries of merchandise that immediately entered consumption channels, warehouses, the Foreign Trade Zones, or the Strategic Petroleum Reserve. They exclude shipments between the United States, Puerto Rico, and U.S. possessions, shipments to U.S. Armed Forces and diplomatic missions abroad for their own use, U.S. goods returned to the United States by its Armed Forces, and in-transit shipments.

**Note 2. Non-Combustion Use of Fossil Fuels.** Most fossil fuels consumed in the United States and elsewhere are combusted to produce heat and power. However, some are used directly for non-combustion use as construction materials, chemical feedstocks, lubricants, solvents, and waxes. For example, coal tars from coal coke manufacturing are used as feedstock in the chemical industry, for metallurgical work, and in anti-dandruff shampoos; natural gas is used to make nitrogenous fertilizers and as chemical feedstocks; asphalt and road oil are used for roofing and paving; hydrocarbon gas liquids are used to create intermediate products that are used in making plastics; lubricants, including motor oil and greases, are used in vehicles and various industrial processes; petrochemical feedstocks are used to make plastics, synthetic fabrics, and related products.

### *Coal*

The U.S. Energy Information Administration (EIA) assumes all non-combustion use of coal comes from the process of manufacturing coal coke in the industrial sector. Among the byproducts of the process are “coal tars” or “coal liquids,” which typically are rich in aromatic hydrocarbons, such as benzene, and are used as chemical feedstock. EIA estimates non-combustion use ratios of coal tar for 1973 forward. Prior to 1998, estimate ratios are based on coal tar production data from the United States International Trade Commission's *Synthetic Organic Chemicals*. For 1998 forward, coal tar production is estimated using chemicals industry coal, coke, and breeze nonfuel use data from EIA, Form EIA-846, “Manufacturing Energy Consumption Survey” (MECS). For Table 1.11b, coal tar values in Table 1.11a are multiplied by 32.0067 million Btu/short ton, which is the product of 4.95 barrels/short ton (the density of coal tar) and 6.466 million Btu/barrel (the approximate heat content of coal tar).

### *Natural Gas*

EIA assumes that all non-combustion use of natural gas takes place in the industrial sector. EIA estimates non-combustion ratios of natural gas using total natural gas nonfuel use data from MECS, and natural gas used as feedstock for hydrogen production data from EIA, Form EIA-820, “Annual Refinery Report.” For Table 1.11b, natural gas values in Table 1.11a are multiplied by the heat content factors for natural gas end-use sectors consumption shown in Table A4.

### *Asphalt and Road Oil*

EIA assumes all asphalt and road oil consumption is for non-combustion use. For Table 1.11b, asphalt and road oil values in Table 1.11a are multiplied by 6.636 million Btu/ barrel (the approximate heat content of asphalt and road oil) and the number of days in the period.

### *Distillate Fuel Oil*

EIA assumes that all non-combustion use of distillate fuel oil occurs in the industrial sector. EIA estimates non-combustion ratios of distillate fuel oil using total distillate fuel oil nonfuel use data from MECS. Ratios prior to 1985 are assumed to be equal to the 1985 ratio. For Table 1.11b, distillate fuel oil values in Table 1.11a are multiplied by the heat content factors for distillate fuel oil consumption shown in Table A3 and the number of days in the period. Distillate fuel oil is included in "other" petroleum products.

### *Hydrocarbon Gas Liquids (HGL)*

EIA estimates non-combustion ratios of hydrocarbon gas liquids (HGL), which include ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). EIA assumes that 100% of ethane, ethylene, and propylene consumption is for non-combustion use; 85% of normal butane, butylene, isobutane, and isobutylene consumption is for non-combustion use; and 50% of natural gasoline consumption is for non-combustion use. Non-combustion use of propane in the industrial sector is estimated using data from the American Petroleum Institute (API), the Propane Education & Research Council (PERC), and EIA's *Petroleum Supply Annual* (PSA). For 1984 through 2009, propane non-combustion ratios are estimated using API propane and propylene chemical industry sales data. Propane non-combustion ratios prior to 1984 are assumed to be equal to the 1984 ratio. For 2010 through 2016, propane non-combustion ratios are estimated by subtracting API data for total odorized propane sales from PSA data for total propane product supplied. Beginning in 2017, propane non-combustion ratios are estimated by subtracting PERC data for total odorized propane sales from PSA data for total propane product supplied. For Table 1.11b, HGL component values are multiplied by the appropriate heat content factors in Table A1 and the number of days in the period.

### *Lubricants*

EIA assumes all lubricants consumption is for non-combustion use. For Table 1.11b, lubricants values in Table 1.11a are multiplied by 6.065 million Btu/barrel (the approximate heat content of lubricants) and the number of days in the period.

### *Petrochemical Feedstocks, Naphtha*

EIA assumes all naphtha for petrochemical feedstocks is for non-combustion use. For Table 1.11b, naphtha petrochemical feedstock values in 1.11a are multiplied by 5.248 million Btu/barrel (the approximate heat content of naphtha for petrochemical feedstocks) and the number of days in the period.

### *Petrochemical Feedstocks, Other Oils*

EIA assumes all other oils for petrochemical feedstocks are for non-combustion use. For Table 1.11b, other oils petrochemical feedstock values in 1.11a are multiplied by 5.825 million Btu/barrel (the approximate heat content of other oils for petrochemical feedstocks) and the number of days in the period.

### *Petrochemical Feedstocks, Still Gas*

EIA assumes all still gas not burned as refinery fuel or for pipeline gas supplies is for non-combustion use. EIA estimates non-combustion ratios of still gas by subtracting data for all known fuel uses (refinery fuel use from the PSA, and pipeline gas supplies from EIA's *Natural Gas Annual*) from the products supplied values in the PSA. The remainder is assumed to be dispatched to chemical plants as a feedstock for non-combustion use. For Table 1.11b, still gas for petrochemical feedstock values in 1.11a are multiplied by the still gas heat content factors (through 2015, the still gas heat content factor is 6.000 million Btu per fuel oil equivalent barrel; beginning in 2016, the still gas heat content factor is 6.287 million Btu per residual fuel oil equivalent barrel) and the number of days in the period.

### *Petroleum Coke*

EIA assumes all non-combustion use of petroleum coke occurs in the industrial sector. Examples include petroleum coke used in the production of chemicals and metals. EIA estimates non-combustion ratios of petroleum coke by subtracting data for all known fuel use by refineries from PSA and MECS data. Non-combustion ratios prior to 1988 are assumed to be equal to the 1988 ratio. For Table 1.11b, petroleum coke values in 1.11a are multiplied by 5.719 million Btu/barrel (the approximate heat content of marketable petroleum coke) and the number of days in the period.

### *Residual Fuel Oil*

EIA assumes that all non-combustion use of residual fuel oil occurs in the industrial sector. EIA estimates non-combustion ratios of residual fuel oil using total minus chemicals industry residual fuel oil nonfuel use data from MECS. Ratios prior to 1994 are assumed to be equal to the 1994 ratio. For Table 1.11b, residual fuel oil values in Table 1.11a are multiplied by 6.287 million Btu/barrel (the approximate heat content of residual fuel oil) and the number of days in the period. Residual fuel oil is included in "other" petroleum products.

### *Special Naphthas*

EIA assumes all special naphthas consumption is for non-combustion use. For Table 1.11b, special naphthas values in Table 1.11a are multiplied by 5.248 million Btu/barrel (the approximate heat content of special naphthas) and the number of days in the period.

### *Waxes*

EIA assumes all waxes consumption is for non-combustion use. For Table 1.11b, waxes values in Table 1.11a are multiplied by 5.537 million Btu/barrel (the approximate heat content of waxes) and the number of days in the period. Waxes are included in "other" petroleum products.

### *Miscellaneous Petroleum Products*

Miscellaneous products include all finished petroleum products not classified elsewhere. EIA assumes all miscellaneous petroleum products consumption is for non-combustion use. For Table 1.11b, miscellaneous petroleum products values in Table 1.11a are multiplied by 5.796 million Btu/barrel (the approximate heat content of miscellaneous petroleum products) and the number of days in the period. Miscellaneous petroleum products are included in "other" petroleum products.

## **Table 1.2 Sources**

### *Coal*

1949–1988: Coal production data from Table 6.1 are converted to Btu by multiplying by the coal production heat content factors in Table A5.

1989 forward: Coal production data from Table 6.1 are converted to Btu by multiplying by the coal production heat content factors in Table A5. Waste coal supplied data from Table 6.1 are converted to Btu by multiplying by the waste coal supplied heat content factors in Table A5. Coal production (including waste coal supplied) is equal to coal production plus waste coal supplied.

### *Natural Gas (Dry)*

1949 forward: Natural gas (dry) production data from Table 4.1 are converted to Btu by multiplying by the natural gas (dry) production heat content factors in Table A4.

### *Crude Oil*

1949 forward: Crude oil (including lease condensate) production data from Table 3.1 are converted to Btu by multiplying by the crude oil (including lease condensate) production heat content factors in Table A2.

### *NGPL*

1949 forward: Natural gas plant liquids (NGPL) production data from Table 3.1 are converted to Btu by multiplying by the NGPL production heat content factors in Table A2.

### *Fossil Fuels Total*

1949 forward: Total fossil fuels production is the sum of the production values for coal, natural gas (dry), crude oil, and NGPL.

### *Nuclear Electric Power*

1949 forward: Nuclear electricity net generation data from Table 7.2a are converted to Btu by multiplying by the nuclear heat rate factors in Table A6.

## *Renewable Energy*

1949 forward: Table 10.1.

## *Total Primary Energy Production*

1949 forward: Total primary energy production is the sum of the production values for fossil fuels, nuclear electric power, and renewable energy.

## **Table 1.3 Sources**

### *Coal*

1949 forward: Coal consumption data from Table 6.1 are converted to Btu by multiplying by the total coal consumption heat content factors in Table A5.

### *Natural Gas*

1949–1979: Natural gas (including supplemental gaseous fuels) consumption data from Table 4.1 are converted to Btu by multiplying by the total natural gas consumption heat content factors in Table A4.

1980 forward: Natural gas (including supplemental gaseous fuels) consumption data from Table 4.1 are converted to Btu by multiplying by the total natural gas consumption heat content factors in Table A4. Supplemental gaseous fuels data in Btu are estimated using the method described in Note 3, “Supplemental Gaseous Fuels,” at the end of Section 4. Natural gas (excluding supplemental gaseous fuels) consumption is equal to natural gas (including supplemental gaseous fuels) consumption minus supplemental gaseous fuels.

### *Petroleum*

1949–1992: Petroleum (excluding biofuels) consumption is equal to total petroleum products supplied from Table 3.6.

1993–2008: Petroleum (excluding biofuels) consumption is equal to total petroleum products supplied from Table 3.6 minus fuel ethanol consumption from Table 10.3.

2009–2011: Petroleum (excluding biofuels) consumption is equal to: total petroleum products supplied from Table 3.6; minus fuel ethanol (minus denaturant) consumption from Table 10.3; minus biodiesel consumption (calculated using biodiesel data from U.S. Energy Information Administration (EIA), EIA-22M, “Monthly Biodiesel Production Survey”; and biomass-based diesel fuel data from EIA-810, “Monthly Refinery Report,” EIA-812, “Monthly Product Pipeline Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1); minus other renewable diesel fuel and other renewable fuels consumption from Table 10.4.

2021 forward: Petroleum (excluding biofuels) consumption is equal to: total petroleum products supplied from Table 3.6; minus fuel ethanol (minus denaturant) consumption from Table 10.3; minus biodiesel-refinery and blender net inputs from EIA, EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1); minus other renewable diesel fuel and other renewable fuels consumption from Table 10.4; minus renewable fuels except fuel ethanol products supplied from U.S. Energy Information Administration (EIA), *Petroleum Supply Monthly* (data are converted to Btu by multiplying by the appropriate heat content factors in Table A1).

### *Coal Coke Net Imports*

1949 forward: Table 1.4c.

### *Fossil Fuels Total*

1949 forward: Total fossil fuels consumption is the sum of the consumption values for coal, natural gas, and petroleum, plus coal coke net imports.

### *Nuclear Electric Power*

1949 forward: Nuclear electricity net generation data from Table 7.2a are converted to Btu by multiplying by the nuclear heat rate factors in Table A6.

## *Renewable Energy*

1949 forward: Table 10.1.

## *Electricity Net Imports*

1949 forward: Table 1.4c.

## *Total Primary Energy Consumption*

1949 forward: Total primary energy consumption is the sum of the consumption values for fossil fuels, nuclear electric power, and renewable energy, plus electricity net imports.

## **Table 1.4a Sources**

### *Coal*

1949 forward: Coal imports data from Table 6.1 are converted to Btu by multiplying by the coal imports heat content factors in Table A5.

### *Coal Coke*

1949 forward: Coal coke imports data from U.S. Department of Commerce, Bureau of the Census, Monthly Report IM 145, are converted to Btu by multiplying by the coal coke imports heat content factor in Table A5.

### *Natural Gas*

1949 forward: Natural gas imports data from Table 4.1 are converted to Btu by multiplying by the natural gas imports heat content factors in Table A4.

### *Crude Oil*

1949 forward: Crude oil imports data from Table 3.3b are converted to Btu by multiplying by the crude oil imports heat content factors in Table A2.

### *Petroleum Products*

1949–1992: Petroleum products (excluding biofuels) imports are equal to total petroleum imports from Table 3.3b minus crude oil imports from Table 3.3b; petroleum products (excluding biofuels) imports data are converted to Btu by multiplying by the total petroleum products imports heat content factors in Table A2.

1993–2008: Petroleum products (excluding biofuels) imports are equal to petroleum products (including biofuels) imports (see 1949–1992 sources above) minus fuel ethanol (minus denaturant) imports (see “Biomass—Fuel Ethanol (Minus Denaturant)” sources below).

2009 forward: Renewable fuels (excluding fuel ethanol) imports data are from U.S. Energy Information Administration, Petroleum Supply Annual (PSA), Tables 1 and 25, and Petroleum Supply Monthly (PSM), Tables 1 and 37 (for biomass-based diesel fuel and other renewable fuels, the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1; for other renewable diesel fuel, the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Petroleum products (excluding biofuels) imports are equal to petroleum products (including biofuels) imports (see 1949–1992 sources above) minus fuel ethanol (minus denaturant) imports (see “Biomass—Fuel Ethanol (Minus Denaturant)” sources below) minus renewable fuels (excluding fuel ethanol) imports.

### *Total Petroleum*

1949 forward: Total petroleum imports are equal to crude oil imports plus petroleum products imports.

### *Biomass—Fuel Ethanol (Minus Denaturant)*

1993 forward: Fuel ethanol (including denaturant) imports data are from PSA/PSM Table 1. Fuel ethanol (minus denaturant) production is equal to fuel ethanol (including denaturant) production from Table 10.3 minus denaturant from Table 10.3. Fuel ethanol (minus denaturant) imports are equal to fuel ethanol (including denaturant) imports multiplied by the ratio of fuel ethanol (minus denaturant) production to fuel ethanol (including denaturant) production.



Fuel ethanol (minus denaturant) imports data are converted to Btu by multiplying by 3.539 million Btu per barrel, the undenatured ethanol heat content factor in Table A3.

#### *Biomass—Biodiesel*

2001 forward: Biodiesel imports data are from Table 10.4, and are converted to Btu by multiplying by the biodiesel heat content factor in Table A1.

#### *Biomass—Other Renewable Fuels*

2009 forward: Other renewable fuels imports data are from PSA Table 25 and PSM Table 37. For other renewable diesel fuel, the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1; for other renewable fuels, the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1.

#### *Total Biomass*

1993–2000: Total biomass imports are equal to fuel ethanol (minus denaturant) imports.

2001–2008: Total biomass imports are equal to fuel ethanol (minus denaturant) imports plus biodiesel imports.

2009 forward: Total biomass imports are the sum of imports values for fuel ethanol (minus denaturant), biodiesel, and other renewable fuels.

#### *Electricity*

1949 forward: Electricity imports data from Table 7.1 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

#### *Total Primary Energy Imports*

1949 forward: Total primary energy imports are the sum of the imports values for coal, coal coke, natural gas, total petroleum, total biomass, and electricity.

### **Table 1.4b Sources**

#### *Coal*

1949 forward: Coal exports data from Table 6.1 are converted to Btu by multiplying by the coal exports heat content factors in Table A5.

#### *Coal Coke*

1949 forward: Coal coke exports data from U.S. Department of Commerce, Bureau of the Census, Monthly Report EM 545, are converted to Btu by multiplying by the coal coke exports heat content factor in Table A5.

#### *Natural Gas*

1949 forward: Natural gas exports data from Table 4.1 are converted to Btu by multiplying by the natural gas exports heat content factors in Table A4.

#### *Crude Oil*

1949 forward: Crude oil exports data from Table 3.3b are converted to Btu by multiplying by the crude oil exports heat content factor in Table A2.

#### *Petroleum Products*

1949–2009: Petroleum products (excluding biofuels) exports are equal to total petroleum exports from Table 3.3b minus crude oil exports from Table 3.3b; petroleum products (excluding biofuels) exports data are converted to Btu by multiplying by the total petroleum products exports heat content factors in Table A2.

2010: Petroleum products (including biofuels) exports are equal to total petroleum exports from Table 3.3b minus crude oil exports from Table 3.3b; petroleum products (including biofuels) exports data are converted to Btu by multiplying by the total petroleum products exports heat content factors in Table A2. Petroleum products (excluding biofuels) exports are equal to petroleum products (including biofuels) exports minus fuel ethanol (minus denaturant) exports (see “Biomass—Fuel Ethanol (Minus Denaturant)” sources below).

2011 forward: Biomass-based diesel fuel exports data are from U.S. Energy Information Administration (EIA), Petroleum Supply Annual (PSA), Table 31, and Petroleum Supply Monthly (PSM), Table 49, and are converted to Btu by multiplying by the biodiesel heat content factor in Table A1. Petroleum products (excluding biofuels) exports are equal to petroleum products (including biofuels) exports (see 2010 sources above) minus fuel ethanol (minus denaturant) exports (see “Biomass—Fuel Ethanol (Minus Denaturant)” sources below) minus biomass-based diesel fuel exports.

#### *Total Petroleum*

1949 forward: Total petroleum exports are equal to crude oil exports plus petroleum products exports.

#### *Biomass—Fuel Ethanol (Minus Denaturant)*

2010 forward: Fuel ethanol (including denaturant) exports data are from PSA/PSM Table 1. Fuel ethanol (minus denaturant) production is equal to fuel ethanol (including denaturant) production from Table 10.3 minus denaturant from Table 10.3. Fuel ethanol (minus denaturant) exports are equal to fuel ethanol (including denaturant) exports multiplied by the ratio of fuel ethanol (minus denaturant) production to fuel ethanol (including denaturant) production. Fuel ethanol (minus denaturant) exports are converted to Btu by multiplying by 3.539 million Btu per barrel, the undenatured ethanol heat content factor in Table A3.

#### *Biomass—Biodiesel*

2001 forward: Biodiesel exports data are from Table 10.4, and are converted to Btu by multiplying by the biodiesel heat content factor in Table A1.

#### *Biomass—Densified Biomass*

2016 forward: Densified biomass exports data are from EIA, Form EIA-63C, “Densified Biomass Fuel Report.”

#### *Total Biomass*

2001–2009: Total biomass exports are equal to biodiesel exports.

2010–2015: Total biomass exports are equal to fuel ethanol (minus denaturant) exports plus biodiesel exports.

2016 forward: Total biomass exports are the sum of the exports values for fuel ethanol (minus denaturant), biodiesel, and densified biomass.

#### *Electricity*

1949 forward: Electricity exports data from Table 7.1 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

#### *Total Primary Energy Exports*

1949 forward: Total primary energy exports are the sum of the exports values for coal, coal coke, natural gas, total petroleum, total biomass, and electricity.

## **Table 1.5 Sources**

U.S. Department of Commerce, U.S. Census Bureau, Foreign Trade Division:

#### *Petroleum Exports*

1974–1987: “U.S. Exports,” FT-410, December issues.

1988 and 1989: “Report on U.S. Merchandise Trade,” Final Revisions.

1990–1992: “U.S. Merchandise Trade,” Final Report.

1993–2016: “U.S. International Trade in Goods and Services,” Annual Revisions.

2017–2019: “U.S. International Trade in Goods and Services,” 2019 Annual Revisions.

2020 and 2021: “U.S. International Trade in Goods and Services,” FT-900, monthly.

### *Petroleum Imports*

1974–1987: “U.S. Merchandise Trade,” FT-900, December issues, 1975–1988.

1988 and 1989: “Report on U.S. Merchandise Trade,” Final Revisions.

1990–1993: “U.S. Merchandise Trade,” Final Report.

1994–2016: “U.S. International Trade in Goods and Services,” Annual Revisions.

2017–2019: “U.S. International Trade in Goods and Services,” 2019 Annual Revisions.

2020 and 2021: “U.S. International Trade in Goods and Services,” FT-900, monthly.

### *Energy Exports and Imports*

1974–1987: U.S. merchandise trade press releases and database printouts for adjustments.

1988: January–July, monthly FT-900 supplement, 1989 issues. August–December, monthly FT-900, 1989 issues.

1989: Monthly FT-900, 1990 issues.

1990–1992: “U.S. Merchandise Trade,” Final Report. 1993–2009: “U.S. International Trade in Goods and Services,” Annual Revisions.

1993–2016: “U.S. International Trade in Goods and Services,” Annual Revisions.

2017–2019: “U.S. International Trade in Goods and Services,” 2019 Annual Revisions.

2020 and 2021: “U.S. International Trade in Goods and Services,” FT-900, monthly.

### *Petroleum Balance*

1974 forward: The petroleum balance is calculated by the U.S. Energy Information Administration (EIA) as petroleum imports minus petroleum exports.

### *Energy Balance*

1974 forward: The energy balance is calculated by EIA as energy imports minus energy exports.

### *Non-Energy Balance*

1974 forward: The non-energy balance is calculated by EIA as the total merchandise balance minus the energy balance.

### *Total Merchandise*

1974–1987: U.S. merchandise trade press releases and database printouts for adjustments.

1988: “Report on U.S. Merchandise Trade, 1988 Final Revisions,” August 18, 1989.

1989: “Report on U.S. Merchandise Trade, 1989 Revisions,” July 10, 1990.

1990: “U.S. Merchandise Trade, 1990 Final Report,” May 10, 1991, and “U.S. Merchandise Trade, December 1992,” February 18, 1993, page 3.

1991: “U.S. Merchandise Trade, 1992 Final Report,” May 12, 1993.

1992–2016: “U.S. International Trade in Goods and Services,” Annual Revisions.

2017–2019: “U.S. International Trade in Goods and Services,” 2019 Annual Revisions.

2020 and 2021: “U.S. International Trade in Goods and Services,” FT-900, monthly.


THIS PAGE INTENTIONALLY LEFT BLANK

## **2. Energy Consumption By Sector**


---

**Figure 2.1 Energy Consumption by Sector**  
(Quadrillion Btu)


Total Consumption by End-Use Sector, 1949–2020



Total Consumption by End-Use Sector, Monthly



By Sector, February 2021



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.

Source: Table 2.1.

**Table 2.1 Energy Consumption by Sector**  
(Trillion Btu)

	End-Use Sectors								Electric Power Sector <sup>c,d</sup>	Balancing Item <sup>g</sup>	Primary Total <sup>h</sup>
	Residential		Commercial <sup>a</sup>		Industrial <sup>b</sup>		Transportation				
	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>		
1950 Total .....	4,830	5,989	2,834	3,893	13,872	16,224	8,383	8,492	4,679	(s)	34,599
1955 Total .....	5,608	7,278	2,561	3,895	16,073	19,455	9,474	9,550	6,461	(s)	40,178
1960 Total .....	6,651	9,040	2,723	4,610	16,949	20,795	10,560	10,596	8,158	(s)	45,041
1965 Total .....	7,280	10,640	3,177	5,846	20,085	25,035	12,399	12,432	11,012	(s)	53,953
1970 Total .....	8,323	13,766	4,237	8,346	22,941	29,605	16,062	16,098	16,253	(s)	67,817
1975 Total .....	7,990	14,814	4,059	9,493	21,400	29,379	18,211	18,245	20,270	1	71,931
1980 Total .....	7,440	15,754	4,105	10,578	22,549	31,993	19,659	19,697	24,269	-1	78,021
1985 Total .....	7,149	16,042	3,732	11,451	19,384	28,757	20,042	20,088	26,032	-4	76,334
1990 Total .....	6,553	16,941	3,894	13,317	21,120	31,749	22,366	22,419	<sup>d</sup> 30,495	7	84,433
1995 Total .....	6,935	18,517	4,101	14,690	22,657	33,908	23,757	23,812	33,479	3	90,931
2000 Total .....	7,156	20,422	4,278	17,175	22,748	34,587	26,456	26,515	38,062	2	98,702
2005 Total .....	6,901	21,613	4,052	17,854	21,343	32,374	28,179	28,261	39,626	(s)	100,102
2006 Total .....	6,155	20,671	3,748	17,707	21,455	32,317	28,618	28,697	39,417	(s)	99,392
2007 Total .....	6,589	21,520	3,923	18,253	21,284	32,306	28,727	28,815	40,371	-1	100,893
2008 Total .....	6,889	21,668	4,100	18,402	20,455	31,261	27,339	27,421	39,969	1	98,754
2009 Total .....	6,637	21,082	4,056	17,888	18,670	28,380	26,510	26,592	38,069	(s)	93,942
2010 Total .....	6,641	21,895	4,023	18,059	20,327	30,574	26,897	26,978	39,619	7	97,513
2011 Total .....	6,473	21,382	4,066	17,982	20,505	30,893	26,518	26,599	39,293	8	96,863
2012 Total .....	5,684	19,870	3,725	17,422	20,781	30,954	26,050	26,126	38,131	2	94,374
2013 Total .....	6,689	21,052	4,161	17,930	21,378	31,525	26,533	26,612	38,357	-1	97,117
2014 Total .....	7,006	21,446	4,390	18,265	21,455	31,691	26,789	26,869	38,629	6	98,276
2015 Total .....	6,465	20,618	4,441	18,157	21,417	31,361	27,162	27,239	37,890	1	97,375
2016 Total .....	6,030	20,179	4,321	18,030	21,553	31,347	27,711	27,786	37,727	-4	97,337
2017 Total .....	6,097	19,886	4,368	17,900	21,953	31,798	27,939	28,014	37,241	(s)	97,599
2018 Total .....	6,982	21,509	4,776	18,440	22,861	32,756	28,388	28,464	38,163	-7	101,162
2019 January .....	1,214	2,536	700	1,810	2,059	2,878	2,299	2,306	3,258	2	9,532
February .....	1,034	2,156	600	1,581	1,777	2,512	2,122	2,128	2,844	(s)	8,377
March .....	906	2,002	551	1,598	1,926	2,716	2,372	2,378	2,940	-2	8,692
April .....	485	1,362	346	1,339	1,843	2,623	2,337	2,343	2,655	-4	7,662
May .....	351	1,356	277	1,391	1,902	2,750	2,436	2,442	2,973	-2	7,937
June .....	249	1,434	229	1,371	1,832	2,671	2,423	2,429	3,173	1	7,906
July .....	231	1,734	227	1,507	1,908	2,796	2,498	2,505	3,677	7	8,548
August .....	231	1,678	234	1,495	1,947	2,825	2,542	2,548	3,592	6	8,552
September .....	223	1,466	223	1,376	1,870	2,684	2,318	2,324	3,216	3	7,854
October .....	376	1,374	310	1,376	1,959	2,739	2,437	2,442	2,849	-2	7,929
November .....	797	1,809	511	1,526	1,951	2,737	2,301	2,307	2,819	-1	8,378
December .....	988	2,163	592	1,640	1,994	2,771	2,348	2,354	3,006	-3	8,926
Total .....	7,085	21,069	4,798	18,011	22,969	32,701	28,432	28,506	37,003	6	100,293
2020 January .....	1,043	2,252	615	1,673	2,010	2,762	2,266	2,272	3,025	-3	8,956
February .....	934	2,020	560	1,549	1,873	2,607	2,128	2,134	2,815	-5	8,305
March .....	707	1,702	445	1,430	1,922	2,664	2,042	2,048	2,727	-5	7,839
April .....	538	1,463	328	1,188	1,643	2,303	1,558	1,562	2,449	-4	6,511
May .....	385	1,445	256	1,195	1,704	2,420	1,787	1,791	2,720	-1	6,851
June .....	254	1,565	215	1,300	1,678	2,430	1,970	1,974	3,152	2	7,272
July .....	228	1,876	207	1,452	1,804	2,606	2,141	2,146	3,700	10	8,091
August .....	217	1,778	208	1,408	1,842	2,656	2,153	2,158	3,579	10	8,010
September .....	243	1,448	225	1,285	1,782	2,513	2,061	2,066	3,001	4	7,317
October .....	382	1,389	298	1,327	1,904	2,661	2,106	2,111	2,799	(s)	7,489
November .....	602	1,587	391	1,352	1,917	2,668	1,985	1,990	2,702	-1	7,596
December .....	1,007	2,288	567	1,599	2,022	2,777	2,035	2,041	3,074	1	8,707
Total .....	6,540	20,803	4,317	16,763	22,102	31,073	24,232	24,295	35,744	9	92,943
2021 January .....	1,097	2,436	610	1,627	<sup>R</sup> 2,012	<sup>R</sup> 2,785	2,009	2,015	3,135	1	<sup>R</sup> 8,865
February .....	1,079	2,328	605	1,570	1,568	2,288	1,832	1,838	2,940	13	8,037
2-Month Total .....	2,176	4,765	1,215	3,197	3,580	5,074	3,841	3,852	6,075	15	16,902
2020 2-Month Total .....	1,977	4,272	1,175	3,222	3,883	5,369	4,394	4,406	5,840	-8	17,261
2019 2-Month Total .....	2,249	4,692	1,299	3,391	3,836	5,390	4,421	4,434	6,102	2	17,909

<sup>a</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>d</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

<sup>e</sup> See "Primary Energy Consumption" in Glossary.

<sup>f</sup> Total energy consumption in the end-use sectors consists of primary energy consumption, electricity retail sales, and electrical system energy losses. See Note 1, "Electrical System Energy Losses," at end of section.

<sup>g</sup> A balancing item. The sum of primary consumption in the five energy-use sectors equals the sum of total consumption in the four end-use sectors. However, total energy consumption does not equal the sum of the sectoral components due

to the use of sector-specific conversion factors for coal and natural gas.

<sup>h</sup> Primary energy consumption total. See Table 1.3.

R=Revised. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.

Notes: • Data are estimates, except for the electric power sector. • See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: • **End-Use Sectors:** Tables 2.2–2.5. • **Electric Power Sector:** Table 2.6. • **Balancing Item:** Calculated as primary energy total consumption minus the sum of total energy consumption in the four end-use sectors.

• **Primary Total:** Table 1.3.


**Figure 2.2 Residential Sector Energy Consumption**

(Quadrillion Btu)


By Major Source, 1949–2020




By Major Source, Monthly



Total, January–February



By Major Source, February 2021



[a] Electricity retail sales.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.

Source: Table 2.2.



**Table 2.2 Residential Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>									Electricity Retail Sales <sup>e</sup>	Electrical System Energy Losses <sup>f</sup>	Total
	Fossil Fuels				Renewable Energy <sup>b</sup>				Total Primary			
	Coal	Natural Gas <sup>c</sup>	Petrol- eum	Total	Geo- thermal	Solar <sup>d</sup>	Bio- mass	Total				
1950 Total .....	1,261	1,240	1,322	3,824	NA	NA	1,006	1,006	4,830	246	913	5,989
1955 Total .....	867	2,198	1,767	4,833	NA	NA	775	775	5,608	438	1,232	7,278
1960 Total .....	585	3,212	2,228	6,025	NA	NA	627	627	6,651	687	1,701	9,040
1965 Total .....	352	4,028	2,432	6,812	NA	NA	468	468	7,280	993	2,367	10,640
1970 Total .....	209	4,987	2,726	7,922	NA	NA	401	401	8,323	1,591	3,852	13,766
1975 Total .....	63	5,023	2,479	7,565	NA	NA	425	425	7,990	2,007	4,817	14,814
1980 Total .....	31	4,825	1,734	6,590	NA	NA	850	850	7,440	2,448	5,866	15,754
1985 Total .....	39	4,534	1,566	6,139	NA	NA	1,010	1,010	7,149	2,709	6,184	16,042
1990 Total .....	31	4,487	1,395	5,912	6	55	580	640	6,553	3,153	7,235	16,941
1995 Total .....	17	4,954	1,374	6,345	7	63	520	589	6,935	3,557	8,026	18,517
2000 Total .....	11	5,105	1,554	6,670	9	58	420	486	7,156	4,069	9,197	20,422
2005 Total .....	8	4,946	1,450	6,405	16	50	430	496	6,901	4,638	10,074	21,613
2006 Total .....	6	4,476	1,222	5,704	18	53	380	451	6,155	4,611	9,905	20,671
2007 Total .....	8	4,835	1,249	6,092	22	55	420	497	6,589	4,750	10,180	21,520
2008 Total .....	NA	5,010	1,325	6,335	26	58	470	555	6,889	4,711	10,068	21,668
2009 Total .....	NA	4,883	1,158	6,041	33	60	504	597	6,637	4,657	9,788	21,082
2010 Total .....	NA	4,878	1,120	5,999	37	65	541	642	6,641	4,933	10,321	21,895
2011 Total .....	NA	4,805	1,034	5,838	40	71	524	635	6,473	4,855	10,054	21,382
2012 Total .....	NA	4,242	886	5,128	40	79	438	557	5,684	4,690	9,496	19,870
2013 Total .....	NA	5,023	963	5,986	40	91	572	703	6,689	4,759	9,604	21,052
2014 Total .....	NA	5,242	1,036	6,279	40	109	579	728	7,006	4,801	9,638	21,446
2015 Total .....	NA	4,777	1,007	5,784	40	128	513	681	6,465	4,791	9,362	20,618
2016 Total .....	NA	4,506	878	5,384	40	162	445	646	6,030	4,815	9,334	20,179
2017 Total .....	NA	4,563	871	5,435	40	193	429	662	6,097	4,704	9,085	19,886
2018 Total .....	NA	5,174	1,022	6,197	40	221	524	785	6,982	5,013	9,515	21,509
2019 January .....	NA	990	162	1,151	3	13	46	63	1,214	455	867	2,536
February .....	NA	840	135	975	3	15	42	59	1,034	398	723	2,156
March .....	NA	714	121	835	3	21	46	70	906	384	712	2,002
April .....	NA	341	73	414	3	23	45	71	485	308	568	1,362
May .....	NA	220	56	276	3	26	46	75	351	342	663	1,356
June .....	NA	134	41	175	3	26	45	74	249	410	776	1,434
July .....	NA	116	38	154	3	27	46	77	231	525	979	1,734
August .....	NA	106	49	155	3	26	46	76	231	512	935	1,678
September .....	NA	114	38	152	3	23	45	71	223	449	794	1,466
October .....	NA	240	66	306	3	20	46	70	376	368	630	1,374
November .....	NA	611	122	733	3	16	45	64	797	350	662	1,809
December .....	NA	781	143	924	3	15	46	64	988	413	762	2,163
Total .....	NA	5,205	1,045	6,250	40	251	544	835	7,085	4,914	9,070	21,069
2020 January .....	NA	851	134	985	3	16	39	58	1,043	424	785	2,252
February .....	NA	759	117	876	3	18	36	58	934	382	704	2,020
March .....	NA	544	98	642	3	24	39	66	707	355	640	1,702
April .....	NA	389	82	471	3	26	38	67	538	333	592	1,463
May .....	NA	244	70	313	3	30	39	72	385	360	700	1,445
June .....	NA	141	43	184	3	30	38	71	254	448	863	1,565
July .....	NA	122	33	155	3	31	39	73	228	569	1,079	1,876
August .....	NA	113	33	146	3	29	39	71	217	542	1,019	1,778
September .....	NA	130	46	177	3	26	38	66	243	436	769	1,448
October .....	NA	249	66	316	3	24	39	66	382	359	649	1,389
November .....	NA	455	87	542	3	20	38	60	602	339	645	1,587
December .....	NA	822	125	947	3	18	39	60	1,007	442	839	2,288
Total .....	NA	4,818	934	5,752	40	291	458	788	6,540	4,988	9,275	20,803
2021 January .....	NA	909	128	1,036	3	19	39	60	1,097	468	871	2,436
February .....	NA	892	129	1,021	3	20	35	58	1,079	434	816	2,328
2-Month Total .....	NA	1,801	257	2,057	6	38	73	118	2,176	902	1,687	4,765
2020 2-Month Total .....	NA	1,610	251	1,861	6	34	75	116	1,977	806	1,489	4,272
2019 2-Month Total .....	NA	1,829	297	2,127	6	28	88	122	2,249	853	1,590	4,692

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> See Table 10.2a for notes on series components.

<sup>c</sup> Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.

<sup>d</sup> Distributed (small-scale) solar photovoltaic (PV) electricity generation in the residential sector and distributed solar thermal energy in the residential, commercial, and industrial sectors. See Tables 10.2a and 10.5.

<sup>e</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

<sup>f</sup> Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total

electricity retail sales. See Note 1, "Electrical System Energy Losses," at end of section.

NA=Not available.

Notes: • Data are estimates, except for electricity retail sales. • See Note 2, "Other Energy Losses," at end of section. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 2.3 Commercial Sector Energy Consumption**

(Quadrillion Btu)


By Major Source, 1949–2020




By Major Source, Monthly



Total, January–February



By Major Source, February 2021



[a] Electricity retail sales.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.

Source: Table 2.3.

**Table 2.3 Commercial Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>										Total Primary	Elec- tricity Retail Sales <sup>g</sup>	Electrical System Energy Losses <sup>h</sup>	Total
	Fossil Fuels				Renewable Energy <sup>b</sup>									
	Coal	Natural Gas <sup>c</sup>	Petro- leum <sup>d</sup>	Total	Hydro- electric Power <sup>e</sup>	Geo- thermal	Solar <sup>f</sup>	Wind	Bio- mass	Total				
1950 Total .....	1,542	401	872	2,815	NA	NA	NA	NA	19	19	2,834	225	834	3,893
1955 Total .....	801	651	1,095	2,547	NA	NA	NA	NA	15	15	2,561	350	984	3,895
1960 Total .....	407	1,056	1,248	2,711	NA	NA	NA	NA	12	12	2,723	543	1,344	4,610
1965 Total .....	265	1,490	1,413	3,168	NA	NA	NA	NA	9	9	3,177	789	1,880	5,846
1970 Total .....	165	2,473	1,592	4,229	NA	NA	NA	NA	8	8	4,237	1,201	2,908	8,346
1975 Total .....	147	2,558	1,346	4,051	NA	NA	NA	NA	8	8	4,059	1,598	3,835	9,493
1980 Total .....	115	2,651	1,318	4,084	NA	NA	NA	NA	21	21	4,105	1,906	4,567	10,578
1985 Total .....	137	2,488	1,083	3,708	NA	NA	NA	NA	24	24	3,732	2,351	5,368	11,451
1990 Total .....	124	2,680	991	3,795	1	3	(s)	—	94	98	3,894	2,860	6,564	13,317
1995 Total .....	117	3,096	769	3,982	1	5	(s)	—	113	119	4,101	3,252	7,337	14,690
2000 Total .....	92	3,252	807	4,150	1	8	1	—	119	128	4,278	3,956	8,942	17,175
2005 Total .....	97	3,073	761	3,931	1	14	2	—	105	121	4,052	4,351	9,451	17,854
2006 Total .....	65	2,902	661	3,627	1	14	3	—	103	120	3,748	4,435	9,525	17,707
2007 Total .....	70	3,085	646	3,801	1	14	4	—	103	122	3,923	4,560	9,771	18,253
2008 Total .....	81	3,228	660	3,970	1	15	6	—	109	131	4,100	4,559	9,743	18,402
2009 Total .....	73	3,187	659	3,919	1	17	8	(s)	112	137	4,056	4,459	9,373	17,888
2010 Total .....	70	3,165	647	3,881	1	19	12	(s)	111	142	4,023	4,539	9,497	18,059
2011 Total .....	62	3,216	632	3,910	(s)	20	20	(s)	115	155	4,066	4,531	9,385	17,982
2012 Total .....	44	2,960	560	3,563	(s)	20	33	1	108	162	3,725	4,528	9,168	17,422
2013 Total .....	41	3,380	558	3,979	(s)	20	41	1	120	182	4,161	4,562	9,206	17,930
2014 Total .....	40	3,572	578	4,190	(s)	20	52	1	127	200	4,390	4,614	9,261	18,265
2015 Total .....	31	3,316	864	4,211	(s)	20	57	1	152	230	4,441	4,643	9,073	18,157
2016 Total .....	24	3,224	832	4,079	2	20	62	1	158	242	4,321	4,665	9,044	18,030
2017 Total .....	21	3,273	820	4,113	2	20	76	1	156	255	4,368	4,616	8,916	17,900
2018 Total .....	19	3,638	845	4,502	2	20	94	2	156	274	4,776	4,715	8,949	18,440
2019 January .....	2	575	101	678	(s)	2	6	(s)	13	21	700	382	728	1,810
February .....	2	490	87	579	(s)	2	6	(s)	12	20	600	348	633	1,581
March .....	2	440	85	527	(s)	2	9	(s)	13	24	551	367	680	1,598
April .....	1	256	65	322	(s)	2	10	(s)	12	24	346	350	644	1,339
May .....	1	192	59	252	(s)	2	10	(s)	12	25	277	379	734	1,391
June .....	1	150	53	204	(s)	2	11	(s)	12	25	229	395	747	1,371
July .....	1	147	53	201	(s)	2	11	(s)	13	26	227	447	834	1,507
August .....	1	146	62	209	(s)	2	11	(s)	13	25	234	446	815	1,495
September .....	1	148	49	199	(s)	2	9	(s)	12	24	223	416	737	1,376
October .....	1	224	62	287	(s)	2	8	(s)	13	23	310	393	672	1,376
November .....	1	403	85	490	(s)	2	6	(s)	12	21	511	351	664	1,526
December .....	2	474	95	571	(s)	2	6	(s)	13	21	592	369	679	1,640
Total .....	17	3,645	857	4,519	2	24	103	2	149	279	4,798	4,643	8,570	18,011
2020 January .....	2	505	87	593	NM	2	7	(s)	13	22	615	372	687	1,673
February .....	2	460	77	539	NM	2	8	(s)	12	22	560	348	641	1,549
March .....	2	349	70	421	NM	2	10	(s)	12	25	445	351	633	1,430
April .....	1	245	58	304	NM	2	11	(s)	11	24	328	309	550	1,188
May .....	1	167	62	230	NM	2	12	(s)	12	26	256	319	621	1,195
June .....	1	136	51	188	NM	2	12	(s)	12	26	215	371	715	1,300
July .....	1	133	47	180	NM	2	13	(s)	12	27	207	430	814	1,452
August .....	1	136	46	182	NM	2	12	(s)	12	26	208	416	783	1,408
September .....	1	147	53	201	(s)	2	11	(s)	11	24	225	383	677	1,285
October .....	1	215	59	275	NM	2	10	(s)	12	24	298	366	662	1,327
November .....	1	304	65	369	NM	2	8	(s)	12	21	391	331	630	1,352
December .....	1	466	78	545	NM	2	7	(s)	12	22	567	356	676	1,599
Total .....	15	3,262	751	4,027	2	24	121	2	141	289	4,317	4,353	8,093	16,763
2021 January .....	1	509	77	588	NM	2	8	(s)	12	22	610	356	661	1,627
February .....	1	507	75	583	NM	2	9	(s)	11	22	605	335	630	1,570
2-Month Total .....	3	1,016	153	1,171	(s)	4	17	(s)	23	44	1,215	690	1,292	3,197
2020 2-Month Total .....	4	965	163	1,132	NM	4	15	(s)	24	44	1,175	719	1,328	3,222
2019 2-Month Total .....	4	1,065	188	1,258	(s)	4	12	(s)	25	42	1,299	730	1,361	3,391

<sup>a</sup> See "Primary Energy Consumption" in Glossary.  
<sup>b</sup> See Table 10.2a for notes on series components and estimation.  
<sup>c</sup> Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.  
<sup>d</sup> Does not include biofuels that have been blended with petroleum—biofuels are included in "Biomass."  
<sup>e</sup> Conventional hydroelectric power.  
<sup>f</sup> Solar photovoltaic (PV) electricity net generation in the commercial sector, both utility-scale and distributed (small-scale). See Tables 10.2a and 10.5.  
<sup>g</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.  
<sup>h</sup> Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Note 1, "Electrical System Energy Losses," at end of section.

NA=Not available. NM=Not meaningful. —=No data reported. (s)=Less than 0.5 trillion Btu.

Notes: • Data are estimates, except for coal totals beginning in 2008; hydroelectric power; solar; wind; and electricity retail sales beginning in 1979.  
• The commercial sector includes commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • See Note 2, "Other Energy Losses," at end of section. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 2.4 Industrial Sector Energy Consumption**

(Quadrillion Btu)


By Major Source, 1949–2020




By Major Source, Monthly



Total, January–February



By Major Source, February 2021



[a] Electricity retail sales.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.

Source: Table 2.4.

**Table 2.4 Industrial Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>											Elec- tricity Retail Sales <sup>i</sup>	Electrical System Energy Losses <sup>j</sup>	Total <sup>k</sup>
	Fossil Fuels <sup>b</sup>				Renewable Energy <sup>c</sup>						Total Primary			
	Coal	Natural Gas <sup>d</sup>	Petro- leum <sup>e</sup>	Total <sup>f</sup>	Hydro- electric Power <sup>g</sup>	Geo- thermal	Solar <sup>h</sup>	Wind	Bio- mass	Total				
1950 Total .....	5,781	3,546	3,943	13,271	69	NA	NA	NA	532	602	13,872	500	1,852	16,224
1955 Total .....	5,620	4,701	5,093	15,404	38	NA	NA	NA	631	669	16,073	887	2,495	19,455
1960 Total .....	4,543	5,973	5,720	16,231	39	NA	NA	NA	680	719	16,949	1,107	2,739	20,795
1965 Total .....	5,127	7,339	6,750	19,197	33	NA	NA	NA	855	888	20,085	1,463	3,487	25,035
1970 Total .....	4,656	9,536	7,754	21,888	34	NA	NA	NA	1,019	1,053	22,941	1,948	4,716	29,605
1975 Total .....	3,667	8,532	8,092	20,304	32	NA	NA	NA	1,063	1,096	21,400	2,346	5,632	29,379
1980 Total .....	3,155	8,333	9,463	20,916	33	NA	NA	NA	1,600	1,633	22,549	2,781	6,664	31,993
1985 Total .....	2,760	7,032	7,655	17,433	33	NA	NA	NA	1,918	1,951	19,384	2,855	6,518	28,757
1990 Total .....	2,756	8,443	8,199	19,402	31	2	(s)	—	1,684	1,717	21,120	3,226	7,404	31,749
1995 Total .....	2,488	9,592	8,524	20,665	55	3	(s)	—	1,934	1,992	22,657	3,455	7,796	33,908
2000 Total .....	2,256	9,500	8,998	20,820	42	4	(s)	—	1,881	1,928	22,748	3,631	8,208	34,587
2005 Total .....	1,954	7,907	9,567	19,472	32	4	(s)	—	1,834	1,871	21,343	3,477	7,554	32,374
2006 Total .....	1,914	7,861	9,693	19,529	29	4	1	—	1,892	1,926	21,455	3,451	7,411	32,317
2007 Total .....	1,865	8,074	9,363	19,326	16	5	1	—	1,937	1,958	21,284	3,507	7,515	32,306
2008 Total .....	1,793	8,083	8,502	18,420	17	5	1	—	2,012	2,035	20,455	3,444	7,362	31,261
2009 Total .....	1,392	7,609	7,720	16,698	18	4	2	—	1,948	1,972	18,670	3,130	6,580	28,380
2010 Total .....	1,631	8,278	8,080	17,983	16	4	3	—	2,320	2,343	20,327	3,314	6,934	30,574
2011 Total .....	1,561	8,481	8,052	18,105	17	4	4	—	2,375	2,401	20,505	3,382	7,005	30,893
2012 Total .....	1,513	8,819	8,063	18,399	22	4	7	—	2,349	2,383	20,781	3,363	6,810	30,954
2013 Total .....	1,546	9,140	8,259	18,929	33	4	9	—	2,403	2,449	21,378	3,362	6,785	31,525
2014 Total .....	1,530	9,441	8,021	18,971	12	4	11	—	2,456	2,484	21,455	3,404	6,832	31,691
2015 Total .....	1,380	9,426	8,138	18,925	13	4	14	(s)	2,460	2,491	21,417	3,366	6,578	31,361
2016 Total .....	1,205	9,617	8,247	19,050	12	4	19	1	2,467	2,503	21,553	3,333	6,461	31,347
2017 Total .....	1,195	9,864	8,433	19,463	13	4	22	1	2,450	2,490	21,953	3,358	6,487	31,798
2018 Total .....	1,180	10,474	8,753	20,381	10	4	24	1	2,440	2,480	22,861	3,414	6,481	32,756
2019 January .....	97	989	766	1,850	1	(s)	2	(s)	206	209	2,059	282	537	2,878
February .....	93	889	606	1,588	1	(s)	2	(s)	187	190	1,777	261	474	2,512
March .....	98	938	686	1,722	1	(s)	2	(s)	201	205	1,926	277	513	2,716
April .....	90	855	702	1,646	1	(s)	3	(s)	193	197	1,843	275	506	2,623
May .....	95	861	744	1,699	1	(s)	3	(s)	199	204	1,902	289	559	2,750
June .....	94	814	725	1,631	1	(s)	3	(s)	196	201	1,832	290	549	2,671
July .....	91	837	775	1,701	1	(s)	3	(s)	204	207	1,908	310	578	2,796
August .....	91	863	787	1,740	1	(s)	3	(s)	203	207	1,947	311	567	2,825
September .....	91	829	761	1,678	(s)	(s)	3	(s)	189	192	1,870	294	520	2,684
October .....	93	878	788	1,757	1	(s)	2	(s)	198	201	1,959	288	492	2,739
November .....	90	927	735	1,750	1	(s)	2	(s)	198	201	1,951	272	514	2,737
December .....	94	978	715	1,784	1	(s)	2	(s)	207	210	1,994	273	504	2,771
Total .....	1,117	10,660	8,790	20,546	9	4	28	1	2,381	2,423	22,969	3,420	6,312	32,701
2020 January .....	90	988	726	1,802	1	(s)	2	(s)	206	209	2,010	264	488	2,762
February .....	89	914	676	1,678	1	(s)	2	(s)	192	195	1,873	258	476	2,607
March .....	88	913	725	1,724	1	(s)	3	(s)	193	197	1,922	265	478	2,664
April .....	72	825	580	1,476	1	(s)	3	(s)	163	167	1,643	237	423	2,303
May .....	68	802	653	1,523	1	(s)	3	(s)	177	182	1,704	243	473	2,420
June .....	74	780	644	1,497	1	(s)	3	1	176	181	1,678	257	495	2,430
July .....	69	823	719	1,612	1	(s)	3	1	187	192	1,804	277	525	2,606
August .....	72	837	744	1,652	1	(s)	3	1	185	190	1,842	283	532	2,656
September .....	71	828	697	1,594	1	(s)	3	1	183	188	1,782	264	467	2,513
October .....	80	877	<sup>R</sup> 753	1,709	1	(s)	3	1	190	195	1,904	270	488	2,661
November .....	81	894	747	1,720	1	(s)	2	1	194	198	1,917	259	492	2,668
December .....	83	978	759	1,818	1	(s)	2	1	200	204	2,022	260	494	2,777
Total .....	936	10,460	8,421	19,805	9	4	32	6	2,246	2,297	22,102	3,137	5,834	31,073
2021 January .....	84	<sup>R</sup> 983	749	<sup>R</sup> 1,813	1	(s)	2	1	195	199	<sup>R</sup> 2,012	270	503	<sup>R</sup> 2,785
February .....	50	833	518	1,398	1	(s)	2	1	166	170	1,568	250	470	2,288
2-Month Total .....	134	1,817	1,267	3,211	1	1	4	2	361	369	3,580	520	973	5,074
2020 2-Month Total .....	179	1,902	1,402	3,480	2	1	4	(s)	397	403	3,883	522	964	5,369
2019 2-Month Total .....	191	1,878	1,372	3,437	2	1	3	(s)	393	399	3,836	543	1,011	5,390

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> Includes non-combustion use of fossil fuels.

<sup>c</sup> See Table 10.2b for notes on series components and estimation.

<sup>d</sup> Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.

<sup>e</sup> Does not include biofuels that have been blended with petroleum—biofuels are included in "Biomass."

<sup>f</sup> Includes coal coke net imports, which are not separately displayed. See Tables 1.4a and 1.4b.

<sup>g</sup> Conventional hydroelectric power.

<sup>h</sup> Solar photovoltaic (PV) electricity net generation in the industrial sector, both utility-scale and distributed (small-scale). See Tables 10.2b and 10.5.

<sup>i</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

<sup>j</sup> Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total

electricity retail sales. See Note 1, "Electrical System Energy Losses," at end of section.

<sup>k</sup> R=Revised. NA=Not available. —=No data reported. (s)=Less than 0.5 trillion Btu.


Notes: • Data are estimates, except for coal totals; hydroelectric power in 1949–1978 and 1989 forward; solar; wind; and electricity retail sales. • The industrial sector includes industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • See Note 2, "Other Energy Losses," at end of section. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: See end of section.

**Figure 2.5 Transportation Sector Energy Consumption**  
(Quadrillion Btu)


By Major Source, 1949–2020




By Major Source, Monthly



Total, January–February



Total, Monthly



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.  
Source: Table 2.5.

**Table 2.5 Transportation Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>						Electricity Retail Sales <sup>e</sup>	Electrical System Energy Losses <sup>f</sup>	Total
	Fossil Fuels				Renewable Energy <sup>b</sup>	Total Primary			
	Coal	Natural Gas <sup>c</sup>	Petroleum <sup>d</sup>	Total	Biomass				
1950 Total .....	1,564	130	6,690	8,383	NA	8,383	23	86	8,492
1955 Total .....	421	254	8,799	9,474	NA	9,474	20	56	9,550
1960 Total .....	75	359	10,125	10,560	NA	10,560	10	26	10,596
1965 Total .....	16	517	11,866	12,399	NA	12,399	10	24	12,432
1970 Total .....	7	745	15,311	16,062	NA	16,062	11	26	16,098
1975 Total .....	1	595	17,615	18,211	NA	18,211	10	24	18,245
1980 Total .....	(g)	650	19,009	19,659	NA	19,659	11	27	19,697
1985 Total .....	(g)	519	19,472	19,992	50	20,042	14	32	20,088
1990 Total .....	(g)	679	21,626	22,305	60	22,366	16	37	22,419
1995 Total .....	(g)	724	22,920	23,644	112	23,757	17	38	23,812
2000 Total .....	(g)	672	25,649	26,321	135	26,456	18	42	26,515
2005 Total .....	(g)	624	27,217	27,840	339	28,179	26	56	28,261
2006 Total .....	(g)	625	27,518	28,143	475	28,618	25	54	28,697
2007 Total .....	(g)	663	27,462	28,126	602	28,727	28	60	28,815
2008 Total .....	(g)	692	25,823	26,515	825	27,339	26	56	27,421
2009 Total .....	(g)	715	24,860	25,575	935	26,510	27	56	26,592
2010 Total .....	(g)	719	25,103	25,822	1,075	26,897	26	55	26,978
2011 Total .....	(g)	734	24,626	25,360	1,159	26,518	26	54	26,599
2012 Total .....	(g)	780	24,111	24,890	1,160	26,050	25	51	26,126
2013 Total .....	(g)	887	24,362	25,249	1,284	26,533	26	53	26,612
2014 Total .....	(g)	760	24,727	25,487	1,302	26,789	26	53	26,869
2015 Total .....	(g)	745	25,083	25,828	1,334	27,162	26	51	27,239
2016 Total .....	(g)	757	25,511	26,268	1,443	27,711	26	50	27,786
2017 Total .....	(g)	799	25,702	26,500	1,439	27,939	26	50	28,014
2018 Total .....	(g)	962	26,011	26,974	1,415	28,388	26	50	28,464
2019 January .....	(g)	114	2,078	2,192	107	2,299	2	4	2,306
February .....	(g)	101	1,913	2,014	108	2,122	2	4	2,128
March .....	(g)	97	2,158	2,255	117	2,372	2	4	2,378
April .....	(g)	73	2,148	2,222	115	2,337	2	4	2,343
May .....	(g)	71	2,240	2,310	126	2,436	2	4	2,442
June .....	(g)	70	2,230	2,301	122	2,423	2	4	2,429
July .....	(g)	80	2,294	2,375	124	2,498	2	4	2,505
August .....	(g)	81	2,339	2,420	122	2,542	2	4	2,548
September .....	(g)	74	2,131	2,205	113	2,318	2	4	2,324
October .....	(g)	77	2,238	2,315	121	2,437	2	3	2,442
November .....	(g)	92	2,092	2,184	116	2,301	2	4	2,307
December .....	(g)	105	2,124	2,229	119	2,348	2	4	2,354
Total .....	(g)	1,035	25,986	27,021	1,411	28,432	26	48	28,506
2020 January .....	(g)	109	2,043	2,153	113	2,266	2	4	2,272
February .....	(g)	101	1,922	2,022	106	2,128	2	4	2,134
March .....	(g)	91	1,854	1,945	97	2,042	2	4	2,048
April .....	(g)	76	1,407	1,483	75	1,558	2	3	1,562
May .....	(g)	71	1,618	1,688	98	1,787	2	3	1,791
June .....	(g)	72	1,789	1,861	109	1,970	2	3	1,974
July .....	(g)	84	1,942	2,025	115	2,141	2	4	2,146
August .....	(g)	81	1,961	2,042	111	2,153	2	3	2,158
September .....	(g)	74	1,875	1,949	112	2,061	2	3	2,066
October .....	(g)	78	1,920	1,999	108	2,106	2	3	2,111
November .....	(g)	82	1,796	1,878	107	1,985	2	3	1,990
December .....	(g)	105	1,819	1,923	112	2,035	2	4	2,041
Total .....	(g)	1,023	21,945	22,968	1,263	24,232	22	41	24,295
2021 January .....	(g)	109	1,807	1,916	94	2,009	2	4	2,015
February .....	(g)	101	1,641	1,742	91	1,832	2	4	1,838
2-Month Total .....	(g)	210	3,448	3,657	184	3,841	4	7	3,852
2020 2-Month Total .....	(g)	210	3,965	4,175	219	4,394	4	8	4,406
2019 2-Month Total .....	(g)	214	3,991	4,206	215	4,421	5	9	4,434

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> See Table 10.2b for notes on series components.

<sup>c</sup> Natural gas only; does not include supplemental gaseous fuels—see Note 3, "Supplemental Gaseous Fuels," at end of Section 4. Data are for natural gas consumed in the operation of pipelines (primarily in compressors) and small amounts consumed as vehicle fuel—see Table 4.3.

<sup>d</sup> Does not include biofuels. Biofuels are included in "Biomass." Includes non-combustion use of lubricants.

<sup>e</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

<sup>f</sup> Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Note 1, "Electrical System Energy Losses," at end of

section.

<sup>g</sup> Beginning in 1978, the small amounts of coal consumed for transportation are reported as industrial sector consumption.

NA=Not available.

Notes: • Data are estimates, except for coal totals through 1977; and electricity retail sales beginning in 1979. • See Note 2, "Other Energy Losses," at end of section. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 2.6 Electric Power Sector Energy Consumption**

(Quadrillion Btu)


By Major Source, 1949–2020




By Major Source, Monthly



Total, January–February



By Major Source, February 2021



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.

Source: Table 2.6.



**Table 2.6 Electric Power Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>												
	Fossil Fuels				Nuclear Electric Power	Renewable Energy <sup>b</sup>						Elec- tricity Net Imports <sup>f</sup>	Total Primary
	Coal	Natural Gas <sup>c</sup>	Petro- leum	Total		Hydro- electric Power <sup>d</sup>	Geo- thermal	Solar <sup>e</sup>	Wind	Bio- mass	Total		
1950 Total .....	2,199	651	472	3,322	0	1,346	NA	NA	NA	5	1,351	6	4,679
1955 Total .....	3,458	1,194	471	5,123	0	1,322	NA	NA	NA	3	1,325	14	6,461
1960 Total .....	4,228	1,785	553	6,565	6	1,569	(s)	NA	NA	2	1,571	15	8,158
1965 Total .....	5,821	2,395	722	8,938	43	2,026	2	NA	NA	3	2,031	(s)	11,012
1970 Total .....	7,227	4,054	2,117	13,399	239	2,600	6	NA	NA	4	2,609	7	16,253
1975 Total .....	8,786	3,240	3,166	15,191	1,900	3,122	34	NA	NA	2	3,158	21	20,270
1980 Total .....	12,123	3,778	2,634	18,534	2,739	2,867	53	NA	NA	4	2,925	71	24,269
1985 Total .....	14,542	3,135	1,090	18,767	4,076	2,937	97	(s)	(s)	14	3,049	140	26,032
1990 Total .....	16,261	3,309	1,289	20,859	6,104	3,014	161	4	29	317	3,524	8	30,495
1995 Total .....	17,466	4,302	755	22,523	7,075	3,149	138	5	33	422	3,747	134	33,479
2000 Total .....	20,220	5,293	1,144	26,658	7,862	2,768	144	5	57	453	3,427	115	38,062
2005 Total .....	20,737	6,015	1,222	27,974	8,161	2,670	147	6	178	406	3,406	85	39,626
2006 Total .....	20,462	6,375	637	27,474	8,215	2,839	145	5	264	412	3,665	63	39,417
2007 Total .....	20,808	7,005	648	28,461	8,459	2,430	145	6	341	423	3,345	107	40,371
2008 Total .....	20,513	6,829	459	27,801	8,426	2,494	146	9	546	435	3,630	112	39,969
2009 Total .....	18,225	7,022	382	25,630	8,355	2,650	146	9	721	441	3,967	116	38,069
2010 Total .....	19,133	7,528	370	27,031	8,434	2,521	148	12	923	459	4,064	89	39,619
2011 Total .....	18,035	7,712	295	26,042	8,269	3,085	149	17	1,167	437	4,855	127	39,293
2012 Total .....	15,821	9,287	214	25,322	8,062	2,606	148	40	1,339	453	4,586	161	38,131
2013 Total .....	16,451	8,376	255	25,082	8,244	2,529	151	83	1,600	470	4,833	197	38,357
2014 Total .....	16,427	8,362	295	25,085	8,338	2,454	151	165	1,726	530	5,026	182	38,629
2015 Total .....	14,138	9,926	276	24,341	8,337	2,308	148	228	1,776	525	4,985	227	37,890
2016 Total .....	12,996	10,301	244	23,542	8,427	2,459	146	328	2,094	505	5,531	227	37,727
2017 Total .....	12,622	9,555	218	22,395	8,419	2,752	147	486	2,341	510	6,235	192	37,241
2018 Total .....	12,053	10,912	260	23,225	8,438	2,651	145	576	2,480	496	6,348	152	38,163
2019 January .....	1,058	876	22	1,956	770	220	12	32	216	41	520	11	3,258
February .....	853	804	16	1,673	676	203	11	34	201	36	485	11	2,844
March .....	834	840	15	1,688	680	233	12	52	229	37	564	8	2,940
April .....	632	763	12	1,407	633	247	11	60	257	34	608	8	2,655
May .....	757	862	18	1,637	701	284	12	63	229	37	624	10	2,973
June .....	837	1,022	16	1,874	718	249	12	70	200	37	567	12	3,173
July .....	1,057	1,294	18	2,370	754	221	12	72	197	40	541	13	3,677
August .....	991	1,318	18	2,327	751	200	12	69	178	40	500	14	3,592
September .....	893	1,115	15	2,023	690	164	12	60	218	37	491	12	3,216
October .....	709	966	11	1,686	648	162	10	54	246	35	507	7	2,849
November .....	793	845	13	1,651	670	179	8	38	224	36	486	12	2,819
December .....	766	941	15	1,722	763	190	10	30	237	39	507	14	3,006
Total .....	10,181	11,646	189	22,016	8,452	2,553	134	635	2,632	448	6,402	133	37,003
2020 January .....	694	960	17	1,671	774	225	11	41	254	38	569	11	3,025
February .....	605	906	13	1,524	689	234	11	50	262	36	593	10	2,815
March .....	546	906	14	1,467	668	209	13	57	263	37	579	13	2,727
April .....	445	787	13	1,245	618	196	13	72	262	33	575	11	2,449
May .....	507	859	14	1,379	672	270	13	86	252	35	656	12	2,720
June .....	693	1,077	17	1,787	702	258	12	85	262	33	650	13	3,152
July .....	941	1,414	18	2,374	725	246	13	92	198	35	583	19	3,700
August .....	954	1,320	17	2,291	720	214	12	84	199	39	548	20	3,579
September .....	731	1,070	12	1,813	686	170	12	70	205	33	489	13	3,001
October .....	641	983	13	1,637	620	162	12	65	256	33	529	13	2,799
November .....	650	791	14	1,455	645	194	13	52	299	34	591	12	2,702
December .....	823	900	17	1,740	730	205	13	48	288	37	590	15	3,074
Total .....	8,231	11,972	180	20,382	8,248	2,581	147	802	2,998	424	6,952	161	35,744
2021 January .....	858	893	17	1,768	750	232	12	51	270	36	601	16	3,135
February .....	907	812	24	1,743	657	196	11	57	237	35	536	3	2,940
2-Month Total .....	1,765	1,706	41	3,511	1,407	428	24	108	507	71	1,138	19	6,075
2020 2-Month Total .....	1,299	1,866	30	3,195	1,463	458	22	91	515	74	1,162	21	5,840
2019 2-Month Total .....	1,911	1,680	38	3,629	1,445	422	23	65	417	77	1,005	22	6,102

a See "Primary Energy Consumption" in Glossary.  
b See Table 10.2c for notes on series components.  
c Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.  
d Conventional hydroelectric power.  
e Solar photovoltaic (PV) and solar thermal electricity net generation in the electric power sector. See Tables 10.2c and 10.5.  
f Net imports equal imports minus exports.  
g Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.  
NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for fuels consumed to produce electricity and useful thermal output.  
• The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • See Note 3, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
Sources: See end of section.

**Table 2.7 U.S. Government Energy Consumption by Agency, Fiscal Years**  
(Trillion Btu)

Fiscal Year <sup>a</sup>	Agri-culture	Defense	DHS <sup>b</sup>	Energy	GSA <sup>c</sup>	HHS <sup>d</sup>	Interior	Justice	NASA <sup>e</sup>	Postal Service	Trans- portation	Veterans Affairs	Other <sup>f</sup>	Total
1975 .....	9.5	1,360.2	--	50.4	22.3	6.5	9.4	5.9	13.4	30.5	19.3	27.1	10.5	1,565.0
1976 .....	9.3	1,183.3	--	50.3	20.6	6.7	9.4	5.7	12.4	30.0	19.5	25.0	11.2	1,383.4
1977 .....	8.9	1,192.3	--	51.6	20.4	6.9	9.5	5.9	12.0	32.7	20.4	25.9	11.9	1,398.5
1978 .....	9.1	1,157.8	--	50.1	20.4	6.5	9.2	5.9	11.2	30.9	20.6	26.8	12.4	1,360.9
1979 .....	9.2	1,175.8	--	49.6	19.6	6.4	10.4	6.4	11.1	29.3	19.6	25.7	12.3	1,375.4
1980 .....	8.6	1,183.1	--	47.4	18.1	6.0	8.5	5.7	10.4	27.2	19.2	24.8	12.3	1,371.2
1981 .....	7.9	1,239.5	--	47.3	18.0	6.7	7.6	5.4	10.0	27.9	18.8	24.0	11.1	1,424.2
1982 .....	7.6	1,264.5	--	49.0	18.1	6.4	7.4	5.8	10.1	27.5	19.1	24.2	11.6	1,451.4
1983 .....	7.4	1,248.3	--	49.5	16.1	6.2	7.7	5.5	10.3	26.5	19.4	24.1	10.8	1,431.8
1984 .....	7.9	1,292.1	--	51.6	16.2	6.4	8.4	6.4	10.6	27.7	19.8	24.6	10.7	1,482.5
1985 .....	8.4	1,250.6	--	52.2	20.7	6.0	7.8	8.2	10.9	27.8	19.6	25.1	13.1	1,450.3
1986 .....	6.8	1,222.8	--	46.9	14.0	6.2	6.9	8.6	11.2	28.0	19.4	25.0	10.8	1,406.7
1987 .....	7.3	1,280.5	--	48.5	13.1	6.6	6.6	8.1	11.3	28.5	19.0	24.9	11.9	1,466.3
1988 .....	7.8	1,165.8	--	49.9	12.4	6.4	7.0	9.4	11.3	29.6	18.7	26.3	15.8	1,360.3
1989 .....	8.7	1,274.4	--	44.2	12.7	6.7	7.1	7.7	12.4	30.3	18.5	26.2	15.6	1,464.7
1990 .....	9.6	1,241.7	--	43.5	17.5	7.1	7.4	7.0	12.4	30.6	19.0	24.9	17.5	1,438.0
1991 .....	9.6	1,269.3	--	42.1	14.0	6.2	7.1	8.0	12.5	30.8	19.0	25.1	18.1	1,461.7
1992 .....	9.1	1,104.0	--	44.3	13.8	6.8	7.0	7.5	12.6	31.7	17.0	25.3	15.7	1,294.8
1993 .....	9.3	1,048.8	--	43.4	14.1	7.2	7.5	9.1	12.4	33.7	19.4	25.7	16.2	1,246.8
1994 .....	9.4	977.0	--	42.1	14.0	7.5	7.9	10.3	12.6	35.0	19.8	25.6	17.1	1,178.2
1995 .....	9.0	926.0	--	47.3	13.7	6.1	6.4	10.2	12.4	36.2	18.7	25.4	17.1	1,128.5
1996 .....	9.1	904.5	--	44.6	14.5	6.6	4.3	12.1	11.5	36.4	19.6	26.8	17.7	1,107.7
1997 .....	7.4	880.0	--	43.1	14.4	7.9	6.6	12.0	12.0	40.8	19.1	27.3	20.8	1,091.2
1998 .....	7.9	837.1	--	31.5	14.1	7.4	6.4	15.8	11.7	39.5	18.5	27.6	19.5	1,037.1
1999 .....	7.8	810.7	--	27.0	14.4	7.1	7.5	15.4	11.4	39.8	22.6	27.5	19.8	1,010.9
2000 .....	7.4	779.1	--	30.5	17.6	8.0	7.8	19.7	11.1	43.3	21.2	27.0	20.3	993.1
2001 .....	7.4	787.2	--	31.1	18.4	8.5	9.5	19.7	10.9	43.4	17.8	27.7	20.7	1,002.3
2002 .....	7.2	837.5	--	30.7	17.5	8.0	8.2	17.7	10.7	41.6	18.3	27.7	18.4	1,043.4
2003 .....	7.7	895.1	18.3	31.9	18.5	10.1	7.3	22.7	10.8	50.9	5.5	30.6	22.7	1,132.3
2004 .....	7.0	960.7	23.5	31.4	18.3	8.8	8.7	17.5	9.9	50.5	5.2	29.9	20.4	1,191.7
2005 .....	7.5	933.2	18.9	29.6	18.4	9.6	8.6	18.8	10.3	53.5	5.0	30.0	23.2	1,166.4
2006 .....	6.8	843.7	17.1	32.9	18.2	9.3	8.1	23.5	10.2	51.8	4.6	29.3	20.9	1,076.4
2007 .....	6.8	864.6	17.1	31.5	19.1	9.9	7.5	20.7	10.6	45.8	5.6	30.0	21.0	1,090.2
2008 .....	6.5	910.8	21.7	32.1	18.8	10.3	7.1	19.0	10.8	47.1	7.7	29.0	22.4	1,143.2
2009 .....	6.6	874.3	18.6	31.1	18.6	10.8	7.9	16.5	10.2	44.2	4.3	29.9	21.8	1,094.8
2010 .....	6.8	889.9	21.2	31.7	18.8	10.4	7.3	15.7	10.1	43.3	5.7	30.2	21.8	1,112.7
2011 .....	8.3	890.3	20.3	33.1	18.5	10.5	7.3	13.9	10.1	43.0	6.7	30.6	21.4	1,114.1
2012 .....	6.7	828.5	20.1	30.3	16.3	10.0	6.7	15.1	8.9	40.8	5.6	29.7	20.5	1,039.3
2013 .....	7.3	749.5	18.9	28.9	16.4	10.5	6.2	15.3	8.7	41.9	5.3	29.9	20.4	959.3
2014 .....	6.3	730.6	18.5	29.4	17.0	9.5	6.2	15.6	8.3	43.0	5.2	31.4	20.6	941.5
2015 .....	6.2	734.5	17.9	30.1	16.3	9.0	6.8	16.2	8.4	44.0	6.0	30.7	19.8	945.8
2016 .....	6.2	709.2	18.1	28.9	15.8	8.7	6.4	15.6	8.5	43.9	6.0	30.3	19.5	917.2
2017 .....	6.3	707.9	19.2	28.8	15.0	8.8	5.9	15.5	8.6	43.7	6.6	29.1	19.7	915.1
2018 .....	6.1	690.6	16.8	27.3	15.6	10.0	6.1	16.2	8.4	45.5	5.8	29.7	18.8	897.0
2019 .....	5.9	682.1	16.2	26.4	15.4	9.8	6.2	15.8	8.6	46.0	5.9	31.9	18.9	889.0

<sup>a</sup> For 1975 and 1976, the U.S. Government's fiscal year was July 1 through June 30. Beginning in 1977, the U.S. Government's fiscal year is October 1 through September 30 (for example, fiscal year 2014 is October 2013 through September 2014).

<sup>b</sup> U.S. Department of Homeland Security.

<sup>c</sup> General Services Administration.

<sup>d</sup> U.S. Department of Health and Human Services.

<sup>e</sup> National Aeronautics and Space Administration.

<sup>f</sup> Includes all U.S. government agencies not separately displayed. See <http://ctsedweb.ee.doe.gov/Annual/Report/AgencyReference.aspx> for agency list.  
-- =Not applicable.

Notes: • Data in this table are developed using conversion factors that often

differ from those in Tables A1--A6. • Data include energy consumed at foreign installations and in foreign operations, including aviation and ocean bunkering, primarily by the U.S. Department of Defense. U.S. Government energy use for electricity generation and uranium enrichment is excluded. • Totals may not equal sum of components due to independent rounding.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all annual data beginning in 1975.

Sources: U.S. Department of Energy, Office of Energy Efficiency and Renewable Energy, Federal Energy Management Program. See <http://ctsedweb.ee.doe.gov/Annual/Report/Report.aspx>, "A-1 Total Site-Delivered Energy Use in All End-Use Sectors, by Federal Agency (Billion Btu)".

**Table 2.8 U.S. Government Energy Consumption by Source, Fiscal Years**  
(Trillion Btu)

Fiscal Year <sup>a</sup>	Coal	Natural Gas <sup>b</sup>	Petroleum						Other Mobility Fuels <sup>f</sup>	Electricity	Purchased Steam and Other <sup>g</sup>	Total
			Aviation Gasoline	Fuel Oil <sup>c</sup>	Jet Fuel	LPG <sup>d</sup>	Motor Gasoline <sup>e</sup>	Total				
1975 .....	77.9	166.2	22.0	376.0	707.4	5.6	63.2	1,174.2	0.0	141.5	5.1	1,565.0
1976 .....	71.3	151.8	11.6	329.7	610.0	4.7	60.4	1,016.4	.0	139.3	4.6	1,383.4
1977 .....	68.4	141.2	8.8	348.5	619.2	4.1	61.4	1,042.1	.0	141.1	5.7	1,398.5
1978 .....	66.0	144.7	6.2	332.3	601.1	3.0	60.1	1,002.9	.0	141.0	6.4	1,360.9
1979 .....	65.1	148.9	4.7	327.1	618.6	3.7	59.1	1,013.1	.0	141.2	7.1	1,375.4
1980 .....	63.5	147.3	4.9	307.7	638.7	3.8	56.5	1,011.6	.2	141.9	6.8	1,371.2
1981 .....	65.1	142.2	4.6	351.3	653.3	3.5	53.2	1,066.0	.2	144.5	6.2	1,424.2
1982 .....	68.6	146.2	3.6	349.4	672.7	3.7	53.1	1,082.5	.2	147.5	6.2	1,451.4
1983 .....	62.4	147.8	2.6	329.5	673.4	3.8	51.6	1,060.8	.2	151.5	9.0	1,431.8
1984 .....	65.3	157.4	1.9	342.9	693.7	3.9	51.2	1,093.6	.2	155.9	10.1	1,482.5
1985 .....	64.8	149.9	1.9	292.6	705.7	3.8	50.4	1,054.3	.2	167.2	13.9	1,450.3
1986 .....	63.8	140.9	1.4	271.6	710.2	3.6	45.3	1,032.1	.3	155.8	13.7	1,406.7
1987 .....	67.0	145.6	1.0	319.5	702.3	3.6	43.1	1,069.5	.4	169.9	13.9	1,466.3
1988 .....	60.2	144.6	6.0	284.8	617.2	2.7	41.2	951.9	.4	171.2	32.0	1,360.3
1989 .....	48.7	152.4	.8	245.3	761.7	3.5	41.1	1,052.4	2.2	188.6	20.6	1,464.7
1990 .....	44.3	159.4	.5	245.2	732.4	3.8	37.2	1,019.1	2.6	193.6	19.1	1,438.0
1991 .....	45.9	154.1	.4	232.6	774.5	3.0	34.1	1,044.7	6.0	192.7	18.3	1,461.7
1992 .....	51.7	151.2	1.0	200.6	628.2	3.0	35.6	868.4	8.4	192.5	22.5	1,294.8
1993 .....	38.3	152.9	.7	187.0	612.4	3.5	34.5	838.1	5.8	193.1	18.6	1,246.8
1994 .....	35.0	143.9	.6	198.5	550.7	3.2	29.5	782.6	7.7	190.9	18.2	1,178.2
1995 .....	31.7	149.4	.3	178.4	522.3	3.0	31.9	735.9	8.4	184.8	18.2	1,128.5
1996 .....	23.3	147.3	.2	170.5	513.0	3.1	27.6	714.4	18.7	184.0	20.1	1,107.7
1997 .....	22.5	153.8	.3	180.0	475.7	2.6	39.0	697.6	14.5	183.6	19.2	1,091.2
1998 .....	23.9	140.4	.2	174.5	445.5	3.5	43.0	666.8	5.9	181.4	18.8	1,037.1
1999 .....	21.2	137.4	.1	162.1	444.7	2.4	41.1	650.4	.4	180.0	21.5	1,010.9
2000 .....	22.7	133.8	.2	171.3	403.1	2.5	43.9	621.0	1.8	193.6	20.2	993.1
2001 .....	18.8	133.7	.2	176.9	415.2	3.1	42.5	638.0	4.8	188.4	18.6	1,002.3
2002 .....	16.9	133.7	.2	165.6	472.9	2.8	41.3	682.8	3.2	188.3	18.5	1,043.4
2003 .....	18.1	135.5	.3	190.8	517.9	3.2	46.3	758.4	3.3	193.8	23.2	1,132.3
2004 .....	17.4	135.3	.2	261.4	508.2	2.9	44.1	816.9	3.1	197.1	22.0	1,191.7
2005 .....	17.1	135.7	.4	241.4	492.2	3.4	48.8	786.1	5.6	197.6	24.3	1,166.4
2006 .....	23.5	132.6	.6	209.3	442.6	2.7	48.3	703.6	2.1	196.7	18.2	1,076.4
2007 .....	20.4	131.5	.4	212.9	461.1	2.7	46.5	723.7	2.9	194.9	16.7	1,090.2
2008 .....	20.8	129.6	.4	198.4	525.4	2.3	49.0	775.4	3.6	196.1	17.7	1,143.2
2009 .....	20.3	131.7	.3	166.4	505.7	3.2	48.3	723.9	10.1	191.3	17.7	1,094.8
2010 .....	20.0	130.1	.4	157.8	535.8	2.5	51.3	747.7	3.0	193.7	18.2	1,112.7
2011 .....	18.5	124.7	.9	166.5	533.6	2.0	52.7	755.8	2.7	193.2	19.1	1,114.1
2012 .....	15.9	116.2	.4	148.6	493.5	1.7	50.1	694.4	3.1	187.2	22.5	1,039.3
2013 .....	14.3	122.5	.7	140.0	424.0	1.9	46.6	613.2	2.8	184.7	21.8	959.3
2014 .....	13.5	125.6	.3	133.5	414.3	1.8	44.9	594.8	3.6	182.1	21.9	941.5
2015 .....	12.6	122.2	.3	134.4	418.9	1.8	46.8	602.2	3.7	184.3	20.9	945.8
2016 .....	10.2	115.4	.3	129.7	403.9	1.7	46.5	582.2	3.6	184.5	21.4	917.2
2017 .....	9.1	115.1	.3	135.1	400.1	1.5	46.4	583.5	2.7	181.7	23.0	915.1
2018 .....	6.2	125.8	.3	127.8	383.2	1.7	45.5	558.5	3.0	180.0	23.6	897.0
2019 .....	5.0	131.6	.3	125.4	376.9	1.8	46.6	551.0	2.7	178.1	20.6	889.0

<sup>a</sup> For 1975 and 1976, the U.S. Government's fiscal year was July 1 through June 30. Beginning in 1977, the U.S. Government's fiscal year is October 1 through September 30 (for example, fiscal year 2014 is October 2013 through September 2014).

<sup>b</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, including diesel fuel; and residual fuel oil, including Navy Special.

<sup>d</sup> Liquefied petroleum gases, primarily propane.

<sup>e</sup> Includes E10 (a mixture of 10% ethanol and 90% motor gasoline) and E15 (a mixture of 15% ethanol and 85% motor gasoline).

<sup>f</sup> Other types of fuel used in vehicles and equipment. Primarily includes alternative fuels such as compressed natural gas (CNG); liquefied natural gas (LNG); E85 (a mixture of 85% ethanol and 15% motor gasoline); B20 (a mixture of 20% biodiesel and 80% diesel fuel); B100 (100% biodiesel); hydrogen; and methanol.

<sup>g</sup> Other types of energy used in facilities. Primarily includes chilled water, but also includes small amounts of renewable energy such as wood and solar thermal.

Notes: • Data in this table are developed using conversion factors that often differ from those in Tables A1–A6. • Data include energy consumed at foreign installations and in foreign operations, including aviation and ocean bunkering, primarily by the U.S. Department of Defense. U.S. Government energy use for electricity generation and uranium enrichment is excluded. • Totals may not equal sum of components due to independent rounding.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> (Excel and CSV files) for all annual data beginning in 1975.

Sources: U.S. Department of Energy, Office of Energy Efficiency and Renewable Energy, Federal Energy Management Program. See <http://ctsedweb.ee.doe.gov/Annual/Report/Report.aspx>, "A-5 Historical Federal Energy Consumption and Cost Data by Agency and Energy Type (FY 1975 to Present)".

## Energy Consumption by Sector

**Note 1. Electrical System Energy Losses.** Electrical system energy losses are calculated as the difference between total primary consumption by the electric power sector (see Table 2.6) and the total energy content of electricity retail sales (see Tables 7.6 and A6). Most of these losses occur at steam-electric power plants (conventional and nuclear) in the conversion of heat energy into mechanical energy to turn electric generators. The loss is a thermodynamically necessary feature of the steam-electric cycle. Part of the energy input-to-output losses is a result of imputing fossil energy equivalent inputs for hydroelectric, geothermal, solar thermal, photovoltaic, and wind energy sources. In addition to conversion losses, other losses include power plant use of electricity, transmission and distribution of electricity from power plants to end-use consumers (also called "line losses"), and unaccounted-for electricity. Total losses are allocated to the end-use sectors in proportion to each sector's share of total electricity sales. Overall, about two thirds of total energy input is lost in conversion. Currently, of electricity generated, approximately 5% is lost in plant use and 7% is lost in transmission and distribution.

**Note 2. Other Energy Losses.** Similar to electrical system energy losses, there are also other energy losses from energy consumption not separately identified. There are losses in the production of energy, the transformation of one form of energy to another form of energy, and the distribution and use of energy. For example, there are transformation losses in the process of refining crude oil into usable petroleum products, processing natural gas into marketable dry gas, and in the process of converting energy from the sun into usable energy with solar panels. All uses of primary energy have efficiency losses, usually in the form of heat, when energy is converted to do useful work. Examples include when motor gasoline is burned to move vehicles, when natural gas is burned to heat homes, or in any household appliance that uses electricity. The Lawrence Livermore National Laboratory estimates primary energy losses by end-use sector by applying an end-use efficiency factor to EIA's *Monthly Energy Review* consumption data. <https://flowcharts.llnl.gov/>.

**Note 3. Energy Consumption Data and Surveys.** Most of the data in this section of the Monthly Energy Review (MER) are developed from a group of energy-related surveys, typically called "supply surveys," conducted by the U.S. Energy Information Administration (EIA). Supply surveys are directed to suppliers and marketers of specific energy sources. They measure the quantities of specific energy sources produced, or the quantities supplied to the market, or both. The data obtained from EIA's supply surveys are integrated to yield the summary consumption statistics published in this section (and in Section 1) of the MER.

Users of EIA's energy consumption statistics should be aware of a second group of energy-related surveys, typically called "consumption surveys." Consumption surveys gather information on the types of energy consumed by end users of energy, along with the characteristics of those end users that can be associated with energy use. For example, the "Manufacturing Energy Consumption Survey" belongs to the consumption survey group because it collects information directly from end users (the manufacturing establishments). There are important differences between the supply and consumption surveys that need to be taken into account in any analysis that uses both data sources. For information on those differences, see "Energy Consumption by End-Use Sector, A Comparison of Measures by Consumption and Supply Surveys," DOE/EIA-0533, U.S. Energy Information Administration, Washington, DC, April 6, 1990.

### Table 2.2 Sources

#### *Coal*

1949–2007: Residential sector coal consumption data from Table 6.2 are converted to Btu by multiplying by the residential and commercial sectors coal consumption heat content factors in Table A5.

#### *Natural Gas*

1949–1979: Residential sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4.

1980 forward: Residential sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4. The residential sector portion of supplemental gaseous fuels data in Btu is estimated using the method described in

Note 3, “Supplemental Gaseous Fuels,” at the end of Section 4. Residential sector natural gas (excluding supplemental gaseous fuels) consumption is equal to residential sector natural gas (including supplemental gaseous fuels) consumption minus the residential sector portion of supplemental gaseous fuels.

### ***Petroleum***

1949 forward: Table 3.8a.

### ***Fossil Fuels Total***

1949–2007: Residential sector total fossil fuels consumption is the sum of the residential sector consumption values for coal, natural gas, and petroleum.

2008 forward: Residential sector total fossil fuels consumption is the sum of the residential sector consumption values for natural gas and petroleum.

### ***Renewable Energy***

1949 forward: Table 10.2a.

### ***Total Primary Energy Consumption***

1949 forward: Residential sector total primary energy consumption is the sum of the residential sector consumption values for fossil fuels and renewable energy.

### ***Electricity Retail Sales***

1949 forward: Residential sector electricity retail sales from Table 7.6 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

### ***Electrical System Energy Losses***

1949 forward: Total electrical system energy losses are equal to electric power sector total primary energy consumption from Table 2.6 minus total electricity retail sales from Table 7.6 (converted to Btu by multiplying by the electricity heat content factor in Table A6). Total electrical system energy losses are allocated to the residential sector in proportion to the residential sector’s share of total electricity retail sales from Table 7.6. See Note 1, “Electrical System Energy Losses.”

### ***Total Energy Consumption***

1949 forward: Residential sector total energy consumption is the sum of the residential sector consumption values for total primary energy, electricity retail sales, and electrical system energy losses.

## **Table 2.3 Sources**

### ***Coal***

1949 forward: Commercial sector coal consumption data from Table 6.2 are converted to Btu by multiplying by the residential and commercial sectors coal consumption heat content factors in Table A5.

### ***Natural Gas***

1949–1979: Commercial sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4.

1980 forward: Commercial sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4. The commercial sector portion of supplemental gaseous fuels data in Btu is estimated using the method described in Note 3, “Supplemental Gaseous Fuels,” at the end of Section 4. Commercial sector natural gas (excluding supplemental gaseous fuels) consumption is equal to commercial sector natural gas (including supplemental gaseous fuels) consumption minus the commercial sector portion of supplemental gaseous fuels.

## ***Petroleum***

1949–1992: Table 3.8a.

1993–2008: The commercial sector share of motor gasoline consumption is equal to commercial sector motor gasoline consumption from Table 3.7a divided by motor gasoline product supplied from Table 3.5. Commercial sector fuel ethanol (including denaturant) consumption is equal to total fuel ethanol (including denaturant) consumption from Table 10.3 multiplied by the commercial sector share of motor gasoline consumption. Commercial sector petroleum (excluding biofuels) consumption is equal to commercial sector petroleum (including biofuels) consumption from Table 3.8a minus commercial sector fuel ethanol (including denaturant) consumption.

2009 forward: Commercial sector fuel ethanol (minus denaturant) consumption is equal to total fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the commercial sector share of motor gasoline consumption (see 1993–2008 sources above). Commercial sector petroleum (excluding biofuels) consumption is equal to commercial sector petroleum (including biofuels) consumption from Table 3.8a minus commercial sector fuel ethanol (minus denaturant) consumption.

## ***Fossil Fuels Total***

1949 forward: Commercial sector total fossil fuels consumption is the sum of the commercial sector consumption values for coal, natural gas, and petroleum.

## ***Renewable Energy***

1949 forward: Table 10.2a.

## ***Total Primary Energy Consumption***

1949 forward: Commercial sector total primary energy consumption is the sum of the commercial sector consumption values for fossil fuels and renewable energy.

## ***Electricity Retail Sales***

1949 forward: Commercial sector electricity retail sales from Table 7.6 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

## ***Electrical System Energy Losses***

1949 forward: Total electrical system energy losses are equal to electric power sector total primary energy consumption from Table 2.6 minus total electricity retail sales from Table 7.6 (converted to Btu by multiplying by the electricity heat content factor in Table A6). Total electrical system energy losses are allocated to the commercial sector in proportion to the commercial sector's share of total electricity retail sales from Table 7.6. See Note 1, "Electrical System Energy Losses."

## ***Total Energy Consumption***

1949 forward: Commercial sector total energy consumption is the sum of the commercial sector consumption values for total primary energy, electricity retail sales, and electrical system energy losses.

## **Table 2.4 Sources**

### ***Coal***

1949 forward: Coke plants coal consumption from Table 6.2 is converted to Btu by multiplying by the coke plants coal consumption heat content factors in Table A5. Other industrial coal consumption from Table 6.2 is converted to Btu by multiplying by the other industrial coal consumption heat content factors in Table A5. Industrial sector coal consumption is equal to coke plants coal consumption and other industrial coal consumption.

### ***Natural Gas***

1949–1979: Industrial sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4.

1980 forward: Industrial sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4. The industrial sector portion of supplemental gaseous fuels data in Btu is estimated using the method described in Note 3, "Supplemental Gaseous Fuels," at the end of Section 4. Industrial sector natural gas (excluding supplemental gaseous fuels) consumption is equal to industrial sector natural gas (including supplemental gaseous fuels) consumption minus the industrial sector portion of supplemental gaseous fuels.

### ***Petroleum***

1949–1992: Table 3.8b.

1993–2008: The industrial sector share of motor gasoline consumption is equal to industrial sector motor gasoline consumption from Table 3.7b divided by motor gasoline product supplied from Table 3.5. Industrial sector fuel ethanol (including denaturant) consumption is equal to total fuel ethanol (including denaturant) consumption from Table 10.3 multiplied by the industrial sector share of motor gasoline consumption. Industrial sector petroleum (excluding biofuels) consumption is equal to industrial sector petroleum (including biofuels) consumption from Table 3.8b minus industrial sector fuel ethanol (including denaturant) consumption.

2009 forward: Industrial sector fuel ethanol (minus denaturant) consumption is equal to total fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the industrial sector share of motor gasoline consumption (see 1993–2008 sources above). Industrial sector petroleum (excluding biofuels) consumption is equal to industrial sector petroleum (including biofuels) consumption from Table 3.8b minus industrial sector fuel ethanol (minus denaturant) consumption.

### ***Coal Coke Net Imports***

1949 forward: Coal coke net imports are equal to coal coke imports from Table 1.4a minus coal coke exports from Table 1.4b.

### ***Fossil Fuels Total***

1949 forward: Industrial sector total fossil fuels consumption is the sum of the industrial sector consumption values for coal, natural gas, and petroleum, plus coal coke net imports.

### ***Renewable Energy***

1949 forward: Table 10.2b.

### ***Total Primary Energy Consumption***

1949 forward: Industrial sector total primary energy consumption is the sum of the industrial sector consumption values for fossil fuels and renewable energy.

### ***Electricity Retail Sales***

1949 forward: Industrial sector electricity retail sales from Table 7.6 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

### ***Electrical System Energy Losses***

1949 forward: Total electrical system energy losses are equal to electric power sector total primary energy consumption from Table 2.6 minus total electricity retail sales from Table 7.6 (converted to Btu by multiplying by the electricity heat content factor in Table A6). Total electrical system energy losses are allocated to the industrial sector in proportion to the industrial sector's share of total electricity retail sales from Table 7.6. See Note 1, "Electrical System Energy Losses."

### ***Total Energy Consumption***

1949 forward: Industrial sector total energy consumption is the sum of the industrial sector consumption values for total primary energy, electricity retail sales, and electrical system energy losses.

## Table 2.5 Sources

### *Coal*

1949–1977: Transportation sector coal consumption data from Table 6.2 are converted to Btu by multiplying by the other industrial sector coal consumption heat content factors in Table A5.

### *Natural Gas*

1949 forward: Transportation sector natural gas consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas end-use sectors consumption heat content factors in Table A4.

### *Petroleum*

1949–1992: Table 3.8c.

1993–2008: The transportation sector share of motor gasoline consumption is equal to transportation sector motor gasoline consumption from Table 3.7c divided by motor gasoline product supplied from Table 3.5. Transportation sector fuel ethanol (including denaturant) consumption is equal to total fuel ethanol (including denaturant) consumption from Table 10.3 multiplied by the transportation sector share of motor gasoline consumption. Transportation sector petroleum (excluding biofuels) consumption is equal to transportation sector petroleum (including biofuels) consumption from Table 3.8c minus transportation sector fuel ethanol (including denaturant) consumption.

2009–2011: Transportation sector fuel ethanol (minus denaturant) consumption is equal to total fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the transportation sector share of motor gasoline consumption (see 1993–2008 sources above). Transportation sector petroleum (excluding biofuels) consumption is equal to: transportation sector petroleum (including biofuels) consumption from Table 3.8c; minus transportation sector fuel ethanol (minus denaturant) consumption; minus biodiesel consumption (calculated using biodiesel data from U.S. Energy Information Administration (EIA), EIA-22M, "Monthly Biodiesel Production Survey"; and biomass-based diesel fuel data from EIA-810, "Monthly Refinery Report," EIA-812, "Monthly Product Pipeline Report," and EIA-815, "Monthly Bulk Terminal and Blender Report" (the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1)); minus other renewable diesel fuel and other renewable fuels consumption from Table 10.4.

2012–2020: Transportation sector fuel ethanol (minus denaturant) consumption is equal to total fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the transportation sector share of motor gasoline consumption (see 1993–2008 sources above). Transportation sector petroleum (excluding biofuels) consumption is equal to: transportation sector petroleum (including biofuels) consumption from Table 3.8c; minus transportation sector fuel ethanol (minus denaturant) consumption; minus biodiesel consumption from Table 10.4; minus other renewable diesel fuel and other renewable fuels consumption from Table 10.4.

2021 forward: Transportation sector fuel ethanol (minus denaturant) consumption is equal to total fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the transportation sector share of motor gasoline consumption (see 1993–2008 sources above). Transportation sector petroleum (excluding biofuels) consumption is equal to: transportation sector petroleum (including biofuels) consumption from Table 3.8c; minus transportation sector fuel ethanol (minus denaturant) consumption; minus biodiesel refinery and blender net inputs from EIA, EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report (data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1); minus other renewable diesel fuel and other renewable fuels consumption from Table 10.4; minus renewable fuels except fuel ethanol products supplied from U.S. Energy Information Administration (EIA), *Petroleum Supply Monthly* (data are converted to Btu by multiplying by the appropriate heat content factors in Table A1).

### *Fossil Fuels Total*

1949–1977: Transportation sector total fossil fuels consumption is the sum of the transportation sector consumption values for coal, natural gas, and petroleum.

1978 forward: Transportation sector total fossil fuels consumption is the sum of the transportation sector consumption values for natural gas and petroleum.



## ***Renewable Energy***

1981 forward: Table 10.2b.

### **Total Primary Energy Consumption**

1949–1980: Transportation sector total primary energy consumption is equal to transportation sector fossil fuels consumption.

1981 forward: Transportation sector total primary energy consumption is the sum of the transportation sector consumption values for fossil fuels and renewable energy.

## ***Electricity Retail Sales***

1949 forward: Transportation sector electricity retail sales from Table 7.6 are converted to Btu by multiplying by the electricity heat content factor in Table A6.

## ***Electrical System Energy Losses***

1949 forward: Total electrical system energy losses are equal to electric power sector total primary energy consumption from Table 2.6 minus total electricity retail sales from Table 7.6 (converted to Btu by multiplying by the electricity heat content factor in Table A6). Total electrical system energy losses are allocated to the transportation sector in proportion to the transportation sector's share of total electricity retail sales from Table 7.6. See Note 1, "Electrical System Energy Losses."

## ***Total Energy Consumption***

1949 forward: Transportation sector total energy consumption is the sum of the transportation sector consumption values for total primary energy, electricity retail sales, and electrical system energy losses.

## **Table 2.6 Sources**

### ***Coal***

1949 forward: Electric power sector coal consumption data from Table 6.2 are converted to Btu by multiplying by the electric power sector coal consumption heat content factors in Table A5.

### ***Natural Gas***

1949–1979: Electric power sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas electric power sector consumption heat content factors in Table A4.

1980 forward: Electric power sector natural gas (including supplemental gaseous fuels) consumption data from Table 4.3 are converted to Btu by multiplying by the natural gas electric power sector consumption heat content factors in Table A4. The electric power sector portion of supplemental gaseous fuels data in Btu is estimated using the method described in Note 3, "Supplemental Gaseous Fuels," at the end of Section 4. Electric power sector natural gas (excluding supplemental gaseous fuels) consumption is equal to electric power sector natural gas (including supplemental gaseous fuels) consumption minus the electric power sector portion of supplemental gaseous fuels.

### ***Petroleum***

1949 forward: Table 3.8c.

### ***Fossil Fuels Total***

1949 forward: Electric power sector total fossil fuels consumption is the sum of the electric power sector consumption values for coal, natural gas, and petroleum.

### ***Nuclear Electric Power***

1949 forward: Nuclear electricity net generation data from Table 7.2a are converted to Btu by multiplying by the nuclear heat rate factors in Table A6.

### ***Renewable Energy***

1949 forward: Table 10.2c.

### ***Electricity Net Imports***

1949 forward: Electricity net imports are equal to electricity imports from Table 1.4a minus electricity exports from Table 1.4b.

### ***Total Primary Energy Consumption***

1949 forward: Electric power sector total primary energy consumption is the sum of the electric power sector consumption values for fossil fuels, nuclear electric power, and renewable energy, plus electricity net imports.


## 3. Petroleum

---


**Figure 3.1 Petroleum Overview**

(Million Barrels Per Day)


Overview, 1949–2020




Crude Oil and Natural Gas Liquids Field Production, 1949–2020



Overview, January–April



Total Field Production [a], Monthly



[a] Crude oil, including lease condensate, and natural gas liquids field production.

[b] Includes lease condensate.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
Source: Table 3.1.

**Table 3.1 Petroleum Overview**  
(Thousand Barrels per Day)

	Field Production <sup>a</sup>					Renewable Fuels and Oxygenates <sup>e</sup>	Processing Gain <sup>f</sup>	Trade			Stock Change <sup>i</sup>	Adjustments <sup>c,j</sup>	Petroleum Products Supplied
	Crude Oil <sup>b,c</sup>			Natural Gas Liquids	Total <sup>c</sup>			Im-ports <sup>g</sup>	Ex-ports	Net Imports <sup>h</sup>			
	48 States <sup>d</sup>	Alaska	Total										
1950 Average .....	5,407	0	5,407	499	5,906	NA	2	850	305	545	-56	-51	6,458
1955 Average .....	6,807	0	6,807	771	7,578	NA	34	1,248	368	880	(s)	-37	8,455
1960 Average .....	7,034	2	7,035	929	7,965	NA	146	1,815	202	1,613	-83	-8	9,797
1965 Average .....	7,774	30	7,804	1,210	9,014	NA	220	2,468	187	2,281	-8	-10	11,512
1970 Average .....	9,408	229	9,637	1,660	11,297	NA	359	3,419	259	3,161	103	-16	14,697
1975 Average .....	8,183	191	8,375	1,633	10,007	NA	460	6,056	209	5,846	32	41	16,322
1980 Average .....	6,980	1,617	8,597	1,573	10,170	NA	597	6,909	544	6,365	140	64	17,056
1985 Average .....	7,146	1,825	8,971	1,609	10,581	NA	557	5,067	781	4,286	-103	200	15,726
1990 Average .....	5,582	1,773	7,355	1,559	8,914	NA	683	8,018	857	7,161	107	338	16,988
1995 Average .....	5,076	1,484	6,560	1,762	8,322	NA	774	8,835	949	7,886	-246	496	17,725
2000 Average .....	4,851	970	5,822	1,911	7,733	NA	948	11,459	1,040	10,419	-69	532	19,701
2005 Average .....	4,320	864	5,184	1,717	6,901	NA	989	13,714	1,165	12,549	<sup>k</sup> 146	509	20,802
2006 Average .....	4,345	741	5,086	1,739	6,825	NA	994	13,707	1,317	12,390	59	537	20,687
2007 Average .....	4,352	722	5,074	1,783	6,857	NA	996	13,468	1,433	12,036	-152	640	20,680
2008 Average .....	4,317	683	5,000	1,784	6,783	NA	993	12,915	1,802	11,114	195	803	19,498
2009 Average .....	4,711	645	5,357	1,910	7,267	746	979	11,691	2,024	9,667	107	221	18,771
2010 Average .....	4,885	600	5,484	2,074	7,558	907	1,068	11,793	2,353	9,441	42	246	19,178
2011 Average .....	5,106	561	5,667	2,216	7,883	1,016	1,076	11,436	2,986	8,450	-138	332	18,896
2012 Average .....	5,995	526	6,521	2,408	8,929	964	1,059	10,598	3,205	7,393	151	289	18,482
2013 Average .....	6,979	515	7,494	2,606	10,100	1,002	1,087	9,859	3,621	6,237	-138	402	18,967
2014 Average .....	8,293	496	8,789	3,015	11,804	1,055	1,081	9,241	4,176	5,065	267	363	19,100
2015 Average .....	8,964	483	9,446	3,342	12,789	1,095	1,062	9,449	4,738	4,711	431	306	19,532
2016 Average .....	8,361	490	8,852	3,509	12,361	1,158	1,118	10,055	5,261	4,795	125	385	19,692
2017 Average .....	8,877	495	9,371	3,783	13,154	1,198	1,111	10,144	6,376	3,768	-364	356	19,952
2018 Average .....	10,485	479	10,964	4,369	15,333	1,234	1,138	9,943	7,601	2,341	44	509	20,512
2019 January .....	11,369	496	11,865	4,554	16,419	1,112	1,109	9,768	7,982	1,786	246	435	20,615
February .....	11,191	488	11,679	4,713	16,392	1,115	1,007	8,671	8,219	452	-597	722	20,284
March .....	11,456	481	11,937	4,729	16,667	1,087	1,038	8,905	7,946	959	-100	324	20,176
April .....	11,659	475	12,135	4,790	16,925	1,138	1,065	9,525	8,382	1,143	596	658	20,333
May .....	11,689	474	12,163	4,840	17,003	1,151	1,064	9,893	8,238	1,655	1,281	795	20,387
June .....	11,633	455	12,088	4,795	16,882	1,159	1,076	9,297	8,576	720	-99	718	20,654
July .....	11,371	448	11,819	4,707	16,526	1,155	1,066	9,601	8,084	1,517	158	629	20,735
August .....	12,043	382	12,425	4,766	17,191	1,133	1,099	9,387	8,438	949	-271	516	21,158
September .....	12,046	449	12,495	4,990	17,485	1,071	1,018	8,712	8,672	40	-77	559	20,248
October .....	12,198	475	12,673	5,022	17,695	1,093	1,014	8,599	9,039	-440	-532	821	20,714
November .....	12,376	484	12,860	4,995	17,854	1,129	1,131	8,103	8,741	-638	-284	976	20,736
December .....	12,321	481	12,802	4,992	17,794	1,157	1,133	9,159	9,331	-171	-44	486	20,443
Average .....	11,782	466	12,248	4,825	17,073	1,125	1,069	9,141	8,471	670	28	635	20,543
2020 January .....	<sup>E</sup> 12,272	<sup>E</sup> 482	<sup>E</sup> 12,755	5,145	<sup>E</sup> 17,900	1,161	1,136	8,572	9,177	-605	550	863	19,905
February .....	<sup>E</sup> 12,269	<sup>E</sup> 477	<sup>E</sup> 12,746	4,965	<sup>E</sup> 17,711	1,142	939	8,457	9,983	-1,526	-664	908	19,839
March .....	<sup>E</sup> 12,268	<sup>E</sup> 470	<sup>E</sup> 12,737	5,253	<sup>E</sup> 17,990	1,049	978	8,345	9,621	-1,276	1,334	876	18,284
April .....	<sup>E</sup> 11,547	<sup>E</sup> 463	<sup>E</sup> 12,010	4,934	<sup>E</sup> 16,944	668	767	7,236	8,452	-1,216	2,654	181	14,691
May .....	<sup>E</sup> 9,615	<sup>E</sup> 404	<sup>E</sup> 10,019	4,745	<sup>E</sup> 14,764	781	807	7,757	6,818	939	1,242	54	16,103
June .....	<sup>E</sup> 10,081	<sup>E</sup> 361	<sup>E</sup> 10,442	5,197	<sup>E</sup> 15,639	969	873	8,367	7,692	675	1,168	447	17,435
July .....	<sup>E</sup> 10,529	<sup>E</sup> 444	<sup>E</sup> 10,973	5,369	<sup>E</sup> 16,342	1,033	936	7,846	8,412	-566	-57	522	18,323
August .....	<sup>E</sup> 10,140	<sup>E</sup> 444	<sup>E</sup> 10,584	5,325	<sup>E</sup> 15,909	1,025	924	7,465	8,498	-1,033	-756	858	18,439
September .....	<sup>E</sup> 10,429	<sup>E</sup> 442	<sup>E</sup> 10,870	5,309	<sup>E</sup> 16,179	1,036	946	7,543	8,376	-833	-650	330	18,307
October .....	<sup>E</sup> 9,979	<sup>E</sup> 459	<sup>E</sup> 10,439	5,299	<sup>E</sup> 15,738	1,053	925	7,372	8,356	-984	-1,288	605	18,624
November .....	<sup>E</sup> 10,704	<sup>E</sup> 464	<sup>E</sup> 11,168	5,323	<sup>E</sup> 16,491	1,096	934	7,616	7,823	-207	109	498	18,702
December .....	<sup>RE</sup> 10,625	<sup>E</sup> 463	<sup>RE</sup> 11,088	5,060	<sup>RE</sup> 16,148	1,073	917	7,728	8,933	-1,205	-1,456	<sup>R</sup> 407	18,796
Average .....	<sup>RE</sup> 10,866	<sup>E</sup> 448	<sup>RE</sup> 11,313	5,161	<sup>RE</sup> 16,475	1,007	924	7,857	8,508	-651	180	<sup>R</sup> 546	18,120
2021 January .....	<sup>RE</sup> 10,601	<sup>RE</sup> 458	<sup>RE</sup> 11,059	5,188	<sup>RE</sup> 16,248	1,064	891	7,915	8,729	-814	-460	<sup>R</sup> 746	18,595
February .....	<sup>RE</sup> 9,405	<sup>RE</sup> 457	<sup>RE</sup> 9,862	<sup>R</sup> 4,215	<sup>RE</sup> 14,077	<sup>R</sup> 938	<sup>R</sup> 765	<sup>R</sup> 7,648	<sup>R</sup> 7,661	<sup>R</sup> -13	<sup>R</sup> -1,272	<sup>R</sup> 405	<sup>R</sup> 17,444
March .....	<sup>E</sup> 10,513	<sup>E</sup> 455	<sup>E</sup> 10,968	<sup>E</sup> 5,060	<sup>E</sup> 16,028	<sup>E</sup> 949	<sup>E</sup> 923	<sup>E</sup> 8,354	<sup>E</sup> 7,432	<sup>E</sup> 922	<sup>E</sup> 315	<sup>E</sup> 710	<sup>E</sup> 19,217
April .....	<sup>E</sup> 10,499	<sup>E</sup> 451	<sup>E</sup> 10,950	<sup>E</sup> 5,151	<sup>E</sup> 16,101	<sup>E</sup> 1,076	<sup>E</sup> 971	<sup>E</sup> 8,321	<sup>E</sup> 8,069	<sup>E</sup> 252	<sup>E</sup> -545	<sup>E</sup> 752	<sup>E</sup> 19,698
4-Month Average ...	<sup>E</sup> 10,274	<sup>E</sup> 455	<sup>E</sup> 10,729	<sup>E</sup> 4,919	<sup>E</sup> 15,648	<sup>E</sup> 1,008	<sup>E</sup> 890	<sup>E</sup> 8,068	<sup>E</sup> 7,980	<sup>E</sup> 88	<sup>E</sup> -471	<sup>E</sup> 659	<sup>E</sup> 18,763
2020 4-Month Average ...	<sup>E</sup> 12,091	<sup>E</sup> 473	<sup>E</sup> 12,563	5,077	<sup>E</sup> 17,641	1,006	957	8,155	9,304	-1,149	981	708	18,181
2019 4-Month Average ...	11,423	485	11,908	4,695	16,603	1,113	1,056	9,228	8,128	1,100	47	529	20,354

<sup>a</sup> Crude oil production on leases, and natural gas processing plant production of natural gas liquids (ethane, propane, normal butane, isobutane, and natural gasoline). Through 1980, also includes natural gas processing plant production of finished petroleum products (aviation gasoline, distillate fuel oil, jet fuel, kerosene, motor gasoline, special naphthas, and miscellaneous products).

<sup>b</sup> Includes lease condensate.

<sup>c</sup> Once a month, data for crude oil production, total field production, and adjustments are revised going back as far as the data year of the U.S. Energy Information Administration's (EIA) last published *Petroleum Supply Annual* (PSA)—these revisions are released at the same time as EIA's *Petroleum Supply Monthly*. Once a year, data for these series are revised going back as far as 10 years—these revisions are released at the same time as the PSA.

<sup>d</sup> United States excluding Alaska and Hawaii.

<sup>e</sup> Renewable fuels and oxygenate plant net production of fuel ethanol, biodiesel, other renewable diesel fuel, other renewable fuels, natural gasoline, finished motor gasoline, and motor gasoline blending components. For 2009–2018, also includes oxygenates (excluding fuel ethanol).

<sup>f</sup> Refinery and blender net production minus refinery and blender net inputs. See Table 3.2.

<sup>g</sup> Includes Strategic Petroleum Reserve imports. See Table 3.3b.

<sup>h</sup> Net imports equal imports minus exports.

<sup>i</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase. The current month stock change estimate is based on the change from the previous month's estimate, rather than the stocks values shown in Table 3.4. Includes crude oil stocks in the Strategic Petroleum Reserve, but excludes distillate fuel oil stocks in the Northeast Home Heating Oil Reserve. See Table 3.4.

<sup>j</sup> An adjustment for crude oil, hydrogen, oxygenates, renewable fuels, other hydrocarbons, motor gasoline blending components, finished motor gasoline, and distillate fuel oil. See EIA's *Petroleum Supply Monthly*, Appendix B, "PSM Explanatory Notes," for further information.

<sup>k</sup> Derived from the 2004 petroleum stocks value that excludes crude oil stocks on leases (1,628 million barrels), not the 2004 petroleum stocks value that includes crude oil stocks on leases (1,645 million barrels).

<sup>R</sup>=Revised. <sup>E</sup>=Estimate. <sup>NA</sup>=Not available. <sup>(s)</sup>=Less than 500 barrels per day and greater than -500 barrels per day.

Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 3.2 Refinery and Blender Net Inputs and Net Production**

(Million Barrels per Day)


Net Inputs and Net Production, 1949–2020




Net Production, Selected Products, 1949–2020



Net Inputs and Net Production, Monthly



Net Production, Selected Products, Monthly



[a] Includes lease condensate.

[b] Natural gas liquids and other liquids.

[c] Beginning in 1993, includes fuel ethanol blended into motor gasoline.

[d] Beginning in 2009, includes renewable diesel fuel (including biodiesel)

blended into distillate fuel oil.

[e] Beginning in 2005, includes kerosene-type jet fuel only.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Source: Table 3.2.

**Table 3.2 Refinery and Blender Net Inputs and Net Production**  
(Thousand Barrels per Day)


	Refinery and Blender Net Inputs <sup>a</sup>				Refinery and Blender Net Production <sup>b</sup>									
	Crude Oil <sup>c</sup>	Natural Gas Liquids <sup>d</sup>	Other Liquids <sup>e</sup>	Total	Distillate Fuel Oil <sup>f</sup>	Hydrocarbon Gas Liquids			Total <sup>h</sup>	Jet Fuel <sup>i</sup>	Motor Gasoline <sup>j</sup>	Residual Fuel Oil	Other Products <sup>k</sup>	Total
						Propane/Propylene								
						Propane	Propylene	Total <sup>g</sup>						
1950 Average .....	5,739	259	19	6,018	1,093	NA	NA	NA	80	( <sup>i</sup> )	2,735	1,165	947	6,019
1955 Average .....	7,480	345	32	7,857	1,651	NA	NA	NA	119	155	3,648	1,152	1,166	7,891
1960 Average .....	8,067	455	61	8,583	1,823	NA	NA	NA	212	241	4,126	908	1,420	8,729
1965 Average .....	9,043	618	88	9,750	2,096	NA	NA	NA	293	523	4,507	736	1,814	9,970
1970 Average .....	10,870	763	121	11,754	2,454	E 184	E 55	239	345	827	5,699	706	2,082	12,113
1975 Average .....	12,442	710	72	13,225	2,653	E 179	E 60	238	311	871	6,518	1,235	2,097	13,685
1980 Average .....	13,481	462	81	14,025	2,661	E 202	E 72	273	330	999	6,492	1,580	2,559	14,622
1985 Average .....	12,002	509	681	13,192	2,686	E 223	E 72	295	391	1,189	6,419	882	2,183	13,750
1990 Average .....	13,409	467	713	14,589	2,925	299	105	404	499	1,488	6,959	950	2,452	15,272
1995 Average .....	13,973	471	775	15,220	3,155	352	151	503	654	1,416	7,459	788	2,522	15,994
2000 Average .....	15,067	380	849	16,295	3,580	366	217	583	705	1,606	7,951	696	2,705	17,243
2005 Average .....	15,220	441	1,149	16,811	3,954	311	229	540	573	1,546	8,318	628	2,782	17,800
2006 Average .....	15,242	501	1,238	16,981	4,040	302	241	543	627	1,481	8,364	635	2,827	17,975
2007 Average .....	15,156	505	1,337	16,999	4,133	330	232	562	655	1,448	8,358	673	2,728	17,994
2008 Average .....	14,648	485	2,019	17,153	4,294	312	207	519	630	1,493	8,548	620	2,561	18,146
2009 Average .....	14,336	485	2,082	16,904	4,048	291	246	537	623	1,396	8,786	598	2,431	17,882
2010 Average .....	14,724	442	2,219	17,385	4,223	282	278	560	659	1,418	9,059	585	2,509	18,452
2011 Average .....	14,806	490	2,300	17,596	4,492	270	282	552	619	1,449	9,058	537	2,518	18,673
2012 Average .....	14,999	509	1,997	17,505	4,550	276	277	553	630	1,471	8,926	501	2,487	18,564
2013 Average .....	15,312	496	2,211	18,019	4,733	284	281	564	623	1,499	9,234	467	2,550	19,106
2014 Average .....	15,848	511	2,214	18,574	4,916	306	281	587	653	1,541	9,570	435	2,537	19,654
2015 Average .....	16,188	517	2,119	18,824	4,983	283	276	559	615	1,590	9,754	417	2,527	19,886
2016 Average .....	16,187	536	2,238	18,961	4,834	307	280	587	632	1,650	9,995	418	2,550	20,079
2017 Average .....	16,590	566	2,031	19,187	5,024	307	285	592	628	1,702	9,954	427	2,563	20,298
2018 Average .....	16,969	575	2,011	19,555	5,168	301	293	594	634	1,806	10,061	425	2,599	20,693
2019 January .....	16,783	675	1,415	18,873	5,250	297	292	589	368	1,771	9,747	398	2,448	19,981
February .....	15,846	592	1,935	18,372	4,905	257	289	545	429	1,689	9,744	309	2,303	19,379
March .....	15,935	512	2,580	19,027	4,968	288	261	549	629	1,728	10,060	357	2,323	20,065
April .....	16,341	486	2,482	19,309	5,059	295	272	567	804	1,728	10,020	389	2,374	20,374
May .....	16,719	460	2,519	19,699	5,212	295	283	577	867	1,729	10,229	363	2,362	20,763
June .....	17,236	431	2,469	20,136	5,351	300	290	591	859	1,883	10,236	430	2,454	21,212
July .....	17,175	448	2,593	20,216	5,246	292	286	579	852	1,922	10,240	390	2,632	21,282
August .....	17,297	481	2,580	20,358	5,266	295	284	579	806	1,924	10,437	410	2,613	21,456
September .....	16,403	601	2,178	19,182	5,035	272	282	553	613	1,799	9,916	383	2,454	20,199
October .....	15,681	712	2,357	18,749	4,794	252	281	533	409	1,653	10,259	340	2,308	19,764
November .....	16,482	744	1,972	19,197	5,231	294	287	581	272	1,833	10,229	314	2,449	20,328
December .....	16,793	716	1,735	19,244	5,309	316	280	596	348	1,890	9,992	249	2,589	20,377
Average .....	16,563	571	2,237	19,371	5,137	288	282	570	606	1,796	10,095	361	2,444	20,439
2020 January .....	16,231	699	1,608	18,538	5,085	297	269	566	388	1,855	9,626	229	2,491	19,674
February .....	15,867	638	1,793	18,298	4,812	280	234	514	381	1,666	9,742	229	2,407	19,237
March .....	15,226	498	1,363	17,088	4,951	279	245	525	621	1,359	8,575	232	2,328	18,067
April .....	12,786	318	1,134	14,238	5,101	230	264	494	683	619	6,352	145	2,106	15,005
May .....	12,958	336	1,660	14,953	4,821	234	258	492	671	505	7,477	167	2,118	15,760
June .....	13,732	402	2,202	16,336	4,580	249	255	504	710	731	8,745	239	2,204	17,209
July .....	14,338	456	2,283	17,077	4,842	265	258	522	732	836	9,026	225	2,350	18,012
August .....	14,151	422	2,675	17,249	4,823	274	252	527	712	851	9,312	192	2,282	18,173
September .....	13,573	536	2,263	16,372	4,493	260	270	530	556	800	9,090	165	2,214	17,318
October .....	13,445	587	2,057	16,089	4,213	258	280	538	410	821	9,252	163	2,154	17,013
November .....	14,124	637	1,477	16,238	4,522	275	285	560	333	1,062	8,882	153	2,219	17,171
December .....	14,140	567	1,652	16,360	4,636	266	292	558	347	1,125	8,810	147	2,212	17,276
Average .....	14,212	508	1,848	16,569	4,740	264	264	528	546	1,018	8,741	191	2,257	17,492
2021 January .....	14,525	588	1,058	16,170	4,554	259	296	555	367	1,226	8,520	169	2,226	17,062
February .....	R 12,374	R 479	R 1,935	R 14,787	R 3,766	R 219	R 245	R 464	343	R 949	R 8,396	R 188	R 1,910	R 15,552
March .....	E 14,156	F 481	RE 2,305	RF 16,941	E 4,439	NA	NA	RE 618	RF 582	E 1,057	E 9,172	E 215	RE 2,399	RE 17,865
April .....	E 15,020	F 449	E 2,362	F 17,830	E 4,585	NA	NA	E 614	F 788	E 1,214	E 9,638	E 190	E 2,386	E 18,802
4-Month Average .....	E 14,052	E 500	E 1,910	E 16,462	E 4,348	NA	NA	E 565	E 522	E 1,115	E 8,939	E 191	E 2,237	E 17,352
2020 4-Month Average .....	15,032	539	1,472	17,043	4,989	272	253	525	519	1,376	8,573	209	2,334	18,000
2019 4-Month Average .....	16,235	566	2,104	18,905	5,049	285	278	563	558	1,730	9,895	364	2,363	19,961

<sup>a</sup> See "Refinery and Blender Net Inputs" in Glossary.  
<sup>b</sup> See "Refinery and Blender Net Production" in Glossary.  
<sup>c</sup> Includes lease condensate.  
<sup>d</sup> Ethane, propane, normal butane, isobutane, and natural gasoline (pentanes plus).  
<sup>e</sup> Unfinished oils (net). Beginning in 1981, also includes aviation gasoline blending components (net) and motor gasoline blending components (net). Beginning in 1993, also includes fuel ethanol. Beginning in 2009, also includes renewable fuels (excluding fuel ethanol), hydrogen, and other hydrocarbons. For 2009–2018, also includes oxygenates (excluding fuel ethanol).  
<sup>f</sup> Beginning in 2009, includes biodiesel and other renewable diesel fuel blended into distillate fuel oil. Beginning in 2021, also includes renewable heating oil blended into distillate fuel oil.  
<sup>g</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures."  
<sup>h</sup> Ethane, propane, normal butane, isobutane, and refinery olefins (ethylene, propylene, butylene, and isobutylene).  
<sup>i</sup> Beginning in 1965, includes kerosene-type jet fuel. (Through 1964, kerosene-type jet fuel is included with kerosene in "Other Products.") For


1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other Products.")  
<sup>j</sup> Finished motor gasoline. Through 1963, also includes aviation gasoline and special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.  
<sup>k</sup> Asphalt and road oil, kerosene, lubricants, petrochemical feedstocks, petroleum coke, still gas (refinery gas), waxes, and miscellaneous products. Through 1964, also includes kerosene-type jet fuel. Beginning in 1964, also includes finished aviation gasoline and special naphthas. Beginning in 2005, also includes naphtha-type jet fuel.  
R=Revised. E=Estimate. F=Forecast. NA=Not available.  
Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
Sources: See end of section.

**Figure 3.3a Petroleum Trade: Overview**


Overview, February 2021



Imports From OPEC and Persian Gulf as Share of Total Imports, 1960–2020



Net Imports as Share of Products Supplied, 1949–2020



Note: OPEC=Organization of the Petroleum Exporting Countries.  
(s)=Less than 0.05 thousand barrels per day and greater than -0.05 thousand barrels per day.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
Source: Table 3.3a.



Table 3.3a Petroleum Trade: Overview

	Imports From Persian Gulf <sup>a</sup>	Imports From OPEC <sup>b</sup>	Imports	Exports	Net Imports	Products Supplied	As Share of Products Supplied				As Share of Total Imports	
							Imports From Persian Gulf <sup>a</sup>	Imports From OPEC <sup>b</sup>	Imports	Net Imports	Imports From Persian Gulf <sup>a</sup>	Imports From OPEC <sup>b</sup>
							Thousand Barrels per Day				Percent	
1950 Average .....	NA	NA	850	305	545	6,458	NA	NA	13.2	8.4	NA	NA
1955 Average .....	NA	NA	1,248	368	880	8,455	NA	NA	14.8	10.4	NA	NA
1960 Average .....	326	1,233	1,815	202	1,613	9,797	3.3	12.6	18.5	16.5	17.9	68.0
1965 Average .....	359	1,439	2,468	187	2,281	11,512	3.1	12.5	21.4	19.8	14.5	58.3
1970 Average .....	184	1,294	3,419	259	3,161	14,697	1.3	8.8	23.3	21.5	5.4	37.8
1975 Average .....	1,165	3,601	6,056	209	5,846	16,322	7.1	22.1	37.1	35.8	19.2	59.5
1980 Average .....	1,519	4,300	6,909	544	6,365	17,056	8.9	25.2	40.5	37.3	22.0	62.2
1985 Average .....	311	1,830	5,067	781	4,286	15,726	2.0	11.6	32.2	27.3	6.1	36.1
1990 Average .....	1,966	4,296	8,018	857	7,161	16,988	11.6	25.3	47.2	42.2	24.5	53.6
1995 Average .....	1,573	4,002	8,835	949	7,886	17,725	8.9	22.6	49.8	44.5	17.8	45.3
2000 Average .....	2,488	5,203	11,459	1,040	10,419	19,701	12.6	26.4	58.2	52.9	21.7	45.4
2005 Average .....	2,334	5,587	13,714	1,165	12,549	20,802	11.2	26.9	65.9	60.3	17.0	40.7
2006 Average .....	2,211	5,517	13,707	1,317	12,390	20,687	10.7	26.7	66.3	59.9	16.1	40.2
2007 Average .....	2,163	5,980	13,468	1,433	12,036	20,680	10.5	28.9	65.1	58.2	16.1	44.4
2008 Average .....	2,370	5,954	12,915	1,802	11,114	19,498	12.2	30.5	66.2	57.0	18.4	46.1
2009 Average .....	1,689	4,776	11,691	2,024	9,667	18,771	9.0	25.4	62.3	51.5	14.4	40.9
2010 Average .....	1,711	4,906	11,793	2,353	9,441	19,178	8.9	25.6	61.5	49.2	14.5	41.6
2011 Average .....	1,861	4,555	11,436	2,986	8,450	18,896	9.9	24.1	60.5	44.7	16.3	39.8
2012 Average .....	2,156	4,271	10,598	3,205	7,393	18,482	11.7	23.1	57.3	40.0	20.3	40.3
2013 Average .....	2,009	3,720	9,859	3,621	6,237	18,967	10.6	19.6	52.0	32.9	20.4	37.7
2014 Average .....	1,875	3,237	9,241	4,176	5,065	19,100	9.8	16.9	48.4	26.5	20.3	35.0
2015 Average .....	1,507	2,894	9,449	4,738	4,711	19,532	7.7	14.8	48.4	24.1	15.9	30.6
2016 Average .....	1,766	3,446	10,055	5,261	4,795	19,692	9.0	17.5	51.1	24.3	17.6	34.3
2017 Average .....	1,746	3,366	10,144	6,376	3,768	19,952	8.8	16.9	50.8	18.9	17.2	33.2
2018 Average .....	1,578	2,888	9,943	7,601	2,341	20,512	7.7	14.1	48.5	11.4	15.9	29.0
2019 January .....	1,304	2,553	9,768	7,982	1,786	20,615	6.3	12.4	47.4	8.7	13.3	26.1
February .....	1,272	1,803	8,671	8,219	452	20,284	6.3	8.9	42.8	2.2	14.7	20.8
March .....	1,096	1,643	8,905	7,946	959	20,176	5.4	8.1	44.1	4.8	12.3	18.5
April .....	947	1,566	9,525	8,382	1,143	20,333	4.7	7.7	46.8	5.6	9.9	16.4
May .....	912	1,693	9,893	8,238	1,655	20,387	4.5	8.3	48.5	8.1	9.2	17.1
June .....	995	1,699	9,297	8,576	720	20,654	4.8	8.2	45.0	3.5	10.7	18.3
July .....	890	1,420	9,601	8,084	1,517	20,735	4.3	6.8	46.3	7.3	9.3	14.8
August .....	794	1,660	9,387	8,438	949	21,158	3.8	7.8	44.4	4.5	8.5	17.7
September .....	980	1,601	8,712	8,672	40	20,248	4.8	7.9	43.0	0.2	11.2	18.4
October .....	741	1,301	8,599	9,039	-440	20,714	3.6	6.3	41.5	-2.1	8.6	15.1
November .....	685	1,322	8,103	8,741	-638	20,736	3.3	6.4	39.1	-3.1	8.5	16.3
December .....	960	1,411	9,159	9,331	-171	20,443	4.7	6.9	44.8	-0.8	10.5	15.4
Average .....	963	1,639	9,141	8,471	670	20,543	4.7	8.0	44.5	3.3	10.5	17.9
2020 January .....	773	926	8,572	9,177	-605	19,905	3.9	4.7	43.1	-3.0	9.0	10.8
February .....	811	981	8,457	9,983	-1,526	19,839	4.1	4.9	42.6	-7.7	9.6	11.6
March .....	772	831	8,345	9,621	-1,276	18,284	4.2	4.5	45.6	-7.0	9.3	10.0
April .....	610	675	7,236	8,452	-1,216	14,691	4.2	4.6	49.3	-8.3	8.4	9.3
May .....	1,429	1,532	7,757	6,818	939	16,103	8.9	9.5	48.2	5.8	18.4	19.8
June .....	1,465	1,617	8,367	7,692	675	17,435	8.4	9.3	48.0	3.9	17.5	19.3
July .....	968	1,014	7,846	8,412	-566	18,323	5.3	5.5	42.8	-3.1	12.3	12.9
August .....	499	622	7,465	8,498	-1,033	18,439	2.7	3.4	40.5	-5.6	6.7	8.3
September .....	511	667	7,543	8,376	-833	18,307	2.8	3.6	41.2	-4.6	6.8	8.8
October .....	573	686	7,372	8,356	-984	18,624	3.1	3.7	39.6	-5.3	7.8	9.3
November .....	456	632	7,616	7,823	-207	18,702	2.4	3.4	40.7	-1.1	6.0	8.3
December .....	339	467	7,728	8,933	-1,205	18,796	1.8	2.5	41.1	-6.4	4.4	6.0
Average .....	767	887	7,857	8,508	-651	18,120	4.2	4.9	43.4	-3.6	9.8	11.3
2021 January .....	380	603	7,915	8,729	-814	18,595	2.0	3.2	42.6	-4.4	4.8	7.6
February .....	<sup>R</sup> 465	<sup>R</sup> 724	<sup>R</sup> 7,648	<sup>R</sup> 7,661	<sup>R</sup> -13	<sup>R</sup> 17,444	<sup>R</sup> 2.7	<sup>R</sup> 4.1	<sup>R</sup> 43.8	<sup>R</sup> -0.1	<sup>R</sup> 6.1	<sup>R</sup> 9.5
March .....	NA	NA	<sup>E</sup> 8,354	<sup>E</sup> 7,432	<sup>E</sup> 922	<sup>E</sup> 19,217	NA	NA	<sup>E</sup> 43.5	<sup>E</sup> 4.8	NA	NA
April .....	NA	NA	<sup>E</sup> 8,321	<sup>E</sup> 8,069	<sup>E</sup> 252	<sup>E</sup> 19,698	NA	NA	<sup>E</sup> 42.2	<sup>E</sup> 1.3	NA	NA
4-Month Average .....	NA	NA	<sup>E</sup> 8,068	<sup>E</sup> 7,980	<sup>E</sup> 88	<sup>E</sup> 18,763	NA	NA	<sup>E</sup> 43.0	<sup>E</sup> 0.5	NA	NA
2020 4-Month Average .....	741	853	8,155	9,304	-1,149	18,181	4.1	4.7	44.9	-6.3	9.1	10.5
2019 4-Month Average .....	1,154	1,896	9,228	8,128	1,100	20,354	5.7	9.3	45.3	5.4	12.5	20.5

<sup>a</sup> Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, United Arab Emirates, and the Neutral Zone (between Kuwait and Saudi Arabia).

<sup>b</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. See Table 3.3c for notes on which countries are included in the data.

R=Revised; E=Estimate; NA=Not available.

Notes: • For the feature article "Measuring Dependence on Imported Oil," published in the August 1995 *Monthly Energy Review*, see [http://www.eia.gov/totalenergy/data/monthly/pdf/historical/imported\\_oil.pdf](http://www.eia.gov/totalenergy/data/monthly/pdf/historical/imported_oil.pdf).

• Beginning in October 1977, data include Strategic Petroleum Reserve imports. See Table 3.3b. • Annual averages may not equal average of months due to independent rounding. • U.S. geographic coverage is the 50 states and the District of Columbia. U.S. exports include shipments to U.S. territories, and imports include

receipts from U.S. territories.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **1949–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports, and unpublished revisions. • **2020 and 2021:** EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.


**Figure 3.3b Petroleum Trade: Imports and Exports by Type**

(Million Barrels per Day)


Imports Overview, 1949–2020




Exports Overview, 1949–2020



Imports, Selected Products, Monthly



Exports, Selected Products, Monthly



[a] Includes fuel ethanol blended into motor gasoline.

[b] Includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

[c] Includes kerosene-type jet fuel only.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Sources: Tables 3.3b and 3.3e.

**Table 3.3b Petroleum Trade: Imports by Type**  
(Thousand Barrels per Day)

	Crude Oil <sup>a</sup>		Distillate Fuel Oil	Hydrocarbon Gas Liquids				Jet Fuel <sup>e</sup>	Motor Gasoline <sup>f</sup>	Residual Fuel Oil	Other <sup>g</sup>	Total
	SPR <sup>b</sup>	Total		Propane/Propylene			Total <sup>d</sup>					
				Propane	Propylene	Total <sup>c</sup>						
1950 Average .....	--	487	7	NA	NA	—	—	( <sup>e</sup> )	(s)	329	27	850
1955 Average .....	--	782	12	NA	NA	—	—	( <sup>e</sup> )	13	417	24	1,248
1960 Average .....	--	1,015	35	NA	NA	NA	4	34	27	637	62	1,815
1965 Average .....	--	1,238	36	NA	NA	NA	21	81	28	946	119	2,468
1970 Average .....	--	1,324	147	NA	NA	26	58	144	67	1,528	150	3,419
1975 Average .....	--	4,105	155	NA	NA	60	185	133	184	1,223	70	6,056
1980 Average .....	44	5,263	142	NA	NA	84	226	80	140	939	120	6,909
1985 Average .....	118	3,201	200	NA	NA	67	235	39	381	510	501	5,067
1990 Average .....	27	5,894	278	NA	NA	115	197	108	342	504	695	8,018
1995 Average .....	—	7,230	193	95	6	102	192	106	265	187	662	8,835
2000 Average .....	8	9,071	295	154	7	161	256	162	427	352	897	11,459
2005 Average .....	52	10,126	329	219	14	233	374	190	603	530	1,562	13,714
2006 Average .....	8	10,118	365	201	26	228	360	186	475	350	1,854	13,707
2007 Average .....	7	10,031	304	162	20	182	276	217	413	372	1,856	13,468
2008 Average .....	19	9,783	213	162	23	185	275	103	302	349	1,891	12,915
2009 Average .....	56	9,013	225	126	21	147	194	81	223	331	1,623	11,691
2010 Average .....	—	9,213	228	93	29	121	179	98	134	366	1,574	11,793
2011 Average .....	—	8,935	179	82	28	110	183	69	105	328	1,637	11,436
2012 Average .....	—	8,527	126	85	31	116	170	55	44	256	1,421	10,598
2013 Average .....	—	7,730	155	103	24	127	182	84	45	225	1,438	9,859
2014 Average .....	—	7,344	195	89	19	108	143	94	49	173	1,242	9,241
2015 Average .....	—	7,363	200	104	19	124	156	132	71	192	1,335	9,449
2016 Average .....	—	7,850	147	120	22	142	180	147	59	205	1,468	10,055
2017 Average .....	—	7,969	151	133	23	156	196	160	32	189	1,448	10,144
2018 Average .....	—	7,768	175	139	18	157	197	124	45	211	1,422	9,943
2019 January .....	—	7,558	307	214	15	230	297	100	45	197	1,263	9,768
February .....	—	6,670	361	173	13	186	246	140	52	165	1,038	8,671
March .....	—	6,783	180	176	10	186	254	144	103	132	1,308	8,905
April .....	—	6,999	121	124	18	143	207	197	76	136	1,788	9,525
May .....	—	7,154	160	107	21	129	183	188	151	169	1,888	9,893
June .....	—	7,152	126	105	20	125	169	174	53	97	1,525	9,297
July .....	—	6,938	174	106	16	122	180	214	91	102	1,902	9,601
August .....	—	6,944	154	105	17	122	178	175	148	144	1,642	9,387
September .....	—	6,483	118	102	17	119	176	186	111	166	1,472	8,712
October .....	—	6,242	186	116	15	131	198	148	124	116	1,585	8,599
November .....	—	5,818	258	132	13	145	191	131	100	198	1,407	8,103
December .....	—	6,833	295	134	15	149	200	171	62	165	1,435	9,159
Average .....	—	6,801	202	133	16	149	207	164	94	149	1,525	9,141
2020 January .....	—	6,408	217	156	11	168	210	148	91	192	1,306	8,572
February .....	—	6,519	148	120	9	129	157	165	90	169	1,208	8,457
March .....	—	6,296	164	111	15	126	159	150	122	129	1,324	8,345
April .....	—	5,520	231	92	14	105	128	143	90	210	916	7,236
May .....	—	6,087	190	79	14	93	116	125	114	150	975	7,757
June .....	—	6,397	154	59	12	72	109	137	120	155	1,295	8,367
July .....	—	5,906	116	95	14	109	140	166	124	130	1,263	7,846
August .....	—	5,432	145	83	13	95	130	166	115	187	1,289	7,465
September .....	—	5,398	180	124	13	137	172	169	152	206	1,268	7,543
October .....	—	5,293	280	125	14	139	166	145	94	187	1,207	7,372
November .....	—	5,570	305	137	12	149	185	148	62	180	1,166	7,616
December .....	—	5,713	464	144	13	157	208	137	88	94	1,025	7,728
Average .....	—	5,877	216	110	13	123	157	150	105	166	1,187	7,857
2021 January .....	—	5,783	371	167	16	183	235	124	40	205	1,157	7,915
February .....	—	R 5,589	R 353	R 166	R 16	R 182	R 242	R 113	R 62	R 155	R 1,135	R 7,648
March .....	—	E 5,801	E 492	NA	NA	E 174	NA	E 114	E 190	E 149	NA	E 8,354
April .....	—	E 5,834	E 187	NA	NA	E 130	NA	E 135	E 204	E 125	NA	E 8,321
4-Month Average .....	—	E 5,755	E 352	NA	NA	E 167	NA	E 122	E 125	E 159	NA	E 8,068
2020 4-Month Average .....	—	6,186	190	120	12	132	164	151	98	175	1,190	8,155
2019 4-Month Average .....	—	7,011	240	172	14	186	252	145	70	158	1,353	9,228

<sup>a</sup> Includes lease condensate.

<sup>b</sup> "SPR" is the Strategic Petroleum Reserve, which began in October 1977. Through 2003, includes crude oil imports by SPR only; beginning in 2004, includes crude oil imports by SPR, and crude oil imports into SPR by others.

<sup>c</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."

<sup>d</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.

<sup>e</sup> Beginning in 1965, includes kerosene-type jet fuel. (Through 1964, kerosene-type jet fuel is included with kerosene in "Other.") For 1956–2004, also includes naphtha-type jet fuel. (Through 1955, naphtha-type jet fuel is included in "Motor Gasoline." Beginning in 2005, naphtha-type jet fuel is included in "Other.")

<sup>f</sup> Finished motor gasoline. Through 1955, also includes naphtha-type jet fuel. Through 1963, also includes aviation gasoline and special naphthas. Through 1980, also includes motor gasoline blending components.

<sup>g</sup> Asphalt and road oil, aviation gasoline blending components, kerosene, lubricants, petrochemical feedstocks, petroleum coke, unfinished oils, waxes, and miscellaneous products. Through 1964, also includes kerosene-type jet fuel. Beginning in 1964, also includes finished aviation gasoline and special naphthas.

Beginning in 1981, also includes motor gasoline blending components. Beginning in 1993, also includes fuel ethanol. Beginning in 2005, also includes naphtha-type jet fuel. Beginning in 2009, also includes renewable fuels (excluding fuel ethanol) and other hydrocarbons. For 2011–2018, also includes oxygenates (excluding fuel ethanol).

R=Revised. E=Estimate. NA=Not available. -- =Not applicable. -- =No data reported. (s)=Less than 500 barrels per day.

Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • 1949–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • 1976–1980: U.S. Energy Information Administration (EIA), *Energy Data Reports, Petroleum Statement, Annual*, annual reports. • 1981–2019: EIA, *Petroleum Supply Annual*, annual reports, and unpublished revisions. • 2020 and 2021: EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.

**Table 3.3c Petroleum Trade: Imports From OPEC Countries**  
(Thousand Barrels per Day)

	Algeria <sup>a</sup>	Angola <sup>b</sup>	Iraq	Kuwait <sup>c</sup>	Libya <sup>d</sup>	Nigeria <sup>e</sup>	Saudi Arabia <sup>c</sup>	United Arab Emirates	Venezuela	Other <sup>f</sup>	Total OPEC
1960 Average	( <sup>a</sup> )	( <sup>b</sup> )	22	182	( <sup>d</sup> )	( <sup>e</sup> )	84	NA	911	34	1,233
1965 Average	( <sup>a</sup> )	( <sup>b</sup> )	16	74	42	( <sup>e</sup> )	158	14	994	142	1,439
1970 Average	8	( <sup>b</sup> )	—	48	47	( <sup>e</sup> )	30	63	989	109	1,294
1975 Average	282	( <sup>b</sup> )	2	16	232	762	715	117	702	773	3,601
1980 Average	488	( <sup>b</sup> )	28	27	554	857	1,261	172	481	432	4,300
1985 Average	187	( <sup>b</sup> )	46	21	4	293	168	45	605	461	1,830
1990 Average	280	( <sup>b</sup> )	518	86	—	800	1,339	17	1,025	231	4,296
1995 Average	234	( <sup>b</sup> )	—	218	—	627	1,344	10	1,480	88	4,002
2000 Average	225	( <sup>b</sup> )	620	272	—	896	1,572	15	1,546	57	5,203
2005 Average	478	( <sup>b</sup> )	531	243	56	1,166	1,537	18	1,529	28	5,587
2006 Average	657	( <sup>b</sup> )	553	185	87	1,114	1,463	9	1,419	29	5,517
2007 Average	670	508	484	181	117	1,134	1,485	10	1,361	29	5,980
2008 Average	548	513	627	210	103	988	1,529	4	1,189	243	5,954
2009 Average	493	460	450	182	79	809	1,004	40	1,063	195	4,776
2010 Average	510	393	415	197	70	1,023	1,096	2	988	212	4,906
2011 Average	358	346	459	191	15	818	1,195	10	951	212	4,555
2012 Average	242	233	476	305	61	441	1,365	3	960	186	4,271
2013 Average	115	216	341	328	59	281	1,329	3	806	243	3,720
2014 Average	110	154	369	311	6	92	1,166	13	789	224	3,237
2015 Average	108	136	229	204	7	81	1,059	4	827	239	2,894
2016 Average	182	168	424	210	16	235	1,106	14	796	295	3,446
2017 Average	189	135	604	145	65	334	955	34	674	231	3,366
2018 Average	176	94	521	79	56	189	901	58	586	227	2,888
2019 January	98	10	429	21	60	181	777	27	634	317	2,553
February	51	—	422	106	36	33	663	32	289	171	1,803
March	136	10	275	129	25	142	666	3	69	187	1,643
April	125	43	265	61	88	137	583	22	114	128	1,566
May	142	46	366	57	111	243	462	22	11	233	1,693
June	122	123	355	26	55	251	579	16	(s)	171	1,699
July	75	—	360	20	39	193	454	36	—	243	1,420
August	63	47	249	46	66	380	461	19	—	329	1,660
September	49	71	400	—	69	245	458	121	—	189	1,601
October	23	75	252	—	86	128	444	22	—	271	1,301
November	34	25	283	41	90	211	355	5	—	278	1,322
December	16	11	436	43	34	163	470	—	—	238	1,411
Average	78	38	341	45	63	193	530	27	92	231	1,639
2020 January	17	10	299	46	67	64	407	7	—	8	926
February	33	33	262	46	36	76	488	6	—	(s)	981
March	12	—	290	23	—	54	445	4	—	3	831
April	1	30	140	—	—	57	431	13	—	3	675
May	1	50	242	—	—	69	1,158	2	—	9	1,532
June	7	66	146	34	—	103	1,221	39	—	2	1,617
July	4	7	136	84	—	34	718	29	—	—	1,014
August	11	12	209	—	(s)	114	273	3	—	—	622
September	14	32	83	35	(s)	91	366	14	—	32	667
October	3	72	121	34	—	30	280	80	—	67	686
November	19	49	111	34	—	119	286	13	—	2	632
December	61	12	89	—	—	93	190	20	—	2	467
Average	15	31	177	28	9	75	522	19	—	11	887
2021 January	24	40	89	—	33	145	237	33	—	(s)	603
February	60	15	140	29	122	78	268	10	—	3	724
2-Month Average	41	28	113	14	75	113	252	22	—	1	660
2020 2-Month Average	25	21	281	46	52	70	447	7	—	4	953
2019 2-Month Average	76	5	426	61	48	111	723	29	470	248	2,197

<sup>a</sup> Algeria joined OPEC in 1969. For 1960–1968, Algeria is included in "Total Non-OPEC" on Table 3.3d.

<sup>b</sup> Angola joined OPEC in January 2007. For 1960–2006, Angola is included in "Total Non-OPEC" on Table 3.3d.

<sup>c</sup> Through 1970, includes half the imports from the Neutral Zone between Kuwait and Saudi Arabia. Beginning in 1971, imports from the Neutral Zone are reported as originating in either Kuwait or Saudi Arabia depending on the country reported to U.S. Customs.

<sup>d</sup> Libya joined OPEC in 1962. For 1960 and 1961, Libya is included in "Total Non-OPEC" on Table 3.3d.

<sup>e</sup> Nigeria joined OPEC in 1971. For 1960–1970, Nigeria is included in "Total Non-OPEC" on Table 3.3d.

<sup>f</sup> Includes these countries for the dates indicated: Congo-Brazzaville (June 2018 forward), Ecuador (1973–1992 and November 2007–2019), Equatorial Guinea (May 2017 forward), Gabon (1975–1994 and July 2016 forward), Indonesia (1962–2008 and January–November 2016), Iran (1960 forward), and Qatar (1961–2018).

NA=Not available. —=No data reported. (s)=Less than 500 barrels per day.

Notes: • See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. Petroleum imports not classified as "OPEC" on this table are included on Table 3.3d. • The country of origin for petroleum products may not be the country of origin for the crude oil from which the products were produced. For example, refined products imported from West European refining areas may have been produced from Middle East crude oil. • Includes imports for the Strategic Petroleum Reserve, which began in October 1977. • Totals may not equal sum of components due to independent rounding. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1960 and monthly data beginning in 1973.

Sources: • **1960–1972:** Bureau of Mines, *Minerals Yearbook*, annual reports. • **1973–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports. • **2020 and 2021:** EIA, *Petroleum Supply Monthly*, monthly reports.

**Table 3.3d Petroleum Trade: Imports From Non-OPEC Countries**  
(Thousand Barrels per Day)

	Brazil	Canada	Colombia	Ecuador <sup>a</sup>	Mexico	Nether-lands	Norway	Russia <sup>b</sup>	United Kingdom	U.S. Virgin Islands	Other	Total Non-OPEC
1960 Average .....	1	120	42	NA	16	NA	NA	—	(s)	NA	NA	581
1965 Average .....	—	323	51	—	48	1	—	—	(s)	—	606	1,029
1970 Average .....	2	766	46	—	42	39	—	3	11	189	1,027	2,126
1975 Average .....	5	846	9	( <sup>a</sup> )	71	19	17	14	14	406	1,052	2,454
1980 Average .....	3	455	4	( <sup>a</sup> )	533	2	144	1	176	388	903	2,609
1985 Average .....	61	770	23	( <sup>a</sup> )	816	58	32	8	310	247	913	3,237
1990 Average .....	49	934	182	( <sup>a</sup> )	755	55	102	45	189	282	1,128	3,721
1995 Average .....	8	1,332	219	97	1,068	15	273	25	383	278	1,136	4,833
2000 Average .....	51	1,807	342	128	1,373	30	343	72	366	291	1,453	6,257
2005 Average .....	156	2,181	196	283	1,662	151	233	410	396	328	2,130	8,127
2006 Average .....	193	2,353	155	278	1,705	174	196	369	272	328	2,168	8,190
2007 Average .....	200	2,455	155	203	1,532	128	142	414	277	346	1,636	7,489
2008 Average .....	258	2,493	200	( <sup>a</sup> )	1,302	168	102	465	236	320	1,416	6,961
2009 Average .....	309	2,479	276	( <sup>a</sup> )	1,210	140	108	563	245	277	1,307	6,915
2010 Average .....	272	2,535	365	( <sup>a</sup> )	1,284	108	89	612	256	253	1,112	6,887
2011 Average .....	253	2,729	433	( <sup>a</sup> )	1,206	100	113	624	159	186	1,077	6,881
2012 Average .....	226	2,946	433	( <sup>a</sup> )	1,035	99	75	477	149	12	874	6,327
2013 Average .....	151	3,142	389	( <sup>a</sup> )	919	89	54	460	147	—	786	6,138
2014 Average .....	160	3,388	318	( <sup>a</sup> )	842	85	45	330	117	—	720	6,004
2015 Average .....	215	3,765	395	( <sup>a</sup> )	758	57	61	371	123	—	811	6,554
2016 Average .....	167	3,780	483	( <sup>a</sup> )	669	60	76	441	122	(s)	812	6,610
2017 Average .....	224	4,054	362	( <sup>a</sup> )	682	62	79	389	111	—	814	6,778
2018 Average .....	171	4,292	333	( <sup>a</sup> )	719	62	94	375	146	—	862	7,055
2019 January .....	141	4,655	380	( <sup>a</sup> )	569	103	88	344	122	—	813	7,215
February .....	90	4,320	420	( <sup>a</sup> )	720	108	69	226	47	—	867	6,868
March .....	172	4,429	412	( <sup>a</sup> )	712	68	80	363	118	—	907	7,262
April .....	153	4,412	472	( <sup>a</sup> )	680	124	112	566	182	—	1,258	7,958
May .....	256	4,428	468	( <sup>a</sup> )	656	218	147	564	266	—	1,198	8,200
June .....	213	4,398	395	( <sup>a</sup> )	574	88	190	534	156	—	1,050	7,598
July .....	338	4,674	379	( <sup>a</sup> )	670	121	51	496	182	—	1,270	8,181
August .....	197	4,379	384	( <sup>a</sup> )	744	138	94	617	146	—	1,027	7,726
September .....	186	4,285	283	( <sup>a</sup> )	589	121	123	486	179	—	859	7,111
October .....	285	4,422	266	( <sup>a</sup> )	548	95	40	675	130	—	838	7,298
November .....	125	3,963	284	( <sup>a</sup> )	705	96	46	649	139	—	774	6,782
December .....	143	4,784	340	( <sup>a</sup> )	641	76	48	696	81	—	939	7,749
Average .....	193	4,432	373	( <sup>a</sup> )	650	113	91	520	146	—	984	7,502
2020 January .....	101	4,505	337	242	854	48	1	601	109	—	848	7,646
February .....	134	4,583	343	236	804	64	—	614	74	—	624	7,476
March .....	120	4,366	322	260	801	114	18	645	62	—	805	7,514
April .....	104	4,088	277	176	631	93	16	408	54	—	713	6,561
May .....	110	3,682	250	58	889	24	44	350	101	—	716	6,225
June .....	159	3,760	369	112	849	98	99	551	87	—	667	6,751
July .....	115	3,981	331	108	755	72	12	563	84	—	808	6,831
August .....	113	3,877	186	242	769	91	20	552	64	—	928	6,843
September .....	92	3,945	351	227	715	125	15	527	91	—	789	6,876
October .....	113	3,968	248	165	574	56	60	660	113	—	727	6,685
November .....	166	4,287	175	227	611	72	36	570	66	—	775	6,984
December .....	173	4,440	219	176	740	132	26	416	116	7	817	7,261
Average .....	125	4,122	284	186	750	82	29	538	85	1	769	6,970
2021 January .....	121	4,468	205	164	747	75	31	649	42	42	767	7,312
February .....	56	4,308	272	134	613	77	56	453	74	34	847	6,924
2-Month Average .....	90	4,392	237	150	684	76	43	556	58	39	805	7,128
2020 2-Month Average .....	117	4,542	340	239	830	56	(s)	607	92	—	740	7,564
2019 2-Month Average .....	117	4,496	399	( <sup>a</sup> )	641	105	79	288	87	—	838	7,050

<sup>a</sup> Ecuador was a member of OPEC from 1973–1992 and November 2007–2019. For those time periods, Ecuador is included in "Total OPEC" on Table 3.3c.

<sup>b</sup> Through 1992, may include imports from republics other than Russia in the former U.S.S.R. See "Union of Soviet Socialist Republics (U.S.S.R.)" in Glossary. NA=Not available. —=No data reported. (s)=Less than 500 barrels per day.

Notes: • See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. Petroleum imports not classified as "OPEC" on Table 3.3c are included on this table. • The country of origin for petroleum products may not be the country of origin for the crude oil from which the products were produced. For example, refined products imported from West European refining areas may have been produced from Middle East crude oil. • Includes imports for the Strategic Petroleum Reserve, which began in October 1977. • Totals may not equal sum of

components due to independent rounding. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1960 and monthly data beginning in 1973.

Sources: • **1960–1972:** Bureau of Mines, *Minerals Yearbook*, annual reports. • **1973–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), *Energy Data Reports, Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports. • **2020 and 2021:** EIA, *Petroleum Supply Monthly*, monthly reports.

**Table 3.3e Petroleum Trade: Exports by Type**  
(Thousand Barrels per Day)

	Crude Oil <sup>a</sup>	Distillate Fuel Oil	Hydrocarbon Gas Liquids		Jet Fuel <sup>d</sup>	Motor Gasoline <sup>e</sup>	Residual Fuel Oil	Other <sup>f</sup>	Total
			Propane <sup>b</sup>	Total <sup>c</sup>					
1950 Average .....	95	34	NA	4	( <sup>d</sup> )	68	44	58	305
1955 Average .....	32	67	NA	12	(s)	95	93	69	368
1960 Average .....	8	27	NA	8	(s)	37	51	71	202
1965 Average .....	3	10	NA	21	3	2	41	108	187
1970 Average .....	14	2	13	27	6	1	54	154	259
1975 Average .....	6	1	13	26	2	2	15	158	209
1980 Average .....	287	3	10	21	1	1	33	197	544
1985 Average .....	204	67	48	64	13	10	197	225	781
1990 Average .....	109	109	28	41	43	55	211	287	857
1995 Average .....	95	183	38	59	26	104	136	12	949
2000 Average .....	50	173	53	78	32	144	139	46	1,040
2005 Average .....	32	138	37	60	53	136	251	496	1,165
2006 Average .....	25	215	45	68	41	142	283	544	1,317
2007 Average .....	27	268	42	70	41	127	330	569	1,433
2008 Average .....	29	528	53	101	61	172	355	555	1,802
2009 Average .....	44	587	85	139	69	195	415	574	2,024
2010 Average .....	42	656	109	164	84	296	405	706	2,353
2011 Average .....	47	854	124	249	97	479	424	835	2,986
2012 Average .....	67	1,007	171	314	132	409	388	886	3,205
2013 Average .....	134	1,134	302	468	156	373	362	994	3,621
2014 Average .....	351	1,101	423	703	163	442	364	1,052	4,176
2015 Average .....	465	1,176	615	966	168	476	326	1,161	4,738
2016 Average .....	591	1,179	799	1,211	175	635	298	1,171	5,261
2017 Average .....	1,158	1,381	914	1,404	184	749	308	1,192	6,376
2018 Average .....	2,048	1,289	949	1,602	223	879	321	1,240	7,601
<b>2019</b> January .....	2,643	1,280	1,030	1,561	264	826	230	1,178	7,982
February .....	2,915	1,160	892	1,517	192	912	242	1,281	8,219
March .....	2,673	1,173	918	1,652	173	873	243	1,159	7,946
April .....	2,911	1,261	1,166	1,923	195	655	357	1,081	8,382
May .....	2,959	1,287	1,085	1,802	194	742	301	954	8,238
June .....	3,100	1,516	1,158	1,860	213	699	194	994	8,576
July .....	2,706	1,374	1,188	1,893	209	683	142	1,077	8,084
August .....	2,755	1,530	1,035	1,832	254	696	287	1,084	8,438
September .....	3,093	1,427	1,124	1,885	243	783	202	1,040	8,672
October .....	3,412	1,205	1,168	2,081	222	898	148	1,074	9,039
November .....	3,080	1,148	1,159	1,981	226	1,049	204	1,053	8,741
December .....	3,537	1,301	1,235	1,955	256	964	199	1,119	9,331
<b>Average</b> .....	<b>2,982</b>	<b>1,306</b>	<b>1,098</b>	<b>1,830</b>	<b>220</b>	<b>815</b>	<b>229</b>	<b>1,090</b>	<b>8,471</b>
<b>2020</b> January .....	3,251	1,263	1,263	2,163	215	822	169	1,294	9,177
February .....	3,708	1,380	1,191	2,202	246	881	231	1,335	9,983
March .....	3,557	1,459	1,337	2,139	214	777	152	1,325	9,621
April .....	3,077	1,096	1,213	2,067	66	762	157	1,226	8,452
May .....	2,929	733	1,053	1,846	23	314	145	828	6,818
June .....	2,753	1,330	1,250	2,032	44	468	154	912	7,692
July .....	3,267	1,368	1,218	2,008	54	597	121	997	8,412
August .....	3,298	1,337	1,139	1,996	30	764	125	946	8,498
September .....	3,238	1,177	1,210	2,015	45	782	141	978	8,376
October .....	2,935	1,078	1,375	2,285	40	824	100	1,094	8,356
November .....	2,726	982	1,331	2,135	79	832	128	942	7,823
December .....	3,371	1,195	1,591	2,239	87	931	76	1,035	8,933
<b>Average</b> .....	<b>3,175</b>	<b>1,199</b>	<b>1,265</b>	<b>2,094</b>	<b>95</b>	<b>729</b>	<b>141</b>	<b>1,075</b>	<b>8,508</b>
<b>2021</b> January .....	3,165	913	1,469	2,381	93	799	74	1,303	8,729
February .....	<sup>R</sup> 2,703	<sup>R</sup> 866	<sup>R</sup> 1,206	<sup>R</sup> 2,175	<sup>R</sup> 68	<sup>R</sup> 687	<sup>R</sup> 116	<sup>R</sup> 1,048	<sup>R</sup> 7,661
March .....	<sup>E</sup> 2,850	<sup>E</sup> 842	NA	NA	<sup>E</sup> 65	<sup>E</sup> 592	<sup>E</sup> 97	NA	<sup>E</sup> 7,432
April .....	<sup>E</sup> 2,925	<sup>E</sup> 997	NA	NA	<sup>E</sup> 92	<sup>E</sup> 643	<sup>E</sup> 136	NA	<sup>E</sup> 8,069
<b>4-Month Average</b> .....	<sup>E</sup> <b>2,916</b>	<sup>E</sup> <b>905</b>	<b>NA</b>	<b>NA</b>	<sup>E</sup> <b>80</b>	<sup>E</sup> <b>680</b>	<sup>E</sup> <b>105</b>	<b>NA</b>	<sup>E</sup> <b>7,980</b>
<b>2020 4-Month Average</b> .....	<b>3,396</b>	<b>1,300</b>	<b>1,253</b>	<b>2,142</b>	<b>185</b>	<b>810</b>	<b>176</b>	<b>1,295</b>	<b>9,304</b>
<b>2019 4-Month Average</b> .....	<b>2,781</b>	<b>1,220</b>	<b>1,003</b>	<b>1,665</b>	<b>206</b>	<b>816</b>	<b>268</b>	<b>1,173</b>	<b>8,128</b>

<sup>a</sup> Includes lease condensate.

<sup>b</sup> Through 1983, also includes 40% of "Butane-Propane Mixtures." Through 2012, also includes propylene.

<sup>c</sup> Ethane, propane, normal butane, isobutane, and natural gasoline (pentanes plus). Through 2012, also includes refinery olefins (ethylene, propylene, butylene, and isobutylene).

<sup>d</sup> Beginning in 1965, includes kerosene-type jet fuel. (Through 1964, kerosene-type jet fuel is included with kerosene in "Other.") For 1953–2004, also includes naphtha-type jet fuel. (Through 1952, naphtha-type jet fuel is included in the products from which it was blended: motor gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other.")

<sup>e</sup> Finished motor gasoline. Through 1952, also includes naphtha-type jet fuel. Through 1963, also includes aviation gasoline and special naphthas. Through 1980, also includes motor gasoline blending components.

<sup>f</sup> Asphalt and road oil, kerosene, lubricants, petrochemical feedstocks, petroleum coke, unfinished oils, waxes, and miscellaneous products. Through 1964, also includes kerosene-type jet fuel. Beginning in 1964, also includes finished aviation gasoline and special naphthas. Beginning in 1981, also includes

motor gasoline blending components. Beginning in 2005, also includes naphtha-type jet fuel. For 2009–2018, also includes oxygenates (excluding fuel ethanol). Beginning in 2010, also includes fuel ethanol. Beginning in 2011, also includes renewable fuels (excluding fuel ethanol).

R=Revised. E=Estimate. NA=Not available. (s)=Less than 500 barrels per day.

Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **1949–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports, and unpublished revisions. • **2020 and 2021:** EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.

**Table 3.3f Petroleum Trade: Exports by Country of Destination**  
(Thousand Barrels per Day)

	Brazil	Canada	China	India	Japan	Mexico	Nether-lands	Singa-pore	South Korea	United Kingdom	Other	Total
<b>1960 Average</b> .....	4	34	NA	NA	62	18	6	NA	NA	12	NA	202
<b>1965 Average</b> .....	3	26	NA	NA	40	27	10	NA	NA	12	NA	187
<b>1970 Average</b> .....	7	31	NA	NA	69	33	15	NA	NA	12	NA	259
<b>1975 Average</b> .....	6	22	NA	1	27	42	23	NA	NA	7	NA	209
<b>1980 Average</b> .....	4	108	—	1	32	28	23	6	2	7	335	544
<b>1985 Average</b> .....	3	74	—	2	108	61	44	24	27	14	424	781
<b>1990 Average</b> .....	2	91	—	6	92	89	54	15	60	11	438	857
<b>1995 Average</b> .....	16	73	2	3	76	125	33	46	57	14	505	949
<b>2000 Average</b> .....	28	110	3	3	90	358	42	36	20	10	342	1,040
<b>2005 Average</b> .....	39	181	12	11	56	268	25	43	16	21	492	1,165
<b>2006 Average</b> .....	42	159	11	8	58	255	83	45	21	28	607	1,317
<b>2007 Average</b> .....	46	189	14	14	54	279	81	71	16	9	660	1,433
<b>2008 Average</b> .....	54	264	13	10	54	333	131	77	18	17	830	1,802
<b>2009 Average</b> .....	55	223	44	30	58	322	192	115	23	33	928	2,024
<b>2010 Average</b> .....	123	233	52	10	88	448	165	128	13	19	1,073	2,353
<b>2011 Average</b> .....	157	351	73	17	79	570	248	121	15	35	1,320	2,986
<b>2012 Average</b> .....	166	416	85	36	89	565	239	115	16	41	1,435	3,205
<b>2013 Average</b> .....	179	549	129	41	117	532	274	136	13	36	1,616	3,621
<b>2014 Average</b> .....	217	809	89	70	150	559	241	124	46	53	1,817	4,176
<b>2015 Average</b> .....	188	955	191	78	166	690	226	122	65	89	1,968	4,738
<b>2016 Average</b> .....	260	935	203	140	250	880	265	147	108	92	1,980	5,261
<b>2017 Average</b> .....	395	871	447	200	350	1,081	251	210	176	186	2,209	6,376
<b>2018 Average</b> .....	400	1,024	374	297	466	1,194	337	185	382	272	2,670	7,601
<b>2019 January</b> .....	457	878	93	401	646	1,177	620	37	339	375	2,957	7,982
February .....	328	1,163	177	455	284	1,234	442	184	607	368	2,977	8,219
March .....	564	944	129	673	505	1,210	372	140	506	263	2,640	7,946
April .....	428	1,155	80	575	516	1,197	440	119	397	293	3,181	8,382
May .....	428	1,030	300	469	580	1,018	294	124	501	372	3,121	8,238
June .....	565	861	424	438	440	993	525	82	807	286	3,155	8,576
July .....	466	979	286	231	589	1,165	355	79	759	269	2,905	8,084
August .....	443	1,052	300	417	574	1,043	373	63	616	383	3,174	8,438
September .....	585	1,013	317	396	633	1,056	478	149	606	322	3,116	8,672
October .....	446	1,190	36	586	558	1,208	553	137	618	285	3,423	9,039
November .....	476	1,148	133	400	595	1,355	360	168	613	371	3,122	8,741
December .....	493	1,026	78	480	709	1,242	595	237	590	439	3,441	9,331
<b>Average</b> .....	<b>474</b>	<b>1,035</b>	<b>196</b>	<b>460</b>	<b>555</b>	<b>1,158</b>	<b>451</b>	<b>126</b>	<b>580</b>	<b>336</b>	<b>3,102</b>	<b>8,471</b>
<b>2020 January</b> .....	462	1,253	98	498	683	1,168	471	150	758	394	3,243	9,177
February .....	546	1,212	82	525	481	1,135	671	280	492	567	3,991	9,983
March .....	512	1,002	251	546	714	1,244	460	248	427	414	3,803	9,621
April .....	410	862	369	458	635	872	380	472	375	290	3,328	8,452
May .....	275	698	1,450	350	489	536	301	147	348	253	1,969	6,818
June .....	299	785	906	559	471	826	411	253	392	303	2,488	7,692
July .....	431	894	851	345	663	975	507	77	409	392	2,866	8,412
August .....	497	760	823	336	390	1,114	478	174	467	456	3,004	8,498
September .....	454	1,045	1,017	429	392	1,039	373	109	431	242	2,847	8,376
October .....	518	850	960	477	458	1,079	375	51	422	347	2,820	8,356
November .....	397	842	637	563	467	1,187	535	60	295	290	2,550	7,823
December .....	484	737	957	644	711	1,313	403	22	422	334	2,905	8,933
<b>Average</b> .....	<b>440</b>	<b>910</b>	<b>703</b>	<b>477</b>	<b>547</b>	<b>1,041</b>	<b>446</b>	<b>169</b>	<b>437</b>	<b>357</b>	<b>2,981</b>	<b>8,508</b>
<b>2021 January</b> .....	511	834	713	673	758	1,021	210	161	533	260	3,054	8,729
February .....	426	814	527	641	383	1,085	570	282	366	149	2,418	7,661
<b>2-Month Average</b> .....	<b>470</b>	<b>825</b>	<b>625</b>	<b>658</b>	<b>580</b>	<b>1,051</b>	<b>381</b>	<b>219</b>	<b>454</b>	<b>207</b>	<b>2,752</b>	<b>8,222</b>
<b>2020 2-Month Average</b> .....	<b>502</b>	<b>1,233</b>	<b>90</b>	<b>511</b>	<b>586</b>	<b>1,152</b>	<b>568</b>	<b>212</b>	<b>629</b>	<b>478</b>	<b>3,605</b>	<b>9,566</b>
<b>2019 2-Month Average</b> .....	<b>396</b>	<b>1,013</b>	<b>133</b>	<b>427</b>	<b>474</b>	<b>1,204</b>	<b>536</b>	<b>107</b>	<b>466</b>	<b>372</b>	<b>2,967</b>	<b>8,095</b>

NA=Not available. —=No data reported.


Notes: • Totals may not equal sum of components due to independent rounding. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1960 and monthly data beginning in 1981.


Sources: • **1960–1972:** Bureau of Mines, *Minerals Yearbook*, annual reports. • **1973–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports. • **2020 and 2021:** EIA, *Petroleum Supply Monthly*, monthly reports.

**Figure 3.4 Petroleum Stocks**


Overview, 1949–2020




SPR and Non-SPR Crude Oil Stocks, 1949–2020



Overview, Monthly



Selected Products, Monthly



[a] Includes kerosene-type jet fuel only.

Notes: • SPR=Strategic Petroleum Reserve. • Stocks are at end of period.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Source: Table 3.4.



**Table 3.4 Petroleum Stocks**  
(Million Barrels)

	Crude Oil <sup>a</sup>			Distillate Fuel Oil <sup>e</sup>	Hydrocarbon Gas Liquids				Jet Fuel <sup>i</sup>	Motor Gasoline <sup>j</sup>	Residual Fuel Oil <sup>k</sup>	Other <sup>l</sup>	Total	
	SPR <sup>b</sup>	Non-SPR <sup>c,d</sup>	Total <sup>d</sup>		Propane/Propylene			Total <sup>h</sup>						
					Propane	Propylene <sup>f</sup>	Total <sup>g</sup>							
1950 Year .....	--	248	248	72	NA	NA	NA	2	( <sup>i</sup> )	116	41	104	583	
1955 Year .....	--	266	266	111	NA	NA	NA	7	3	165	39	123	715	
1960 Year .....	--	240	240	138	NA	NA	NA	23	7	195	45	137	785	
1965 Year .....	--	220	220	155	NA	NA	NA	35	19	175	56	176	836	
1970 Year .....	--	276	276	195	NA	NA	NA	44	28	209	54	181	1,018	
1975 Year .....	--	271	271	209	NA	NA	NA	82	133	30	235	74	181	1,133
1980 Year .....	108	358	466	205	NA	NA	NA	71	137	42	261	92	189	1,392
1985 Year .....	493	321	814	144	NA	NA	NA	39	82	40	223	50	165	1,519
1990 Year .....	586	323	908	132	NA	NA	NA	49	104	52	220	49	156	1,621
1995 Year .....	592	303	895	130	NA	NA	NA	43	100	40	202	37	158	1,563
2000 Year .....	541	286	826	118	NA	NA	NA	41	88	45	196	36	159	1,468
2005 Year .....	685	308	992	136	NA	NA	NA	57	117	42	208	37	148	1,682
2006 Year .....	689	296	984	144	NA	NA	NA	62	125	39	212	42	157	1,703
2007 Year .....	697	268	965	134	NA	NA	NA	52	106	39	218	39	146	1,648
2008 Year .....	702	308	1,010	146	NA	NA	NA	55	127	38	214	36	149	1,719
2009 Year .....	727	307	1,034	166	NA	NA	NA	50	113	43	223	37	142	1,758
2010 Year .....	727	312	1,039	164	46	2	47	118	43	219	41	145	1,770	
2011 Year .....	696	308	1,004	149	48	2	50	121	41	223	34	146	1,720	
2012 Year .....	695	338	1,033	135	63	2	64	148	40	231	34	154	1,775	
2013 Year .....	696	327	1,023	128	40	1	42	121	37	228	38	149	1,724	
2014 Year .....	691	361	1,052	136	72	2	74	170	38	240	34	151	1,822	
2015 Year .....	695	449	1,144	161	91	2	93	192	40	235	42	164	1,979	
2016 Year .....	695	485	1,180	166	77	2	79	196	43	239	41	161	2,025	
2017 Year .....	663	422	1,084	146	62	2	64	187	41	237	29	167	1,892	
2018 Year .....	649	443	1,092	140	64	2	66	184	42	247	28	176	1,908	
2019 January .....	649	449	1,098	140	51	1	53	161	41	262	30	182	1,914	
February .....	649	452	1,101	136	46	1	47	151	42	252	28	187	1,897	
March .....	649	459	1,108	132	49	2	51	160	42	237	29	186	1,894	
April .....	649	470	1,118	128	53	2	55	175	41	231	29	190	1,912	
May .....	645	481	1,126	130	63	2	65	202	39	236	30	189	1,952	
June .....	645	463	1,108	131	72	2	73	224	41	230	30	184	1,949	
July .....	645	442	1,086	138	78	2	80	238	43	235	31	182	1,954	
August .....	645	430	1,075	136	91	2	93	256	43	230	29	177	1,946	
September .....	645	426	1,070	132	96	3	98	263	44	232	30	172	1,943	
October .....	641	443	1,085	120	95	2	97	253	40	224	30	176	1,927	
November .....	635	446	1,081	126	88	2	90	232	41	234	33	172	1,918	
December .....	635	433	1,068	140	80	2	81	212	40	254	31	172	1,917	
2020 January .....	635	443	1,078	143	75	2	76	195	44	264	31	179	1,934	
February .....	635	454	1,089	133	64	1	65	179	43	252	31	188	1,914	
March .....	635	482	1,117	127	60	1	62	181	40	261	34	196	1,956	
April .....	638	529	1,167	151	62	1	63	196	40	257	37	188	2,035	
May .....	648	521	1,169	176	67	1	68	210	40	258	39	181	2,074	
June .....	656	532	1,188	175	75	2	77	234	42	253	40	177	2,109	
July .....	656	519	1,175	178	85	1	87	257	41	249	36	171	2,107	
August .....	648	504	1,152	179	95	2	97	283	40	237	35	159	2,084	
September .....	642	497	1,140	172	101	2	102	299	40	227	32	155	2,064	
October .....	639	494	1,132	155	95	1	96	287	38	227	31	154	2,024	
November .....	638	500	1,139	156	90	1	92	267	38	241	31	155	2,028	
December .....	638	485	1,123	160	70	1	72	229	39	243	30	157	1,982	
2021 January .....	638	476	1,114	163	54	1	55	192	43	255	32	170	1,968	
February .....	638	R 493	R 1,131	R 143	R 41	R 1	R 42	171	R 40	R 241	R 31	R 175	R 1,933	
March .....	E 638	E 499	E 1,137	E 145	NA	NA	E 40	RF 171	E 38	E 234	E 31	RE 174	E 1,930	
April .....	E 633	E 485	E 1,118	E 136	NA	NA	E 42	F 175	E 40	E 236	E 32	E 177	E 1,914	


<sup>a</sup> Includes lease condensate.  
<sup>b</sup> "SPR" is the Strategic Petroleum Reserve, which began in October 1977. Crude oil stocks in the SPR include non-U.S. stocks held under foreign or commercial storage agreements.  
<sup>c</sup> All crude oil stocks other than those in "SPR."  
<sup>d</sup> Beginning in 1981, includes stocks of Alaskan crude oil in transit.  
<sup>e</sup> Excludes stocks in the Northeast Home Heating Oil Reserve. Beginning in 2009, includes biodiesel and other renewable diesel fuel blended into distillate fuel oil. Beginning in 2021, also includes renewable heating oil blended into distillate fuel oil.  
<sup>f</sup> Includes propylene stocks at refineries only.  
<sup>g</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."  
<sup>h</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.  
<sup>i</sup> Beginning in 1965, includes kerosene-type jet fuel. (Through 1964, kerosene-type jet fuel is included with kerosene in "Other.") For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other.")  
<sup>j</sup> Includes finished motor gasoline and motor gasoline blending components; excludes oxygenates. Through 1963, also includes aviation gasoline and special naphthas.  
<sup>k</sup> Through 2019, includes residual fuel oil stocks at (or in) refineries, bulk

terminals, and pipelines. Beginning in 2020, includes residual fuel oil stocks at refineries and bulk terminals only.  
<sup>l</sup> Asphalt and road oil, aviation gasoline blending components, kerosene, lubricants, petrochemical feedstocks, petroleum coke, unfinished oils, waxes, and miscellaneous products. Through 1964, also includes kerosene-type jet fuel. Beginning in 1964, also includes finished aviation gasoline and special naphthas. Beginning in 1993, also includes fuel ethanol. Beginning in 2005, also includes naphtha-type jet fuel. For 2005–2018, also includes oxygenates (excluding fuel ethanol). Beginning in 2009, also includes renewable fuels (excluding fuel ethanol) and other hydrocarbons.  
R=Revised. E=Estimate. F=Forecast. NA=Not available. -- =Not applicable.  
Notes: • Stocks are at end of period. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.  
Sources: • **1949–1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976–1980:** U.S. Energy Information Administration (EIA), *Energy Data Reports, Petroleum Statement, Annual*, annual reports. • **1981–2019:** EIA, *Petroleum Supply Annual*, annual reports, and unpublished revisions. • **2020 and 2021:** EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system, Short-Term Integrated Forecasting System, and *Monthly Energy Review* data system calculations.


**Figure 3.5 Petroleum Products Supplied by Type**

(Million Barrels per Day)


Total Petroleum and Motor Gasoline, 1949–2020




Selected Products, 1949–2020



Selected Products, Monthly



Total, January–April



[a] Beginning in 1993, includes fuel ethanol blended into motor gasoline.

[b] For 2009–2020, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil. Beginning in 2021, includes refinery and blender net inputs of renewable diesel fuel (including biodiesel) blended

into distillate fuel oil.

[c] Beginning in 2005, includes kerosene-type jet fuel only.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Source: Table 3.5.

**Table 3.5 Petroleum Products Supplied by Type**  
(Thousand Barrels per Day)

	Asphalt and Road Oil	Avia- tion Gas- oline	Distil- late Fuel Oil <sup>a</sup>	Hydrocarbon Gas Liquids				Jet Fuel <sup>d</sup>	Kero- sene	Lubri- cants	Motor Gas- oline <sup>e</sup>	Petro- leum Coke	Resid- ual Fuel Oil	Other <sup>f</sup>	Total
				Propane/Propylene			Total <sup>c</sup>								
				Pro- pane	Propy- lene	Total <sup>b</sup>									
1950 Average .....	180	108	1,082	E 146	E 13	E 158	234	( <sup>d</sup> )	323	106	2,616	41	1,517	250	6,458
1955 Average .....	254	192	1,592	E 251	E 22	E 273	404	154	320	116	3,463	67	1,526	366	8,455
1960 Average .....	302	161	1,872	E 386	E 33	E 419	621	371	271	117	3,969	149	1,529	435	9,797
1965 Average .....	368	120	2,126	E 523	E 45	E 568	841	602	267	129	4,593	202	1,608	657	11,511
1970 Average .....	447	55	2,540	E 727	E 55	782	1,224	967	263	136	5,785	212	2,204	866	14,697
1975 Average .....	419	39	2,851	E 730	E 60	790	1,352	1,001	159	137	6,675	247	2,462	982	16,322
1980 Average .....	396	35	2,866	E 742	E 72	813	1,590	1,068	158	159	6,579	237	2,508	1,460	17,056
1985 Average .....	425	27	2,868	E 810	E 72	883	1,721	1,218	114	145	6,831	264	1,202	909	15,726
1990 Average .....	483	24	3,021	E 812	E 105	917	1,705	1,522	43	164	7,235	339	1,229	1,225	16,988
1995 Average .....	486	21	3,207	E 938	E 157	1,096	2,100	1,514	54	156	7,789	365	852	1,180	17,725
2000 Average .....	525	20	3,722	E 1,011	E 224	1,235	2,434	1,725	67	166	8,472	406	909	1,255	19,701
2005 Average .....	546	19	4,118	E 986	E 243	1,229	2,146	1,679	70	141	9,159	515	920	1,489	20,802
2006 Average .....	521	18	4,169	E 947	E 268	1,215	2,135	1,633	54	137	9,253	522	689	1,557	20,687
2007 Average .....	494	17	4,196	E 983	E 252	1,235	2,191	1,622	32	142	9,286	490	723	1,487	20,680
2008 Average .....	417	15	3,945	E 924	E 230	1,154	2,044	1,539	14	131	8,989	464	622	1,317	19,498
2009 Average .....	360	14	3,631	E 893	E 267	1,160	2,127	1,393	18	118	8,997	427	511	1,175	18,771
2010 Average .....	362	15	3,800	852	305	1,157	2,263	1,432	20	131	8,993	376	535	1,251	19,178
2011 Average .....	355	15	3,899	851	310	1,161	2,250	1,425	12	125	8,753	361	461	1,240	18,896
2012 Average .....	340	14	3,741	862	308	1,170	2,293	1,398	5	114	8,682	360	369	1,165	18,482
2013 Average .....	323	12	3,827	969	306	1,275	2,501	1,434	5	121	8,843	354	319	1,227	18,967
2014 Average .....	327	12	4,037	870	298	1,167	2,443	1,470	9	126	8,921	347	257	1,151	19,100
2015 Average .....	343	11	3,995	865	295	1,160	2,550	1,548	6	138	9,178	349	259	1,153	19,532
2016 Average .....	351	11	3,877	833	301	1,134	2,541	1,614	9	130	9,317	345	326	1,170	19,692
2017 Average .....	351	11	3,932	803	309	1,111	2,637	1,682	5	121	9,327	316	342	1,228	19,952
2018 Average .....	327	12	4,146	888	311	1,199	3,014	1,707	5	117	9,329	327	318	1,210	20,512
2019 January .....	195	9	4,327	1,372	320	1,692	3,715	1,621	26	114	8,778	294	319	1,217	20,615
February .....	201	9	4,307	1,237	299	1,536	3,590	1,607	17	105	9,072	128	279	969	20,284
March .....	232	13	4,184	963	265	1,228	3,136	1,711	(s)	97	9,184	295	221	1,102	20,176
April .....	318	12	4,120	657	289	945	2,886	1,756	2	156	9,411	235	177	1,261	20,333
May .....	369	15	4,110	558	302	860	2,745	1,773	1	107	9,497	320	192	1,257	20,387
June .....	413	16	3,993	525	311	836	2,753	1,802	1	104	9,703	403	322	1,144	20,654
July .....	510	17	3,911	591	297	888	2,930	1,847	1	129	9,533	405	342	1,110	20,735
August .....	507	13	4,029	541	294	834	2,854	1,841	(s)	115	9,834	337	329	1,299	21,158
September .....	480	15	3,921	761	283	1,044	3,041	1,702	6	96	9,198	263	305	1,222	20,248
October .....	438	14	4,224	895	316	1,211	3,148	1,727	2	130	9,308	232	319	1,172	20,714
November .....	310	12	4,201	1,169	301	1,470	3,398	1,711	12	105	9,209	347	208	1,222	20,736
December .....	198	9	3,927	1,172	306	1,478	3,499	1,809	14	94	8,971	363	284	1,275	20,443
Average .....	348	13	4,103	868	298	1,166	3,139	1,743	7	113	9,309	303	275	1,189	20,543
2020 January .....	191	14	3,998	1,087	282	1,369	3,396	1,673	24	123	8,761	251	258	1,217	19,905
February .....	191	8	4,011	1,243	254	1,497	3,208	1,629	30	108	8,967	261	150	1,276	19,839
March .....	204	8	3,913	936	257	1,193	3,311	1,387	7	62	7,781	255	109	1,247	18,284
April .....	292	6	3,505	746	278	1,024	2,857	691	2	82	5,853	189	125	1,088	14,691
May .....	365	14	3,533	626	274	900	2,881	596	(s)	83	7,188	219	81	1,143	16,103
June .....	511	11	3,492	394	263	657	2,760	786	1	104	8,286	227	232	1,026	17,435
July .....	491	13	3,610	494	275	770	3,021	964	1	116	8,458	247	341	1,062	18,323
August .....	479	11	3,663	563	259	822	2,891	1,016	10	94	8,508	375	305	1,088	18,439
September .....	422	12	3,818	686	285	971	2,923	921	8	103	8,545	294	320	940	18,307
October .....	401	12	4,022	870	299	1,168	3,373	1,007	3	110	8,255	233	276	932	18,624
November .....	318	11	3,889	957	300	1,257	3,701	1,130	1	111	7,978	310	207	1,048	18,702
December .....	237	10	3,860	1,155	298	1,453	4,022	1,144	8	110	7,836	255	196	1,118	18,796
Average .....	342	11	3,776	812	277	1,089	3,197	1,078	8	100	8,034	260	217	1,099	18,120
2021 January .....	239	11	3,934	1,200	323	1,522	3,999	1,131	9	110	7,666	257	242	996	18,595
February .....	R 201	R 5	R 3,946	R 1,061	R 266	R 1,328	R 2,893	R 1,092	R 32	113	R 7,744	R 163	R 259	R 996	R 17,444
March .....	F 257	F 6	E 3,937	NA	NA	E 1,436	RF 3,194	E 1,123	RF 11	F 100	E 8,685	F 279	E 281	RE 1,344	E 19,217
April .....	F 326	F 5	E 4,090	NA	NA	E 1,078	F 3,398	E 1,206	F 4	F 105	E 8,937	F 244	E 162	E 1,222	E 19,698
4-Month Average .....	E 257	E 7	E 3,977	NA	NA	E 1,344	E 3,383	E 1,138	E 14	E 107	E 8,265	E 238	E 236	E 1,142	E 18,763
2020 4-Month Average .....	219	9	3,857	1,001	268	1,269	3,196	1,346	16	94	7,838	239	161	1,207	18,181
2019 4-Month Average .....	237	10	4,234	1,056	293	1,349	3,329	1,675	11	118	9,110	241	249	1,140	20,354

<sup>a</sup> Beginning in 2009, includes biodiesel and other renewable diesel fuel blended into distillate fuel oil. For 2011–2020, also includes biodiesel adjustments (supply of biodiesel not reported as input on surveys) reclassified as distillate fuel oil adjustments. Beginning in 2021, also includes renewable heating oil blended into distillate fuel oil.

<sup>b</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."

<sup>c</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.

<sup>d</sup> Beginning in 1957, includes kerosene-type jet fuel. For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other.")

<sup>e</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>f</sup> Petrochemical feedstocks, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1964, also includes special naphthas. Beginning in 1981,

also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel. Beginning in 2021, also includes renewable fuels (excluding fuel ethanol) products supplied.

R=Revised. E=Estimate. F=Forecast. NA=Not available. (s)=Less than 500 barrels per day and greater than -500 barrels per day.


Notes: • Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: See end of section.

**Figure 3.6 Heat Content of Petroleum Products Supplied by Type**


Total, 1949–2020



Petroleum Products Supplied as Share of Total Energy Consumption, 1949–2020



By Product, April 2021



[a] Includes refinery and blender net inputs of renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

[b] Includes kerosene-type jet fuel only.

[c] Includes fuel ethanol blended into motor gasoline.

[d] All petroleum products not separately displayed.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Sources: Tables 1.1 and 3.6.

**Table 3.6 Heat Content of Petroleum Products Supplied by Type**  
(Trillion Btu)

	Asphalt and Road Oil	Avia- tion Gasoline	Distil- late Fuel Oil <sup>a</sup>	Hydrocarbon Gas Liquids				Jet Fuel <sup>d</sup>	Kero- sene	Lubri- cants	Motor Gasoline <sup>e</sup>	Petro- leum Coke	Resid- ual Fuel Oil	Other <sup>f</sup>	Total
				Propane/Propylene			Total <sup>c</sup>								
				Pro- pane	Propy- lene	Total <sup>b</sup>									
1950 Total .....	435	199	2,300	E 204	E 18	E 222	326	( <sup>d</sup> )	668	236	5,015	90	3,482	546	13,298
1955 Total .....	615	354	3,385	E 352	E 30	E 383	562	301	662	258	6,640	147	3,502	798	17,225
1960 Total .....	734	298	3,992	E 543	E 47	E 589	866	739	563	259	7,631	328	3,517	947	19,874
1965 Total .....	890	222	4,519	E 733	E 63	E 796	1,170	1,215	553	286	8,806	444	3,691	1,390	23,184
1970 Total .....	1,082	100	5,401	E 1,019	E 77	E 1,096	1,667	1,973	544	301	11,091	465	5,057	1,817	29,499
1975 Total .....	1,014	71	6,061	E 1,024	E 84	E 1,108	1,811	2,047	329	304	12,798	542	5,649	2,071	32,699
1980 Total .....	962	64	6,110	E 1,043	E 100	E 1,143	2,135	2,190	329	354	12,648	522	5,772	3,073	34,159
1985 Total .....	1,029	50	6,098	E 1,136	E 101	E 1,237	2,252	2,497	236	322	13,098	582	2,759	1,945	30,866
1990 Total .....	1,170	45	6,422	E 1,138	E 147	E 1,285	2,259	3,129	88	362	13,872	745	2,820	2,589	33,500
1995 Total .....	1,178	40	6,812	E 1,316	E 220	E 1,536	2,791	3,132	112	346	14,794	802	1,955	2,499	34,458
2000 Total .....	1,276	36	7,927	E 1,421	E 315	E 1,735	3,216	3,580	140	369	16,127	895	2,091	2,636	38,292
2005 Total .....	1,323	35	8,745	E 1,382	E 341	E 1,723	2,812	3,475	144	312	17,358	1,125	2,111	3,122	40,561
2006 Total .....	1,261	33	8,831	E 1,328	E 375	E 1,703	2,768	3,379	111	303	17,511	1,141	1,581	3,276	40,196
2007 Total .....	1,197	32	8,858	E 1,379	E 352	E 1,731	2,835	3,358	67	313	17,428	1,072	1,659	3,134	39,952
2008 Total .....	1,012	28	8,346	E 1,299	E 323	E 1,622	2,656	3,193	30	291	16,799	1,017	1,432	2,788	37,591
2009 Total .....	873	27	7,657	E 1,252	E 374	E 1,626	2,707	2,883	36	262	16,714	937	1,173	2,483	35,752
2010 Total .....	878	27	8,011	E 1,194	E 428	E 1,621	2,881	2,963	41	291	16,632	831	1,228	2,645	36,427
2011 Total .....	859	27	8,211	E 1,194	E 434	E 1,628	2,811	2,950	25	276	16,175	801	1,058	2,621	35,815
2012 Total .....	827	25	7,898	E 1,212	E 432	E 1,645	2,887	2,901	11	254	16,085	802	849	2,474	35,012
2013 Total .....	783	22	8,051	E 1,358	E 429	E 1,787	3,166	2,969	11	268	16,332	786	731	2,583	35,702
2014 Total .....	793	22	8,492	E 1,219	E 417	E 1,636	3,067	3,042	19	280	16,473	772	590	2,430	35,978
2015 Total .....	832	21	8,402	E 1,212	E 413	E 1,626	3,221	3,204	13	305	16,941	776	595	2,435	36,745
2016 Total .....	853	20	8,170	E 1,171	E 423	E 1,594	3,184	3,350	18	289	17,238	771	751	2,553	37,198
2017 Total .....	849	21	8,263	E 1,126	E 432	E 1,557	3,272	3,481	11	267	17,201	708	784	2,667	37,525
2018 Total .....	793	22	8,715	E 1,245	E 436	E 1,680	3,720	3,533	11	259	17,209	730	729	2,630	38,351
2019 January .....	40	1	773	163	38	201	397	285	5	21	1,375	56	62	225	3,240
February .....	37	1	695	133	32	165	343	255	3	18	1,283	22	49	162	2,869
March .....	48	2	747	115	31	146	328	301	(s)	18	1,438	56	43	204	3,185
April .....	63	2	712	76	33	109	288	299	(s)	28	1,426	43	33	225	3,120
May .....	76	2	733	66	36	102	285	312	(s)	20	1,487	61	37	232	3,246
June .....	82	2	690	61	36	96	281	306	(s)	19	1,471	74	61	205	3,191
July .....	105	3	698	70	35	106	310	325	(s)	24	1,493	77	67	206	3,306
August .....	104	2	719	64	35	99	302	324	(s)	22	1,540	64	64	240	3,380
September .....	96	2	677	88	33	120	311	290	1	18	1,394	48	57	218	3,112
October .....	90	2	754	107	38	144	334	304	(s)	25	1,458	44	62	217	3,290
November .....	62	2	726	135	35	169	347	291	2	19	1,396	64	39	219	3,166
December .....	41	1	701	140	36	176	370	318	2	18	1,405	69	55	235	3,216
Total .....	844	23	8,625	1,217	418	1,635	3,897	3,608	14	250	17,166	678	631	2,585	38,322
2020 January .....	39	2	714	129	33	163	352	294	4	23	1,372	48	50	225	3,123
February .....	37	1	670	138	28	167	307	268	5	19	1,314	46	27	221	2,914
March .....	42	1	699	112	31	142	345	244	1	12	1,219	48	21	230	2,862
April .....	58	1	605	86	32	118	280	118	(s)	15	887	35	24	194	2,217
May .....	75	2	631	75	33	107	295	105	(s)	16	1,126	42	16	211	2,518
June .....	102	2	603	45	30	76	272	134	(s)	19	1,256	42	44	184	2,656
July .....	101	2	644	59	33	92	306	169	(s)	22	1,325	47	66	196	2,878
August .....	98	2	654	67	31	98	300	178	2	18	1,333	71	59	201	2,915
September .....	84	2	659	79	33	112	298	157	1	19	1,295	54	60	169	2,798
October .....	82	2	718	104	36	139	359	177	(s)	21	1,293	44	54	172	2,922
November .....	63	2	672	110	35	145	376	192	(s)	20	1,209	57	39	187	2,818
December .....	49	2	689	138	35	173	430	201	1	21	1,227	48	38	206	2,912
Total .....	831	20	7,956	1,142	389	1,531	3,918	2,237	16	223	14,855	582	499	2,396	33,533
2021 January .....	49	2	703	143	38	181	426	199	2	21	1,201	49	47	183	2,882
February .....	R 37	F 1	R 637	R 114	R 29	R 143	R 281	R 173	R 5	F 19	R 1,095	R 28	R 46	R 166	R 2,488
March .....	F 53	F 1	E 703	NA	NA	E 171	RF 332	E 197	RF 2	F 19	E 1,360	F 53	E 55	RE 237	E 3,012
April .....	F 65	F 1	E 706	NA	NA	E 124	F 341	E 205	F 1	F 19	E 1,354	F 45	E 31	E 220	E 2,988
4-Month Total .....	E 204	E 4	E 2,749	NA	NA	E 619	E 1,381	E 775	E 9	E 78	E 5,011	E 175	E 178	E 806	E 11,370
2020 4-Month Total .....	176	5	2,687	465	124	590	1,283	923	11	69	4,791	177	122	870	11,115
2019 4-Month Total .....	188	6	2,926	487	135	622	1,357	1,139	8	86	5,523	177	188	815	12,413

<sup>a</sup> Beginning in 2009, includes biodiesel and other renewable diesel fuel blended into distillate fuel oil. For 2011–2020, also includes biodiesel adjustments (supply of biodiesel not reported as input on surveys) reclassified as distillate fuel oil adjustments. Beginning in 2021, also includes renewable heating oil blended into distillate fuel oil.

<sup>b</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."

<sup>c</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.

<sup>d</sup> Beginning in 1957, includes kerosene-type jet fuel. For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other.")

<sup>e</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>f</sup> Petrochemical feedstocks, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1964, also includes special naphthas. Beginning in 1981,

also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel. Beginning in 2021, also includes renewable fuels (excluding fuel ethanol) products supplied.

R=Revised. E=Estimate. F=Forecast. NA=Not available. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.


Notes: • Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: See end of section.

**Figure 3.7 Petroleum Consumption by Sector**


By Sector, 1949–2020



By Sector, February 2021



Sector Shares, 1949 and 2020



[a] Includes combined-heat-and-power plants and a small number of electricity-only plants.

(s)=Less than 0.5 percent.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
Sources: Tables 3.7a–3.7c.

**Table 3.7a Petroleum Consumption: Residential and Commercial Sectors**  
(Thousand Barrels per Day)

	Residential Sector				Commercial Sector <sup>a</sup>						
	Distillate Fuel Oil	HGL <sup>b</sup>	Kero-sene	Total	Distillate Fuel Oil	HGL <sup>b</sup>	Kero-sene	Motor Gasoline <sup>c,d</sup>	Petroleum Coke	Residual Fuel Oil	Total
		Propane				Propane					
1950 Average .....	390	104	168	662	123	28	23	52	NA	185	411
1955 Average .....	562	144	179	885	177	38	24	69	NA	209	519
1960 Average .....	736	217	171	1,123	232	58	23	35	NA	243	590
1965 Average .....	805	275	161	1,242	251	74	26	40	NA	281	672
1970 Average .....	883	392	144	1,419	276	102	30	45	NA	311	764
1975 Average .....	850	365	78	1,293	276	92	24	46	NA	214	653
1980 Average .....	617	222	51	890	243	63	20	56	NA	245	626
1985 Average .....	514	224	77	815	297	68	16	50	NA	99	530
1990 Average .....	460	252	31	742	252	73	6	58	0	100	489
1995 Average .....	426	282	36	743	225	78	11	10	(s)	62	385
2000 Average .....	424	395	46	865	230	107	14	23	(s)	40	415
2005 Average .....	402	366	40	809	210	94	10	24	(s)	50	389
2006 Average .....	335	318	32	685	189	88	7	26	(s)	33	343
2007 Average .....	342	345	21	708	181	87	4	32	(s)	33	337
2008 Average .....	354	394	10	758	181	113	2	24	(s)	31	351
2009 Average .....	276	391	13	680	187	99	2	28	(s)	31	348
2010 Average .....	266	378	14	658	185	100	2	28	(s)	27	343
2011 Average .....	248	351	9	608	186	102	2	24	(s)	23	336
2012 Average .....	228	281	4	513	168	96	1	21	(s)	14	300
2013 Average .....	233	331	4	568	163	108	(s)	22	(s)	11	304
2014 Average .....	253	349	7	609	169	114	1	29	(s)	3	318
2015 Average .....	262	318	5	584	171	106	1	<sup>d</sup> 204	(s)	2	483
2016 Average .....	206	306	7	518	154	107	1	203	(s)	2	467
2017 Average .....	205	307	4	517	153	111	1	196	(s)	2	462
2018 Average .....	241	361	4	606	153	126	1	199	(s)	1	480
2019 January .....	383	754	20	1,157	266	209	3	189	(s)	2	669
February .....	353	710	13	1,076	245	199	2	195	(s)	2	643
March .....	282	592	(s)	874	196	172	(s)	197	(s)	1	568
April .....	187	353	1	542	130	119	(s)	202	(s)	1	453
May .....	142	254	1	397	99	97	(s)	204	0	1	400
June .....	123	166	1	290	86	77	(s)	209	0	1	372
July .....	115	144	1	261	80	72	(s)	205	0	1	358
August .....	177	148	(s)	325	123	73	(s)	211	0	1	408
September .....	102	171	4	278	71	78	1	198	0	(s)	348
October .....	154	322	2	478	107	112	(s)	200	0	1	420
November .....	312	576	9	897	217	169	2	198	0	1	587
December .....	358	652	11	1,020	249	186	2	193	(s)	2	631
Average .....	223	402	5	630	155	130	1	200	(s)	1	487
2020 January .....	292	660	18	970	203	185	3	188	(s)	1	581
February .....	256	<sup>R</sup> 630	23	<sup>R</sup> 909	178	178	4	193	(s)	1	<sup>R</sup> 555
March .....	224	477	5	706	156	144	1	167	0	1	469
April .....	208	396	2	606	145	126	(s)	126	0	1	398
May .....	227	243	(s)	471	158	92	(s)	155	0	1	405
June .....	148	150	1	299	103	71	(s)	178	0	1	353
July .....	96	135	1	232	67	68	(s)	182	0	(s)	317
August .....	85	137	8	229	59	68	1	183	0	(s)	312
September .....	146	175	6	327	102	76	1	184	0	1	364
October .....	164	308	2	474	114	106	(s)	177	0	1	399
November .....	205	443	1	649	143	136	(s)	171	0	1	452
December .....	249	667	6	922	173	187	1	168	0	1	530
Average .....	192	368	6	565	133	120	1	173	(s)	1	<sup>R</sup> 428
2021 January .....	238	705	7	949	165	195	1	165	0	1	527
February .....	270	758	24	1,053	188	207	4	166	(s)	1	567
2-Month Average .....	253	730	15	998	176	201	3	166	(s)	1	546
2020 2-Month Average .....	275	645	20	940	191	182	4	190	(s)	1	568
2019 2-Month Average .....	369	733	17	1,118	256	204	3	192	(s)	2	657

<sup>a</sup> Commercial sector fuel use, including that at commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Hydrocarbon gas liquids.

<sup>c</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>d</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>R</sup>=Revised. NA=Not available. (s)=Less than 500 barrels per day and greater than -500 barrels per day.

Notes: • Data are estimates. • For total petroleum consumption by all sectors, see petroleum products supplied data in Table 3.5. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 3.7b Petroleum Consumption: Industrial Sector**  
(Thousand Barrels per Day)

	Industrial Sector <sup>a</sup>												
	Asphalt and Road Oil	Distil- late Fuel Oil	Hydrocarbon Gas Liquids				Kero- sene	Lubri- cants	Motor Gasoline <sup>d,e</sup>	Petro- leum Coke	Resid- ual Fuel Oil	Other <sup>f</sup>	Total
			Propane/Propylene			Total <sup>c</sup>							
			Pro- pane	Propy- lene	Total <sup>b</sup>								
1950 Average .....	180	328	12	13	24	100	132	43	131	41	617	250	1,822
1955 Average .....	254	466	59	22	81	212	116	47	173	67	686	366	2,387
1960 Average .....	302	476	98	33	131	333	78	48	198	149	689	435	2,708
1965 Average .....	368	541	152	45	197	470	80	62	179	202	689	657	3,247
1970 Average .....	447	577	201	55	256	699	89	70	150	203	708	866	3,808
1975 Average .....	419	630	242	60	302	863	58	68	116	246	658	982	4,038
1980 Average .....	396	621	445	72	516	1,293	87	82	82	234	586	1,460	4,842
1985 Average .....	425	526	497	72	569	1,408	21	75	114	261	326	909	4,065
1990 Average .....	483	541	471	105	576	1,364	6	84	97	325	179	1,225	4,304
1995 Average .....	486	532	566	157	723	1,727	7	80	105	328	147	1,180	4,594
2000 Average .....	525	563	500	224	724	1,923	8	86	79	361	105	1,255	4,903
2005 Average .....	546	594	506	243	749	1,666	19	72	187	404	123	1,489	5,100
2006 Average .....	521	594	521	268	789	1,710	14	71	198	425	104	1,557	5,193
2007 Average .....	494	595	536	252	787	1,744	6	73	161	412	84	1,487	5,056
2008 Average .....	417	637	389	230	619	1,510	2	67	131	394	84	1,317	4,559
2009 Average .....	360	509	383	267	650	1,617	2	61	128	363	57	1,175	4,272
2010 Average .....	362	547	369	305	674	1,780	4	61	140	310	52	1,251	4,508
2011 Average .....	355	586	393	310	703	1,792	2	58	138	295	59	1,240	4,523
2012 Average .....	340	602	480	308	788	1,910	1	53	136	319	30	1,165	4,558
2013 Average .....	323	601	525	306	831	2,057	1	57	142	295	21	1,227	4,723
2014 Average .....	327	648	401	298	698	1,974	1	59	114	290	18	1,151	4,582
2015 Average .....	343	555	436	295	731	2,122	1	64	<sup>e</sup> 140	295	15	1,153	4,688
2016 Average .....	351	548	415	301	717	2,123	1	61	142	289	23	1,170	4,706
2017 Average .....	351	572	379	309	688	2,214	1	56	143	269	22	1,228	4,856
2018 Average .....	327	595	396	311	707	2,521	1	55	146	278	19	1,210	5,152
2019 January .....	195	773	404	320	724	2,747	3	54	136	242	21	1,217	5,388
February .....	201	720	324	299	623	2,677	2	50	141	79	19	969	4,858
March .....	232	652	194	265	459	2,367	(s)	46	143	258	15	1,102	4,814
April .....	318	613	180	289	469	2,409	(s)	74	146	210	12	1,261	5,043
May .....	369	603	202	302	504	2,390	(s)	51	147	274	12	1,257	5,103
June .....	413	485	278	311	589	2,505	(s)	50	151	368	21	1,144	5,136
July .....	510	422	369	297	666	2,708	(s)	61	148	357	22	1,110	5,338
August .....	507	419	315	294	608	2,628	(s)	54	153	293	20	1,299	5,374
September .....	480	529	507	283	789	2,787	1	46	143	226	19	1,222	5,452
October .....	438	671	456	316	772	2,709	(s)	62	145	221	21	1,172	5,437
November .....	310	585	419	301	721	2,649	1	50	143	326	14	1,222	5,299
December .....	198	409	330	306	635	2,656	1	45	139	332	19	1,275	5,074
Average .....	348	573	331	298	630	2,602	1	53	145	267	18	1,189	5,195
2020 January .....	191	762	238	282	520	2,547	2	59	136	209	16	1,217	<sup>R</sup> 5,139
February .....	191	784	431	254	685	2,396	3	51	139	228	10	1,276	<sup>R</sup> 5,079
March .....	204	654	311	257	568	2,685	1	29	121	213	7	1,247	5,161
April .....	292	341	220	278	497	2,330	(s)	39	91	152	8	1,088	4,341
May .....	365	295	<sup>R</sup> 286	274	561	2,541	(s)	39	112	182	5	1,143	4,682
June .....	511	287	168	263	431	2,534	(s)	49	129	177	15	1,026	4,728
July .....	491	387	287	275	563	2,814	(s)	55	131	197	22	1,062	5,158
August .....	479	421	<sup>R</sup> 354	259	613	2,681	1	45	132	328	20	1,088	5,194
September .....	422	543	430	285	715	2,668	1	49	133	268	20	940	5,043
October .....	401	652	451	299	749	2,954	(s)	52	128	213	17	932	5,350
November .....	318	616	374	300	<sup>R</sup> 673	3,117	(s)	52	124	275	13	1,048	5,563
December .....	237	588	297	298	595	3,164	1	52	122	211	13	1,118	5,505
Average .....	342	527	320	277	597	2,705	1	48	125	221	14	1,099	<sup>R</sup> 5,080
2021 January .....	239	782	295	323	618	3,095	1	52	119	214	15	913	5,431
February .....	201	659	92	266	358	1,923	3	54	120	115	17	885	3,977
2-Month Average .....	221	724	199	296	495	2,539	2	53	120	167	16	900	4,741
2020 2-Month Average .....	191	773	331	268	599	2,474	3	55	138	218	13	1,246	5,110
2019 2-Month Average .....	198	748	366	310	676	2,714	2	52	138	165	20	1,099	5,136

<sup>a</sup> Industrial sector fuel use, including that at industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>b</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."

<sup>c</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.

<sup>d</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>e</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>f</sup> Petrochemical feedstocks, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1964, also includes special naphthas. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified

as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

<sup>R</sup>=Revised. (s)=Less than 500 barrels per day and greater than -500 barrels per day.

Notes: • Data are estimates. • For total petroleum consumption by all sectors, see petroleum products supplied data in Table 3.5. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.



**Table 3.7c Petroleum Consumption: Transportation and Electric Power Sectors**  
(Thousand Barrels per Day)

	Transportation Sector									Electric Power Sector <sup>a</sup>			
	Aviation Gasoline	Distillate Fuel Oil <sup>c</sup>	HGL <sup>b</sup>	Jet Fuel <sup>e</sup>	Lubricants	Motor Gasoline <sup>f,g</sup>	Residual Fuel Oil	Other <sup>h</sup>	Total	Distillate Fuel Oil <sup>i</sup>	Petroleum Coke	Residual Fuel Oil	Total
			Propane <sup>d</sup>										
1950 Average .....	108	226	2	( <sup>e</sup> )	64	2,433	524	NA	3,356	15	NA	192	207
1955 Average .....	192	372	9	154	70	3,221	440	NA	4,458	15	NA	191	206
1960 Average .....	161	418	13	371	68	3,736	367	NA	5,135	10	NA	231	241
1965 Average .....	120	514	23	602	67	4,374	336	NA	6,036	14	NA	302	316
1970 Average .....	55	738	32	967	66	5,589	332	NA	7,778	66	9	853	928
1975 Average .....	39	998	31	992	70	6,512	310	NA	8,951	107	1	1,280	1,388
1980 Average .....	35	1,311	13	1,062	77	6,441	608	NA	9,546	79	2	1,069	1,151
1985 Average .....	27	1,491	21	1,218	71	6,667	342	NA	9,838	40	3	435	478
1990 Average .....	24	1,722	16	1,522	80	7,080	443	NA	10,888	45	14	507	566
1995 Average .....	21	1,973	13	1,514	76	7,674	397	NA	11,668	51	37	247	334
2000 Average .....	20	2,422	8	1,725	81	8,370	386	NA	13,012	82	45	378	505
2005 Average .....	19	2,858	20	1,679	68	8,948	365	NA	13,957	54	111	382	547
2006 Average .....	18	3,017	20	1,633	67	9,029	395	NA	14,178	35	97	157	289
2007 Average .....	17	3,037	16	1,622	69	9,093	433	NA	14,287	42	78	173	293
2008 Average .....	15	2,738	29	1,539	64	8,834	402	NA	13,621	34	70	104	209
2009 Average .....	14	2,626	20	1,393	57	8,841	344	( <sup>h</sup> )	13,297	33	63	79	175
2010 Average .....	15	2,764	<sup>d</sup> 5	1,432	70	8,824	389	( <sup>h</sup> )	13,499	38	65	67	170
2011 Average .....	15	2,849	5	1,425	67	8,591	338	( <sup>h</sup> )	13,291	30	66	41	137
2012 Average .....	14	2,719	5	1,398	61	8,525	291	( <sup>h</sup> )	13,013	25	41	33	99
2013 Average .....	12	2,804	5	1,434	65	8,679	253	( <sup>h</sup> )	13,253	26	59	34	119
2014 Average .....	12	2,928	5	1,470	67	8,778	195	( <sup>h</sup> )	13,455	39	57	41	137
2015 Average .....	11	2,974	5	1,548	74	8,835	202	( <sup>h</sup> )	13,650	33	54	41	128
2016 Average .....	11	2,944	5	1,614	70	8,973	271	( <sup>h</sup> )	13,888	26	57	31	113
2017 Average .....	11	2,976	5	1,682	64	8,988	290	( <sup>h</sup> )	14,016	26	47	29	101
2018 Average .....	12	3,118	5	1,707	62	8,984	263	( <sup>h</sup> )	14,152	38	49	34	121
2019 January .....	9	2,868	5	1,621	60	8,453	263	( <sup>h</sup> )	13,279	38	52	33	123
February .....	9	2,963	5	1,607	55	8,736	238	( <sup>h</sup> )	13,612	26	48	21	95
March .....	13	3,031	5	1,711	51	8,844	185	( <sup>h</sup> )	13,840	23	37	20	80
April .....	12	3,168	5	1,756	82	9,062	144	( <sup>h</sup> )	14,229	21	25	21	67
May .....	15	3,240	5	1,773	56	9,146	155	( <sup>h</sup> )	14,390	26	47	24	97
June .....	16	3,272	5	1,802	55	9,344	274	( <sup>h</sup> )	14,768	26	35	27	88
July .....	17	3,269	5	1,847	68	9,180	291	( <sup>h</sup> )	14,677	24	48	29	101
August .....	13	3,287	5	1,841	60	9,470	277	( <sup>h</sup> )	14,953	24	43	31	98
September .....	15	3,195	5	1,702	51	8,857	258	( <sup>h</sup> )	14,083	23	38	27	87
October .....	14	3,270	5	1,727	69	8,964	272	( <sup>h</sup> )	14,319	23	11	26	60
November .....	12	3,062	5	1,711	55	8,868	169	( <sup>h</sup> )	13,883	25	21	24	70
December .....	9	2,885	5	1,809	50	8,639	239	( <sup>h</sup> )	13,635	27	31	25	83
Average .....	13	3,127	5	1,743	59	8,965	231	( <sup>h</sup> )	14,142	26	36	26	88
2020 January .....	14	2,714	5	1,673	65	8,436	215	( <sup>h</sup> )	13,122	27	41	25	93
February .....	8	2,768	5	1,629	57	8,635	118	( <sup>h</sup> )	13,219	23	32	21	77
March .....	8	2,861	5	1,387	33	7,493	83	( <sup>h</sup> )	11,869	19	42	19	79
April .....	6	2,795	5	691	43	5,637	98	( <sup>h</sup> )	9,275	16	37	18	72
May .....	14	2,835	5	596	44	6,922	56	( <sup>h</sup> )	10,470	19	37	19	75
June .....	11	2,930	5	786	55	7,979	193	( <sup>h</sup> )	11,958	24	50	24	98
July .....	13	3,034	5	964	61	8,145	293	( <sup>h</sup> )	12,514	25	50	26	101
August .....	11	3,075	5	1,016	49	8,193	259	( <sup>h</sup> )	12,608	23	47	26	96
September .....	12	3,009	5	921	54	8,229	275	( <sup>h</sup> )	12,505	18	26	25	69
October .....	12	3,069	5	1,007	58	7,950	232	( <sup>h</sup> )	12,332	22	21	26	69
November .....	11	2,904	5	1,130	58	7,682	170	( <sup>h</sup> )	11,960	21	34	23	79
December .....	10	2,826	5	1,144	58	7,546	158	( <sup>h</sup> )	11,746	24	44	24	92
Average .....	11	2,902	5	1,078	53	7,736	179	( <sup>h</sup> )	11,964	22	39	23	83
2021 January .....	11	2,728	5	1,131	58	7,383	198	82	11,596	21	43	28	91
February .....	5	2,761	5	1,092	60	7,457	211	112	11,702	67	48	30	145
2-Month Average .....	9	2,744	5	1,112	59	7,418	204	96	11,647	43	45	29	117
2020 2-Month Average .....	11	2,740	5	1,652	61	8,532	168	( <sup>h</sup> )	13,169	25	37	23	85
2019 2-Month Average .....	9	2,913	5	1,614	58	8,587	251	( <sup>h</sup> )	13,437	32	50	27	110

<sup>a</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>b</sup> Hydrocarbon gas liquids.

<sup>c</sup> Beginning in 2009, includes biodiesel and other renewable diesel fuel blended into distillate fuel oil. For 2011–2020, also includes biodiesel adjustments (supply of biodiesel not reported as input on surveys) reclassified as distillate fuel oil adjustments.

<sup>d</sup> There is a discontinuity in this time series between 2009 and 2010 due to a change in data sources.

<sup>e</sup> Beginning in 1957, includes kerosene-type jet fuel. For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other" on Table 3.7b.)

<sup>f</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>g</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>h</sup> Renewable fuels (excluding fuel ethanol) products supplied. Includes supply

of non-fuel ethanol biofuels (such as B100 biodiesel and R100 renewable diesel fuel) not reported as input on surveys. For 2009–2020, data in this category were classified as renewable fuels (excluding fuel ethanol) adjustments.

<sup>i</sup> Fuel oil nos. 1, 2, and 4. Through 1979, data are for gas turbine and internal combustion plant use of petroleum. Through 2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>j</sup> Fuel oil nos. 5 and 6. Through 1979, data are for steam plant use of petroleum. Through 2000, electric utility data also include a small amount of fuel oil no. 4.

NA=Not available.

Notes: • Transportation sector data are estimates. • For total petroleum consumption by all sectors, see petroleum products supplied data in Table 3.5. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: See end of section.

This table has been modified to include a column for "Other" consumption in the Transportation Sector.


**Figure 3.8a Heat Content of Petroleum Consumption by End-Use Sector, 1949-2020**

(Quadrillion Btu)


Residential and Commercial [a] Sectors, Selected Products



Industrial [a] Sector, Selected Products



Transportation Sector, Selected Products



[a] Includes combined-heat-and-power plants and a small number of electricity-only plants.

[b] Hydrocarbon gas liquids.

[c] Beginning in 1993, includes fuel ethanol blended into motor gasoline.

[d] From 2009–2020, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil. Beginning in 2021, includes refinery and blender net inputs of renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

[e] Beginning in 2005, includes kerosene-type jet fuel only.

Note: Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term “petroleum consumption” in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft.


Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Sources: Tables 3.8a–3.8c.


**Figure 3.8b Heat Content of Petroleum Consumption by End-Use Sector, Monthly**

(Quadrillion Btu)


Residential and Commercial [a] Sectors, Selected Products



Industrial [a] Sector, Selected Products



Transportation Sector, Selected Products



[a] Includes combined-heat-and-power plants and a small number of electricity-only plants.

[b] Hydrocarbon gas liquids.

[c] Includes fuel ethanol blended into motor gasoline.

[d] Through 2020, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil. Beginning in 2021, includes refinery and blender net inputs of renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

[e] Includes kerosene-type jet fuel only.

Note: Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Sources: Tables 3.8a–3.8c.

**Table 3.8a Heat Content of Petroleum Consumption: Residential and Commercial Sectors**  
(Trillion Btu)

	Residential Sector				Commercial Sector <sup>a</sup>						
	Distillate Fuel Oil	HGL <sup>b</sup>	Kero-sene	Total	Distillate Fuel Oil	HGL <sup>b</sup>	Kero-sene	Motor Gasoline <sup>c,d</sup>	Petroleum Coke	Residual Fuel Oil	Total
		Propane				Propane					
1950 Total .....	829	146	347	1,322	262	39	47	100	NA	424	872
1955 Total .....	1,194	202	371	1,767	377	54	51	133	NA	480	1,095
1960 Total .....	1,568	305	354	2,228	494	81	48	67	NA	559	1,248
1965 Total .....	1,713	386	334	2,432	534	103	54	77	NA	645	1,413
1970 Total .....	1,878	549	298	2,726	587	143	61	86	NA	714	1,592
1975 Total .....	1,807	512	161	2,479	587	130	49	89	NA	492	1,346
1980 Total .....	1,316	312	107	1,734	518	88	41	107	NA	565	1,318
1985 Total .....	1,092	315	159	1,566	631	95	33	96	NA	228	1,083
1990 Total .....	978	353	64	1,395	536	102	12	111	0	230	991
1995 Total .....	904	395	74	1,374	478	109	22	18	(s)	141	769
2000 Total .....	904	556	95	1,554	490	151	30	44	(s)	92	807
2005 Total .....	853	514	84	1,450	447	132	22	46	(s)	116	762
2006 Total .....	709	446	66	1,222	400	123	15	48	(s)	75	662
2007 Total .....	721	484	44	1,249	381	122	9	60	(s)	75	648
2008 Total .....	750	553	21	1,325	384	158	4	45	(s)	71	663
2009 Total .....	582	548	28	1,158	395	139	4	52	(s)	71	662
2010 Total .....	562	530	29	1,120	391	140	5	52	(s)	62	650
2011 Total .....	523	493	19	1,034	391	143	3	44	(s)	54	635
2012 Total .....	482	396	8	886	355	136	1	39	(s)	31	562
2013 Total .....	491	463	8	963	344	152	1	40	(s)	24	561
2014 Total .....	533	490	14	1,036	357	160	2	54	1	8	581
2015 Total .....	551	446	10	1,007	360	148	1	<sup>d</sup> 376	1	4	890
2016 Total .....	435	430	14	878	326	150	2	375	(s)	4	858
2017 Total .....	432	431	8	871	323	156	1	361	(s)	4	845
2018 Total .....	508	507	8	1,022	323	176	1	366	(s)	3	870
2019 January .....	68	90	4	162	48	25	1	30	(s)	(s)	103
February .....	57	76	2	135	40	21	(s)	28	(s)	(s)	89
March .....	50	70	(s)	121	35	21	(s)	31	(s)	(s)	87
April .....	32	41	(s)	73	23	14	(s)	31	(s)	(s)	67
May .....	25	30	(s)	56	18	12	(s)	32	0	(s)	61
June .....	21	19	(s)	41	15	9	(s)	32	0	(s)	55
July .....	21	17	(s)	38	14	9	(s)	32	0	(s)	55
August .....	32	18	(s)	49	22	9	(s)	33	0	(s)	64
September .....	18	20	1	38	12	9	(s)	30	0	(s)	52
October .....	28	38	(s)	66	19	13	(s)	31	0	(s)	64
November .....	54	66	2	122	38	19	(s)	30	0	(s)	88
December .....	64	78	2	143	44	22	(s)	30	(s)	(s)	97
Total .....	471	563	11	1,045	327	182	2	369	(s)	2	883
2020 January .....	52	79	3	134	36	22	1	29	(s)	(s)	89
February .....	43	70	4	117	30	20	1	28	(s)	(s)	79
March .....	40	57	1	98	28	17	(s)	26	0	(s)	72
April .....	36	46	(s)	82	25	15	(s)	19	0	(s)	59
May .....	41	29	(s)	70	28	11	(s)	24	0	(s)	64
June .....	26	17	(s)	43	18	8	(s)	27	0	(s)	53
July .....	17	16	(s)	33	12	8	(s)	28	0	(s)	49
August .....	15	16	1	33	11	8	(s)	29	0	(s)	48
September .....	25	20	1	46	18	9	(s)	28	0	(s)	55
October .....	29	37	(s)	66	20	13	(s)	28	0	(s)	61
November .....	36	51	(s)	87	25	16	(s)	26	0	(s)	67
December .....	45	79	1	125	31	22	(s)	26	0	(s)	80
Total .....	405	517	12	934	281	168	2	319	(s)	2	773
2021 January .....	43	84	1	128	30	23	(s)	26	0	(s)	79
February .....	44	82	4	129	30	22	1	24	(s)	(s)	77
2-Month Total .....	86	165	5	257	60	45	1	49	(s)	(s)	156
2020 2-Month Total .....	95	149	7	251	66	42	1	58	(s)	(s)	168
2019 2-Month Total .....	125	166	6	297	87	46	1	57	(s)	1	192

<sup>a</sup> Commercial sector fuel use, including that at commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Hydrocarbon gas liquids.

<sup>c</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>d</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

NA=Not available. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.

Notes: • Data are estimates. • For total heat content of petroleum consumption by all sectors, see data for heat content of petroleum products supplied in Table 3.6. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 3.8b Heat Content of Petroleum Consumption: Industrial Sector**  
(Trillion Btu)

	Industrial Sector <sup>a</sup>												
	Asphalt and Road Oil	Distil- late Fuel Oil	Hydrocarbon Gas Liquids				Kero- sene	Lubri- cants	Motor Gasoline <sup>d,e</sup>	Petro- leum Coke	Resid- ual Fuel Oil	Other <sup>f</sup>	Total
			Propane/Propylene			Total <sup>c</sup>							
			Pro- pane	Propy- lene	Total <sup>b</sup>								
1950 Total .....	435	698	17	18	34	138	274	94	251	90	1,416	546	3,943
1955 Total .....	615	991	83	30	113	293	241	103	332	147	1,573	798	5,093
1960 Total .....	734	1,016	137	47	184	461	161	107	381	328	1,584	947	5,720
1965 Total .....	890	1,150	213	63	276	649	165	137	342	444	1,582	1,390	6,750
1970 Total .....	1,082	1,226	282	77	359	930	185	155	288	446	1,624	1,817	7,754
1975 Total .....	1,014	1,339	339	84	423	1,126	119	149	223	540	1,509	2,071	8,092
1980 Total .....	962	1,324	625	100	726	1,718	181	182	158	516	1,349	3,073	9,463
1985 Total .....	1,029	1,119	696	101	798	1,813	44	166	218	575	748	1,944	7,655
1990 Total .....	1,170	1,150	660	147	807	1,781	12	186	185	714	411	2,588	8,199
1995 Total .....	1,178	1,130	794	220	1,014	2,269	15	178	200	721	337	2,498	8,525
2000 Total .....	1,276	1,199	703	315	1,017	2,498	16	190	150	796	241	2,635	8,999
2005 Total .....	1,323	1,262	709	341	1,050	2,138	39	160	354	894	281	3,122	9,574
2006 Total .....	1,261	1,258	731	375	1,106	2,171	30	156	374	938	239	3,276	9,703
2007 Total .....	1,197	1,256	751	352	1,103	2,207	13	161	302	910	193	3,134	9,373
2008 Total .....	1,012	1,348	547	323	870	1,904	4	150	245	870	194	2,788	8,514
2009 Total .....	873	1,073	537	374	911	1,992	4	135	238	805	130	2,483	7,733
2010 Total .....	878	1,153	517	428	944	2,204	7	136	260	694	120	2,645	8,096
2011 Total .....	859	1,236	551	434	985	2,169	4	127	254	663	135	2,621	8,069
2012 Total .....	827	1,271	674	432	1,107	2,349	2	118	252	717	70	2,474	8,080
2013 Total .....	783	1,266	736	429	1,164	2,544	1	125	263	663	48	2,583	8,277
2014 Total .....	793	1,366	562	417	979	2,409	3	131	210	653	41	2,430	8,035
2015 Total .....	832	1,170	611	413	1,025	2,620	2	142	<sup>e</sup> 258	663	34	2,435	8,155
2016 Total .....	853	1,157	584	423	1,007	2,597	2	135	262	653	52	2,553	8,265
2017 Total .....	849	1,205	532	432	964	2,679	1	125	264	610	50	2,667	8,451
2018 Total .....	793	1,254	556	436	991	3,030	2	122	269	629	43	2,630	8,772
2019 January .....	40	138	48	38	86	282	(s)	10	21	47	4	225	768
February .....	37	116	35	32	67	245	(s)	8	20	14	3	162	607
March .....	48	117	23	31	55	237	(s)	9	22	49	3	204	688
April .....	63	106	21	33	54	233	(s)	13	22	39	2	225	704
May .....	76	108	24	36	60	243	(s)	9	23	53	2	232	746
June .....	82	84	32	36	68	252	(s)	9	23	68	4	205	727
July .....	105	76	44	35	79	283	(s)	11	23	68	4	206	777
August .....	104	75	37	35	72	275	(s)	10	24	56	4	240	788
September .....	96	92	58	33	91	282	(s)	8	22	42	4	218	762
October .....	90	120	54	38	92	282	(s)	12	23	42	4	217	790
November .....	62	101	48	35	83	261	(s)	9	22	60	3	219	736
December .....	41	73	39	36	76	270	(s)	8	22	63	4	235	716
Total .....	844	1,206	465	418	882	3,144	1	118	267	602	41	2,585	8,809
2020 January .....	39	136	28	33	62	251	(s)	11	21	40	3	225	727
February .....	37	131	48	28	76	216	(s)	9	20	41	2	221	678
March .....	42	117	37	31	68	270	(s)	6	19	41	1	230	726
April .....	58	59	25	32	57	219	(s)	7	14	28	1	194	581
May .....	75	53	34	33	67	255	(s)	7	17	35	1	211	655
June .....	102	50	19	30	50	246	(s)	9	19	33	3	184	645
July .....	101	69	34	33	67	281	(s)	10	21	38	4	196	721
August .....	98	75	42	31	73	275	(s)	8	21	63	4	201	745
September .....	84	94	50	33	82	269	(s)	9	20	50	4	169	698
October .....	82	117	54	36	89	309	(s)	10	20	41	3	172	754
November .....	63	107	43	35	78	309	(s)	10	19	51	2	187	748
December .....	49	105	35	35	71	328	(s)	10	19	41	2	206	760
Total .....	831	1,113	450	389	839	3,226	2	106	231	502	32	2,396	8,438
2021 January .....	49	140	35	38	74	319	(s)	10	19	41	3	169	750
February .....	37	106	10	29	38	177	1	9	17	20	3	149	519
2-Month Total .....	87	246	45	67	112	495	1	19	36	61	6	318	1,269
2020 2-Month Total .....	76	268	76	62	138	467	1	20	42	81	5	445	1,405
2019 2-Month Total .....	77	255	83	70	153	527	1	19	41	61	7	387	1,375

<sup>a</sup> Industrial sector fuel use, including that at industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>b</sup> Propane and propylene. Through 1983, also includes 40% of "Butane-Propane Mixtures" and 30% of "Ethane-Propane Mixtures."

<sup>c</sup> Ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). Through 1983, also includes plant condensate and unfractionated stream.

<sup>d</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>e</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>f</sup> Petrochemical feedstocks, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1964, also includes special naphthas. Beginning in 1981,

also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

(s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.

Notes: • Data are estimates. • For total heat content of petroleum consumption by all sectors, see data for heat content of petroleum products supplied in Table 3.6. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 3.8c Heat Content of Petroleum Consumption: Transportation and Electric Power Sectors** (Trillion Btu)

	Transportation Sector									Electric Power Sector <sup>a</sup>			
	Aviation Gasoline	Distillate Fuel Oil <sup>c</sup>	HGL <sup>b</sup>	Jet Fuel <sup>e</sup>	Lubricants	Motor Gasoline <sup>f,g</sup>	Residual Fuel Oil	Other <sup>h</sup>	Total	Distillate Fuel Oil <sup>i</sup>	Petroleum Coke	Residual Fuel Oil	Total
			Propane <sup>d</sup>										
1950 Total .....	199	480	3	( <sup>e</sup> )	141	4,664	1,201	NA	6,690	32	NA	440	472
1955 Total .....	354	791	13	301	155	6,175	1,009	NA	8,799	32	NA	439	471
1960 Total .....	298	892	19	739	152	7,183	844	NA	10,125	22	NA	530	553
1965 Total .....	222	1,093	32	1,215	149	8,386	770	NA	11,866	29	NA	693	722
1970 Total .....	100	1,569	44	1,973	147	10,716	761	NA	15,311	141	19	1,958	2,117
1975 Total .....	71	2,121	43	2,029	155	12,485	711	NA	17,615	226	2	2,937	3,166
1980 Total .....	64	2,795	18	2,179	172	12,383	1,398	NA	19,009	169	5	2,459	2,634
1985 Total .....	50	3,170	30	2,497	156	12,784	786	NA	19,472	85	7	998	1,090
1990 Total .....	45	3,661	23	3,129	176	13,575	1,016	NA	21,626	97	30	1,163	1,289
1995 Total .....	40	4,191	18	3,132	168	14,576	911	NA	23,036	108	81	566	755
2000 Total .....	36	5,159	12	3,580	179	15,933	888	NA	25,787	175	99	871	1,144
2005 Total .....	35	6,068	28	3,475	151	16,958	837	NA	27,553	114	231	876	1,222
2006 Total .....	33	6,390	28	3,379	147	17,088	906	NA	27,972	73	203	361	637
2007 Total .....	32	6,411	22	3,358	152	17,066	994	NA	28,034	89	163	397	648
2008 Total .....	28	5,792	40	3,193	141	16,510	926	NA	26,630	73	146	240	459
2009 Total .....	27	5,537	28	2,883	127	16,425	791	( <sup>h</sup> )	25,817	70	132	181	382
2010 Total .....	27	5,826	<sup>d</sup> 7	2,963	155	16,320	892	( <sup>h</sup> )	26,190	80	137	154	370
2011 Total .....	27	5,997	7	2,950	148	15,877	776	( <sup>h</sup> )	25,783	64	138	93	295
2012 Total .....	25	5,736	7	2,901	135	15,795	671	( <sup>h</sup> )	25,270	52	85	77	214
2013 Total .....	22	5,894	7	2,969	143	16,030	581	( <sup>h</sup> )	25,646	55	123	77	255
2014 Total .....	22	6,154	7	3,042	149	16,209	447	( <sup>h</sup> )	26,030	82	118	95	295
2015 Total .....	21	6,251	7	3,204	163	<sup>g</sup> 16,308	463	( <sup>h</sup> )	26,417	70	112	94	276
2016 Total .....	20	6,197	8	3,350	154	16,601	623	( <sup>h</sup> )	26,954	55	118	71	244
2017 Total .....	21	6,248	7	3,481	142	16,576	665	( <sup>h</sup> )	27,140	55	97	66	218
2018 Total .....	22	6,550	7	3,533	137	16,573	604	( <sup>h</sup> )	27,426	81	101	78	260
2019 January .....	1	512	1	285	11	1,324	51	( <sup>h</sup> )	2,185	7	9	6	22
February .....	1	477	1	255	9	1,236	42	( <sup>h</sup> )	2,021	4	8	4	16
March .....	2	541	1	301	10	1,385	36	( <sup>h</sup> )	2,275	4	7	4	15
April .....	2	547	1	299	15	1,373	27	( <sup>h</sup> )	2,263	4	4	4	12
May .....	2	578	1	312	11	1,432	30	( <sup>h</sup> )	2,366	5	8	5	18
June .....	2	565	1	306	10	1,416	52	( <sup>h</sup> )	2,352	5	6	5	16
July .....	3	583	1	325	13	1,438	57	( <sup>h</sup> )	2,418	4	8	6	18
August .....	2	586	1	324	11	1,483	54	( <sup>h</sup> )	2,461	4	8	6	18
September .....	2	552	1	290	9	1,342	49	( <sup>h</sup> )	2,244	4	6	5	15
October .....	2	583	1	304	13	1,404	53	( <sup>h</sup> )	2,359	4	2	5	11
November .....	2	529	1	291	10	1,344	32	( <sup>h</sup> )	2,208	4	4	5	13
December .....	1	515	1	318	9	1,353	47	( <sup>h</sup> )	2,243	5	6	5	15
Total .....	23	6,567	7	3,608	131	16,531	529	( <sup>h</sup> )	27,397	54	76	59	189
2020 January .....	2	484	1	294	12	1,321	42	( <sup>h</sup> )	2,156	5	7	5	17
February .....	1	462	1	268	10	1,265	21	( <sup>h</sup> )	2,028	4	5	4	13
March .....	1	510	1	244	6	1,173	16	( <sup>h</sup> )	1,952	3	7	4	14
April .....	1	482	1	118	8	854	18	( <sup>h</sup> )	1,482	3	6	3	13
May .....	2	506	1	105	8	1,084	11	( <sup>h</sup> )	1,716	3	7	4	14
June .....	2	506	1	134	10	1,209	36	( <sup>h</sup> )	1,897	4	9	4	17
July .....	2	541	1	169	11	1,276	57	( <sup>h</sup> )	2,057	5	9	5	18
August .....	2	549	1	178	9	1,283	50	( <sup>h</sup> )	2,072	4	8	5	17
September .....	2	519	1	157	10	1,247	52	( <sup>h</sup> )	1,987	3	4	5	12
October .....	2	547	1	177	11	1,245	45	( <sup>h</sup> )	2,028	4	4	5	13
November .....	2	501	1	192	11	1,164	32	( <sup>h</sup> )	1,903	4	6	4	14
December .....	2	504	1	201	11	1,182	31	( <sup>h</sup> )	1,930	4	8	5	17
Total .....	20	6,111	6	2,237	117	14,305	413	( <sup>h</sup> )	23,209	46	81	53	180
2021 January .....	2	487	1	199	11	1,156	39	14	1,908	4	8	5	17
February .....	1	446	(s)	173	10	1,055	37	17	1,739	11	8	5	24
2-Month Total .....	3	933	1	372	21	2,211	76	31	3,647	15	15	11	41
2020 2-Month Total .....	3	946	1	562	22	2,586	63	( <sup>h</sup> )	4,184	9	13	9	30
2019 2-Month Total .....	3	989	1	540	21	2,560	93	( <sup>h</sup> )	4,206	11	17	10	38

<sup>a</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>b</sup> Hydrocarbon gas liquids.

<sup>c</sup> Beginning in 2009, includes biodiesel and other renewable diesel fuel blended into distillate fuel oil. For 2011–2020, also includes biodiesel adjustments (supply of biodiesel not reported as input on surveys) reclassified as distillate fuel oil adjustments.

<sup>d</sup> There is a discontinuity in this time series between 2009 and 2010 due to a change in data sources.

<sup>e</sup> Beginning in 1957, includes kerosene-type jet fuel. For 1952–2004, also includes naphtha-type jet fuel. (Through 1951, naphtha-type jet fuel is included in the products from which it was blended—gasoline, kerosene, and distillate fuel oil. Beginning in 2005, naphtha-type jet fuel is included in "Other" on Table 3.8b.)

<sup>f</sup> Finished motor gasoline. Through 1963, also includes special naphthas. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>g</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of motor gasoline consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>h</sup> Renewable fuels (excluding fuel ethanol) products supplied. Includes supply of non-fuel ethanol biofuels (such as B100 biodiesel and R100 renewable diesel

fuel) not reported as input on surveys. For 2009–2020, data in this category were classified as renewable fuels (excluding fuel ethanol) adjustments.

<sup>i</sup> Fuel oil nos. 1, 2, and 4. Through 1979, data are for gas turbine and internal combustion plant use of petroleum. Through 2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>j</sup> Fuel oil nos. 5 and 6. Through 1979, data are for steam plant use of petroleum. Through 2000, electric utility data also include a small amount of fuel oil no. 4.

NA=Not available. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.

Notes: • Transportation sector data are estimates. • For total heat content of petroleum consumption by all sectors, see data for heat content of petroleum products supplied in Table 3.6. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft. See Note 1, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

This table has been modified to include a column for "Other" consumption in the Transportation Sector.

## Petroleum

**Note 1. Petroleum Products Supplied and Petroleum Consumption.** Total petroleum products supplied is the sum of the products supplied for each petroleum product, crude oil, unfinished oils, and gasoline blending components. This also includes petroleum products supplied for non-combustion use in the industrial and transportation sectors (see Tables 1.11a and 1.11b). In general, except for crude oil, product supplied of each product is computed as follows: field production, plus renewable fuels and oxygenate plant net production, plus refinery and blender net production, plus imports, plus net receipts, plus adjustments, minus stock change, minus refinery and blender net inputs, minus exports. Crude oil product supplied is the sum of crude oil burned on leases and at pipeline pump stations as reported on Form EIA-813, "Monthly Crude Oil Report." Prior to 1983, crude oil burned on leases and used at pipeline pump stations was reported as either distillate or residual fuel oil and was included as product supplied for these products. Petroleum product supplied (see Tables 3.5 and 3.6) is an approximation of petroleum consumption and is synonymous with the term "Petroleum Consumption" in Tables 3.7a–3.8c.

**Note 2. Petroleum Survey Respondents.** The U.S. Energy Information Administration (EIA) uses a number of sources and methods to maintain the survey respondent lists. On a regular basis, survey managers review such industry publications as the *Oil & Gas Journal* and *Oil Daily* for information on facilities or companies starting up or closing down operations. Those sources are augmented by articles in newspapers, communications from respondents indicating changes in status, and information received from survey systems.

To supplement routine frames maintenance and to provide more thorough coverage, a comprehensive frames investigation is conducted every 3 years. This investigation results in the reassessment and recompilation of the complete frame for each survey. The effort also includes the evaluation of the impact of potential frame changes on the historical time series of data from these respondents. The results of this frame study are usually implemented in January to provide a full year under the same frame.

**Note 3. Historical Petroleum Data.** Detailed information on petroleum data through 1993 can be found in Notes 1–6 on pages 60 and 61 in the July 2013 *Monthly Energy Review* (MER) at <http://www.eia.gov/totalenergy/data/monthly/archive/00351307.pdf>. The notes discuss:

Note 1, "Petroleum Survey Respondents": In 1993, EIA added numerous companies that produce, blend, store, or import oxygenates to the monthly surveys.

Note 2, "Motor Gasoline": In 1981, EIA expanded its universe to include nonrefinery blenders and separated blending components from finished motor gasoline as a reporting category. In 1993, EIA made adjustments to finished motor gasoline product supplied data to more accurately account for fuel ethanol and motor gasoline blending components blended into finished motor gasoline.

Note 3, "Distillate and Residual Fuel Oils": In 1981, EIA eliminated the requirement to report crude oil in pipelines or burned on leases as either distillate or residual fuel oil.

Note 4, "Petroleum New Stock Basis": In 1975, 1979, 1981, and 1983, EIA added numerous respondents to bulk terminal and pipeline surveys; in 1984, EIA made changes in the reporting of natural gas liquids; and in 1993, EIA changed how it collected bulk terminal and pipeline stocks of oxygenates. These changes affected stocks reported and stock change calculations.

Note 5, "Stocks of Alaskan Crude Oil": In 1981, EIA began to include data for stocks of Alaskan crude oil in transit.

Note 6, "Petroleum Data Discrepancies": In 1976, 1978, and 1979, there are some small discrepancies between data in the MER and the *Petroleum Supply Annual*.

### Table 3.1 Sources

1949–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports.

1976–1980: U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports.

1981–2001: EIA, *Petroleum Supply Annual* (PSA), annual reports.

2002 forward: EIA, PSA, annual reports, and unpublished revisions; *Petroleum Supply Monthly*, monthly reports; revisions to crude oil production, total field production, and adjustments (based on crude oil production data from: Form EIA-914, "Monthly Crude Oil, Lease Condensate, and Natural Gas Production Report"; state government agencies; U.S. Department of the Interior, Bureau of Safety and Environmental Enforcement, and predecessor agencies; and Form EIA-182, "Domestic Crude Oil First Purchase Report"); and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.

## Table 3.2 Sources

1949–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports; and U.S. Energy Information Administration (EIA) estimates. (For 1967–1975, refinery and blender net production estimates for propylene are equal to "Propane/Propylene Production at Refineries for Chemical Use"; and estimates for propane are equal to total propane/propylene minus propylene.)

1976–1980: EIA, Energy Data Reports, *Petroleum Statement, Annual*, annual reports, and estimates. (Refinery and blender net production estimates for propylene are equal to "Propane/Propylene Production at Refineries for Chemical Use"; and estimates for propane are equal to total propane/propylene minus propylene.)

1981–2019: EIA, *Petroleum Supply Annual*, annual reports, unpublished revisions, and estimates. (For 1981–1985, refinery and blender net production estimates for propylene are equal to "Propane/Propylene Production at Refineries for Petrochemical Use"; and estimates for propane are equal to total propane/propylene minus propylene. For 1986–1988, refinery and blender net production estimates for propylene are created using the 1989 annual propylene share of "Net Refinery Production of Propane/Propylene"; and estimates for propane are equal to total propane/propylene minus propylene.)

2020 and 2021: EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system, Short-Term Integrated Forecasting System, and *Monthly Energy Review* data system calculations.

## Table 3.5 Sources

1949–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports; and U.S. Energy Information Administration (EIA) estimates. (For 1949–1966, product supplied estimates for total propane/propylene are created using sales and shipments data from Bureau of Mines, Mineral Industry Surveys, *Sales of Liquefied Petroleum Gases and Ethane*, annual reports, and *Shipments of Liquefied Petroleum Gases and Ethane*, annual reports—annual growth rates of sales and shipments are applied to the 1967 total propane/propylene product supplied value to create historical annual estimates. For 1949–1966, product supplied estimates for propylene are created using the 1967 annual propylene share of total propane/propylene product supplied; and estimates for propane are equal to total propane/propylene minus propylene. For 1967–1975, product supplied estimates for propylene are equal to propylene refinery and blender net production from Table 3.2; and estimates for propane are equal to total propane/propylene minus propylene.)

1976–1980: EIA, Energy Data Reports, *Petroleum Statement, Annual*, annual reports, and estimates. (Product supplied estimates for propylene are equal to propylene refinery and blender net production from Table 3.2; and estimates for propane are equal to total propane/propylene minus propylene.)

1981–2019: EIA, *Petroleum Supply Annual*, annual reports, unpublished revisions, and estimates. (For 1981–1992, product supplied estimates for propylene are equal to propylene refinery and blender net production from Table 3.2; and estimates for propane are equal to total propane/propylene minus propylene. For 1993–2009, product supplied



estimates for propylene are equal to propylene refinery and blender net production from Table 3.2, plus propylene imports from Table 3.3b; and estimates for propane are equal to total propane/propylene minus propylene.)

2020 and 2021: EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system, Short-Term Integrated Forecasting System, and *Monthly Energy Review* data system calculations.

## Table 3.6 Sources

### *Asphalt and Road Oil*

Product supplied data in thousand barrels per day for asphalt and road oil are from Table 3.5, and are converted to trillion Btu by multiplying by the asphalt and road oil heat content factor in Table A1.

### *Aviation Gasoline*

Product supplied data in thousand barrels per day for aviation gasoline are from Table 3.5, and are converted to trillion Btu by multiplying by the aviation gasoline (finished) heat content factor in Table A1.

### *Distillate Fuel Oil*

1949–2008: Product supplied data in thousand barrels per day for distillate fuel oil are from Table 3.5, and are converted to trillion Btu by multiplying by the distillate fuel oil heat content factors in Table A3.

2009–2011: Consumption data for biodiesel are calculated using biodiesel data from U.S. Energy Information Administration (EIA), EIA-22M, “Monthly Biodiesel Production Survey”; and biomass-based diesel fuel data from EIA-810, “Monthly Refinery Report,” EIA-812, “Monthly Product Pipeline Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1). Consumption data for other renewable diesel fuel are set equal to refinery and blender net inputs data from EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Product supplied data for distillate fuel oil from Table 3.5, minus consumption data for biodiesel and other renewable diesel fuel, are converted to Btu by multiplying by the distillate fuel oil heat content factors in Table A3. Total distillate fuel oil product supplied is the sum of values for distillate fuel oil (excluding biodiesel and other renewable diesel fuel), biodiesel, and other renewable diesel fuel.

2012–2020: Consumption data for biodiesel are from Table 10.4. Consumption data for other renewable diesel fuel are set equal to refinery and blender net inputs data from EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Product supplied data for distillate fuel oil from Table 3.5, minus consumption data for biodiesel and other renewable diesel fuel, are converted to Btu by multiplying by the distillate fuel oil heat content factors in Table A3. Total distillate fuel oil product supplied is the sum of the values for distillate fuel oil (excluding biodiesel and other renewable diesel fuel), biodiesel, and other renewable diesel fuel.

2021 forward: Refinery and blender net inputs data for biodiesel and other renewable diesel fuel are set equal to refinery and blender net inputs data from EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the biodiesel and other renewable diesel fuel heat content factors in Table A1). Product supplied data for distillate fuel oil from Table 3.5, minus refinery and blender net inputs data for biodiesel and other renewable diesel fuel, are converted to Btu by multiplying by the distillate fuel oil heat content factors in Table A3. Total distillate fuel oil product supplied is the sum of the values for distillate fuel oil (excluding biodiesel and other renewable diesel fuel), biodiesel, and other renewable diesel fuel.

### *Hydrocarbon Gas Liquids (HGL)—Propane*

Product supplied data in thousand barrels per day for propane are from Table 3.5, and are converted to trillion Btu by multiplying by the propane heat content factor in Table A1.

### ***Hydrocarbon Gas Liquids (HGL)—Propylene***

Product supplied data in thousand barrels per day for propylene are from Table 3.5, and are converted to trillion Btu by multiplying by the propylene heat content factor in Table A1.

### ***Hydrocarbon Gas Liquids (HGL)—Propane/Propylene Total***

Prior to the current two months, total propane/propylene product supplied is the sum of the data in trillion Btu for propane and propylene.

For the current two months, product supplied data in thousand barrels per day for total propane/propylene are from Table 3.5, and are converted to trillion Btu by multiplying by the propane/propylene heat content factor in Table A1.

### ***Hydrocarbon Gas Liquids (HGL)—Total***

Prior to the current two months, product supplied data in thousand barrels per day for the component products of HGL (ethane, propane, normal butane, isobutane, natural gasoline, and refinery olefins—ethylene, propylene, butylene, and isobutylene) are from the PSA, PSM, and earlier publications (see sources for Table 3.5). These data are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1. Total HGL product supplied is the sum of the data in trillion Btu for the HGL component products.

For the current two months: Note that "liquefied petroleum gases" ("LPG") below include ethane, propane, normal butane, isobutane, and refinery olefins (ethylene, propylene, butylene, and isobutylene), but exclude natural gasoline. Product supplied data in thousand barrels per day for LPG are from EIA's Short-Term Integrated Forecasting System (STIFS). (The STIFS model results are used in EIA's *Short-Term Energy Outlook*, which is accessible on the Web at <https://www.eia.gov/outlooks/steo/>.) These data are converted to trillion Btu by multiplying by the previous year's quantity-weighted LPG heat content factor (derived using LPG component heat content factors in Table A1). Product supplied data in thousand barrels per day for natural gasoline are from STIFS, and are converted to trillion Btu by multiplying by the natural gasoline heat content factor in Table A1. Total HGL product supplied is the sum of the data in trillion Btu for LPG and natural gasoline.

### ***Jet Fuel***

Product supplied data in thousand barrels per day for kerosene-type jet fuel and, through 2004, naphtha-type jet fuel are from the PSA, PSM, and earlier publications (see sources for Table 3.5). These data are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1. Total jet fuel product supplied is the sum of the data in trillion Btu for kerosene-type and naphtha-type jet fuel.

### ***Kerosene***

Product supplied data in thousand barrels per day for kerosene are from Table 3.5, and are converted to trillion Btu by multiplying by the kerosene heat content factor in Table A1.

### ***Lubricants***

Product supplied data in thousand barrels per day for lubricants are from Table 3.5, and are converted to trillion Btu by multiplying by the lubricants heat content factor in Table A1.

### ***Motor Gasoline***

Product supplied data in thousand barrels per day for motor gasoline are from Table 3.5, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

### ***Other Petroleum Products***

Prior to the current two months, product supplied data in thousand barrels per day for "other" petroleum products are from the PSA, PSM, and earlier publications (see sources for Table 3.5). "Other" petroleum products include petrochemical feedstocks, special naphthas, still gas (refinery gas), waxes, and miscellaneous products; beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components; beginning in 1983, also includes crude oil burned as fuel; beginning in 2005, also includes naphtha-type jet fuel; and beginning in 2021, also includes renewable fuels excluding fuel ethanol (biodiesel, other renewable diesel fuel, and other renewable fuels).

These data are converted to trillion Btu by multiplying by the appropriate heat content factors in MER Table A1. Total "Other" petroleum product supplied is the sum of the data in trillion Btu for the individual products.

For the current two months, total "Other" petroleum products supplied is calculated by first estimating total petroleum products supplied (product supplied data in thousand barrels per day for total petroleum from Table 3.5 are converted to trillion Btu by multiplying by the total petroleum consumption heat content factor in Table A3), and then subtracting data in trillion Btu (from Table 3.6) for asphalt and road oil, aviation gasoline, distillate fuel oil, jet fuel, kerosene, total HGL, lubricants, motor gasoline, petroleum coke, and residual fuel oil.

### ***Petroleum Coke***

Product supplied data in thousand barrels per day for petroleum coke are from Table 3.5, and are converted to trillion Btu by multiplying by the petroleum coke heat content factors in Table A3.

### ***Residual Fuel Oil***

Product supplied data in thousand barrels per day for residual fuel oil are from Table 3.5, and are converted to trillion Btu by multiplying by the residual fuel oil heat content factor in Table A1.

### ***Total Petroleum***

Total petroleum products supplied is the sum of the data in trillion Btu for the products (except "Propane") shown in Table 3.6.

## **Tables 3.7a–3.7c Sources**

Petroleum consumption data for 1949–1972 are from the following sources:

1949–1959: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports, and U.S. Energy Information Administration (EIA) estimates.

1960–1972: EIA, State Energy Data System.

Petroleum consumption data beginning in 1973 are derived from data for "petroleum products supplied" from the following sources:

1973–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement Annual*, annual reports.

1976–1980: EIA, Energy Data Reports, *Petroleum Statement Annual*, annual reports.

1981–2019: EIA, *Petroleum Supply Annual* (PSA), annual reports, and unpublished revisions.

2020 and 2021: EIA, *Petroleum Supply Monthly* (PSM), monthly reports.

Beginning in 1973, energy-use allocation procedures by individual product are as follows:

### ***Asphalt and Road Oil***

All consumption of asphalt and road oil is assigned to the industrial sector.

### ***Aviation Gasoline***

All consumption of aviation gasoline is assigned to the transportation sector.

### ***Distillate Fuel Oil***

Distillate fuel oil consumption is assigned to the sectors as follows:

#### ***Distillate Fuel Oil, Electric Power Sector***

See sources for Table 7.4b. For 1973–1979, electric utility consumption of distillate fuel oil is assumed to be the amount of petroleum (minus small amounts of kerosene and kerosene-type jet fuel deliveries) consumed in gas turbine and internal combustion plants. For 1980–2000, electric utility consumption of distillate fuel oil is assumed to be the amount of light oil (fuel oil nos. 1 and 2, plus small amounts of kerosene and jet fuel) consumed.

### ***Distillate Fuel Oil, End-Use Sectors, Annual Data***

The aggregate end-use amount is total distillate fuel oil product supplied minus the amount consumed by the electric power sector. The end-use total consumed annually is allocated to the individual end-use sectors (residential, commercial, industrial, and transportation) in proportion to each sector's share of sales as reported in EIA's *Fuel Oil and Kerosene Sales (Sales)* report series (DOE/EIA-0535), which is based primarily on data collected by Form EIA-821, "Annual Fuel Oil and Kerosene Sales Report" (previously Form EIA-172). Shares for the current year are based on the most recent Sales report.

Following are notes on the individual sector groupings:

Beginning in 1979, the residential sector sales total is directly from the Sales reports. Through 1978, each year's sales subtotal of the heating plus industrial category is split into residential, commercial, and industrial (including farm) in proportion to the 1979 shares.

Beginning in 1979, the commercial sector sales total is directly from the Sales reports. Through 1978, each year's sales subtotal of the heating plus industrial category is split into residential, commercial, and industrial (including farm) in proportion to the 1979 shares.

Beginning in 1979, the industrial sector sales total is the sum of the sales for industrial, farm, oil company, off-highway diesel, and all other uses. Through 1978, each year's sales subtotal of the heating plus industrial category is split into residential, commercial, and industrial (including farm) in proportion to the 1979 shares, and this estimated industrial portion is added to oil company, off-highway diesel, and all other uses.

The transportation sector sales total is the sum of the sales for railroad, vessel bunkering, on-highway diesel, and military uses for all years.

### ***Distillate Fuel Oil, End-Use Sectors, Monthly Data***

Residential sector and commercial sector monthly consumption is estimated by allocating the annual estimates, which are described above, into the months in proportion to each month's share of the year's sales of No. 2 heating oil. (For each month of the current year, the residential and commercial consumption increase from the same month in the previous year is based on the percent increase in that month's No. 2 heating oil sales from the same month in the previous year.) The years' No. 2 heating oil sales totals are from the following sources: for 1973–1980, the Ethyl Corporation, *Monthly Report of Heating Oil Sales*; for 1981 and 1982, the American Petroleum Institute, *Monthly Report of Heating Oil Sales*; and for 1983 forward, EIA, Form EIA-782A, "Refiners'/Gas Plant Operators' Monthly Petroleum Product Sales Report," No. 2 Fuel Oil Sales to End Users and for Resale.

The transportation highway use portion is allocated into the months in proportion to each month's share of the year's total sales for highway use as reported by the Federal Highway Administration's Table MF-25, "Private and Commercial Highway Use of Special Fuels by Months." Beginning in 1994, the sales-for-highway-use data are no longer available as a monthly series; the 1993 data are used for allocating succeeding year's totals into months.

A distillate fuel oil "balance" is calculated as total distillate fuel oil product supplied minus the amount consumed by the electric power sector, residential sector, commercial sector, and for highway use.

Industrial sector monthly consumption is estimated by multiplying each month's distillate fuel oil "balance" by the annual industrial consumption share of the annual distillate fuel oil "balance."

Total transportation sector monthly consumption is estimated as total distillate fuel oil product supplied minus the amount consumed by the residential, commercial, industrial, and electric power sectors.

### ***Hydrocarbon Gas Liquids (HGL)—Propane***

Annual residential sector propane consumption: Through 2002, annual residential sector propane consumption is estimated by applying the average of the state residential shares for 2003–2008 to the combined residential and commercial propane sales. Beginning in 2003, annual residential sector propane consumption is assumed to equal propane retail sales to the residential sector and sales to retailers/cylinder markets.

Monthly residential sector propane consumption: Beginning in 1973, annual residential sector propane consumption is split into the estimated portion for residential space heating and water heating, and the estimated portion for all other residential uses. The annual values in thousand barrels for residential space heating and water heating are allocated to the months in proportion to U.S. heating degree days in Table 1.9. The annual values in thousand barrels for all other residential uses are allocated to the months by dividing the annual values by the number of days in the year and then multiplying by the number of days in the month. Monthly total residential sector propane consumption is the sum of the monthly values for residential space heating and water heating and for all other residential uses.

Annual commercial sector propane consumption: Through 2002, annual commercial sector propane consumption is equal to the combined residential and commercial propane sales minus residential sector propane consumption. Beginning in 2003, annual commercial sector propane consumption is assumed to equal commercial sector propane sales.

Monthly commercial sector propane consumption: Beginning in 1973, annual commercial sector propane consumption is split into the estimated portion for commercial space heating and water heating, and the estimated portion for all other commercial uses. The annual values in thousand barrels for commercial space heating and water heating are allocated to the months in proportion to U.S. heating degree days in Table 1.9. The annual values in thousand barrels for all other commercial uses are allocated to the months by dividing the annual values by the number of days in the year and then multiplying by the number of days in the month. Monthly total commercial sector propane consumption is the sum of the monthly values for commercial space heating and water heating and for all other commercial uses.

Annual transportation sector propane consumption: Through 2009, annual transportation sector propane consumption is assumed to equal the transportation portion of propane sales for internal combustion engines (these sales are allocated between the transportation and industrial sectors using data for special fuels used on highways provided by the U.S. Department of Transportation, Federal Highway Administration). Beginning in 2010, annual transportation sector propane consumption is from EIA, *Annual Energy Outlook*, Table 37, "Transportation Sector Energy Use by Fuel Type within a Mode."

Monthly transportation sector propane consumption: Beginning in 1973, the annual values in thousand barrels for transportation sector propane consumption are allocated to the months by dividing the annual values by the number of days in the year and then multiplying by the number of days in the month.

Annual and monthly industrial sector propane consumption: Industrial sector propane consumption is estimated as the difference between propane total product supplied from Table 3.5 and the sum of the estimated propane consumption by the residential, commercial, and transportation sectors.

Sources of the annual consumption estimates for creating annual sector shares are:

1973–1982: EIA's "Sales of Liquefied Petroleum Gases and Ethane" reports, based primarily on data collected by Form EIA-174, "Sales of Liquefied Petroleum Gases."

1983: End-use consumption estimates for 1983 are based on 1982 end-use consumption because the collection of data under Form EIA-174 was discontinued after data year 1982.

1984–2007: American Petroleum Institute (API), "Sales of Natural Gas Liquids and Liquefied Refinery Gases," table on sales of natural gas liquids and liquefied refinery gases by end use. EIA adjusts the data to remove quantities of natural gasoline and to estimate withheld values.

2008 and 2009: Propane consumption is from API, "Sales of Natural Gas Liquids and Liquefied Refinery Gases," table on sales of propane by end use. EIA adjusts the data to estimate withheld values. Other LPG consumption is from EIA, PSA, annual reports, and is allocated to the industrial sector.

2010–2016: Propane consumption is from API, "Sales of Natural Gas Liquids and Liquefied Refinery Gases," table on sales of odorized propane by end use; and EIA, *Annual Energy Outlook*, Table 37, "Transportation Sector Energy Use by Fuel Type Within a Mode." EIA adjusts the data to estimate withheld values. Other LPG consumption is from EIA, PSA, annual reports, and is allocated to the industrial sector.

2017 forward: Propane consumption is from Propane Education & Research Council, "Retail Propane Sales Report," data on propane sales by sector; and EIA, *Annual Energy Outlook*, Table 37, "Transportation Sector Energy Use by Fuel Type Within a Mode." EIA adjusts the data to estimate withheld values. Other LPG consumption is from EIA, PSA, annual reports, and is allocated to the industrial sector.

### ***Hydrocarbon Gas Liquids (HGL)—Propylene***

Industrial sector propylene consumption is equal to propylene product supplied in Table 3.5.

### ***Hydrocarbon Gas Liquids (HGL)—Propane/Propylene Total***

Industrial sector total propane/propylene consumption is the sum of the industrial sector consumption values for propane and propylene.

### ***Hydrocarbon Gas Liquids (HGL)—Total***

The residential, commercial, and transportation sector total HGL consumption values are equal to the propane consumption values for those sectors. The industrial sector total HGL consumption value is equal to total HGL product supplied in Table 3.5 minus propane consumption in the residential, commercial, and transportation sectors.

### ***Jet Fuel***

Through 1982, small amounts of kerosene-type jet fuel were consumed by the electric power sector. Kerosene-type jet fuel deliveries to the electric power sector as reported on Form FERC-423 (formerly Form FPC-423) were used as estimates of this consumption. Through 2004, all remaining jet fuel (kerosene-type and naphtha-type) is assigned to the transportation sector. Beginning in 2005, kerosene-type jet fuel is assigned to the transportation sector, while naphtha-type jet fuel is classified under "Other Petroleum Products," which is assigned to the industrial sector. (Note: Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft.)

### ***Kerosene***

Kerosene product supplied is allocated to the individual end-use sectors (residential, commercial, and industrial) in proportion to each sector's share of sales as reported in EIA's *Fuel Oil and Kerosene Sales (Sales)* report series (DOE/EIA-0535), which is based primarily on data collected by Form EIA-821, "Annual Fuel Oil and Kerosene Sales Report" (previously Form EIA-172).

Beginning in 1979, the residential sector sales total is directly from the Sales reports. Through 1978, each year's sales category called "heating" is allocated to the residential, commercial, and industrial sectors in proportion to the 1979 shares.

Beginning in 1979, the commercial sector sales total is directly from the Sales reports. Through 1978, each year's sales category called "heating" is allocated to the residential, commercial, and industrial sectors in proportion to the 1979 shares.

Beginning in 1979, the industrial sector sales total is the sum of the sales for industrial, farm, and all other uses. Through 1978, each year's sales category called "heating" is allocated to the residential, commercial and industrial sectors in proportion to the 1979 shares, and the estimated industrial (including farm) portion is added to all other uses.

### ***Lubricants***

1973–2009: The consumption of lubricants is allocated to the industrial and transportation sectors for all months according to proportions developed from annual sales of lubricants to the two sectors from U.S. Department of Commerce, U.S. Census Bureau, *Current Industrial Reports*, "Sales of Lubricating and Industrial Oils and Greases." The 1973 shares are applied to 1973 and 1974; the 1975 shares are applied to 1975 and 1976; and the 1977 shares are applied to 1977 through 2009.

2010 forward: The consumption of lubricants in the industrial sector is estimated by EIA based on Kline & Company data on finished lubricant demand for industrial (less marine and railroad) use. The consumption of lubricants in the transportation sector is estimated by EIA based on Kline & Company data on finished lubricant demand for consumer

total, commercial total, marine, and railroad use. Estimates for lubricant consumption from 2010 forward are not compatible with data before 2010.

### ***Motor Gasoline***

The total monthly consumption of motor gasoline is allocated to the sectors in proportion to aggregations of annual sales categories created on the basis of the U.S. Department of Transportation, Federal Highway Administration, *Highway Statistics*, Tables MF-21, MF-24, and MF-25, as follows:

Through 2014, commercial sales are the sum of sales for public non-highway use and miscellaneous use. Beginning in 2015, commercial sales are the sum of sales for public non-highway use, lawn and garden use, and miscellaneous use.

For all years, industrial sales are the sum of sales for agriculture, construction, and "industrial and commercial" use (as classified in the *Highway Statistics*).

Through 2014, transportation sales are the sum of sales for highway use (minus the sales of special fuels, which are primarily diesel fuel and are accounted for in the transportation sector of distillate fuel) and sales for marine use. Beginning in 2015, transportation sales are the sum of sales for highway use (minus the sales of special fuels, which are primarily diesel fuel and are accounted for in the transportation sector of distillate fuel) and sales for boating use and recreational vehicle use.

### ***Petroleum Coke***

Portions of petroleum coke are consumed by the electric power sector (see sources for Table 7.4b) and the commercial sector (see sources for Table 7.4c). The remaining petroleum coke is assigned to the industrial sector.

### ***Residual Fuel Oil***

Residual fuel oil consumption is assigned to the sectors as follows:

#### ***Residual Fuel Oil, Electric Power Sector***

See sources for Table 7.4b. For 1973–1979, electric utility consumption of residual fuel oil is assumed to be the amount of petroleum consumed in steam-electric power plants. For 1980–2000, electric utility consumption of residual fuel oil is assumed to be the amount of heavy oil (fuel oil nos. 4, 5, and 6) consumed.

#### ***Residual Fuel Oil, End-Use Sectors, Annual Data***

The aggregate end-use amount is total residual fuel oil product supplied minus the amount consumed by the electric power sector. The end-use total consumed annually is allocated to the individual end-use sectors (commercial, industrial, and transportation) in proportion to each sector's share of sales as reported in EIA's *Fuel Oil and Kerosene Sales (Sales)* report series (DOE/EIA-535), which is based primarily on data collected by Form EIA-821, "Annual Fuel Oil and Kerosene Sales Report" (previously Form EIA-172). Shares for the current year are based on the most recent Sales report.

Following are notes on the individual sector groupings:

Beginning in 1979, commercial sales data are directly from the Sales reports. Through 1978, each year's sales subtotal of the heating plus industrial category is allocated to the commercial and industrial sectors in proportion to the 1979 shares.

Beginning in 1979, industrial sales data are the sum of sales for industrial, oil company, and all other uses. Through 1978, each year's sales subtotal of the heating plus industrial category is allocated to the commercial and industrial sectors in proportion to the 1979 shares, and the estimated industrial portion is added to oil company and all other uses.

Transportation sales are the sum of sales for railroad, vessel bunkering, and military uses for all years.

#### ***Residual Fuel Oil, End-Use Sectors, Monthly Data***

Commercial sector monthly consumption is estimated by allocating the annual estimates, which are described above, into the months in proportion to each month's share of the year's sales of No. 2 heating oil. (For each month of the current year, the consumption increase from the same month in the previous year is based on the percent increase in

that month's No. 2 heating oil sales from the same month in the previous year.) The years' No. 2 heating oil sales totals are from the following sources: for 1973–1980, the Ethyl Corporation, *Monthly Report of Heating Oil Sales*; for 1981 and 1982, the American Petroleum Institute, *Monthly Report of Heating Oil Sales*; and for 1983 forward, EIA, Form EIA-782A, "Refiners'/Gas Plant Operators' Monthly Petroleum Product Sales Report," No. 2 Fuel Oil Sales to End Users and for Resale.

A residual fuel oil "balance" is calculated as total residual fuel oil product supplied minus the amount consumed by the electric power sector, commercial sector, and by industrial combined-heat-and-power plants (see sources for Table 7.4c).

Transportation sector monthly consumption is estimated by multiplying each month's residual fuel oil "balance" by the annual transportation consumption share of the annual residual fuel oil "balance."

Total industrial sector monthly consumption is estimated as total residual fuel oil product supplied minus the amount consumed by the commercial, transportation, and electric power sectors.

### ***Other Petroleum Products***

Consumption of renewable fuels excluding fuel ethanol is assigned to the transportation sector. Consumption of all remaining petroleum products, which include petrochemical feedstocks, special naphthas, still gas (refinery gas), waxes, and miscellaneous products, is assigned to the industrial sector. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

### ***Renewable Fuels Excluding Fuel Ethanol***

Beginning in 2021, renewable fuels excluding fuel ethanol consumption is assigned to the transportation sector. Renewable fuels excluding fuel ethanol consumption consists of products supplied of biodiesel, other renewable diesel fuel, and other renewable fuels; consumption does not include renewable fuels blended with distillate fuel oil, motor gasoline, or other petroleum products.

## **Table 3.8a Sources**

### ***Distillate Fuel Oil***

Residential and commercial sector consumption data in thousand barrels per day for distillate fuel oil are from Table 3.7a, and are converted to trillion Btu by multiplying by the distillate fuel oil heat content factors in Table A3.

### ***Hydrocarbon Gas Liquids (HGL)—Propane***

Residential and commercial sector consumption data in thousand barrels per day for propane are from Table 3.7a, and are converted to trillion Btu by multiplying by the propane heat content factor in Table A1. The residential and commercial sector total HGL consumption values are equal to the propane consumption values for those sectors.

### ***Kerosene***

Residential and commercial sector consumption data in thousand barrels per day for kerosene are from Table 3.7a, and are converted to trillion Btu by multiplying by the kerosene heat content factor in Table A1.

### ***Motor Gasoline***

Commercial sector consumption data in thousand barrels per day for motor gasoline are from Table 3.7a, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

### ***Petroleum Coke***

1949–2003: Commercial sector consumption data in thousand barrels per day for petroleum coke are from Table 3.7a, and are converted to trillion Btu by multiplying by the total petroleum coke heat content factor in Table A1.

2004 forward: Commercial sector consumption data in thousand barrels per day for petroleum coke are from Table 3.7a, and are converted to trillion Btu by multiplying by the marketable petroleum coke heat content factor in Table A1.



### ***Residual Fuel Oil***

Commercial sector consumption data in thousand barrels per day for residual fuel oil are from Table 3.7a, and are converted to trillion Btu by multiplying by the residual fuel oil heat content factor in Table A1.

### ***Total Petroleum***

Residential sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under "Residential Sector" in Table 3.8a. Commercial sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under "Commercial Sector" in Table 3.8a.

## **Table 3.8b Sources**

### ***Asphalt and Road Oil***

Industrial sector consumption data in thousand barrels per day for asphalt and road oil are from Table 3.7b, and are converted to trillion Btu by multiplying by the asphalt and road oil heat content factor in Table A1.

### ***Distillate Fuel Oil***

Industrial sector consumption data in thousand barrels per day for distillate fuel oil are from Table 3.7b, and are converted to trillion Btu by multiplying by the distillate fuel oil heat content factors in Table A3.

### ***Hydrocarbon Gas Liquids (HGL)—Propane***

Industrial sector propane consumption data are calculated by subtracting propane consumption data in trillion Btu for the residential (Table 3.8a), commercial (Table 3.8a), and transportation (Table 3.8c) sectors from total propane consumption (see sources for Table 3.6).

### ***Hydrocarbon Gas Liquids (HGL)—Propylene***

Product supplied data in thousand barrels per day for propylene are from Table 3.5, and are converted to trillion Btu by multiplying by the propylene heat content factor in Table A1.

### ***Hydrocarbon Gas Liquids (HGL)—Propane/Propylene Total***

Total industrial sector propane/propylene consumption is the sum of the data in trillion Btu for propane and propylene.

### ***Hydrocarbon Gas Liquids (HGL)—Total***

Industrial sector consumption data for HGL are calculated by subtracting HGL consumption data in trillion Btu for the residential (Table 3.8a), commercial (Table 3.8a), and transportation (Table 3.8c) sectors from total HGL consumption (Table 3.6).

### ***Kerosene***

Industrial sector consumption data in thousand barrels per day for kerosene are from Table 3.7b, and are converted to trillion Btu by multiplying by the kerosene heat content factor in Table A1.

### ***Lubricants***

Industrial sector consumption data in thousand barrels per day for lubricants are from Table 3.7b, and are converted to trillion Btu by multiplying by the lubricants heat content factor in Table A1.

### ***Motor Gasoline***

Industrial sector consumption data in thousand barrels per day for motor gasoline are from Table 3.7b, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

### ***Other Petroleum Products***

Industrial sector "Other" petroleum data are equal to the "Other" petroleum data in Table 3.6 minus "Renewable Fuels Excluding Fuel Ethanol" data (see sources for Table 3.8c).

### ***Petroleum Coke***

1949–2003: Industrial sector consumption data in thousand barrels per day for petroleum coke are from Table 3.7b, and are converted to trillion Btu by multiplying by the total petroleum coke heat content factor in Table A1.

2004 forward: Industrial sector consumption data for petroleum coke are calculated by subtracting petroleum coke consumption data in trillion Btu for the commercial (Table 3.8a) and electric power (Table 3.8c) sectors from total petroleum coke consumption (Table 3.6).

### ***Residual Fuel Oil***

Industrial sector consumption data in thousand barrels per day for residual fuel oil are from Table 3.7b, and are converted to trillion Btu by multiplying by the residual fuel oil heat content factor in Table A1.

### ***Total Petroleum***

Industrial sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown in Table 3.8b.

## **Table 3.8c Sources**

### ***Aviation Gasoline***

Transportation sector consumption data in thousand barrels per day for aviation gasoline are from Table 3.7c, and are converted to trillion Btu by multiplying by the aviation gasoline (finished) heat content factor in Table A1.

### ***Distillate Fuel Oil, Electric Power Sector***

Electric power sector consumption data in thousand barrels per day for distillate fuel oil are from Table 3.7c, and are converted to trillion Btu by multiplying by the distillate fuel oil heat content factors in Table A3.

### ***Distillate Fuel Oil, Transportation Sector***

1949–2008: Transportation sector consumption data in thousand barrels per day for distillate fuel oil are from Table 3.7c, and are converted to trillion Btu by multiplying by the distillate fuel oil heat content factors in Table A3.

2009–2011: Consumption data for biodiesel are calculated using biodiesel data from U.S. Energy Information Administration (EIA), EIA-22M, “Monthly Biodiesel Production Survey”; and biomass-based diesel fuel data from EIA-810, “Monthly Refinery Report,” EIA-812, “Monthly Product Pipeline Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the biodiesel heat content factor in Table A1). Consumption data for other renewable diesel fuel are set equal to refinery and blender net inputs data from EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Transportation sector distillate fuel oil consumption data from Table 3.7c, minus consumption data for biodiesel and other renewable diesel fuel, are converted to Btu by multiplying by the distillate fuel oil heat content factors in Table A3. Total transportation sector distillate fuel oil consumption is the sum of the values for distillate fuel oil (excluding biodiesel and other renewable diesel fuel), biodiesel, and other renewable diesel fuel.

2012–2020: Consumption data for biodiesel are from Table 10.4. Consumption data for other renewable diesel fuel are set equal to refinery and blender net inputs data from EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Transportation sector distillate fuel oil consumption data from Table 3.7c, minus consumption data for biodiesel and other renewable diesel fuel, are converted to Btu by multiplying by the distillate fuel oil heat content factors in Table A3. Total transportation sector distillate fuel oil consumption is the sum of the values for distillate fuel oil (excluding biodiesel and other renewable diesel fuel), biodiesel, and other renewable diesel fuel.

2021 forward: Refinery and blender net inputs data for biodiesel and other renewable diesel fuel are set equal to refinery and blender net inputs data from EIA-810, “Monthly Refinery Report,” and EIA-815, “Monthly Bulk Terminal and Blender Report” (the data are converted to Btu by multiplying by the biodiesel and other renewable diesel fuel heat content factors in Table A1). Transportation sector distillate fuel oil consumption data from Table 3.7c, minus refinery and blender net inputs data for biodiesel and other renewable diesel fuel, are converted to Btu by multiplying by the distillate fuel oil heat content factors in Table A3. Total transportation sector distillate fuel oil consumption is the sum of the values for distillate fuel oil (excluding biodiesel and other renewable diesel fuel), biodiesel, and other renewable diesel fuel.

### ***Hydrocarbon Gas Liquids (HGL)—Propane***

Transportation sector consumption data in thousand barrels per day for propane are from Table 3.7c, and are converted to trillion Btu by multiplying by the propane heat content factor in Table A1. The transportation sector total HGL consumption values are equal to the transportation sector propane consumption values.

### ***Jet Fuel***

Transportation sector consumption data in thousand barrels per day for kerosene-type jet fuel and, through 2004, naphtha-type jet fuel (see sources for Table 3.7c) are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1. Total transportation sector jet fuel consumption is the sum of the data in trillion Btu for kerosene-type and naphtha-type jet fuel. (Note: Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. Other measurements of consumption by fuel type or sector may differ. For example, jet fuel product supplied may not equal jet fuel consumed by U.S.-flagged aircraft.)

### ***Lubricants***

Transportation sector consumption data in thousand barrels per day for lubricants are from Table 3.7c, and are converted to trillion Btu by multiplying by the lubricants heat content factor in Table A1.

### ***Motor Gasoline***

Transportation sector consumption data in thousand barrels per day for motor gasoline are from Table 3.7c, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

### ***Petroleum Coke***

1949–2003: Electric power sector consumption data in thousand barrels per day for petroleum coke are from Table 3.7c, and are converted to trillion Btu by multiplying by the total petroleum coke heat content factor in Table A1.

2004 forward: Electric power sector consumption data in thousand barrels per day for petroleum coke are from Table 3.7c, and are converted to trillion Btu by multiplying by the marketable petroleum coke heat content factor in Table A1.

### ***Renewable Fuels Excluding Fuel Ethanol***

Beginning in 2021, transportation sector data in thousand barrels per day for "Renewable Fuels Excluding Fuel Ethanol" are converted to trillion Btu by multiplying the fuel types (biodiesel, other renewable diesel fuel, and other renewable fuels) by the appropriate heat content factors in Table A1.

### ***Residual Fuel Oil***

Transportation and electric power consumption data in thousand barrels per day for residual fuel oil are from Table 3.7c, and are converted to trillion Btu by multiplying by the residual fuel oil heat content factor in Table A1.

### ***Total Petroleum***

Transportation sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under "Transportation Sector" in Table 3.8c. Electric power sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under "Electric Power Sector" in Table 3.8c.


THIS PAGE INTENTIONALLY LEFT BLANK

## 4. Natural Gas


---

**Figure 4.1 Natural Gas**  
(Trillion Cubic Feet)


Overview, 1949–2020




Consumption by Sector, 1949–2020



Overview, Monthly



Consumption by Sector, Monthly



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#naturalgas>.  
Sources: Tables 4.1 and 4.3.

**Table 4.1 Natural Gas Overview**  
(Billion Cubic Feet)

	Gross Withdrawals <sup>a</sup>	Marketed Production (Wet) <sup>b</sup>	NGPL Production <sup>c</sup>	Dry Gas Production <sup>d</sup>	Supplemental Gaseous Fuels <sup>e</sup>	Trade			Net Storage Withdrawals <sup>f</sup>	Balancing Item <sup>g</sup>	Consumption <sup>h</sup>
						Imports	Exports	Net Imports			
1950 Total .....	8,480	6,282	260	6,022	NA	0	26	-26	-54	-175	5,767
1955 Total .....	11,720	9,405	377	9,029	NA	11	31	-20	-68	-247	8,694
1960 Total .....	15,088	12,771	543	12,228	NA	156	11	144	-132	-274	11,967
1965 Total .....	17,963	16,040	753	15,286	NA	456	26	430	-118	-319	15,280
1970 Total .....	23,786	21,921	906	21,014	NA	821	70	751	-398	-228	21,139
1975 Total .....	21,104	20,109	872	19,236	NA	953	73	880	-344	-235	19,538
1980 Total .....	21,870	20,180	777	19,403	155	985	49	936	23	-640	19,877
1985 Total .....	19,607	17,270	816	16,454	126	950	55	894	235	-428	17,281
1990 Total .....	21,523	18,594	784	17,810	123	1,532	86	1,447	-513	307	19,174
1995 Total .....	23,744	19,506	908	18,599	110	2,841	154	2,687	415	396	22,207
2000 Total .....	24,174	20,198	1,016	19,182	90	3,782	244	3,538	829	-306	23,333
2005 Total .....	23,457	18,927	876	18,051	64	4,341	729	3,612	52	236	22,014
2006 Total .....	23,535	19,410	906	18,504	66	4,186	724	3,462	-436	103	21,699
2007 Total .....	24,664	20,196	930	19,266	63	4,608	822	3,785	192	-203	23,104
2008 Total .....	25,636	21,112	953	20,159	61	3,984	963	3,021	34	2	23,277
2009 Total .....	26,057	21,648	1,024	20,624	65	3,751	1,072	2,679	-355	-103	22,910
2010 Total .....	26,816	22,382	1,066	21,316	65	3,741	1,137	2,604	-13	115	24,087
2011 Total .....	28,479	24,036	1,134	22,902	60	3,469	1,506	1,963	-354	-94	24,477
2012 Total .....	29,542	25,283	1,250	24,033	61	3,138	1,619	1,519	-9	-66	25,538
2013 Total .....	29,523	25,562	1,357	24,206	55	2,883	1,572	1,311	546	38	26,155
2014 Total .....	31,405	27,498	1,608	25,890	60	2,695	1,514	1,181	-254	-283	26,593
2015 Total .....	32,915	28,772	1,707	27,065	59	2,718	1,784	935	-547	-268	27,244
2016 Total .....	32,592	28,400	1,808	26,592	57	3,006	2,335	671	340	-216	27,444
2017 Total .....	33,292	29,204	1,897	27,306	66	3,033	3,154	-121	254	-360	27,146
2018 Total .....	37,326	33,009	2,235	30,774	69	2,889	3,608	-719	314	-299	30,140
2019 January .....	3,385	2,981	208	2,773	5	291	365	-74	730	-17	3,417
February .....	3,067	2,709	189	2,520	5	233	330	-97	586	-1	3,013
March .....	3,396	3,019	211	2,809	5	253	374	-121	257	-28	2,922
April .....	3,329	2,934	205	2,729	5	207	338	-132	-401	8	2,209
May .....	3,432	3,055	213	2,842	5	208	369	-161	-494	-62	2,131
June .....	3,317	2,969	207	2,761	5	201	360	-159	-452	-39	2,117
July .....	3,412	3,084	215	2,869	5	230	393	-163	-270	-50	2,391
August .....	3,467	3,159	220	2,939	5	220	385	-165	-303	-46	2,430
September .....	3,399	3,054	213	2,841	5	208	395	-186	-440	-16	2,203
October .....	3,571	3,200	223	2,977	5	211	426	-215	-364	-98	2,305
November .....	3,496	3,120	218	2,902	5	224	441	-218	159	-71	2,778
December .....	3,621	3,232	226	3,007	5	256	481	-225	433	-58	3,163
Total .....	40,892	36,515	2,548	33,968	62	2,742	4,656	-1,915	-558	-477	31,080
2020 January .....	E 3,590	E 3,182	234	E 2,948	6	262	510	-248	571	20	3,296
February .....	E 3,342	E 2,959	212	E 2,747	6	238	454	-216	535	-40	3,033
March .....	E 3,561	E 3,166	235	E 2,931	6	213	497	-284	49	7	2,708
April .....	E 3,372	E 3,002	214	E 2,788	6	190	421	-231	-306	-12	2,245
May .....	E 3,298	E 2,934	212	E 2,722	5	187	395	-209	-448	1	2,071
June .....	E 3,225	E 2,876	226	E 2,651	5	188	338	-151	-358	-12	2,135
July .....	E 3,383	E 3,023	241	E 2,783	6	210	349	-139	-161	4	2,493
August .....	E 3,388	E 3,037	240	E 2,797	4	211	359	-148	-227	-21	2,404
September .....	E 3,273	E 2,914	230	E 2,684	4	174	395	-221	-323	30	2,174
October .....	RE 3,379	E 2,996	238	RE 2,757	5	199	482	-282	-92	R -64	2,323
November .....	RE 3,370	RE 2,990	231	E 2,760	5	212	527	-315	-4	-6	2,440
December .....	RE 3,508	RE 3,094	225	RE 2,869	6	267	552	-285	587	R -18	R 3,158
Total .....	RE 40,690	RE 36,173	2,737	RE 33,436	64	2,552	5,281	-2,729	-178	R -110	30,482
2021 January .....	RE 3,499	RE 3,093	R 232	RE 2,861	5	284	562	-278	707	R -9	R 3,286
February .....	E 2,935	E 2,588	171	E 2,417	6	272	427	-155	781	-13	3,037
2-Month Total .....	E 6,434	E 5,682	403	E 5,279	11	556	989	-433	1,488	-22	6,323
2020 2-Month Total .....	E 6,932	E 6,140	446	E 5,695	12	501	965	-464	1,106	-20	6,329
2019 2-Month Total .....	6,452	5,689	397	5,292	10	524	695	-171	1,316	-17	6,431

<sup>a</sup> Gases withdrawn from natural gas, crude oil, coalbed, and shale gas wells. Includes natural gas, natural gas plant liquids, and nonhydrocarbon gases; but excludes lease condensate.

<sup>b</sup> Gross withdrawals minus natural repressuring, nonhydrocarbon gases removed, and vented and flared. See Note 1, "Natural Gas Production," at end of section.

<sup>c</sup> Natural gas plant liquids (NGPL) production, gaseous equivalent. This data series was previously called "Extraction Loss." See Note 2, "Natural Gas Plant Liquids Production," at end of section.

<sup>d</sup> Marketed production (wet) minus NGPL production.

<sup>e</sup> See Note 3, "Supplemental Gaseous Fuels," at end of section.

<sup>f</sup> Net withdrawals from underground storage. For 1980–2017, also includes net withdrawals of liquefied natural gas in above-ground tanks. See Note 4, "Natural Gas Storage," at end of section.

<sup>g</sup> See Note 5, "Natural Gas Balancing Item," at end of section. Beginning in 1980, excludes transit shipments that cross the U.S.-Canada border (i.e., natural gas delivered to its destination via the other country).

<sup>h</sup> See Note 6, "Natural Gas Consumption," at end of section.

<sup>i</sup> Through 1979, may include unknown quantities of nonhydrocarbon gases.

<sup>j</sup> For 1989–1992, a small amount of consumption at independent power

producers may be counted in both "Other Industrial" and "Electric Power Sector" on Table 4.3. See Note 7, "Natural Gas Consumption, 1989–1992," at end of section.

R=Revised. E=Estimate. NA=Not available.

Notes: • See Note 8, "Natural Gas Data Adjustments, 1993–2000," at end of section. • Through 1964, all volumes are shown on a pressure base of 14.65 psia (pounds per square inch absolute) at 60° Fahrenheit; beginning in 1965, the pressure base is 14.73 psia at 60° Fahrenheit. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia (except Alaska, for which underground storage is excluded from "Net Storage Withdrawals" through 2012).

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **Imports and Exports:** Table 4.2. • **Consumption:** Table 4.3. • **Balancing Item:** Calculated as consumption minus dry gas production, supplemental gaseous fuels, net imports, and net storage withdrawals. • **All Other Data: 1949–2019—**U.S. Energy Information Administration (EIA), *Natural Gas Annual*, annual reports. **2020 forward—**EIA, *Natural Gas Monthly*, April 2021, Table 1.

**Table 4.2 Natural Gas Trade by Country**  
(Billion Cubic Feet)

	Imports									Exports <sup>a</sup>				
	Algeria <sup>b</sup>	Canada <sup>c</sup>	Egypt <sup>b</sup>	Mexico <sup>c</sup>	Nigeria <sup>b</sup>	Qatar <sup>b</sup>	Trinidad and Tobago <sup>b</sup>	Other <sup>b,d</sup>	Total	Canada <sup>c</sup>	Japan <sup>b</sup>	Mexico <sup>c</sup>	Other <sup>b,e</sup>	Total
1950 Total .....	0	0	0	0	0	0	0	0	0	3	0	23	0	26
1955 Total .....	0	11	0	(s)	0	0	0	0	11	11	0	20	0	31
1960 Total .....	0	109	0	47	0	0	0	0	156	6	0	6	0	11
1965 Total .....	0	405	0	52	0	0	0	0	456	18	0	8	0	26
1970 Total .....	1	779	0	(s)	0	0	0	0	821	11	44	15	0	70
1975 Total .....	5	948	0	0	0	0	0	0	953	10	53	9	0	73
1980 Total .....	86	797	0	102	0	0	0	0	985	(s)	45	4	0	49
1985 Total .....	24	926	0	0	0	0	0	0	950	(s)	53	2	0	55
1990 Total .....	84	1,448	0	0	0	0	0	0	1,532	17	53	16	0	86
1995 Total .....	18	2,816	0	7	0	0	0	0	2,841	28	65	61	0	154
2000 Total .....	47	3,544	0	12	13	46	99	21	3,782	73	66	106	0	244
2005 Total .....	97	3,700	73	9	8	3	439	11	4,341	358	65	305	0	729
2006 Total .....	17	3,590	120	13	57	0	389	0	4,186	341	61	322	0	724
2007 Total .....	77	3,783	115	54	95	18	448	18	4,608	482	47	292	2	822
2008 Total .....	0	3,589	55	43	12	3	267	15	3,984	559	39	365	0	963
2009 Total .....	0	3,271	160	28	13	13	236	29	3,751	701	31	338	3	1,072
2010 Total .....	0	3,280	73	30	42	46	190	81	3,741	739	33	333	32	1,137
2011 Total .....	0	3,117	35	3	2	91	129	92	3,469	937	18	499	52	1,506
2012 Total .....	0	2,963	3	0	0	34	112	26	3,138	971	14	620	14	1,619
2013 Total .....	0	2,786	0	1	3	7	70	17	2,883	911	0	661	0	1,572
2014 Total .....	0	2,635	0	1	0	0	43	16	2,695	770	13	729	3	1,514
2015 Total .....	0	2,626	0	1	0	0	71	20	2,718	701	8	1,054	20	1,784
2016 Total .....	0	2,918	0	(s)	0	0	84	3	3,006	771	11	1,405	148	2,335
2017 Total .....	0	2,955	0	1	6	0	70	0	3,033	917	53	1,671	513	3,154
2018 Total .....	0	2,811	0	3	3	0	66	6	2,889	836	126	1,871	775	3,608
2019 January .....	0	276	0	(s)	0	0	12	3	291	87	17	165	95	365
February .....	0	226	0	(s)	0	0	7	0	233	92	10	142	86	330
March .....	0	249	0	(s)	0	0	3	0	253	93	7	157	117	374
April .....	0	204	0	(s)	0	0	3	0	207	71	14	150	102	338
May .....	0	208	0	(s)	0	0	0	0	208	70	7	174	117	369
June .....	0	201	0	(s)	0	0	0	0	201	62	15	173	110	360
July .....	0	228	0	(s)	0	0	3	0	230	69	21	192	111	393
August .....	0	217	0	(s)	0	0	3	0	220	78	18	182	107	385
September .....	0	208	0	(s)	0	0	0	0	208	72	28	173	122	395
October .....	0	205	0	(s)	0	0	6	0	211	76	25	178	147	426
November .....	0	221	0	(s)	0	0	3	0	224	92	18	162	170	441
December .....	0	245	0	1	3	0	7	0	256	109	21	161	189	481
Total .....	0	2,687	0	2	3	0	47	3	2,742	972	201	2,010	1,474	4,656
2020 January .....	0	249	0	(s)	2	0	9	3	262	99	32	168	211	510
February .....	0	232	0	(s)	0	0	6	0	238	77	21	154	201	454
March .....	0	210	0	(s)	0	0	3	(s)	213	87	22	174	215	497
April .....	0	187	0	(s)	0	0	3	0	190	72	18	139	192	421
May .....	0	184	0	(s)	0	0	3	0	187	68	14	145	169	395
June .....	0	183	0	(s)	3	0	2	0	188	67	22	163	87	338
July .....	0	206	0	(s)	0	0	4	0	210	72	11	181	86	349
August .....	0	208	0	(s)	0	0	3	0	211	61	23	190	86	359
September .....	0	173	0	(s)	0	0	1	0	174	62	7	185	141	395
October .....	0	199	0	(s)	0	0	0	0	199	73	32	193	184	482
November .....	0	209	0	(s)	0	0	3	(s)	212	80	33	169	245	527
December .....	0	261	0	(s)	3	0	3	(s)	267	83	54	165	250	552
Total .....	0	2,501	0	2	7	0	39	3	2,552	900	288	2,026	2,067	5,281
2021 January .....	0	278	0	(s)	0	0	6	(s)	284	<sup>R</sup> 84	64	173	<sup>R</sup> 241	562
February .....	0	265	0	1	0	0	6	0	272	78	18	150	180	427
2-Month Total .....	0	543	0	1	0	0	12	0	556	162	83	323	421	989
2020 2-Month Total .....	0	481	0	1	2	0	14	3	501	177	54	322	412	965
2019 2-Month Total .....	0	502	0	(s)	0	0	19	3	524	179	28	307	181	695

<sup>a</sup> Includes re-exports.

<sup>b</sup> As liquefied natural gas.

<sup>c</sup> By pipeline, except for small amounts of: liquefied natural gas (LNG) imported from Canada in 1973, 1977, 1981, and 2013 forward; LNG exported to Canada in 2007 and 2012 forward; compressed natural gas (CNG) imported from Canada in 2014 forward; CNG exported to Canada in 2013 forward; and LNG exported to Mexico beginning in 1998. See Note 9, "Natural Gas Imports and Exports," at end of section.

<sup>d</sup> Australia in 1997–2001 and 2004; Brunei in 2002; Equatorial Guinea in 2007; Indonesia in 1986 and 2000; Malaysia in 1999 and 2002–2005; Norway in 2008–2016 and 2020; Oman in 2000–2005; Peru in 2010 and 2011; United Arab Emirates in 1996–2000; United Kingdom in 2018; Yemen in 2010–2015; and Other (unassigned) in 2004–2015.

<sup>e</sup> Argentina in 2016–2020; Bahamas in 2017–2020; Bangladesh 2019 and 2020; Barbados in 2016–2020; Belgium in 2019 and 2020; Brazil in 2010–2012, and 2014–2020; Chile in 2011, 2016–2020; China in 2011, 2016–2020; Croatia in 2020; Colombia in 2018–2020; Dominican Republic in 2016–2020; Egypt in 2015–2018; France in 2018–2020; Greece in 2018–2020; Haiti 2019 and 2020; India in 2010–2012, 2016–2020; Israel 2018 and 2020; Italy in 2016–2020; Jamaica 2018–2020; Jordan in 2016–2020; Kuwait in 2016–2020; Lithuania in 2017 and 2019–2020; Malaysia in 2019; Malta in 2017–2020; Netherlands in 2017–2020; Pakistan in 2017–2020; Panama in 2018–2020; Poland in 2017–2020; Portugal in

2012, 2016–2020; Russia in 2007; Singapore in 2018–2020; South Korea in 2009–2011, 2016–2020; Spain in 2010–2011, 2016–2020; Taiwan in 2015, 2017–2020; Thailand in 2017, 2019–2020; Turkey in 2015–2020; United Arab Emirates in 2016–2020; and United Kingdom in 2010, 2011, 2017–2020.

(s)=Less than 500 million cubic feet.

Notes: • See Note 9, "Natural Gas Imports and Exports," at end of section. • Through 1964, all volumes are shown on a pressure base of 14.65 psia (pounds per square inch absolute) at 60° Fahrenheit; beginning in 1965, the pressure base is 14.73 psia at 60° Fahrenheit. • Totals may not equal sum of components due to independent rounding. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • 1949–1954: U.S. Energy Information Administration (EIA) estimates based on Bureau of Mines, Minerals Yearbook, "Natural Gas" chapter. • 1955–1971: Federal Power Commission data. • 1972–1987: EIA, Form FPC-14, "Annual Report for Importers and Exporters of Natural Gas." • 1988–2019: EIA, *Natural Gas Annual*, annual reports. • 2020 forward: EIA, *Natural Gas Monthly*, March 2021, Tables 4 and 5; and U.S. Department of Energy, Office of Fossil Energy, "Natural Gas Imports and Exports."



**Table 4.3 Natural Gas Consumption by Sector**  
(Billion Cubic Feet)

	End-Use Sectors										Electric Power Sector <sup>f,g</sup>	Total	
	Residential	Commercial <sup>a</sup>	Industrial					Transportation					
			Lease and Plant Fuel	Other Industrial			Total	Pipelines <sup>d</sup> and Distribution <sup>e</sup>	Vehicle Fuel	Total			
				CHP <sup>b</sup>	Non-CHP <sup>c</sup>	Total							
1950 Total .....	1,198	388	928	(h)	2,498	2,498	3,426	126	NA	126	629	5,767	
1955 Total .....	2,124	629	1,131	(h)	3,411	3,411	4,542	245	NA	245	1,153	8,694	
1960 Total .....	3,103	1,020	1,237	(h)	4,535	4,535	5,771	347	NA	347	1,725	11,967	
1965 Total .....	3,903	1,444	1,156	(h)	5,955	5,955	7,112	501	NA	501	2,321	15,280	
1970 Total .....	4,837	2,399	1,399	(h)	7,851	7,851	9,249	722	NA	722	3,932	21,139	
1975 Total .....	4,924	2,508	1,396	(h)	6,968	6,968	8,365	583	NA	583	3,158	19,538	
1980 Total .....	4,752	2,611	1,026	(h)	7,172	7,172	8,198	635	NA	635	3,682	19,877	
1985 Total .....	4,433	2,432	966	(h)	5,901	5,901	6,867	504	NA	504	3,044	17,281	
1990 Total .....	4,391	2,623	1,236		<sup>i</sup> 5,963	<sup>i</sup> 7,018	8,255	660	(s)	660	<sup>i</sup> 3,245	<sup>i</sup> 19,174	
1995 Total .....	4,850	3,031	1,220		6,906	8,164	9,384	700	5	705	4,237	22,207	
2000 Total .....	4,996	3,182	1,151		6,757	8,142	9,293	642	13	655	5,206	23,333	
2005 Total .....	4,827	2,999	1,112		6,084	6,601	7,713	584	23	607	5,869	22,014	
2006 Total .....	4,368	2,832	1,142		6,115	6,527	7,669	584	24	608	6,222	21,699	
2007 Total .....	4,722	3,013	1,226		6,050	6,655	7,881	621	25	646	6,841	23,104	
2008 Total .....	4,892	3,153	1,220		955	5,715	6,670	7,890	648	26	674	6,668	23,277
2009 Total .....	4,779	3,119	1,275		990	5,178	6,167	7,443	670	27	697	6,873	22,910
2010 Total .....	4,782	3,103	1,286		1,029	5,797	6,826	8,112	674	29	703	7,387	24,087
2011 Total .....	4,714	3,155	1,323		1,063	5,931	6,994	8,317	688	30	718	7,574	24,477
2012 Total .....	4,150	2,895	1,396		1,149	6,077	7,226	8,622	731	30	761	9,111	25,538
2013 Total .....	4,897	3,295	1,483		1,170	6,255	7,425	8,909	833	30	863	8,191	26,155
2014 Total .....	5,087	3,466	1,512		1,145	6,501	7,646	9,158	700	35	735	8,146	26,593
2015 Total .....	4,613	3,202	1,576		1,222	6,300	7,522	9,098	678	39	718	9,613	27,244
2016 Total .....	4,347	3,110	1,545		1,209	6,519	7,729	9,274	687	42	729	9,985	27,444
2017 Total .....	4,412	3,164	1,584		1,257	6,693	7,949	9,533	722	48	770	9,266	27,146
2018 Total .....	4,998	3,514	1,694		1,314	7,103	8,417	10,112	877	50	927	10,590	30,140
2019 January .....	953	554	151		121	680	801	952	105	4	110	849	3,417
February .....	809	472	137		108	611	719	856	93	4	97	779	3,013
March .....	688	424	153		113	638	751	903	89	4	93	814	2,922
April .....	328	246	148		105	571	676	824	66	4	71	740	2,209
May .....	212	185	154		111	564	675	830	64	4	68	836	2,131
June .....	129	145	150		111	524	635	785	64	4	68	991	2,117
July .....	112	142	156		118	532	650	806	73	4	77	1,255	2,391
August .....	102	141	160		120	552	672	832	74	4	78	1,278	2,430
September .....	110	143	154		114	530	644	799	67	4	71	1,081	2,203
October .....	232	216	162		114	570	684	846	70	4	74	937	2,305
November .....	589	389	158		117	618	735	893	85	4	89	819	2,778
December .....	752	457	163		122	657	779	942	96	4	101	912	3,163
Total .....	5,016	3,513	1,846		1,374	7,047	8,422	10,268	944	51	995	11,288	31,080
2020 January .....	821	487	<sup>E</sup> 161		125	666	791	952	<sup>E</sup> 100	<sup>E</sup> 5	<sup>E</sup> 105	931	3,296
February .....	733	443	<sup>E</sup> 150		114	618	732	881	<sup>E</sup> 92	<sup>E</sup> 5	<sup>E</sup> 97	879	3,033
March .....	525	337	<sup>E</sup> 160		115	605	720	880	<sup>E</sup> 82	<sup>E</sup> 5	<sup>E</sup> 87	879	2,708
April .....	375	237	<sup>E</sup> 152		107	537	644	796	<sup>E</sup> 68	<sup>E</sup> 5	<sup>E</sup> 73	764	2,245
May .....	235	161	<sup>E</sup> 148		108	517	625	773	<sup>E</sup> 63	<sup>E</sup> 5	<sup>E</sup> 68	834	2,071
June .....	136	132	<sup>E</sup> 145		110	497	607	753	<sup>E</sup> 65	<sup>E</sup> 5	<sup>E</sup> 70	1,046	2,135
July .....	117	128	<sup>E</sup> 153		116	525	641	794	<sup>E</sup> 76	<sup>E</sup> 5	<sup>E</sup> 81	1,372	2,493
August .....	109	131	<sup>E</sup> 154		116	537	654	807	<sup>E</sup> 73	<sup>E</sup> 5	<sup>E</sup> 78	1,280	2,404
September .....	125	142	<sup>E</sup> 147		107	543	651	798	<sup>E</sup> 66	<sup>E</sup> 5	<sup>E</sup> 71	1,038	2,174
October .....	240	207	<sup>E</sup> 151		112	582	695	846	<sup>E</sup> 71	<sup>E</sup> 5	<sup>E</sup> 76	954	2,323
November .....	439	293	<sup>E</sup> 151		111	600	711	862	<sup>E</sup> 74	<sup>E</sup> 5	<sup>E</sup> 79	767	2,440
December .....	793	449	<sup>RE</sup> 156		125	662	787	943	<sup>E</sup> 96	<sup>E</sup> 5	<sup>E</sup> 101	873	<sup>R</sup> 3,158
Total .....	4,648	3,147	<sup>E</sup> 1,829		1,367	6,890	8,257	10,086	<sup>E</sup> 926	<sup>E</sup> 59	<sup>E</sup> 985	11,616	30,482
2021 January .....	876	491	<sup>E</sup> 156		123	<sup>R</sup> 669	<sup>R</sup> 791	<sup>R</sup> 948	<sup>E</sup> 100	<sup>E</sup> 5	<sup>E</sup> 105	866	<sup>R</sup> 3,286
February .....	860	489	<sup>E</sup> 131		99	573	672	803	<sup>E</sup> 92	<sup>E</sup> 5	<sup>E</sup> 97	788	3,037
2-Month Total .....	1,736	980	<sup>E</sup> 287		222	1,242	1,464	1,751	<sup>E</sup> 192	<sup>E</sup> 10	<sup>E</sup> 202	1,654	6,323
2020 2-Month Total .....	1,553	930	<sup>E</sup> 310		239	1,284	1,523	1,834	<sup>E</sup> 192	<sup>E</sup> 10	<sup>E</sup> 202	1,810	6,329
2019 2-Month Total .....	1,762	1,026	288		229	1,292	1,521	1,808	198	8	206	1,628	6,431

<sup>a</sup> All commercial sector fuel use, including that at commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Table 7.4c for CHP fuel use.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and a small number of industrial electricity-only plants.

<sup>c</sup> All industrial sector fuel use other than that in "Lease and Plant Fuel" and "CHP."

<sup>d</sup> Natural gas consumed in the operation of pipelines, primarily in compressors. Beginning in 2009, includes line loss, which is known volumes of natural gas that are the result of leaks, damage, accidents, migration, and/or blow down.

<sup>e</sup> Natural gas used as fuel in the delivery of natural gas to consumers. Beginning in 2009, includes line loss, which is known volumes of natural gas that are the result of leaks, damage, accidents, migration, and/or blow down.

<sup>f</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>g</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

<sup>h</sup> Included in "Non-CHP."

<sup>i</sup> For 1989–1992, a small amount of consumption at independent power producers may be counted in both "Other Industrial" and "Electric Power Sector." See Note 7, "Natural Gas Consumption, 1989–1992," at end of section.

R=Revised. E=Estimate. NA=Not available. (s)=Less than 500 million cubic feet.

Notes: • Data are for natural gas, plus a small amount of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of section.

• See Note 8, "Natural Gas Data Adjustments, 1993–2000," at end of section.

• See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • Through 1964, all volumes are shown on a pressure base of 14.65 psia (pounds per square inch absolute) at 60° Fahrenheit; beginning in 1965, the pressure base is 14.73 psia at 60° Fahrenheit. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **Residential, Commercial, Lease and Plant Fuel, Other Industrial Total and Pipelines and Distribution: 1949–2019**—U.S. Energy Information Administration (EIA), *Natural Gas Annual (NGA)*, annual reports and unpublished revisions. **2020 forward**—EIA, *Natural Gas Monthly (NGM)*, April 2021, Table 2. • **Other Industrial CHP:** Table 7.4c. • **Other Industrial Non-CHP:** Calculated as other industrial total minus other industrial CHP. • **Industrial Total:** Calculated as lease and plant fuel plus other industrial total. • **Vehicle Fuel: 1990 and 1991**—EIA, NGA 2000, (November 2001), Table 95. **1992–1998**—EIA, "Alternatives to Traditional Transportation Fuels 1999" (October 1999), Table 10, and "Alternatives to Traditional Transportation Fuels 2003" (February 2004), Table 10. Data for compressed natural gas and liquefied natural gas in gasoline-equivalent gallons were converted to cubic feet by multiplying by the motor gasoline conversion factor (see Table A3) and dividing by the natural gas end-use sectors conversion factor (see Table A4). **1999–2019**—EIA, NGA, annual reports. **2020 forward**—EIA, NGM, April 2021, Table 2. • **Transportation Total:** Calculated as pipelines and distribution plus vehicle fuel. • **Electric Power Sector:** Table 7.4b. • **Total Consumption:** Calculated as the sum of residential, commercial, industrial total, transportation total, and electric power sector.

**Table 4.4 Natural Gas in Underground Storage**  
(Volumes in Billion Cubic Feet)

	Natural Gas in Underground Storage, End of Period			Change in Working Gas From Same Period Previous Year		Storage Activity		
	Base Gas	Working Gas	Total <sup>a</sup>	Volume	Percent	Withdrawals	Injections	Net <sup>b,c</sup>
1950 Total .....	NA	NA	NA	NA	NA	175	230	-54
1955 Total .....	863	505	1,368	40	8.7	437	505	-68
1960 Total .....	NA	NA	2,184	NA	NA	713	844	-132
1965 Total .....	1,848	1,242	3,090	83	7.2	960	1,078	-118
1970 Total .....	2,326	1,678	4,004	257	18.1	1,459	1,857	-398
1975 Total .....	3,162	2,212	5,374	162	7.9	1,760	2,104	-344
1980 Total .....	3,642	2,655	6,297	-99	-3.6	1,910	1,896	14
1985 Total .....	3,842	2,607	6,448	-270	-9.4	2,359	2,128	231
1990 Total .....	3,868	3,068	6,936	555	22.1	1,934	2,433	-499
1995 Total .....	4,349	2,153	6,503	-453	-17.4	2,974	2,566	408
2000 Total .....	4,352	1,719	6,071	-806	-31.9	3,498	2,684	814
2005 Total .....	4,200	2,635	6,835	-61	-2.3	3,057	3,002	55
2006 Total .....	4,211	3,070	7,281	435	16.5	2,493	2,924	-431
2007 Total .....	4,234	2,879	7,113	-191	-6.2	3,325	3,133	192
2008 Total .....	4,232	2,840	7,073	-39	-1.4	3,374	3,340	34
2009 Total .....	4,277	3,130	7,407	290	10.2	2,966	3,315	-349
2010 Total .....	4,301	3,111	7,412	-19	-6	3,274	3,291	-17
2011 Total .....	4,302	3,462	7,764	351	11.3	3,074	3,422	-348
2012 Total .....	4,372	3,413	7,785	-49	-1.4	2,818	2,825	-7
2013 Total .....	4,365	2,890	7,255	-523	-15.3	3,702	3,156	546
2014 Total .....	4,365	3,141	7,506	251	8.7	3,586	3,839	-253
2015 Total .....	4,372	3,667	8,038	525	16.7	3,100	3,638	-539
2016 Total .....	4,380	3,297	7,677	-370	-10.1	3,325	2,977	348
2017 Total .....	4,360	3,033	7,392	-264	-8.0	3,590	3,337	254
2018 Total .....	4,361	2,708	7,069	-324	-10.7	3,999	3,676	324
<b>2019 January</b> .....	4,366	1,994	6,360	-147	-6.8	804	95	709
February .....	4,366	1,426	5,792	-246	-14.7	672	104	568
March .....	4,361	1,185	5,545	-205	-14.8	435	190	245
April .....	4,367	1,559	5,927	133	9.3	104	486	-382
May .....	4,372	2,031	6,403	184	9.9	85	557	-472
June .....	4,375	2,461	6,835	266	12.1	92	523	-431
July .....	4,374	2,714	7,089	333	14.0	162	416	-254
August .....	4,377	2,998	7,374	381	14.6	168	453	-286
September .....	4,378	3,415	7,793	465	15.7	109	529	-419
October .....	4,379	3,762	8,141	526	16.2	116	461	-346
November .....	4,380	3,610	7,990	580	19.1	351	201	150
December .....	4,380	3,188	7,568	480	17.7	556	138	418
<b>Total</b> .....	<b>4,380</b>	<b>3,188</b>	<b>7,568</b>	<b>480</b>	<b>17.7</b>	<b>3,653</b>	<b>4,153</b>	<b>-500</b>
<b>2020 January</b> .....	4,380	2,616	6,997	622	31.2	665	94	571
February .....	4,379	2,081	6,460	655	45.9	634	99	535
March .....	4,379	2,030	6,409	845	71.3	285	236	49
April .....	4,384	2,333	6,717	773	49.6	131	437	-306
May .....	4,387	2,778	7,165	747	36.8	74	522	-448
June .....	4,389	3,133	7,523	672	27.3	85	443	-358
July .....	4,390	3,294	7,684	579	21.3	151	312	-161
August .....	4,390	3,522	7,912	524	17.5	174	401	-227
September .....	4,389	3,840	8,229	425	12.4	126	450	-323
October .....	4,393	3,929	8,321	166	4.4	191	283	-92
November .....	4,394	3,932	8,325	322	8.9	214	218	-4
December .....	4,394	3,341	7,735	153	4.8	681	94	587
<b>Total</b> .....	<b>4,394</b>	<b>3,341</b>	<b>7,735</b>	<b>153</b>	<b>4.8</b>	<b>3,412</b>	<b>3,590</b>	<b>-178</b>
<b>2021 January</b> .....	4,394	2,635	7,029	19	.7	783	76	707
February .....	4,390	1,858	6,248	-223	-10.7	904	122	781
<b>2-Month Total</b> .....	--	--	--	--	--	<b>1,687</b>	<b>198</b>	<b>1,488</b>
<b>2020 2-Month Total</b> .....	--	--	--	--	--	<b>1,299</b>	<b>193</b>	<b>1,106</b>
<b>2019 2-Month Total</b> .....	--	--	--	--	--	<b>1,476</b>	<b>199</b>	<b>1,277</b>

<sup>a</sup> For total underground storage capacity at the end of each calendar year, see Note 4, "Natural Gas Storage," at end of section.

<sup>b</sup> For 1980–2018, data differ from those shown on Table 4.1, which includes liquefied natural gas storage for that period.

<sup>c</sup> Positive numbers indicate that withdrawals are greater than injections. Negative numbers indicate that injections are greater than withdrawals. Net withdrawals or injections may not equal the difference between applicable ending stocks. See Note 4, "Natural Gas Storage," at end of section.

NA=Not available.

Notes: • Through 1964, all volumes are shown on a pressure base of 14.65 psia (pounds per square inch absolute) at 60° Fahrenheit; beginning in 1965, the pressure base is 14.73 psia at 60° Fahrenheit. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia (except Alaska, which is excluded through 2012).

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data

beginning in 1973.

Sources: • **Storage Activity: 1949–1975**—U.S. Energy Information Administration (EIA), *Natural Gas Annual 1994, Volume 2*, Table 9. **1976–1979**—EIA, *Natural Gas Production and Consumption 1979*, Table 1. **1980–1995**—EIA, *Historical Natural Gas Annual 1930 Through 2000*, Table 11. **1996–2014**—EIA, *Natural Gas Monthly (NGM)*, monthly issues. **2015 forward**—EIA, NGM, January 2021, Table 8. • **All Other Data: 1954–1974**—American Gas Association, *Gas Facts*, annual issues. **1975 and 1976**—Federal Energy Administration (FEA), Form FEA-G318-M-0, "Underground Gas Storage Report," and Federal Power Commission (FPC), Form FPC-8, "Underground Gas Storage Report." **1977 and 1978**—EIA, Form FEA-G318-M-0, "Underground Gas Storage Report," and Federal Energy Regulatory Commission (FERC), Form FERC-8, "Underground Gas Storage Report." **1979–1995**—EIA, Form EIA-191, "Underground Gas Storage Report," and FERC, Form FERC-8, "Underground Gas Storage Report." **1996–2019**—EIA, NGA, annual reports. **2020 forward**—EIA, NGM, April 2021, Table 8.

**Note 1. Natural Gas Production.** Final annual data are from the U.S. Energy Information Administration's (EIA) *Natural Gas Annual (NGA)*.

Data for the two most recent months presented are estimated. Some of the data for earlier months are also estimated or computed. For a discussion of computation and estimation procedures, see EIA's *Natural Gas Monthly (NGM)*.

Monthly data are considered preliminary until after publication of the NGA. Preliminary monthly data are gathered from reports to the Interstate Oil Compact Commission and the U.S. Minerals Management Service. Volumetric data are converted, as necessary, to a standard pressure base of 14.73 psia (pounds per square inch absolute) at 60° Fahrenheit. Unless there are major changes, data are not revised until after publication of the NGA.

Differences between annual data in the NGA and the sum of preliminary monthly data (January–December) are allocated proportionally to the months to create final monthly data.

**Note 2. Natural Gas Plant Liquids Production.** Natural gas plant liquids (NGPL) production is the reduction in volume of natural gas resulting from the removal of natural gas liquid constituents at natural gas processing plants—these natural gas plant liquids are transferred to petroleum supply.

Annual data are from EIA's *Natural Gas Annual (NGA)*, where they are estimated on the basis of the type and quantity of liquid products extracted from the gas stream and the calculated volume of such products at standard conditions. For a detailed explanation of the calculations used to derive estimated NGPL production, see the NGA.

Through 2006, preliminary monthly data are estimated on the basis of NGPL production as an annual percentage of marketed production. Beginning in 2007, preliminary monthly data are estimated on the basis of NGPL production reported on Form EIA-816, "Monthly Natural Gas Liquids Report."

Monthly data are revised and considered final after publication of the NGA. Final monthly data are estimated by allocating annual NGPL production data to the months on the basis of total natural gas marketed production data from the NGA.

**Note 3. Supplemental Gaseous Fuels.** Supplemental gaseous fuels are any substances that, introduced into or commingled with natural gas, increase the volume available for disposition. Such substances include, but are not limited to, propane-air, refinery gas, coke oven gas, still gas, manufactured gas, biomass gas, and air or inert gases added for Btu stabilization.

Annual data beginning with 1980 are from EIA's *Natural Gas Annual (NGA)*. Unknown quantities of supplemental gaseous fuels are included in consumption data for 1979 and earlier years. Monthly data are considered preliminary until after publication of the NGA. Monthly estimates are based on the annual ratio of supplemental gaseous fuels to the sum of dry gas production, net imports, and net withdrawals from storage. The ratio is applied to the monthly sum of the three elements to compute a monthly supplemental gaseous fuels figure.

Although the total amount of supplemental gaseous fuels consumed is known for 1980 forward, the amount consumed by each energy-use sector is estimated by EIA. These estimates are used to create natural gas (without supplemental gaseous fuels) data for Tables 1.3, 2.2, 2.3, 2.4, and 2.6 (note: to avoid double-counting in these tables, supplemental gaseous fuels are accounted for in their primary energy category: "Coal," "Petroleum," or "Biomass"). It is assumed that supplemental gaseous fuels are commingled with natural gas consumed by the residential, commercial, other industrial, and electric power sectors, but are not commingled with natural gas used for lease and plant fuel, pipelines and distribution, or vehicle fuel. The estimated consumption of supplemental gaseous fuels by each sector (residential, commercial, other industrial, and electric power) is calculated as that sector's natural gas consumption (see Table 4.3) divided by the sum of natural gas consumption by the residential, commercial, other industrial, and electric power sectors (see Table 4.3), and then multiplied by total supplemental gaseous fuels consumption (see Table 4.1). For estimated sectoral consumption of supplemental gaseous fuels in Btu, the residential, commercial, and other industrial values in cubic feet are multiplied by the "End-Use Sectors" conversion factors (see Table A4), and the electric power

values in cubic feet are multiplied by the "Electric Power Sector" conversion factors (see Table A4). Total supplemental gaseous fuels consumption in Btu is calculated as the sum of the Btu values for the sectors.

**Note 4. Natural Gas Storage.** Natural gas in storage at the end of a reporting period may not equal the quantity derived by adding or subtracting net injections or withdrawals from the quantity in storage at the end of the previous period. Injection and withdrawal data from the FERC-8/EIA-191 survey may be adjusted to correspond to data from Form EIA-176 for publication of EIA's *Natural Gas Annual* (NGA).

Total underground storage capacity, which includes both active and inactive fields, at the end of each calendar year since 1975 (first year data were available), in billion cubic feet, was:

Total underground storage capacity, including active and inactive fields (billion cubic feet)										
Decade	Year-0	Year-1	Year-2	Year-3	Year-4	Year-5	Year-6	Year-7	Year-8	Year-9
1970s						6,280	6,544	6,678	6,890	6,929
1980s	7,434	7,805	7,915	7,985	8,043	8,087	8,145	8,124	8,124	8,120
1990s	7,794	7,993	7,932	7,989	8,043	7,953	7,980	8,332	8,179	8,229
2000s	8,241	8,182	8,207	8,206	8,255	8,268	8,330	8,402	8,499	8,656
2010s	8,764	8,849	8,991	9,173	9,233	9,231	9,239	9,261	9,241	9,231
2020s	<sup>P</sup> 9,259									

P=Preliminary

Through 1990, monthly underground storage data are collected from the Federal Energy Regulatory Commission Form FERC-8 (interstate data) and EIA Form EIA-191 (intrastate data). Beginning in 1991, all data are collected on the revised Form EIA-191. Injection and withdrawal data from the EIA-191 survey may be adjusted to correspond to data from Form EIA-176 following publication of EIA's NGA.

The final monthly and annual storage and withdrawal data for 1980–2017 include both underground and liquefied natural gas (LNG) storage. Annual data on LNG additions and withdrawals are from Form EIA-176. Monthly data are estimated by computing the ratio of each month's underground storage additions and withdrawals to annual underground storage additions and withdrawals and applying the ratio to the annual LNG data.

**Note 5. Natural Gas Balancing Item.** The balancing item for natural gas represents the difference between the sum of the components of natural gas supply and the sum of components of natural gas disposition. The differences may be due to quantities lost or to the effects of data reporting problems. Reporting problems include differences due to the net result of conversions of flow data metered at varying temperature and pressure bases and converted to a standard temperature and pressure base; the effect of variations in company accounting and billing practices; differences between billing cycle and calendar period time frames; and imbalances resulting from the merger of data reporting systems that vary in scope, format, definitions, and type of respondents.

**Note 6. Natural Gas Consumption.** Natural gas consumption statistics include data for the following: "Residential Sector": residential deliveries; "Commercial Sector": commercial deliveries, including to commercial combined-heat-and-power (CHP) and commercial electricity-only plants; "Industrial Sector": lease and plant fuel use, and other industrial deliveries, including to industrial CHP and industrial electricity-only plants also includes the relatively small amount of natural gas consumption for non-combustion use (see Tables 1.11a and 1.11b); "Transportation Sector": pipelines and distribution use, and vehicle fuel use; and "Electric Power Sector": electric utility and independent power producer use.

Final data for series other than "Other Industrial CHP" and "Electric Power Sector" are from EIA's *Natural Gas Annual* (NGA). Monthly data are considered preliminary until after publication of the NGA. For more detailed information on the methods of estimating preliminary and final monthly data, see EIA's *Natural Gas Monthly*.

**Note 7. Natural Gas Consumption, 1989–1992.** Prior to 1993, deliveries to nonutility generators were not separately collected from natural gas companies on Form EIA-176, "Annual Report of Natural and Supplemental Gas Supply and Disposition." As a result, for 1989–1992, those volumes are probably included in both the industrial and electric power

sectors and double-counted in total consumption. In 1993, 0.28 trillion cubic feet was reported as delivered to nonutility generators.

**Note 8. Natural Gas Data Adjustments, 1993–2000.** For 1993–2000, the original data for natural gas delivered to industrial consumers (now "Other Industrial" in Table 4.3) included deliveries to both industrial users and independent power producers (IPPs). These data were adjusted to remove the estimated consumption at IPPs from "Other Industrial" and include it with electric utilities under "Electric Power Sector." (To estimate the monthly IPP consumption, the monthly pattern for Other Industrial CHP in Table 4.3 was used.)

For 1996–2000, monthly data for several natural gas series shown in EIA's Natural Gas Navigator (see [http://www.eia.gov/dnav/ng/ng\\_cons\\_sum\\_dcu\\_nus\\_m.htm](http://www.eia.gov/dnav/ng/ng_cons_sum_dcu_nus_m.htm)) were not reconciled and updated to be consistent with the final annual data in EIA's *Natural Gas Annual*. In the *Monthly Energy Review*, monthly data for these series were adjusted so that the monthly data sum to the final annual values. The Table 4.1 data series (and years) that were adjusted are: Gross Withdrawals (1996, 1997), Marketed Production (1997), NGPL Production (1997, 1998, and 2000), Dry Gas Production (1996, 1997), Supplemental Gaseous Fuels (1997–2000), Balancing Item (1997–2000), and Total Consumption (1997–2000). The Table 4.3 data series (and years) that were adjusted are: Lease and Plant Fuel (1997–2000), Total Industrial (1997–2000), Pipelines and Distribution (2000), Total Transportation (2000), and Total Consumption (1997–2000).

**Note 9. Natural Gas Imports and Exports.** The United States imports natural gas via pipeline from Canada and Mexico; and imports liquefied natural gas (LNG) via tanker from Algeria, Australia, Brunei, Egypt, Equatorial Guinea, Indonesia, Malaysia, Nigeria, Norway, Oman, Peru, Qatar, Trinidad and Tobago, the United Arab Emirates, and Yemen. In addition, small amounts of LNG arrived from Canada in 1973 (667 million cubic feet), 1977 (572 million cubic feet), 1981 (6 million cubic feet), 2013 (555 million cubic feet), 2014 (132 million cubic feet), 2015 (437 million cubic feet), 2016 (924 million cubic feet), 2017 (1,569 million cubic feet), 2018 (1,885 million cubic feet), 2019 (226 million cubic feet), 2020 (43 million cubic feet), and 2021 (10 million cubic feet). Also, small amounts of compressed natural gas (CNG) were imported from Canada in 2014 forward. The United States exports natural gas via pipeline to Canada and Mexico; and exports LNG via tanker to Argentina, Bahamas, Bangladesh, Barbados, Belgium, Brazil, Chile, China, Columbia, Dominican Republic, Egypt, France, Greece, Haiti, India, Israel, Italy, Jamaica, Japan, Jordan, Kuwait, Lithuania, Malaysia, Malta, Netherlands, Pakistan, Panama, Poland, Portugal, Russia, Singapore, South Korea, Spain, Taiwan, Thailand, Turkey, United Arab Emirates, and United Kingdom. Also, small amounts of LNG have gone to Mexico since 1998 and to Canada in 2007 and 2012 forward. Small amounts of CNG have been exported to Canada since 2013.

Annual and final monthly data are from the annual EIA Form FPC-14, "Annual Report for Importers and Exporters of Natural Gas," which requires data to be reported by month for the calendar year.

Preliminary monthly data are EIA estimates. For a discussion of estimation procedures, see EIA's *Natural Gas Monthly*. Preliminary data are revised after publication of EIA's *U.S. Imports and Exports of Natural Gas*.


THIS PAGE INTENTIONALLY LEFT BLANK

## **5. Crude Oil and Natural Gas Resource Development**


---

**Figure 5.1 Crude Oil and Natural Gas Resource Development Indicators**


Rotary Rigs in Operation by Type, 1949–2020




Rotary Rigs in Operation by Type, Monthly



Active Well Service Rig Count, Monthly



Total Wells Drilled by Type, 1949–2010



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#crude>.

Sources: Tables 5.1 and 5.2.



**Table 5.1 Crude Oil and Natural Gas Drilling Activity Measurements**  
(Number of Rigs)

	Rotary Rigs in Operation <sup>a</sup>					Active Well Service Rig Count <sup>c</sup>
	By Site		By Type		Total <sup>b</sup>	
	Onshore	Offshore	Crude Oil	Natural Gas		
1950 Average .....	NA	NA	NA	NA	2,154	NA
1955 Average .....	NA	NA	NA	NA	2,686	NA
1960 Average .....	NA	NA	NA	NA	1,748	NA
1965 Average .....	NA	NA	NA	NA	1,388	NA
1970 Average .....	NA	NA	NA	NA	1,028	NA
1975 Average .....	1,554	106	NA	NA	1,660	2,486
1980 Average .....	2,678	231	NA	NA	2,909	4,089
1985 Average .....	1,774	206	NA	NA	1,980	4,716
1990 Average .....	902	108	532	464	1,010	3,658
1995 Average .....	622	101	323	385	723	3,041
2000 Average .....	778	140	197	720	918	2,692
2005 Average .....	1,287	94	194	1,184	1,381	2,222
2006 Average .....	1,559	90	274	1,372	1,649	2,364
2007 Average .....	1,695	72	297	1,466	1,768	2,388
2008 Average .....	1,814	65	379	1,491	1,879	2,515
2009 Average .....	1,046	44	278	801	1,089	1,722
2010 Average .....	1,514	31	591	943	1,546	1,854
2011 Average .....	1,846	32	984	887	1,879	2,075
2012 Average .....	1,871	48	1,357	558	1,919	2,113
2013 Average .....	1,705	56	1,373	383	1,761	2,064
2014 Average .....	1,804	57	1,527	333	1,862	2,024
2015 Average .....	943	35	750	226	978	1,481
2016 Average .....	486	23	408	100	509	1,061
2017 Average .....	856	20	703	172	876	1,187
2018 Average .....	1,013	19	841	190	1,032	1,292
2019 January .....	1,044	21	866	199	1,065	1,295
February .....	1,029	20	853	195	1,048	1,299
March .....	1,001	22	830	193	1,023	1,292
April .....	990	22	824	189	1,013	1,321
May .....	965	21	802	184	986	1,316
June .....	945	24	790	179	970	1,297
July .....	930	25	782	172	955	1,297
August .....	900	26	760	166	926	1,272
September .....	852	26	726	152	878	1,221
October .....	825	23	708	139	848	1,173
November .....	788	22	678	130	810	1,149
December .....	781	23	673	128	804	1,108
Average .....	920	23	774	169	943	1,253
2020 January .....	770	21	671	118	791	1,086
February .....	768	23	678	110	790	1,046
March .....	752	20	663	106	771	802
April .....	548	18	471	93	565	456
May .....	335	13	267	79	348	490
June .....	262	12	196	76	274	549
July .....	243	12	181	72	255	617
August .....	237	13	178	70	250	674
September .....	242	15	181	73	257	741
October .....	266	14	204	73	280	788
November .....	298	12	234	74	311	800
December .....	326	15	260	80	341	811
Average .....	417	15	345	85	433	738
2021 January .....	358	16	287	86	374	835
February .....	381	17	305	91	397	838
March .....	395	13	315	92	408	R 923
April .....	424	12	341	94	436	NA
4-Month Average .....	391	14	313	91	406	NA
2020 4-Month Average .....	713	20	623	107	733	848
2019 4-Month Average .....	1,015	21	842	194	1,036	1,302

<sup>a</sup> Rotary rigs in operation are reported weekly on Fridays. Monthly data are averages of 4- or 5-week reporting periods. Multi-month data are averages of the reported weekly data over the covered months. Annual data are averages of 52- or 53-week reporting periods. Published data are rounded to the nearest whole number.

<sup>b</sup> Sum of rigs drilling for crude oil, rigs drilling for natural gas, and other rigs (not shown) drilling for miscellaneous purposes, such as service wells, injection wells, and stratigraphic tests. Therefore, "Total" values may not equal the sum of "Crude Oil" and "Natural Gas." "Total" values may not equal the sum of "Onshore" and "Offshore" due to independent rounding.

<sup>c</sup> The number of rigs doing true workovers (where tubing is pulled from the well),

or doing rod string and pump repair operations, and that are, on average, crewed and working every day of the month.

R=Revised. NA=Not available.

Note: Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#crude> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **Rotary Rigs in Operation:** Baker Hughes, Inc., Houston, TX, "North America Rig Count," used with permission. See <http://phx.corporate-ir.net/phoenix.zhtml?c=79687&p=irol-reports&other>. • **Active Well Service Rig Count:** Energy Workforce & Technology Council, Houston, TX.

**Table 5.2 Crude Oil and Natural Gas Exploratory and Development Wells**

	Wells Drilled												Total Footage Drilled
	Exploratory				Development				Total				
	Crude Oil	Natural Gas	Dry	Total	Crude Oil	Natural Gas	Dry	Total	Crude Oil	Natural Gas	Dry	Total	
	Number												
1950 Total .....	1,583	431	8,292	10,306	22,229	3,008	6,507	31,744	23,812	3,439	14,799	42,050	157,358
1955 Total .....	2,236	874	11,832	14,942	28,196	3,392	8,620	40,208	30,432	4,266	20,452	55,150	226,182
1960 Total .....	1,321	868	9,515	11,704	20,937	4,281	8,697	33,915	22,258	5,149	18,212	45,619	192,176
1965 Total .....	946	515	8,005	9,466	17,119	3,967	8,221	29,307	18,065	4,482	16,226	38,773	174,882
1970 Total .....	757	477	6,162	7,396	12,211	3,534	4,869	20,614	12,968	4,011	11,031	28,010	138,556
1975 Total .....	982	1,248	7,129	9,359	15,966	6,879	6,517	29,362	16,948	8,127	13,646	38,721	180,494
1980 Total .....	1,777	2,099	9,081	12,957	31,182	15,362	11,704	58,248	32,959	17,461	20,785	71,205	316,943
1985 Total .....	1,680	1,200	8,954	11,834	33,581	13,124	12,257	58,962	35,261	14,324	21,211	70,796	314,409
1990 Total .....	778	811	3,652	5,241	12,061	10,435	4,593	27,089	12,839	11,246	8,245	32,330	156,044
1995 Total .....	570	558	2,024	3,152	7,678	7,524	2,790	17,992	8,248	8,082	4,814	21,144	117,156
2000 Total .....	288	657	1,341	2,286	7,802	16,394	2,805	27,001	8,090	17,051	4,146	29,287	144,425
2005 Total .....	539	2,141	1,462	4,142	10,240	26,449	3,191	39,880	10,779	28,590	4,653	44,022	240,307
2006 Total .....	646	2,456	1,547	4,649	12,739	30,382	3,659	46,780	13,385	32,838	5,206	51,429	282,675
2007 Total .....	808	2,794	1,582	5,184	12,563	29,925	3,399	45,887	13,371	32,719	4,981	51,071	301,515
2008 January .....	88	208	144	440	1,111	2,321	272	3,704	1,199	2,529	416	4,144	25,306
February .....	82	230	107	419	1,080	2,261	247	3,588	1,162	2,491	354	4,007	24,958
March .....	66	216	127	409	1,132	2,363	271	3,766	1,198	2,579	398	4,175	26,226
April .....	68	189	130	387	1,177	2,415	281	3,873	1,245	2,604	411	4,260	26,920
May .....	88	206	124	418	1,317	2,449	240	4,006	1,405	2,655	364	4,424	27,947
June .....	63	195	139	397	1,428	2,540	299	4,267	1,491	2,735	438	4,664	28,739
July .....	79	163	171	413	1,439	2,695	344	4,478	1,518	2,858	515	4,891	29,140
August .....	67	165	144	376	1,448	2,735	379	4,562	1,515	2,900	523	4,938	28,942
September .....	52	166	164	382	1,488	2,667	355	4,510	1,540	2,833	519	4,892	28,960
October .....	80	243	173	496	1,549	2,841	373	4,763	1,629	3,084	546	5,259	31,505
November .....	97	192	160	449	1,361	2,418	334	4,113	1,458	2,610	494	4,562	29,276
December .....	67	172	132	371	1,206	2,196	313	3,715	1,273	2,368	445	4,086	26,222
Total .....	897	2,345	1,715	4,957	15,736	29,901	3,708	49,345	16,633	32,246	5,423	54,302	334,141
2009 January .....	80	171	99	350	1,192	2,253	250	3,695	1,272	2,424	349	4,045	28,077
February .....	62	125	88	275	991	1,925	195	3,111	1,053	2,050	283	3,386	25,440
March .....	59	146	88	293	867	1,771	210	2,848	926	1,917	298	3,141	25,304
April .....	36	68	93	197	755	1,396	205	2,356	791	1,464	298	2,553	21,406
May .....	47	90	80	217	584	1,136	156	1,876	631	1,226	236	2,093	20,055
June .....	44	91	75	210	804	1,297	189	2,290	848	1,388	264	2,500	16,301
July .....	40	100	101	241	789	1,188	217	2,194	829	1,288	318	2,435	13,543
August .....	49	84	88	221	867	1,372	207	2,446	916	1,456	295	2,667	15,970
September .....	61	71	96	228	945	1,170	207	2,322	1,006	1,241	303	2,550	15,547
October .....	55	79	78	212	966	1,167	222	2,355	1,021	1,246	300	2,567	17,261
November .....	38	83	85	206	931	1,133	199	2,263	969	1,216	284	2,469	16,236
December .....	34	98	84	216	894	1,074	213	2,181	928	1,172	297	2,397	16,424
Total .....	605	1,206	1,055	2,866	10,585	16,882	2,470	29,937	11,190	18,088	3,525	32,803	231,562
2010 January .....	55	91	81	227	898	1,264	169	2,331	953	1,355	250	2,558	15,304
February .....	44	71	67	182	871	1,096	144	2,111	915	1,167	211	2,293	16,862
March .....	59	85	88	232	1,062	1,224	216	2,502	1,121	1,309	304	2,734	15,102
April .....	49	78	77	204	1,173	1,152	249	2,574	1,222	1,230	326	2,778	17,904
May .....	48	107	86	241	1,282	1,208	255	2,745	1,330	1,315	341	2,986	17,987
June .....	61	100	90	251	1,385	1,250	302	2,937	1,446	1,350	392	3,188	19,408
July .....	46	103	105	254	1,386	1,443	390	3,219	1,432	1,546	495	3,473	20,847
August .....	56	104	94	254	1,434	1,402	314	3,150	1,490	1,506	408	3,404	22,923
September .....	57	73	88	218	1,374	1,358	268	3,000	1,431	1,431	356	3,218	23,037
October .....	75	87	117	279	1,502	1,463	283	3,248	1,577	1,550	400	3,527	22,123
November .....	62	114	103	279	1,400	1,352	263	3,015	1,462	1,466	366	3,294	24,561
December .....	57	92	70	219	1,317	1,379	243	2,939	1,374	1,471	313	3,158	23,189
Total .....	669	1,105	1,066	2,840	15,084	15,591	3,096	33,771	15,753	16,696	4,162	36,611	239,247

Notes: • Data are estimates. • For 1960–1969, data are for well completion reports received by the American Petroleum Institute during the reporting year; for all other years, data are for well completions in a given year. • Through 1989, these well counts include only the original drilling of a hole intended to discover or further develop already discovered crude oil or natural gas resources. Other drilling activities, such as drilling an old well deeper, drilling of laterals from the original well, drilling of service and injection wells, and drilling for resources other than crude oil or natural gas are excluded. Beginning in 1990, a new well is defined as the first hole in the ground whether it is lateral or not. Due to the methodology used to estimate ultimate well counts from the available partially reported data, the counts shown on this page are frequently revised. See Note, "Crude Oil and

Natural Gas Exploratory and Development Wells," at end of section. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#crude> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **1949–1965:** Gulf Publishing Company, *World Oil*, "Forecast-Review" issue. • **1966–1969:** American Petroleum Institute (API), *Quarterly Review of Drilling Statistics for the United States*, annual summaries and monthly reports. • **1970–1989:** U.S. Energy Information Administration (EIA) computations based on well reports submitted to the API. • **1990 forward:** EIA computations based on well reports submitted to IHS, Inc., Denver, CO.

Data for 2011 forward in this table have been removed while EIA evaluates the quality of the data and the estimation methodology.

## Crude Oil and Natural Gas Resource Development

---

**Note. Crude Oil and Natural Gas Exploratory and Development Wells.** Three well types are considered in the *Monthly Energy Review* (MER) drilling statistics: “completed for crude oil,” “completed for natural gas,” and “dry hole.” Wells that productively encounter both crude oil and natural gas are categorized as “completed for crude oil.” Both development wells and exploratory wells (new field wildcats, new pool tests, and extension tests) are included in the statistics. All other classes of wells drilled in connection with the search for producible hydrocarbons are excluded. If a lateral is drilled at the same time as the original hole it is not counted separately, but its footage is included.

Prior to the March 1985 MER, drilling statistics consisted of completion data for the above types and classes of wells as reported to the American Petroleum Institute (API) during a given month. Due to time lags between the date of well completion and the date of completion reporting to the API, as-reported well completions proved to be an inaccurate indicator of drilling activity. During 1982, for example, as-reported well completions rose, while the number of actual completions fell. Consequently, the drilling statistics published since the March 1985 MER are U.S. Energy Information Administration (EIA) estimates produced by statistically imputing well counts and footage based on the partial data available from the API. These estimates are subject to continuous revision as new data, some of which pertain to earlier months and years, become available. Additional information about the EIA estimation methodology may be found in “Estimating Well Completions,” a feature article published in the March 1985 MER.

THIS PAGE INTENTIONALLY LEFT BLANK


## 6. Coal

---


**Figure 6.1 Coal**

(Million Short Tons)


Overview, 1949–2020




Consumption by Sector, 1949–2020



Overview, Monthly



Electric Power Sector Consumption, Monthly



[a] Includes combined-heat-power (CHP) plants and a small number of electricity-only plants.

[b] For 1978 forward, small amounts of transportation sector use are

included in "Industrial."

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#coal>.

Sources: Tables 6.1 and 6.2.

**Table 6.1 Coal Overview**  
(Thousand Short Tons)

	Production <sup>a</sup>	Waste Coal Supplied <sup>b</sup>	Trade			Stock Change <sup>d,e</sup>	Losses and Unaccounted for <sup>e,f</sup>	Consumption
			Imports	Exports	Net Imports <sup>c</sup>			
<b>1950 Total</b> .....	560,388	NA	365	29,360	-28,995	27,829	9,462	494,102
<b>1955 Total</b> .....	490,838	NA	337	54,429	-54,092	-3,974	-6,292	447,012
<b>1960 Total</b> .....	434,329	NA	262	37,981	-37,719	-3,194	1,722	398,081
<b>1965 Total</b> .....	526,954	NA	184	51,032	-50,848	1,897	2,244	471,965
<b>1970 Total</b> .....	612,661	NA	36	71,733	-71,697	11,100	6,633	523,231
<b>1975 Total</b> .....	654,641	NA	940	66,309	-65,369	32,154	-5,522	562,640
<b>1980 Total</b> .....	829,700	NA	1,194	91,742	-90,548	25,595	10,827	702,730
<b>1985 Total</b> .....	883,638	NA	1,952	92,680	-90,727	-27,934	2,796	818,049
<b>1990 Total</b> .....	1,029,076	3,339	2,699	105,804	-103,104	26,542	-1,730	904,498
<b>1995 Total</b> .....	1,032,974	8,561	9,473	88,547	-79,074	-275	632	962,104
<b>2000 Total</b> .....	1,073,612	9,089	12,513	58,489	-45,976	-48,309	938	1,084,095
<b>2005 Total</b> .....	1,131,498	13,352	30,460	49,942	-19,482	-9,702	9,092	1,125,978
<b>2006 Total</b> .....	1,162,750	14,409	36,246	49,647	-13,401	42,642	8,824	1,112,292
<b>2007 Total</b> .....	1,146,635	14,076	36,347	59,163	-22,816	5,812	4,085	1,127,998
<b>2008 Total</b> .....	1,171,809	14,146	34,208	81,519	-47,311	12,354	5,740	1,120,548
<b>2009 Total</b> .....	1,074,923	13,666	22,639	59,097	-36,458	39,668	14,985	997,478
<b>2010 Total</b> .....	1,084,368	13,651	19,353	81,716	-62,363	-13,039	182	1,048,514
<b>2011 Total</b> .....	1,095,628	13,209	13,088	107,259	-94,171	211	11,506	1,002,948
<b>2012 Total</b> .....	1,016,458	11,196	9,159	125,746	-116,586	6,902	14,980	889,185
<b>2013 Total</b> .....	984,842	11,279	8,906	117,659	-108,753	-38,525	1,451	924,442
<b>2014 Total</b> .....	1,000,049	12,090	11,350	97,257	-85,907	-2,601	11,101	917,731
<b>2015 Total</b> .....	896,941	9,969	11,318	73,958	-62,640	40,704	5,452	798,115
<b>2016 Total</b> .....	728,364	10,138	9,846	60,271	-50,425	-45,441	2,449	731,071
<b>2017 Total</b> .....	774,609	9,951	7,803	96,945	-89,142	-26,033	4,596	716,856
<b>2018 Total</b> .....	756,167	10,431	5,954	116,244	-110,290	-37,160	5,363	688,105
<b>2019 January</b> .....	65,836	976	625	9,329	-8,704	-4,034	1,942	60,199
February .....	58,315	824	358	6,752	-6,393	1,568	1,978	49,200
March .....	55,667	850	706	9,132	-8,427	-1,181	923	48,348
April .....	61,213	598	537	8,642	-8,105	9,889	6,535	37,282
May .....	61,862	648	408	8,979	-8,572	9,276	602	44,060
June .....	56,706	700	660	8,308	-7,648	1,558	-68	48,267
July .....	59,069	574	511	6,469	-5,958	-5,362	-756	59,802
August .....	63,795	593	519	7,749	-7,230	935	-88	56,311
September .....	58,597	410	651	7,742	-7,091	1,747	-943	51,113
October .....	57,674	498	742	6,590	-5,848	9,912	895	41,518
November .....	54,393	611	466	7,582	-7,116	4,816	-2,798	45,869
December .....	53,184	723	515	6,491	-5,976	6,413	-3,058	44,575
<b>Total</b> .....	<b>706,309</b>	<b>8,003</b>	<b>6,697</b>	<b>93,765</b>	<b>-87,068</b>	<b>35,538</b>	<b>5,164</b>	<b>586,543</b>
<b>2020 January</b> .....	55,612	681	535	6,234	-5,699	6,084	3,789	40,722
February .....	47,379	665	343	6,829	-6,486	5,195	381	35,982
March .....	46,061	527	461	6,914	-6,453	4,810	2,525	32,800
April .....	39,000	515	365	5,480	-5,115	6,796	899	26,704
May .....	36,934	499	498	4,719	-4,222	2,621	769	29,821
June .....	39,259	580	284	4,579	-4,295	-5,691	1,326	39,909
July .....	43,196	706	473	5,359	-4,886	-14,294	361	52,950
August .....	47,499	764	314	4,522	-4,209	-7,939	-1,719	53,712
September .....	45,119	701	501	5,371	-4,870	-1,217	280	41,888
October .....	45,024	679	263	5,045	-4,782	5,720	-2,306	37,507
November .....	44,380	645	639	7,018	-6,379	2,763	-2,145	38,029
December .....	44,839	800	423	7,001	-6,578	-4,224	-4,005	47,290
<b>Total</b> .....	<b>534,302</b>	<b>7,763</b>	<b>5,098</b>	<b>69,071</b>	<b>-63,972</b>	<b>624</b>	<b>154</b>	<b>477,315</b>
<b>2021 January</b> .....	48,565	F 667	526	5,730	-5,204	-6,958	1,793	49,193
February .....	40,292	RF 667	309	7,395	-7,087	R -15,765	R -907	R 50,544
March .....	49,892	NA	R 241	R 7,581	R -7,340	NA	NA	NA
April .....	48,324	NA	NA	NA	NA	NA	NA	NA
<b>4-Month Total</b> .....	<b>187,073</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>
<b>2020 4-Month Total</b> .....	<b>188,052</b>	<b>2,388</b>	<b>1,704</b>	<b>25,456</b>	<b>-23,753</b>	<b>22,885</b>	<b>7,594</b>	<b>136,207</b>
<b>2019 4-Month Total</b> .....	<b>241,031</b>	<b>3,247</b>	<b>2,225</b>	<b>33,855</b>	<b>-31,629</b>	<b>6,242</b>	<b>11,377</b>	<b>195,029</b>

<sup>a</sup> Beginning in 2001, includes a small amount of refuse recovery (coal recaptured from a refuse mine and cleaned to reduce the concentration of noncombustible materials).

<sup>b</sup> Waste coal (including fine coal, coal obtained from a refuse bank or slurry dam, anthracite culm, bituminous gob, and lignite waste) consumed by the electric power and industrial sectors. Beginning in 1989, waste coal supplied is counted as a supply-side item to balance the same amount of waste coal included in "Consumption."

<sup>c</sup> Net imports equal imports minus exports. A minus sign indicates exports are greater than imports.

<sup>d</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase. See Table 6.3 for stocks data coverage.

<sup>e</sup> In 1949, stock change is included in "Losses and Unaccounted for."

<sup>f</sup> The difference between calculated coal supply and disposition, due to coal

quantities lost or to data reporting problems.

R=Revised. NA=Not available. F=Forecast.

Notes: • For methodology used to calculate production, consumption, and stocks, see Note 1, "Coal Production," Note 2, "Coal Consumption," and Note 3, "Coal Stocks," at end of section. • Data values preceded by "F" are derived from the U.S. Energy Information Administration's Short-Term Integrated Forecasting System. See Note 4, "Coal Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#coal> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 6.2 Coal Consumption by Sector**  
(Thousand Short Tons)

	End-Use Sectors										Electric Power Sector <sup>e,f</sup>	Total
	Resi- dential	Commercial			Coke Plants	Industrial			Trans- portation			
		CHP <sup>a</sup>	Other <sup>b</sup>	Total		Other Industrial						
						CHP <sup>c</sup>	Non-CHP <sup>d</sup>	Total				
1950 Total .....	51,562	(g)	63,021	63,021	104,014	(h)	120,623	120,623	224,637	63,011	91,871	494,102
1955 Total .....	35,590	(g)	32,852	32,852	107,743	(h)	110,096	110,096	217,839	16,972	143,759	447,012
1960 Total .....	24,159	(g)	16,789	16,789	81,385	(h)	96,017	96,017	177,402	3,046	176,685	398,081
1965 Total .....	14,635	(g)	11,041	11,041	95,286	(h)	105,560	105,560	200,846	655	244,788	471,965
1970 Total .....	9,024	(g)	7,090	7,090	96,481	(h)	90,156	90,156	186,637	298	320,182	523,231
1975 Total .....	2,823	(g)	6,587	6,587	83,598	(h)	63,646	63,646	147,244	24	405,962	562,640
1980 Total .....	1,355	(g)	5,097	5,097	66,657	(h)	60,347	60,347	127,004	(h)	569,274	702,730
1985 Total .....	1,711	(g)	6,068	6,068	41,056	(h)	75,372	75,372	116,429	(h)	693,841	818,049
1990 Total .....	1,345	1,191	4,189	5,379	38,877	27,781	48,549	76,330	115,207	(h)	782,567	904,498
1995 Total .....	755	1,419	3,633	5,052	33,011	29,363	43,693	73,055	106,067	(h)	850,230	962,104
2000 Total .....	454	1,547	2,126	3,673	28,939	28,031	37,177	65,208	94,147	(h)	985,821	1,084,095
2005 Total .....	378	1,922	2,420	4,342	23,434	25,875	34,465	60,340	83,774	(h)	1,037,485	1,125,978
2006 Total .....	290	1,886	1,050	2,936	22,957	25,262	34,210	59,472	82,429	(h)	1,026,636	1,112,292
2007 Total .....	353	1,927	1,247	3,173	22,715	22,537	34,078	56,615	79,331	(h)	1,045,141	1,127,998
2008 Total .....	(i)	2,021	1,485	3,506	22,070	21,902	32,491	54,393	76,463	(h)	1,040,580	1,120,548
2009 Total .....	(i)	1,798	1,412	3,210	15,326	19,766	25,549	45,314	60,641	(h)	933,627	997,478
2010 Total .....	(i)	1,720	1,361	3,081	21,092	24,638	24,650	49,289	70,381	(h)	975,052	1,048,514
2011 Total .....	(i)	1,668	1,125	2,793	21,434	22,319	23,919	46,238	67,671	(h)	932,484	1,002,948
2012 Total .....	(i)	1,450	595	2,045	20,751	20,065	22,773	42,838	63,589	(h)	823,551	889,185
2013 Total .....	(i)	1,356	595	1,951	21,474	19,761	23,294	43,055	64,529	(h)	857,962	924,442
2014 Total .....	(i)	1,063	824	1,887	21,297	19,076	23,870	42,946	64,243	(h)	851,602	917,731
2015 Total .....	(i)	798	706	1,503	19,708	16,984	21,475	38,459	58,167	(h)	738,444	798,115
2016 Total .....	(i)	683	500	1,183	16,485	14,720	20,129	34,849	51,333	(h)	678,554	731,071
2017 Total .....	(i)	610	451	1,061	17,538	12,975	20,289	33,264	50,801	(h)	664,993	716,856
2018 Total .....	(i)	577	395	972	18,337	12,233	19,347	31,580	49,917	(h)	637,217	688,105
2019 January .....	(i)	59	51	111	1,515	1,119	1,487	2,606	4,121	(h)	55,967	60,199
February .....	(i)	54	47	102	1,393	1,005	1,577	2,582	3,974	(h)	45,124	49,200
March .....	(i)	58	50	108	1,556	932	1,654	2,587	4,142	(h)	44,098	48,348
April .....	(i)	40	27	67	1,450	893	1,444	2,337	3,786	(h)	33,429	37,282
May .....	(i)	38	26	64	1,624	873	1,455	2,328	3,952	(h)	40,045	44,060
June .....	(i)	27	18	45	1,586	844	1,494	2,338	3,925	(h)	44,297	48,267
July .....	(i)	35	13	48	1,498	846	1,478	2,324	3,822	(h)	55,932	59,802
August .....	(i)	37	14	51	1,487	854	1,487	2,341	3,829	(h)	52,431	56,311
September .....	(i)	40	15	55	1,469	814	1,526	2,340	3,810	(h)	47,249	51,113
October .....	(i)	37	27	65	1,494	856	1,579	2,436	3,930	(h)	37,523	41,518
November .....	(i)	44	32	76	1,387	904	1,524	2,429	3,816	(h)	41,977	45,869
December .....	(i)	49	36	86	1,508	950	1,498	2,448	3,956	(h)	40,534	44,575
Total .....	(i)	519	357	876	17,967	10,892	18,203	29,095	47,062	(h)	538,606	586,543
2020 January .....	(i)	41	55	96	1,435	984	1,400	2,384	3,818	(h)	36,808	40,722
February .....	(i)	49	66	115	1,434	940	1,426	2,366	3,801	(h)	32,067	35,982
March .....	(i)	41	55	96	1,408	887	1,431	2,318	3,725	(h)	28,979	32,800
April .....	(i)	29	14	44	1,192	774	1,071	1,845	3,037	(h)	23,624	26,704
May .....	(i)	32	15	47	1,055	750	1,099	1,849	2,904	(h)	26,870	29,821
June .....	(i)	35	17	52	1,208	699	1,204	1,903	3,111	(h)	36,746	39,909
July .....	(i)	35	11	46	1,019	761	1,195	1,956	2,975	(h)	49,930	52,950
August .....	(i)	37	11	49	1,086	735	1,253	1,988	3,074	(h)	50,590	53,712
September .....	(i)	41	13	54	1,058	775	1,213	1,988	3,046	(h)	38,788	41,888
October .....	(i)	34	22	56	1,153	850	1,452	2,301	3,454	(h)	33,997	37,507
November .....	(i)	36	23	58	1,167	826	1,504	2,330	3,497	(h)	34,473	38,029
December .....	(i)	50	32	82	1,200	909	1,447	2,356	3,556	(h)	43,653	47,290
Total .....	(i)	459	334	793	14,414	9,890	15,694	25,584	39,998	(h)	436,524	477,315
2021 January .....	(i)	49	F 15	F 64	F 1,230	886	F 1,514	F 2,400	F 3,631	(h)	45,498	49,193
February .....	(i)	60	F 14	F 74	F 1,442	803	F 1,425	F 2,228	F 3,370	(h)	48,101	50,544
2-Month Total .....	(i)	109	E 29	E 138	E 1,372	1,690	E 2,939	E 4,628	E 6,000	(h)	93,599	99,737
2020 2-Month Total .....	(i)	89	121	210	2,869	1,924	2,826	4,750	7,619	(h)	68,874	76,704
2019 2-Month Total .....	(i)	114	98	212	2,907	2,124	3,064	5,188	8,095	(h)	101,091	109,399

<sup>a</sup> Commercial combined-heat-and-power (CHP) and a small number of commercial electricity-only plants, such as those at hospitals and universities. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>b</sup> All commercial sector fuel use other than that in "Commercial CHP."

<sup>c</sup> Industrial combined-heat-and-power (CHP) and a small number of industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>d</sup> All industrial sector fuel use other than that in "Coke Plants" and "Industrial CHP."

<sup>e</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>f</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

<sup>g</sup> Included in "Commercial Other."

<sup>h</sup> Included in "Industrial Non-CHP."

<sup>i</sup> Beginning in 2008, residential coal consumption data are no longer collected by the U.S. Energy Information Administration (EIA).

E=Estimate. F=Forecast.

Notes: • CHP monthly values are from Table 7.4c; electric power sector monthly values are from Table 7.4b; all other monthly values are estimates derived from collected quarterly and annual data. See Note 2, "Coal Consumption," at end of section. • Data values preceded by "F" are derived from EIA's Short-Term Integrated Forecasting System. See Note 4, "Coal Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#coal> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.



**Table 6.3 Coal Stocks by Sector**  
(Thousand Short Tons)

	Producers and Distributors	End-Use Sectors					Electric Power Sector <sup>c,d</sup>	Total
		Residential <sup>a</sup> and Commercial	Industrial			Total		
			Coke Plants	Other <sup>b</sup>	Total			
1950 Year .....	NA	2,462	16,809	26,182	42,991	45,453	31,842	77,295
1955 Year .....	NA	998	13,422	15,880	29,302	30,300	41,391	71,691
1960 Year .....	NA	666	11,122	11,637	22,759	23,425	51,735	75,160
1965 Year .....	NA	353	10,640	13,122	23,762	24,115	54,525	78,640
1970 Year .....	NA	300	9,045	11,781	20,826	21,126	71,908	93,034
1975 Year .....	12,108	233	8,797	8,529	17,326	17,559	110,724	140,391
1980 Year .....	24,379	NA	9,067	11,951	21,018	21,018	183,010	228,407
1985 Year .....	33,133	NA	3,420	10,438	13,857	13,857	156,376	203,367
1990 Year .....	33,418	NA	3,329	8,716	12,044	12,044	156,166	201,629
1995 Year .....	34,444	NA	2,632	5,702	8,334	8,334	126,304	169,083
2000 Year .....	31,905	NA	1,494	4,587	6,081	6,081	102,296	140,282
2005 Year .....	34,971	NA	2,615	5,582	8,196	8,196	101,137	144,304
2006 Year .....	36,548	NA	2,928	6,506	9,434	9,434	140,964	186,946
2007 Year .....	33,977	NA	1,936	5,624	7,560	7,560	151,221	192,758
2008 Year .....	34,688	498	2,331	6,007	8,338	8,836	161,589	205,112
2009 Year .....	47,718	529	1,957	5,109	7,066	7,595	189,467	244,780
2010 Year .....	49,820	552	1,925	4,525	6,451	7,003	174,917	231,740
2011 Year .....	51,897	603	2,610	4,455	7,065	7,668	172,387	231,951
2012 Year .....	46,157	583	2,522	4,475	6,997	7,581	185,116	238,853
2013 Year .....	45,652	495	2,200	4,097	6,297	6,792	147,884	200,328
2014 Year .....	38,894	449	2,640	4,196	6,836	7,285	151,548	197,727
2015 Year .....	35,871	394	2,236	4,382	6,618	7,012	195,548	238,431
2016 Year .....	25,309	360	1,675	3,637	5,312	5,672	162,009	192,990
2017 Year .....	23,999	310	1,718	3,242	4,960	5,270	137,687	166,956
2018 Year .....	21,692	247	1,807	3,258	5,065	5,312	102,793	129,796
2019 January .....	21,391	238	1,873	3,116	4,989	5,227	99,145	125,763
February .....	23,551	229	1,939	2,974	4,913	5,142	98,637	127,331
March .....	24,160	221	2,005	2,832	4,837	5,058	96,932	126,150
April .....	22,767	214	2,102	2,883	4,985	5,199	108,072	136,039
May .....	24,273	208	2,199	2,934	5,133	5,341	115,700	145,314
June .....	24,529	201	2,296	2,985	5,281	5,483	116,861	146,872
July .....	25,240	212	2,352	3,046	5,398	5,609	110,661	141,511
August .....	26,441	222	2,407	3,107	5,514	5,736	110,268	142,445
September .....	27,714	232	2,463	3,168	5,631	5,863	110,615	144,192
October .....	29,683	237	2,420	3,198	5,618	5,855	118,566	154,104
November .....	30,717	242	2,376	3,228	5,605	5,846	122,357	158,921
December .....	31,320	246	2,333	3,258	5,591	5,838	128,176	165,334
2020 January .....	F 31,382	235	2,271	3,178	5,449	5,684	134,352	171,418
February .....	F 31,803	223	2,210	3,097	5,307	5,530	139,280	176,613
March .....	F 30,829	212	2,148	3,017	5,165	5,376	145,218	181,423
April .....	F 31,168	212	2,106	3,010	5,116	5,329	151,723	188,219
May .....	F 31,522	212	2,064	3,004	5,068	5,281	154,037	190,840
June .....	F 29,510	213	2,022	2,998	5,020	5,233	150,406	185,149
July .....	F 27,716	220	2,007	2,957	4,963	5,183	137,956	170,854
August .....	F 28,138	227	1,991	2,915	4,906	5,133	129,645	162,916
September .....	F 27,537	234	1,975	2,874	4,849	5,083	129,079	161,699
October .....	F 29,025	239	1,868	2,865	4,733	4,972	133,421	167,419
November .....	F 29,152	245	1,761	2,856	4,617	4,862	136,168	170,182
December .....	F 28,484	250	1,654	2,848	4,501	4,751	132,723	165,958
2021 January .....	F 27,799	F 188	F 1,969	F 3,646	F 5,615	F 5,803	125,399	159,000
February .....	F 28,313	F 176	F 1,652	F 3,377	F 5,029	F 5,206	109,717	143,236

<sup>a</sup> Through 1979, data are for the residential and commercial sectors. Beginning in 2008, data are for the commercial sector only.

<sup>b</sup> Through 1979, data are for manufacturing plants and the transportation sector. For 1980–2007, data are for manufacturing plants only. Beginning in 2008, data are for manufacturing plants and coal transformation/processing plants.

<sup>c</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>d</sup> Excludes waste coal. Through 1998, data are for electric utilities only. Beginning in 1999, data are for electric utilities and independent power producers. NA=Not available. F=Forecast.

Notes: • Stocks are at end of period. • Electric power sector monthly values

are from Table 7.5; producers and distributors monthly values are estimates derived from collected annual data; all other monthly values are estimates derived from collected quarterly values. • Data values preceded by "F" are derived from the U.S. Energy Information Administration's Short-Term Integrated Forecasting System. See Note 4, "Coal Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#coal> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Note 1. Coal Production.** Preliminary monthly estimates of national coal production are the sum of weekly estimates developed by the U.S. Energy Information Administration (EIA) and published in the *Weekly Coal Production* report. When a week extends into a new month, production is allocated on a daily basis and added to the appropriate month. Weekly estimates are based on Association of American Railroads (AAR) data showing the number of railcars loaded with coal during the week by Class I and certain other railroads.

Through 2001, the weekly coal production model converted AAR data into short tons of coal by using the average number of short tons of coal per railcar loaded reported in the “Quarterly Freight Commodity Statistics” from the Surface Transportation Board. If an average coal tonnage per railcar loaded was not available for a specific railroad, the national average was used. To derive the estimate of total weekly production, the total rail tonnage for the week was divided by the ratio of quarterly production shipped by rail and total quarterly production. Data for the corresponding quarter of previous years were used to derive this ratio. This method ensured that the seasonal variations were preserved in the production estimates.

From 2002 through 2014, the weekly coal production model used statistical auto regressive methods to estimate national coal production as a function of railcar loadings of coal, heating degree-days, and cooling degree-days. On Thursday of each week, EIA received from the AAR data for the previous week. The latest weekly national data for heating degree-days and cooling degree-days were obtained from the National Oceanic and Atmospheric Administration’s Climate Prediction Center.

Beginning in 2015, the revised weekly coal production model uses statistical auto regressive methods to estimate national coal production as a function of railcar loadings of coal. EIA receives AAR data on Thursday of each week for prior week car loadings. The weekly coal model is run and a national level coal production estimate is obtained. From there, state-level estimates are calculated using historical state production share. The state estimates are then aggregated to various regional-level estimates. The weekly coal model is refit every quarter after preliminary coal data are available.

When preliminary quarterly data become available, the monthly and weekly estimates are adjusted to conform to the quarterly figures. The adjustment procedure uses historical state-level production data, the methodology for which can be seen in the documentation located at <http://www.eia.gov/coal/production/weekly/>. Initial estimates of annual production published in January of the following year are based on preliminary production data covering the first nine months (three quarters) and weekly/monthly estimates for the fourth quarter. All quarterly, monthly, and weekly production figures are adjusted to conform to the final annual production data published in the *Monthly Energy Review* in the fall of the following year.

**Note 2. Coal Consumption.** Forecast data (designated by an “F”) are derived from forecasted values shown in EIA’s *Short-Term Energy Outlook* (DOE/EIA-0202) table titled “U.S. Coal Supply, Consumption, and Inventories.” The monthly estimates are based on the quarterly values, which are released in March, June, September, and December. The estimates are revised quarterly as collected data become available from the data sources. Sector-specific information follows.

**Residential and Commercial**—Through 2007, coal consumption by the residential and commercial sectors is reported to EIA for the two sectors combined; EIA estimates the amount consumed by the sectors individually. To create the estimates, it is first assumed that an occupied coal-heated housing unit consumes fuel at the same Btu rate as an oil-heated housing unit. Then, for the years in which data are available on the number of occupied housing units by heating source (1973–1981 and subsequent odd-numbered years), residential consumption of coal is estimated using the following steps: a ratio is created of the number of occupied housing units heated by coal to the number of occupied housing units heated by oil; that ratio is then multiplied by the Btu quantity of oil consumed by the residential sector to derive an estimate of the Btu quantity of coal consumed by the residential sector; and, finally, the amount estimated as the residential sector consumption is subtracted from the residential and commercial sectors’ combined consumption to derive the commercial sector’s estimated consumption. Beginning in 2008, residential coal consumption data are not collected by EIA, and commercial coal consumption data are taken directly from reported data.

**Industrial Coke Plants**—Through 1979, monthly coke plant consumption data were taken directly from reported data. For 1980–1987, coke plant consumption estimates were derived by proportioning reported quarterly data by using the ratios of monthly-to-quarterly consumption data in 1979, the last year in which monthly data were reported. Beginning in 1988, monthly coke plant consumption estimates are derived from the reported quarterly data by using monthly ratios of raw steel production data from the American Iron and Steel Institute. The ratios are the monthly raw steel production from open hearth and basic oxygen process furnaces as a proportion of the quarterly production from those kinds of furnaces. Coal coke consumption values also include the relatively small amount consumed for non-combustion use (See Tables 1.11a and 1.11b).

**Industrial Other**—Through 1977, monthly consumption data for the other industrial sector (all industrial users minus coke plants) were derived by using reported data to modify baseline consumption figures from the most recent U.S. Census Bureau Annual Survey of Manufactures or Census of Manufactures. For 1978 and 1979, monthly estimates were derived from data reported on Forms EIA-3 and EIA-6. For 1980–1987, monthly figures were estimated by proportioning quarterly data by using the ratios of monthly-to-quarterly consumption data in 1979, the last year in which monthly data were reported on Form EIA-3. Beginning in 1988, monthly consumption for the other industrial sector is estimated from reported quarterly data by using ratios derived from industrial production indices published by the Board of Governors of the Federal Reserve System. Indices for six major industry groups are used as the basis for calculating the ratios: food manufacturing, which is North American Industry Classification System (NAICS) code 311; paper manufacturing, NAICS 322; chemical manufacturing, NAICS 325; petroleum and coal products, NAICS 324; non-metallic mineral products manufacturing, NAICS 327; and primary metal manufacturing, NAICS 331. The monthly ratios are computed as the monthly sum of the weighted indices as a proportion of the quarterly sum of the weighted indices by using the 1977 proportion as the weights. Through 2007, quarterly consumption data for the other industrial sector were derived by adding beginning stocks at manufacturing plants to current receipts and subtracting ending stocks at manufacturing plants. In this calculation, current receipts are the greater of either reported receipts from manufacturing plants (Form EIA-3) or reported shipments to the other industrial sector (Form EIA-6), thereby ensuring that agriculture, forestry, fishing, and construction consumption data were included where appropriate. Beginning in 2008, quarterly consumption totals for other industrial coal include data for manufacturing and mining only. Over time, surveyed coal consumption data for agriculture, forestry, fishing, and construction dwindled to about 20–30 thousand short tons annually. Therefore, in 2008, EIA consolidated its programs by eliminating agriculture, forestry, fishing, and construction as surveyed sectors.

**Electric Power Sector**—Monthly consumption data for electric power plants are taken directly from reported data.

**Note 3. Coal Stocks.** Coal stocks data are reported by major end-use sector. Forecast data (designated by an “F”) are derived from forecasted values shown in EIA’s *Short-Term Energy Outlook* (DOE/EIA-0202) table titled “U.S. Coal Supply, Consumption, and Inventories.” The monthly estimates are based on the quarterly values (released in March, June, September, and December) or annual values. The estimates are revised as collected data become available from the data sources. Sector-specific information follows.

**Producers and Distributors**—Through 1997, quarterly stocks at producers and distributors were taken directly from reported data. Monthly data were estimated by using one-third of the current quarterly change to indicate the monthly change in stocks. Beginning in 1998, end-of-year stocks are taken from reported data. Monthly stocks are estimated by a model.

**Residential and Commercial**—Through 1979, stock estimates for the residential and commercial sector were taken directly from reported data. For 1980–2007, stock estimates were not collected. Beginning in 2008, quarterly commercial (excluding residential) stocks data are collected on Form EIA-3 (data for “Commercial and Institutional Coal Users”).

**Industrial Coke Plants**—Through 1979, monthly stocks at coke plants were taken directly from reported data. Beginning

in 1980, coke plant stocks are estimated by using one-third of the current quarterly change to indicate the monthly change in stocks. Quarterly stocks are taken directly from data reported on Form EIA-5.

**Industrial Other**—Through 1977, stocks for the other industrial sector were derived by using reported data to modify baseline figures from a one-time Bureau of Mines survey of consumers. For 1978–1982, monthly estimates were derived by judgmentally proportioning reported quarterly data based on representative seasonal patterns of supply and demand. Beginning in 1983, other industrial coal stocks are estimated as indicated above for coke plants. Quarterly stocks are taken directly from data reported on Form EIA-3 and therefore include only manufacturing industries; data for agriculture, forestry, fishing, mining, and construction stocks are not available.

**Electric Power Sector**—Monthly stocks data at electric power plants are taken directly from reported data.

**Note 4. Coal Forecast Values.** Data values preceded by “F” in this section are forecast values. They are derived from EIA’s Short-Term Integrated Forecasting System (STIFS). The model is driven primarily by data and assumptions about key macroeconomic variables, the world oil price, and weather. The coal forecast relies on other variables as well, such as alternative fuel prices (natural gas and oil) and power generation by sources other than fossil fuels, including nuclear and hydroelectric power. Each month, EIA staff review the model output and make adjustments, if appropriate, based on their knowledge of developments in the coal industry.

The STIFS model results are published monthly in EIA’s *Short-Term Energy Outlook*, which is accessible on the Web at <http://www.eia.gov/forecasts/steo/>.

## Table 6.1 Sources

### *Production*

1949–September 1977: U.S. Department of the Interior, Bureau of Mines, *Minerals Yearbook and Minerals Industry Surveys*.

October 1977 forward: U.S. Energy Information Administration (EIA), *Weekly Coal Production*.

### *Waste Coal Supplied*

1989–1997: EIA, Form EIA-867, “Annual Nonutility Power Producer Report.”

1998–2000: EIA, Form EIA-860B, “Annual Electric Generator Report—Nonutility.”

2001–2003: EIA, Form EIA-906, “Power Plant Report,” and Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms.

2004–2007: EIA, Form EIA-906, “Power Plant Report,” Form EIA-920, “Combined Heat and Power Plant Report,” and Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms.

2008 forward: EIA, Form EIA-923, “Power Plant Operations Report,” and Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called, “Quarterly Survey of Non-Electric Sector Coal Data”); and, for forecast values, EIA, Short-Term Integrated Forecasting System.

### *Imports and Exports*

1949 forward: U.S. Department of Commerce, U.S. Census Bureau, Monthly Reports IM 145 (Imports) and EM 545 (Exports).

### *Stock Change*

1950 forward: Calculated from data in Table 6.3.

### *Losses and Unaccounted for*

1949 forward: Calculated as the sum of production, imports, and waste coal supplied, minus exports, stock change, and consumption.

## Table 6.2 Sources

### *Residential and Commercial Total*

Through 2007, coal consumption by the residential and commercial sectors combined is reported to the U.S. Energy Information Administration (EIA). EIA estimates the sectors individually using the method described in Note 2, “Consumption,” at the end of Section 6. Data for the residential and commercial sectors combined are from:

1949–1976: U.S. Department of the Interior (DOI), Bureau of Mines (BOM), *Minerals Yearbook*.

January–September 1977: DOI, BOM, Form 6-1400, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.” October 1977–1979: EIA, Form EIA-2, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

1980–1997: EIA, Form EIA-6, “Coal Distribution Report,” quarterly.

1998–2007: DOI, Mine Safety and Health Administration, Form 7000-2, “Quarterly Coal Consumption and Quality Report—Coke Plants.”

### *Commercial Total*

Beginning in 2008, coal consumption by the commercial (excluding residential) sector is reported to EIA. Data for total commercial consumption are from: 2008 forward: EIA, Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called, “Quarterly Survey of Non-Electric Sector Coal Data”); and, for forecast values, EIA, Short-Term Integrated Forecasting System (STIFS).

### *Commercial CHP*

1989 forward: Table 7.4c.

### *Commercial Other*

1949 forward: Calculated as “Commercial Total” minus “Commercial CHP.”

### *Industrial Coke Plants*

1949–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–1980: EIA, Form EIA-5/5A, “Coke and Coal Chemicals—Monthly/Annual Supplement.”

1981–1984: EIA, Form EIA-5/5A, “Coke Plant Report—Quarterly/Annual Supplement.”

1985 forward: EIA, Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants”; and, for forecast values, EIA, STIFS.

### *Other Industrial Total*

1949–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–1979: EIA, Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms.

1980–1997: EIA, Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms and Form EIA-6, “Coal Distribution Report,” quarterly.

1998–2007: EIA, Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms, Form EIA-6A, “Coal Distribution Report,” annual, and Form EIA-7A, “Coal Production Report,” annual.

2008 forward: EIA, Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called, “Quarterly Survey of Non-Electric Sector Coal Data”) and Form EIA-7A, “Coal Production Report,” annual; and, for forecast values, EIA, STIFS.

### *Other Industrial CHP*

1989 forward: Table 7.4c.

### *Other Industrial Non-CHP*

1949 forward: Calculated as “Other Industrial Total” minus “Other Industrial CHP.”

### *Transportation*

1949–1976: DOI, BOM, *Minerals Yearbook*.

January–September 1977: DOI, BOM, Form 6-1400, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

October–December 1977: EIA, Form EIA-6, “Coal Distribution Report,” quarterly.

### *Electric Power*

1949 forward: Table 7.4b.

## **Table 6.3 Sources**

### *Producers and Distributors*

1973–1979: U.S. Department of the Interior (DOI), Bureau of Mines (BOM), Form 6-1419Q, “Distribution of Bituminous Coal and Lignite Shipments.”

1980–1997: U.S. Energy Information Administration (EIA), Form EIA-6, “Coal Distribution Report,” quarterly.

1998–2007: EIA, Form EIA-6A, “Coal Distribution Report,” annual.

2008 forward: EIA, Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called, “Quarterly Survey of Non-Electric Sector Coal Data”); (data for “Commercial and Institutional Coal Users”); and, for forecast values, EIA, STIFS.

### *Residential and Commercial*

1949–1976: DOI, BOM, *Minerals Yearbook*.

January–September 1977: DOI, BOM, Form 6-1400, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

October 1977–1979: EIA, Form EIA-2, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

2008 forward: EIA, Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Coal Data”); and, for forecast values, EIA, STIFS.

### *Industrial Coke Plants*

1949–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–1980: EIA, Form EIA-5/5A, “Coke and Coal Chemicals—Monthly/Annual.”

1981–1984: EIA, Form EIA-5/5A, “Coke Plant Report—Quarterly/Annual Supplement.”

1985 forward: EIA, Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants” and, for forecast values, EIA, STIFS.

### *Industrial Other*

1949–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–2007: EIA, Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms.

2008 forward: EIA, Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called, “Quarterly Survey of Non-Electric Sector Coal Data”); and, for forecast values, EIA, STIFS.

### *Electric Power*

1949 forward: Table 7.5.


## 7. Electricity

---


**Figure 7.1 Electricity Overview**

(Billion Kilowatthours)


Overview, 2020




Net Generation [a] by Sector, 1989–2020



Net Generation [a] by Sector, Monthly



Trade, 1949–2020



[a] Data are for utility-scale facilities.

[b] Electricity retail sales to ultimate customers reported by electric utilities and other energy service providers.

[c] See “Direct Use” in Glossary.

[d] Includes commercial sector.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.  
Source: Table 7.1.



**Table 7.1 Electricity Overview**  
(Billion Kilowatthours)

	Net Generation <sup>a</sup>				Trade			T&D Losses <sup>f</sup> and Unaccounted for <sup>g</sup>	End Use		
	Electric Power Sector <sup>b</sup>	Com- mercial Sector <sup>c</sup>	Indus- trial Sector <sup>d</sup>	Total	Imports <sup>e</sup>	Exports <sup>e</sup>	Net Imports <sup>e</sup>		Retail Sales <sup>h</sup>	Direct Use <sup>i</sup>	Total
1950 Total .....	329	NA	5	334	2	(s)	2	44	291	NA	291
1955 Total .....	547	NA	3	550	5	(s)	4	58	497	NA	497
1960 Total .....	756	NA	4	759	5	1	5	76	688	NA	688
1965 Total .....	1,055	NA	3	1,058	4	4	(s)	104	954	NA	954
1970 Total .....	1,532	NA	3	1,535	6	4	2	145	1,392	NA	1,392
1975 Total .....	1,918	NA	3	1,921	11	5	6	180	1,747	NA	1,747
1980 Total .....	2,286	NA	3	2,290	25	4	21	216	2,094	NA	2,094
1985 Total .....	2,470	NA	3	2,473	46	5	41	190	2,324	NA	2,324
1990 Total .....	2,901	6	<sup>d</sup> 131	3,038	18	16	2	203	2,713	125	2,837
1995 Total .....	3,194	8	151	3,353	43	4	39	229	3,013	151	3,164
2000 Total .....	3,638	8	157	3,802	49	15	34	244	3,421	171	3,592
2005 Total .....	3,902	8	145	4,055	44	19	25	269	3,661	150	3,811
2006 Total .....	3,908	8	148	4,065	43	24	18	266	3,670	147	3,817
2007 Total .....	4,005	8	143	4,157	51	20	31	298	3,765	126	3,890
2008 Total .....	3,974	8	137	4,119	57	24	33	286	3,734	132	3,866
2009 Total .....	3,810	8	132	3,950	52	18	34	261	3,597	127	3,724
2010 Total .....	3,972	9	144	4,125	45	19	26	264	3,755	132	3,887
2011 Total .....	3,948	10	142	4,100	52	15	37	255	3,750	133	3,883
2012 Total .....	3,890	11	146	4,048	59	12	47	263	3,695	138	3,832
2013 Total .....	3,904	12	150	4,066	69	11	58	256	3,725	143	3,868
2014 Total .....	3,937	13	144	4,094	67	13	53	244	3,765	139	3,903
2015 Total .....	3,919	13	146	4,078	76	9	67	244	3,759	141	3,900
2016 Total .....	3,918	13	146	4,077	73	6	67	241	3,762	140	3,902
2017 Total .....	3,877	13	144	4,034	66	9	56	226	3,723	141	3,864
2018 Total .....	4,018	13	147	4,178	58	14	44	219	3,859	144	4,003
2019 January .....	345	1	13	360	5	1	3	22	329	<sup>E</sup> 13	341
February .....	303	1	11	315	5	1	3	11	296	<sup>E</sup> 11	307
March .....	313	1	12	327	5	3	2	15	302	<sup>E</sup> 12	314
April .....	284	1	11	297	4	2	2	14	274	<sup>E</sup> 11	285
May .....	317	1	12	330	5	2	3	25	297	<sup>E</sup> 11	308
June .....	340	1	12	353	5	2	4	23	321	<sup>E</sup> 12	333
July .....	396	1	13	410	6	2	4	25	376	<sup>E</sup> 13	389
August .....	387	1	13	401	6	2	4	20	373	<sup>E</sup> 13	385
September .....	347	1	12	361	5	2	4	12	340	<sup>E</sup> 12	353
October .....	307	1	12	320	4	1	2	2	308	<sup>E</sup> 12	320
November .....	302	1	13	316	5	1	4	22	286	<sup>E</sup> 12	298
December .....	324	1	13	338	5	1	4	20	310	<sup>E</sup> 13	322
Total .....	3,966	14	149	4,128	59	20	39	212	3,811	143	3,955
2020 January .....	326	1	13	341	5	1	3	20	311	<sup>E</sup> 13	324
February .....	305	1	12	318	4	2	3	19	290	<sup>E</sup> 12	302
March .....	294	1	12	307	5	1	4	14	285	<sup>E</sup> 12	297
April .....	264	1	11	276	5	1	3	11	258	<sup>E</sup> 11	269
May .....	292	1	11	304	5	2	4	27	270	<sup>E</sup> 11	281
June .....	340	1	12	353	5	1	4	30	316	<sup>E</sup> 11	327
July .....	401	1	12	414	7	1	5	33	375	<sup>E</sup> 12	387
August .....	386	1	12	400	7	1	6	29	364	<sup>E</sup> 12	376
September .....	322	1	11	334	5	1	4	9	318	<sup>E</sup> 11	329
October .....	302	1	11	314	5	1	4	15	292	<sup>E</sup> 11	303
November .....	290	1	12	303	4	1	3	22	273	<sup>E</sup> 11	284
December .....	331	1	13	345	5	1	4	26	311	<sup>E</sup> 12	323
Total .....	3,853	13	143	4,009	61	14	47	254	3,664	<sup>E</sup> 138	3,802
2021 January .....	337	1	13	351	<sup>F</sup> 6	<sup>F</sup> 1	<sup>F</sup> 5	22	321	<sup>E</sup> 12	333
February .....	316	1	10	327	<sup>F</sup> 3	<sup>F</sup> 2	<sup>F</sup> 1	19	299	<sup>E</sup> 10	309
2-Month Total .....	653	2	23	678	<sup>F</sup> 9	<sup>F</sup> 3	<sup>F</sup> 6	41	620	<sup>E</sup> 22	642
2020 2-Month Total .....	631	2	25	659	9	3	6	39	601	<sup>E</sup> 25	626
2019 2-Month Total .....	648	2	24	675	9	3	6	33	624	<sup>E</sup> 24	648

<sup>a</sup> Electricity net generation at utility-scale facilities. Does not include distributed (small-scale) solar photovoltaic (PV) generation shown on Table 10.6. See Note 1, "Coverage of Electricity Statistics," at end of section.

<sup>b</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>c</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>d</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants. Through 1988, data are for industrial hydroelectric power only.

<sup>e</sup> Electricity transmitted across U.S. borders. Net imports equal imports minus exports.

<sup>f</sup> Transmission and distribution losses (electricity losses that occur between the point of generation and delivery to the customer). See Note 1, "Electrical System Energy Losses," at end of Section 2.

<sup>g</sup> Data collection frame differences and nonsampling error.

<sup>h</sup> Electricity retail sales to ultimate customers by electric utilities and, beginning

in 1996, other energy service providers.

<sup>i</sup> Use of electricity that is 1) self-generated, 2) produced by either the same entity that consumes the power or an affiliate, and 3) used in direct support of a service or industrial process located within the same facility or group of facilities that house the generating equipment. Direct use is exclusive of station use.

<sup>E</sup>=Estimate. NA=Not available. F=Forecast. (s)=Less than 0.5 billion kilowatthours.

Notes: • See Note 1, "Coverage of Electricity Statistics," and Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of section.

• Data values preceded by "F" are derived from the U.S. Energy Information Administration's Short-Term Integrated Forecasting System. See Note 3, "Electricity Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.


**Figure 7.2 Electricity Net Generation**

(Billion Kilowatthours)


Total (All Sectors), Major Sources, 1949–2020




Total (All Sectors), Major Sources, Monthly




Electric Power Sector, Major Sources, 2020



Commercial Sector, Major Sources, 2020



Industrial Sector, Major Sources, 2020



[a] Conventional hydroelectric power, wood, waste, geothermal, solar, and wind.

[b] Blast furnace gas, and other manufactured and waste derived from fossil fuels.

[c] Conventional hydroelectric power.

Note: Data are for utility-scale facilities.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.

Sources: Tables 7.2a-7.2c.

**Table 7.2a Electricity Net Generation: Total (All Sectors)**

(Sum of Tables 7.2b and 7.2c; Million Kilowatthours)

	Fossil Fuels				Nuclear Electric Power	Hydro- electric Pumped Storage <sup>e</sup>	Renewable Energy						Total <sup>i</sup>
	Coal <sup>a</sup>	Petro- leum <sup>b</sup>	Natural Gas <sup>c</sup>	Other Gases <sup>d</sup>			Conven- tional Hydro- electric Power <sup>f</sup>	Biomass		Geo- thermal	Solar <sup>i</sup>	Wind	
								Wood <sup>g</sup>	Waste <sup>h</sup>				
1950 Total .....	154,520	33,734	44,559	NA	0	{ f }	100,885	390	NA	NA	NA	NA	334,088
1955 Total .....	301,363	37,138	95,285	NA	0	{ f }	116,236	276	NA	NA	NA	NA	550,299
1960 Total .....	403,067	47,987	157,970	NA	518	{ f }	149,440	140	NA	33	NA	NA	759,156
1965 Total .....	570,926	64,801	221,559	NA	3,657	{ f }	196,984	269	NA	189	NA	NA	1,058,386
1970 Total .....	704,394	184,183	372,890	NA	21,804	{ f }	250,957	136	220	525	NA	NA	1,535,111
1975 Total .....	852,786	289,095	299,778	NA	172,505	{ f }	303,153	18	174	3,246	NA	NA	1,920,755
1980 Total .....	1,161,562	245,994	346,240	NA	251,116	{ f }	279,182	275	158	5,073	NA	NA	2,289,600
1985 Total .....	1,402,128	100,202	291,946	NA	383,691	{ f }	284,311	743	640	9,325	11	6	2,473,002
1990 Total <sup>k</sup> .....	1,594,011	126,460	372,765	10,383	576,862	-3,508	292,866	32,522	13,260	15,434	367	2,789	3,037,827
1995 Total .....	1,709,426	74,554	496,058	13,870	673,402	-2,725	310,833	36,521	20,405	13,378	497	3,164	3,353,487
2000 Total .....	1,966,265	111,221	601,038	13,955	753,893	-5,539	275,573	37,595	23,131	14,093	493	5,593	3,802,105
2005 Total .....	2,012,873	122,225	760,960	13,464	781,986	-6,558	270,321	38,856	15,420	14,692	550	17,811	4,055,423
2006 Total .....	1,990,511	64,166	816,441	14,177	787,219	-6,558	289,246	38,762	16,099	14,568	508	26,589	4,064,702
2007 Total .....	2,016,456	65,739	896,590	13,453	806,425	-6,896	247,510	39,014	16,525	14,637	612	34,450	4,156,745
2008 Total .....	1,985,801	46,243	882,981	11,707	806,208	-6,288	254,831	37,300	17,734	14,840	864	55,363	4,119,388
2009 Total .....	1,755,904	38,937	920,979	10,632	798,855	-4,627	273,445	36,050	18,443	15,009	891	73,886	3,950,331
2010 Total .....	1,847,290	37,061	987,697	11,313	806,968	-5,501	260,203	37,172	18,917	15,219	1,212	94,652	4,125,060
2011 Total .....	1,733,430	30,182	1,013,689	11,566	790,204	-6,421	319,355	37,449	19,222	15,316	1,818	120,177	4,100,141
2012 Total .....	1,514,043	23,190	1,225,894	11,898	769,331	-4,950	276,240	37,799	19,823	15,562	4,327	140,822	4,047,765
2013 Total .....	1,581,115	27,164	1,124,836	12,853	789,016	-4,681	268,565	40,028	20,830	15,775	9,036	167,840	4,065,964
2014 Total .....	1,581,710	30,232	1,126,609	12,022	797,166	-6,174	259,367	42,340	21,650	15,877	17,691	181,655	4,093,606
2015 Total .....	1,352,398	28,249	1,333,482	13,117	797,178	-5,091	249,080	41,929	21,703	15,918	24,893	190,719	4,077,601
2016 Total .....	1,239,149	24,205	1,378,307	12,807	805,694	-6,686	267,812	40,947	21,813	15,826	36,054	226,993	4,076,675
2017 Total .....	1,205,835	21,390	1,296,442	12,469	804,950	-6,495	300,333	41,124	21,610	15,927	53,287	254,303	4,034,271
2018 Total .....	1,149,487	25,226	1,469,133	13,463	807,084	-5,905	292,524	40,936	20,896	15,967	63,825	272,667	4,178,277
2019 January .....	100,905	2,213	121,589	1,025	73,701	-323	24,798	3,465	1,672	1,390	3,580	24,301	359,509
February .....	79,929	1,507	112,142	948	64,715	-389	22,881	3,042	1,498	1,293	3,836	22,623	315,026
March .....	78,352	1,390	115,813	1,086	65,080	-409	26,334	3,217	1,625	1,422	5,899	25,773	326,657
April .....	59,922	1,183	104,059	948	60,581	-103	27,820	2,807	1,510	1,254	6,752	28,915	296,663
May .....	71,885	1,674	117,059	1,054	67,124	-368	31,982	3,051	1,564	1,342	7,162	25,779	330,423
June .....	78,540	1,519	137,836	1,009	68,805	-385	28,078	3,159	1,581	1,328	7,971	22,446	352,988
July .....	100,771	1,795	171,955	1,185	72,199	-622	24,875	3,498	1,617	1,375	8,133	22,101	410,038
August .....	94,040	1,731	174,968	1,147	71,911	-579	22,579	3,539	1,636	1,393	7,877	19,978	401,430
September .....	85,707	1,504	149,697	1,112	66,064	-671	18,526	3,211	1,530	1,368	6,817	24,513	360,518
October .....	66,777	1,142	130,948	924	62,033	-373	18,306	3,063	1,573	1,141	6,093	27,625	320,352
November .....	75,549	1,232	117,910	1,047	64,125	-509	20,218	3,137	1,525	984	4,364	25,184	315,849
December .....	72,581	1,451	131,839	1,107	73,074	-529	21,478	3,355	1,633	1,183	3,453	26,644	338,402
Total .....	964,957	18,341	1,585,814	12,591	809,409	-5,261	287,874	38,543	18,964	15,473	71,937	295,882	4,127,855
2020 January .....	65,100	1,612	133,158	1,105	74,170	-377	25,332	3,345	1,671	1,265	4,657	28,547	340,669
February .....	56,114	1,257	125,594	1,131	65,950	-247	26,370	3,145	1,515	1,274	5,706	29,397	318,168
March .....	50,644	1,390	123,697	1,014	63,997	-353	23,594	3,192	1,682	1,517	6,496	29,525	307,479
April .....	40,624	1,219	107,960	747	59,170	-325	22,112	2,968	1,594	1,450	8,126	29,416	276,127
May .....	46,530	1,286	115,871	810	64,338	-367	30,485	3,094	1,617	1,450	9,767	28,309	304,277
June .....	65,335	1,667	143,245	757	67,205	-499	29,059	2,988	1,456	1,371	9,641	29,524	352,766
July .....	89,831	1,794	185,445	856	69,385	-686	27,676	3,106	1,564	1,435	10,478	22,270	414,243
August .....	91,252	1,701	173,927	1,006	68,982	-784	24,082	3,303	1,589	1,430	9,508	22,413	399,504
September .....	68,448	1,249	141,453	948	65,727	-525	19,162	2,941	1,512	1,392	7,891	23,064	334,270
October .....	59,895	1,224	131,658	895	59,362	-423	18,321	2,802	1,516	1,380	7,346	28,880	313,910
November .....	61,332	1,444	109,037	940	61,760	-369	21,832	3,105	1,476	1,489	5,895	33,704	302,702
December .....	78,700	1,652	125,704	972	69,871	-368	23,086	3,260	1,612	1,478	5,381	32,462	344,970
Total .....	773,805	17,495	1,616,748	11,182	789,919	-5,321	291,111	37,249	18,805	16,930	90,891	337,510	4,009,085
2021 January .....	81,806	1,589	125,323	985	71,832	-424	26,159	3,253	1,620	1,404	5,732	30,427	350,815
February .....	87,848	2,284	111,672	767	62,954	-425	22,137	2,936	1,419	1,327	6,502	26,673	327,019
2-Month Total .....	169,654	3,874	236,995	1,752	134,787	-849	48,297	6,188	3,039	2,731	12,234	57,100	677,834
2020 2-Month Total .....	121,214	2,869	258,752	2,236	140,120	-623	51,702	6,490	3,186	2,539	10,363	57,944	658,836
2019 2-Month Total .....	180,834	3,720	233,731	1,972	138,416	-712	47,678	6,508	3,170	2,683	7,416	46,924	674,536

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, waste oil, and, beginning in 2011, propane.

<sup>c</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>d</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>e</sup> Pumped storage facility production minus energy used for pumping.

<sup>f</sup> Through 1989, hydroelectric pumped storage is included in "Conventional Hydroelectric Power."

<sup>g</sup> Wood and wood-derived fuels.

<sup>h</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>i</sup> Electricity net generation from solar thermal and photovoltaic (PV) energy at utility-scale facilities. Does not include distributed (small-scale) solar photovoltaic

generation. See Table 10.6.

<sup>j</sup> Includes batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, all data except hydroelectric are for electric utilities only; hydroelectric data through 1988 include industrial plants as well as electric utilities. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

NA=Not available.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section, "Table 7.2b Sources" and "Table 7.2c Sources."

**Table 7.2b Electricity Net Generation: Electric Power Sector**  
(Subset of Table 7.2a; Million Kilowatthours)

	Fossil Fuels				Nuclear Electric Power	Hydro-electric Pumped Storage <sup>e</sup>	Renewable Energy						Total <sup>j</sup>
	Coal <sup>a</sup>	Petroleum <sup>b</sup>	Natural Gas <sup>c</sup>	Other Gases <sup>d</sup>			Conventional Hydro-electric Power <sup>f</sup>	Biomass		Geo-thermal	Solar <sup>i</sup>	Wind	
								Wood <sup>g</sup>	Waste <sup>h</sup>				
1950 Total .....	154,520	33,734	44,559	NA	0	{ }	95,938	390	NA	NA	NA	NA	329,141
1955 Total .....	301,363	37,138	95,285	NA	0	{ }	112,975	276	NA	NA	NA	NA	547,038
1960 Total .....	403,067	47,987	157,970	NA	518	{ }	145,833	140	NA	33	NA	NA	755,549
1965 Total .....	570,926	64,801	221,559	NA	3,657	{ }	193,851	269	NA	189	NA	NA	1,055,252
1970 Total .....	704,394	184,183	372,890	NA	21,804	{ }	247,714	136	220	525	NA	NA	1,531,868
1975 Total .....	852,786	289,095	299,778	NA	172,505	{ }	300,047	18	174	3,246	NA	NA	1,917,649
1980 Total .....	1,161,562	245,994	346,240	NA	251,116	{ }	276,021	275	158	5,073	NA	NA	2,286,439
1985 Total .....	1,402,128	100,202	291,946	NA	383,691	{ }	281,149	743	640	9,325	11	6	2,469,841
1990 Total <sup>k</sup> .....	1,572,109	118,864	309,486	621	576,862	-3,508	289,753	7,032	11,500	15,434	367	2,789	2,901,322
1995 Total .....	1,686,056	68,146	419,179	1,927	673,402	-2,725	305,410	7,597	17,986	13,378	497	3,164	3,194,230
2000 Total .....	1,943,111	105,192	517,978	2,028	753,893	-5,539	271,338	8,916	20,307	14,093	493	5,593	3,637,529
2005 Total .....	1,992,054	116,482	683,829	3,777	781,986	-6,558	267,040	10,570	13,031	14,692	550	17,811	3,902,192
2006 Total .....	1,969,737	59,708	734,417	4,254	787,219	-6,558	286,254	10,341	13,927	14,568	508	26,589	3,908,077
2007 Total .....	1,998,390	61,306	814,752	4,042	806,425	-6,896	245,843	10,711	14,294	14,637	612	34,450	4,005,343
2008 Total .....	1,968,838	42,881	802,372	3,200	806,208	-6,288	253,096	10,638	15,379	14,840	864	55,363	3,974,349
2009 Total .....	1,741,123	35,811	841,006	3,058	798,855	-4,627	271,506	10,738	15,954	15,009	891	73,886	3,809,837
2010 Total .....	1,827,738	34,679	901,389	2,967	806,968	-5,501	258,455	11,446	16,376	15,219	1,206	94,636	3,972,386
2011 Total .....	1,717,891	28,202	926,290	2,939	790,204	-6,421	317,531	10,733	15,989	15,316	1,727	120,121	3,948,186
2012 Total .....	1,500,557	20,072	1,132,791	2,984	769,331	-4,950	273,859	11,050	16,555	15,562	4,164	140,749	3,890,358
2013 Total .....	1,567,722	24,510	1,028,949	4,322	789,016	-4,681	265,058	12,302	16,918	15,775	8,724	167,742	3,903,715
2014 Total .....	1,568,774	28,043	1,033,172	3,358	797,166	-6,174	258,046	15,027	17,602	15,877	17,304	181,496	3,937,003
2015 Total .....	1,340,993	26,505	1,237,656	3,715	797,178	-5,091	247,636	14,563	17,823	15,918	24,456	190,547	3,919,294
2016 Total .....	1,229,663	22,710	1,279,380	3,912	805,694	-6,686	266,326	13,420	18,183	15,826	35,497	226,790	3,918,078
2017 Total .....	1,197,838	20,039	1,196,753	4,126	804,950	-6,495	298,711	13,641	18,084	15,927	52,724	254,074	3,877,453
2018 Total .....	1,142,173	23,928	1,365,822	4,086	807,084	-5,905	291,148	13,385	17,623	15,934	63,253	272,396	4,018,167
2019 January .....	100,294	2,104	112,144	360	73,701	-323	24,658	1,141	1,412	1,348	3,546	24,273	345,324
February .....	79,382	1,420	103,949	351	64,715	-389	22,772	947	1,266	1,252	3,798	22,598	302,635
March .....	77,819	1,307	107,124	383	65,080	-409	26,208	939	1,364	1,378	5,841	25,746	313,385
April .....	59,426	1,089	95,861	329	60,581	-103	27,695	769	1,276	1,227	6,690	28,888	284,309
May .....	71,388	1,597	108,445	324	67,124	-368	31,857	965	1,347	1,304	7,095	25,757	317,498
June .....	78,043	1,435	128,930	329	68,805	-385	27,965	975	1,346	1,294	7,898	22,426	339,709
July .....	100,225	1,652	162,249	372	72,199	-622	24,788	1,151	1,383	1,342	8,053	22,084	395,547
August .....	93,517	1,636	165,140	377	71,911	-579	22,504	1,172	1,393	1,362	7,803	19,964	386,904
September .....	85,216	1,417	140,483	342	66,064	-671	18,461	1,045	1,303	1,338	6,754	24,494	346,894
October .....	66,311	1,056	121,934	189	62,033	-373	18,232	899	1,334	1,103	6,040	27,599	306,999
November .....	75,046	1,146	108,683	326	64,125	-509	20,139	957	1,288	941	4,323	25,160	302,253
December .....	72,065	1,361	122,198	354	73,074	-529	21,374	1,060	1,380	1,140	3,423	26,616	324,174
Total .....	958,732	17,220	1,477,139	4,037	809,409	-5,261	286,652	12,020	16,091	15,031	71,265	295,604	3,965,629
2020 January .....	64,548	1,514	123,298	354	74,170	-377	25,222	1,053	1,422	1,229	4,615	28,520	326,217
February .....	55,590	1,177	116,654	370	65,950	-247	26,260	1,004	1,284	1,233	5,657	29,368	304,885
March .....	50,145	1,306	114,766	288	63,997	-353	23,483	949	1,437	1,473	6,436	29,496	294,084
April .....	40,189	1,157	100,048	150	59,170	-325	22,002	823	1,364	1,410	8,052	29,386	264,054
May .....	46,094	1,210	107,853	161	64,338	-367	30,367	944	1,382	1,411	9,679	28,282	291,979
June .....	64,920	1,576	134,669	133	67,205	-499	28,950	907	1,247	1,338	9,555	29,446	340,019
July .....	89,368	1,691	176,293	162	69,385	-686	27,571	992	1,339	1,404	10,386	22,186	400,737
August .....	90,814	1,609	164,758	303	68,982	-784	23,985	1,159	1,365	1,400	9,428	22,341	386,013
September .....	67,978	1,170	133,123	297	65,727	-525	19,076	847	1,307	1,359	7,824	22,977	321,755
October .....	59,440	1,139	123,640	238	59,362	-423	18,237	808	1,292	1,341	7,284	28,770	301,722
November .....	60,896	1,350	100,783	306	61,760	-369	21,736	922	1,253	1,448	5,845	33,582	290,110
December .....	78,215	1,557	116,315	337	69,871	-368	22,981	1,015	1,370	1,434	5,338	32,329	331,059
Total .....	768,196	16,456	1,512,199	3,097	789,919	-5,321	289,870	11,423	16,062	16,481	90,097	336,681	3,852,634
2021 January .....	81,340	1,505	116,050	326	71,832	-424	26,047	1,031	1,371	1,360	5,689	30,319	337,092
February .....	87,393	2,172	104,470	191	62,954	-425	22,043	1,021	1,216	1,288	6,452	26,561	315,905
2-Month Total .....	168,733	3,677	220,520	517	134,787	-849	48,090	2,052	2,587	2,648	12,142	56,880	652,998
2020 2-Month Total .....	120,138	2,691	239,952	723	140,120	-623	51,481	2,057	2,706	2,462	10,272	57,888	631,102
2019 2-Month Total .....	179,676	3,524	216,093	711	138,416	-712	47,430	2,088	2,677	2,600	7,344	46,871	647,958

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, waste oil, and, beginning in 2011, propane.

<sup>c</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>d</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>e</sup> Pumped storage facility production minus energy used for pumping.

<sup>f</sup> Through 1989, hydroelectric pumped storage is included in "Conventional Hydroelectric Power."

<sup>g</sup> Wood and wood-derived fuels.

<sup>h</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>i</sup> Electricity net generation from solar thermal and photovoltaic (PV) energy at utility-scale facilities. Does not include distributed (small-scale) solar photovoltaic

generation. See Table 10.6.

<sup>j</sup> Includes batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

NA=Not available.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 7.2c Electricity Net Generation: Commercial and Industrial Sectors**  
(Subset of Table 7.2a; Million Kilowatthours)

	Commercial Sector <sup>a</sup>					Industrial Sector <sup>b</sup>							
	Coal <sup>c</sup>	Petro- leum <sup>d</sup>	Natural Gas <sup>e</sup>	Biomass	Total <sup>g</sup>	Coal <sup>c</sup>	Petro- leum <sup>d</sup>	Natural Gas <sup>e</sup>	Other Gases <sup>h</sup>	Hydro- electric Power <sup>i</sup>	Biomass		Total <sup>k</sup>
				Waste <sup>f</sup>							Wood <sup>j</sup>	Waste <sup>f</sup>	
1950 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	4,946	NA	NA	4,946
1955 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,261	NA	NA	3,261
1960 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,607	NA	NA	3,607
1965 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,134	NA	NA	3,134
1970 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,244	NA	NA	3,244
1975 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,106	NA	NA	3,106
1980 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,161	NA	NA	3,161
1985 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,161	NA	NA	3,161
1990 Total .....	796	589	3,272	812	5,837	21,107	7,008	60,007	9,641	2,975	25,379	949	130,830
1995 Total .....	998	379	5,162	1,519	8,232	22,372	6,030	71,717	11,943	5,304	28,868	900	151,025
2000 Total .....	1,097	432	4,262	1,985	7,903	22,056	5,597	78,798	11,927	4,135	28,652	839	156,673
2005 Total .....	1,353	375	4,249	1,657	8,492	19,466	5,368	72,882	9,687	3,195	28,271	733	144,739
2006 Total .....	1,310	235	4,355	1,599	8,371	19,464	4,223	77,669	9,923	2,899	28,400	572	148,254
2007 Total .....	1,371	189	4,257	1,599	8,273	16,694	4,243	77,580	9,411	1,590	28,287	631	143,128
2008 Total .....	1,261	142	4,188	1,534	7,926	15,703	3,219	76,421	8,507	1,676	26,641	821	137,113
2009 Total .....	1,096	163	4,225	1,748	8,165	13,686	2,963	75,748	7,574	1,868	25,292	740	132,329
2010 Total .....	1,111	124	4,725	1,672	8,592	18,441	2,258	81,583	8,343	1,668	25,706	869	144,082
2011 Total .....	1,049	89	5,487	2,315	10,080	14,490	1,891	81,911	8,624	1,799	26,691	917	141,875
2012 Total .....	883	196	6,603	2,319	11,301	12,603	2,922	86,500	8,913	2,353	26,725	948	146,107
2013 Total .....	839	124	7,154	2,567	12,234	12,554	2,531	88,733	8,531	3,463	27,691	1,346	150,015
2014 Total .....	595	255	7,227	2,681	12,520	12,341	1,934	86,209	8,664	1,282	27,239	1,367	144,083
2015 Total .....	509	191	7,471	2,637	12,595	10,896	1,552	88,355	9,401	1,410	27,318	1,243	145,712
2016 Total .....	383	82	7,730	2,496	12,706	9,103	1,412	91,197	8,895	1,269	27,458	1,134	145,890
2017 Total .....	329	112	8,042	2,515	13,060	7,669	1,239	91,647	8,343	1,382	27,412	1,012	143,758
2018 Total .....	303	140	8,419	2,404	13,312	7,011	1,157	94,892	9,377	1,149	27,475	868	146,798
2019 January .....	29	21	706	195	1,160	581	88	8,739	664	124	2,317	65	13,025
February .....	27	10	654	171	1,057	521	77	7,538	597	94	2,086	61	11,335
March .....	33	9	711	189	1,173	500	74	7,978	702	108	2,267	71	12,099
April .....	22	8	646	168	1,053	475	85	7,552	619	106	2,034	65	11,301
May .....	18	7	663	159	1,072	479	70	7,951	730	104	2,084	58	11,854
June .....	13	6	711	178	1,133	484	79	8,196	680	95	2,179	57	12,147
July .....	18	9	869	180	1,313	528	133	8,837	813	71	2,331	55	13,178
August .....	17	12	852	185	1,290	506	83	8,976	770	59	2,357	57	13,236
September .....	21	10	731	179	1,150	470	77	8,483	770	52	2,157	48	12,474
October .....	21	9	666	173	1,072	445	76	8,348	735	63	2,157	67	12,281
November .....	23	9	667	171	1,066	480	77	8,561	721	67	2,174	67	12,531
December .....	27	11	735	181	1,151	489	80	8,906	753	91	2,289	72	13,077
Total .....	268	121	8,610	2,129	13,689	5,957	1,000	100,065	8,554	1,033	26,433	743	148,537
2020 January .....	22	11	751	177	1,167	530	87	9,108	752	93	2,284	72	13,284
February .....	29	6	688	166	1,096	495	73	8,253	761	92	2,135	65	12,186
March .....	22	6	663	181	1,095	477	78	8,268	726	96	2,239	65	12,300
April .....	13	5	562	165	966	422	58	7,351	597	95	2,144	64	11,107
May .....	14	7	597	174	1,038	422	69	7,421	649	95	2,146	62	11,260
June .....	17	7	680	161	1,104	398	83	7,896	624	86	2,074	49	11,643
July .....	17	10	817	173	1,264	447	92	8,335	695	84	2,101	52	12,242
August .....	15	10	798	172	1,228	423	82	8,370	702	80	2,130	51	12,263
September .....	24	8	717	162	1,119	446	71	7,612	652	73	2,087	44	11,397
October .....	17	8	623	163	1,023	437	77	7,395	656	71	1,985	61	11,165
November .....	19	8	624	166	1,025	417	87	7,631	635	81	2,175	57	11,567
December .....	26	9	687	174	1,105	460	86	8,702	636	90	2,235	68	12,806
Total .....	235	97	8,207	2,035	13,230	5,374	943	96,342	8,085	1,035	25,735	708	143,221
2021 January .....	25	10	685	183	1,121	440	75	8,588	659	92	2,212	66	12,602
February .....	36	NM	616	148	1,013	419	96	6,587	577	76	1,900	55	10,101
2-Month Total .....	62	26	1,300	331	2,133	859	171	15,175	1,235	168	4,112	122	22,703
2020 2-Month Total .....	51	18	1,439	343	2,264	1,025	160	17,360	1,513	185	4,419	137	25,471
2019 2-Month Total .....	56	31	1,360	366	2,217	1,102	165	16,277	1,262	217	4,403	126	24,360

<sup>a</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>d</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>g</sup> Includes a small amount of conventional hydroelectric power, geothermal, other gases, solar photovoltaic (PV) energy, wind, wood, and other, which are not separately displayed. Does not include distributed (small-scale) solar photovoltaic generation, shown on Table 10.6.

<sup>h</sup> Blast furnace gas, and other manufactured and waste gases derived from

fossil fuels. Through 2010, also includes propane gas.

<sup>i</sup> Conventional hydroelectric power.

<sup>j</sup> Wood and wood-derived fuels.

<sup>k</sup> Includes photovoltaic (PV) energy, wind, batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels). Does not include distributed (small-scale) solar photovoltaic generation shown on Table 10.6.

NA=Not available. NM=Not meaningful.


Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.


Sources: See end of section.

**Figure 7.3 Consumption of Selected Combustible Fuels for Electricity Generation**


Coal by Sector, 1989–2020




Petroleum by Sector, 1989–2020




Natural Gas by Sector, 1989–2020




Other Gases [b] by Sector, 1989–2020



Wood by Sector, 1989–2020



Waste by Sector, 1989–2020



[a] Includes commercial sector.

[b] Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

Note: Data are for utility-scale facilities.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.

Sources: Tables 7.3a-7.3c.

**Table 7.3a Consumption of Combustible Fuels for Electricity Generation:  
Total (All Sectors) (Sum of Tables 7.3b and 7.3c)**

	Coal <sup>a</sup>	Petroleum					Natural Gas <sup>f</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>j</sup>
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	Total <sup>e</sup>			Wood <sup>h</sup>	Waste <sup>i</sup>	
	Thousand Short Tons	Thousand Barrels			Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu			
1950 Total .....	91,871	5,423	69,998	NA	NA	75,421	629	NA	5	NA	NA
1955 Total .....	143,759	5,412	69,862	NA	NA	75,274	1,153	NA	3	NA	NA
1960 Total .....	176,685	3,824	84,371	NA	NA	88,195	1,725	NA	2	NA	NA
1965 Total .....	244,788	4,928	110,274	NA	NA	115,203	2,321	NA	3	NA	NA
1970 Total .....	320,182	24,123	311,381	NA	636	338,686	3,932	NA	1	2	NA
1975 Total .....	405,962	38,907	467,221	NA	70	506,479	3,158	NA	(s)	2	NA
1980 Total .....	569,274	29,051	391,163	NA	179	421,110	3,682	NA	3	2	NA
1985 Total .....	693,841	14,635	158,779	NA	231	174,571	3,044	NA	8	7	NA
1990 Total <sup>k</sup> .....	792,457	18,143	190,652	437	1,914	218,800	3,692	112	442	211	36
1995 Total .....	860,594	19,615	95,507	680	3,355	132,578	4,738	133	480	316	42
2000 Total .....	994,933	31,675	143,381	1,450	3,744	195,228	5,691	126	496	330	46
2005 Total .....	1,041,448	20,651	141,518	2,968	8,330	206,785	6,036	110	355	230	173
2006 Total .....	1,030,556	13,174	58,473	2,174	7,363	110,634	6,462	115	350	241	172
2007 Total .....	1,046,795	15,683	63,833	2,917	6,036	112,615	7,089	115	353	245	168
2008 Total .....	1,042,335	12,832	38,191	2,822	5,417	80,932	6,896	97	339	267	172
2009 Total .....	934,683	12,658	28,576	2,328	4,821	67,668	7,121	84	320	272	170
2010 Total .....	979,684	14,050	23,997	2,056	4,994	65,071	7,680	90	350	281	184
2011 Total .....	934,938	11,231	14,251	1,844	5,012	52,387	7,884	91	348	279	205
2012 Total .....	825,734	9,285	11,755	1,565	3,675	40,977	9,485	103	390	290	204
2013 Total .....	860,729	9,784	11,766	1,681	4,852	47,492	8,596	115	398	298	200
2014 Total .....	853,634	14,465	14,704	2,363	4,412	53,593	8,544	110	431	314	200
2015 Total .....	739,594	12,438	14,124	2,363	4,044	49,145	10,017	106	407	313	204
2016 Total .....	677,371	9,662	11,195	1,548	4,253	43,671	10,170	74	360	305	199
2017 Total .....	663,911	9,707	10,442	1,547	3,490	39,144	9,508	71	364	304	190
2018 Total .....	636,213	14,223	12,407	1,985	3,623	46,727	10,833	79	362	298	190
2019 January .....	55,834	1,206	996	303	326	4,135	873	6	31	23	17
February .....	45,025	739	580	163	272	2,844	801	5	27	21	15
March .....	43,976	734	611	131	235	2,651	836	6	28	23	16
April .....	33,353	648	621	149	155	2,194	763	5	24	21	16
May .....	40,015	830	735	136	294	3,169	863	6	27	22	17
June .....	44,218	812	790	145	216	2,828	1,017	6	28	22	17
July .....	55,863	775	895	148	309	3,363	1,284	7	31	23	17
August .....	52,349	758	961	150	276	3,251	1,306	6	32	23	18
September .....	47,188	725	786	157	231	2,824	1,109	6	28	22	17
October .....	37,431	742	794	172	83	2,123	965	5	26	22	16
November .....	41,907	779	718	130	129	2,272	847	6	27	22	16
December .....	40,461	873	763	179	197	2,800	939	6	29	23	17
Total .....	537,620	9,620	9,251	1,965	2,724	34,454	11,602	72	338	267	199
2020 January .....	36,773	859	761	158	261	3,082	958	6	28	23	16
February .....	32,039	696	616	131	190	2,393	902	6	27	21	14
March .....	28,989	593	583	192	262	2,678	902	6	27	23	16
April .....	23,623	504	544	137	221	2,288	783	4	24	21	15
May .....	26,849	596	588	104	231	2,442	854	5	26	22	16
June .....	36,708	749	700	123	308	3,115	1,068	5	25	20	15
July .....	49,856	813	801	135	318	3,337	1,396	5	27	21	16
August .....	50,516	747	800	128	295	3,152	1,304	6	29	22	16
September .....	38,757	563	732	115	159	2,206	1,058	6	24	21	15
October .....	33,943	714	787	143	131	2,300	975	5	24	21	15
November .....	34,437	657	677	121	211	2,509	790	6	26	20	15
December .....	43,588	776	720	127	279	3,020	899	6	28	22	17
Total .....	436,076	8,268	8,310	1,613	2,866	32,520	11,888	66	315	256	186
2021 January .....	45,412	663	842	127	268	2,971	892	6	27	22	16
February .....	47,989	1,869	822	352	269	4,387	804	4	26	19	14
2-Month Total .....	93,401	2,532	1,664	480	536	7,358	1,696	10	53	41	29
2020 2-Month Total .....	68,812	1,555	1,377	289	451	5,474	1,860	13	55	43	30
2019 2-Month Total .....	100,859	1,945	1,576	467	598	6,979	1,674	11	58	44	32

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Fuel oil nos. 1, 2, and 4. For 1949–1979, data are for gas turbine and internal combustion plant use of petroleum. For 1980–2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1949–1979, data are for steam plant use of petroleum. For 1980–2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and

tire-derived fuels).

<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • Data are for fuels consumed to produce electricity. Data also include fuels consumed to produce useful thermal output at a small number of electric utility combined-heat-and-power (CHP) plants. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See "Table 7.3b Sources" at end of section and sources for Table 7.3c.

**Table 7.3b Consumption of Combustible Fuels for Electricity Generation:  
Electric Power Sector** (Subset of Table 7.3a)

	Coal <sup>a</sup>	Petroleum					Natural Gas <sup>f</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>j</sup>
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	Total <sup>e</sup>			Wood <sup>h</sup>	Waste <sup>i</sup>	
	Thousand Short Tons	Thousand Barrels			Thousand Short Tons	Thousand Barrels	Billion Cubic Feet		Trillion Btu		
1950 Total .....	91,871	5,423	69,998	NA	NA	75,421	629	NA	5	NA	NA
1955 Total .....	143,759	5,412	69,862	NA	NA	75,274	1,153	NA	3	NA	NA
1960 Total .....	176,685	3,824	84,371	NA	NA	88,195	1,725	NA	2	NA	NA
1965 Total .....	244,788	4,928	110,274	NA	NA	115,203	2,321	NA	3	NA	NA
1970 Total .....	320,182	24,123	311,381	NA	636	338,686	3,932	NA	1	2	NA
1975 Total .....	405,962	38,907	467,221	NA	70	506,479	3,158	NA	(s)	2	NA
1980 Total .....	569,274	29,051	391,163	NA	179	421,110	3,682	NA	3	2	NA
1985 Total .....	693,841	14,635	158,779	NA	231	174,571	3,044	NA	8	7	NA
1990 Total <sup>k</sup> .....	781,301	16,394	183,285	25	1,008	204,745	3,147	6	106	180	(s)
1995 Total .....	847,854	18,066	88,895	441	2,452	119,663	4,094	18	106	282	2
2000 Total .....	982,713	29,722	138,047	403	3,155	183,946	5,014	19	126	294	1
2005 Total .....	1,033,567	19,450	138,337	2,591	7,877	199,760	5,485	24	166	205	116
2006 Total .....	1,022,802	12,578	56,347	1,783	6,905	105,235	5,891	28	163	216	117
2007 Total .....	1,041,346	15,135	62,072	2,496	5,523	107,316	6,502	27	165	221	117
2008 Total .....	1,036,891	12,318	37,222	2,608	5,000	77,149	6,342	23	159	242	122
2009 Total .....	929,692	11,848	27,768	2,110	4,485	64,151	6,567	21	160	244	115
2010 Total .....	971,245	13,677	23,560	1,848	4,679	62,477	7,085	20	177	249	116
2011 Total .....	928,857	10,961	13,861	1,655	4,726	50,105	7,265	18	166	241	133
2012 Total .....	820,762	9,000	11,292	1,339	2,861	35,937	8,788	19	171	250	132
2013 Total .....	855,546	9,511	11,322	1,488	4,189	43,265	7,888	41	187	251	130
2014 Total .....	848,803	14,052	14,132	2,157	4,039	50,537	7,849	29	220	266	127
2015 Total .....	735,433	12,056	13,893	2,086	3,789	46,978	9,322	29	215	268	127
2016 Total .....	674,239	9,421	11,056	1,284	4,018	41,853	9,590	20	191	261	126
2017 Total .....	661,033	9,398	10,299	1,332	3,273	37,394	8,917	21	195	262	121
2018 Total .....	633,593	13,795	12,259	1,757	3,444	45,030	10,215	21	189	257	125
2019 January .....	55,611	1,160	982	286	313	3,991	815	2	17	20	11
February .....	44,821	715	570	141	261	2,731	751	2	14	18	10
March .....	43,799	708	602	113	222	2,531	782	2	14	19	11
April .....	33,185	623	614	121	139	2,055	712	2	11	18	10
May .....	39,832	805	731	116	280	3,050	809	2	14	19	11
June .....	44,040	786	785	126	202	2,708	962	2	14	19	11
July .....	55,665	742	891	131	285	3,189	1,223	2	16	20	12
August .....	52,153	725	957	132	261	3,120	1,245	2	17	20	12
September .....	47,008	688	781	138	216	2,689	1,051	2	15	19	11
October .....	37,268	709	787	155	68	1,990	908	1	13	19	11
November .....	41,727	749	710	107	116	2,144	789	2	13	19	11
December .....	40,274	844	754	159	183	2,670	880	2	15	20	12
Total .....	535,382	9,254	9,163	1,724	2,545	32,868	10,928	21	171	231	133
2020 January .....	36,580	831	754	135	245	2,948	898	2	14	20	11
February .....	31,854	675	608	114	178	2,285	847	2	14	18	10
March .....	28,815	569	578	173	249	2,564	847	2	13	20	11
April .....	23,475	485	540	121	212	2,204	734	1	11	19	11
May .....	26,702	570	582	84	218	2,326	803	1	13	19	11
June .....	36,573	721	695	107	294	2,994	1,014	1	12	17	10
July .....	49,708	778	796	119	302	3,202	1,338	1	13	19	11
August .....	50,371	715	794	118	280	3,026	1,246	2	16	19	11
September .....	38,601	530	728	103	146	2,094	1,006	1	11	18	11
October .....	33,788	685	783	126	119	2,187	924	1	12	18	10
November .....	34,288	626	671	105	196	2,383	738	2	12	17	10
December .....	43,425	749	712	109	265	2,896	840	2	14	19	11
Total .....	434,178	7,935	8,242	1,415	2,703	31,109	11,235	16	154	222	130
2021 January .....	45,255	634	835	114	255	2,860	834	2	13	19	11
February .....	47,837	1,833	813	306	259	4,247	759	1	14	17	10
2-Month Total .....	93,092	2,467	1,648	421	514	7,106	1,593	3	27	35	21
2020 2-Month Total .....	68,433	1,506	1,363	249	423	5,233	1,745	4	28	37	21
2019 2-Month Total .....	100,431	1,875	1,551	426	574	6,722	1,566	4	30	38	21

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Fuel oil nos. 1, 2, and 4. For 1949–1979, data are for gas turbine and internal combustion plant use of petroleum. For 1980–2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1949–1979, data are for steam plant use of petroleum. For 1980–2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • Data are for fuels consumed to produce electricity. Data also include fuels consumed to produce useful thermal output at a small number of electric utility combined-heat-and-power (CHP) plants. • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.



**Table 7.3c Consumption of Selected Combustible Fuels for Electricity Generation: Commercial and Industrial Sectors** (Subset of Table 7.3a)

	Commercial Sector <sup>a</sup>				Industrial Sector <sup>b</sup>						
	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Biomass	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
				Waste <sup>f</sup>					Wood <sup>h</sup>	Waste <sup>f</sup>	
Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu	Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu				
1990 Total .....	417	953	28	15	10,740	13,103	517	104	335	16	36
1995 Total .....	569	649	43	21	12,171	12,265	601	114	373	13	40
2000 Total .....	514	823	37	26	11,706	10,459	640	107	369	10	45
2005 Total .....	377	585	34	20	7,504	6,440	518	85	189	5	46
2006 Total .....	347	333	35	21	7,408	5,066	536	87	187	3	45
2007 Total .....	361	258	34	19	5,089	5,041	554	88	188	4	41
2008 Total .....	369	166	33	20	5,075	3,617	520	73	179	5	39
2009 Total .....	317	190	34	23	4,674	3,328	520	62	160	4	42
2010 Total .....	314	172	39	24	8,125	2,422	555	70	172	8	55
2011 Total .....	347	137	47	31	5,735	2,145	572	74	182	7	57
2012 Total .....	307	279	63	33	4,665	4,761	633	84	219	8	54
2013 Total .....	513	335	67	36	4,670	3,892	642	74	210	11	50
2014 Total .....	202	462	72	36	4,629	2,594	623	81	210	11	54
2015 Total .....	163	260	70	35	3,999	1,907	625	77	191	10	58
2016 Total .....	111	116	46	34	3,021	1,701	534	53	169	10	53
2017 Total .....	95	204	50	34	2,783	1,545	541	49	169	8	49
2018 Total .....	87	279	53	33	2,534	1,418	565	57	172	7	46
2019 January .....	8	34	5	3	214	109	54	4	15	1	4
February .....	8	16	4	2	197	97	46	4	13	1	3
March .....	9	17	5	3	168	103	49	4	14	1	4
April .....	6	16	4	2	161	123	46	4	13	1	3
May .....	6	17	4	2	178	102	50	4	13	(s)	4
June .....	4	17	5	3	174	104	50	4	14	(s)	4
July .....	5	24	6	3	193	150	55	5	15	(s)	4
August .....	5	21	5	3	190	110	56	5	15	(s)	4
September .....	6	27	5	2	175	108	53	5	13	(s)	4
October .....	6	23	4	2	157	109	52	4	14	1	4
November .....	6	23	4	2	173	105	53	4	14	1	4
December .....	7	23	5	3	180	107	55	5	14	1	4
Total .....	76	257	56	30	2,161	1,329	618	51	167	6	45
2020 January .....	6	24	5	2	187	109	56	4	14	1	3
February .....	9	13	4	2	177	94	51	5	13	1	3
March .....	6	17	4	2	168	97	51	4	14	1	3
April .....	4	12	4	2	144	72	45	4	13	(s)	3
May .....	4	20	4	2	142	96	46	4	13	(s)	3
June .....	5	20	4	2	130	101	50	4	13	(s)	3
July .....	5	25	5	2	143	109	53	4	13	(s)	3
August .....	4	24	5	2	140	102	53	4	13	(s)	3
September .....	7	23	5	2	149	89	48	4	13	(s)	3
October .....	5	17	4	2	149	96	47	4	12	(s)	3
November .....	6	20	4	2	144	106	48	4	14	(s)	3
December .....	7	19	4	2	155	104	54	4	14	1	3
Total .....	69	236	52	28	1,829	1,175	601	50	161	6	37
2021 January .....	7	23	4	2	150	88	54	4	14	1	3
February .....	11	27	4	2	141	113	41	3	12	(s)	2
2-Month Total .....	18	50	8	4	291	201	95	8	26	1	6
2020 2-Month Total .....	14	38	9	5	364	204	106	9	28	1	5
2019 2-Month Total .....	16	50	9	5	411	206	100	8	28	1	8

<sup>a</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>d</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous

technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

(s)=Less than 0.5 trillion Btu.


Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of section. • Data are for fuels consumed to produce electricity. Through 1988, data are not available. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual and monthly data beginning in 1989.


Sources: • **1989–1997:** U.S. Energy Information Administration (EIA), Form EIA-867, "Annual Nonutility Power Producer Report." • **1998–2000:** EIA, Form EIA-860B, "Annual Electric Generator Report—Nonutility." • **2001–2003:** EIA, Form EIA-906, "Power Plant Report." • **2004–2007:** EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." • **2008 forward:** EIA, Form EIA-923, "Power Plant Operations Report."

**Figure 7.4 Consumption of Selected Combustible Fuels for Electricity Generation and Useful Thermal Output**


Coal by Sector, 1989–2020




Petroleum by Sector, 1989–2020




Natural Gas by Sector, 1989–2020




Other Gases [b] by Sector, 1989–2020



Wood by Sector, 1989–2020



Waste by Sector, 1989–2020



[a] Includes commercial sector.

[b] Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

Note: Data are for utility-scale facilities.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.

Sources: Tables 7.4a-7.4c.

**Table 7.4a Consumption of Combustible Fuels for Electricity Generation and Useful Thermal Output: Total (All Sectors)** (Sum of Tables 7.4b and 7.4c)

	Coal <sup>a</sup>	Petroleum					Natural Gas <sup>f</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>j</sup>
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	Total <sup>e</sup>			Wood <sup>h</sup>	Waste <sup>i</sup>	
	Thousand Short Tons	Thousand Barrels			Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu			
1950 Total .....	91,871	5,423	69,998	NA	NA	75,421	629	NA	5	NA	NA
1955 Total .....	143,759	5,412	69,862	NA	NA	75,274	1,153	NA	3	NA	NA
1960 Total .....	176,685	3,824	84,371	NA	NA	88,195	1,725	NA	2	NA	NA
1965 Total .....	244,788	4,928	110,274	NA	NA	115,203	2,321	NA	3	NA	NA
1970 Total .....	320,182	24,123	311,381	NA	636	338,686	3,932	NA	1	2	NA
1975 Total .....	405,962	38,907	467,221	NA	70	506,479	3,158	NA	(s)	2	NA
1980 Total .....	569,274	29,051	391,163	NA	179	421,110	3,682	NA	3	2	NA
1985 Total .....	693,841	14,635	158,779	NA	231	174,571	3,044	NA	8	7	NA
1990 Total <sup>k</sup> .....	811,538	20,194	209,081	1,332	2,832	244,765	4,346	288	1,256	257	86
1995 Total .....	881,012	21,697	112,168	1,322	4,590	158,140	5,572	313	1,382	374	97
2000 Total .....	1,015,398	34,572	156,673	2,904	4,669	217,494	6,677	356	1,380	401	109
2005 Total .....	1,065,281	24,446	156,915	4,270	9,113	231,193	7,021	348	1,353	289	237
2006 Total .....	1,053,783	14,655	69,846	3,396	8,622	131,005	7,404	341	1,399	300	247
2007 Total .....	1,069,606	17,042	74,616	4,237	7,299	132,389	7,962	329	1,336	304	239
2008 Total .....	1,064,503	14,137	43,477	3,765	6,314	92,948	7,689	300	1,263	328	212
2009 Total .....	955,190	14,800	33,672	3,218	5,828	80,830	7,938	259	1,137	333	228
2010 Total .....	1,001,411	15,247	26,944	2,777	6,053	75,231	8,502	262	1,226	346	237
2011 Total .....	956,470	11,735	16,877	2,540	6,092	61,610	8,724	282	1,241	340	261
2012 Total .....	845,066	9,945	13,571	2,185	5,021	50,805	10,371	302	1,273	355	252
2013 Total .....	879,078	10,277	14,199	2,212	6,338	58,378	9,479	305	1,318	376	236
2014 Total .....	871,741	15,107	16,615	2,908	5,695	63,106	9,410	304	1,378	395	236
2015 Total .....	756,226	12,924	16,136	3,008	5,188	58,009	10,952	290	1,351	398	237
2016 Total .....	693,958	10,278	12,231	2,173	5,352	51,441	11,322	296	1,330	383	238
2017 Total .....	678,578	10,168	11,508	2,033	4,467	46,043	10,677	299	1,303	375	226
2018 Total .....	650,027	15,066	13,584	2,578	4,552	53,988	12,039	353	1,291	367	226
2019 January .....	57,146	1,427	1,121	362	399	4,905	982	24	112	29	21
February .....	46,183	802	659	217	338	3,368	898	22	100	26	18
March .....	45,088	779	685	172	308	3,175	937	24	105	28	19
April .....	34,362	680	679	201	227	2,693	854	23	96	26	18
May .....	40,956	967	785	177	364	3,747	957	23	101	26	19
June .....	45,168	839	840	183	287	3,295	1,112	22	101	26	19
July .....	56,813	806	942	180	385	3,851	1,386	25	108	26	20
August .....	53,323	800	1,003	188	346	3,720	1,410	24	109	27	21
September .....	48,103	768	841	198	310	3,356	1,206	23	101	25	19
October .....	38,417	776	860	213	146	2,581	1,062	23	101	27	19
November .....	42,926	821	787	267	186	2,803	947	23	103	27	19
December .....	41,533	903	847	222	269	3,317	1,046	24	108	29	20
Total .....	550,017	10,369	10,049	2,580	3,563	40,811	12,798	281	1,246	322	234
2020 January .....	37,833	892	817	201	336	3,589	1,068	25	106	29	18
February .....	33,056	723	676	166	239	2,757	1,004	25	100	26	17
March .....	29,907	620	630	231	301	2,988	1,005	25	101	28	18
April .....	24,427	530	589	168	252	2,546	880	20	97	26	18
May .....	27,652	628	637	143	290	2,858	952	20	102	26	18
June .....	37,480	783	753	157	379	3,589	1,166	19	93	23	17
July .....	50,726	849	853	177	385	3,802	1,500	21	98	25	19
August .....	51,362	785	864	164	371	3,669	1,408	22	99	25	19
September .....	39,605	607	784	142	228	2,675	1,156	21	95	24	17
October .....	34,881	758	839	181	205	2,803	1,077	22	97	25	18
November .....	35,334	711	736	153	280	3,001	889	22	101	25	18
December .....	44,612	817	804	164	353	3,550	1,009	22	108	28	19
Total .....	446,874	8,705	8,982	2,048	3,618	37,827	13,113	264	1,198	310	216
2021 January .....	46,433	711	920	161	340	3,490	1,001	23	104	27	18
February .....	48,964	1,989	910	427	333	4,988	898	18	93	24	16
2-Month Total .....	95,398	2,700	1,830	587	672	8,478	1,899	41	198	52	34
2020 2-Month Total .....	70,888	1,615	1,493	367	574	6,347	2,072	50	206	55	35
2019 2-Month Total .....	103,329	2,229	1,780	579	737	8,272	1,880	46	212	56	39

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Fuel oil nos. 1, 2, and 4. For 1949–1979, data are for gas turbine and internal combustion plant use of petroleum. For 1980–2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1949–1979, data are for steam plant use of petroleum. For 1980–2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes

non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See "Table 7.4b Sources" at end of section and sources for Table 7.4c.

**Table 7.4b Consumption of Combustible Fuels for Electricity Generation and Useful Thermal Output: Electric Power Sector** (Subset of Table 7.4a)

	Coal <sup>a</sup>	Petroleum					Natural Gas <sup>f</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	Total <sup>e</sup>			Wood <sup>h</sup>	Waste <sup>i</sup>	
	Thousand Short Tons	Thousand Barrels			Thousand Short Tons	Thousand Barrels	Billion Cubic Feet		Trillion Btu		
1950 Total .....	91,871	5,423	69,998	NA	NA	75,421	629	NA	5	NA	NA
1955 Total .....	143,759	5,412	69,862	NA	NA	75,274	1,153	NA	3	NA	NA
1960 Total .....	176,685	3,824	84,371	NA	NA	88,195	1,725	NA	2	NA	NA
1965 Total .....	244,788	4,928	110,274	NA	NA	115,203	2,321	NA	3	NA	NA
1970 Total .....	320,182	24,123	311,381	NA	636	338,686	3,932	NA	1	2	NA
1975 Total .....	405,962	38,907	467,221	NA	70	506,479	3,158	NA	(s)	2	NA
1980 Total .....	569,274	29,051	391,163	NA	179	421,110	3,682	NA	3	2	NA
1985 Total .....	693,841	14,635	158,779	NA	231	174,571	3,044	NA	8	7	NA
1990 Total <sup>k</sup> .....	782,567	16,567	184,915	26	1,008	206,550	3,245	11	129	188	(s)
1995 Total .....	850,230	18,553	90,023	499	2,674	122,447	4,237	24	125	296	2
2000 Total .....	985,821	30,016	138,513	454	3,275	185,358	5,206	25	134	318	1
2005 Total .....	1,037,485	19,675	139,409	2,685	8,083	202,184	5,869	84	185	221	123
2006 Total .....	1,026,636	12,646	57,345	1,870	7,101	107,365	6,222	65	182	231	125
2007 Total .....	1,045,141	15,327	63,086	2,594	5,685	109,431	6,841	61	186	237	124
2008 Total .....	1,040,580	12,547	38,241	2,670	5,119	79,056	6,668	61	177	258	131
2009 Total .....	933,627	12,035	28,782	2,210	4,611	66,081	6,873	55	180	261	124
2010 Total .....	975,052	13,790	24,503	1,877	4,777	64,055	7,387	52	196	264	124
2011 Total .....	932,484	11,021	14,803	1,658	4,837	51,667	7,574	50	182	255	143
2012 Total .....	823,551	9,080	12,203	1,339	2,974	37,495	9,111	54	190	262	143
2013 Total .....	857,962	9,598	12,283	1,489	4,285	44,794	8,191	60	207	262	139
2014 Total .....	851,602	14,235	15,132	2,208	4,132	52,235	8,146	44	251	279	137
2015 Total .....	738,444	12,193	14,929	2,131	3,907	48,787	9,613	44	244	281	136
2016 Total .....	678,554	9,510	11,242	1,322	4,138	42,763	9,985	45	224	281	139
2017 Total .....	664,993	9,481	10,464	1,375	3,399	38,318	9,266	46	229	280	132
2018 Total .....	637,217	13,967	12,446	1,855	3,549	46,013	10,590	47	221	275	136
2019 January .....	55,967	1,181	1,009	297	322	4,096	849	4	19	22	12
February .....	45,124	729	586	142	271	2,809	779	4	16	19	11
March .....	44,098	714	618	114	231	2,602	814	5	16	21	12
April .....	33,429	627	629	122	151	2,132	740	4	14	20	11
May .....	40,045	812	745	117	289	3,117	836	4	16	21	12
June .....	44,297	790	799	127	210	2,768	991	4	16	20	12
July .....	55,932	745	902	132	295	3,255	1,255	4	19	21	13
August .....	52,431	730	967	133	270	3,179	1,278	4	19	21	13
September .....	47,249	693	799	139	226	2,760	1,081	4	17	20	12
October .....	37,523	714	804	157	70	2,027	937	3	15	21	12
November .....	41,977	754	725	109	126	2,218	819	4	16	20	12
December .....	40,534	849	769	160	194	2,749	912	4	18	22	13
Total .....	538,606	9,336	9,352	1,750	2,655	33,712	11,288	47	201	248	145
2020 January .....	36,808	835	763	137	256	3,016	931	4	17	21	12
February .....	32,067	679	616	115	188	2,350	879	4	16	20	11
March .....	28,979	574	587	175	258	2,628	879	4	15	21	12
April .....	23,624	492	551	122	222	2,277	764	3	13	20	12
May .....	26,870	575	593	85	229	2,399	834	3	15	20	12
June .....	36,746	726	705	108	301	3,045	1,046	2	15	18	11
July .....	49,930	782	809	120	309	3,256	1,372	2	16	20	12
August .....	50,590	720	806	120	289	3,088	1,280	4	19	20	12
September .....	38,788	535	741	104	156	2,162	1,038	3	13	19	11
October .....	33,997	692	799	128	128	2,260	954	3	14	19	11
November .....	34,473	632	689	106	207	2,461	767	4	15	19	11
December .....	43,653	755	737	111	275	2,978	873	4	17	21	12
Total .....	436,524	7,999	8,396	1,430	2,819	31,921	11,616	40	185	238	142
2021 January .....	45,498	638	856	117	268	2,950	866	4	16	20	12
February .....	48,101	1,881	834	320	269	4,379	788	2	16	18	11
2-Month Total .....	93,599	2,519	1,691	437	537	7,329	1,654	6	33	38	22
2020 2-Month Total .....	68,874	1,515	1,379	252	444	5,366	1,810	8	33	41	24
2019 2-Month Total .....	101,091	1,909	1,595	439	592	6,905	1,628	8	36	41	23

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Fuel oil nos. 1, 2, and 4. For 1949–1979, data are for gas turbine and internal combustion plant use of petroleum. For 1980–2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1949–1979, data are for steam plant use of petroleum. For 1980–2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and

tire-derived fuels).

<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 7.4c Consumption of Selected Combustible Fuels for Electricity Generation and Useful Thermal Output: Commercial and Industrial Sectors** (Subset of Table 7.4a)

	Commercial Sector <sup>a</sup>				Industrial Sector <sup>b</sup>						
	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Biomass	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
				Waste <sup>f</sup>					Wood <sup>h</sup>	Waste <sup>f</sup>	
Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu	Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu				
1990 Total .....	1,191	2,056	46	28	27,781	36,159	1,055	275	1,125	41	86
1995 Total .....	1,419	1,245	78	40	29,363	34,448	1,258	290	1,255	38	95
2000 Total .....	1,547	1,615	85	47	28,031	30,520	1,386	331	1,244	35	108
2005 Total .....	1,922	1,630	68	34	25,875	27,380	1,084	264	1,166	34	94
2006 Total .....	1,886	935	68	36	25,262	22,706	1,115	277	1,216	33	102
2007 Total .....	1,927	752	70	31	22,537	22,207	1,050	268	1,148	36	98
2008 Total .....	2,021	671	66	34	21,902	13,222	955	239	1,084	35	60
2009 Total .....	1,798	521	76	36	19,766	14,228	990	204	955	35	82
2010 Total .....	1,720	437	86	36	24,638	10,740	1,029	210	1,029	47	91
2011 Total .....	1,668	333	87	43	22,319	9,610	1,063	232	1,057	43	94
2012 Total .....	1,450	457	111	45	20,065	12,853	1,149	249	1,082	47	81
2013 Total .....	1,356	887	118	47	19,761	12,697	1,170	246	1,109	67	69
2014 Total .....	1,063	758	119	47	19,076	10,112	1,145	260	1,122	70	72
2015 Total .....	798	622	116	47	16,984	8,600	1,222	246	1,103	70	73
2016 Total .....	683	404	127	48	14,720	8,273	1,209	251	1,100	54	70
2017 Total .....	610	516	154	48	12,975	7,209	1,257	253	1,069	47	65
2018 Total .....	577	681	135	47	12,233	7,294	1,314	306	1,065	45	62
2019 January .....	59	100	12	4	1,119	708	121	20	92	4	6
February .....	54	51	11	3	1,005	508	108	18	83	4	5
March .....	58	53	11	3	932	521	113	20	89	4	5
April .....	40	39	10	3	893	522	105	19	82	3	5
May .....	38	137	10	3	873	493	111	19	85	2	5
June .....	27	29	11	3	844	498	111	19	84	3	5
July .....	35	48	13	3	846	548	118	21	89	2	5
August .....	37	44	12	3	854	498	120	20	90	2	5
September .....	40	54	11	3	814	541	114	20	83	2	5
October .....	37	44	11	3	856	510	114	19	86	3	5
November .....	44	55	11	3	904	530	117	19	86	4	5
December .....	49	52	12	3	950	516	122	20	90	4	5
Total .....	519	707	135	39	10,892	6,393	1,374	234	1,040	35	61
2020 January .....	41	60	12	3	984	514	125	21	88	4	4
February .....	49	37	11	3	940	370	114	21	84	4	4
March .....	41	37	11	3	887	323	115	20	85	3	4
April .....	29	24	10	3	774	245	107	17	83	3	4
May .....	32	42	10	3	750	417	108	18	87	3	4
June .....	35	38	10	3	699	505	110	17	78	2	4
July .....	35	53	12	3	761	493	116	18	82	2	4
August .....	37	57	12	3	735	523	116	18	80	2	4
September .....	41	45	11	3	775	467	107	18	82	2	4
October .....	34	35	10	3	850	508	112	19	83	3	4
November .....	36	45	10	3	826	495	111	18	86	3	4
December .....	50	45	11	3	909	527	125	18	90	4	5
Total .....	459	518	130	36	9,890	5,387	1,367	223	1,008	36	50
2021 January .....	49	58	12	3	886	481	123	19	88	4	4
February .....	60	92	11	3	803	518	99	16	76	3	4
2-Month Total .....	109	150	22	6	1,690	999	222	35	164	7	8
2020 2-Month Total .....	89	97	23	6	1,924	884	239	41	172	8	8
2019 2-Month Total .....	114	151	23	7	2,124	1,217	229	37	176	7	10

<sup>a</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>d</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, waste oil, and, beginning in 2011, propane.

<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>g</sup> Blast furnace gas, and other manufactured and waste gases derived from fossil fuels. Through 2010, also includes propane gas.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).


Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual and monthly data beginning in 1989.


Sources: • **1989–1997:** U.S. Energy Information Administration (EIA), Form EIA-867, "Annual Nonutility Power Producer Report." • **1998–2000:** EIA, Form EIA-860B, "Annual Electric Generator Report—Nonutility." • **2001–2003:** EIA, Form EIA-906, "Power Plant Report." • **2004–2007:** EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." • **2008 forward:** EIA, Form EIA-923, "Power Plant Operations Report."

**Figure 7.5 Stocks of Coal and Petroleum: Electric Power Sector**


Coal, 1949–2020




Total Petroleum, 1949–2020



Coal, Monthly



Total Petroleum, Monthly



Note: Data are for utility-sale facilities.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.

Source: Table 7.5.

**Table 7.5 Stocks of Coal and Petroleum: Electric Power Sector**

	Coal <sup>a</sup>	Petroleum				
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	Total <sup>e,f</sup>
	Thousand Short Tons	Thousand Barrels			Thousand Short Tons	Thousand Barrels
1950 Year .....	31,842	NA	NA	NA	NA	10,201
1955 Year .....	41,391	NA	NA	NA	NA	13,671
1960 Year .....	51,735	NA	NA	NA	NA	19,572
1965 Year .....	54,525	NA	NA	NA	NA	25,647
1970 Year .....	71,908	NA	NA	NA	239	39,151
1975 Year .....	110,724	16,432	108,825	NA	31	125,413
1980 Year .....	183,010	30,023	105,351	NA	52	135,635
1985 Year .....	156,376	16,386	57,304	NA	49	73,933
1990 Year .....	156,166	16,471	67,030	NA	94	83,970
1995 Year .....	126,304	15,392	35,102	NA	65	50,821
2000 Year <sup>g</sup> .....	102,296	15,127	24,748	NA	211	40,932
2005 Year .....	101,137	18,778	27,624	NA	530	50,062
2006 Year .....	140,964	18,013	28,823	1,380	674	51,583
2007 Year .....	151,221	18,395	24,136	1,902	554	47,203
2008 Year .....	161,589	17,761	21,088	1,634	739	44,178
2009 Year .....	189,467	17,886	19,068	1,651	1,394	45,575
2010 Year .....	174,917	16,758	16,629	1,454	1,019	39,936
2011 Year .....	172,387	16,649	15,491	1,603	508	36,282
2012 Year .....	185,116	16,433	12,999	1,430	495	33,336
2013 Year .....	147,884	16,068	12,926	1,393	390	32,336
2014 Year .....	151,548	18,309	12,764	1,249	827	36,459
2015 Year .....	195,548	17,955	12,566	1,173	1,340	38,396
2016 Year .....	162,009	17,855	11,789	949	845	34,818
2017 Year .....	137,687	16,342	10,930	816	864	32,407
2018 Year .....	102,793	16,436	8,785	756	539	28,674
<b>2019</b> January .....	99,145	16,430	8,672	689	528	28,429
February .....	98,637	16,462	9,011	680	505	28,680
March .....	96,932	16,489	9,034	679	503	28,715
April .....	108,072	16,635	9,007	688	513	28,895
May .....	115,700	16,716	8,994	697	444	28,625
June .....	116,861	16,632	8,854	700	388	28,125
July .....	110,661	16,554	8,570	703	354	27,599
August .....	110,268	16,413	8,090	706	380	27,109
September .....	110,615	16,460	8,281	708	292	26,910
October .....	118,566	16,557	8,156	701	292	26,876
November .....	122,357	16,434	8,563	722	464	28,038
<b>December</b> .....	<b>128,176</b>	<b>16,733</b>	<b>8,549</b>	<b>678</b>	<b>471</b>	<b>28,317</b>
<b>2020</b> January .....	134,352	16,414	8,076	630	508	27,660
February .....	139,280	16,246	8,129	620	600	27,994
March .....	145,218	16,496	8,286	549	541	28,036
April .....	151,723	16,369	8,480	546	541	28,102
May .....	154,037	16,567	8,422	535	529	28,169
June .....	150,406	16,515	8,505	525	480	27,944
July .....	137,956	17,174	8,560	499	456	28,511
August .....	129,645	16,925	7,773	518	408	27,257
September .....	129,079	17,011	8,212	514	417	27,820
October .....	133,421	16,954	8,270	506	457	28,014
November .....	136,168	16,768	8,156	500	472	27,786
<b>December</b> .....	<b>132,723</b>	<b>16,796</b>	<b>8,251</b>	<b>500</b>	<b>298</b>	<b>27,038</b>
<b>2021</b> January .....	125,399	16,742	8,211	497	253	26,715
February .....	109,717	16,052	8,063	469	207	25,621

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, and lignite; excludes waste coal.

<sup>b</sup> Fuel oil nos. 1, 2 and 4. For 1973–1979, data are for gas turbine and internal combustion plant stocks of petroleum. For 1980–2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1973–1979, data are for steam plant stocks of petroleum. For 1980–2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel and kerosene. Through 2003, data also include a small amount of waste oil.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Distillate fuel oil and residual fuel oil. Beginning in 1970, also includes petroleum coke. Beginning in 2002, also includes other liquids.

<sup>g</sup> Through 1998, data are for electric utilities only. Beginning in 1999, data are for electric utilities and independent power producers.

NA=Not available.

Notes: • Data are for utility-scale facilities. See Note 1, "Coverage of Electricity Statistics," at end of section. • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose

primary business is to sell electricity, or electricity and heat, to the public. • Stocks are at end of period. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **1949–September 1977:** Federal Power Commission, Form FPC-4, "Monthly Power Plant Report." • **October 1977–1981:** Federal Energy Regulatory Commission, Form FPC-4, "Monthly Power Plant Report." • **1982–1988:** U.S. Energy Information Administration (EIA), Form EIA-759, "Monthly Power Plant Report." • **1989–1997:** EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report." • **1998–2000:** EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility." • **2001–2003:** EIA, Form EIA-906, "Power Plant Report." • **2004–2007:** EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." • **2008 forward:** EIA, Form EIA-923, "Power Plant Operations Report."


**Figure 7.6 Electricity End Use**

(Billion Kilowatthours)


Electricity End Use Overview, 1989–2020




Retail Sales [a] by Sector, February 2021




Retail Sales [a] by Sector, 1949–2020



Retail Sales [a] by Sector, Monthly



Retail Sales [a] Total, January–February



[a] Electricity retail sales to ultimate customers reported by utilities and other energy service providers.

[b] See “Direct Use” in Glossary.

[c] Commercial sector, including public street and highway lighting, inter-

departmental sales, and other sales to public authorities.

[d] Transportation sector, including sales to railroads and railways.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.

Source: Table 7.6.



**Table 7.6 Electricity End Use**  
(Million Kilowatthours)

	Retail Sales <sup>a</sup>					Direct Use <sup>f</sup>	Total End Use <sup>g</sup>
	Residential	Commercial <sup>b</sup>	Industrial <sup>c</sup>	Transportation <sup>d</sup>	Total Retail Sales <sup>e</sup>		
<b>1950 Total</b> .....	72,200	E 65,971	146,479	E 6,793	291,443	NA	291,443
<b>1955 Total</b> .....	128,401	E 102,547	259,974	E 5,826	496,748	NA	496,748
<b>1960 Total</b> .....	201,463	E 159,144	324,402	E 3,066	688,075	NA	688,075
<b>1965 Total</b> .....	291,013	E 231,126	428,727	E 2,923	953,789	NA	953,789
<b>1970 Total</b> .....	466,291	E 352,041	570,854	E 3,115	1,392,300	NA	1,392,300
<b>1975 Total</b> .....	588,140	E 468,296	687,680	E 2,974	1,747,091	NA	1,747,091
<b>1980 Total</b> .....	717,495	558,643	815,067	3,244	2,094,449	NA	2,094,449
<b>1985 Total</b> .....	793,934	689,121	836,772	4,147	2,323,974	NA	2,323,974
<b>1990 Total</b> .....	924,019	838,263	945,522	4,751	2,712,555	124,529	2,837,084
<b>1995 Total</b> .....	1,042,501	953,117	1,012,693	4,975	3,013,287	150,677	3,163,963
<b>2000 Total</b> .....	1,192,446	1,159,347	1,064,239	5,382	3,421,414	170,943	3,592,357
<b>2005 Total</b> .....	1,359,227	1,275,079	1,019,156	7,506	3,660,969	150,016	3,810,984
<b>2006 Total</b> .....	1,351,520	1,299,744	1,011,298	7,358	3,669,919	146,927	3,816,845
<b>2007 Total</b> .....	1,392,241	1,336,315	1,027,832	8,173	3,764,561	125,670	3,890,231
<b>2008 Total</b> .....	1,380,662	1,336,133	1,009,516	7,653	3,733,965	132,197	3,866,161
<b>2009 Total</b> .....	1,364,758	1,306,853	917,416	7,768	3,596,795	126,938	3,723,733
<b>2010 Total</b> .....	1,445,708	1,330,199	971,221	7,712	3,754,841	131,910	3,886,752
<b>2011 Total</b> .....	1,422,801	1,328,057	991,316	7,672	3,749,846	132,754	3,882,600
<b>2012 Total</b> .....	1,374,515	1,327,101	985,714	7,320	3,694,650	137,657	3,832,306
<b>2013 Total</b> .....	1,394,812	1,337,079	985,352	7,625	3,724,868	143,462	3,868,330
<b>2014 Total</b> .....	1,407,208	1,352,158	997,576	7,758	3,764,700	138,574	3,903,274
<b>2015 Total</b> .....	1,404,096	1,360,752	986,508	7,637	3,758,992	141,168	3,900,160
<b>2016 Total</b> .....	1,411,058	1,367,191	976,715	7,497	3,762,462	139,844	3,902,306
<b>2017 Total</b> .....	1,378,648	1,352,888	984,298	7,523	3,723,356	141,114	3,864,470
<b>2018 Total</b> .....	1,469,093	1,381,755	1,000,673	7,665	3,859,185	144,114	4,003,299
<b>2019 January</b> .....	133,318	112,012	82,610	670	328,609	E 12,544	341,154
February .....	116,608	102,071	76,447	672	295,798	E 10,958	306,756
March .....	112,605	107,468	81,093	686	301,853	E 11,737	313,589
April .....	90,384	102,446	80,460	610	273,900	E 10,925	284,825
May .....	100,331	111,201	84,661	608	296,802	E 11,430	308,232
June .....	120,116	115,745	84,992	608	321,462	E 11,743	333,205
July .....	153,749	130,951	90,752	642	376,095	E 12,814	388,909
August .....	150,083	130,776	91,062	653	372,574	E 12,845	385,419
September .....	131,567	122,059	86,160	677	340,463	E 12,048	352,511
October .....	107,997	115,305	84,396	543	308,241	E 11,808	320,050
November .....	102,453	102,840	79,625	614	285,532	E 12,023	297,556
December .....	121,078	108,001	80,095	648	309,823	E 12,582	322,405
<b>Total</b> .....	<b>1,440,289</b>	<b>1,360,877</b>	<b>1,002,353</b>	<b>7,632</b>	<b>3,811,150</b>	<b>143,458</b>	<b>3,954,609</b>
<b>2020 January</b> .....	124,413	108,903	77,339	664	311,318	E 12,780	324,098
February .....	111,929	101,904	75,664	622	290,120	E 11,746	301,866
March .....	104,006	102,937	77,658	577	285,177	E 11,846	297,023
April .....	97,465	90,631	69,591	458	258,145	E 10,676	268,821
May .....	105,412	93,406	71,220	448	270,486	E 10,875	281,361
June .....	131,242	108,699	75,230	480	315,651	E 11,273	326,924
July .....	166,891	126,010	81,278	555	374,734	E 11,943	386,677
August .....	158,801	122,035	82,852	525	364,212	E 11,930	376,142
September .....	127,706	112,297	77,468	532	318,002	E 11,067	329,069
October .....	105,145	107,404	79,079	514	292,142	E 10,778	302,920
November .....	99,444	97,091	75,866	525	272,926	E 11,135	284,061
December .....	129,504	104,403	76,289	632	310,828	E 12,302	323,130
<b>Total</b> .....	<b>1,461,958</b>	<b>1,275,718</b>	<b>919,533</b>	<b>6,532</b>	<b>3,663,741</b>	<b>E 138,351</b>	<b>3,802,093</b>
<b>2021 January</b> .....	137,243	104,192	79,222	563	321,219	E 12,135	333,354
February .....	127,076	98,175	73,246	554	299,051	E 9,828	308,878
<b>2-Month Total</b> .....	<b>264,319</b>	<b>202,366</b>	<b>152,468</b>	<b>1,116</b>	<b>620,269</b>	<b>E 21,963</b>	<b>642,232</b>
<b>2020 2-Month Total</b> .....	<b>236,342</b>	<b>210,807</b>	<b>153,003</b>	<b>1,287</b>	<b>601,438</b>	<b>E 24,526</b>	<b>625,964</b>
<b>2019 2-Month Total</b> .....	<b>249,926</b>	<b>214,083</b>	<b>159,057</b>	<b>1,341</b>	<b>624,407</b>	<b>E 23,503</b>	<b>647,909</b>

<sup>a</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

<sup>b</sup> Commercial sector, including public street and highway lighting, interdepartmental sales, and other sales to public authorities.

<sup>c</sup> Industrial sector. Through 2002, excludes agriculture and irrigation; beginning in 2003, includes agriculture and irrigation.

<sup>d</sup> Transportation sector, including sales to railroads and railways.

<sup>e</sup> The sum of "Residential," "Commercial," "Industrial," and "Transportation."

<sup>f</sup> Use of electricity that is 1) self-generated, 2) produced by either the same entity that consumes the power or an affiliate, and 3) used in direct support of a service or industrial process located within the same facility or group of facilities

that house the generating equipment. Direct use is exclusive of station use.

<sup>g</sup> The sum of "Total Retail Sales" and "Direct Use."

E=Estimate. NA=Not available.

Notes: • See Note 1, "Coverage of Electricity Statistics," at end of section.

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Note 1. Coverage of Electricity Statistics.** Data in Section 7 cover the following:

Through 1984, data for electric utilities also include institutions (such as universities) and military facilities that generated electricity primarily for their own use; beginning in 1985, data for electric utilities exclude institutions and military facilities. Beginning in 1989, data for the commercial sector include institutions and military facilities.

The generation, consumption, and stocks data in Section 7 are for utility-scale facilities—those with a combined generation nameplate capacity of 1 megawatt or more. Data exclude distributed (small-scale) facilities—those with a combined generator nameplate capacity of less than 1 megawatt. For data on distributed solar photovoltaic (PV) generation in the residential, commercial, and industrial sectors, see Table 10.6.

**Note 2. Classification of Power Plants into Energy-Use Sectors.** The U.S. Energy Information Administration (EIA) classifies power plants (both electricity-only and combined-heat-and-power plants) into energy-use sectors based on the North American Industry Classification System (NAICS), which replaced the Standard Industrial Classification (SIC) system in 1997. Plants with a NAICS code of 22 are assigned to the Electric Power Sector. Those with NAICS codes beginning with 11 (agriculture, forestry, fishing, and hunting); 21 (mining, including oil and gas extraction); 23 (construction); 31–33 (manufacturing); 2212 (natural gas distribution); and 22131 (water supply and irrigation systems) are assigned to the Industrial Sector. Those with all other codes are assigned to the Commercial Sector. Form EIA-860, "Annual Electric Generator Report," asks respondents to indicate the primary purpose of the facility by assigning a NAICS code from the list at [http://www.eia.gov/survey/form/eia\\_860/instructions.pdf](http://www.eia.gov/survey/form/eia_860/instructions.pdf).

**Note 3. Electricity Forecast Values.** Data values preceded by "F" in this section are forecast values. They are derived from EIA's Short-Term Integrated Forecasting System (STIFS). STIFS is driven primarily by data and assumptions about key macroeconomic variables, energy prices, and weather. The electricity forecast relies on additional variables such as alternative fuel prices (natural gas and oil) and power generation by sources other than fossil fuels, including nuclear, renewables, and hydroelectric power. Each month, EIA staff review the model output and make adjustments, if appropriate, based on their knowledge of developments in the electricity industry.

The STIFS model results are published monthly in EIA's Short-Term Energy Outlook, which is accessible on the Web at <http://www.eia.gov/forecasts/steo/>.

## Table 7.1 Sources

### *Net Generation, Electric Power Sector*

1949 forward: Table 7.2b.

### *Net Generation, Commercial and Industrial Sectors*

1949 forward: Table 7.2c.

### *Trade*

1949–September 1977: Unpublished Federal Power Commission data.

October 1977–1980: Unpublished Economic Regulatory Administration (ERA) data.

1981: U.S. Department of Energy (DOE), Office of Energy Emergency Operations, "Report on Electric Energy Exchanges with Canada and Mexico for Calendar Year 1981," April 1982 (revised June 1982).

1982 and 1983: DOE, ERA, *Electricity Exchanges Across International Borders*.

1984–1986: DOE, ERA, *Electricity Transactions Across International Borders*.

1987 and 1988: DOE, ERA, Form ERA-781R, "Annual Report of International Electrical Export/Import Data."

1989: DOE, Fossil Energy, Form FE-781R, "Annual Report of International Electrical Export/Import Data."

1990–2000: National Energy Board of Canada; and DOE, Office of Electricity Delivery and Energy Reliability, Form FE-781R, "Annual Report of International Electrical Export/Import Data."

2001–May 2011: National Energy Board of Canada; DOE, Office of Electricity Delivery and Energy Reliability, Form OE-781R, "Monthly Electricity Imports and Exports Report," and predecessor form; and California Independent System Operator.

June 2011–2015: National Energy Board of Canada; California Independent System Operator; and EIA estimates for Texas transfers.

2016 forward: EIA, Form EIA-111, "Quarterly Electricity Imports and Exports Report"; and for forecast values, EIA Short-Term Integrated Forecasting System (STIFS).

### ***T&D Losses and Unaccounted for***

1949 forward: Calculated as the sum of total net generation and imports minus end use and exports.

### ***End Use***

1949 forward: Table 7.6.

## **Table 7.2b Sources**

1949–September 1977: Federal Power Commission, Form FPC-4, "Monthly Power Plant Report."

October 1977–1981: Federal Energy Regulatory Commission, Form FPC-4, "Monthly Power Plant Report."

1982–1988: U.S. Energy Information Administration (EIA), Form EIA-759, "Monthly Power Plant Report."

1989–1997: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report."

1998–2000: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility."

2001–2003: EIA, Form EIA-906, "Power Plant Report."

2004–2007: EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report."

2008 forward: EIA, Form EIA-923, "Power Plant Operations Report".

## **Table 7.2c Sources**

### **Industrial Sector, Hydroelectric Power, 1949–1988**

1949–September 1977: Federal Power Commission (FPC), Form FPC-4, "Monthly Power Plant Report," for plants with generating capacity exceeding 10 megawatts, and FPC, Form FPC-12C, "Industrial Electric Generating Capacity," for all other plants.

October 1977–1978: Federal Energy Regulatory Commission (FERC), Form FPC-4, "Monthly Power Plant Report," for plants with generating capacity exceeding 10 megawatts, and FERC, Form FPC-12C, "Industrial Electric Generating Capacity," for all other plants.

1979: FERC, Form FPC-4, "Monthly Power Plant Report," for plants with generating capacity exceeding 10 megawatts, and U.S. Energy Information Administration (EIA) estimates for all other plants.

1980–1988: Estimated by EIA as the average generation over the 6-year period of 1974–1979.

### ***All Data, 1989 Forward***

1989–1997: EIA, Form EIA-867, "Annual Nonutility Power Producer Report."

1998–2000: EIA, Form EIA-860B, "Annual Electric Generator Report—Nonutility."

2001–2003: EIA, Form EIA-906, "Power Plant Report."

2004–2007: EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report."

2008 forward: EIA, Form EIA-923, "Power Plant Operations Report".

### Table 7.3b Sources

1949–September 1977: Federal Power Commission, Form FPC-4, "Monthly Power Plant Report."

October 1977–1981: Federal Energy Regulatory Commission, Form FPC-4, "Monthly Power Plant Report."

1982–1988: U.S. Energy Information Administration (EIA), Form EIA-759, "Monthly Power Plant Report."

1989–1997: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report."

1998–2000: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility."

2001–2003: EIA, Form EIA-906, "Power Plant Report."

2004–2007: EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report."

2008 forward: EIA, Form EIA-923, "Power Plant Operations Report".

### Table 7.4b Sources

1949–September 1977: Federal Power Commission, Form FPC-4, "Monthly Power Plant Report."

October 1977–1981: Federal Energy Regulatory Commission, Form FPC-4, "Monthly Power Plant Report."

1982–1988: U.S. Energy Information Administration (EIA), Form EIA-759, "Monthly Power Plant Report."

1989–1997: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report."

1998–2000: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility."

2001–2003: EIA, Form EIA-906, "Power Plant Report."

2004–2007: EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report."

2008 forward: EIA, Form EIA-923, "Power Plant Operations Report".

### Table 7.6 Sources

#### *Retail Sales, Residential and Industrial*

1949–September 1977: Federal Power Commission, Form FPC-5, "Monthly Statement of Electric Operating Revenue and Income."

October 1977–February 1980: Federal Energy Regulatory Commission (FERC), Form FPC-5, "Monthly Statement of Electric Operating Revenue and Income."

March 1980–1982: FERC, Form FPC-5, "Electric Utility Company Monthly Statement."

1983: U.S. Energy Information Administration (EIA), Form EIA-826, "Electric Utility Company Monthly Statement."

1984–2003: EIA, Form EIA-861, "Annual Electric Utility Report."

2004 forward: EIA, *Electric Power Monthly (EPM)* April 2021, Table 5.1.

### ***Retail Sales, Commercial***

1949–2002: Data are estimates. See estimation methodology at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_elec.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_elec.pdf).

2003: EIA, Form EIA-861, "Annual Electric Utility Report."

2004 forward: EIA, EPM, April 2021, Table 5.1.

### ***Retail Sales, Transportation***

1949–2002: Data are estimates. See estimation methodology at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_elec.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_elec.pdf).

2003: EIA, Form EIA-861, "Annual Electric Utility Report."

2004 forward: EIA, EPM April 2021, Table 5.1.

### ***Direct Use, Annual***

1989–1997: EIA, Form EIA-867, "Annual Nonutility Power Producer Report."

1998–2000: EIA, Form EIA-860B, "Annual Electric Generator Report—Nonutility."

2001–2019: EIA, *Electric Power Annual* 2019, October 2020, Table 2.2.

2020: Sum of monthly estimates.

### ***Direct Use, Monthly***

1989 forward: Annual shares are calculated as annual direct use divided by annual commercial and industrial net generation (on Table 7.1). Then monthly direct use estimates are calculated as the annual share multiplied by the monthly commercial and industrial net generation values. For 2020, the 2019 annual share is used.


THIS PAGE INTENTIONALLY LEFT BLANK

## 8. Nuclear Energy


---

**Figure 8.1 Nuclear Energy Overview**


Electricity Net Generation, 1957–2020




Nuclear Share of Electricity Net Generation, 1957–2020



Nuclear Electricity Net Generation—February



Capacity Factor, Monthly



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#nuclear>.  
Sources: Tables 7.2a and 8.1.



**Table 8.1 Nuclear Energy Overview**

	Total Operable Units <sup>a,b</sup>	Net Summer Capacity of Operable Units <sup>b,c</sup>	Nuclear Electricity Net Generation	Nuclear Share of Electricity Net Generation	Capacity Factor <sup>d</sup>
	Number	Million Kilowatts	Million Kilowatthours	Percent	
1957 Total .....	1	0.055	10	(s)	NA
1960 Total .....	3	.411	518	.1	NA
1965 Total .....	13	.793	3,657	.3	NA
1970 Total .....	20	7.004	21,804	1.4	NA
1975 Total .....	57	37.267	172,505	9.0	55.9
1980 Total .....	71	51.810	251,116	11.0	56.3
1985 Total .....	96	79.397	383,691	15.5	58.0
1990 Total .....	112	99.624	576,862	19.0	66.0
1995 Total .....	109	99.515	673,402	20.1	77.4
2000 Total .....	104	97.860	753,893	19.8	88.1
2005 Total .....	104	99.988	781,986	19.3	89.3
2006 Total .....	104	100.334	787,219	19.4	89.6
2007 Total .....	104	100.266	806,425	19.4	91.8
2008 Total .....	104	100.755	806,208	19.6	<sup>d</sup> 91.1
2009 Total .....	104	101.004	798,855	20.2	90.3
2010 Total .....	104	101.167	806,968	19.6	91.1
2011 Total .....	104	<sup>c</sup> 101.419	790,204	19.3	89.1
2012 Total .....	104	101.885	769,331	19.0	86.1
2013 Total .....	100	99.240	789,016	19.4	89.9
2014 Total .....	99	98.569	797,166	19.5	91.7
2015 Total .....	99	98.672	797,178	19.6	92.3
2016 Total .....	99	99.565	805,694	19.8	92.3
2017 Total .....	99	99.629	804,950	20.0	92.3
2018 Total .....	98	99.433	807,084	19.3	92.5
2019 January .....	98	99.440	73,701	20.5	99.6
February .....	98	99.440	64,715	20.5	96.8
March .....	98	99.440	65,080	19.9	88.0
April .....	98	99.595	60,581	20.4	84.5
May .....	97	98.922	67,124	20.3	90.8
June .....	97	98.922	68,805	19.5	96.6
July .....	97	98.922	72,199	17.6	98.1
August .....	97	98.922	71,911	17.9	97.7
September .....	96	98.119	66,064	18.3	93.1
October .....	96	98.119	62,033	19.4	85.0
November .....	96	98.119	64,125	20.3	90.8
December .....	96	98.119	73,074	21.6	100.1
Total .....	96	98.119	809,409	19.6	93.4
2020 January .....	96	<sup>E</sup> 98.128	74,170	21.8	<sup>E</sup> 101.6
February .....	96	<sup>E</sup> 98.128	65,950	20.7	<sup>E</sup> 96.6
March .....	96	<sup>E</sup> 98.128	63,997	20.8	<sup>E</sup> 87.7
April .....	95	<sup>E</sup> 97.116	59,170	21.4	<sup>E</sup> 83.8
May .....	95	<sup>E</sup> 97.116	64,338	21.1	<sup>E</sup> 89.1
June .....	95	<sup>E</sup> 97.116	67,205	19.1	<sup>E</sup> 96.1
July .....	95	<sup>E</sup> 97.116	69,385	16.7	<sup>E</sup> 96.0
August .....	95	<sup>E</sup> 96.515	68,982	17.3	<sup>E</sup> 95.9
September .....	94	<sup>E</sup> 96.515	65,727	19.7	<sup>E</sup> 94.6
October .....	94	<sup>E</sup> 96.555	59,362	18.9	<sup>E</sup> 82.6
November .....	94	<sup>E</sup> 96.555	61,760	20.4	<sup>E</sup> 88.8
December .....	94	<sup>E</sup> 96.555	69,871	20.3	<sup>E</sup> 97.3
Total .....	94	<sup>E</sup> 96.555	789,919	19.7	<sup>E</sup> 92.5
2021 January .....	94	<sup>E</sup> 96.438	71,832	20.5	<sup>E</sup> 100.2
February .....	94	<sup>E</sup> 96.435	62,954	19.3	<sup>E</sup> 97.1
2-Month Total .....	94	<sup>E</sup> 96.435	134,787	19.9	<sup>E</sup> 98.7
2020 2-Month Total .....	96	<sup>E</sup> 98.128	140,120	21.3	<sup>E</sup> 99.2
2019 2-Month Total .....	98	99.440	138,416	20.5	98.3

<sup>a</sup> Total of nuclear generating units holding full-power licenses, or equivalent permission to operate, at end of period. See Note 1, "Operable Nuclear Reactors," at end of section.

<sup>b</sup> At end of period.

<sup>c</sup> For the definition of "Net Summer Capacity," see Note 2, "Nuclear Capacity," at end of section. Beginning in 2011, monthly capacity values are estimated in two steps: 1) uprates and derates reported on Form EIA-860M are added to specific months; and 2) the difference between the resulting year-end capacity (from data reported on Form EIA-860M) and final capacity (reported on Form EIA-860) is allocated to the month of January.

<sup>d</sup> Beginning in 2008, capacity factor data are calculated using a new

methodology. For an explanation of the method of calculating the capacity factor, see Note 2, "Nuclear Capacity," at end of section.

E=Estimate. NA=Not available. (s)=Less than 0.05%.


Notes: • For a discussion of nuclear reactor unit coverage, see Note 1, "Operable Nuclear Reactors," at end of section. • Nuclear electricity net generation totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#nuclear> (Excel and CSV files) for all available annual data beginning in 1957 and monthly data beginning in 1973.


Sources: See end of section.

**Figure 8.2 Uranium Overview**


Production and Trade, 1949–2020



Inventories, End of Year 1981–2020



Average Prices, 1981–2020



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.  
Note: See “Uranium Oxide” in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#nuclear>.  
Source: Table 8.2.

**Table 8.2 Uranium Overview**

	Domestic Concentrate Production <sup>a</sup>	Purchased Imports <sup>b</sup>	Export <sup>b</sup> Sales	Electric Plant Purchases From Domestic Suppliers	Loaded Into U.S. Nuclear Reactors <sup>c</sup>	Inventories			Average Price	
						Domestic Suppliers	Electric Plants	Total	Purchased Imports	Domestic Purchases
Million Pounds Uranium Oxide									Dollars <sup>d</sup> per Pound Uranium Oxide	
1950 .....	0.92	5.5	0.0	NA	NA	NA	NA	NA	NA	NA
1955 .....	5.56	7.6	.0	NA	NA	NA	NA	NA	NA	NA
1960 .....	35.28	36.0	.0	NA	NA	NA	NA	NA	NA	NA
1965 .....	20.88	8.0	.0	NA	NA	NA	NA	NA	NA	NA
1970 .....	25.81	.0	4.2	NA	NA	NA	NA	NA	--	NA
1975 .....	23.20	1.4	1.0	NA	NA	NA	NA	NA	NA	NA
1980 .....	43.70	3.6	5.8	NA	NA	NA	NA	NA	NA	NA
1981 .....	38.47	6.6	4.4	32.6	NA	NA	NA	159.2	32.90	34.65
1982 .....	26.87	17.1	6.2	27.1	NA	NA	NA	174.8	27.23	38.37
1983 .....	21.16	8.2	3.3	24.2	NA	NA	NA	191.8	26.16	38.21
1984 .....	14.88	12.5	2.2	22.5	NA	25.0	160.2	185.2	21.86	32.65
1985 .....	11.31	11.7	5.3	21.7	NA	23.7	153.2	176.9	20.08	31.43
1986 .....	13.51	13.5	1.6	18.9	NA	27.0	144.1	171.1	20.07	30.01
1987 .....	12.99	15.1	1.0	20.8	NA	25.4	137.8	163.2	19.14	27.37
1988 .....	13.13	15.8	3.3	17.6	NA	19.3	125.5	144.8	19.03	26.15
1989 .....	13.84	13.1	2.1	18.4	NA	22.2	115.8	138.1	16.75	19.56
1990 .....	8.89	23.7	2.0	20.5	NA	26.4	102.7	129.1	12.55	15.70
1991 .....	7.95	16.3	3.5	26.8	34.6	20.7	98.0	118.7	15.55	13.66
1992 .....	5.65	23.3	2.8	23.4	43.0	25.2	92.1	117.3	11.34	13.45
1993 .....	3.06	21.0	3.0	15.5	45.1	24.5	81.2	105.7	10.53	13.14
1994 .....	3.35	36.6	17.7	22.7	40.4	21.5	65.4	86.9	8.95	10.30
1995 .....	6.04	41.3	9.8	22.3	51.1	13.7	58.7	72.5	10.20	11.11
1996 .....	6.32	45.4	11.5	23.7	46.2	13.9	66.1	80.0	13.15	13.81
1997 .....	5.64	43.0	17.0	19.4	48.2	40.4	65.9	106.2	11.81	12.87
1998 .....	4.70	43.7	15.1	21.6	38.2	70.7	65.8	136.5	11.19	12.31
1999 .....	4.61	47.6	8.5	21.4	58.8	68.8	58.3	127.1	10.55	11.88
2000 .....	3.98	44.9	13.6	24.3	51.5	56.5	54.8	111.3	9.84	11.45
2001 .....	2.64	46.7	11.7	27.5	52.7	48.1	55.6	103.8	9.51	10.45
2002 .....	e,E 2.34	52.7	15.4	22.7	57.2	48.7	53.5	102.1	10.05	10.35
2003 .....	e,E 2.00	53.0	13.2	21.7	62.3	39.9	45.6	85.5	10.59	10.84
2004 .....	2.28	66.1	13.2	28.2	50.1	37.5	57.7	95.2	12.25	11.91
2005 .....	2.69	65.5	20.5	27.3	58.3	29.1	64.7	93.8	14.83	13.98
2006 .....	4.11	64.8	18.7	27.9	51.7	29.1	77.5	106.6	19.31	18.54
2007 .....	4.53	54.1	14.8	18.5	45.5	31.2	81.2	112.4	34.18	33.13
2008 .....	3.90	57.1	17.2	20.4	51.3	27.0	83.0	110.0	41.30	43.43
2009 .....	3.71	58.9	23.5	17.6	49.4	26.8	84.8	111.5	41.23	44.53
2010 .....	4.23	55.3	23.1	16.2	44.3	24.7	86.5	111.3	47.01	44.88
2011 .....	3.99	54.4	16.7	19.8	50.9	22.3	89.8	112.1	54.00	53.41
2012 .....	4.15	56.2	18.0	21.5	49.5	23.3	97.6	120.9	51.44	56.51
2013 .....	4.66	57.4	18.9	23.3	42.6	21.3	113.1	134.4	48.27	52.51
2014 .....	4.89	56.5	20.0	20.5	50.5	18.7	114.0	132.7	44.03	43.99
2015 .....	3.34	64.2	25.7	19.6	47.4	14.3	121.1	135.5	42.95	43.03
2016 .....	2.92	50.7	17.2	18.8	41.7	16.7	128.0	144.6	40.45	41.64
2017 .....	2.44	42.1	14.0	14.0	45.5	17.8	123.9	141.7	37.09	38.57
2018 .....	1.65	41.5	13.9	11.1	50.4	19.3	111.2	130.5	35.73	42.98
2019 .....	.17	42.9	11.7	W	43.2	<sup>R</sup> 17.5	<sup>R</sup> 113.1	<sup>R</sup> 130.7	34.77	W
2020 .....	W	<sup>R</sup> 39.6	<sup>R</sup> 9.9	<sup>R</sup> 10.5	<sup>P</sup> 48.6	<sup>P</sup> 16.0	<sup>P</sup> 107.2	<sup>P</sup> 123.1	<sup>R</sup> 33.79	<sup>R</sup> 35.92

<sup>a</sup> See "Uranium Concentrate" in Glossary.

<sup>b</sup> Import quantities through 1970 are reported for fiscal years. Prior to 1968, the Atomic Energy Commission was the sole purchaser of all imported uranium oxide. Trade data prior to 1982 were for transactions conducted by uranium suppliers only. For 1982 forward, transactions by uranium buyers (consumers) have been included. Buyer imports and exports prior to 1982 are believed to be small.

<sup>c</sup> Does not include any fuel rods removed from reactors and later reloaded.

<sup>d</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>e</sup> Value has been rounded to avoid disclosure of individual company data.

R=Revised. P=Preliminary. E=Estimate. NA=Not available. W=Value withheld to avoid disclosure of individual company data. — =Not applicable.

Note: See "Uranium Oxide" in Glossary.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly#nuclear> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **1949–1966:** U.S. Department of Energy, Grand Junction Office, *Statistical Data of the Uranium Industry*, Report No. GJO-100, annual reports.

• **1967–2002:** U.S. Energy Information Administration (EIA), *Uranium Industry Annual*, annual reports. • **2003–2017:** EIA, "Domestic Uranium Production Report," annual reports; and EIA, "Uranium Marketing Annual Report," annual reports. • **2018 forward:** EIA, "2020 Domestic Uranium Production Report" (May 2021), Table 3; and EIA, "2020 Uranium Marketing Annual Report" (May 2021), Tables 5, 18, 19, 21, and 22.

**Note 1. Operable Nuclear Reactors.** A reactor is defined as operable when it possesses a full-power license from the Nuclear Regulatory Commission or its predecessor, the Atomic Energy Commission, or equivalent permission to operate, at the end of the year or month shown. The definition includes units retaining full-power licenses during long, non-routine shutdowns that for a time rendered them unable to generate electricity.

**Note 2. Nuclear Capacity.** Nuclear generating units may have more than one type of net capacity rating, including the following:

(a) Net Summer Capacity—The steady hourly output that generating equipment is expected to supply to system load, exclusive of auxiliary power, as demonstrated by test at the time of summer peak demand. Auxiliary power of a typical nuclear power plant is about 5% of gross generation.

(b) Net Design Capacity or Net Design Electrical Rating (DER)—The nominal net electrical output of a unit, specified by the utility and used for plant design.

Through 2007, the monthly capacity factors are calculated as the monthly nuclear electricity net generation divided by the maximum possible nuclear electricity net generation for that month. The maximum possible nuclear electricity net generation is the number of hours in the month (assuming 24-hour days, with no adjustment for changes to or from Daylight Savings Time) multiplied by the net summer capacity of operable nuclear generating units at the end of the month. That fraction is then multiplied by 100 to obtain a percentage. Annual capacity factors are calculated as the annual nuclear electricity net generation divided by the annual maximum possible nuclear electricity net generation (the sum of the monthly values for maximum possible nuclear electricity net generation). For the methodology used to calculate capacity factors beginning in 2008, see U.S. Energy Information Administration, *Electric Power Monthly*, Appendix C notes on “Average Capacity Factors.”

### Table 8.1 Sources

#### *Total Operable Units and Net Summer Capacity of Operable Units*

1957–1982: Compiled from various sources, primarily U.S. Department of Energy, Office of Nuclear Reactor Programs, “U.S. Central Station Nuclear Electric Generating Units: Significant Milestones.”

1983 forward: U.S. Energy Information Administration (EIA), Form EIA-860, “Annual Electric Generator Report,” and predecessor forms; Form EIA-860M, “Monthly Update to the Annual Electric Generator Report”; and monthly updates as appropriate. See <https://www.eia.gov/nuclear/generation/index.html> for a list of operable units.

#### *Nuclear Electricity Net Generation and Nuclear Share of Electricity Net Generation*

1957 forward: Table 7.2a.

#### *Capacity Factor*

1973–2007: Calculated by EIA using the method described above in Note 2.


2008 forward: EIA, Form EIA-860, “Annual Electric Generator Report”; Form EIA-860M, “Monthly Update to the Annual Electric Generator Report”; and Form EIA-923, “Power Plant Operations Report.”

## 9. Energy Prices

---

**Figure 9.1 Petroleum Prices**


Crude Oil Prices, 1949–2020



Composite Refiner Acquisition Cost, Monthly



Refiner Prices to End Users: Select Products, February 2021



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.

Sources: Tables 9.1, 9.5 and 9.7.

**Table 9.1 Crude Oil Price Summary**  
(Dollars<sup>a</sup> per Barrel)

	Domestic First Purchase Price <sup>c</sup>	F.O.B. Cost of Imports <sup>d</sup>	Landed Cost of Imports <sup>e</sup>	Refiner Acquisition Cost <sup>b</sup>		
				Domestic	Imported	Composite
1950 Average .....	2.51	NA	NA	NA	NA	NA
1955 Average .....	2.77	NA	NA	NA	NA	NA
1960 Average .....	2.88	NA	NA	NA	NA	NA
1965 Average .....	2.86	NA	NA	NA	NA	NA
1970 Average .....	3.18	NA	NA	<sup>E</sup> 3.46	<sup>E</sup> 2.96	<sup>E</sup> 3.40
1975 Average .....	7.67	11.18	12.70	8.39	13.93	10.38
1977 Average .....	8.57	13.24	14.36	9.55	14.53	11.96
1982 Average .....	28.52	32.02	33.18	31.22	33.55	31.87
1987 Average .....	15.40	16.69	17.65	17.76	18.13	17.90
1992 Average .....	15.99	16.77	17.75	18.63	18.20	18.43
1997 Average .....	17.23	16.94	18.11	19.61	18.53	19.04
1998 Average .....	10.87	10.76	11.84	13.18	12.04	12.52
1999 Average .....	15.56	16.47	17.23	17.90	17.26	17.51
2000 Average .....	26.72	26.27	27.53	29.11	27.70	28.26
2005 Average .....	50.28	47.60	49.29	52.94	48.86	50.24
2006 Average .....	59.69	57.03	59.11	62.62	59.02	60.24
2007 Average .....	66.52	66.36	67.97	69.65	67.04	67.94
2008 Average .....	94.04	90.32	93.33	98.47	92.77	94.74
2009 Average .....	56.35	57.78	60.23	59.49	59.17	59.29
2010 Average .....	74.71	74.19	76.50	78.01	75.86	76.69
2011 Average .....	95.73	101.66	102.92	100.71	102.63	101.87
2012 Average .....	94.52	99.78	101.00	100.72	101.09	100.93
2013 Average .....	95.99	96.56	96.99	102.91	98.11	100.49
2014 Average .....	87.39	85.65	88.16	94.05	89.56	92.02
2015 Average .....	44.39	41.91	45.38	49.94	46.38	48.39
2016 Average .....	38.29	36.37	38.56	42.41	38.75	40.66
2017 Average .....	48.05	45.58	48.50	52.05	49.12	50.68
2018 Average .....	61.40	56.31	58.89	67.05	60.95	64.38
<b>2019</b> January .....	48.00	48.70	49.25	54.06	49.71	52.29
February .....	52.60	54.23	56.17	58.24	56.66	57.62
March .....	57.46	57.54	59.48	61.97	61.14	61.64
April .....	63.00	61.31	63.62	67.21	65.42	66.51
May .....	59.73	60.74	63.70	65.17	65.03	65.11
June .....	54.34	54.56	57.43	59.81	58.16	59.16
July .....	56.47	54.51	57.00	61.47	59.18	60.53
August .....	53.63	51.98	54.91	57.88	55.41	56.90
September .....	55.14	52.68	55.06	59.41	57.31	58.60
October .....	53.14	50.40	53.74	56.69	54.44	55.85
November .....	54.96	51.87	54.48	59.42	55.27	57.88
December .....	58.41	51.57	53.92	62.23	56.85	60.27
<b>Total</b> .....	<b>55.59</b>	<b>54.27</b>	<b>56.60</b>	<b>60.31</b>	<b>57.94</b>	<b>59.38</b>
<b>2020</b> January .....	56.86	46.98	51.03	60.36	53.96	57.94
February .....	50.03	41.65	44.57	53.98	47.42	51.37
March .....	31.80	24.10	26.77	34.98	28.50	32.55
April .....	15.99	13.91	17.18	21.25	16.74	19.41
May .....	18.09	19.28	22.73	24.97	22.56	23.84
June .....	33.53	32.41	36.05	37.25	36.14	36.80
July .....	37.55	35.35	38.91	40.55	39.33	40.07
August .....	39.42	35.99	40.15	42.82	41.72	42.41
September .....	36.89	35.45	37.96	40.42	38.76	39.83
October .....	36.46	34.35	37.11	40.06	37.80	39.21
November .....	38.23	36.22	39.25	41.56	39.12	40.68
December .....	43.97	<sup>R</sup> 41.86	<sup>R</sup> 44.78	46.69	45.30	46.19
<b>Total</b> .....	<b>37.07</b>	<sup>R</sup> <b>33.15</b>	<sup>R</sup> <b>36.31</b>	<b>41.31</b>	<b>37.42</b>	<b>39.80</b>
<b>2021</b> January .....	<sup>R</sup> 49.73	<sup>R</sup> 46.00	<sup>R</sup> 48.47	<sup>R</sup> 52.45	<sup>R</sup> 49.52	51.36
February .....	<sup>R</sup> 56.72	<sup>R</sup> 51.57	<sup>R</sup> 53.39	<sup>R</sup> 60.08	<sup>R</sup> 55.57	<sup>R</sup> 58.31
March .....	NA	NA	NA	<sup>E</sup> 64.27	<sup>E</sup> 58.97	<sup>E</sup> 62.20

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 1, "Crude Oil Refinery Acquisition Costs," at end of section.

<sup>c</sup> See Note 2, "Crude Oil Domestic First Purchase Prices," at end of section.

<sup>d</sup> See Note 3, "Crude Oil F.O.B. Costs," at end of section.

<sup>e</sup> See Note 4, "Crude Oil Landed Costs," at end of section.

<sup>R</sup>=Revised. <sup>NA</sup>=Not available. <sup>E</sup>=Estimate.

Notes: • Domestic first purchase prices and refinery acquisition costs for the current two months are preliminary. F.O.B. and landed costs for the current three months are preliminary. • Through 1980, F.O.B. and landed costs reflect the

period of reporting; beginning in 1981, they reflect the period of loading. • Annual averages are the averages of the monthly prices, weighted by volume. • Geographic coverage is the 50 states, the District of Columbia, Puerto Rico, the Virgin Islands, and all U.S. Territories and Possessions.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 9.2 F.O.B. Costs of Crude Oil Imports From Selected Countries**

(Dollars<sup>a</sup> per Barrel)

	Selected Countries							Persian Gulf Nations <sup>b</sup>	Total OPEC <sup>c</sup>	Total Non-OPEC <sup>c</sup>
	Angola	Colombia	Mexico	Nigeria	Saudi Arabia	United Kingdom	Venezuela			
1973 Average <sup>d</sup>	W	W	—	7.81	3.25	—	5.39	3.68	5.43	4.80
1975 Average	10.97	—	11.44	11.82	10.87	—	11.04	10.88	11.34	10.62
1980 Average	33.45	W	31.06	35.93	28.17	34.36	24.81	28.92	32.21	32.85
1985 Average	26.30	—	25.33	28.04	22.04	27.64	23.64	23.31	25.67	25.96
1990 Average	20.23	20.75	19.26	22.46	20.36	23.43	19.55	18.54	20.40	20.32
1995 Average	16.58	16.73	15.64	17.40	W	16.94	13.86	W	15.36	16.02
2000 Average	27.90	29.04	25.39	28.70	24.62	27.21	24.45	24.72	25.56	26.77
2005 Average	52.48	51.89	43.00	55.95	47.96	54.48	46.39	47.21	49.60	45.79
2006 Average	62.23	59.77	52.91	65.69	56.09	66.03	55.80	56.02	59.18	55.35
2007 Average	67.80	67.93	61.35	76.64	W	69.96	64.10	69.93	69.58	62.69
2008 Average	95.66	91.17	84.61	102.06	93.03	96.33	88.06	91.44	93.15	87.15
2009 Average	57.07	57.90	56.47	64.61	57.87	65.63	55.58	59.53	58.53	57.16
2010 Average	78.18	72.56	72.46	80.83	76.44	W	70.30	75.65	75.23	73.24
2011 Average	111.82	100.21	100.90	115.35	107.08	—	97.23	106.47	105.34	98.49
2012 Average	111.23	106.43	101.84	114.51	106.65	—	100.15	105.45	104.39	95.71
2013 Average	107.71	101.24	98.40	110.06	101.16	W	97.52	100.62	100.57	93.67
2014 Average	W	80.75	86.55	W	95.60	—	84.51	94.03	89.76	82.95
2015 Average	W	47.52	44.90	W	47.53	—	40.73	46.95	43.25	41.19
2016 Average	42.68	35.28	36.22	46.20	39.30	W	34.71	38.76	38.51	34.81
2017 Average	W	48.34	46.66	54.77	51.30	W	45.60	50.16	49.55	43.30
2018 Average	74.44	62.51	62.75	71.41	68.23	71.65	61.25	66.55	65.61	51.41
2019 January	—	53.27	54.81	W	W	W	48.25	58.54	54.94	46.13
February	—	56.59	58.52	W	W	W	W	62.58	63.09	51.63
March	—	61.28	60.66	W	67.34	W	—	65.62	65.95	55.66
April	—	67.09	63.13	W	70.60	70.45	—	68.89	70.54	59.56
May	W	65.40	62.16	70.81	W	69.74	—	65.97	67.80	59.17
June	W	61.09	58.75	W	W	W	—	62.67	63.28	51.82
July	W	W	58.93	W	W	W	—	62.08	63.82	52.32
August	—	59.37	50.72	W	59.24	W	—	57.90	59.51	50.47
September	—	W	56.73	W	60.27	W	—	58.79	59.66	51.05
October	—	W	51.74	W	W	W	—	56.42	58.30	48.81
November	—	59.42	51.24	W	60.69	W	—	58.47	60.86	49.22
December	—	58.95	55.23	—	63.59	W	—	61.63	61.72	50.26
Average	66.97	60.61	56.72	67.21	63.48	65.20	48.57	61.43	62.11	52.36
2020 January	—	56.90	53.70	W	49.26	W	—	50.36	53.02	46.47
February	—	W	47.74	W	W	W	—	W	53.00	40.64
March	W	27.34	28.59	W	W	W	—	24.18	28.28	23.56
April	W	19.88	12.25	W	21.44	—	—	21.44	22.79	11.81
May	—	W	22.92	W	W	W	—	29.19	30.80	18.09
June	—	33.32	34.36	W	W	W	—	40.84	41.40	31.38
July	—	W	37.95	W	42.86	—	—	40.60	41.48	34.64
August	—	40.34	40.16	W	W	—	—	W	44.02	35.77
September	—	37.36	38.42	W	W	—	—	W	41.19	35.17
October	W	W	37.12	W	—	—	—	—	40.10	34.01
November	—	W	39.55	—	—	W	—	W	W	36.14
December	W	W	45.09	W	<sup>R</sup> W	—	—	W	<sup>R</sup> 52.06	40.99
Average	W	36.03	36.00	W	<sup>R</sup> 33.55	43.39	—	<sup>R</sup> 34.86	<sup>R</sup> 37.69	32.74
2021 January	—	W	<sup>R</sup> 50.55	—	52.71	—	—	52.52	52.90	<sup>R</sup> 45.33
February	—	W	55.85	W	W	—	—	56.91	59.61	50.73

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, United Arab Emirates, and the Neutral Zone (between Kuwait and Saudi Arabia).

<sup>c</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary for exact years of each country's membership. On this table, "Total OPEC" for all years includes Algeria, Iran, Iraq, Kuwait, Libya, Nigeria, Qatar, Saudi Arabia, United Arab Emirates, and Venezuela; Angola is included in "Total OPEC" 2007 forward; Gabon is included in "Total OPEC" 1974–1995 and July 2016 forward; Ecuador is included in "Total OPEC" 1973–1992 and 2008 forward; Indonesia is included in "Total OPEC" 1973–2008 and 2016.

<sup>d</sup> Based on October, November, and December data only.

<sup>R</sup>=Revised. —=No data reported. W=Value withheld to avoid disclosure of individual company data.

Notes: • The Free on Board (F.O.B.) cost at the country of origin excludes all

costs related to insurance and transportation. See "F.O.B. (Free on Board)" in Glossary, and Note 3, "Crude Oil F.O.B. Costs," at end of section. • Values for the current two months are preliminary. • Through 1980, prices reflect the period of reporting; beginning in 1981, prices reflect the period of loading. • Annual averages are averages of the monthly prices, including prices not published, weighted by volume. • Cargoes that are purchased on a "netback" basis, or under similar contractual arrangements whereby the actual purchase price is not established at the time the crude oil is acquired for importation into the United States, are not included in the published data until the actual prices have been determined and reported. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.



**Table 9.3 Landed Costs of Crude Oil Imports From Selected Countries**  
(Dollars<sup>a</sup> per Barrel)

	Selected Countries								Persian Gulf Nations <sup>b</sup>	Total OPEC <sup>c</sup>	Total Non-OPEC <sup>c</sup>
	Angola	Canada	Colombia	Mexico	Nigeria	Saudi Arabia	United Kingdom	Venezuela			
1973 Average <sup>d</sup>	W	5.33	W	—	9.08	5.37	—	5.99	5.91	6.85	5.64
1975 Average	11.81	12.84	—	12.61	12.70	12.50	—	12.36	12.64	12.70	12.70
1980 Average	34.76	30.11	W	31.77	37.15	29.80	35.68	25.92	30.59	33.56	33.99
1985 Average	27.39	25.71	—	25.63	28.96	24.72	28.36	24.43	25.50	26.86	26.53
1990 Average	21.51	20.48	22.34	19.64	23.33	21.82	22.65	20.31	20.55	21.23	20.98
1995 Average	17.66	16.65	17.45	16.19	18.25	16.84	17.91	14.81	16.78	16.61	16.95
2000 Average	29.57	26.69	29.68	26.03	30.04	26.58	29.26	26.05	26.77	27.29	27.80
2005 Average	54.31	44.73	53.42	43.47	57.55	50.31	55.28	47.87	49.68	51.36	47.31
2006 Average	64.85	53.90	62.13	53.76	68.26	59.19	67.44	57.37	58.92	61.21	57.14
2007 Average	71.27	60.38	70.91	62.31	78.01	70.78	72.47	66.13	69.83	71.14	63.96
2008 Average	98.18	90.00	93.43	85.97	104.83	94.75	96.95	90.76	93.59	95.49	90.59
2009 Average	61.32	57.60	58.50	57.35	68.01	62.14	63.87	57.78	62.15	61.90	58.58
2010 Average	80.61	72.80	74.25	72.86	83.14	79.29	80.29	72.43	78.60	78.28	74.68
2011 Average	114.05	89.92	102.57	101.21	116.43	108.83	118.45	100.14	108.01	107.84	98.64
2012 Average	114.95	84.24	107.07	102.45	116.88	108.15	W	101.58	107.74	107.56	95.05
2013 Average	110.81	84.41	103.00	99.06	112.87	102.60	111.23	99.34	102.53	102.98	91.99
2014 Average	99.25	81.30	88.29	87.48	102.16	94.91	W	86.88	95.30	93.10	84.67
2015 Average	51.73	41.99	49.53	45.51	54.70	49.78	W	42.87	49.43	47.44	44.09
2016 Average	44.65	36.27	38.86	36.64	48.11	42.14	W	35.50	41.20	40.54	37.09
2017 Average	54.17	44.93	50.60	47.73	56.48	52.56	56.11	47.02	51.42	51.26	46.67
2018 Average	73.42	48.34	66.75	63.48	71.93	69.40	73.28	62.46	67.55	67.22	54.27
2019 January	—	40.33	56.26	56.12	W	61.69	W	51.68	59.80	57.34	45.44
February	—	50.48	59.69	59.72	W	66.37	W	52.72	64.07	62.76	53.82
March	—	54.61	64.65	61.82	W	67.50	W	55.25	65.81	65.30	57.85
April	W	59.01	69.08	64.18	75.99	69.74	73.00	—	68.83	69.89	62.21
May	72.84	58.49	68.17	62.81	72.66	67.93	71.30	W	67.05	68.82	62.19
June	W	50.84	65.87	59.32	69.37	65.06	65.41	—	63.71	65.04	55.30
July	W	51.14	64.10	59.50	67.57	64.14	64.63	—	63.83	64.76	55.02
August	—	50.68	59.22	51.59	65.76	61.59	W	—	60.87	61.75	52.99
September	W	50.64	58.77	57.73	66.34	61.59	64.40	—	61.03	61.58	53.27
October	W	49.64	57.88	53.03	65.73	62.36	63.06	—	59.89	60.99	51.93
November	W	49.20	60.91	52.57	69.20	64.85	W	—	62.06	62.97	51.97
December	—	48.36	62.66	56.78	W	65.83	W	—	63.23	63.52	52.13
Average	68.58	51.10	62.83	57.96	68.78	64.86	66.65	52.36	63.27	63.41	54.65
2020 January	—	45.70	62.93	55.93	W	53.68	W	—	55.30	57.36	49.70
February	—	39.83	54.16	49.62	62.07	52.48	W	—	52.65	54.24	42.80
March	W	23.47	35.15	29.42	W	23.94	W	—	27.04	29.04	25.97
April	30.93	13.34	23.24	13.73	W	22.33	W	—	22.78	23.66	14.91
May	W	17.45	28.61	24.35	W	28.84	W	—	29.99	30.70	20.75
June	—	34.85	33.13	35.04	W	39.88	W	—	40.56	41.07	35.20
July	—	37.69	37.64	38.72	W	43.68	W	—	42.74	43.46	38.38
August	—	38.89	41.71	40.88	W	43.83	—	—	42.75	43.04	39.86
September	W	35.66	38.27	39.01	W	43.13	W	—	41.83	42.13	37.39
October	W	35.73	38.29	37.53	W	44.98	W	—	43.49	42.11	36.68
November	W	36.98	43.35	40.06	W	W	48.92	—	43.86	45.41	38.83
December	W	41.59	46.62	45.76	53.81	R 54.19	51.22	—	R 51.59	R 52.89	43.75
Average	37.41	33.82	41.16	37.18	47.08	R 35.37	44.36	—	R 37.58	R 38.83	35.91
2021 January	W	R 46.06	W	R 51.28	W	R 54.02	—	—	R 53.80	R 54.46	R 47.86
February	—	50.41	59.09	56.56	W	W	W	—	58.88	60.40	52.71

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, United Arab Emirates, and the Neutral Zone (between Kuwait and Saudi Arabia).

<sup>c</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary for exact years of each country's membership. On this table, "Total OPEC" for all years includes Algeria, Iran, Iraq, Kuwait, Libya, Nigeria, Qatar, Saudi Arabia, United Arab Emirates, and Venezuela; Angola is included in "Total OPEC" 2007 forward; Gabon is included in "Total OPEC" 1974–1995 and July 2016 forward; Ecuador is included in "Total OPEC" 1973–1992 and 2008 forward; Indonesia is included in "Total OPEC" 1973–2008 and 2016.

<sup>d</sup> Based on October, November, and December data only.

R=Revised. —=No data reported. W=Value withheld to avoid disclosure of individual company data.

Notes: • See "Landed Costs" in Glossary, and Note 4, "Crude Oil Landed Costs," at end of section. • Values for the current two months are preliminary. • Through 1980, prices reflect the period of reporting; beginning in 1981, prices

reflect the period of loading. • Annual averages are averages of the monthly prices, including prices not published, weighted by volume. • Cargoes that are purchased on a "netback" basis, or under similar contractual arrangements whereby the actual purchase price is not established at the time the crude oil is acquired for importation into the United States, are not included in the published data until the actual prices have been determined and reported. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: • **October 1973–September 1977:** Federal Energy Administration, Form FEA-F701-M-0, "Transfer Pricing Report." • **October 1977–December 1977:** U.S. Energy Information Administration (EIA), Form FEA-F701-M-0, "Transfer Pricing Report." • **1978–2007:** EIA, *Petroleum Marketing Annual 2008*, Table 22. • **2008 forward:** EIA, *Petroleum Marketing Monthly*, May 2021, Table 22.

**Table 9.4 Retail Motor Gasoline and On-Highway Diesel Fuel Prices**

(Dollars<sup>a</sup> per Gallon, Including Taxes)

	Platt's / Bureau of Labor Statistics Data				U.S. Energy Information Administration Data			
	Motor Gasoline by Grade				Regular Motor Gasoline by Area Type			On-Highway Diesel Fuel
	Leaded Regular	Unleaded Regular	Unleaded Premium <sup>b</sup>	All Grades <sup>c</sup>	Conventional Gasoline Areas <sup>d</sup>	Reformulated Gasoline Areas <sup>e</sup>	All Areas	
1950 Average .....	0.268	NA	NA	NA	--	--	--	--
1955 Average .....	.291	NA	NA	NA	--	--	--	--
1960 Average .....	.311	NA	NA	NA	--	--	--	--
1965 Average .....	.312	NA	NA	NA	--	--	--	--
1970 Average .....	.357	NA	NA	NA	--	--	--	--
1975 Average .....	.567	NA	NA	NA	--	--	--	--
1980 Average .....	1.191	1.245	NA	1.221	--	--	--	--
1985 Average .....	1.115	1.202	1.340	1.196	--	--	--	--
1990 Average .....	1.149	1.164	1.349	1.217	NA	NA	NA	NA
1995 Average .....	--	1.147	1.336	1.205	1.103	1.163	1.111	1.109
2000 Average .....	--	1.510	1.693	1.563	1.462	1.543	1.484	1.491
2005 Average .....	--	2.295	2.491	2.338	2.240	2.335	2.270	2.402
2006 Average .....	--	2.589	2.805	2.635	2.533	2.654	2.572	2.705
2007 Average .....	--	2.801	3.033	2.849	2.767	2.857	2.796	2.885
2008 Average .....	--	3.266	3.519	3.317	3.213	3.314	3.246	3.803
2009 Average .....	--	2.350	2.607	2.401	2.315	2.433	2.353	2.467
2010 Average .....	--	2.788	3.047	2.836	2.742	2.864	2.782	2.992
2011 Average .....	--	3.527	3.792	3.577	3.476	3.616	3.521	3.840
2012 Average .....	--	3.644	3.922	3.695	3.552	3.757	3.618	3.968
2013 Average .....	--	3.526	3.843	3.584	3.443	3.635	3.505	3.922
2014 Average .....	--	3.367	3.713	3.425	3.299	3.481	3.358	3.825
2015 Average .....	--	2.448	2.866	2.510	2.334	2.629	2.429	2.707
2016 Average .....	--	2.142	2.610	2.204	2.070	2.296	2.143	2.304
2017 Average .....	--	2.408	2.911	2.469	2.333	2.586	2.415	2.650
2018 Average .....	--	2.735	3.270	2.794	2.631	2.904	2.719	3.178
2019 January .....	--	2.289	2.874	2.352	2.145	2.464	2.248	2.980
February .....	--	2.353	2.901	2.412	2.223	2.495	2.309	2.997
March .....	--	2.564	3.079	2.620	2.443	2.673	2.516	3.076
April .....	--	2.835	3.382	2.894	2.694	3.023	2.798	3.121
May .....	--	2.901	3.471	2.963	2.731	3.136	2.859	3.161
June .....	--	2.752	3.328	2.814	2.601	2.963	2.716	3.089
July .....	--	2.776	3.327	2.836	2.640	2.954	2.740	3.045
August .....	--	2.655	3.222	2.716	2.521	2.836	2.621	3.005
September .....	--	2.630	3.214	2.694	2.489	2.814	2.592	3.016
October .....	--	2.673	3.297	2.741	2.497	2.907	2.627	3.053
November .....	--	2.620	3.254	2.687	2.480	2.853	2.598	3.069
December .....	--	2.587	3.190	2.652	2.469	2.744	2.555	3.055
Average .....	--	2.636	3.212	2.698	2.501	2.827	2.604	3.056
2020 January .....	--	2.567	3.157	2.631	2.459	2.740	2.548	3.048
February .....	--	2.465	3.071	2.530	2.348	2.645	2.442	2.910
March .....	--	2.267	2.893	2.334	2.126	2.468	2.234	2.729
April .....	--	1.876	2.527	1.946	1.721	2.096	1.841	2.493
May .....	--	1.879	2.490	1.946	1.769	2.084	1.870	2.392
June .....	--	2.076	2.673	2.141	1.998	2.263	2.082	2.408
July .....	--	2.176	2.783	2.243	2.099	2.365	2.183	2.434
August .....	--	2.177	2.795	2.245	2.093	2.374	2.182	2.429
September .....	--	2.193	2.810	2.260	2.095	2.375	2.183	2.414
October .....	--	2.159	2.782	2.228	2.073	2.344	2.158	2.389
November .....	--	2.090	2.727	2.159	2.015	2.312	2.108	2.432
December .....	--	2.168	2.778	2.235	2.105	2.387	2.195	2.585
Average .....	--	2.174	2.791	2.242	2.074	2.370	2.168	2.551
2021 January .....	--	2.326	2.921	2.391	2.244	2.527	2.334	2.681
February .....	--	2.496	3.073	2.559	2.412	2.694	2.501	2.847
March .....	--	2.791	3.386	2.856	2.725	2.997	2.810	3.152
April .....	--	2.839	3.455	2.907	2.771	3.048	2.858	3.130

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> The 1981 average (available in Web file) is based on September through December data only.

<sup>c</sup> Also includes grades of motor gasoline not shown separately.

<sup>d</sup> Any area that does not require the sale of reformulated gasoline.

<sup>e</sup> "Reformulated Gasoline Areas" are ozone nonattainment areas designated by the U.S. Environmental Protection Agency that require the use of reformulated gasoline (RFG). Areas are reclassified each time a shift in or out of an RFG program occurs due to federal or state regulations.

NA=Not available. --=Not applicable.

Notes: • See Note 5, "Motor Gasoline Prices," at end of section. • See "Motor Gasoline Grades," "Motor Gasoline, Conventional," "Motor Gasoline, Oxygenated," and "Motor Gasoline, Reformulated" in Glossary. • Geographic coverage: for columns 1–4, current coverage is 85 urban areas; for columns 5–7, coverage is the 50 states and the District of Columbia; for column 8, coverage is the 48 contiguous

states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **Motor Gasoline by Grade, Monthly Data: October 1973 forward**—U.S. Department of Labor, Bureau of Labor Statistics (BLS), *U.S. City Average Gasoline Prices*. • **Motor Gasoline by Grade, Annual Data: 1949–1973**—Platt's *Oil Price Handbook and Oilmanac*, 1974, 51st Edition. **1974 forward**—calculated by the U.S. Energy Information Administration (EIA) as simple averages of the BLS monthly data. • **Regular Motor Gasoline by Area Type:** EIA, calculated as simple averages of weighted weekly estimates from "Weekly U.S. Retail Gasoline Prices, Regular Grade." • **On-Highway Diesel Fuel:** EIA, calculated as simple averages of weighted weekly estimates from "Weekly Retail On-Highway Diesel Prices."

**Table 9.5 Refiner Prices of Residual Fuel Oil**

(Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Residual Fuel Oil Sulfur Content Less Than or Equal to 1%		Residual Fuel Oil Sulfur Content Greater Than 1%		Average	
	Sales for Resale	Sales to End Users	Sales for Resale	Sales to End Users	Sales for Resale	Sales to End Users
<b>1978 Average</b> .....	<b>0.293</b>	<b>0.314</b>	<b>0.245</b>	<b>0.275</b>	<b>0.263</b>	<b>0.298</b>
<b>1980 Average</b> .....	<b>.608</b>	<b>.675</b>	<b>.479</b>	<b>.523</b>	<b>.528</b>	<b>.607</b>
<b>1985 Average</b> .....	<b>.610</b>	<b>.644</b>	<b>.560</b>	<b>.582</b>	<b>.577</b>	<b>.610</b>
<b>1990 Average</b> .....	<b>.472</b>	<b>.505</b>	<b>.372</b>	<b>.400</b>	<b>.413</b>	<b>.444</b>
<b>1995 Average</b> .....	<b>.383</b>	<b>.436</b>	<b>.338</b>	<b>.377</b>	<b>.363</b>	<b>.392</b>
<b>2000 Average</b> .....	<b>.627</b>	<b>.708</b>	<b>.512</b>	<b>.566</b>	<b>.566</b>	<b>.602</b>
<b>2005 Average</b> .....	<b>1.115</b>	<b>1.168</b>	<b>.842</b>	<b>.974</b>	<b>.971</b>	<b>1.048</b>
<b>2006 Average</b> .....	<b>1.202</b>	<b>1.342</b>	<b>1.085</b>	<b>1.173</b>	<b>1.136</b>	<b>1.218</b>
<b>2007 Average</b> .....	<b>1.406</b>	<b>1.436</b>	<b>1.314</b>	<b>1.350</b>	<b>1.350</b>	<b>1.374</b>
<b>2008 Average</b> .....	<b>1.918</b>	<b>2.144</b>	<b>1.843</b>	<b>1.889</b>	<b>1.866</b>	<b>1.964</b>
<b>2009 Average</b> .....	<b>1.337</b>	<b>1.413</b>	<b>1.344</b>	<b>1.306</b>	<b>1.342</b>	<b>1.341</b>
<b>2010 Average</b> .....	<b>1.756</b>	<b>1.920</b>	<b>1.679</b>	<b>1.619</b>	<b>1.697</b>	<b>1.713</b>
<b>2011 Average</b> .....	<b>2.389</b>	<b>2.736</b>	<b>2.316</b>	<b>2.257</b>	<b>2.336</b>	<b>2.401</b>
<b>2012 Average</b> .....	<b>2.548</b>	<b>3.025</b>	<b>2.429</b>	<b>2.433</b>	<b>2.457</b>	<b>2.592</b>
<b>2013 Average</b> .....	<b>2.363</b>	<b>2.883</b>	<b>2.249</b>	<b>2.353</b>	<b>2.278</b>	<b>2.482</b>
<b>2014 Average</b> .....	<b>2.153</b>	<b>2.694</b>	<b>1.996</b>	<b>2.221</b>	<b>2.044</b>	<b>2.325</b>
<b>2015 Average</b> .....	<b>.971</b>	<b>1.529</b>	<b>.999</b>	<b>1.227</b>	<b>.996</b>	<b>1.285</b>
<b>2016 Average</b> .....	<b>.736</b>	<b>1.138</b>	<b>.746</b>	<b>.897</b>	<b>.745</b>	<b>.945</b>
<b>2017 Average</b> .....	<b>1.112</b>	<b>W</b>	<b>1.117</b>	<b>1.237</b>	<b>1.116</b>	<b>1.287</b>
<b>2018 Average</b> .....	<b>1.397</b>	<b>W</b>	<b>1.466</b>	<b>1.587</b>	<b>1.463</b>	<b>1.662</b>
<b>2019 January</b> .....	<b>1.626</b>	<b>W</b>	<b>1.326</b>	<b>1.417</b>	<b>1.357</b>	<b>1.425</b>
February .....	<b>1.808</b>	<b>W</b>	<b>1.458</b>	<b>1.553</b>	<b>1.508</b>	<b>1.568</b>
March .....	<b>W</b>	<b>W</b>	<b>1.542</b>	<b>1.606</b>	<b>1.581</b>	<b>1.639</b>
April .....	<b>W</b>	<b>W</b>	<b>1.549</b>	<b>1.648</b>	<b>1.577</b>	<b>1.685</b>
May .....	<b>W</b>	<b>W</b>	<b>1.502</b>	<b>1.607</b>	<b>1.505</b>	<b>1.635</b>
June .....	<b>W</b>	<b>W</b>	<b>1.367</b>	<b>1.527</b>	<b>1.372</b>	<b>1.601</b>
July .....	<b>1.455</b>	<b>W</b>	<b>1.492</b>	<b>1.572</b>	<b>1.489</b>	<b>1.625</b>
August .....	<b>1.331</b>	<b>W</b>	<b>1.235</b>	<b>1.345</b>	<b>1.247</b>	<b>1.466</b>
September .....	<b>W</b>	<b>W</b>	<b>1.325</b>	<b>1.511</b>	<b>1.337</b>	<b>1.560</b>
October .....	<b>1.535</b>	<b>W</b>	<b>1.188</b>	<b>1.393</b>	<b>1.263</b>	<b>1.543</b>
November .....	<b>1.681</b>	<b>W</b>	<b>1.220</b>	<b>1.364</b>	<b>1.353</b>	<b>1.594</b>
December .....	<b>1.758</b>	<b>W</b>	<b>1.460</b>	<b>1.543</b>	<b>1.597</b>	<b>1.745</b>
<b>Average</b> .....	<b>1.649</b>	<b>W</b>	<b>1.391</b>	<b>1.510</b>	<b>1.428</b>	<b>1.584</b>
<b>2020 January</b> .....	<b>1.788</b>	<b>W</b>	<b>1.526</b>	<b>1.634</b>	<b>1.675</b>	<b>1.939</b>
February .....	<b>1.673</b>	<b>W</b>	<b>1.336</b>	<b>1.557</b>	<b>1.540</b>	<b>1.735</b>
March .....	<b>1.188</b>	<b>W</b>	<b>.993</b>	<b>1.146</b>	<b>1.121</b>	<b>1.371</b>
April .....	<b>.796</b>	<b>W</b>	<b>.639</b>	<b>.942</b>	<b>.733</b>	<b>.976</b>
May .....	<b>.792</b>	<b>W</b>	<b>NA</b>	<b>.727</b>	<b>.775</b>	<b>.817</b>
June .....	<b>1.018</b>	<b>W</b>	<b>1.013</b>	<b>.894</b>	<b>1.017</b>	<b>.949</b>
July .....	<b>1.153</b>	<b>W</b>	<b>1.089</b>	<b>.981</b>	<b>1.137</b>	<b>1.071</b>
August .....	<b>1.189</b>	<b>W</b>	<b>1.068</b>	<b>1.026</b>	<b>1.135</b>	<b>1.224</b>
September .....	<b>1.098</b>	<b>W</b>	<b>1.000</b>	<b>1.035</b>	<b>1.066</b>	<b>1.200</b>
October .....	<b>1.078</b>	<b>W</b>	<b>.996</b>	<b>1.071</b>	<b>1.041</b>	<b>1.151</b>
November .....	<b>1.164</b>	<b>W</b>	<b>1.098</b>	<b>1.068</b>	<b>1.145</b>	<b>1.145</b>
December .....	<b>1.351</b>	<b>W</b>	<b>1.266</b>	<b>1.193</b>	<b>1.320</b>	<b>1.290</b>
<b>Average</b> .....	<b>1.186</b>	<b>W</b>	<b>1.066</b>	<b>1.090</b>	<b>1.143</b>	<b>1.246</b>
<b>2021 January</b> .....	<b>1.491</b>	<b>W</b>	<b>1.352</b>	<b>1.344</b>	<b>1.432</b>	<b>1.462</b>
February .....	<b>1.583</b>	<b>W</b>	<b>1.422</b>	<b>1.463</b>	<b>1.512</b>	<b>1.617</b>

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

NA=Not available. W=Value withheld to avoid disclosure of individual company data.

Notes: • Sales for resale are those made to purchasers other than ultimate consumers. Sales to end users are those made directly to ultimate consumers, including bulk consumers (such as agriculture, industry, and electric utilities) and commercial consumers. • Values for the current month are preliminary. • Through 1982, prices are U.S. Energy Information Administration (EIA)

estimates. See Note 6, "Historical Petroleum Prices," at end of section.

• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1978 and monthly data beginning in 1982.

Sources: • **1978–2007:** EIA, *Petroleum Marketing Annual 2007*, Table 17.

• **2008 forward:** EIA, *Petroleum Marketing Monthly*, May 2021, Table 16.

**Table 9.6 Refiner Prices of Petroleum Products for Resale**

(Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Finished Motor Gasoline <sup>b</sup>	Finished Aviation Gasoline	Kerosene- Type Jet Fuel	Kerosene	No. 2 Fuel Oil	No. 2 Diesel Fuel	Propane (Consumer Grade)
<b>1978 Average</b> .....	<b>0.434</b>	<b>0.537</b>	<b>0.386</b>	<b>0.404</b>	<b>0.369</b>	<b>0.365</b>	<b>0.237</b>
<b>1980 Average</b> .....	<b>.941</b>	<b>1.128</b>	<b>.868</b>	<b>.864</b>	<b>.803</b>	<b>.801</b>	<b>.415</b>
<b>1985 Average</b> .....	<b>.835</b>	<b>1.130</b>	<b>.794</b>	<b>.874</b>	<b>.776</b>	<b>.772</b>	<b>.398</b>
<b>1990 Average</b> .....	<b>.786</b>	<b>1.063</b>	<b>.773</b>	<b>.839</b>	<b>.697</b>	<b>.694</b>	<b>.386</b>
<b>1995 Average</b> .....	<b>.626</b>	<b>.975</b>	<b>.539</b>	<b>.580</b>	<b>.511</b>	<b>.538</b>	<b>.344</b>
<b>2000 Average</b> .....	<b>.963</b>	<b>1.330</b>	<b>.880</b>	<b>.969</b>	<b>.886</b>	<b>.898</b>	<b>.595</b>
<b>2005 Average</b> .....	<b>1.670</b>	<b>2.076</b>	<b>1.723</b>	<b>1.757</b>	<b>1.623</b>	<b>1.737</b>	<b>.933</b>
<b>2006 Average</b> .....	<b>1.969</b>	<b>2.490</b>	<b>1.961</b>	<b>2.007</b>	<b>1.834</b>	<b>2.012</b>	<b>1.031</b>
<b>2007 Average</b> .....	<b>2.182</b>	<b>2.758</b>	<b>2.171</b>	<b>2.249</b>	<b>2.072</b>	<b>2.203</b>	<b>1.194</b>
<b>2008 Average</b> .....	<b>2.586</b>	<b>3.342</b>	<b>3.020</b>	<b>2.851</b>	<b>2.745</b>	<b>2.994</b>	<b>1.437</b>
<b>2009 Average</b> .....	<b>1.767</b>	<b>2.480</b>	<b>1.719</b>	<b>1.844</b>	<b>1.657</b>	<b>1.713</b>	<b>.921</b>
<b>2010 Average</b> .....	<b>2.165</b>	<b>2.874</b>	<b>2.185</b>	<b>2.299</b>	<b>2.147</b>	<b>2.214</b>	<b>1.212</b>
<b>2011 Average</b> .....	<b>2.867</b>	<b>3.739</b>	<b>3.014</b>	<b>3.065</b>	<b>2.907</b>	<b>3.034</b>	<b>1.467</b>
<b>2012 Average</b> .....	<b>2.929</b>	<b>3.919</b>	<b>3.080</b>	<b>3.163</b>	<b>3.031</b>	<b>3.109</b>	<b>1.033</b>
<b>2013 Average</b> .....	<b>2.812</b>	<b>3.869</b>	<b>2.953</b>	<b>3.084</b>	<b>2.966</b>	<b>3.028</b>	<b>1.048</b>
<b>2014 Average</b> .....	<b>2.618</b>	<b>3.687</b>	<b>2.763</b>	<b>2.882</b>	<b>2.741</b>	<b>2.812</b>	<b>1.165</b>
<b>2015 Average</b> .....	<b>1.726</b>	<b>2.764</b>	<b>1.592</b>	<b>1.735</b>	<b>1.565</b>	<b>1.667</b>	<b>.555</b>
<b>2016 Average</b> .....	<b>1.454</b>	<b>2.404</b>	<b>1.295</b>	<b>1.383</b>	<b>1.239</b>	<b>1.378</b>	<b>.523</b>
<b>2017 Average</b> .....	<b>1.689</b>	<b>2.682</b>	<b>1.603</b>	<b>1.730</b>	<b>1.600</b>	<b>1.691</b>	<b>.800</b>
<b>2018 Average</b> .....	<b>1.980</b>	<b>3.006</b>	<b>2.073</b>	<b>2.160</b>	<b>2.002</b>	<b>2.130</b>	<b>.877</b>
<b>2019 January</b> .....	<b>1.483</b>	<b>2.394</b>	<b>1.822</b>	<b>2.021</b>	<b>1.813</b>	<b>1.789</b>	<b>.775</b>
February .....	1.624	2.527	1.925	2.111	1.907	1.950	.772
March .....	1.881	2.874	1.960	2.087	1.958	2.020	.754
April .....	2.138	3.100	2.022	2.073	1.993	2.100	.660
May .....	2.110	3.021	2.061	2.057	1.989	2.106	.595
June .....	1.909	2.841	1.879	1.914	1.824	1.874	.493
July .....	1.984	2.988	1.938	1.969	1.847	1.938	.478
August .....	1.820	2.854	1.864	1.861	1.795	1.865	.458
September .....	1.854	2.829	1.898	1.984	1.901	1.955	.477
October .....	1.871	2.857	1.931	2.003	1.926	1.984	.544
November .....	1.819	2.783	1.922	2.046	1.884	1.974	.655
December .....	1.757	2.734	1.932	2.087	1.919	1.943	.632
<b>Average</b> .....	<b>1.858</b>	<b>2.842</b>	<b>1.929</b>	<b>2.017</b>	<b>1.895</b>	<b>1.958</b>	<b>.622</b>
<b>2020 January</b> .....	<b>1.743</b>	<b>2.752</b>	<b>1.891</b>	<b>2.008</b>	<b>1.863</b>	<b>1.858</b>	<b>.557</b>
February .....	1.669	2.698	1.613	1.802	1.627	1.671	.530
March .....	1.127	2.279	1.189	1.115	1.238	1.278	.410
April .....	.645	1.590	.703	.837	.872	.908	.378
May .....	1.049	1.869	.690	.848	.795	.878	.454
June .....	1.311	2.134	1.002	1.099	1.002	1.135	.514
July .....	1.380	2.253	1.144	1.172	1.152	1.254	.507
August .....	1.389	2.219	1.162	1.250	1.179	1.275	.536
September .....	1.354	2.246	1.076	1.215	1.091	1.195	.516
October .....	1.312	2.217	1.107	1.293	1.089	1.215	.597
November .....	1.287	2.123	1.180	1.322	1.156	1.315	.630
December .....	1.394	2.289	1.353	1.585	1.341	1.475	.725
<b>Average</b> .....	<b>1.330</b>	<b>2.233</b>	<b>1.295</b>	<b>1.310</b>	<b>1.246</b>	<b>1.286</b>	<b>.535</b>
<b>2021 January</b> .....	<b>1.575</b>	<b>2.482</b>	<b>1.456</b>	<b>1.688</b>	<b>1.481</b>	<b>1.580</b>	<b>R .922</b>
February .....	1.784	2.658	1.598	1.939	1.667	1.806	1.032

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 5, "Motor Gasoline Prices," at end of section.

R=Revised.

Notes: • Sales for resale are those made to purchasers other than ultimate consumers. Sales to end users are shown in Table 9.7; they are sales made directly to ultimate consumers, including bulk consumers (such as agriculture, industry, and electric utilities) and residential and commercial consumers. • Values for the current month are preliminary. • Through 1982, prices are U.S. Energy

Information Administration (EIA) estimates. See Note 6, "Historical Petroleum Prices," at end of section. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1978 and monthly data beginning in 1982.

Sources: • **1978–2007:** EIA, *Petroleum Marketing Annual 2007*, Table 4.  
• **2008 forward:** EIA, *Petroleum Marketing Monthly*, May 2021, Table 4.

**Table 9.7 Refiner Prices of Petroleum Products to End Users**

(Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Finished Motor Gasoline <sup>b</sup>	Finished Aviation Gasoline	Kerosene- Type Jet Fuel	Kerosene	No. 2 Fuel Oil	No. 2 Diesel Fuel	Propane (Consumer Grade)
<b>1978 Average</b> .....	0.484	0.516	0.387	0.421	0.400	0.377	0.335
<b>1980 Average</b> .....	1.035	1.084	.868	.902	.788	.818	.482
<b>1985 Average</b> .....	.912	1.201	.796	1.030	.849	.789	.717
<b>1990 Average</b> .....	.883	1.120	.766	.923	.734	.725	.745
<b>1995 Average</b> .....	.765	1.005	.540	.589	.562	.560	.492
<b>2000 Average</b> .....	1.106	1.306	.899	1.123	.927	.935	.603
<b>2005 Average</b> .....	1.829	2.231	1.735	1.957	1.705	1.786	1.089
<b>2006 Average</b> .....	2.128	2.682	1.998	2.244	1.982	2.096	1.358
<b>2007 Average</b> .....	2.345	2.849	2.165	2.263	2.241	2.267	1.489
<b>2008 Average</b> .....	2.775	3.273	3.052	3.283	2.986	3.150	1.892
<b>2009 Average</b> .....	1.888	2.442	1.704	2.675	1.962	1.834	1.220
<b>2010 Average</b> .....	2.301	3.028	2.201	3.063	2.462	2.314	1.481
<b>2011 Average</b> .....	3.050	3.803	3.054	3.616	3.193	3.117	1.709
<b>2012 Average</b> .....	3.154	3.971	3.104	3.843	3.358	3.202	1.139
<b>2013 Average</b> .....	3.049	3.932	2.979	3.842	3.335	3.122	1.028
<b>2014 Average</b> .....	2.855	3.986	2.772	W	3.329	2.923	1.097
<b>2015 Average</b> .....	2.003	W	1.629	W	2.016	1.819	.481
<b>2016 Average</b> .....	1.730	W	1.319	W	1.716	1.511	.498
<b>2017 Average</b> .....	1.976	W	1.629	W	2.010	1.811	.772
<b>2018 Average</b> .....	2.303	W	2.119	3.113	2.380	2.256	.925
<b>2019 January</b> .....	1.854	W	1.827	W	2.195	1.960	.756
February .....	1.949	W	1.956	W	2.367	2.080	.784
March .....	2.137	W	2.005	W	2.376	2.158	.761
April .....	2.487	W	2.063	W	2.461	2.259	.686
May .....	2.520	W	2.141	W	2.389	2.272	.599
June .....	2.366	W	1.907	3.312	2.156	2.078	.464
July .....	2.375	W	1.973	3.260	2.206	2.100	.487
August .....	2.252	W	1.901	W	2.155	2.037	.461
September .....	2.242	W	1.937	3.203	2.200	2.101	.473
October .....	2.289	W	1.965	W	2.174	2.134	.516
November .....	2.229	W	1.979	W	2.321	2.126	.635
December .....	2.182	W	1.979	W	2.361	2.072	.601
<b>Average</b> .....	<b>2.245</b>	<b>W</b>	<b>1.970</b>	<b>W</b>	<b>2.269</b>	<b>2.114</b>	<b>.603</b>
<b>2020 January</b> .....	2.150	W	1.958	W	2.328	2.002	.502
February .....	2.060	W	1.667	W	2.113	1.835	.469
March .....	1.862	W	1.257	W	1.813	1.486	.378
April .....	1.490	W	.740	W	1.220	1.137	.368
May .....	1.598	W	.728	W	1.162	1.130	.421
June .....	1.768	W	1.046	3.321	1.338	1.354	.515
July .....	1.806	2.761	1.175	3.059	1.394	1.431	.518
August .....	1.814	2.805	1.188	3.163	1.464	1.456	.541
September .....	1.804	2.613	1.110	W	1.411	1.386	.508
October .....	1.773	2.495	1.134	W	1.360	1.400	.548
November .....	1.736	2.485	1.216	W	1.760	1.482	.577
December .....	1.828	2.674	1.395	W	2.004	1.624	.697
<b>Average</b> .....	<b>1.829</b>	<b>2.685</b>	<b>1.293</b>	<b>W</b>	<b>1.660</b>	<b>1.486</b>	<b>.502</b>
<b>2021 January</b> .....	1.986	2.829	1.485	W	2.103	1.713	R .908
February .....	2.201	3.148	1.642	W	2.173	1.933	.972

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 5, "Motor Gasoline Prices," at end of section.

R=Revised. W=Value withheld to avoid disclosure of individual company data.

Notes: • Sales to end users are those made directly to ultimate consumers, including bulk consumers (such as agriculture, industry, and electric utilities) and residential and commercial consumers. Sales for resale are shown in Table 9.6; they are sales made to purchasers other than ultimate consumers. • Values for the current month are preliminary. • Through 1982, prices are U.S. Energy

Information Administration (EIA) estimates. See Note 6, "Historical Petroleum Prices," at end of section. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1978 and monthly data beginning in 1982.

Sources: • **1978–2007:** EIA, *Petroleum Marketing Annual 2007*, Table 2. • **2008 forward:** EIA, *Petroleum Marketing Monthly*, May 2021, Table 2.


**Figure 9.2 Average Retail Prices of Electricity**

(Cents [a] per Kilowatthour)


By Sector, 1960–2020




By Sector, Monthly



Total, January–February



By Sector, February 2021



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.  
 [b] Public street and highway lighting, interdepartmental sales, other sales to public authorities, agricultural and irrigation, and transportation including railroads and railways.

Note: Includes taxes.  
 Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
 Source: Table 9.8.

**Table 9.8 Average Retail Prices of Electricity**  
(Cents<sup>a</sup> per Kilowatthour, Including Taxes)

	Residential	Commercial <sup>b</sup>	Industrial <sup>c</sup>	Transportation <sup>d</sup>	Other <sup>e</sup>	Total
<b>1960 Average</b> .....	2.60	2.40	1.10	NA	1.90	1.80
<b>1965 Average</b> .....	2.40	2.20	1.00	NA	1.80	1.70
<b>1970 Average</b> .....	2.20	2.10	1.00	NA	1.80	1.70
<b>1975 Average</b> .....	3.50	3.50	2.10	NA	3.10	2.90
<b>1980 Average</b> .....	5.40	5.50	3.70	NA	4.80	4.70
<b>1985 Average</b> .....	7.39	7.27	4.97	NA	6.09	6.44
<b>1990 Average</b> .....	7.83	7.34	4.74	NA	6.40	6.57
<b>1995 Average</b> .....	8.40	7.69	4.66	NA	6.88	6.89
<b>2000 Average</b> .....	8.24	7.43	4.64	NA	6.56	6.81
<b>2005 Average</b> .....	9.45	8.67	5.73	8.57	--	8.14
<b>2006 Average</b> .....	10.40	9.46	6.16	9.54	--	8.90
<b>2007 Average</b> .....	10.65	9.65	6.39	9.70	--	9.13
<b>2008 Average</b> .....	11.26	10.26	6.96	10.71	--	9.74
<b>2009 Average</b> .....	11.51	10.16	6.83	10.66	--	9.82
<b>2010 Average</b> .....	11.54	10.19	6.77	10.56	--	9.83
<b>2011 Average</b> .....	11.72	10.24	6.82	10.46	--	9.90
<b>2012 Average</b> .....	11.88	10.09	6.67	10.21	--	9.84
<b>2013 Average</b> .....	12.13	10.26	6.89	10.55	--	10.07
<b>2014 Average</b> .....	12.52	10.74	7.10	10.45	--	10.44
<b>2015 Average</b> .....	12.65	10.64	6.91	10.09	--	10.41
<b>2016 Average</b> .....	12.55	10.43	6.76	9.63	--	10.27
<b>2017 Average</b> .....	12.89	10.66	6.88	9.68	--	10.48
<b>2018 Average</b> .....	12.87	10.67	6.92	9.70	--	10.53
<b>2019</b>						
January .....	12.47	10.30	6.58	9.83	--	10.24
February .....	12.72	10.54	6.69	10.02	--	10.40
March .....	12.84	10.46	6.73	9.25	--	10.34
April .....	13.25	10.52	6.51	9.45	--	10.24
May .....	13.31	10.54	6.69	9.46	--	10.38
June .....	13.32	10.90	6.87	10.01	--	10.74
July .....	13.26	11.02	7.14	9.82	--	11.00
August .....	13.30	11.02	7.40	9.65	--	11.05
September .....	13.16	10.96	7.06	9.78	--	10.82
October .....	12.81	10.74	6.84	9.72	--	10.39
November .....	13.03	10.57	6.72	9.52	--	10.38
December .....	12.68	10.32	6.38	9.46	--	10.22
<b>Average</b> .....	<b>13.01</b>	<b>10.68</b>	<b>6.81</b>	<b>9.66</b>	--	<b>10.54</b>
<b>2020</b>						
January .....	12.79	10.23	6.34	9.67	--	10.28
February .....	12.85	10.36	6.41	9.45	--	10.29
March .....	13.08	10.41	6.38	9.82	--	10.29
April .....	13.28	10.42	6.40	9.63	--	10.41
May .....	13.15	10.45	6.53	9.34	--	10.47
June .....	13.27	10.95	6.93	10.53	--	10.96
July .....	13.25	10.90	7.17	10.24	--	11.14
August .....	13.31	10.95	7.07	10.25	--	11.10
September .....	13.54	11.07	7.01	10.34	--	11.07
October .....	13.70	10.79	6.71	9.88	--	10.73
November .....	13.35	10.59	6.48	9.89	--	10.45
December .....	12.80	10.48	6.40	9.81	--	10.44
<b>Average</b> .....	<b>13.20</b>	<b>10.65</b>	<b>6.66</b>	<b>9.90</b>	--	<b>10.66</b>
<b>2021</b>						
January .....	12.69	10.31	6.35	9.64	--	10.35
February .....	13.34	11.93	8.15	9.93	--	11.60
<b>2-Month Average</b> .....	<b>13.00</b>	<b>11.09</b>	<b>7.22</b>	<b>9.79</b>	--	<b>10.95</b>
<b>2020 2-Month Average</b> .....	<b>12.82</b>	<b>10.29</b>	<b>6.37</b>	<b>9.56</b>	--	<b>10.29</b>
<b>2019 2-Month Average</b> .....	<b>12.58</b>	<b>10.42</b>	<b>6.63</b>	<b>9.92</b>	--	<b>10.32</b>

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Price" in Glossary.

<sup>b</sup> Commercial sector. For 1960–2002, prices exclude public street and highway lighting, interdepartmental sales, and other sales to public authorities.

<sup>c</sup> Industrial sector. For 1960–2002, prices exclude agriculture and irrigation.

<sup>d</sup> Transportation sector, including railroads and railways.

<sup>e</sup> Public street and highway lighting, interdepartmental sales, other sales to public authorities, agriculture and irrigation, and transportation including railroads and railways.

NA=Not available. -- =Not applicable.

Notes: • Beginning in 2003, the category "Other" has been replaced by "Transportation," and the categories "Commercial" and "Industrial" have been redefined. • Prices are calculated by dividing revenue by sales. Revenue may not correspond to sales for a particular month because of energy service provider billing and accounting procedures. That lack of correspondence could result in uncharacteristic increases or decreases in the monthly prices. • Prices include state and local taxes, energy or demand charges, customer service charges, environmental surcharges, franchise fees, fuel adjustments, and other miscellaneous charges applied to end-use customers during normal billing operations. Prices do not include deferred charges, credits, or other adjustments, such as fuel or revenue from purchased power, from previous reporting periods. • Through 1979, data are for Classes A and B privately owned electric utilities only.

(Class A utilities are those with operating revenues of \$2.5 million or more; Class B utilities are those with operating revenues between \$1 million and \$2.5 million.) For 1980–1982, data are for selected Class A utilities whose electric operating revenues were \$100 million or more during the previous year. For 1983, data are for a selected sample of electric utilities. Beginning in 1984, data are for a census of electric utilities. Beginning in 1996, data also include energy service providers selling to retail customers. • See Note 7, "Electricity Retail Prices," at end of section for plant coverage, and for information on preliminary and final values. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1960 and monthly data beginning in 1976.

Sources: • **1960–September 1977:** Federal Power Commission, Form FPC-5, "Monthly Statement of Electric Operating Revenues and Income." • **October 1977–February 1980:** Federal Energy Regulatory Commission (FERC), Form FPC-5, "Monthly Statement of Electric Operating Revenues and Income." • **March 1980–1982:** FERC, Form FERC-5, "Electric Utility Company Monthly Statement." • **1983:** U.S. Energy Information Administration (EIA), Form EIA-826, "Electric Utility Company Monthly Statement." • **1984–2010:** EIA, Form EIA-861, "Annual Electric Power Industry Report." • **2011 forward:** EIA, *Electric Power Monthly*, April 2021, Table 5.3.


**Figure 9.3 Cost of Fossil-Fuel Receipts at Electric Generating Plants**

(Dollars [a] per Million Btu, Including Taxes)


Costs, 1973–2020



Costs, Monthly



By Fuel Type



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
Source: Table 9.9.



**Table 9.9 Cost of Fossil-Fuel Receipts at Electric Generating Plants**  
(Dollars<sup>a</sup> per Million Btu, Including Taxes)

	Coal	Petroleum				Natural Gas <sup>e</sup>	All Fossil Fuels <sup>f</sup>
		Residual Fuel Oil <sup>b</sup>	Distillate Fuel Oil <sup>c</sup>	Petroleum Coke	Total <sup>d</sup>		
<b>1973 Average</b> .....	<b>0.41</b>	<b>0.79</b>	<b>NA</b>	<b>NA</b>	<b>0.80</b>	<b>0.34</b>	<b>0.48</b>
<b>1975 Average</b> .....	<b>.81</b>	<b>2.01</b>	<b>NA</b>	<b>NA</b>	<b>2.02</b>	<b>.75</b>	<b>1.04</b>
<b>1980 Average</b> .....	<b>1.35</b>	<b>4.27</b>	<b>NA</b>	<b>NA</b>	<b>4.35</b>	<b>2.20</b>	<b>1.93</b>
<b>1985 Average</b> .....	<b>1.65</b>	<b>4.24</b>	<b>NA</b>	<b>NA</b>	<b>4.32</b>	<b>3.44</b>	<b>2.09</b>
<b>1990 Average</b> .....	<b>1.45</b>	<b>3.32</b>	<b>5.38</b>	<b>.80</b>	<b>3.35</b>	<b>2.32</b>	<b>1.69</b>
<b>1995 Average</b> .....	<b>1.32</b>	<b>2.59</b>	<b>3.99</b>	<b>.65</b>	<b>2.57</b>	<b>1.98</b>	<b>1.45</b>
<b>2000 Average</b> .....	<b>1.25</b>	<b>3.73</b>	<b>5.34</b>	<b>.78</b>	<b>3.34</b>	<b>3.56</b>	<b>1.86</b>
<b>2005 Average<sup>g</sup></b> .....	<b>1.54</b>	<b>7.06</b>	<b>11.72</b>	<b>1.11</b>	<b>6.44</b>	<b>8.21</b>	<b>3.25</b>
<b>2006 Average</b> .....	<b>1.69</b>	<b>7.85</b>	<b>13.28</b>	<b>1.33</b>	<b>6.23</b>	<b>6.94</b>	<b>3.02</b>
<b>2007 Average</b> .....	<b>1.77</b>	<b>8.64</b>	<b>14.85</b>	<b>1.51</b>	<b>7.17</b>	<b>7.11</b>	<b>3.23</b>
<b>2008 Average</b> .....	<b>2.07</b>	<b>13.62</b>	<b>21.46</b>	<b>2.11</b>	<b>10.87</b>	<b>9.01</b>	<b>4.12</b>
<b>2009 Average</b> .....	<b>2.21</b>	<b>8.98</b>	<b>13.22</b>	<b>1.61</b>	<b>7.02</b>	<b>4.74</b>	<b>3.04</b>
<b>2010 Average</b> .....	<b>2.27</b>	<b>12.57</b>	<b>16.61</b>	<b>2.28</b>	<b>9.54</b>	<b>5.09</b>	<b>3.26</b>
<b>2011 Average</b> .....	<b>2.39</b>	<b>18.35</b>	<b>22.46</b>	<b>3.03</b>	<b>12.48</b>	<b>4.72</b>	<b>3.29</b>
<b>2012 Average</b> .....	<b>2.38</b>	<b>21.03</b>	<b>23.49</b>	<b>2.24</b>	<b>12.48</b>	<b>3.42</b>	<b>2.83</b>
<b>2013 Average</b> .....	<b>2.34</b>	<b>19.26</b>	<b>23.03</b>	<b>2.18</b>	<b>11.57</b>	<b>4.33</b>	<b>3.09</b>
<b>2014 Average</b> .....	<b>2.37</b>	<b>18.30</b>	<b>21.88</b>	<b>1.98</b>	<b>11.60</b>	<b>5.00</b>	<b>3.31</b>
<b>2015 Average</b> .....	<b>2.22</b>	<b>9.89</b>	<b>14.06</b>	<b>1.84</b>	<b>6.74</b>	<b>3.23</b>	<b>2.65</b>
<b>2016 Average</b> .....	<b>2.11</b>	<b>8.45</b>	<b>10.90</b>	<b>1.65</b>	<b>5.24</b>	<b>2.87</b>	<b>2.47</b>
<b>2017 Average</b> .....	<b>2.06</b>	<b>11.00</b>	<b>13.22</b>	<b>2.13</b>	<b>7.10</b>	<b>3.37</b>	<b>2.65</b>
<b>2018 Average</b> .....	<b>2.06</b>	<b>12.97</b>	<b>16.16</b>	<b>2.54</b>	<b>9.68</b>	<b>3.55</b>	<b>2.83</b>
<b>2019</b> January .....	2.10	11.30	14.12	2.08	8.53	4.00	3.01
February .....	2.07	12.28	15.19	2.27	9.60	3.63	2.86
March .....	2.08	13.68	15.70	2.43	10.52	3.46	2.81
April .....	2.07	13.89	16.35	2.71	11.12	2.89	2.50
May .....	2.05	13.47	16.19	2.24	9.52	2.77	2.44
June .....	2.03	12.92	14.85	2.18	9.64	2.58	2.36
July .....	2.02	12.93	15.10	2.01	7.99	2.54	2.34
August .....	2.00	13.72	14.82	1.72	6.94	2.42	2.26
September .....	1.96	11.53	15.04	1.67	9.23	2.59	2.34
October .....	1.96	12.65	15.37	1.57	10.58	2.49	2.27
November .....	1.96	12.05	15.28	1.46	7.75	2.96	2.50
December .....	1.91	12.85	14.73	1.14	8.68	2.91	2.47
<b>Average</b> .....	<b>2.02</b>	<b>12.66</b>	<b>15.19</b>	<b>1.91</b>	<b>9.07</b>	<b>2.89</b>	<b>2.50</b>
<b>2020</b> January .....	1.94	13.15	14.54	1.53	6.32	2.63	2.32
February .....	1.91	12.68	13.78	1.47	7.12	2.40	2.22
March .....	1.94	10.29	10.83	1.36	6.61	2.14	2.09
April .....	1.93	8.19	8.82	1.38	4.55	2.10	2.04
May .....	1.90	5.69	7.29	1.61	4.26	2.16	2.07
June .....	1.91	6.25	8.97	1.46	4.61	2.01	1.99
July .....	1.91	7.38	10.68	1.54	4.96	2.03	2.01
August .....	1.94	9.66	10.44	1.87	5.27	2.39	2.22
September .....	1.94	9.56	9.83	1.93	6.21	2.42	2.23
October .....	1.92	8.68	10.07	2.08	6.63	2.49	2.26
November .....	1.91	8.83	10.35	2.25	6.10	2.99	2.48
December .....	1.92	9.20	11.14	2.33	7.01	3.17	2.61
<b>Average</b> .....	<b>1.92</b>	<b>9.08</b>	<b>10.54</b>	<b>1.70</b>	<b>5.81</b>	<b>2.39</b>	<b>2.21</b>
<b>2021</b> January .....	1.90	10.32	12.16	2.59	7.28	3.19	2.63
February .....	1.93	11.37	13.69	2.33	8.68	15.52	9.34
<b>2-Month Average</b> .....	<b>1.92</b>	<b>10.81</b>	<b>13.10</b>	<b>2.47</b>	<b>7.98</b>	<b>8.90</b>	<b>5.71</b>
<b>2020 2-Month Average</b> .....	<b>1.93</b>	<b>12.85</b>	<b>14.20</b>	<b>1.50</b>	<b>6.71</b>	<b>2.51</b>	<b>2.27</b>
<b>2019 2-Month Average</b> .....	<b>2.08</b>	<b>11.82</b>	<b>14.60</b>	<b>2.17</b>	<b>9.05</b>	<b>3.82</b>	<b>2.94</b>

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> For 1973–2001, electric utility data are for heavy oil (fuel oil nos. 5 and 6, and small amounts of fuel oil no. 4).

<sup>c</sup> For 1973–2001, electric utility data are for light oil (fuel oil nos. 1 and 2).

<sup>d</sup> For all years, includes residual fuel oil and distillate fuel oil. For 1990 forward, also includes petroleum coke. For 1973–2012, also includes jet fuel, kerosene, and waste oil. For 1983–2012, also includes other petroleum, such as propane and refined motor oil.

<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels. For 1973–2000, data also include a small amount of blast furnace gas and other gases derived from fossil fuels.

<sup>f</sup> Weighted average of costs shown under "Coal," "Petroleum," and "Natural Gas."

<sup>g</sup> Through 2001, data are for electric utilities only. Beginning in 2002, data also include independent power producers, and electric generating plants in the

commercial and industrial sectors.

NA=Not available.

Notes: • Receipts are purchases of fuel. • Yearly costs are averages of monthly values, weighted by quantities in Btu. • For this table, there are several breaks in the data series related to what plants and fuels are covered. Beginning in 2013, data cover all regulated generating plants; plus unregulated plants whose total fossil-fueled nameplate generating capacity is 50 megawatts or more for coal, and 200 megawatts or more for natural gas, residual fuel oil, distillate fuel oil, and petroleum coke. For data coverage before 2013, see EIA, *Electric Power Monthly*, Appendix C, Form EIA-923 notes, "Receipts and cost and quality of fossil fuels" section. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.


**Figure 9.4 Natural Gas Prices**

(Dollars [a] per Thousand Cubic Feet)


Wellhead and Citygate, 1949–2020



Consuming Sectors, 1967–2020



Consuming Sectors, Monthly



[a] Prices are not adjusted for inflation. See “Nominal Dollars” in Glossary.  
[b] Includes taxes.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
Source: Table 9.10.

**Table 9.10 Natural Gas Prices**  
(Dollars<sup>a</sup> per Thousand Cubic Feet)

	Wellhead Price <sup>i</sup>	City-gate Price <sup>g</sup>	Consuming Sectors <sup>b</sup>								
			Residential		Commercial <sup>c</sup>		Industrial <sup>d</sup>		Transportation	Electric Power <sup>e</sup>	
			Price <sup>h</sup>	Percentage of Sector <sup>i</sup>	Price <sup>h</sup>	Percentage of Sector <sup>i</sup>	Price <sup>h</sup>	Percentage of Sector <sup>i</sup>	Vehicle Fuel <sup>j</sup> Price <sup>h</sup>	Price <sup>h</sup>	Percentage of Sector <sup>i,k</sup>
1950 Average .....	0.07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1955 Average .....	.10	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1960 Average .....	.14	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1965 Average .....	.16	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1970 Average .....	.17	NA	1.09	NA	.77	NA	.37	NA	NA	.29	NA
1975 Average .....	.44	NA	1.71	NA	1.35	NA	.96	NA	NA	.77	96.1
1980 Average .....	1.59	NA	3.68	NA	3.39	NA	2.56	NA	NA	2.27	96.9
1985 Average .....	2.51	3.75	6.12	NA	5.50	NA	3.95	68.8	NA	3.55	94.0
1990 Average .....	1.71	3.03	5.80	99.2	4.83	86.6	2.93	35.2	3.39	2.38	76.8
1995 Average .....	1.55	2.78	6.06	99.0	5.05	76.7	2.71	24.5	3.98	2.02	71.4
2000 Average .....	3.68	4.62	7.76	92.6	6.59	63.9	4.45	19.8	5.54	4.38	50.5
2005 Average .....	7.33	8.67	12.70	98.1	11.34	82.1	8.56	24.0	9.14	8.47	91.3
2006 Average .....	6.39	8.61	13.73	98.1	12.00	80.8	7.87	23.4	8.72	7.11	93.4
2007 Average .....	6.25	8.16	13.08	98.0	11.34	80.4	7.68	22.2	8.50	7.31	92.2
2008 Average .....	7.97	9.18	13.89	97.5	12.23	79.7	9.65	20.4	11.75	9.26	101.1
2009 Average .....	3.67	6.48	12.14	97.4	10.06	77.8	5.33	18.8	8.13	4.93	101.1
2010 Average .....	4.48	6.18	11.39	97.4	9.47	77.5	5.49	18.0	6.25	5.27	100.8
2011 Average .....	3.95	5.63	11.03	96.3	8.91	67.3	5.13	16.3	7.48	4.89	101.2
2012 Average .....	E 2.66	4.73	10.65	95.8	8.10	65.2	3.88	16.2	8.04	3.54	95.5
2013 Average .....	NA	4.88	10.32	95.7	8.08	65.8	4.64	16.6	9.76	4.49	94.9
2014 Average .....	NA	5.71	10.97	95.5	8.90	65.8	5.62	15.9	NA	5.19	94.6
2015 Average .....	NA	4.26	10.38	95.6	7.91	65.7	3.93	14.8	NA	3.38	94.6
2016 Average .....	NA	3.71	10.05	95.8	7.28	64.8	3.51	14.9	NA	2.99	95.6
2017 Average .....	NA	4.16	10.91	95.9	7.88	65.4	4.08	14.8	NA	3.51	95.4
2018 Average .....	NA	4.23	10.50	96.0	7.79	65.8	4.19	14.5	NA	3.68	95.4
2019 January .....	NA	4.03	9.36	96.4	7.67	70.1	5.02	13.7	NA	4.16	96.4
February .....	NA	3.91	9.40	96.1	7.55	69.3	4.62	14.1	NA	3.78	95.5
March .....	NA	4.07	9.42	96.0	7.41	69.1	4.31	13.7	NA	3.60	95.7
April .....	NA	3.72	10.85	95.6	7.73	64.1	3.99	13.0	NA	2.99	96.2
May .....	NA	3.66	12.76	95.7	8.06	60.6	3.64	12.6	NA	2.85	97.9
June .....	NA	4.17	15.55	95.6	8.23	58.1	3.54	12.4	NA	2.66	97.1
July .....	NA	4.17	17.74	95.9	8.47	56.0	3.34	13.0	NA	2.63	96.6
August .....	NA	4.15	18.38	96.1	8.42	55.6	3.20	12.3	NA	2.50	96.5
September .....	NA	4.07	17.61	96.2	8.34	56.2	3.34	12.2	NA	2.68	96.8
October .....	NA	3.42	12.50	96.8	7.64	60.3	3.42	12.0	NA	2.58	96.5
November .....	NA	3.46	9.33	96.6	6.98	66.7	3.86	12.7	NA	3.08	96.3
December .....	NA	3.50	9.30	96.4	7.19	68.8	3.88	12.8	NA	3.04	96.4
Average .....	NA	3.81	10.51	96.2	7.61	65.5	3.90	12.9	NA	2.99	96.5
2020 January .....	NA	3.28	9.51	96.4	7.25	69.4	3.66	13.1	NA	2.74	89.2
February .....	NA	3.10	9.12	96.3	6.87	68.9	3.54	13.2	NA	2.50	90.4
March .....	NA	3.23	9.85	96.1	7.32	66.5	3.34	13.0	NA	2.23	88.9
April .....	NA	3.05	10.66	95.9	7.28	63.7	2.96	12.8	NA	2.20	89.7
May .....	NA	3.37	11.85	95.7	7.74	59.0	2.86	13.2	NA	2.25	89.6
June .....	NA	3.85	15.37	95.9	8.19	56.6	2.72	12.9	NA	2.08	88.3
July .....	NA	3.86	17.63	96.3	8.50	55.7	2.55	12.8	NA	2.10	85.5
August .....	NA	3.96	18.42	95.9	8.51	54.3	2.92	12.4	NA	2.47	87.3
September .....	NA	4.10	16.99	96.6	8.47	54.8	3.16	13.2	NA	2.49	87.8
October .....	NA	3.47	12.36	96.6	7.62	60.6	3.25	13.0	NA	2.57	88.4
November .....	NA	3.80	11.07	96.8	7.66	65.4	3.93	13.2	NA	3.08	90.7
December .....	NA	3.55	9.81	96.8	7.42	69.6	4.07	13.7	NA	3.30	90.8
Average .....	NA	3.42	10.84	96.3	7.48	64.6	3.29	13.0	NA	2.48	88.6
2021 January .....	NA	3.45	9.74	96.7	7.43	70.4	4.04	13.4	NA	3.33	91.2
February .....	NA	12.43	9.55	96.7	7.58	70.0	9.43	12.6	NA	16.29	88.2
2-Month Average .....	NA	7.87	9.65	96.7	7.51	70.2	6.44	13.0	NA	9.38	89.8
2020 2-Month Average .....	NA	3.20	9.32	96.4	7.07	69.2	3.60	13.1	NA	2.63	89.8
2019 2-Month Average .....	NA	3.97	9.38	96.2	7.61	69.7	4.83	13.9	NA	3.98	96.0

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 8, "Natural Gas Prices," at end of section.

<sup>c</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>d</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>e</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 2001, data are for electric utilities only; beginning in 2002, data also include independent power producers.

<sup>f</sup> See "Natural Gas Wellhead Price" in Glossary.

<sup>g</sup> See "Citygate" in Glossary.

<sup>h</sup> Includes taxes.

<sup>i</sup> The percentage of the sector's consumption in Table 4.3 for which price data are available. For details on how the percentages are derived, see Table 9.10 sources at end of section.

<sup>j</sup> Much of the natural gas delivered for vehicle fuel represents deliveries to fueling stations that are used primarily or exclusively by fleet vehicles. Thus, the prices are often those associated with the cost of gas in the operation of fleet vehicles.

<sup>k</sup> Percentages exceed 100% when reported natural gas receipts are greater than reported natural gas consumption—this can occur when combined-heat-and-power plants report fuel receipts related to non-electric generating activities.

NA=Not available. E=Estimate.

Notes: • Prices are for natural gas, plus a small amount of supplemental gaseous fuels. • Prices are intended to include all taxes. See Note 8, "Natural Gas Prices," at end of section. • Wellhead annual and year-to-date prices are simple averages of the monthly prices; all other annual and year-to-date prices are volume-weighted averages of the monthly prices. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1976.

Sources: See end of section.

**Note 1. Crude Oil Refinery Acquisition Costs.** Beginning with January 1981, refiner acquisition costs of crude oil are from data collected on U.S. Energy Information Administration (EIA) Form EIA-14, "Refiners' Monthly Cost Report." Those costs were previously published from data collected on Economic Regulatory Administration (ERA) Form ERA-49, "Domestic Crude Oil Entitlements Program Refiners Monthly Report." Form ERA-49 was discontinued with the decontrol of crude oil on January 28, 1981. Crude oil purchases and costs are defined for Form EIA-14 in accordance with conventions used for Form ERA-49. The respondents for the two forms are also essentially the same. However, due to possible different interpretations of the filing requirements and a different method for handling prior period adjustments, care must be taken when comparing the data collected on the two forms.

The refiner acquisition cost of crude oil is the average price paid by refiners for crude oil booked into their refineries in accordance with accounting procedures generally accepted and consistently and historically applied by the refiners concerned. Domestic crude oil is that oil produced in the United States or from the outer continental shelf as defined in 43 USC Section 1331. Imported crude oil is either that oil reported on Form ERA-51, "Transfer Pricing Report," or any crude oil that is not domestic oil. The composite cost is the weighted average of domestic and imported crude oil costs.

Crude oil costs and volumes reported on Form ERA-49 excluded unfinished oils but included the Strategic Petroleum Reserve (SPR). Crude oil costs and volumes reported on Federal Energy Administration (FEA) Form FEA-P110-M-1, "Refiners' Monthly Cost Allocation Report," included unfinished oils but excluded SPR. Imported averages derived from Form ERA-49 exclude oil purchased for SPR, whereas the composite averages derived from Form ERA-49 include SPR. None of the prices derived from Form EIA-14 include either unfinished oils or SPR.

**Note 2. Crude Oil Domestic First Purchase Prices.** The average domestic first purchase price represents the average price at which all domestic crude oil is purchased. Crude oil domestic first purchase prices were derived as follows: for 1949–1973, weighted average domestic first purchase values as reported by state agencies and calculated by the Bureau of Mines; for 1974 and 1975, weighted averages of a sample survey of major first purchasers' purchases; for 1976 forward, weighted averages of all first purchasers' purchases. The data series was previously called "Actual Domestic Wellhead Price."

**Note 3. Crude Oil F.O.B. Costs.** F.O.B. literally means "Free on Board." It denotes a transaction whereby the seller makes the product available with an agreement on a given port at a given price; it is the responsibility of the buyer to arrange for the transportation and insurance.

**Note 4. Crude Oil Landed Costs.** The landed cost of imported crude oil from selected countries does not represent the total cost of all imported crude. Prior to April 1975, imported crude costs to U.S. company-owned refineries in the Caribbean were not included in the landed cost, and costs of crude oil from countries that export only small amounts to the United States were also excluded. Beginning in April 1975, however, coverage was expanded to include U.S. company-owned refineries in the Caribbean. Landed costs do not include supplemental fees.

**Note 5. Motor Gasoline Prices.** Several different series of motor gasoline prices are published in this section. U.S. city average retail prices of motor gasoline by grade are calculated monthly by the Bureau of Labor Statistics during the development of the Consumer Price Index (CPI). These prices include all federal, state, and local taxes paid at the time of sale. Prior to 1977, prices were collected in 56 urban areas. From 1978 forward, prices are collected from a new sample of service stations in 85 urban areas selected to represent all urban consumers—about 80 percent of the total U.S. population. The service stations are selected initially, and on a replacement basis, in such a way that they represent the purchasing habits of the CPI population. Service stations in the current sample include those providing all types of service (i.e., full-, mini-, and self-serve).

Regular motor gasoline prices by area type are determined by EIA in a weekly survey of retail motor gasoline outlets (Form EIA-878, "Motor Gasoline Price Survey"). Prices include all federal, state, and local taxes paid at the time of sale. A representative sample of outlets by geographic area and size is randomly selected from a sampling frame of approximately 115,000 retail motor gasoline outlets. Monthly and annual prices are simple averages of weighted

weekly estimates from "Weekly U.S. Retail Gasoline Prices, Regular Grade." For more information on the survey methodology, see EIA, *Weekly Petroleum Status Report*, Appendix B, "Weekly Petroleum Price Surveys" section.

Refiner prices of finished motor gasoline for resale and to end users are determined by EIA in a monthly survey of refiners and gas plant operators (Form EIA-782A). The prices do not include any federal, state, or local taxes paid at the time of sale. Estimates of prices prior to January 1983 are based on Form FEA-P302-M-1/EIA-460, "Petroleum Industry Monthly Report for Product Prices," and also exclude all federal, state, or local taxes paid at the time of sale. Sales for resale are those made to purchasers who are other-than-ultimate consumers. Sales to end users are sales made directly to the consumer of the product, including bulk consumers (such as agriculture, industry, and utilities) and residential and commercial consumers.

**Note 6. Historical Petroleum Prices.** Starting in January 1983, Form EIA-782, "Monthly Petroleum Product Sales Report," replaced 10 previous surveys. Every attempt was made to continue the most important price series. However, prices published through December 1982 and those published since January 1983 do not necessarily form continuous data series due to changes in survey forms, definitions, instructions, populations, samples, processing systems, and statistical procedures. To provide historical data, continuous series were generated for annual data 1978–1982 and for monthly data 1981 and 1982 by estimating the prices that would have been published had Form EIA-782 survey and system been in operation at that time. This form of estimation was performed after detailed adjustment was made for product and sales type matching and for discontinuity due to other factors. An important difference between the previous and present prices is the distinction between wholesale and resale and between retail and end user. The resale category continues to include sales among resellers. However, sales to bulk consumers, such as utility, industrial, and commercial accounts previously included in the wholesale category, are now counted as made to end users. The end-user category continues to include retail sales through company-owned and operated outlets but also includes sales to the bulk consumers such as agriculture, industry, and electric utilities. Additional information may be found in "Estimated Historic Time Series for the EIA-782," a feature article by Paula Weir, printed in the December 1983 [3] *Petroleum Marketing Monthly*, published by EIA.

**Note 7. Electricity Retail Prices.** Average annual retail prices of electricity have the following plant coverage: Through 1979, annual data are for Classes A and B privately owned electric utilities only. For 1980–1982, annual data are for selected Class A utilities whose electric operating revenues were \$100 million or more during the previous year. For 1983, annual data are for a selected sample of electric utilities. Beginning in 1984, data are for a census of electric utilities. Beginning in 1996, annual data also include energy service providers selling to retail customers.

Average monthly retail prices of electricity have the following plant coverage: Through 1985, monthly data are derived from selected privately owned electric utilities and, therefore, are not national averages. Beginning in 1986, monthly data are based on a sample of publicly and privately owned electric utilities. Beginning in 1996, monthly data also include energy service providers selling to retail customers.

Preliminary monthly data are from Form EIA-861M (formerly Form EIA-826), "Monthly Electric Power Industry Report," which is a monthly collection of data from approximately 450 of the largest publicly and privately owned electric utilities as well as a census of energy service providers with retail sales in deregulated states; a model is then applied to the collected data to estimate for the entire universe of U.S. electric utilities. Preliminary annual data are the sum of the monthly revenues divided by the sum of the monthly sales. When final annual data become available each year from Form EIA-861, "Annual Electric Power Industry Report," their ratios to the preliminary Form EIA-861M values are used to derive adjusted final monthly values.

**Note 8. Natural Gas Prices.** Natural gas prices are intended to include all taxes. Instructions on the data collection forms specifically direct that all federal, state, and local taxes, surcharges, and/or adjustments billed to consumers are to be included. However, sales and other taxes itemized on more than 3,000 consumers' bills are sometimes excluded by the reporting utilities. Delivered-to-consumers prices for 1987 forward represent natural gas delivered and sold to residential, commercial, industrial, vehicle fuel, and electric power consumers. They do not include the price of natural

gas delivered on behalf of third parties to residential, commercial, industrial, and vehicle fuel customers except for certain states in the residential and commercial sectors for 2002 forward. Volumes of natural gas delivered on behalf of third parties are included in the consumption data shown in Table 4.3. Additional information is available in EIA, *Natural Gas Monthly*, Appendix C.

## Table 9.1 Sources

### *Domestic First Purchase Price*

1949–1976: U.S. Department of the Interior (DOI), Bureau of Mines (BOM), *Minerals Yearbook*, "Crude Petroleum and Petroleum Products" chapter.

1977: Federal Energy Administration, based on Form FEA-P124, "Domestic Crude Oil Purchaser's Monthly Report."

1978–2009: U.S. Energy Information Administration (EIA), *Petroleum Marketing Annual* 2009, Table 1.

2010 forward: EIA, *Petroleum Marketing Monthly*, May 2021, Table 1.

### *F.O.B. and Landed Cost of Imports*

October 1973–September 1977: Federal Energy Administration, Form FEA-F701-M-0, "Transfer Pricing Report."

October–December 1977: EIA, Form FEA-F701-M-0, "Transfer Pricing Report."

1978–2009: EIA, *Petroleum Marketing Annual* 2009, Table 1.

2010 forward: EIA, *Petroleum Marketing Monthly*, May 2021, Table 1.

### *Refiner Acquisition Cost*

1968–1973: EIA estimates. The cost of domestic crude oil was derived by adding estimated transportation costs to the reported average domestic first purchase price. The cost of imported crude oil was derived by adding an estimated ocean transport cost based on the published "Average Freight Rate Assessment" to the average "Free Alongside Ship" value published by the U.S. Census Bureau.

1974–1976: DOI, BOM, *Minerals Yearbook*, "Crude Petroleum and Petroleum Products" chapter.

1977: January–September, FEA, based on Form FEA-P110-M-1, "Refiners' Monthly Cost Allocation Report."

1977: October–December, EIA, based on Form FEA-P110-M-1, "Refiners' Monthly Cost Allocation Report."

1978–2009: EIA, *Petroleum Marketing Annual* 2009, Table 1.

2010 forward: EIA, *Petroleum Marketing Monthly*, May 2021, Table 1.

## Table 9.2 Sources

October 1973–September 1977: Federal Energy Administration, Form FEA-F701-M-0, "Transfer Pricing Report."

October 1977–December 1977: U.S. Energy Information Administration (EIA), Form FEA-F701-M-0, "Transfer Pricing Report."

1978–2009: EIA, *Petroleum Marketing Annual* 2009, Table 21.

2010 forward: EIA, *Petroleum Marketing Monthly*, May 2021, Table 21.

## Table 9.9 Sources

1973–September 1977: Federal Power Commission, Form FPC-423, "Monthly Report of Cost and Quality of Fuels for

Electric Utility Plants." October 1977–December 1977: Federal Energy Regulatory Commission, Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants."

1978 and 1979: U.S. Energy Information Administration (EIA), Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants."

1980–1989: EIA, *Electric Power Monthly*, June issues.

1990–2000: EIA, *Electric Power Monthly*, April 2003, Table 26.

2001–2007: EIA, *Electric Power Monthly*, October 2008, Table 4.1; Federal Energy Regulatory Commission, Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants"; and EIA, Form EIA-423, "Monthly Cost and Quality of Fuels for Electric Plants Report."

2008 forward: EIA, *Electric Power Monthly*, April 2021, Table 4.1; and Form EIA-923, "Power Plant Operations Report."

## Table 9.10 Sources

### *All Prices Except Vehicle Fuel and Electric Power*

1949–2015: U.S. Energy Information Administration (EIA), *Natural Gas Annual* (NGA), annual reports and unpublished revisions.

2016 forward: EIA, *Natural Gas Monthly* (NGM), April 2021, Table 3.

### *Vehicle Fuel Price*

1989–2013: EIA, NGA, annual reports.

### *Electric Power Sector Price*

1967–1972: EIA, NGA, annual reports.

1973–1998: EIA, NGA 2000, Table 96.

1999–2002: EIA, NGM, November 2004, Table 4.

2003–2007: Federal Energy Regulatory Commission, Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants," and EIA, Form EIA-423 "Monthly Cost and Quality of Fuels for Electric Plants Report."

2008 forward: Form EIA-923, "Power Plant Operations Report."

### *Percentage of Residential Sector*

1989–2013: EIA, Form EIA-176, "Annual Report of Natural and Supplemental Gas Supply and Disposition." Calculated as the total amount of natural gas delivered to residential consumers minus the amount delivered for the account of others, and then divided by the total amount delivered to residential consumers.

2014 forward: EIA, Form EIA-857, "Monthly Report of Natural Gas Purchases and Deliveries to Consumers."

### *Percentage of Commercial Sector*

1987–2015: EIA, NGA, annual reports. Calculated as the total amount of natural gas delivered to commercial consumers minus the amount delivered for the account of others, and then divided by the total amount delivered to commercial consumers.

2016 forward: EIA, NGM, April 2021, Table 3.

### ***Percentage of Industrial Sector***

1982–2015: EIA, NGA, annual reports. Calculated as the total amount of natural gas delivered to industrial consumers minus the amount delivered for the account of others, and then divided by the total amount delivered to industrial consumers.

2016 forward: EIA, NGM, April 2021, Table 3.

### ***Percentage of Electric Power Sector***

1973–2001: Calculated by EIA as the quantity of natural gas receipts by electric utilities reported on Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants" (and predecessor forms) divided by the quantity of natural gas consumed by the electric power sector (for 1973 –1988, see *Monthly Energy Review (MER)*, Table 7.3b; for 1989–2001, see MER, Table 7.4b).

2002–2007: Calculated by EIA as the quantity of natural gas receipts by electric utilities and independent power producers reported on Form FERC-423, "Monthly Report of Cost and Quality of Fuels for Electric Utility Plants," and EIA-423, "Monthly Cost and Quality of Fuels for Electric Plants Report," divided by the quantity of natural gas consumed by the electric power sector (see MER, Table 7.4b).

2008 forward: Calculated by EIA as the quantity of natural gas receipts by electric utilities and independent power producers reported on Form EIA-923, "Power Plant Operations Report," divided by the quantity of natural gas consumed by the electric power sector (see MER, Table 7.4b).




# 10. Renewable Energy

---


**Figure 10.1 Renewable Energy Consumption**

(Quadrillion Btu)


Major Sources, 1949–2020




By Source, 2020



By Sector, 2020



Compared With Other Resources, 1949–2020



[a] See Table 10.1 for definition.

[b] Conventional hydroelectric power.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#renewable>.

Sources: Tables 1.3 and 10.1–10.2c.

**Table 10.1 Renewable Energy Production and Consumption by Source**  
(Trillion Btu)

	Production <sup>a</sup>				Consumption								
	Biomass			Total Renewable Energy <sup>e</sup>	Hydroelectric Power <sup>f</sup>	Geothermal <sup>g</sup>	Solar <sup>h</sup>	Wind <sup>i</sup>	Biomass				Total Renewable Energy
	Wood <sup>b</sup>	Bio-fuels <sup>c</sup>	Total <sup>d</sup>						Wood <sup>j</sup>	Waste <sup>k</sup>	Bio-fuels <sup>l</sup>	Total	
1950 Total .....	1,562	NA	1,562	2,978	1,415	NA	NA	NA	1,562	NA	NA	1,562	2,978
1955 Total .....	1,424	NA	1,424	2,784	1,360	NA	NA	NA	1,424	NA	NA	1,424	2,784
1960 Total .....	1,320	NA	1,320	2,928	1,608	(s)	NA	NA	1,320	NA	NA	1,320	2,928
1965 Total .....	1,335	NA	1,335	3,396	2,059	2	NA	NA	1,335	NA	NA	1,335	3,396
1970 Total .....	1,429	NA	1,431	4,070	2,634	6	NA	NA	1,429	2	NA	1,431	4,070
1975 Total .....	1,497	NA	1,499	4,687	3,155	34	NA	NA	1,497	2	NA	1,499	4,687
1980 Total .....	2,474	NA	2,475	5,428	2,900	53	NA	NA	2,474	2	NA	2,475	5,428
1985 Total .....	2,687	93	3,016	6,084	2,970	97	(s)	(s)	2,687	236	93	3,016	6,084
1990 Total .....	2,216	111	2,735	6,040	3,046	171	59	29	2,216	408	111	2,735	6,040
1995 Total .....	2,370	198	3,099	6,557	3,205	152	68	33	2,370	531	200	3,101	6,559
2000 Total .....	2,262	233	3,006	6,102	2,811	164	63	57	2,262	511	236	3,008	6,104
2005 Total .....	2,137	561	3,101	6,221	2,703	181	58	178	2,137	403	574	3,114	6,234
2006 Total .....	2,099	716	3,212	6,586	2,869	181	61	264	2,099	397	766	3,262	6,637
2007 Total .....	2,089	970	3,472	6,510	2,446	186	66	341	2,089	413	983	3,485	6,523
2008 Total .....	2,059	1,374	3,868	7,192	2,511	192	74	546	2,059	435	1,357	3,851	7,175
2009 Total .....	1,935	1,570	3,957	7,625	2,669	200	78	721	1,935	452	1,553	3,940	7,608
2010 Total .....	2,217	1,868	4,553	8,314	2,539	208	91	923	2,217	468	1,821	4,506	8,267
2011 Total .....	2,213	2,029	4,704	9,300	3,103	212	112	1,168	2,213	462	1,934	4,609	9,204
2012 Total .....	2,151	1,929	4,547	8,886	2,629	212	159	1,340	2,151	467	1,890	4,508	8,847
2013 Total .....	2,338	1,981	4,816	9,418	2,562	214	225	1,601	2,338	496	2,014	4,848	9,451
2014 Total .....	2,401	2,103	5,020	9,766	2,467	214	337	1,728	2,401	516	2,077	4,994	9,740
2015 Total .....	2,312	2,161	4,992	9,729	2,321	212	427	1,777	2,312	518	2,153	4,983	9,720
2016 Total .....	2,299	2,275	5,077	10,425	2,472	210	570	2,096	2,226	503	2,287	5,017	10,365
2017 Total .....	2,263	2,344	5,103	11,200	2,767	210	777	2,343	2,185	495	2,304	4,983	11,080
2018 Total .....	2,356	2,397	5,239	11,509	2,663	209	915	2,482	2,261	487	2,283	5,032	11,302
2019 January .....	203	195	437	945	221	18	52	216	196	39	177	413	921
February .....	184	177	397	875	204	16	56	201	176	36	172	384	862
March .....	197	191	426	992	235	18	84	230	189	38	186	414	980
April .....	186	193	415	1,032	248	16	95	257	178	36	185	398	1,015
May .....	193	202	432	1,065	285	17	102	230	185	36	199	421	1,054
June .....	192	197	425	1,002	250	17	110	200	182	36	194	412	989
July .....	201	203	440	989	222	18	113	197	192	37	197	426	975
August .....	204	199	440	946	201	18	109	178	193	37	194	424	930
September .....	192	182	408	904	165	17	95	218	182	35	179	396	891
October .....	194	192	423	932	163	16	85	246	185	37	191	413	922
November .....	193	192	422	903	180	14	63	224	184	37	187	408	889
December .....	202	203	444	942	191	16	53	237	192	39	194	425	922
Total .....	2,340	2,328	5,110	11,527	2,564	201	1,017	2,635	2,236	442	2,255	4,933	11,350
2020 January .....	189	203	432	994	226	17	66	254	182	39	187	408	970
February .....	180	187	403	994	235	16	78	262	172	36	174	382	973
March .....	188	184	410	995	210	19	94	263	178	38	162	379	964
April .....	179	113	328	917	197	18	112	262	171	36	112	319	908
May .....	187	137	360	1,033	271	18	132	252	179	36	146	361	1,035
June .....	177	164	374	1,044	259	17	130	263	167	33	167	367	1,037
July .....	181	181	397	999	246	18	139	198	174	35	179	388	991
August .....	184	179	399	960	214	18	129	200	176	35	175	386	946
September .....	179	175	388	891	171	18	109	205	169	33	174	376	879
October .....	182	184	402	941	163	18	101	257	174	36	173	382	921
November .....	184	186	405	999	194	18	81	300	175	35	173	383	978
December .....	195	188	421	1,008	206	19	74	289	184	38	178	400	988
Total .....	2,207	2,081	4,719	11,777	2,592	214	1,246	3,006	2,101	430	2,000	4,532	11,590
2021 January .....	<sup>R</sup> 189	177	<sup>R</sup> 404	<sup>R</sup> 1,005	233	18	79	271	181	38	157	375	976
February .....	171	140	345	885	197	17	88	238	162	33	141	337	877
2-Month Total .....	361	318	750	1,890	430	35	167	508	343	71	298	712	1,853
2020 2-Month Total .....	370	391	835	1,988	460	33	144	516	354	75	361	790	1,943
2019 2-Month Total .....	387	372	834	1,820	425	34	109	418	373	75	350	797	1,783

<sup>a</sup> For hydroelectric power, geothermal, solar, wind, and biomass waste, production equals consumption.

<sup>b</sup> Wood and wood-derived fuels. Through 2015, wood production equals consumption. Beginning in 2016, wood production equals consumption plus densified biomass exports.

<sup>c</sup> Total biomass inputs to the production of fuel ethanol and biodiesel; excludes other biofuels.

<sup>d</sup> Includes biomass waste.

<sup>e</sup> Hydroelectric power, geothermal, solar, wind, and biomass.

<sup>f</sup> Conventional hydroelectricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>g</sup> Geothermal electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), and geothermal heat pump and direct use energy.

<sup>h</sup> Solar photovoltaic (PV) and solar thermal electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), and solar thermal direct use energy.

<sup>i</sup> Wind electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>j</sup> Wood and wood-derived fuels.

<sup>k</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>l</sup> Fuel ethanol (minus denaturant), biodiesel, other renewable diesel fuel, and other renewable fuels consumption; plus losses and co-products from the production of fuel ethanol and biodiesel.

<sup>R</sup>=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Production data are estimates. Consumption data are estimates, except for hydroelectric power in 1949–1978 and 1989 forward, and wind. • See Note, "Renewable Energy Production and Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: • **Production:** Tables 10.2a–10.4 and U.S. Energy Information Administration, Form EIA-63C, "Densified Biomass Fuel Report." • **Consumption:** Tables 10.2a–10.2c.

**Table 10.2a Renewable Energy Consumption: Residential and Commercial Sectors**  
(Trillion Btu)

	Residential Sector				Commercial Sector <sup>a</sup>								
	Geo-thermal <sup>b</sup>	Solar <sup>c</sup>	Biomass	Total	Hydro-electric Power <sup>e</sup>	Geo-thermal <sup>f</sup>	Solar <sup>g</sup>	Wind <sup>h</sup>	Biomass				Total
			Wood <sup>d</sup>						Wood <sup>d</sup>	Waste <sup>i</sup>	Fuel Ethanol <sup>j,k</sup>	Total	
1950 Total .....	NA	NA	1,006	1,006	NA	NA	NA	NA	19	NA	NA	19	19
1955 Total .....	NA	NA	775	775	NA	NA	NA	NA	15	NA	NA	15	15
1960 Total .....	NA	NA	627	627	NA	NA	NA	NA	12	NA	NA	12	12
1965 Total .....	NA	NA	468	468	NA	NA	NA	NA	9	NA	NA	9	9
1970 Total .....	NA	NA	401	401	NA	NA	NA	NA	8	NA	NA	8	8
1975 Total .....	NA	NA	425	425	NA	NA	NA	NA	8	NA	NA	8	8
1980 Total .....	NA	NA	850	850	NA	NA	NA	NA	21	NA	NA	21	21
1985 Total .....	NA	NA	1,010	1,010	NA	NA	NA	NA	24	NA	(s)	24	24
1990 Total .....	6	55	580	640	1	3	(s)	—	66	28	(s)	94	98
1995 Total .....	7	63	520	589	1	5	(s)	—	72	40	(s)	113	119
2000 Total .....	9	58	420	486	1	8	1	—	71	47	(s)	119	128
2005 Total .....	16	50	430	496	1	14	2	—	70	34	1	105	121
2006 Total .....	18	53	380	451	1	14	3	—	65	36	1	103	120
2007 Total .....	22	55	420	497	1	14	4	—	70	31	2	103	122
2008 Total .....	26	58	470	555	1	15	6	—	73	34	2	109	131
2009 Total .....	33	60	504	597	1	17	8	(s)	73	36	3	112	137
2010 Total .....	37	65	541	642	1	19	12	(s)	72	36	3	111	142
2011 Total .....	40	71	524	635	(s)	20	20	(s)	69	43	3	115	155
2012 Total .....	40	79	438	557	(s)	20	33	1	61	45	3	108	162
2013 Total .....	40	91	572	703	(s)	20	41	1	70	47	3	120	182
2014 Total .....	40	109	579	728	(s)	20	52	1	76	47	4	127	200
2015 Total .....	40	128	513	681	(s)	20	57	1	79	47	<sup>k</sup> 26	152	230
2016 Total .....	40	162	445	646	2	20	62	1	84	48	26	158	242
2017 Total .....	40	193	429	662	2	20	76	1	84	48	25	156	255
2018 Total .....	40	221	524	785	2	20	94	2	84	47	25	156	274
2019 January .....	3	13	46	63	(s)	2	6	(s)	7	4	2	13	21
February .....	3	15	42	59	(s)	2	6	(s)	7	3	2	12	20
March .....	3	21	46	70	(s)	2	9	(s)	7	3	2	13	24
April .....	3	23	45	71	(s)	2	10	(s)	7	3	2	12	24
May .....	3	26	46	75	(s)	2	10	(s)	7	3	2	12	25
June .....	3	26	45	74	(s)	2	11	(s)	7	3	2	12	25
July .....	3	27	46	77	(s)	2	11	(s)	7	3	2	13	26
August .....	3	26	46	76	(s)	2	11	(s)	7	3	2	13	25
September .....	3	23	45	71	(s)	2	9	(s)	7	3	2	12	24
October .....	3	20	46	70	(s)	2	8	(s)	7	3	2	13	23
November .....	3	16	45	64	(s)	2	6	(s)	7	3	2	12	21
December .....	3	15	46	64	(s)	2	6	(s)	7	3	2	13	21
Total .....	40	251	544	835	2	24	103	2	84	39	26	149	279
2020 January .....	3	16	39	58	NM	2	7	(s)	7	3	2	13	22
February .....	3	18	36	58	NM	2	8	(s)	7	3	2	12	22
March .....	3	24	39	66	NM	2	10	(s)	7	3	2	12	25
April .....	3	26	38	67	NM	2	11	(s)	7	3	1	11	24
May .....	3	30	39	72	NM	2	12	(s)	7	3	2	12	26
June .....	3	30	38	71	NM	2	12	(s)	7	3	2	12	26
July .....	3	31	39	73	NM	2	13	(s)	7	3	2	12	27
August .....	3	29	39	71	NM	2	12	(s)	7	3	2	12	26
September .....	3	26	38	66	(s)	2	11	(s)	7	3	2	11	24
October .....	3	24	39	66	NM	2	10	(s)	7	3	2	12	24
November .....	3	20	38	60	NM	2	8	(s)	7	3	2	12	21
December .....	3	18	39	60	NM	2	7	(s)	7	3	2	12	22
Total .....	40	291	458	788	2	24	121	2	83	36	22	141	289
2021 January .....	3	19	39	60	NM	2	8	(s)	7	3	2	12	22
February .....	3	20	35	58	NM	2	9	(s)	6	3	2	11	22
2-Month Total .....	6	38	73	118	(s)	4	17	(s)	13	6	3	23	44
2020 2-Month Total .....	6	34	75	116	NM	4	15	(s)	14	6	4	24	44
2019 2-Month Total .....	6	28	88	122	(s)	4	12	(s)	14	7	4	25	42

<sup>a</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>b</sup> Geothermal heat pump and direct use energy.

<sup>c</sup> Distributed (small-scale) solar photovoltaic (PV) electricity generation in the residential sector (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6) and distributed solar thermal energy in the residential, commercial, and industrial sectors. See Table 10.5.

<sup>d</sup> Wood and wood-derived fuels.

<sup>e</sup> Conventional hydroelectricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>f</sup> Geothermal heat pump and direct use energy. Beginning in December 2018, also includes geothermal electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>g</sup> Solar photovoltaic (PV) electricity net generation in the commercial sector (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), both utility-scale and distributed (small-scale). See Table 10.5.

<sup>h</sup> Wind electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste,

agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>j</sup> The fuel ethanol (minus denaturant) portion of motor fuels, such as E10, consumed by the commercial sector.

<sup>k</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of fuel ethanol consumption are larger than in 2014, while the transportation sector share is smaller.

NA=Not available. NM=Not meaningful. —=No data reported. (s)=Less than 0.5 trillion Btu.

Notes: • Residential sector data are estimates. Commercial sector data are estimates, except for hydroelectric power, wind, and biomass waste. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 10.2b Renewable Energy Consumption: Industrial and Transportation Sectors**  
(Trillion Btu)

	Industrial Sector <sup>a</sup>										Transportation Sector			
	Hydro-electric Power <sup>b</sup>	Geo-thermal <sup>c</sup>	Solar <sup>d</sup>	Wind <sup>e</sup>	Biomass					Total	Biomass			
					Wood <sup>f</sup>	Waste <sup>g</sup>	Fuel Ethanol <sup>h,i</sup>	Losses and Co-products <sup>j</sup>	Total		Fuel Ethanol <sup>h,k</sup>	Bio-diesel <sup>l</sup>	Other <sup>m</sup>	Total
1950 Total .....	69	NA	NA	NA	532	NA	NA	NA	532	602	NA	NA	NA	NA
1955 Total .....	38	NA	NA	NA	631	NA	NA	NA	631	669	NA	NA	NA	NA
1960 Total .....	39	NA	NA	NA	680	NA	NA	NA	680	719	NA	NA	NA	NA
1965 Total .....	33	NA	NA	NA	855	NA	NA	NA	855	888	NA	NA	NA	NA
1970 Total .....	34	NA	NA	NA	1,019	NA	NA	NA	1,019	1,053	NA	NA	NA	NA
1975 Total .....	32	NA	NA	NA	1,063	NA	NA	NA	1,063	1,096	NA	NA	NA	NA
1980 Total .....	33	NA	NA	NA	1,600	NA	NA	NA	1,600	1,633	NA	NA	NA	NA
1985 Total .....	33	NA	NA	NA	1,645	230	1	42	1,918	1,951	50	NA	NA	50
1990 Total .....	31	2	(s)	—	1,442	192	1	49	1,684	1,717	60	NA	NA	60
1995 Total .....	55	3	(s)	—	1,652	195	2	86	1,934	1,992	112	NA	NA	112
2000 Total .....	42	4	(s)	—	1,636	145	1	99	1,881	1,928	135	NA	NA	135
2005 Total .....	32	4	(s)	—	1,452	148	7	227	1,834	1,871	327	12	NA	339
2006 Total .....	29	4	1	—	1,472	130	10	280	1,892	1,926	442	33	NA	475
2007 Total .....	16	5	1	—	1,413	145	10	369	1,937	1,958	557	45	NA	602
2008 Total .....	17	5	1	—	1,339	143	12	519	2,012	2,035	786	39	NA	825
2009 Total .....	18	4	2	—	1,178	154	13	603	1,948	1,972	894	41	—	935
2010 Total .....	16	4	3	—	1,409	168	17	727	2,320	2,343	1,041	33	(s)	1,075
2011 Total .....	17	4	4	(s)	1,438	165	17	756	2,375	2,401	1,045	113	1	1,159
2012 Total .....	22	4	7	(s)	1,462	159	17	711	2,349	2,383	1,045	115	1	1,160
2013 Total .....	33	4	9	(s)	1,489	187	18	709	2,403	2,449	1,072	182	30	1,284
2014 Total .....	12	4	11	1	1,495	190	14	757	2,456	2,484	1,093	181	28	1,302
2015 Total .....	13	4	14	(s)	1,476	190	18	776	2,460	2,491	1,110	191	33	1,334
2016 Total .....	12	4	19	1	1,474	174	18	801	2,467	2,503	1,143	266	34	1,443
2017 Total .....	13	4	22	1	1,442	168	18	821	2,450	2,490	1,156	253	30	1,439
2018 Total .....	10	4	24	1	1,432	165	19	824	2,440	2,480	1,152	243	19	1,415
2019 January .....	1	(s)	2	(s)	123	14	1	67	206	209	89	16	2	107
February .....	1	(s)	2	(s)	112	13	1	61	187	190	90	17	1	108
March .....	1	(s)	2	(s)	120	14	2	66	201	205	95	20	1	117
April .....	1	(s)	3	(s)	113	13	2	66	193	197	94	20	2	115
May .....	1	(s)	3	(s)	116	13	2	69	199	204	103	22	2	126
June .....	1	(s)	3	(s)	114	12	2	68	196	201	100	20	2	122
July .....	1	(s)	3	(s)	120	12	2	69	204	207	100	22	2	124
August .....	1	(s)	3	(s)	121	12	2	68	203	207	100	21	2	122
September .....	(s)	(s)	3	(s)	113	12	1	62	189	192	93	19	1	113
October .....	1	(s)	2	(s)	117	14	2	66	198	201	101	19	1	121
November .....	1	(s)	2	(s)	117	13	2	67	198	201	99	17	(s)	116
December .....	1	(s)	2	(s)	121	14	2	71	207	210	98	19	2	119
Total .....	9	4	28	1	1,407	156	19	800	2,381	2,423	1,162	231	18	1,411
2020 January .....	1	(s)	2	(s)	119	14	2	70	206	209	95	17	2	113
February .....	1	(s)	2	(s)	113	13	1	64	192	195	86	19	1	106
March .....	1	(s)	3	(s)	116	14	1	62	193	197	78	18	1	97
April .....	1	(s)	3	(s)	113	13	1	36	163	167	53	19	3	75
May .....	1	(s)	3	(s)	118	13	1	44	177	182	78	19	1	98
June .....	1	(s)	3	1	108	12	1	55	176	181	89	19	1	109
July .....	1	(s)	3	1	113	12	1	60	187	192	91	23	1	115
August .....	1	(s)	3	1	111	12	1	60	185	190	89	21	2	111
September .....	1	(s)	3	1	112	12	1	59	183	188	89	22	1	112
October .....	1	(s)	3	1	114	13	1	62	190	195	85	21	2	108
November .....	1	(s)	2	1	116	13	1	63	194	198	86	19	2	107
December .....	1	(s)	2	1	121	14	1	63	200	204	88	22	2	112
Total .....	9	4	32	6	1,376	156	16	698	2,246	2,297	1,006	238	19	1,263
2021 January .....	1	(s)	2	1	119	14	1	60	195	199	79	13	2	94
February .....	1	(s)	2	1	105	12	1	48	166	170	73	15	2	91
2-Month Total .....	1	1	4	2	224	27	2	108	361	369	152	28	4	184
2020 2-Month Total .....	2	1	4	(s)	232	28	3	135	397	403	181	36	3	219
2019 2-Month Total .....	2	1	3	(s)	235	27	3	128	393	399	179	32	3	215

<sup>a</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>b</sup> Conventional hydroelectricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>c</sup> Geothermal heat pump and direct use energy.

<sup>d</sup> Solar photovoltaic (PV) electricity net generation in the industrial sector (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), both utility-scale and distributed (small-scale). See Table 10.5.

<sup>e</sup> Wind electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>f</sup> Wood and wood-derived fuels.

<sup>g</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>h</sup> The fuel ethanol (minus denaturant) portion of motor fuels, such as E10, consumed by the industrial sector.

<sup>i</sup> There is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors. Beginning in 2015, the commercial and industrial sector shares of fuel ethanol consumption are larger than in 2014, while the transportation sector share is smaller.

<sup>j</sup> Losses and co-products from the production of fuel ethanol and biodiesel. Does not include natural gas, electricity, and other non-biomass energy used in the production of fuel ethanol and biodiesel—these are included in the industrial sector consumption statistics for the appropriate energy source.

<sup>k</sup> The fuel ethanol (minus denaturant) portion of motor fuels, such as E10 and E85, consumed by the transportation sector.

<sup>l</sup> Although there is biodiesel use in other sectors, all biodiesel consumption is assigned to the transportation sector.

<sup>m</sup> Other renewable diesel fuel and other renewable fuels consumption. Although there is other renewable diesel fuel and other renewable fuels use in other sectors, all consumption is assigned to the transportation sector. See "Renewable Diesel Fuel (Other)" and "Renewable Fuels (Other)" in Glossary.

NA=Not available. —=No data reported. (s)=Less than 0.5 trillion Btu.

Notes: • Industrial sector data are estimates, except for hydroelectric power in 1949–1978 and 1989 forward, and wind. Transportation sector data are estimates, except for biodiesel beginning in 2012. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: See end of section.

**Table 10.2c Renewable Energy Consumption: Electric Power Sector**  
(Trillion Btu)

	Hydro- electric Power <sup>a</sup>	Geo- thermal <sup>b</sup>	Solar <sup>c</sup>	Wind <sup>d</sup>	Biomass			Total
					Wood <sup>e</sup>	Waste <sup>f</sup>	Total	
1950 Total .....	1,346	NA	NA	NA	5	NA	5	1,351
1955 Total .....	1,322	NA	NA	NA	3	NA	3	1,325
1960 Total .....	1,569	(s)	NA	NA	2	NA	2	1,571
1965 Total .....	2,026	2	NA	NA	3	NA	3	2,031
1970 Total .....	2,600	6	NA	NA	1	2	4	2,609
1975 Total .....	3,122	34	NA	NA	(s)	2	2	3,158
1980 Total .....	2,867	53	NA	NA	3	2	4	2,925
1985 Total .....	2,937	97	(s)	(s)	8	7	14	3,049
1990 Total .....	3,014	161	4	29	129	188	317	3,524
1995 Total .....	3,149	138	5	33	125	296	422	3,747
2000 Total .....	2,768	144	5	57	134	318	453	3,427
2005 Total .....	2,670	147	6	178	185	221	406	3,406
2006 Total .....	2,839	145	5	264	182	231	412	3,665
2007 Total .....	2,430	145	6	341	186	237	423	3,345
2008 Total .....	2,494	146	9	546	177	258	435	3,630
2009 Total .....	2,650	146	9	721	180	261	441	3,967
2010 Total .....	2,521	148	12	923	196	264	459	4,064
2011 Total .....	3,085	149	17	1,167	182	255	437	4,855
2012 Total .....	2,606	148	40	1,339	190	262	453	4,586
2013 Total .....	2,529	151	83	1,600	207	262	470	4,833
2014 Total .....	2,454	151	165	1,726	251	279	530	5,026
2015 Total .....	2,308	148	228	1,776	244	281	525	4,985
2016 Total .....	2,459	146	328	2,094	224	281	505	5,531
2017 Total .....	2,752	147	486	2,341	229	280	510	6,235
2018 Total .....	2,651	145	576	2,480	221	275	496	6,348
2019 January .....	220	12	32	216	19	22	41	520
February .....	203	11	34	201	16	19	36	485
March .....	233	12	52	229	16	21	37	564
April .....	247	11	60	257	14	20	34	608
May .....	284	12	63	229	16	21	37	624
June .....	249	12	70	200	16	20	37	567
July .....	221	12	72	197	19	21	40	541
August .....	200	12	69	178	19	21	40	500
September .....	164	12	60	218	17	20	37	491
October .....	162	10	54	246	15	21	35	507
November .....	179	8	38	224	16	20	36	486
December .....	190	10	30	237	18	22	39	507
<b>Total .....</b>	<b>2,553</b>	<b>134</b>	<b>635</b>	<b>2,632</b>	<b>201</b>	<b>248</b>	<b>448</b>	<b>6,402</b>
2020 January .....	225	11	41	254	17	21	38	569
February .....	234	11	50	262	16	20	36	593
March .....	209	13	57	263	15	21	37	579
April .....	196	13	72	262	13	20	33	575
May .....	270	13	86	252	15	20	35	656
June .....	258	12	85	262	15	18	33	650
July .....	246	13	92	198	16	20	35	583
August .....	214	12	84	199	19	20	39	548
September .....	170	12	70	205	13	19	33	489
October .....	162	12	65	256	14	19	33	529
November .....	194	13	52	299	15	19	34	591
December .....	205	13	48	288	17	21	37	590
<b>Total .....</b>	<b>2,581</b>	<b>147</b>	<b>802</b>	<b>2,998</b>	<b>185</b>	<b>238</b>	<b>424</b>	<b>6,952</b>
2021 January .....	232	12	51	270	16	20	36	601
February .....	196	11	57	237	16	18	35	536
<b>2-Month Total .....</b>	<b>428</b>	<b>24</b>	<b>108</b>	<b>507</b>	<b>33</b>	<b>38</b>	<b>71</b>	<b>1,138</b>
2020 2-Month Total .....	458	22	91	515	33	41	74	1,162
2019 2-Month Total .....	422	23	65	417	36	41	77	1,005

<sup>a</sup> Conventional hydroelectricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>b</sup> Geothermal electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>c</sup> Solar photovoltaic (PV) and solar thermal electricity net generation in the electric power sector (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6). See Table 10.5.

<sup>d</sup> Wind electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6).

<sup>e</sup> Wood and wood-derived fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes

non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual data beginning in 1949 and monthly data beginning in 1973.

Sources: Tables 7.2b, 7.4b, and A6.



**Table 10.3 Fuel Ethanol Overview**

	Feed-stock <sup>a</sup>	Losses and Co-products <sup>b</sup>	Denaturant <sup>c</sup>	Production <sup>d</sup>			Trade <sup>d</sup>	Stocks <sup>d,f</sup>	Stock Change <sup>d,g</sup>	Consumption <sup>d</sup>			Consumption Minus Denaturant <sup>h</sup>
							Net Imports <sup>e</sup>						
	TBtu	TBtu	Mbbl	Mbbl	MMgal	TBtu	Mbbl	Mbbl	Mbbl	Mbbl	MMgal	TBtu	TBtu
<b>1981 Total</b> .....	13	6	40	1,978	83	7	NA	NA	NA	1,978	83	7	7
<b>1985 Total</b> .....	93	42	294	14,693	617	52	NA	NA	NA	14,693	617	52	51
<b>1990 Total</b> .....	111	49	356	17,802	748	63	NA	NA	NA	17,802	748	63	62
<b>1995 Total</b> .....	198	86	647	32,325	1,358	115	387	2,186	-207	32,919	1,383	117	114
<b>2000 Total</b> .....	233	99	773	38,627	1,622	138	116	3,400	-624	39,367	1,653	140	137
<b>2005 Total</b> .....	550	227	1,859	92,961	3,904	331	3,234	5,563	-439	96,634	4,059	344	335
<b>2006 Total</b> .....	683	280	2,326	116,294	4,884	414	17,408	8,760	3,197	130,505	5,481	465	453
<b>2007 Total</b> .....	907	368	3,105	155,263	6,521	553	10,457	10,535	1,775	163,945	6,886	584	569
<b>2008 Total</b> .....	1,286	518	4,433	221,637	9,309	790	12,610	14,226	3,691	230,556	9,683	822	800
<b>2009 Total</b> .....	1,503	602	5,688	260,424	10,938	928	4,720	16,594	2,368	262,776	11,037	937	910
<b>2010 Total</b> .....	1,823	726	6,506	316,617	13,298	1,128	-9,115	17,941	1,347	306,155	12,858	1,091	1,061
<b>2011 Total</b> .....	1,904	754	6,649	331,646	13,929	1,181	-24,365	18,238	297	306,984	12,893	1,093	1,065
<b>2012 Total</b> .....	1,801	709	6,264	314,714	13,218	1,120	-5,891	20,350	2,112	306,711	12,882	1,092	1,064
<b>2013 Total</b> .....	1,805	707	6,181	316,493	13,293	1,127	-5,761	16,424	-3,926	314,658	13,216	1,120	1,092
<b>2014 Total</b> .....	1,938	755	6,476	340,781	14,313	1,213	-18,371	18,739	2,315	320,095	13,444	1,139	1,111
<b>2015 Total</b> .....	1,998	774	6,636	352,553	14,807	1,254	-17,632	21,596	2,857	332,064	13,947	1,181	1,153
<b>2016 Total</b> .....	2,072	798	6,920	366,981	15,413	1,306	-27,002	19,758	-1,838	341,817	14,356	1,216	1,187
<b>2017 Total</b> .....	2,138	819	6,657	379,435	15,936	1,349	-31,268	23,043	3,285	344,882	14,485	1,226	1,199
<b>2018 Total</b> .....	2,156	821	5,819	383,127	16,091	1,361	-39,410	23,418	375	343,342	14,420	1,220	1,197
<b>2019 January</b> .....	177	67	550	31,603	1,327	112	-3,243	25,115	1,697	26,663	1,120	95	93
February .....	160	61	498	28,599	1,201	102	-2,283	24,506	-609	26,925	1,131	96	94
March .....	173	65	504	30,863	1,296	110	-3,653	23,396	-1,110	28,320	1,189	101	99
April .....	174	66	462	30,981	1,301	110	-3,195	23,331	-65	27,851	1,170	99	97
May .....	182	69	471	32,466	1,364	115	-2,355	22,843	-488	30,599	1,285	109	107
June .....	179	68	505	31,898	1,340	113	-2,340	22,583	-260	29,818	1,252	106	104
July .....	182	69	512	32,541	1,367	116	-2,312	22,892	309	29,920	1,257	106	104
August .....	179	68	513	31,921	1,341	113	-2,397	22,727	-165	29,689	1,247	106	103
September .....	164	62	474	29,232	1,228	104	-1,237	23,012	285	27,710	1,164	99	96
October .....	173	66	504	30,941	1,300	110	-1,998	21,784	-1,228	30,171	1,267	107	105
November .....	176	66	536	31,358	1,317	111	-2,029	21,646	-138	29,467	1,238	105	102
December .....	186	71	560	33,275	1,398	118	-3,234	22,352	706	29,335	1,232	104	102
<b>Total</b> .....	<b>2,104</b>	<b>796</b>	<b>6,089</b>	<b>375,678</b>	<b>15,778</b>	<b>1,336</b>	<b>-30,276</b>	<b>22,352</b>	<b>-1,066</b>	<b>346,468</b>	<b>14,552</b>	<b>1,232</b>	<b>1,206</b>
<b>2020 January</b> .....	186	70	543	33,343	1,400	119	-3,426	24,047	<sup>i</sup> 1,698	28,219	1,185	100	98
February .....	170	64	478	30,516	1,282	109	-4,376	24,555	508	25,632	1,077	91	89
March .....	164	62	478	29,406	1,235	105	-3,082	27,501	2,946	23,378	982	83	81
April .....	94	36	311	16,945	712	60	-2,457	26,102	-1,399	15,887	667	57	55
May .....	118	44	382	21,098	886	75	-1,622	22,247	-3,855	23,331	980	83	81
June .....	145	54	472	25,958	1,090	92	-1,883	19,826	-2,421	26,496	1,113	94	92
July .....	160	60	530	28,707	1,206	102	-1,508	19,784	-42	27,241	1,144	97	95
August .....	158	60	512	28,419	1,194	101	-1,563	20,143	359	26,497	1,113	94	92
September .....	155	58	497	27,778	1,167	99	-1,410	20,027	-116	26,484	1,112	94	92
October .....	164	62	569	29,402	1,235	105	-2,525	21,422	1,395	25,482	1,070	91	88
November .....	166	63	611	29,908	1,256	106	-2,275	23,257	1,835	25,798	1,084	92	89
December .....	167	63	594	30,097	1,264	107	-2,413	24,687	1,430	26,254	1,103	93	91
<b>Total</b> .....	<b>1,847</b>	<b>695</b>	<b>5,977</b>	<b>331,577</b>	<b>13,926</b>	<b>1,180</b>	<b>-28,541</b>	<b>24,687</b>	<b><sup>i</sup>2,338</b>	<b>300,698</b>	<b>12,629</b>	<b>1,070</b>	<b>1,045</b>
<b>2021 January</b> .....	160	60	491	28,847	1,212	103	-3,956	26,080	1,393	23,498	987	84	82
February .....	127	48	391	22,928	963	82	-2,437	24,715	-1,365	21,856	918	78	76
<b>2-Month Total</b> .....	<b>288</b>	<b>108</b>	<b>882</b>	<b>51,775</b>	<b>2,175</b>	<b>184</b>	<b>-6,393</b>	<b>24,715</b>	<b>28</b>	<b>45,354</b>	<b>1,905</b>	<b>161</b>	<b>158</b>
<b>2020 2-Month Total</b> .....	<b>357</b>	<b>134</b>	<b>1,021</b>	<b>63,859</b>	<b>2,682</b>	<b>227</b>	<b>-7,803</b>	<b>24,555</b>	<b>2,206</b>	<b>53,850</b>	<b>2,262</b>	<b>192</b>	<b>188</b>
<b>2019 2-Month Total</b> .....	<b>337</b>	<b>127</b>	<b>1,048</b>	<b>60,202</b>	<b>2,528</b>	<b>214</b>	<b>-5,525</b>	<b>24,506</b>	<b>1,088</b>	<b>53,589</b>	<b>2,251</b>	<b>191</b>	<b>186</b>

<sup>a</sup> Total corn and other biomass inputs to the production of undenatured ethanol used for fuel ethanol.

<sup>b</sup> Losses and co-products from the production of fuel ethanol. Does not include natural gas, electricity, and other non-biomass energy used in the production of fuel ethanol—these are included in the industrial sector consumption statistics for the appropriate energy source.

<sup>c</sup> The amount of denaturant in fuel ethanol produced.

<sup>d</sup> Includes denaturant.

<sup>e</sup> Through 2009, data are for fuel ethanol imports only; data for fuel ethanol exports are not available. Beginning in 2010, data are for fuel ethanol imports minus fuel ethanol (including industrial alcohol) exports.

<sup>f</sup> Stocks are at end of period.

<sup>g</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase.

<sup>h</sup> Consumption of fuel ethanol minus denaturant. Data for fuel ethanol minus denaturant are used to develop data for "Renewable Energy/Biomass" in Tables 10.1–10.2b, as well as in Sections 1 and 2.

<sup>i</sup> Derived from the preliminary 2019 stocks value (22,349 thousand barrels), not the final 2019 value (22,352 thousand barrels) that is shown under "Stocks." NA=Not available.

Notes: • Mbbl = thousand barrels. MMgal = million U.S. gallons. TBtu = trillion Btu. • Fuel ethanol data in thousand barrels are converted to million gallons by multiplying by 0.042, and are converted to Btu by multiplying by the approximate heat content of fuel ethanol—see Table A3. • Through 1980, data are not available. For 1981–1992, data are estimates. For 1993–2008, only data for feedstock, losses and co-products, and denaturant are estimates. Beginning in 2009, only data for feedstock, and losses and co-products, are estimates. • See "Denaturant," "Ethanol," "Fuel Ethanol," and "Fuel Ethanol Minus Denaturant" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual and monthly data beginning in 1981.

Sources: See end of section.

**Table 10.4 Biodiesel and Other Renewable Fuels Overview**

	Biodiesel <sup>a</sup>													Other Renew- able Fuels <sup>g</sup>
	Feed- stock <sup>b</sup>	Losses and Co- prod- ucts <sup>c</sup>	Production			Trade			Stocks <sup>e</sup>	Stock Change <sup>f</sup>	Consumption			
						Imports	Exports	Net Imports <sup>d</sup>						
			TBtu	TBtu	Mbbl	MMgal	TBtu	Mbbl			Mbbl	Mbbl	Mbbl	
2001 Total	1	(s)	204	9	1	81	41	40	NA	NA	244	10	1	NA
2005 Total	12	(s)	2,162	91	12	214	213	1	NA	NA	2,163	91	12	NA
2006 Total	32	(s)	5,963	250	32	1,105	856	250	NA	NA	6,213	261	33	NA
2007 Total	63	1	11,662	490	62	3,455	6,696	-3,241	NA	NA	8,422	354	45	NA
2008 Total	88	1	16,145	678	87	7,755	16,673	-8,918	NA	NA	7,228	304	39	NA
2009 Total	67	1	12,281	516	66	1,906	6,546	-4,640	711	711	<sup>h</sup> 7,663	322	41	-
2010 Total	44	1	8,177	343	44	564	2,588	-2,024	672	-39	6,192	260	33	(s)
2011 Total	125	2	23,035	967	123	890	1,799	-908	2,005	<sup>i</sup> 1,028	21,099	886	113	1
2012 Total	128	2	23,588	991	126	853	3,056	-2,203	1,984	-20	21,406	899	115	1
2013 Total	176	2	32,368	1,359	173	8,152	4,675	3,477	3,810	1,825	34,020	1,429	182	30
2014 Total	165	2	30,452	1,279	163	4,578	1,974	2,604	3,131	-679	33,735	1,417	181	28
2015 Total	163	2	30,080	1,263	161	8,399	2,091	6,308	3,943	813	35,575	1,494	191	33
2016 Total	203	3	37,327	1,568	200	16,879	2,098	14,781	6,398	2,454	49,653	2,085	266	34
2017 Total	206	3	37,993	1,596	204	9,374	2,228	7,146	4,268	-2,130	47,269	1,985	253	30
2018 Total	240	3	44,222	1,857	237	3,969	2,470	1,499	4,662	394	45,326	1,904	243	19
2019 January	19	(s)	3,427	144	18	308	85	223	5,354	692	2,957	124	16	2
February	17	(s)	3,108	131	17	233	91	142	5,502	148	3,101	130	17	1
March	18	(s)	3,353	141	18	543	226	317	5,389	-113	3,783	159	20	1
April	20	(s)	3,623	152	19	410	370	40	5,330	-59	3,721	156	20	2
May	20	(s)	3,681	155	20	281	440	-159	4,815	-515	4,037	170	22	2
June	18	(s)	3,370	142	18	310	300	10	4,408	-406	3,787	159	20	2
July	21	(s)	3,776	159	20	333	392	-59	4,088	-321	4,039	170	22	2
August	20	(s)	3,712	156	20	216	291	-75	3,860	-228	3,865	162	21	2
September	18	(s)	3,377	142	18	280	238	42	3,706	-154	3,574	150	19	1
October	19	(s)	3,436	144	18	314	158	156	3,738	32	3,560	150	19	1
November	16	(s)	3,034	127	16	417	56	361	3,887	149	3,246	136	17	(s)
December	17	(s)	3,163	133	17	433	83	350	3,907	20	3,493	147	19	2
Total	223	3	41,060	1,725	220	4,078	2,730	1,348	3,907	-756	43,163	1,813	231	18
2020 January	17	(s)	3,196	134	17	336	31	305	4,312	<sup>j</sup> 394	3,107	130	17	2
February	17	(s)	3,067	129	16	302	76	226	4,046	-266	3,559	149	19	1
March	20	(s)	3,594	151	19	333	215	118	4,419	373	3,339	140	18	1
April	19	(s)	3,407	143	18	611	526	85	4,392	-27	3,519	148	19	3
May	19	(s)	3,505	147	19	475	496	-21	4,340	-51	3,535	148	19	1
June	20	(s)	3,590	151	19	446	494	-48	4,318	-23	3,565	150	19	1
July	21	(s)	3,849	162	21	346	341	5	3,878	-440	4,294	180	23	1
August	21	(s)	3,872	163	21	234	524	-290	3,560	-318	3,900	164	21	2
September	21	(s)	3,790	159	20	360	426	-66	3,220	-340	4,064	171	22	1
October	21	(s)	3,798	160	20	420	113	307	3,476	256	3,849	162	21	2
November	20	(s)	3,593	151	19	448	73	375	3,922	445	3,522	148	19	2
December	21	(s)	3,775	159	20	373	64	309	3,884	-38	4,122	173	22	2
Total	234	3	43,036	1,807	231	4,684	3,380	1,304	3,884	<sup>j</sup> -35	44,375	1,864	238	19
2021 January	17	(s)	3,115	131	17	228	222	6	4,565	681	2,440	102	13	2
February	13	(s)	2,406	101	13	263	122	141	4,253	-312	2,859	120	15	2
2-Month Total	30	(s)	5,521	232	30	491	343	148	4,253	369	5,299	223	28	4
2020 2-Month Total	34	(s)	6,263	263	34	638	108	530	4,046	128	6,666	280	36	3
2019 2-Month Total	36	(s)	6,534	274	35	541	177	364	5,502	840	6,058	254	32	3

<sup>a</sup> Includes biodiesel only; excludes other biofuels. See "Biodiesel" and "Biofuels" in Glossary.

<sup>b</sup> Total vegetable oil and other biomass inputs to the production of biodiesel—calculated by multiplying biodiesel production by 5.433 million Btu per barrel. See "Biodiesel Feedstock" entry in the "Thermal Conversion Factor Source Documentation" at the end of Appendix A.

<sup>c</sup> Losses and co-products from the production of biodiesel. Does not include natural gas, electricity, and other non-biomass energy used in the production of biodiesel—these are included in the industrial sector consumption statistics for the appropriate energy source.

<sup>d</sup> Net imports equal imports minus exports.

<sup>e</sup> Stocks are at end of period. Includes biodiesel stocks at (or in) refineries, pipelines, and bulk terminals. Beginning in 2011, also includes stocks at biodiesel production plants.

<sup>f</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase.

<sup>g</sup> Other renewable diesel fuel and other renewable fuels consumption. See "Renewable Diesel Fuel (Other)" and "Renewable Fuels (Other)" in Glossary.

<sup>h</sup> In 2009, because of incomplete data coverage and differing data sources, a "Balancing Item" amount of 733 thousand barrels (653 thousand barrels in January

2009; 80 thousand barrels in February 2009) is used to balance biodiesel supply and disposition.

<sup>i</sup> Derived from the final 2010 stocks value for bulk terminals and biodiesel production plants (977 thousand barrels), not the final 2010 value for bulk terminals only (672 thousand barrels) that is shown under "Stocks."

<sup>j</sup> Derived from the preliminary 2019 stocks value (3,919 thousand barrels), not the final 2019 value (3,907 thousand barrels) that is shown under "Stocks."

NA=Not available. —=No data reported. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu, or less than 500 barrels and greater than -500 barrels.

Notes: • Mbbl = thousand barrels. MMgal = million U.S. gallons. TBtu = trillion Btu. • Biodiesel data in thousand barrels are converted to million gallons by multiplying by 0.042, and are converted to Btu by multiplying by 5.359 million Btu per barrel (the approximate heat content of biodiesel—see Table A1). • Through 2000, data are not available. Beginning in 2001, data not from U.S. Energy Information Administration (EIA) surveys are estimates. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual and monthly data beginning in 2001.

Sources: See end of section.



**Table 10.5 Solar Energy Consumption**  
(Trillion Btu)

	Distributed <sup>a</sup> Solar Energy <sup>b</sup>						Utility-Scale <sup>c</sup> Solar Energy <sup>b</sup>				Total <sup>k</sup>
	Heat <sup>f</sup>	Electricity <sup>d</sup>				Total <sup>g</sup>	Electricity <sup>e</sup>				
		Residential Sector	Commercial Sector	Industrial Sector	Total		Commercial Sector <sup>h</sup>	Industrial Sector <sup>i</sup>	Electric Power Sector <sup>j</sup>	Total	
1985 Total .....	NA	NA	NA	NA	NA	NA	NA	NA	(s)	(s)	(s)
1990 Total .....	55	(s)	(s)	(s)	(s)	55	—	—	4	4	59
1995 Total .....	63	(s)	(s)	(s)	1	63	—	—	5	5	68
2000 Total .....	57	(s)	1	(s)	1	58	—	—	5	5	63
2005 Total .....	49	1	2	(s)	3	52	—	—	6	6	58
2006 Total .....	51	2	3	1	5	56	—	—	5	5	61
2007 Total .....	53	2	4	1	7	60	—	—	6	6	66
2008 Total .....	54	4	6	1	11	66	(s)	—	9	9	74
2009 Total .....	55	5	8	2	15	69	(s)	—	9	9	78
2010 Total .....	56	9	12	3	24	79	(s)	(s)	12	12	91
2011 Total .....	58	13	20	4	37	95	1	(s)	17	18	112
2012 Total .....	59	20	32	7	59	118	1	(s)	40	41	159
2013 Total .....	61	31	38	9	78	138	3	(s)	83	86	225
2014 Total .....	62	47	49	11	107	169	4	(s)	165	168	337
2015 Total .....	63	65	53	14	132	195	4	(s)	228	232	427
2016 Total .....	64	98	57	19	174	237	5	(s)	328	333	570
2017 Total .....	65	128	71	22	221	286	5	(s)	486	491	777
2018 Total .....	65	156	89	24	269	334	5	(s)	576	581	915
2019 January .....	4	10	6	1	17	20	(s)	(s)	32	32	52
February .....	4	11	6	2	18	22	(s)	(s)	34	34	56
March .....	5	15	8	2	26	31	(s)	(s)	52	53	84
April .....	6	17	9	2	29	35	(s)	(s)	60	60	95
May .....	7	19	10	3	32	38	1	(s)	63	64	102
June .....	7	19	10	3	32	39	1	(s)	70	71	110
July .....	7	20	10	3	33	40	1	(s)	72	72	113
August .....	7	19	10	3	32	39	1	(s)	69	70	109
September .....	6	17	9	3	29	35	(s)	(s)	60	61	95
October .....	5	15	8	2	25	31	(s)	(s)	54	54	85
November .....	4	12	6	2	20	24	(s)	(s)	38	39	63
December .....	4	11	6	2	18	22	(s)	(s)	30	31	53
Total .....	65	186	98	27	311	377	5	1	635	641	1,017
2020 January .....	4	12	7	2	21	24	(s)	(s)	41	41	66
February .....	4	14	7	2	23	27	(s)	(s)	50	51	78
March .....	5	18	10	3	30	36	(s)	(s)	57	58	94
April .....	6	21	11	3	34	40	1	(s)	72	72	112
May .....	7	23	12	3	38	45	1	(s)	86	87	132
June .....	7	23	12	3	38	45	1	(s)	85	86	130
July .....	7	24	12	3	39	46	1	(s)	92	93	139
August .....	7	23	12	3	37	44	1	(s)	84	85	129
September .....	6	20	10	3	33	39	1	(s)	70	70	109
October .....	5	19	9	3	30	36	(s)	(s)	65	65	101
November .....	4	15	7	2	25	29	(s)	(s)	52	52	81
December .....	4	14	7	2	22	26	(s)	(s)	48	48	74
Total .....	65	226	115	31	372	436	6	1	802	809	1,246
2021 January .....	4	15	8	2	24	28	(s)	(s)	51	51	79
February .....	4	16	8	2	26	30	(s)	(s)	57	58	88
2-Month Total .....	8	31	16	4	51	58	1	(s)	108	109	167
2020 2-Month Total .....	8	26	14	4	44	52	1	(s)	91	92	144
2019 2-Month Total .....	7	21	12	3	35	43	1	(s)	65	66	109

<sup>a</sup> Data are estimates for distributed (small-scale) facilities (combined generator nameplate capacity less than 1 megawatt).

<sup>b</sup> See "Photovoltaic Energy" and "Solar Thermal Energy" in Glossary.

<sup>c</sup> Data are for utility-scale facilities (combined generator nameplate capacity of 1 megawatt or more).

<sup>d</sup> Solar photovoltaic (PV) electricity generation at distributed (small-scale) facilities connected to the electric power grid (converted to Btu by multiplying by the fossil fuels heat rate factors in Table A6).

<sup>e</sup> Solar photovoltaic (PV) and solar thermal electricity net generation at utility-scale facilities (converted to Btu by multiplying by the fossil fuels heat rate factors in Table A6).

<sup>f</sup> Solar thermal direct use energy in the residential, commercial, and industrial sectors for all end uses, such as pool heating, hot water heating, and space heating.

<sup>g</sup> Data are the sum of "Distributed Solar Energy Heat" and "Distributed Solar Energy Electricity."

<sup>h</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at

end of Section 7.

<sup>i</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>j</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>k</sup> Data are the sum of "Distributed Solar Energy Total" and "Utility-Scale Solar Energy Total."

NA=Not available. —=No data reported. (s)=Less than 0.5 trillion Btu.

Notes: • Distributed (small-scale) solar energy data for all years, and utility-scale solar energy data for the current two years, are estimates. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual and monthly data beginning in 1984.

Sources: See end of section.

**Table 10.6 Solar Electricity Net Generation**  
(Million Kilowatthours)

	Distributed <sup>a</sup> Solar Generation <sup>b</sup>				Utility-Scale <sup>c</sup> Solar Generation <sup>b</sup>				Total
	Residential Sector	Commercial Sector	Industrial Sector	Total	Commercial Sector <sup>d</sup>	Industrial Sector <sup>e</sup>	Electric Power Sector <sup>f</sup>	Total	
<b>1985 Total</b> .....	NA	NA	NA	NA	NA	NA	11	11	11
<b>1990 Total</b> .....	12	18	4	33	—	—	367	367	400
<b>1995 Total</b> .....	20	30	7	58	—	—	497	497	554
<b>2000 Total</b> .....	39	59	13	110	—	—	493	493	604
<b>2005 Total</b> .....	121	182	40	344	—	—	550	550	894
<b>2006 Total</b> .....	177	266	59	501	—	—	508	508	1,009
<b>2007 Total</b> .....	250	375	83	708	—	—	612	612	1,319
<b>2008 Total</b> .....	401	603	133	1,137	(s)	—	864	864	2,002
<b>2009 Total</b> .....	539	810	179	1,529	(s)	—	891	891	2,420
<b>2010 Total</b> .....	900	1,237	274	2,411	5	2	1,206	1,212	3,623
<b>2011 Total</b> .....	1,358	2,020	447	3,825	84	7	1,727	1,818	5,643
<b>2012 Total</b> .....	2,058	3,351	742	6,151	148	14	4,164	4,327	10,478
<b>2013 Total</b> .....	3,217	4,024	891	8,132	294	17	8,724	9,036	17,167
<b>2014 Total</b> .....	4,947	5,146	1,139	11,233	371	16	17,304	17,691	28,924
<b>2015 Total</b> .....	6,999	5,689	1,451	14,139	416	21	24,456	24,893	39,032
<b>2016 Total</b> .....	10,595	6,158	2,060	18,812	529	27	35,497	36,054	54,866
<b>2017 Total</b> .....	13,942	7,685	2,364	23,990	521	42	52,724	53,287	77,277
<b>2018 Total</b> .....	17,105	9,798	2,636	29,539	525	47	63,253	63,825	93,365
<b>2019</b> January .....	1,107	629	168	1,903	30	4	3,546	3,580	5,483
February .....	1,205	676	178	2,059	34	5	3,798	3,836	5,895
March .....	1,727	933	254	2,914	50	7	5,841	5,899	8,813
April .....	1,935	1,032	278	3,245	54	8	6,690	6,752	9,997
May .....	2,130	1,110	309	3,549	58	9	7,095	7,162	10,711
June .....	2,175	1,118	311	3,604	63	10	7,898	7,971	11,575
July .....	2,268	1,171	321	3,760	69	10	8,053	8,133	11,893
August .....	2,184	1,116	311	3,611	64	9	7,803	7,877	11,488
September .....	1,930	994	281	3,205	55	8	6,754	6,817	10,022
October .....	1,697	881	255	2,833	46	7	6,040	6,093	9,926
November .....	1,346	683	198	2,228	36	5	4,323	4,364	6,592
December .....	1,210	657	179	2,047	26	4	3,423	3,453	5,500
<b>Total</b> .....	<b>20,914</b>	<b>11,002</b>	<b>3,041</b>	<b>34,957</b>	<b>587</b>	<b>85</b>	<b>71,265</b>	<b>71,937</b>	<b>106,894</b>
<b>2020</b> January .....	1,385	736	192	2,313	36	5	4,615	4,657	6,970
February .....	1,578	834	212	2,624	43	7	5,657	5,706	8,330
March .....	2,050	1,082	292	3,424	52	8	6,436	6,496	9,920
April .....	2,311	1,189	316	3,817	64	10	8,052	8,126	11,943
May .....	2,611	1,309	349	4,269	74	14	9,679	9,767	14,035
June .....	2,611	1,305	354	4,270	72	13	9,555	9,641	13,911
July .....	2,681	1,356	370	4,407	78	14	10,386	10,478	14,885
August .....	2,541	1,302	358	4,201	68	12	9,428	9,508	13,708
September .....	2,243	1,159	322	3,724	56	11	7,824	7,891	11,615
October .....	2,089	1,018	291	3,399	52	10	7,284	7,346	10,744
November .....	1,731	809	226	2,767	42	8	5,845	5,895	8,662
December .....	1,538	783	204	2,526	36	7	5,338	5,381	7,907
<b>Total</b> .....	<b>25,370</b>	<b>12,884</b>	<b>3,486</b>	<b>41,740</b>	<b>673</b>	<b>121</b>	<b>90,097</b>	<b>90,891</b>	<b>132,631</b>
<b>2021</b> January .....	1,671	861	216	2,749	35	8	5,689	5,732	8,481
February .....	1,774	935	231	2,939	41	8	6,452	6,502	9,441
<b>2-Month Total</b> .....	<b>3,445</b>	<b>1,796</b>	<b>447</b>	<b>5,688</b>	<b>77</b>	<b>16</b>	<b>12,142</b>	<b>12,234</b>	<b>17,922</b>
<b>2020 2-Month Total</b> .....	<b>2,963</b>	<b>1,570</b>	<b>404</b>	<b>4,937</b>	<b>79</b>	<b>12</b>	<b>10,272</b>	<b>10,363</b>	<b>15,300</b>
<b>2019 2-Month Total</b> .....	<b>2,311</b>	<b>1,305</b>	<b>346</b>	<b>3,962</b>	<b>64</b>	<b>9</b>	<b>7,344</b>	<b>7,416</b>	<b>11,378</b>

<sup>a</sup> Data are estimates for solar photovoltaic (PV) electricity generation at small-scale facilities (combined generator nameplate capacity less than 1 megawatt) connected to the electric power grid.

<sup>b</sup> See "Photovoltaic Energy" and "Solar Thermal Energy" in Glossary.

<sup>c</sup> Solar photovoltaic (PV) and solar thermal electricity net generation at utility-scale facilities (combined generator nameplate capacity of 1 megawatt or more).

<sup>d</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>e</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note 2, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>f</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

NA=Not available. —=No data reported. (s)=Less than 0.5 million kilowatthours.

Notes: • Distributed (small-scale) solar generation data for all years, and

utility-scale solar energy data for the current two years, are estimates. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> (Excel and CSV files) for all available annual and monthly data beginning in 1984.

Sources: • **Distributed Solar Generation: 1989–2013**—Calculated as distributed solar energy consumption (see Table 10.5) divided by the total fossil fuels heat rate factors (see Table A6). **2014 forward**—U.S. Energy Information Administration (EIA), *Electric Power Monthly*, monthly reports, Tables 1.1, 1.2.C, 1.2.D, and 1.2.E. • **Utility-Scale Solar Generation: 1984–1988**—EIA, Form EIA-759, "Monthly Power Plant Report." **1989–1997**: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report." **1998–2000**: EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility." **2001–2003**: EIA, Form EIA-906, "Power Plant Report." **2004–2007**: EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." **2008 forward**: EIA, Form EIA-923, "Power Plant Operations Report." • **Total**: Calculated as distributed solar generation plus utility-scale solar generation.

**Note. Renewable Energy Production and Consumption.** In Tables 1.1, 1.3, and 10.1, renewable energy consumption consists of: conventional hydroelectricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6); geothermal electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), and geothermal heat pump and geothermal direct use energy; solar thermal and photovoltaic electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6), and solar thermal direct use energy; wind electricity net generation (converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6); wood and wood-derived fuels consumption; biomass waste (municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass) consumption; fuel ethanol (minus denaturant), biodiesel, other renewable diesel fuel, and other renewable fuels consumption; and losses and co-products from the production of fuel ethanol and biodiesel. In Tables 1.1, 1.2, and 10.1, renewable energy production is assumed to equal consumption for all renewable energy sources except biofuels and wood. Biofuels production comprises biomass inputs to the production of fuel ethanol and biodiesel, but does not include biomass inputs to the production of other renewable diesel fuel and other renewable fuels. Wood production is the sum of wood consumption and densified biomass exports.

## Table 10.2a Sources

### *Residential Sector, Geothermal*

1989–2011: Annual estimates by the U.S. Energy Information Administration (EIA) based on data from Oregon Institute of Technology, Geo-Heat Center.

2012 forward: Annual estimates assumed by EIA to be equal to that of 2011.

(For 1989 forward, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

### *Residential Sector, Solar*

1989 forward: Residential sector solar consumption is the sum of the values for "Distributed Solar Energy Consumption: Heat" (which includes solar thermal direct use energy in the residential, commercial, and industrial sectors) from Table 10.5 and "Distributed Solar Energy Consumption: Electricity, Residential Sector" from Table 10.5.

### *Residential Sector, Wood*

1949–1979: Annual estimates are from EIA, *Estimates of U.S. Wood Energy Consumption from 1949 to 1981*, Table A2.

1980–2008: Annual estimates are based on EIA, Form EIA-457, "Residential Energy Consumption Survey"; and National Oceanic and Atmospheric Administration regional heating degree-day data.

2009 forward: Annual estimates based on EIA, Form EIA-457, "Residential Energy Consumption Survey"; and residential wood consumption growth rates from EIA's *Annual Energy Outlook* data system.

(For 1973 forward, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

### *Residential Sector, Total Renewable Energy*

1949–1988: Residential sector total renewable energy consumption is equal to residential sector wood consumption.

1989 forward: Residential sector total renewable energy consumption is the sum of the residential sector consumption values for geothermal, solar, and wood.

### *Commercial Sector, Hydroelectric Power*

1989 forward: Commercial sector conventional hydroelectricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," and predecessor forms, are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Commercial Sector, Geothermal Heat Pump and Direct Use Energy***

1989–2011: Annual estimates by EIA based on data from Oregon Institute of Technology, Geo-Heat Center.

2012 forward: Annual estimates assumed by EIA to be equal to that of 2011.

(For 1989 forward, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

### ***Commercial Sector, Geothermal Electricity Net Generation***

December 2018 forward: Commercial sector geothermal electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Commercial Sector, Geothermal Total***

1989–November 2018: Commercial sector geothermal total consumption is equal to commercial sector heat pump and direct use energy.

December 2018 forward: Commercial sector geothermal total consumption is the sum of the commercial sector values for geothermal heat pump and direct use energy, and geothermal electricity net generation.

### ***Commercial Sector, Solar***

1989 forward: Commercial sector solar consumption is the sum of the values for "Distributed Solar Energy Consumption: Electricity, Commercial Sector" from Table 10.5 and "Utility-Scale Solar Energy Consumption: Electricity, Commercial Sector" from Table 10.5.

### ***Commercial Sector, Wind***

2009 forward: Commercial sector wind electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Commercial Sector, Wood***

1949–1979: Annual estimates are from EIA, *Estimates of U.S. Wood Energy Consumption from 1949 to 1981*, Table A2.

1980–1983: Annual estimates are from EIA, *Estimates of U.S. Wood Energy Consumption 1980–1983*, Table ES1.

1984: Annual estimate assumed by EIA to be equal to that of 1983.

1985–1988: Annual estimates interpolated by EIA.

(For 1973–1988, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

1989 forward: Monthly/annual commercial sector combined-heat-and-power (CHP) wood consumption data are from EIA, Form EIA-923, "Power Plant Operations Report," and predecessor forms. Annual estimates for commercial sector non-CHP wood consumption are based on EIA, Form EIA-871, "Commercial Buildings Energy Consumption Survey" (for 2014–2016, the annual estimates are based on commercial sector biomass consumption growth rates from EIA's *Annual Energy Outlook* data system; for 2017 forward, annual estimates are assumed by EIA to be equal to that of 2016). For 1989 forward, monthly estimates for commercial sector non-CHP wood consumption are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. Commercial sector total wood consumption is the sum of commercial sector CHP and non-CHP wood consumption.

### ***Commercial Sector, Biomass Waste***

1989 forward: Table 7.4c.

### ***Commercial Sector, Fuel Ethanol (Minus Denaturant)***

1981 forward: The commercial sector share of motor gasoline consumption is equal to commercial sector motor gasoline consumption from Table 3.7a divided by motor gasoline product supplied from Table 3.5. Commercial sector

fuel ethanol (minus denaturant) consumption is equal to fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the commercial sector share of motor gasoline consumption. Note that there is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors; beginning in 2015, the commercial and industrial sector shares of fuel ethanol consumption are larger than in 2014, while the transportation sector share is smaller.

### ***Commercial Sector, Total Biomass***

1949–1980: Commercial sector total biomass consumption is equal to commercial sector wood consumption.

1981–1988: Commercial sector total biomass consumption is the sum of the commercial sector consumption values for wood and fuel ethanol (minus denaturant).

1989 forward: Commercial sector total biomass consumption is the sum of the commercial sector consumption values for wood, waste, and fuel ethanol (minus denaturant).

### ***Commercial Sector, Total Renewable Energy***

1949–1988: Commercial sector total renewable energy consumption is equal to commercial sector total biomass consumption.

1989–2007: Commercial sector total renewable energy consumption is the sum of the commercial sector consumption values for conventional hydroelectric power, geothermal, and total biomass.

2008: Commercial sector total renewable energy consumption is the sum of the commercial sector consumption values for conventional hydroelectric power, geothermal, solar, and total biomass.

2009 forward: Commercial sector total renewable energy is the sum of the commercial sector consumption values for conventional hydroelectric power, geothermal, solar, wind, and total biomass.

## **Table 10.2b Sources**

### ***Industrial Sector, Hydroelectric Power***

1949 forward: Industrial sector conventional hydroelectricity net generation data from Table 7.2c are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Industrial Sector, Geothermal***

1989–2009: Annual estimates by the U.S. Energy Information Administration (EIA) based on data from Oregon Institute of Technology, Geo-Heat Center.

2010 forward: Annual estimates assumed by EIA to be equal to that of 2009.

(For 1989 forward, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

### ***Industrial Sector, Solar***

1989 forward: Industrial sector solar consumption is the sum of the values for "Distributed Solar Energy Consumption: Electricity, Industrial Sector" from Table 10.5 and "Utility-Scale Solar Energy Consumption: Electricity, Industrial Sector" from Table 10.6.

### ***Industrial Sector, Wind***

2011 forward: Industrial sector wind electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Industrial Sector, Wood***

1949–1979: Annual estimates are from EIA, *Estimates of U.S. Wood Energy Consumption from 1949 to 1981*, Table A2.



1980–1983: Annual estimates are from EIA, *Estimates of U.S. Wood Energy Consumption 1980–1983*, Table ES1.

1984: Annual estimate is from EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 1.

1985 and 1986: Annual estimates interpolated by EIA.

1987: Annual estimate is from EIA, *Estimates of Biofuels Consumption in the United States During 1987*, Table 2.

1988: Annual estimate interpolated by EIA.

(For 1973–1988, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

1989 forward: Monthly/annual industrial sector combined-heat-and-power (CHP) wood consumption data are from EIA, Form EIA-923, "Power Plant Operations Report," and predecessor forms. Annual estimates for industrial sector non-CHP wood consumption are based on EIA, Form EIA-846, "Manufacturing Energy Consumption Survey" (for 2019 forward, the annual estimates are assumed by EIA to be equal to that of 2018). For 1989 forward, monthly estimates for industrial sector non-CHP wood consumption are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. Industrial sector total wood consumption is the sum of industrial sector CHP and non-CHP wood consumption.

### *Industrial Sector, Biomass Waste*

1981: Annual estimate is calculated as total waste consumption (from EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 8) minus electric power sector waste consumption (from MER Table 10.2c).

1982 and 1983: Annual estimates are calculated as total waste consumption (based on *Estimates of U.S. Biofuels Consumption 1990*, Table 8) minus electric power sector waste consumption (from MER, Table 10.2c).

1984: Annual estimate is calculated as total waste consumption (from EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 8) minus electric power sector waste consumption (from MER, Table 10.2c).

1985 and 1986: Annual estimates interpolated by EIA.

1987: Annual estimate is calculated as total waste consumption (from EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 8) minus electric power sector waste consumption (from MER, Table 10.2c).

1988: Annual estimate interpolated by EIA.

(For 1973–1988, monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.)

1989 forward: Monthly/annual industrial sector combined-heat-and-power (CHP) consumption data are from Table 7.4c. Annual estimates for industrial sector non-CHP waste consumption are based on information presented in Government Advisory Associates, *Resource Recovery Yearbook* and *Methane Recovery Yearbook*, and information provided by the U.S. Environmental Protection Agency, Landfill Methane Outreach Program (for 2014 forward, the annual estimates are assumed by EIA to be equal to that of 2013). For 1989 forward, monthly estimates for industrial sector non-CHP waste consumption are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. Industrial sector total waste consumption is the sum of industrial sector CHP and non-CHP waste consumption.

### *Industrial Sector, Fuel Ethanol (Minus Denaturant)*

1981 forward: The industrial sector share of motor gasoline consumption is equal to industrial sector motor gasoline consumption from Table 3.7b divided by motor gasoline product supplied from Table 3.5. Industrial sector fuel ethanol (minus denaturant) consumption is equal to fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the industrial sector share of motor gasoline consumption. Note that there is a discontinuity in this time series between

2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors; beginning in 2015, the commercial and industrial sector shares of fuel ethanol consumption are larger than in 2014, while the transportation sector share is smaller.

### *Industrial Sector, Biomass Losses and Co-products*

1981 forward: Calculated as fuel ethanol losses and co-products from Table 10.3 plus biodiesel losses and co-products from Table 10.4.

### *Industrial Sector, Total Biomass*

1949–1980: Industrial sector total biomass consumption is equal to industrial sector wood consumption.

1981 forward: Industrial sector total biomass consumption is the sum of the industrial sector consumption values for wood, waste, fuel ethanol (minus denaturant), and biomass losses and co-products.

### *Industrial Sector, Total Renewable Energy*

1949–1988: Industrial sector total renewable energy consumption is the sum of the industrial sector consumption values for conventional hydroelectric power and total biomass.

1989–2009: Industrial sector total renewable energy consumption is the sum of the industrial sector consumption values for conventional hydroelectric power, geothermal, and total biomass.

2010: Industrial sector total renewable energy consumption is the sum of the industrial sector consumption values for conventional hydroelectric power, geothermal, solar, and total biomass.

2011 forward: Industrial sector total renewable energy consumption is the sum of the industrial sector consumption values for conventional hydroelectric power, geothermal, solar, wind, and total biomass.

### *Transportation Sector, Fuel Ethanol (Minus Denaturant)*

1981 forward: The transportation sector share of motor gasoline consumption is equal to transportation sector motor gasoline consumption from Table 3.7c divided by motor gasoline product supplied from Table 3.5. Transportation sector fuel ethanol (minus denaturant) consumption is equal to fuel ethanol (minus denaturant) consumption from Table 10.3 multiplied by the transportation sector share of motor gasoline consumption. Note that there is a discontinuity in this time series between 2014 and 2015 due to a change in the method for allocating motor gasoline consumption to the end-use sectors; beginning in 2015, the commercial and industrial sector shares of fuel ethanol consumption are larger than in 2014, while the transportation sector share is smaller.

### *Transportation Sector, Biodiesel*

2001 forward: Table 10.4. Transportation sector biodiesel consumption is assumed to equal total biodiesel consumption.

### *Transportation Sector, Other Renewable Fuels*

2009 forward: Table 10.4.

### *Transportation Sector, Total Renewable Energy*

1981–2000: Transportation sector total renewable energy consumption is equal to transportation sector fuel ethanol (minus denaturant) consumption.

2001–2008: Transportation sector total renewable energy consumption is the sum of the transportation sector consumption values for fuel ethanol (minus denaturant) and biodiesel.

2009 forward: Transportation sector total renewable energy consumption is the sum of the transportation sector consumption values for fuel ethanol (minus denaturant), biodiesel, and other renewable fuels.

## Table 10.3 Sources

### *Feedstock*

1981 forward: Calculated as fuel ethanol production (in thousand barrels) minus denaturant, and then multiplied by the fuel ethanol feedstock factor—see Table A3.

### *Losses and Co-products*

1981 forward: Calculated as fuel ethanol feedstock plus denaturant minus fuel ethanol production.

### *Denaturant*

1981–2008: Data in thousand barrels for petroleum denaturant in fuel ethanol produced are estimated as 2% of fuel ethanol production; these data are converted to Btu by multiplying by 4.661 million Btu per barrel (the estimated quantity-weighted factor of natural gasoline and conventional motor gasoline used as denaturant).

2009–2019: U.S. Energy Information Administration (EIA), *Petroleum Supply Annual* (PSA), annual reports, Table 1. Data in thousand barrels for net production of natural gasoline at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 4.638 million Btu per barrel (the approximate heat content of natural gasoline). Data in thousand barrels for net production of conventional motor gasoline and motor gasoline blending components at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 5.222 million Btu per barrel (the approximate heat content of motor gasoline blending components). Total denaturant is the sum of the values for natural gasoline, conventional motor gasoline, and motor gasoline blending components.

2020 and 2021: EIA, *Petroleum Supply Monthly* (PSM), monthly reports, Table 1. Data in thousand barrels for net production of natural gasoline at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 4.638 million Btu per barrel (the approximate heat content of natural gasoline). Data in thousand barrels for net production of conventional motor gasoline and motor gasoline blending components at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 5.222 million Btu per barrel (the approximate heat content of motor gasoline blending components). Total denaturant is the sum of the values for natural gasoline, conventional motor gasoline, and motor gasoline blending components.

### *Production*

1981–1992: Fuel ethanol production is assumed to equal fuel ethanol consumption—see sources for "Consumption."

1993–2004: Calculated as fuel ethanol consumption plus fuel ethanol stock change minus fuel ethanol net imports. These data differ slightly from the original production data from EIA, Form EIA-819, "Monthly Oxygenate Report," and predecessor form, which were not reconciled and updated to be consistent with the final balance.

2005–2008: EIA, Form EIA-819, "Monthly Oxygenate Report."

2009–2019: EIA, PSA, annual reports, Table 1, data for net production of fuel ethanol at renewable fuels and oxygenate plants.

2020 and 2021: EIA, PSM, monthly reports, Table 1, data for net production of fuel ethanol at renewable fuels and oxygenate plants.

### *Trade, Stocks, and Stock Change*

1992–2019: EIA, PSA, annual reports, Table 1.

2020 and 2021: EIA, PSM, monthly reports, Table 1.

### *Consumption*

1981–1989: EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 10; and interpolated values for 1982, 1983, 1985, 1986, and 1988.



1990–1992: EIA, *Estimates of U.S. Biomass Energy Consumption 1992*, Table D2; and interpolated value for 1991.

1993–2004: EIA, PSA, annual reports, Tables 2 and 16. Calculated as 10% of oxygenated finished motor gasoline field production (Table 2), plus fuel ethanol refinery input (Table 16).

2005–2008: EIA, PSA, annual reports, Tables 1 and 15. Calculated as motor gasoline blending components adjustments (Table 1), plus finished motor gasoline adjustments (Table 1), plus fuel ethanol refinery and blender net inputs (Table 15).

2009–2019: EIA, PSA, annual reports, Table 1. Calculated as fuel ethanol refinery and blender net inputs minus fuel ethanol adjustments.

2020 and 2021: EIA, PSM, monthly reports, Table 1. Calculated as fuel ethanol refinery and blender net inputs minus fuel ethanol adjustments.

### ***Consumption Minus Denaturant***

1981 forward: Calculated as fuel ethanol consumption minus the amount of denaturant in fuel ethanol consumed. Denaturant in fuel ethanol consumed is estimated by multiplying denaturant in fuel ethanol produced by the fuel ethanol consumption-to-production ratio.

## **Table 10.4 Sources**

### ***Biodiesel Feedstock***

2001 forward: Calculated as biodiesel production in thousand barrels multiplied by 5.433 million Btu per barrel (the biodiesel feedstock factor—see "Biodiesel Feedstock" entry in the "Thermal Conversion Factor Source Documentation" at the end of Appendix A).

### ***Biodiesel Losses and Co-products***

2001 forward: Calculated as biodiesel feedstock minus biodiesel production.

### ***Biodiesel Production***

2001–2005: U.S. Department of Agriculture, Commodity Credit Corporation, Bioenergy Program records. Annual data are derived from quarterly data. Monthly data are estimated by dividing the annual data by the number of days in the year and then multiplying by the number of days in the month.

2006: U.S. Department of Commerce, U.S. Census Bureau, "M311K—Fats and Oils: Production, Consumption, and Stocks," data for soybean oil consumed in methyl esters (biodiesel). In addition, the U.S. Energy Information Administration (EIA) estimates that 14.4 million gallons of yellow grease were consumed in methyl esters (biodiesel).

2007: U.S. Department of Commerce, U.S. Census Bureau, "M311K—Fats and Oils: Production, Consumption, and Stocks," data for all fats and oils consumed in methyl esters (biodiesel).

2008: EIA, *Monthly Biodiesel Production Report*, December 2009 (release date October 2010), Table 11. Monthly data for 2008 are estimated based on U.S. Department of Commerce, U.S. Census Bureau, M311K data, multiplied by the EIA 2008 annual value's share of the M311K 2008 annual value.

2009 and 2010: EIA, *Monthly Biodiesel Production Report*, monthly reports, Table 1.

2011–2019: EIA, *Petroleum Supply Annual* (PSA), annual reports, Table 1, data for renewable fuels except fuel ethanol.

2020: EIA, *Petroleum Supply Monthly* (PSM), monthly reports, Table 1, data for renewable fuels except fuel ethanol.

2021: EIA, biodiesel data from EIA-819, "Monthly Report of Biofuels, Fuels from Non-Biogenic Wastes, Fuel Oxygenates, Isooctane, and Isooctene."

### ***Biodiesel Trade***

2001–2011: For imports, U.S. Department of Agriculture, data for the following Harmonized Tariff Schedule codes: 3824.90.40.20, "Fatty Esters Animal/Vegetable Mixture" (data through June 2010); and 3824.90.40.30,

"Biodiesel/Mixes" (data for July 2010–2011). For exports, U.S. Department of Agriculture, data for the following Schedule B codes: 3824.90.40.00, "Fatty Substances Animal/Vegetable/Mixture" (data through 2010); and 3824.90.40.30, "Biodiesel <70%" (data for 2011). (The data above are converted from pounds to gallons by dividing by 7.4.) Although these categories include products other than biodiesel (such as biodiesel coprocessed with petroleum feedstocks; and products destined for soaps, cosmetics, and other items), biodiesel is the largest component. In the absence of other reliable data for biodiesel trade, EIA sees these data as good substitutes.

2012–2018: EIA, PSA, annual reports, Tables 25 and 31, data for biomass-based diesel fuel.

2019: EIA, PSA, annual report, Tables 25 and 31, data for biodiesel.

2020 and 2021: EIA, PSM, monthly reports, Tables 37 and 49, data for biodiesel.

### ***Biodiesel Stocks and Stock Change***

2009–2018: EIA, biodiesel data from EIA-22M, "Monthly Biodiesel Production Survey"; and biomass-based diesel fuel data from EIA-810, "Monthly Refinery Report," EIA-812, "Monthly Product Pipeline Report," and EIA-815, "Monthly Bulk Terminal and Blender Report."

2019–September 2020: EIA, biodiesel data from EIA-22M, "Monthly Biodiesel Production Survey," EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report."

October 2020 forward: EIA, biodiesel data from EIA-810, "Monthly Refinery Report," EIA-815, "Monthly Bulk Terminal and Blender Report," and EIA-819, "Monthly Report of Biofuels, Fuels from Non-Biogenic Wastes, Fuel Oxygenates, Isooctane, and Isooctene."

### ***Biodiesel Consumption***

2001–2008: Calculated as biodiesel production plus biodiesel net imports.

January and February 2009: EIA, PSA, Table 1, data for refinery and blender net inputs of renewable fuels except fuel ethanol.

March 2009 forward: Calculated as biodiesel production plus biodiesel net imports minus biodiesel stock change.

### ***Other Renewable Fuels***

2009 forward: Consumption data for "Other Renewable Diesel Fuel" are set equal to refinery and blender net inputs data from EIA, EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report" (data are converted to Btu by multiplying by the other renewable diesel fuel heat content factor in Table A1). Consumption data for "Other Renewable Fuels" are set equal to refinery and blender net inputs data from EIA, EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report" (data are converted to Btu by multiplying by the other renewable fuels heat content factor in Table A1). "Other Renewable Fuels" in Table 10.4 is calculated as other renewable diesel fuel consumption plus other renewable fuels consumption.

## **Table 10.5 Sources**

### ***Distributed Solar Energy Consumption: Heat***

#### ***Annual Data***

1989–2009: Annual estimates by the U.S. Energy Information Administration (EIA) based on EIA, Form EIA-63A, "Annual Solar Thermal Collector/Reflector Shipments Report." Solar energy consumption by solar thermal non-electric applications (mainly in the residential sector, but with some in the commercial and industrial sectors) is based on assumptions about the stock of equipment in place and other factors.

2010 forward: Annual estimates based on commercial sector solar thermal growth rates from EIA's *Annual Energy Outlook* (AEO) data system. (Annual estimates are subject to revision when a new AEO is released.)

### ***Monthly Data***

1989–2013: Monthly estimates for each year are obtained by allocating a given year's annual value to the months in that year. Each month's allocator is the average of that month's "Distributed Solar Energy Consumption: Electricity, Total" values in 2014 and 2015. The allocators, when rounded, are as follows: January—5%; February—6%; March—8%; April—9%; May—10%; June—10%; July—10%; August—10%; September—9%; October—9%; November—7%; and December—7%.

2014 forward: Once all 12 months of "Distributed Solar Energy Consumption: Electricity, Total" data are available for a given year, they are used as allocators and applied to the annual estimate in order to derive monthly estimates for that year. Initial monthly estimates for the current year use the previous year's allocators.

### ***Distributed Solar Energy Consumption: Electricity, Residential Sector***

Beginning in 2014, monthly and annual data for residential sector distributed (small-scale) solar photovoltaic generation are from EIA, *Electric Power Monthly*, Table 1.2.E. Those data are converted to consumption data in Btu by multiplying by the total fossil fuels heat rate factors in MER Table A6.

Backcasts for earlier periods are developed as follows:

### ***Annual Data***

1989–2003: Annual growth rates are calculated based on distributed (small-scale) solar electricity consumption in all sectors. Consumption is estimated using information on shipments of solar panels from EIA, Form EIA-63B, "Annual Photovoltaic Cell/Module Shipments Report," and assumptions about the stock of equipment in place and other factors. The growth rates are applied to more recent data to create historical annual estimates.

2004–2008: Annual growth rates based on commercial sector solar photovoltaic growth rates from EIA's *Annual Energy Outlook* (AEO) data system are applied to more recent data to create historical annual estimates. (Annual estimates are subject to revision when a new AEO is released.)

2009–2013: Annual growth rates based on residential sector solar photovoltaic growth rates from EIA's *Annual Energy Outlook* (AEO) data system are applied to more recent data to create historical annual estimates. (Annual estimates are subject to revision when a new AEO is released.)

### ***Monthly Data***

1989–2013: See "Distributed Solar Energy Consumption: Heat, Monthly Data."

### ***Distributed Solar Energy Consumption: Electricity, Commercial Sector***

Beginning in 2014, monthly and annual data for commercial sector distributed (small-scale) solar photovoltaic generation are from EIA, *Electric Power Monthly*, Table 1.2.C. Those data are converted to consumption data in Btu by multiplying by the total fossil fuels heat rate factors in MER Table A6.

Backcasts for earlier periods are developed as follows:

### ***Annual Data***

1989–2003: Annual growth rates based on EIA, Form EIA-63B, "Annual Photovoltaic Cell/Module Shipments Report," are applied to more recent data to create historical annual estimates. (See "Distributed Solar Energy Consumption: Electricity, Residential Sector" sources above for details.)

2004–2013: Annual growth rates based on commercial sector solar photovoltaic growth rates from EIA's *Annual Energy Outlook* (AEO) data system are applied to more recent data to create historical annual estimates. (Annual estimates are subject to revision when a new AEO is released.)

### ***Monthly Data***

1989–2013: See "Distributed Solar Energy Consumption: Heat, Monthly Data."

### ***Distributed Solar Energy Consumption: Electricity, Industrial Sector***

Beginning in 2014, monthly and annual data for industrial sector distributed (small-scale) solar photovoltaic generation are from EIA, *Electric Power Monthly*, Table 1.2.D. Those data are converted to consumption data in Btu by multiplying by the total fossil fuels heat rate factors in MER Table A6.

Backcasts for earlier periods are developed as follows:

#### ***Annual Data***

1989–2003: Annual growth rates based on EIA, Form EIA-63B, "Annual Photovoltaic Cell/Module Shipments Report," are applied to more recent data to create historical annual estimates. (See "Distributed Solar Energy Consumption: Electricity, Residential Sector" sources above for details.)

2004–2013: Annual growth rates based on commercial sector solar photovoltaic growth rates from EIA's *Annual Energy Outlook* (AEO) data system are applied to more recent data to create historical annual estimates. (Annual estimates are subject to revision when a new AEO is released.)

#### ***Monthly Data***

1989–2013: See "Distributed Solar Energy Consumption: Heat, Monthly Data."

### ***Distributed Solar Energy Consumption: Electricity, Total***

1989 forward: Distributed (small-scale) solar energy consumption for total electricity is the sum of the distributed solar energy consumption (for electricity) values for the residential, commercial, and industrial sectors.

### ***Distributed Solar Energy Consumption: Total***

1989 forward: Distributed (small-scale) solar energy consumption total is the sum of distributed solar energy consumption values for heat and total electricity.

### ***Utility-Scale Solar Energy Consumption: Electricity, Commercial Sector***

2008 forward: Commercial sector solar photovoltaic and solar thermal electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Utility-Scale Solar Energy Consumption: Electricity, Industrial Sector***

2010 forward: Industrial sector solar photovoltaic and solar thermal electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the total fossil fuels heat rate factors in Table A6.

### ***Utility-Scale Solar Energy Consumption: Electricity, Electric Power Sector***

1984 forward: Electric power sector solar photovoltaic and solar thermal electricity net generation data from Table 7.2b are converted to Btu by multiplying the total fossil fuels heat rate factors in Table A6.

### ***Utility-Scale Solar Energy Consumption: Electricity, Total***

1984 forward: Utility-scale solar energy consumption for total electricity is the sum of the utility-scale solar energy consumption (for electricity) values for the commercial, industrial, and electric power sectors.

### ***Solar Energy Consumption: Total***

1984 forward: Total solar energy consumption is the sum of the values for total distributed solar energy consumption and total utility-scale solar energy consumption.


# 11. Environment

---


**Figure 11.1 Carbon Dioxide Emissions From Energy Consumption by Source**

(Million Metric Tons of Carbon Dioxide)


Total [a], 1973–2020




Total [a], Monthly




By Major Source, 1973–2020




By Major Source, Monthly



Total [a], January–February



By Major Source, February 2021



[a] Excludes emissions from biomass energy consumption.

[b] Includes coal coke net imports.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#environment>.

Source: Table 11.1.

**Table 11.1 Carbon Dioxide Emissions From Energy Consumption by Source**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal <sup>b</sup>	Natural Gas <sup>c</sup>	Petroleum										Total	Total <sup>h,i</sup>
			Aviation Gasoline	Distillate Fuel Oil <sup>d</sup>	HGL <sup>e</sup>	Jet Fuel	Kero-sene	Lubri-cants	Motor Gasoline <sup>f</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>g</sup>		
<b>1973 Total</b> .....	1,206	1,176	6	480	80	155	32	13	911	55	510	99	2,341	4,723
<b>1975 Total</b> .....	1,181	1,044	5	442	73	146	24	11	911	52	445	94	2,203	4,428
<b>1980 Total</b> .....	1,435	1,059	4	446	78	156	24	13	900	50	455	131	2,257	4,752
<b>1985 Total</b> .....	1,637	927	3	445	82	178	17	12	930	56	217	83	2,024	4,588
<b>1990 Total</b> .....	1,821	1,027	3	470	75	223	6	13	988	72	222	115	2,187	5,041
<b>1995 Total</b> .....	1,913	1,186	3	498	90	222	8	13	1,042	78	154	107	2,214	5,324
<b>2000 Total</b> .....	2,156	1,246	3	579	106	254	10	14	1,133	85	165	107	2,455	5,868
<b>2005 Total</b> .....	2,181	1,183	2	639	92	246	10	12	1,208	110	166	135	2,621	5,998
<b>2006 Total</b> .....	2,147	1,171	2	645	86	240	8	11	1,216	106	125	147	2,586	5,915
<b>2007 Total</b> .....	2,172	1,246	2	647	90	238	5	12	1,208	99	131	143	2,575	6,005
<b>2008 Total</b> .....	2,140	1,255	2	610	89	226	2	11	1,139	94	113	126	2,411	5,818
<b>2009 Total</b> .....	1,876	1,234	2	555	86	204	3	10	1,126	87	92	107	2,273	5,393
<b>2010 Total</b> .....	1,986	1,292	2	583	85	210	3	11	1,110	81	97	115	2,295	5,584
<b>2011 Total</b> .....	1,875	1,311	2	592	79	209	2	10	1,077	78	83	114	2,247	5,445
<b>2012 Total</b> .....	1,657	1,372	2	569	76	206	1	9	1,071	78	67	110	2,188	5,228
<b>2013 Total</b> .....	1,718	1,409	2	573	85	210	1	10	1,086	77	58	116	2,217	5,355
<b>2014 Total</b> .....	1,714	1,440	2	606	86	216	1	10	1,095	77	46	108	2,247	5,412
<b>2015 Total</b> .....	1,480	1,483	1	598	87	227	1	11	1,125	77	47	112	2,287	5,262
<b>2016 Total</b> .....	1,354	1,494	1	576	83	237	1	11	1,144	77	59	120	2,310	5,169
<b>2017 Total</b> .....	1,316	1,475	1	584	86	247	1	10	1,140	71	62	126	2,327	5,130
<b>2018 Total</b> .....	1,260	1,631	2	618	98	250	1	10	1,141	73	57	123	2,373	5,275
<b>2019 January</b> .....	110	186	(s)	55	13	20	(s)	1	91	6	5	11	202	499
February .....	90	164	(s)	49	11	18	(s)	1	85	2	4	7	177	432
March .....	89	159	(s)	53	10	21	(s)	1	95	6	3	10	199	448
April .....	69	120	(s)	50	8	21	(s)	1	95	4	3	11	193	383
May .....	81	115	(s)	52	7	22	(s)	1	98	6	3	12	201	398
June .....	89	115	(s)	49	7	22	(s)	1	97	7	5	10	197	401
July .....	109	130	(s)	49	7	23	(s)	1	99	8	5	10	202	442
August .....	103	132	(s)	51	7	23	(s)	1	102	6	5	12	207	443
September .....	94	119	(s)	48	7	21	(s)	1	92	5	5	11	189	403
October .....	76	125	(s)	54	9	22	(s)	1	96	4	5	11	202	404
November .....	84	151	(s)	52	10	21	(s)	1	92	6	3	11	196	432
December .....	82	172	(s)	50	11	23	(s)	1	93	7	4	11	200	455
<b>Total</b> .....	<b>1,076</b>	<b>1,686</b>	<b>2</b>	<b>613</b>	<b>105</b>	<b>256</b>	<b>1</b>	<b>9</b>	<b>1,137</b>	<b>67</b>	<b>50</b>	<b>127</b>	<b>2,367</b>	<b>5,140</b>
<b>2020 January</b> .....	75	179	(s)	51	10	21	(s)	1	91	5	4	11	194	448
February .....	66	165	(s)	47	9	19	(s)	1	87	5	2	12	182	414
March .....	60	147	(s)	50	10	17	(s)	(s)	81	5	2	12	176	385
April .....	49	122	(s)	43	7	8	(s)	1	59	3	2	10	133	305
May .....	55	112	(s)	45	7	7	(s)	1	74	4	1	11	151	318
June .....	73	116	(s)	43	6	9	(s)	1	83	4	3	9	158	348
July .....	96	135	(s)	45	7	12	(s)	1	88	5	5	9	172	404
August .....	98	130	(s)	46	7	13	(s)	1	88	7	5	10	177	406
September .....	77	118	(s)	47	7	11	(s)	1	86	5	5	8	169	364
October .....	69	126	(s)	51	9	13	(s)	1	86	4	4	8	176	371
November .....	70	132	(s)	48	10	14	(s)	1	80	6	3	9	170	372
December .....	86	171	(s)	49	13	14	(s)	1	81	5	3	10	176	435
<b>Total</b> .....	<b>873</b>	<b>1,651</b>	<b>1</b>	<b>563</b>	<b>102</b>	<b>159</b>	<b>1</b>	<b>8</b>	<b>984</b>	<b>58</b>	<b>39</b>	<b>118</b>	<b>2,035</b>	<b>4,571</b>
<b>2021 January</b> .....	90	<sup>R</sup> 178	(s)	51	13	14	(s)	1	80	5	4	8	175	444
February .....	91	165	(s)	46	10	12	(s)	1	73	3	4	7	156	413
<b>2-Month Total</b> .....	<b>181</b>	<b>344</b>	<b>(s)</b>	<b>97</b>	<b>23</b>	<b>26</b>	<b>(s)</b>	<b>1</b>	<b>152</b>	<b>8</b>	<b>7</b>	<b>15</b>	<b>330</b>	<b>856</b>
<b>2020 2-Month Total</b> .....	<b>141</b>	<b>344</b>	<b>(s)</b>	<b>98</b>	<b>20</b>	<b>40</b>	<b>1</b>	<b>2</b>	<b>178</b>	<b>9</b>	<b>6</b>	<b>23</b>	<b>376</b>	<b>862</b>
<b>2019 2-Month Total</b> .....	<b>200</b>	<b>350</b>	<b>(s)</b>	<b>105</b>	<b>23</b>	<b>38</b>	<b>1</b>	<b>1</b>	<b>176</b>	<b>8</b>	<b>9</b>	<b>18</b>	<b>379</b>	<b>931</b>

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Includes coal coke net imports.

<sup>c</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>d</sup> Distillate fuel oil, excluding biodiesel.

<sup>e</sup> Hydrocarbon gas liquids.

<sup>f</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>g</sup> Aviation gasoline blending components, crude oil, motor gasoline blending components, petrochemical feedstocks, special naphthas, still gas, unfinished oils, waxes, and miscellaneous petroleum products.

<sup>h</sup> Includes electric power sector use of geothermal energy and non-biomass waste. See Table 11.6.

<sup>i</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

R=Revised. (s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption, plus the relatively small amount of emissions from the non-combustion use of fossil fuels. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.


**Figure 11.2 Carbon Dioxide Emissions From Energy Consumption by Sector**

(Million Metric Tons of Carbon Dioxide)


Total [a] by End-Use Sector [b], 1973–2020




Residential Sector by Major Source, 1973–2020




Commercial Sector by Major Source, 1973–2020




Industrial Sector by Major Source, 1973–2020



Transportation Sector by Major Source, 1973–2020



Electric Power Sector by Major Source, 1973–2020



[a] Excludes emissions from biomass energy consumption.

[b] Emissions from energy consumption in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total

electricity retail sales.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#environment>.

Sources: Tables 11.2–11.6.



**Table 11.2 Carbon Dioxide Emissions From Energy Consumption: Residential Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum				Retail Electricity <sup>e</sup>	Total <sup>f</sup>
			Distillate Fuel Oil <sup>c</sup>	HGL <sup>d</sup>	Kerosene	Total		
<b>1973 Total</b> .....	9	264	147	36	16	199	435	907
<b>1975 Total</b> .....	6	266	132	32	12	176	419	867
<b>1980 Total</b> .....	3	256	96	20	8	124	529	911
<b>1985 Total</b> .....	4	241	80	20	11	111	553	909
<b>1990 Total</b> .....	3	238	72	22	5	98	624	963
<b>1995 Total</b> .....	2	263	66	25	5	96	678	1,039
<b>2000 Total</b> .....	1	271	66	35	7	108	805	1,185
<b>2005 Total</b> .....	1	262	62	32	6	101	897	1,261
<b>2006 Total</b> .....	1	237	52	28	5	85	869	1,191
<b>2007 Total</b> .....	1	257	53	31	3	86	897	1,241
<b>2008 Total</b> .....	NA	266	55	35	2	91	877	1,235
<b>2009 Total</b> .....	NA	259	43	35	2	79	819	1,157
<b>2010 Total</b> .....	NA	259	41	33	2	77	874	1,210
<b>2011 Total</b> .....	NA	255	38	31	1	71	823	1,149
<b>2012 Total</b> .....	NA	225	35	25	1	61	757	1,043
<b>2013 Total</b> .....	NA	267	36	29	1	66	768	1,100
<b>2014 Total</b> .....	NA	278	39	31	1	71	766	1,115
<b>2015 Total</b> .....	NA	253	40	28	1	69	714	1,037
<b>2016 Total</b> .....	NA	239	32	27	1	60	683	982
<b>2017 Total</b> .....	NA	242	32	27	1	59	645	947
<b>2018 Total</b> .....	NA	275	37	32	1	70	671	1,016
<b>2019 January</b> .....	NA	53	5	6	(s)	11	61	124
February .....	NA	45	4	5	(s)	9	50	104
March .....	NA	38	4	4	(s)	8	47	93
April .....	NA	18	2	3	(s)	5	34	57
May .....	NA	12	2	2	(s)	4	41	56
June .....	NA	7	2	1	(s)	3	51	61
July .....	NA	6	2	1	(s)	3	70	79
August .....	NA	6	2	1	(s)	3	67	76
September .....	NA	6	1	1	(s)	3	57	65
October .....	NA	13	2	2	(s)	4	42	60
November .....	NA	32	4	4	(s)	8	44	85
December .....	NA	41	5	5	(s)	10	49	100
<b>Total</b> .....	NA	276	34	36	1	71	611	958
<b>2020 January</b> .....	NA	45	4	5	(s)	9	48	102
February .....	NA	40	3	4	(s)	8	42	90
March .....	NA	29	3	4	(s)	7	37	73
April .....	NA	21	3	3	(s)	6	33	59
May .....	NA	13	3	2	(s)	5	37	55
June .....	NA	7	2	1	(s)	3	52	63
July .....	NA	6	1	1	(s)	2	75	83
August .....	NA	6	1	1	(s)	2	71	80
September .....	NA	7	2	1	(s)	3	52	62
October .....	NA	13	2	2	(s)	4	42	59
November .....	NA	24	3	3	(s)	6	39	69
December .....	NA	44	3	5	(s)	8	54	106
<b>Total</b> .....	NA	256	30	33	1	63	578	897
<b>2021 January</b> .....	NA	48	3	5	(s)	8	56	113
February .....	NA	47	3	5	(s)	9	56	112
<b>2-Month Total</b> .....	NA	96	6	10	(s)	17	113	225
<b>2020 2-Month Total</b> .....	NA	85	7	9	1	17	89	192
<b>2019 2-Month Total</b> .....	NA	97	9	10	(s)	20	111	228

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Hydrocarbon gas liquids.

<sup>e</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 11.6.

<sup>f</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Table 11.3 Carbon Dioxide Emissions From Energy Consumption: Commercial Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum							Retail Electricity <sup>f</sup>	Total <sup>g</sup>
			Distillate Fuel Oil <sup>c</sup>	HGL <sup>d</sup>	Kerosene	Motor Gasoline <sup>e</sup>	Petroleum Coke	Residual Fuel Oil	Total		
<b>1973 Total</b> .....	15	141	47	9	5	6	NA	52	120	334	609
<b>1975 Total</b> .....	14	136	43	8	4	6	NA	39	100	333	583
<b>1980 Total</b> .....	11	141	38	6	3	8	NA	44	98	412	662
<b>1985 Total</b> .....	13	132	46	6	2	7	NA	18	79	480	705
<b>1990 Total</b> .....	12	142	39	6	1	8	0	18	73	566	793
<b>1995 Total</b> .....	11	164	35	7	2	1	(s)	11	56	620	851
<b>2000 Total</b> .....	9	173	36	9	2	3	(s)	7	58	783	1,022
<b>2005 Total</b> .....	9	163	33	8	2	3	(s)	9	55	841	1,069
<b>2006 Total</b> .....	6	154	29	8	1	3	(s)	6	47	835	1,043
<b>2007 Total</b> .....	7	164	28	8	1	4	(s)	6	46	861	1,078
<b>2008 Total</b> .....	8	171	28	10	(s)	3	(s)	6	47	849	1,075
<b>2009 Total</b> .....	7	169	29	9	(s)	3	(s)	6	47	784	1,007
<b>2010 Total</b> .....	7	168	29	9	(s)	3	(s)	5	46	804	1,025
<b>2011 Total</b> .....	6	171	29	9	(s)	3	(s)	4	45	768	990
<b>2012 Total</b> .....	4	157	26	9	(s)	3	(s)	2	40	731	932
<b>2013 Total</b> .....	4	179	25	10	(s)	3	(s)	2	39	736	958
<b>2014 Total</b> .....	4	190	26	10	(s)	4	(s)	1	41	736	970
<b>2015 Total</b> .....	3	176	26	9	(s)	25	(s)	(s)	61	692	932
<b>2016 Total</b> .....	2	171	24	9	(s)	25	(s)	(s)	59	662	894
<b>2017 Total</b> .....	2	174	24	10	(s)	24	(s)	(s)	58	633	867
<b>2018 Total</b> .....	2	193	24	11	(s)	24	(s)	(s)	59	632	886
<b>2019 January</b> .....	(s)	31	3	2	(s)	2	(s)	(s)	7	51	89
February .....	(s)	26	3	1	(s)	2	(s)	(s)	6	44	76
March .....	(s)	23	3	1	(s)	2	(s)	(s)	6	45	74
April .....	(s)	14	2	1	(s)	2	(s)	(s)	5	38	57
May .....	(s)	10	1	1	(s)	2	0	(s)	4	45	60
June .....	(s)	8	1	1	(s)	2	0	(s)	4	49	61
July .....	(s)	8	1	1	(s)	2	0	(s)	4	60	72
August .....	(s)	8	2	1	(s)	2	0	(s)	4	59	71
September .....	(s)	8	1	1	(s)	2	0	(s)	3	53	64
October .....	(s)	12	1	1	(s)	2	0	(s)	4	45	62
November .....	(s)	21	3	1	(s)	2	0	(s)	6	44	72
December .....	(s)	25	3	1	(s)	2	(s)	(s)	7	44	76
<b>Total</b> .....	2	193	24	11	(s)	24	(s)	(s)	60	578	833
<b>2020 January</b> .....	(s)	27	3	1	(s)	2	(s)	(s)	6	42	75
February .....	(s)	24	2	1	(s)	2	(s)	(s)	5	38	68
March .....	(s)	19	2	1	(s)	2	0	(s)	5	37	61
April .....	(s)	13	2	1	(s)	1	0	(s)	4	30	47
May .....	(s)	9	2	1	(s)	2	0	(s)	4	33	47
June .....	(s)	7	1	1	(s)	2	0	(s)	4	43	54
July .....	(s)	7	1	1	(s)	2	0	(s)	3	56	67
August .....	(s)	7	1	1	(s)	2	0	(s)	3	55	65
September .....	(s)	8	1	1	(s)	2	0	(s)	4	45	57
October .....	(s)	11	1	1	(s)	2	0	(s)	4	42	58
November .....	(s)	16	2	1	(s)	2	0	(s)	5	38	59
December .....	(s)	25	2	1	(s)	2	0	(s)	5	43	74
<b>Total</b> .....	1	173	21	11	(s)	21	(s)	(s)	53	504	731
<b>2021 January</b> .....	(s)	27	2	1	(s)	2	0	(s)	5	43	75
February .....	(s)	27	2	1	(s)	2	(s)	(s)	5	44	76
<b>2-Month Total</b> .....	(s)	54	4	3	(s)	3	(s)	(s)	11	86	151
<b>2020 2-Month Total</b> .....	(s)	51	5	3	(s)	4	(s)	(s)	11	80	143
<b>2019 2-Month Total</b> .....	(s)	57	6	3	(s)	4	(s)	(s)	13	95	165

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Hydrocarbon gas liquids.

<sup>e</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>f</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 11.6.

<sup>g</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Table 11.4 Carbon Dioxide Emissions From Energy Consumption: Industrial Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Coal Coke Net Imports	Natural Gas <sup>b</sup>	Petroleum									Retail Elec- tricity <sup>g</sup>	Total <sup>h</sup>
				Distillate Fuel Oil <sup>c</sup>	HGL <sup>d</sup>	Kero- sene	Lubri- cants	Motor Gasoline <sup>e</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>f</sup>	Total		
1973 Total .....	371	-1	533	106	31	11	7	18	54	146	99	473	515	1,892
1975 Total .....	335	2	438	97	30	9	6	16	52	119	94	421	490	1,686
1980 Total .....	289	-4	428	96	52	13	7	11	50	106	131	465	601	1,778
1985 Total .....	255	-2	361	81	54	3	6	15	55	59	83	357	583	1,554
1990 Total .....	258	1	436	84	45	1	7	13	69	32	115	366	638	1,698
1995 Total .....	233	7	492	82	57	1	7	14	69	27	107	364	659	1,755
2000 Total .....	211	7	486	87	61	1	7	11	75	19	107	368	719	1,791
2005 Total .....	182	5	406	92	49	3	6	25	86	22	135	418	672	1,684
2006 Total .....	180	7	408	91	49	2	6	26	85	19	147	425	650	1,669
2007 Total .....	175	3	419	91	50	1	6	21	83	15	143	410	662	1,669
2008 Total .....	168	5	419	98	41	(s)	6	17	79	15	126	382	642	1,615
2009 Total .....	131	-3	395	78	41	(s)	5	16	73	10	107	331	550	1,404
2010 Total .....	152	-1	427	84	42	1	5	17	67	9	115	340	587	1,507
2011 Total .....	146	1	438	90	38	(s)	5	17	64	10	114	339	574	1,498
2012 Total .....	141	(s)	455	93	42	(s)	4	17	69	5	110	341	543	1,481
2013 Total .....	144	-2	472	92	46	(s)	5	17	64	4	116	344	542	1,501
2014 Total .....	143	-2	488	100	45	(s)	5	14	65	3	108	340	543	1,512
2015 Total .....	129	-2	487	85	49	(s)	5	17	66	3	112	337	502	1,454
2016 Total .....	113	-2	497	84	46	(s)	5	17	65	4	120	342	473	1,423
2017 Total .....	112	-3	510	88	48	(s)	5	18	61	4	126	349	461	1,429
2018 Total .....	110	-3	533	91	54	(s)	5	18	62	3	123	357	457	1,455
2019 January .....	9	(s)	50	10	5	(s)	(s)	1	5	(s)	11	33	38	130
February .....	9	(s)	45	8	4	(s)	(s)	1	1	(s)	7	23	33	110
March .....	9	(s)	48	9	4	(s)	(s)	1	5	(s)	10	29	34	120
April .....	8	(s)	44	8	4	(s)	(s)	1	4	(s)	11	29	30	111
May .....	9	(s)	44	8	4	(s)	(s)	2	5	(s)	12	31	34	118
June .....	9	(s)	42	6	5	(s)	(s)	2	7	(s)	10	30	36	116
July .....	8	(s)	43	6	5	(s)	(s)	2	7	(s)	10	30	42	122
August .....	8	(s)	44	5	5	(s)	(s)	2	6	(s)	12	30	41	124
September .....	8	(s)	42	7	5	(s)	(s)	1	4	(s)	11	29	37	117
October .....	9	(s)	45	9	5	(s)	(s)	1	4	(s)	11	32	33	118
November .....	8	(s)	47	7	5	(s)	(s)	1	6	(s)	11	31	34	121
December .....	9	(s)	50	5	5	(s)	(s)	1	6	(s)	11	30	32	121
Total .....	104	-2	543	88	58	(s)	4	18	60	3	127	358	426	1,429
2020 January .....	8	(s)	50	10	4	(s)	(s)	1	4	(s)	11	31	30	119
February .....	8	(s)	47	10	3	(s)	(s)	1	4	(s)	12	31	28	113
March .....	8	(s)	47	9	5	(s)	(s)	1	4	(s)	12	31	28	113
April .....	7	(s)	42	4	3	(s)	(s)	1	3	(s)	10	22	23	93
May .....	6	(s)	41	4	4	(s)	(s)	1	3	(s)	11	24	25	97
June .....	7	(s)	40	4	4	(s)	(s)	1	3	(s)	9	22	30	99
July .....	6	(s)	42	5	5	(s)	(s)	1	4	(s)	9	25	36	110
August .....	7	(s)	43	5	5	(s)	(s)	1	6	(s)	10	29	37	115
September .....	7	(s)	42	7	5	(s)	(s)	1	5	(s)	8	27	31	107
October .....	7	(s)	45	9	6	(s)	(s)	1	4	(s)	8	29	31	112
November .....	8	(s)	46	8	6	(s)	(s)	1	5	(s)	9	30	30	112
December .....	8	(s)	50	8	7	(s)	(s)	1	4	(s)	10	30	32	119
Total .....	87	-1	533	81	59	(s)	4	15	50	2	118	330	363	1,312
2021 January .....	8	(s)	50	10	6	(s)	(s)	1	4	(s)	8	30	32	120
February .....	5	(s)	42	8	3	(s)	(s)	1	2	(s)	7	22	32	101
2-Month Total .....	13	-1	92	18	9	(s)	1	2	6	(s)	15	52	65	221
2020 2-Month Total .....	17	(s)	97	20	7	(s)	1	3	8	(s)	23	62	58	233
2019 2-Month Total .....	18	(s)	96	19	10	(s)	1	3	6	1	18	57	70	240

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Hydrocarbon gas liquids.

<sup>e</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>f</sup> Aviation gasoline blending components, crude oil, motor gasoline blending components, petrochemical feedstocks, special naphthas, still gas, unfinished oils, waxes, and miscellaneous petroleum products.

<sup>g</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 11.6.

<sup>h</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

(s)=Less than 0.5 million metric tons and greater than -0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption, plus the relatively small amount of emissions from the non-combustion use of fossil fuels. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Table 11.5 Carbon Dioxide Emissions From Energy Consumption: Transportation Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

		Coal	Natural Gas <sup>b</sup>	Petroleum							Retail Elec- tricity <sup>f</sup>	Total <sup>g</sup>
				Aviation Gasoline	Distillate Fuel Oil <sup>c</sup>	HGL <sup>d</sup>	Jet Fuel	Lubri- cants	Motor Gasoline <sup>e</sup>	Residual Fuel Oil		
1973 Total	(s)	39	6	163	3	152	6	886	57	1,273	2	1,315
1975 Total	(s)	32	5	155	3	145	6	889	56	1,258	2	1,292
1980 Total	(h)	34	4	204	1	155	6	881	110	1,363	2	1,400
1985 Total	(h)	28	3	232	2	178	6	908	62	1,391	3	1,421
1990 Total	(h)	36	3	268	1	223	7	967	80	1,548	3	1,588
1995 Total	(h)	38	3	307	1	222	6	1,026	72	1,637	3	1,679
2000 Total	(h)	36	3	377	1	254	7	1,119	70	1,830	4	1,870
2005 Total	(h)	33	2	444	2	246	6	1,180	66	1,946	5	1,984
2006 Total	(h)	33	2	467	2	240	5	1,187	71	1,974	5	2,012
2007 Total	(h)	35	2	469	1	238	6	1,183	78	1,977	5	2,018
2008 Total	(h)	37	2	424	3	226	5	1,119	73	1,852	5	1,893
2009 Total	(h)	38	2	400	2	204	5	1,107	62	1,782	5	1,825
2010 Total	(h)	38	2	423	(s)	210	6	1,089	70	1,800	5	1,843
2011 Total	(h)	39	2	431	(s)	209	6	1,057	61	1,766	4	1,809
2012 Total	(h)	41	2	411	(s)	206	5	1,051	53	1,728	4	1,773
2013 Total	(h)	47	2	416	(s)	210	5	1,066	46	1,745	4	1,796
2014 Total	(h)	40	2	435	(s)	216	6	1,077	35	1,770	4	1,815
2015 Total	(h)	40	1	441	(s)	227	6	1,083	37	1,795	4	1,839
2016 Total	(h)	40	1	431	(s)	237	6	1,102	49	1,827	4	1,871
2017 Total	(h)	42	1	436	(s)	247	5	1,099	52	1,842	4	1,888
2018 Total	(h)	51	2	460	(s)	250	5	1,099	48	1,864	4	1,919
2019 January	(h)	6	(s)	36	(s)	20	(s)	88	4	149	(s)	155
February	(h)	5	(s)	34	(s)	18	(s)	82	3	137	(s)	143
March	(h)	5	(s)	38	(s)	21	(s)	92	3	155	(s)	160
April	(h)	4	(s)	38	(s)	21	1	91	2	154	(s)	158
May	(h)	4	(s)	41	(s)	22	(s)	95	2	160	(s)	164
June	(h)	4	(s)	40	(s)	22	(s)	94	4	160	(s)	164
July	(h)	4	(s)	41	(s)	23	(s)	95	4	164	(s)	169
August	(h)	4	(s)	41	(s)	23	(s)	99	4	168	(s)	172
September	(h)	4	(s)	39	(s)	21	(s)	89	4	153	(s)	157
October	(h)	4	(s)	41	(s)	22	(s)	93	4	160	(s)	165
November	(h)	5	(s)	37	(s)	21	(s)	89	3	150	(s)	155
December	(h)	6	(s)	36	(s)	23	(s)	89	4	152	(s)	158
Total	(h)	55	2	462	(s)	256	5	1,095	42	1,862	3	1,920
2020 January	(h)	6	(s)	34	(s)	21	(s)	87	3	146	(s)	152
February	(h)	5	(s)	32	(s)	19	(s)	84	2	137	(s)	143
March	(h)	5	(s)	36	(s)	17	(s)	78	1	133	(s)	138
April	(h)	4	(s)	34	(s)	8	(s)	57	1	101	(s)	105
May	(h)	4	(s)	35	(s)	7	(s)	72	1	116	(s)	120
June	(h)	4	(s)	36	(s)	9	(s)	80	3	128	(s)	132
July	(h)	4	(s)	38	(s)	12	(s)	84	4	139	(s)	144
August	(h)	4	(s)	38	(s)	13	(s)	85	4	141	(s)	145
September	(h)	4	(s)	36	(s)	11	(s)	83	4	135	(s)	139
October	(h)	4	(s)	38	(s)	13	(s)	83	4	138	(s)	142
November	(h)	4	(s)	35	(s)	14	(s)	77	3	129	(s)	133
December	(h)	6	(s)	35	(s)	14	(s)	78	2	130	(s)	136
Total	(h)	54	1	428	(s)	159	4	948	33	1,573	3	1,630
2021 January	(h)	6	(s)	35	(s)	14	(s)	77	3	130	(s)	136
February	(h)	5	(s)	32	(s)	12	(s)	70	3	118	(s)	123
2-Month Total	(h)	11	(s)	67	(s)	26	1	147	6	247	(s)	259
2020 2-Month Total	(h)	11	(s)	66	(s)	40	1	171	5	284	(s)	295
2019 2-Month Total	(h)	11	(s)	70	(s)	38	1	170	7	286	1	298

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Hydrocarbon gas liquids.

<sup>e</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>f</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 11.6.

<sup>g</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

<sup>h</sup> Beginning in 1978, the small amounts of coal consumed for transportation are reported as industrial sector consumption.

(s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption, plus the relatively small amount of emissions from the non-combustion use of fossil fuels. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Table 11.6 Carbon Dioxide Emissions From Energy Consumption: Electric Power Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum				Geo-thermal	Non-Biomass Waste <sup>d</sup>	Total <sup>e</sup>
			Distillate Fuel Oil <sup>c</sup>	Petroleum Coke	Residual Fuel Oil	Total			
<b>1973 Total</b> .....	<b>812</b>	<b>199</b>	<b>20</b>	<b>2</b>	<b>254</b>	<b>276</b>	<b>NA</b>	<b>NA</b>	<b>1,286</b>
<b>1975 Total</b> .....	<b>824</b>	<b>172</b>	<b>17</b>	<b>(s)</b>	<b>231</b>	<b>248</b>	<b>NA</b>	<b>NA</b>	<b>1,244</b>
<b>1980 Total</b> .....	<b>1,137</b>	<b>200</b>	<b>12</b>	<b>1</b>	<b>194</b>	<b>207</b>	<b>NA</b>	<b>NA</b>	<b>1,544</b>
<b>1985 Total</b> .....	<b>1,367</b>	<b>166</b>	<b>6</b>	<b>1</b>	<b>79</b>	<b>86</b>	<b>NA</b>	<b>NA</b>	<b>1,619</b>
<b>1990 Total</b> .....	<b>1,548</b>	<b>176</b>	<b>7</b>	<b>3</b>	<b>92</b>	<b>102</b>	<b>(s)</b>	<b>6</b>	<b>1,831</b>
<b>1995 Total</b> .....	<b>1,661</b>	<b>228</b>	<b>8</b>	<b>8</b>	<b>45</b>	<b>61</b>	<b>(s)</b>	<b>10</b>	<b>1,960</b>
<b>2000 Total</b> .....	<b>1,927</b>	<b>281</b>	<b>13</b>	<b>10</b>	<b>69</b>	<b>91</b>	<b>(s)</b>	<b>10</b>	<b>2,310</b>
<b>2005 Total</b> .....	<b>1,984</b>	<b>319</b>	<b>8</b>	<b>24</b>	<b>69</b>	<b>101</b>	<b>(s)</b>	<b>11</b>	<b>2,416</b>
<b>2006 Total</b> .....	<b>1,954</b>	<b>338</b>	<b>5</b>	<b>21</b>	<b>28</b>	<b>55</b>	<b>(s)</b>	<b>12</b>	<b>2,358</b>
<b>2007 Total</b> .....	<b>1,987</b>	<b>372</b>	<b>6</b>	<b>17</b>	<b>31</b>	<b>54</b>	<b>(s)</b>	<b>11</b>	<b>2,425</b>
<b>2008 Total</b> .....	<b>1,959</b>	<b>362</b>	<b>5</b>	<b>15</b>	<b>19</b>	<b>39</b>	<b>(s)</b>	<b>12</b>	<b>2,373</b>
<b>2009 Total</b> .....	<b>1,741</b>	<b>373</b>	<b>5</b>	<b>13</b>	<b>14</b>	<b>33</b>	<b>(s)</b>	<b>11</b>	<b>2,158</b>
<b>2010 Total</b> .....	<b>1,828</b>	<b>399</b>	<b>6</b>	<b>14</b>	<b>12</b>	<b>32</b>	<b>(s)</b>	<b>11</b>	<b>2,270</b>
<b>2011 Total</b> .....	<b>1,723</b>	<b>409</b>	<b>5</b>	<b>14</b>	<b>7</b>	<b>26</b>	<b>(s)</b>	<b>11</b>	<b>2,170</b>
<b>2012 Total</b> .....	<b>1,511</b>	<b>493</b>	<b>4</b>	<b>9</b>	<b>6</b>	<b>19</b>	<b>(s)</b>	<b>11</b>	<b>2,034</b>
<b>2013 Total</b> .....	<b>1,571</b>	<b>444</b>	<b>4</b>	<b>13</b>	<b>6</b>	<b>23</b>	<b>(s)</b>	<b>11</b>	<b>2,050</b>
<b>2014 Total</b> .....	<b>1,569</b>	<b>444</b>	<b>6</b>	<b>12</b>	<b>7</b>	<b>26</b>	<b>(s)</b>	<b>11</b>	<b>2,050</b>
<b>2015 Total</b> .....	<b>1,350</b>	<b>527</b>	<b>5</b>	<b>11</b>	<b>7</b>	<b>24</b>	<b>(s)</b>	<b>11</b>	<b>1,913</b>
<b>2016 Total</b> .....	<b>1,241</b>	<b>547</b>	<b>4</b>	<b>12</b>	<b>6</b>	<b>22</b>	<b>(s)</b>	<b>11</b>	<b>1,821</b>
<b>2017 Total</b> .....	<b>1,206</b>	<b>507</b>	<b>4</b>	<b>10</b>	<b>5</b>	<b>19</b>	<b>(s)</b>	<b>11</b>	<b>1,743</b>
<b>2018 Total</b> .....	<b>1,151</b>	<b>579</b>	<b>6</b>	<b>10</b>	<b>6</b>	<b>22</b>	<b>(s)</b>	<b>11</b>	<b>1,764</b>
<b>2019 January</b> .....	<b>101</b>	<b>46</b>	<b>(s)</b>	<b>1</b>	<b>1</b>	<b>2</b>	<b>(s)</b>	<b>1</b>	<b>150</b>
February .....	81	43	(s)	1	(s)	1	(s)	1	126
March .....	80	45	(s)	1	(s)	1	(s)	1	126
April .....	60	40	(s)	(s)	(s)	1	(s)	1	103
May .....	72	46	(s)	1	(s)	2	(s)	1	121
June .....	80	54	(s)	1	(s)	1	(s)	1	136
July .....	101	69	(s)	1	(s)	2	(s)	1	172
August .....	95	70	(s)	1	(s)	2	(s)	1	167
September .....	85	59	(s)	1	(s)	1	(s)	1	147
October .....	68	51	(s)	(s)	(s)	1	(s)	1	121
November .....	76	45	(s)	(s)	(s)	1	(s)	1	123
December .....	73	50	(s)	1	(s)	1	(s)	1	125
<b>Total</b> .....	<b>973</b>	<b>618</b>	<b>4</b>	<b>8</b>	<b>5</b>	<b>16</b>	<b>(s)</b>	<b>11</b>	<b>1,618</b>
<b>2020 January</b> .....	<b>66</b>	<b>51</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>120</b>
February .....	58	48	(s)	1	(s)	1	(s)	1	108
March .....	52	48	(s)	1	(s)	1	(s)	1	102
April .....	43	42	(s)	1	(s)	1	(s)	1	86
May .....	48	46	(s)	1	(s)	1	(s)	1	96
June .....	66	57	(s)	1	(s)	2	(s)	1	126
July .....	90	75	(s)	1	(s)	2	(s)	1	168
August .....	91	70	(s)	1	(s)	2	(s)	1	164
September .....	70	57	(s)	(s)	(s)	1	(s)	1	129
October .....	61	52	(s)	(s)	(s)	1	(s)	1	115
November .....	62	42	(s)	1	(s)	1	(s)	1	106
December .....	79	48	(s)	1	(s)	1	(s)	1	129
<b>Total</b> .....	<b>786</b>	<b>635</b>	<b>3</b>	<b>8</b>	<b>4</b>	<b>16</b>	<b>(s)</b>	<b>11</b>	<b>1,448</b>
<b>2021 January</b> .....	<b>82</b>	<b>47</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>(s)</b>	<b>1</b>	<b>132</b>
February .....	87	43	1	1	(s)	2	(s)	1	133
<b>2-Month Total</b> .....	<b>169</b>	<b>90</b>	<b>1</b>	<b>2</b>	<b>1</b>	<b>3</b>	<b>(s)</b>	<b>2</b>	<b>264</b>
<b>2020 2-Month Total</b> .....	<b>124</b>	<b>99</b>	<b>1</b>	<b>1</b>	<b>1</b>	<b>3</b>	<b>(s)</b>	<b>2</b>	<b>227</b>
<b>2019 2-Month Total</b> .....	<b>183</b>	<b>89</b>	<b>1</b>	<b>2</b>	<b>1</b>	<b>3</b>	<b>(s)</b>	<b>2</b>	<b>277</b>

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Municipal solid waste from non-biogenic sources, and tire-derived fuels. Through 1994, also includes blast furnace gas, and other manufactured and waste gases derived from fossil fuels.

<sup>e</sup> Excludes emissions from biomass energy consumption. See Table 11.7.

NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy

consumption. See "Section 11 Methodology and Sources" at end of section.

• See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 11.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Table 11.7 Carbon Dioxide Emissions From Biomass Energy Consumption**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	By Source					By Sector					
	Wood <sup>b</sup>	Biomass Waste <sup>c</sup>	Fuel Ethanol <sup>d</sup>	Bio-diesel	Total	Residential	Commercial <sup>e</sup>	Industrial <sup>f</sup>	Transportation	Electric Power <sup>g</sup>	Total
<b>1973 Total</b> .....	143	(s)	NA	NA	143	33	1	109	NA	(s)	143
<b>1975 Total</b> .....	140	(s)	NA	NA	141	40	1	100	NA	(s)	141
<b>1980 Total</b> .....	232	(s)	NA	NA	232	80	2	150	NA	(s)	232
<b>1985 Total</b> .....	252	14	3	NA	270	95	2	168	3	1	270
<b>1990 Total</b> .....	208	24	4	NA	237	54	8	147	4	23	237
<b>1995 Total</b> .....	222	30	8	NA	260	49	9	166	8	28	260
<b>2000 Total</b> .....	212	27	9	NA	248	39	9	161	9	29	248
<b>2005 Total</b> .....	200	37	23	1	261	40	10	150	23	37	261
<b>2006 Total</b> .....	197	36	31	2	266	36	9	151	33	38	266
<b>2007 Total</b> .....	196	37	39	3	276	39	9	146	41	39	276
<b>2008 Total</b> .....	193	39	55	3	290	44	10	139	57	40	290
<b>2009 Total</b> .....	182	41	62	3	288	47	10	125	64	41	288
<b>2010 Total</b> .....	208	42	73	2	325	51	10	149	74	42	325
<b>2011 Total</b> .....	208	42	73	8	331	49	11	151	80	40	331
<b>2012 Total</b> .....	202	42	73	8	325	41	10	153	80	42	325
<b>2013 Total</b> .....	219	45	75	13	353	54	11	158	87	43	353
<b>2014 Total</b> .....	225	47	76	13	361	54	12	158	88	49	361
<b>2015 Total</b> .....	217	47	79	14	357	48	13	157	90	48	357
<b>2016 Total</b> .....	209	46	81	20	355	42	14	155	98	47	355
<b>2017 Total</b> .....	205	45	82	19	351	40	14	152	98	47	351
<b>2018 Total</b> .....	212	44	82	18	356	49	14	151	97	46	356
<b>2019 January</b> .....	18	4	6	1	30	4	1	13	7	4	30
February .....	17	3	6	1	27	4	1	12	7	3	27
March .....	18	3	7	1	29	4	1	13	8	3	29
April .....	17	3	7	1	28	4	1	12	8	3	28
May .....	17	3	7	2	30	4	1	12	9	3	30
June .....	17	3	7	1	29	4	1	12	8	3	29
July .....	18	3	7	2	30	4	1	13	8	4	30
August .....	18	3	7	2	30	4	1	13	8	4	30
September .....	17	3	7	1	28	4	1	12	8	3	28
October .....	17	3	7	1	29	4	1	12	8	3	29
November .....	17	3	7	1	29	4	1	12	8	3	29
December .....	18	4	7	1	30	4	1	13	8	4	30
<b>Total</b> .....	210	40	83	17	350	51	13	147	97	41	350
<b>2020 January</b> .....	17	4	7	1	29	4	1	13	8	4	29
February .....	16	3	6	1	27	3	1	12	7	3	27
March .....	17	3	6	1	27	4	1	12	7	3	27
April .....	16	3	4	1	24	4	1	12	5	3	24
May .....	17	3	6	1	27	4	1	12	7	3	27
June .....	16	3	6	1	26	4	1	11	7	3	26
July .....	16	3	6	2	28	4	1	12	8	3	28
August .....	16	3	6	2	28	4	1	12	8	4	28
September .....	16	3	6	2	27	4	1	12	8	3	27
October .....	16	3	6	2	27	4	1	12	7	3	27
November .....	16	3	6	1	27	4	1	12	7	3	27
December .....	17	3	6	2	29	4	1	13	8	3	29
<b>Total</b> .....	197	39	72	18	325	43	13	144	86	39	325
<b>2021 January</b> .....	17	3	6	1	27	4	1	13	6	3	27
February .....	15	3	5	1	25	3	1	11	6	3	25
<b>2-Month Total</b> .....	32	6	11	2	52	7	2	24	12	7	52
<b>2020 2-Month Total</b> .....	33	7	13	3	56	7	2	24	15	7	56
<b>2019 2-Month Total</b> .....	35	7	13	2	57	8	2	25	15	7	57

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Wood and wood-derived fuels.

<sup>c</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass.

<sup>d</sup> Fuel ethanol minus denaturant.

<sup>e</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>f</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>g</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Carbon dioxide emissions from biomass energy consumption are excluded from the energy-related carbon dioxide emissions reported in Tables 11.1–11.6. See Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Data are estimates. See "Section 11 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> (Excel and CSV files) for all available annual and monthly data beginning in 1973.

Sources: See end of section.

**Note 1. Emissions of Carbon Dioxide and Other Greenhouse Gases.** Greenhouse gases are those gases—such as water vapor, carbon dioxide (CO<sub>2</sub>), methane, nitrous oxide, hydrofluorocarbons (HFCs), perfluorocarbons (PFCs), and sulfur hexafluoride—that are transparent to solar (short-wave) radiation but opaque to long-wave (infrared) radiation, thus preventing long-wave radiant energy from leaving Earth's atmosphere. The net effect is a trapping of absorbed radiation and a tendency to warm the planet's surface.

The vast majority of U.S. CO<sub>2</sub> emissions come from fossil fuel combustion, with smaller amounts from the non-combustion use of fossil fuels, as well as from electricity generation using geothermal energy and non-biomass waste. Other sources of CO<sub>2</sub> emissions include industrial processes, such as cement and limestone production. Data in the U.S. Energy Information Administration's (EIA) *Monthly Energy Review* (MER) Tables 11.1–11.6 are estimates for U.S. CO<sub>2</sub> emissions from energy consumption, plus the non-combustion use of fossil fuels (excluded are estimates for CO<sub>2</sub> emissions from biomass energy consumption, which appear in MER Table 11.7).

For annual U.S. estimates of CO<sub>2</sub> emissions from all sources, as well as emissions for other greenhouse gases, see the U.S. Environmental Protection Agency's *Inventory of U.S. Greenhouse Gas Emissions and Sinks* reports at <https://www.epa.gov/ghgemissions/inventory-us-greenhouse-gas-emissions-and-sinks>.

**Note 2. Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion.** Carbon dioxide (CO<sub>2</sub>) emissions from the combustion of biomass to produce energy are excluded from the energy-related CO<sub>2</sub> emissions reported in MER Tables 11.1–11.6, but appear in MER Table 11.7. According to current international convention (see the Intergovernmental Panel on Climate Change's "2006 IPCC Guidelines for National Greenhouse Gas Inventories"), carbon released through biomass combustion is excluded from reported energy-related emissions. The release of carbon from biomass combustion is assumed to be balanced by the uptake of carbon when the feedstock is grown, resulting in zero net emissions over some period of time. (This is not to say that biomass energy is carbon-neutral. Energy inputs are required in order to grow, fertilize, and harvest the feedstock and to produce and process the biomass into fuels.)

However, analysts have debated whether increased use of biomass energy may result in a decline in terrestrial carbon stocks, leading to a net positive release of carbon rather than the zero net release assumed by its exclusion from reported energy-related emissions. For example, the clearing of forests for biofuel crops could result in an initial release of carbon that is not fully recaptured in subsequent use of the land for agriculture.

To reflect the potential net emissions, the international convention for greenhouse gas inventories is to report biomass emissions in the category "agriculture, forestry, and other land use," usually based on estimates of net changes in carbon stocks over time.

This indirect accounting of CO<sub>2</sub> emissions from biomass can potentially lead to confusion in accounting for and understanding the flow of CO<sub>2</sub> emissions within energy and non-energy systems. In recognition of this issue, reporting of CO<sub>2</sub> emissions from biomass combustion alongside other energy-related CO<sub>2</sub> emissions offers an alternative accounting treatment. It is important, however, to avoid misinterpreting emissions from fossil energy and biomass energy sources as necessarily additive. Instead, the combined total of direct CO<sub>2</sub> emissions from biomass and energy-related CO<sub>2</sub> emissions implicitly assumes that none of the carbon emitted was previously or subsequently reabsorbed in terrestrial sinks or that other emissions sources offset any such sequestration.

## Section 11 Methodology and Sources

To estimate carbon dioxide emissions from energy consumption for the *Monthly Energy Review* (MER), Tables 11.1–11.7, the U.S. Energy Information Administration (EIA) uses the following methodology and sources:

### *Step 1. Determine Fuel Consumption*

Coal—Coal sectoral (residential, commercial, coke plants, other industrial, transportation, electric power) consumption data in thousand short tons are from MER Table 6.2. Coal sectoral consumption data are converted to trillion Btu by multiplying by the coal heat content factors in MER Table A5.

Coal Coke Net Imports—Coal coke net imports data in trillion Btu are derived from coal coke imports and exports data in MER Tables 1.4a and 1.4b.

Natural Gas (excluding supplemental gaseous fuels)—Natural gas sectoral consumption data in trillion Btu are from MER Tables 2.2–2.6.

Petroleum—Total and sectoral consumption (product supplied) data in thousand barrels per day for asphalt and road oil, aviation gasoline, distillate fuel oil, hydrocarbon gas liquids (HGL), jet fuel, kerosene, lubricants, motor gasoline, petroleum coke, and residual fuel oil are from MER Tables 3.5 and 3.7a–3.7c. For the component products of HGL (ethane/ethylene, propane/propylene, normal butane/butylene, isobutane/isobutylene, and natural gasoline) and "other petroleum" (aviation gasoline blending components, crude oil, motor gasoline blending components, naphthas for petrochemical feedstock use, other oils for petrochemical feedstock use, special naphthas, still gas, unfinished oils, waxes, and miscellaneous petroleum products), consumption (product supplied) data in thousand barrels per day are from EIA's *Petroleum Supply Annual* (PSA), *Petroleum Supply Monthly* (PSM), and earlier publications (see sources for MER Table 3.5). Petroleum consumption data by product are converted to trillion Btu by multiplying by the petroleum heat content factors in MER Tables A1 and A3.

Biomass—Sectoral consumption data in trillion Btu for wood, biomass waste, fuel ethanol (minus denaturant), and biodiesel are from MER Tables 10.2a–10.2c.

### ***Step 2. Remove Biofuels From Petroleum***

Distillate Fuel Oil—Beginning in 2009, the distillate fuel oil data (for total and transportation sector) in Step 1 include biodiesel and other renewable diesel fuel, which are non-fossil renewable fuels.

2009–2011: To remove the biodiesel portion from distillate fuel oil, data for biodiesel consumption (calculated using data from EIA, EIA-22M, "Monthly Biodiesel Production Survey") and biomass-based diesel fuel data (from EIA-810, "Monthly Refinery Report," EIA-812, "Monthly Product Pipeline Report," and EIA-815, "Monthly Bulk Terminal and Blender Report") are converted to trillion Btu by multiplying by the biodiesel heat content factor in MER Table A1, and then subtracted from the distillate fuel oil consumption values. To remove the other renewable diesel fuel portion from distillate fuel oil, data for refinery and blender net inputs (from EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report") are converted to trillion Btu by multiplying by the other renewable diesel fuel heat content factor in MER Table A1, and then subtracted from the distillate fuel oil consumption values.

2012–2020: To remove the biodiesel portion from distillate fuel oil, data for biodiesel consumption (from MER Table 10.4) is subtracted from the distillate fuel oil consumption values. To remove the other renewable diesel fuel portion from distillate fuel oil, data for refinery and blender net inputs (from EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report") are converted to trillion Btu by multiplying by the other renewable diesel fuel heat content factor in MER Table A1, and then subtracted from the distillate fuel oil consumption values.

2021 forward: To remove the biodiesel and other renewable diesel fuel portions from distillate fuel oil, data for refinery and blender net inputs (from EIA-810, "Monthly Refinery Report," and EIA-815, "Monthly Bulk Terminal and Blender Report") are converted to trillion Btu by multiplying by the biodiesel and other renewable diesel fuel heat content factors in MER Table A1, and then subtracted from the distillate fuel oil consumption values.

Motor Gasoline—Beginning in 1993, the motor gasoline data (for total, commercial sector, industrial sector, and transportation sector) in Step 1 include fuel ethanol, a non-fossil renewable fuel. To remove the fuel ethanol portion from motor gasoline, data in trillion Btu for fuel ethanol consumption (from MER Tables 10.2a, 10.2b, and 10.3) are subtracted from the motor gasoline consumption values. (Note that about 2% of fuel ethanol is fossil-based petroleum denaturant, to make the fuel ethanol undrinkable. For 1993–2008, petroleum denaturant is double counted in the PSA product supplied statistics, in both the original product category—e.g., natural gasoline—and also in the finished motor gasoline category; for this time period for MER Section 11, petroleum denaturant is removed along with the fuel ethanol from motor gasoline, but left in the original product. Beginning in 2009, petroleum denaturant is counted only in the



PSA/PSM product supplied statistics for motor gasoline; for this time period for MER Section 11, petroleum denaturant is left in motor gasoline.)

### ***Step 3. Remove Carbon Sequestered by Non-Combustion Use***

The following fuels have industrial non-combustion uses as chemical feedstocks and other products: coal, natural gas, asphalt and road oil, distillate fuel oil, hydrocarbon gas liquids (ethane/ethylene, propane/propylene, normal butane/butylene, isobutane/isobutylene, and natural gasoline), lubricants (which have industrial and transportation non-combustion uses), naphthas for petrochemical feedstock use, other oils for petrochemical feedstock use, petroleum coke, residual fuel oil, special naphthas, still gas, waxes, and miscellaneous petroleum products. In the non-combustion use of these fuels, some of the carbon is sequestered, and is thus subtracted from the fuel consumption values in Steps 1 and 2.

Estimates of annual non-combustion use and associated carbon sequestration are developed by EIA using the methodology detailed in "Documentation for *Emissions of Greenhouse Gases in the United States 2008*" at [https://www.eia.gov/environment/archive/1605/ggrpt/documentation/pdf/0638\\_2008.pdf](https://www.eia.gov/environment/archive/1605/ggrpt/documentation/pdf/0638_2008.pdf).

To obtain monthly estimates of non-combustion use and associated carbon sequestration, monthly patterns for industrial consumption and product supplied data series are used. For coal non-combustion use, the monthly pattern for coke plants coal consumption from MER Table 6.2 is used. For natural gas, the monthly pattern for other industrial non-CHP natural gas consumption from MER Table 4.3 is used. For distillate fuel oil, petroleum coke, and residual fuel oil, the monthly patterns for industrial consumption from MER Table 3.7b are used. For the other petroleum products, the monthly patterns for product supplied from the PSA and PSM are used. See Tables 1.11a and 1.11b for estimates of fossil fuel non-combustion uses.

### ***Step 4. Determine Carbon Dioxide Emissions From Energy Consumption***

Carbon dioxide (CO<sub>2</sub>) emissions data in million metric tons are calculated by multiplying consumption values in trillion Btu from Steps 1 and 2 (minus the carbon sequestered in non-combustion use in Step 3) by the CO<sub>2</sub> emissions factors at [http://www.eia.gov/environment/archive/1605/ggrpt/excel/CO2\\_coeffs\\_09\\_v2.xls](http://www.eia.gov/environment/archive/1605/ggrpt/excel/CO2_coeffs_09_v2.xls).

Coal—CO<sub>2</sub> emissions for coal are calculated for each sector (residential, commercial, coke plants, other industrial, transportation, electric power). Total coal emissions are the sum of the sectoral coal emissions.

Coal Coke Net Imports—CO<sub>2</sub> emissions for coal coke net imports are calculated.

Natural Gas—CO<sub>2</sub> emissions for natural gas are calculated for each sector (residential, commercial, industrial, transportation, electric power). Total natural gas emissions are the sum of the sectoral natural gas emissions.

Petroleum—CO<sub>2</sub> emissions are calculated for each petroleum product. Total petroleum emissions are the sum of the product emissions. Total HGL emissions are the sum of the emissions for the component products (ethane/ethylene, propane/propylene, normal butane/butylene, isobutane/isobutylene, and natural gasoline); residential, commercial, and transportation sector HGL emissions are estimated by multiplying consumption values in trillion Btu from MER Tables 3.8a and 3.8c by the propane emissions factor; industrial sector HGL emissions are estimated as total HGL emissions minus emissions by the other sectors.

Geothermal and Non-Biomass Waste—Annual CO<sub>2</sub> emissions data for geothermal and non-biomass waste are EIA estimates based on Form EIA-923, "Power Plant Operations Report" (and predecessor forms). Monthly estimates are created by dividing the annual data by the number of days in the year and then multiplying by the number of days in the month. (Annual estimates for the current year are set equal to those of the previous year.)

Biomass—CO<sub>2</sub> emissions for wood, biomass waste, fuel ethanol (minus denaturant), and biodiesel are calculated for each sector. Total emissions for each biomass fuel are the sum of the sectoral emissions. The following factors, in million metric tons CO<sub>2</sub> per quadrillion Btu, are used: wood—93.80; biomass waste—90.70; fuel ethanol—68.44; and biodiesel—73.84. For 1973–1988, the biomass portion of waste in MER Tables 10.2a–10.2c is estimated as 67%; for 1989–2000, the biomass portion of waste is estimated as 67% in 1989 to 58% in 2000, based on the biogenic shares of

total municipal solid waste shown in EIA's "Methodology for Allocating Municipal Solid Waste to Biogenic and Non-Biogenic Energy," Table 1 at <http://www.eia.gov/totalenergy/data/monthly/pdf/historical/msw.pdf>.

# Appendix A

## British Thermal Unit Conversion Factors

---

## British Thermal Unit Conversion Factors

The thermal conversion factors presented in the following tables can be used to estimate the heat content in British thermal units (Btu) of a given amount of energy measured in physical units, such as barrels or cubic feet. For example, 10 barrels of asphalt has a heat content of approximately 66.36 million Btu (10 barrels x 6.636 million Btu per barrel = 66.36 million Btu).

The heat content rates (i.e., thermal conversion factors) provided in this section represent the gross (or higher or upper) energy content of the fuels. Gross heat content rates are applied in all Btu calculations for the *Monthly Energy Review* and are commonly used in energy calculations in the United States; net (or lower) heat content rates are typically used in European energy calculations. The difference between the two rates is the amount of energy that is consumed to vaporize water that is created during the combustion process. Generally, the difference ranges from 2% to 10%, depending on the specific fuel and its hydrogen content. Some fuels, such as unseasoned wood, can be more than 40% different in their gross and net heat content rates. See "Heat Content" and "British Thermal Unit (Btu)" in the Glossary for more information.

In general, the annual thermal conversion factors presented in Tables A2 through A6 are computed from final annual data or from the best available data and labeled "preliminary." Often, the current year's factors are labeled "estimate," and are set equal to the previous year's values until data become available to calculate the factors. The source of each factor is described in the section entitled "Thermal Conversion Factor Source Documentation," which follows Table A6 in this appendix.

**Table A1. Approximate Heat Content of Petroleum and Other Liquids**  
(Million Btu per Barrel, Except as Noted)

Commodity	Heat Content	Commodity	Heat Content
Asphalt and Road Oil	6.636	Kerosene	5.670
Aviation Gasoline (Finished)	5.048	Lubricants	6.065
Aviation Gasoline Blending Components	5.048	Motor Gasoline (Finished)—see Tables A2 and A3	
Biodiesel (Biomass-Based Diesel Fuel)	5.359	Motor Gasoline Blending Components (MGBC)	
Crude Oil—see Table A2		Through 2006	5.253
Distillate Fuel Oil—see Table A3 for averages		Beginning in 2007	5.222
15 ppm sulfur and under	5.770	Other Renewable Diesel Fuel	5.494
Greater than 15 ppm to 500 ppm sulfur	5.817	Other Renewable Fuels	5.359
Greater than 500 ppm sulfur	5.825	Oxygenates (excluding Fuel Ethanol)	4.247
Fuel Ethanol—see Table A3		Petrochemical Feedstocks	
Hydrocarbon Gas Liquids		Naphtha Less Than 401°F	5.248
Natural Gas Liquids		Other Oils Equal to or Greater Than 401°F	5.825
Ethane	2.783	Petroleum Coke—see Table A3 for averages	
Propane	3.841	Total, through 2003	6.024
Normal Butane	4.353	Catalyst, beginning in 2004	<sup>a</sup> 6.287
Isobutane	4.183	Marketable, beginning in 2004	5.719
Natural Gasoline (Pentanes Plus)	4.638	Residual Fuel Oil	6.287
Refinery Olefins		Special Naphthas	5.248
Ethylene	2.436	Still Gas	
Propylene	3.835	Through 2015	<sup>b</sup> 6.000
Butylene	4.377	Beginning in 2016	<sup>a</sup> 6.287
Isobutylene	4.355	Unfinished Oils	5.825
Hydrogen	<sup>c</sup> 6.287	Waxes	5.537
Jet Fuel, Kerosene Type	5.670	Miscellaneous Products	5.796
Jet Fuel, Naphtha Type	5.355	Other Hydrocarbons	5.825

<sup>a</sup> Per residual fuel oil equivalent barrel (6.287 million Btu per barrel).

<sup>b</sup> Per fuel oil equivalent barrel (6.000 million Btu per barrel).

<sup>c</sup> Hydrogen has a gross heat content of 323.6 Btu per standard cubic foot (at 60 degrees Fahrenheit and 1 atmosphere), and 6.287 million Btu per residual fuel oil equivalent barrel. For hydrogen, barrels can be converted to standard cubic feet by multiplying by 19,426 standard cubic feet per barrel of residual fuel oil equivalent.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A2. Approximate Heat Content of Petroleum Production, Imports, and Exports**  
(Million Btu per Barrel)

	Production		Imports				Exports			
			Crude Oil <sup>a</sup>	Petroleum Products		Total <sup>d</sup>	Crude Oil <sup>a</sup>	Petroleum Products		Total <sup>d</sup>
	Crude Oil <sup>a</sup>	Natural Gas Plant Liquids <sup>b</sup>		Motor Gasoline <sup>c</sup>	Total Products <sup>d</sup>			Motor Gasoline <sup>e</sup>	Total Products <sup>d</sup>	
1950 .....	5.800	4.470	5.943	5.253	6.263	6.080	5.800	5.253	5.751	5.766
1955 .....	5.800	4.346	5.924	5.253	6.234	6.040	5.800	5.253	5.765	5.768
1960 .....	5.800	4.253	5.911	5.253	6.161	6.021	5.800	5.253	5.835	5.834
1965 .....	5.800	4.197	5.872	5.253	6.123	5.997	5.800	5.253	5.742	5.743
1970 .....	5.800	4.090	5.822	5.253	6.088	5.985	5.800	5.253	5.811	5.810
1975 .....	5.800	3.923	5.821	5.253	5.935	5.858	5.800	5.253	5.747	5.748
1980 .....	5.800	<sup>b</sup> 3.864	5.812	5.253	5.748	5.796	5.800	5.253	5.841	5.820
1981 .....	5.800	3.860	5.818	5.253	5.659	5.775	5.800	5.253	5.837	5.821
1982 .....	5.800	3.798	5.826	5.253	5.664	5.775	5.800	5.253	5.829	5.820
1983 .....	5.800	3.755	5.825	5.253	5.677	5.774	5.800	5.253	5.800	5.800
1984 .....	5.800	3.745	5.823	5.253	5.613	5.745	5.800	5.253	5.867	5.850
1985 .....	5.800	3.752	5.832	5.253	5.572	5.736	5.800	5.253	5.819	5.814
1986 .....	5.800	3.733	5.903	5.253	5.624	5.808	5.800	5.253	5.839	5.832
1987 .....	5.800	3.742	5.901	5.253	5.599	5.820	5.800	5.253	5.860	5.858
1988 .....	5.800	3.751	5.900	5.253	5.618	5.820	5.800	5.253	5.842	5.840
1989 .....	5.800	3.764	5.906	5.253	5.641	5.833	5.800	5.253	5.869	5.857
1990 .....	5.800	3.758	5.934	5.253	5.614	5.849	5.800	5.253	5.838	5.833
1991 .....	5.800	3.740	5.948	5.253	5.636	5.873	5.800	5.253	5.827	5.823
1992 .....	5.800	3.739	5.953	5.253	5.623	5.877	5.800	5.253	5.774	5.777
1993 .....	5.800	3.735	5.954	5.253	5.539	5.866	5.800	5.253	5.681	5.693
1994 .....	5.800	3.728	5.950	5.253	5.416	5.835	5.800	5.253	5.693	5.704
1995 .....	5.800	3.728	5.938	5.253	5.345	5.830	5.800	5.253	5.692	5.703
1996 .....	5.800	3.703	5.947	5.253	5.373	5.828	5.800	5.253	5.663	5.678
1997 .....	5.800	3.686	5.954	5.253	5.333	5.836	5.800	5.253	5.663	5.678
1998 .....	5.800	3.694	5.953	5.253	5.314	5.833	5.800	5.253	5.505	5.539
1999 .....	5.800	3.663	5.942	5.253	5.291	5.815	5.800	5.253	5.530	5.564
2000 .....	5.800	3.648	5.959	5.253	5.309	5.823	5.800	5.253	5.529	5.542
2001 .....	5.800	3.652	5.976	5.253	5.330	5.838	5.800	5.253	5.637	5.641
2002 .....	5.800	3.646	5.971	5.253	5.362	5.845	5.800	5.253	5.517	5.519
2003 .....	5.800	3.659	5.970	5.253	5.381	5.845	5.800	5.253	5.628	5.630
2004 .....	5.800	3.636	5.981	5.253	5.429	5.853	5.800	5.253	5.532	5.539
2005 .....	5.800	3.638	5.977	5.253	5.436	5.835	5.800	5.253	5.504	5.513
2006 .....	5.800	3.622	5.980	5.253	5.431	5.836	5.800	<sup>e</sup> 5.219	5.415	5.423
2007 .....	5.800	3.609	5.985	5.222	5.483	5.857	5.800	5.188	5.465	5.471
2008 .....	5.800	3.614	5.990	5.222	5.459	5.861	5.800	5.215	5.587	5.591
2009 .....	5.800	3.598	5.988	5.222	5.509	5.878	5.800	5.221	5.674	5.677
2010 .....	5.800	3.573	5.989	5.222	5.545	5.892	5.800	5.214	5.601	5.604
2011 .....	5.800	3.573	6.008	5.222	5.538	5.905	5.800	5.216	5.526	5.530
2012 .....	5.800	3.588	6.165	5.222	5.501	6.035	5.800	5.217	5.520	5.526
2013 .....	5.800	3.629	6.010	5.222	5.497	5.899	5.800	5.216	5.470	5.482
2014 .....	5.800	3.640	6.035	5.222	5.518	5.929	5.800	5.218	5.369	5.406
2015 .....	5.717	3.669	6.065	5.222	5.504	5.941	5.682	5.218	5.279	5.319
2016 .....	5.722	3.632	6.053	5.222	5.491	5.929	5.724	5.218	5.184	5.245
2017 .....	5.723	3.612	6.050	5.222	5.489	5.930	5.738	<sup>e</sup> 5.222	5.151	5.258
2018 .....	5.706	3.591	6.063	5.222	<sup>d</sup> 5.491	<sup>d</sup> 5.938	5.721	5.222	<sup>d</sup> 5.088	<sup>d</sup> 5.259
2019 .....	5.698	3.607	6.061	5.222	5.464	5.908	5.708	5.222	5.022	5.263
2020 .....	<sup>P</sup> 5.691	<sup>P</sup> 3.593	<sup>P</sup> 6.079	<sup>P</sup> 5.222	<sup>P</sup> 5.515	<sup>P</sup> 5.937	<sup>P</sup> 5.710	<sup>P</sup> 5.222	<sup>P</sup> 4.922	<sup>P</sup> 5.216
2021 .....	<sup>E</sup> 5.691	<sup>E</sup> 3.593	<sup>E</sup> 6.079	<sup>E</sup> 5.222	<sup>E</sup> 5.515	<sup>E</sup> 5.937	<sup>E</sup> 5.710	<sup>E</sup> 5.222	<sup>E</sup> 4.922	<sup>E</sup> 5.216

<sup>a</sup> Includes lease condensate.

<sup>b</sup> Natural gas processing plant production of natural gas liquids (ethane, propane, normal butane, isobutane, and natural gasoline). Through 1980, also includes natural gas processing plant production of finished petroleum products (aviation gasoline, distillate fuel oil, jet fuel, kerosene, motor gasoline, special naphthas, and miscellaneous products).

<sup>c</sup> Excludes fuel ethanol, methyl tertiary butyl ether (MTBE), and other oxygenates blended into motor gasoline.

<sup>d</sup> Through 2017, the imports and exports factors are developed using old hydrocarbon gas liquids heat content values shown in Table A1 of the September 2019 *Monthly Energy Review* (MER). Beginning in 2018, the factors are developed using heat content values shown in Table A1 of the current MER.

<sup>e</sup> For 2006–2016, includes MTBE blended into motor gasoline; excludes MTBE in other years. For all years, excludes fuel ethanol and other non-MTBE oxygenates blended into motor gasoline.

<sup>P</sup>=Preliminary. <sup>E</sup>=Estimate.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A3. Approximate Heat Content of Petroleum Consumption and Fuel Ethanol**  
(Million Btu per Barrel)

	Total Petroleum <sup>a</sup> Consumption by Sector						Distillate Fuel Oil Consumption <sup>i</sup>	Hydrocarbon Gas Liquids Consumption <sup>g</sup>	Motor Gasoline (Finished) Consumption <sup>h</sup>	Petroleum Coke Consumption <sup>i</sup>	Fuel Ethanol <sup>j</sup>	Fuel Ethanol Feedstock Factor <sup>k</sup>
	Residential	Commercial <sup>b</sup>	Industrial <sup>b</sup>	Transportation <sup>b,c</sup>	Electric Power <sup>d,e</sup>	Total <sup>b,c</sup>						
1950 .....	5.473	5.817	5.927	5.461	6.254	5.642	5.825	3.810	5.253	6.024	NA	NA
1955 .....	5.470	5.781	5.847	5.407	6.254	5.581	5.825	3.810	5.253	6.024	NA	NA
1960 .....	5.418	5.781	5.772	5.387	6.267	5.542	5.825	3.810	5.253	6.024	NA	NA
1965 .....	5.365	5.761	5.695	5.386	6.267	5.517	5.825	3.810	5.253	6.024	NA	NA
1970 .....	5.262	5.709	5.579	5.393	6.252	5.499	5.825	3.731	5.253	6.024	NA	NA
1975 .....	5.255	5.649	5.490	5.392	6.250	5.489	5.825	3.671	5.253	6.024	NA	NA
1980 .....	5.322	5.752	5.340	5.441	6.254	5.472	5.825	3.669	5.253	6.024	3.564	6.586
1981 .....	5.284	5.693	5.268	5.433	6.258	5.440	5.825	3.632	5.253	6.024	3.564	6.562
1982 .....	5.267	5.699	5.211	5.423	6.258	5.406	5.825	3.588	5.253	6.024	3.564	6.539
1983 .....	5.141	5.592	5.214	5.416	6.255	5.396	5.825	3.535	5.253	6.024	3.564	6.515
1984 .....	5.308	5.658	5.167	5.418	6.251	5.385	5.825	3.580	5.253	6.024	3.564	6.492
1985 .....	5.264	5.598	5.159	5.423	6.247	5.377	5.825	3.584	5.253	6.024	3.564	6.469
1986 .....	5.269	5.632	5.237	5.426	6.257	5.410	5.825	3.631	5.253	6.024	3.564	6.446
1987 .....	5.241	5.594	5.203	5.429	6.249	5.395	5.825	3.663	5.253	6.024	3.564	6.423
1988 .....	5.259	5.598	5.196	5.433	6.250	5.402	5.825	3.643	5.253	6.024	3.564	6.400
1989 .....	5.195	5.549	5.190	5.438	6.240	5.403	5.825	3.679	5.253	6.024	3.564	6.377
1990 .....	5.146	5.554	5.219	5.442	6.244	5.403	5.825	3.630	5.253	6.024	3.564	6.355
1991 .....	5.096	5.529	5.130	5.441	6.246	5.375	5.825	3.626	5.253	6.024	3.564	6.332
1992 .....	5.126	5.514	5.133	5.443	6.238	5.369	5.825	3.643	5.253	6.024	3.564	6.309
1993 .....	5.103	5.505	5.140	5.413	6.230	5.354	5.825	3.628	5.217	6.024	3.564	6.287
1994 .....	5.097	5.513	5.115	5.413	6.213	5.344	5.820	3.657	5.214	6.024	3.564	6.264
1995 .....	5.062	5.476	5.084	5.409	6.187	5.326	5.820	3.641	5.204	6.024	3.564	6.242
1996 .....	4.997	5.431	5.076	5.416	6.194	5.323	5.820	3.629	5.211	6.024	3.564	6.220
1997 .....	4.988	5.389	5.083	5.410	6.198	5.322	5.820	3.627	5.205	6.024	3.564	6.198
1998 .....	4.974	5.363	5.101	5.406	6.210	5.335	5.819	3.619	5.203	6.024	3.564	6.176
1999 .....	4.902	5.289	5.052	5.406	6.204	5.313	5.819	3.628	5.202	6.024	3.564	6.167
2000 .....	4.908	5.313	5.015	5.415	6.188	5.311	5.819	3.610	5.201	6.024	3.564	6.159
2001 .....	4.936	5.323	5.104	5.405	6.199	5.331	5.819	3.604	5.201	6.024	3.564	6.151
2002 .....	4.885	5.291	5.053	5.404	6.172	5.309	5.819	3.588	5.199	6.024	3.564	6.143
2003 .....	4.920	5.313	5.108	5.400	6.182	5.326	5.819	3.610	5.197	6.024	3.564	6.106
2004 .....	4.952	5.324	5.106	5.407	6.134	5.330	5.818	3.591	5.192	5.982	3.564	6.069
2005 .....	4.915	5.360	5.143	5.408	6.126	5.342	5.818	3.589	5.196	5.982	3.564	6.032
2006 .....	4.886	5.296	5.120	5.405	6.038	5.323	5.803	3.551	5.185	5.987	3.564	5.995
2007 .....	4.833	5.270	5.079	5.376	6.064	5.293	5.784	3.544	5.142	5.996	3.564	5.959
2008 .....	4.772	5.156	5.103	5.342	6.013	5.268	5.780	3.549	5.106	5.992	3.564	5.922
2009 .....	4.664	5.217	4.959	5.320	5.987	5.218	5.781	3.487	5.090	6.017	3.564	5.901
2010 .....	4.664	5.195	4.921	5.316	5.956	5.204	5.778	3.489	5.067	6.059	3.562	5.880
2011 .....	4.657	5.176	4.887	5.315	5.900	5.193	5.776	3.423	5.063	6.077	3.561	5.859
2012 .....	4.714	5.126	4.844	5.306	5.925	5.176	5.774	3.440	5.062	6.084	3.560	5.838
2013 .....	4.648	5.053	4.801	5.302	5.892	5.157	5.774	3.468	5.060	6.089	3.560	5.817
2014 .....	4.664	5.016	4.804	5.300	5.906	5.161	5.773	3.439	5.059	6.100	3.559	5.797
2015 .....	4.721	5.050	4.767	5.302	5.915	5.154	5.773	3.461	5.057	6.085	3.558	5.776
2016 .....	4.631	5.022	4.798	5.303	5.885	5.161	5.773	3.424	5.055	6.104	3.558	5.755
2017 .....	4.623	5.006	4.768	5.305	5.893	5.153	5.772	3.400	5.053	6.132	3.556	5.735
2018 .....	4.620	4.971	4.664	5.310	5.896	5.122	5.772	3.381	5.054	6.122	3.553	5.715
2019 .....	4.540	4.962	4.645	5.307	5.900	5.111	5.771	3.401	5.052	6.132	3.555	5.694
2020 .....	E 4.514	E 4.941	E 4.538	E 5.300	P 5.889	P 5.056	P 5.771	P 3.349	P 5.052	P 6.130	P 3.558	5.674
2021 .....	E 4.514	E 4.941	E 4.538	E 5.300	E 5.889	E 5.056	E 5.771	E 3.349	E 5.052	E 6.130	E 3.558	5.654

<sup>a</sup> Petroleum products supplied, including natural gas plant liquids and crude oil burned directly as fuel. Quantity-weighted averages of the petroleum products included in each category are calculated by using heat content values for individual products shown in Tables A1 and A3.

<sup>b</sup> Beginning in 1993, includes fuel ethanol blended into motor gasoline.

<sup>c</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>d</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>e</sup> Electric power sector factors are weighted average heat contents for distillate fuel oil, petroleum coke, and residual fuel oil; they exclude other liquids.

<sup>f</sup> There is a discontinuity in this time series between 1993 and 1994; beginning in 1994, the single constant factor is replaced by a quantity-weighted factor.

Quantity-weighted averages of the sulfur-content categories of distillate fuel oil are calculated by using heat content values shown in Table A1. Excludes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>g</sup> Quantity-weighted averages of the major components of hydrocarbon gas liquids are calculated by using heat content values shown in Table A1. The factor for 1967 is used as the estimated factor for 1949–1966.

<sup>h</sup> Through 1992, excludes oxygenates. Beginning in 1993, includes fuel ethanol blended into motor gasoline; and for 1993–2006, also includes methyl tertiary butyl ether (MTBE) and other oxygenates blended into motor gasoline.

<sup>i</sup> There is a discontinuity in this time series between 2003 and 2004; beginning in 2004, the single constant factor is replaced by a quantity-weighted factor.

Quantity-weighted averages of the two categories of petroleum coke are calculated by using heat content values shown in Table A1.

<sup>j</sup> Includes denaturant (petroleum added to ethanol to make it undrinkable). Fuel ethanol factors are weighted average heat contents for undenatured ethanol (3.539 million Btu per barrel) and products used as denaturant (natural gasoline, finished motor gasoline, and motor gasoline blending components—see Tables A1 and A3 for factors). The factor for 2009 is used as the estimated factor for 1980–2008.

<sup>k</sup> Corn input to the production of undenatured ethanol (million Btu corn per barrel undenatured ethanol), used as the factor to estimate total biomass inputs to the production of undenatured ethanol. Observed ethanol yields (gallons undenatured ethanol per bushel of corn) are 2.5 in 1980, 2.666 in 1998, 2.68 in 2002, 2.78 in 2008, and 2.82 in 2012; yields in other years are estimated. Corn is assumed to have a gross heat content of 0.392 million Btu per bushel. Undenatured ethanol is assumed to have a gross heat content of 3.539 million Btu per barrel.

P=Preliminary. E=Estimate. NA=Not available.

Note: The heat content values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A4. Approximate Heat Content of Natural Gas**  
(Btu per Cubic Foot)

	Production		Consumption <sup>a</sup>			Imports	Exports
	Marketed	Dry	End-Use Sectors <sup>b</sup>	Electric Power Sector <sup>c</sup>	Total		
1950 .....	1,119	1,035	1,035	1,035	1,035	--	1,035
1955 .....	1,120	1,035	1,035	1,035	1,035	1,035	1,035
1960 .....	1,107	1,035	1,035	1,035	1,035	1,035	1,035
1965 .....	1,101	1,032	1,032	1,032	1,032	1,032	1,032
1970 .....	1,102	1,031	1,031	1,031	1,031	1,031	1,031
1975 .....	1,095	1,021	1,020	1,026	1,021	1,026	1,014
1980 .....	1,098	1,026	1,024	1,035	1,026	1,022	1,013
1981 .....	1,103	1,027	1,025	1,035	1,027	1,014	1,011
1982 .....	1,107	1,028	1,026	1,036	1,028	1,018	1,011
1983 .....	1,115	1,031	1,031	1,030	1,031	1,024	1,010
1984 .....	1,109	1,031	1,030	1,035	1,031	1,005	1,010
1985 .....	1,112	1,032	1,031	1,038	1,032	1,002	1,011
1986 .....	1,110	1,030	1,029	1,034	1,030	997	1,008
1987 .....	1,112	1,031	1,031	1,032	1,031	999	1,011
1988 .....	1,109	1,029	1,029	1,028	1,029	1,002	1,018
1989 .....	1,107	1,031	1,032	<sup>c</sup> 1,028	1,031	1,004	1,019
1990 .....	1,105	1,029	1,029	1,027	1,029	1,012	1,018
1991 .....	1,108	1,030	1,031	1,025	1,030	1,014	1,022
1992 .....	1,110	1,030	1,031	1,025	1,030	1,011	1,018
1993 .....	1,106	1,027	1,027	1,025	1,027	1,020	1,016
1994 .....	1,105	1,028	1,029	1,025	1,028	1,022	1,011
1995 .....	1,106	1,026	1,027	1,021	1,026	1,021	1,011
1996 .....	1,109	1,026	1,027	1,020	1,026	1,022	1,011
1997 .....	1,107	1,026	1,027	1,020	1,026	1,023	1,011
1998 .....	1,109	1,031	1,033	1,024	1,031	1,023	1,011
1999 .....	1,107	1,027	1,028	1,022	1,027	1,022	1,006
2000 .....	1,107	1,025	1,026	1,021	1,025	1,023	1,006
2001 .....	1,105	1,028	1,029	1,026	1,028	1,023	1,010
2002 .....	1,103	1,024	1,025	1,020	1,024	1,022	1,008
2003 .....	1,103	1,028	1,029	1,025	1,028	1,025	1,009
2004 .....	1,104	1,026	1,026	1,027	1,026	1,025	1,009
2005 .....	1,104	1,028	1,028	1,028	1,028	1,025	1,009
2006 .....	1,103	1,028	1,028	1,028	1,028	1,025	1,009
2007 .....	1,102	1,027	1,027	1,027	1,027	1,025	1,009
2008 .....	1,100	1,027	1,027	1,027	1,027	1,025	1,009
2009 .....	1,101	1,025	1,025	1,025	1,025	1,025	1,009
2010 .....	1,098	1,023	1,023	1,022	1,023	1,025	1,009
2011 .....	1,142	1,022	1,022	1,021	1,022	1,025	1,009
2012 .....	1,091	1,024	1,025	1,022	1,024	1,025	1,009
2013 .....	1,101	1,027	1,028	1,025	1,027	1,025	1,009
2014 .....	1,116	1,032	1,033	1,029	1,032	1,025	1,009
2015 .....	1,124	1,037	1,038	1,035	1,037	1,025	1,009
2016 .....	1,128	1,037	1,039	1,034	1,037	1,025	1,009
2017 .....	1,129	1,036	1,037	1,034	1,036	1,025	1,009
2018 .....	1,134	1,036	1,038	1,033	1,036	1,025	1,009
2019 .....	1,140	1,038	1,040	1,034	1,038	1,025	1,009
2020 .....	<sup>E</sup> 1,140	<sup>P</sup> 1,037	<sup>P</sup> 1,039	<sup>P</sup> 1,033	<sup>P</sup> 1,037	<sup>E</sup> 1,025	<sup>E</sup> 1,009
2021 .....	<sup>E</sup> 1,140	<sup>E</sup> 1,037	<sup>E</sup> 1,039	<sup>E</sup> 1,033	<sup>E</sup> 1,037	<sup>E</sup> 1,025	<sup>E</sup> 1,009

<sup>a</sup> Consumption factors are for natural gas, plus a small amount of supplemental gaseous fuels.

<sup>b</sup> Residential, commercial, industrial, and transportation sectors.

<sup>c</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

P=Preliminary. E=Estimate. -- =Not applicable.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A5. Approximate Heat Content of Coal and Coal Coke**  
(Million Btu per Short Ton)

	Coal									Coal Coke
	Production <sup>a</sup>	Waste Coal Supplied <sup>b</sup>	Consumption					Imports	Exports	Imports and Exports
			Residential and Commercial Sectors <sup>c</sup>	Industrial Sector		Electric Power Sector <sup>e,f</sup>	Total			
				Coke Plants	Other <sup>d</sup>					
1950 .....	25.090	NA	24.461	26.798	24.820	23.937	24.989	25.020	26.788	24.800
1955 .....	25.201	NA	24.373	26.794	24.821	24.056	24.982	25.000	26.907	24.800
1960 .....	24.906	NA	24.226	26.791	24.609	23.927	24.713	25.003	26.939	24.800
1965 .....	24.775	NA	24.028	26.787	24.385	23.780	24.537	25.000	26.973	24.800
1970 .....	23.842	NA	23.203	26.784	22.983	22.573	23.440	25.000	26.982	24.800
1975 .....	22.897	NA	22.261	26.782	22.436	21.642	22.506	25.000	26.562	24.800
1980 .....	22.415	NA	22.543	26.790	22.690	21.295	21.947	25.000	26.384	24.800
1981 .....	22.308	NA	22.474	26.794	22.585	21.085	21.713	25.000	26.160	24.800
1982 .....	22.239	NA	22.695	26.797	22.712	21.194	21.674	25.000	26.223	24.800
1983 .....	22.052	NA	22.775	26.798	22.691	21.133	21.576	25.000	26.291	24.800
1984 .....	22.010	NA	22.844	26.799	22.543	21.101	21.573	25.000	26.402	24.800
1985 .....	21.870	NA	22.646	26.798	22.020	20.959	21.366	25.000	26.307	24.800
1986 .....	21.913	NA	22.947	26.798	22.198	21.084	21.462	25.000	26.292	24.800
1987 .....	21.922	NA	23.404	26.799	22.381	21.136	21.517	25.000	26.291	24.800
1988 .....	21.823	NA	23.571	26.799	22.360	20.900	21.328	25.000	26.299	24.800
1989 .....	21.765	<sup>b</sup> 10.391	23.650	26.800	22.347	<sup>e</sup> 20.898	21.307	25.000	26.160	24.800
1990 .....	21.822	9.303	23.137	26.799	22.457	20.779	21.197	25.000	26.202	24.800
1991 .....	21.681	10.758	23.114	26.799	22.460	20.730	21.120	25.000	26.188	24.800
1992 .....	21.682	10.396	23.105	26.799	22.250	20.709	21.068	25.000	26.161	24.800
1993 .....	21.418	10.638	22.994	26.800	22.123	20.677	21.010	25.000	26.335	24.800
1994 .....	21.394	11.097	23.112	26.800	22.068	20.589	20.929	25.000	26.329	24.800
1995 .....	21.326	11.722	23.118	26.800	21.950	20.543	20.880	25.000	26.180	24.800
1996 .....	21.322	12.147	23.011	26.800	22.105	20.547	20.870	25.000	26.174	24.800
1997 .....	21.296	12.158	22.494	26.800	22.172	20.518	20.830	25.000	26.251	24.800
1998 .....	21.418	12.639	21.620	27.426	23.164	20.516	20.881	25.000	26.800	24.800
1999 .....	21.070	12.552	23.880	27.426	22.489	20.490	20.818	25.000	26.081	24.800
2000 .....	21.072	12.360	25.020	27.426	22.433	20.511	20.828	25.000	26.117	24.800
2001 .....	<sup>a</sup> 20.772	12.169	24.909	27.426	22.622	20.337	20.671	25.000	25.998	24.800
2002 .....	20.673	12.165	22.962	27.426	22.562	20.238	20.541	25.000	26.062	24.800
2003 .....	20.499	12.360	22.242	27.425	22.468	20.082	20.387	25.000	25.972	24.800
2004 .....	20.424	12.266	22.324	27.426	22.473	19.980	20.290	25.000	26.108	24.800
2005 .....	20.348	12.093	22.342	26.279	22.178	19.988	20.246	25.000	25.494	24.800
2006 .....	20.310	12.080	22.066	26.271	22.050	19.931	20.181	25.000	25.453	24.800
2007 .....	20.340	12.090	22.069	26.329	22.371	19.909	20.168	25.000	25.466	24.800
2008 .....	20.208	12.121	<sup>c</sup> 23.035	26.281	22.304	19.713	19.979	25.000	25.399	24.800
2009 .....	19.963	12.076	22.852	26.334	21.823	19.521	19.741	25.000	25.633	24.800
2010 .....	20.173	11.960	22.611	26.295	21.846	19.623	19.870	25.000	25.713	24.800
2011 .....	20.142	11.604	22.099	26.299	21.568	19.341	19.600	25.000	25.645	24.800
2012 .....	20.215	11.539	21.300	28.636	21.449	19.211	19.544	23.128	24.551	24.800
2013 .....	20.182	11.103	21.233	28.705	21.600	19.174	19.513	22.379	24.605	24.800
2014 .....	20.146	11.474	21.307	28.458	21.525	19.290	19.611	22.187	25.032	24.800
2015 .....	19.880	11.527	20.699	28.526	21.258	19.146	19.482	22.633	25.048	24.800
2016 .....	19.977	11.496	20.078	28.608	21.055	19.153	19.459	22.327	25.655	24.800
2017 .....	20.025	11.438	19.467	28.673	20.802	18.981	19.303	21.489	24.628	24.800
2018 .....	20.160	11.419	19.269	28.608	20.739	18.915	19.258	20.415	24.294	24.800
2019 .....	20.053	11.513	19.084	28.629	20.721	18.903	19.292	20.558	24.584	24.800
2020 .....	<sup>P</sup> 19.858	<sup>P</sup> 10.301	<sup>P</sup> 18.297	<sup>P</sup> 28.717	<sup>P</sup> 20.414	<sup>P</sup> 18.856	<sup>P</sup> 19.236	<sup>P</sup> 20.347	<sup>P</sup> 24.986	<sup>P</sup> 24.800
2021 .....	<sup>E</sup> 19.858	<sup>E</sup> 10.301	<sup>E</sup> 18.297	<sup>E</sup> 28.717	<sup>E</sup> 20.414	<sup>E</sup> 18.856	<sup>E</sup> 19.236	<sup>E</sup> 20.347	<sup>E</sup> 24.986	<sup>E</sup> 24.800

<sup>a</sup> Beginning in 2001, includes a small amount of refuse recovery (coal recaptured from a refuse mine, and cleaned to reduce the concentration of noncombustible materials).

<sup>b</sup> Waste coal (including fine coal, coal obtained from a refuse bank or slurry dam, anthracite culm, bituminous gob, and lignite waste) consumed by the electric power and industrial sectors. Beginning in 1989, waste coal supplied is counted as a supply-side item to balance the same amount of waste coal included in "Consumption."

<sup>c</sup> Through 2007, used as the thermal conversion factor for coal consumption by the residential and commercial sectors. Beginning in 2008, used as the thermal conversion factor for coal consumption by the commercial sector only.

<sup>d</sup> Includes transportation. Excludes coal synfuel plants.

<sup>e</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>f</sup> Electric power sector factors are for anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and, beginning in 1998, coal synfuel.

P=Preliminary. E=Estimate. NA=Not available.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.



**Table A6. Approximate Heat Rates for Electricity, and Heat Content of Electricity**  
(Btu per Kilowatthour)

	Approximate Heat Rates <sup>a</sup> for Electricity Net Generation						Heat Content <sup>j</sup> of Electricity <sup>k</sup>
	Fossil Fuels <sup>b</sup>				Nuclear <sup>h</sup>	Noncombustible Renewable Energy <sup>g,i</sup>	
	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Total Fossil Fuels <sup>f,g</sup>			
1950 .....	NA	NA	NA	14,030	--	14,030	3,412
1955 .....	NA	NA	NA	11,699	--	11,699	3,412
1960 .....	NA	NA	NA	10,760	11,629	10,760	3,412
1965 .....	NA	NA	NA	10,453	11,804	10,453	3,412
1970 .....	NA	NA	NA	10,494	10,977	10,494	3,412
1975 .....	NA	NA	NA	10,406	11,013	10,406	3,412
1980 .....	NA	NA	NA	10,388	10,908	10,388	3,412
1981 .....	NA	NA	NA	10,453	11,030	10,453	3,412
1982 .....	NA	NA	NA	10,454	11,073	10,454	3,412
1983 .....	NA	NA	NA	10,520	10,905	10,520	3,412
1984 .....	NA	NA	NA	10,440	10,843	10,440	3,412
1985 .....	NA	NA	NA	10,447	10,622	10,447	3,412
1986 .....	NA	NA	NA	10,446	10,579	10,446	3,412
1987 .....	NA	NA	NA	10,419	10,442	10,419	3,412
1988 .....	NA	NA	NA	10,324	10,602	10,324	3,412
1989 .....	NA	NA	NA	10,432	10,583	10,432	3,412
1990 .....	NA	NA	NA	10,402	10,582	10,402	3,412
1991 .....	NA	NA	NA	10,436	10,484	10,436	3,412
1992 .....	NA	NA	NA	10,342	10,471	10,342	3,412
1993 .....	NA	NA	NA	10,309	10,504	10,309	3,412
1994 .....	NA	NA	NA	10,316	10,452	10,316	3,412
1995 .....	NA	NA	NA	10,312	10,507	10,312	3,412
1996 .....	NA	NA	NA	10,340	10,503	10,340	3,412
1997 .....	NA	NA	NA	10,213	10,494	10,213	3,412
1998 .....	NA	NA	NA	10,197	10,491	10,197	3,412
1999 .....	NA	NA	NA	10,226	10,450	10,226	3,412
2000 .....	NA	NA	NA	10,201	10,429	10,201	3,412
2001 .....	10,378	10,742	10,051	<sup>b</sup> 10,333	10,443	10,333	3,412
2002 .....	10,314	10,641	9,533	10,173	10,442	10,173	3,412
2003 .....	10,297	10,610	9,207	10,125	10,422	10,125	3,412
2004 .....	10,331	10,571	8,647	10,016	10,428	10,016	3,412
2005 .....	10,373	10,631	8,551	9,999	10,436	9,999	3,412
2006 .....	10,351	10,809	8,471	9,919	10,435	9,919	3,412
2007 .....	10,375	10,794	8,403	9,884	10,489	9,884	3,412
2008 .....	10,378	11,015	8,305	9,854	10,452	9,854	3,412
2009 .....	10,414	10,923	8,160	9,760	10,459	9,760	3,412
2010 .....	10,415	10,984	8,185	9,756	10,452	9,756	3,412
2011 .....	10,444	10,829	8,152	9,716	10,464	9,716	3,412
2012 .....	10,498	10,991	8,039	9,516	10,479	9,516	3,412
2013 .....	10,459	10,713	7,948	9,541	10,449	9,541	3,412
2014 .....	10,428	10,814	7,907	9,510	10,459	9,510	3,412
2015 .....	10,495	10,687	7,878	9,319	10,458	9,319	3,412
2016 .....	10,493	10,811	7,870	9,232	10,459	9,232	3,412
2017 .....	10,465	10,834	7,812	9,213	10,459	9,213	3,412
2018 .....	10,481	11,095	7,821	9,104	10,455	9,104	3,412
2019 .....	10,551	11,205	7,732	8,905	10,442	8,905	3,412
2020 .....	<sup>E</sup> 10,551	<sup>E</sup> 11,205	<sup>E</sup> 7,732	<sup>E</sup> 8,905	<sup>E</sup> 10,442	<sup>E</sup> 8,905	3,412
2021 .....	<sup>E</sup> 10,551	<sup>E</sup> 11,205	<sup>E</sup> 7,732	<sup>E</sup> 8,905	<sup>E</sup> 10,442	<sup>E</sup> 8,905	3,412

<sup>a</sup> The values in columns 1–6 of this table are for net heat rates. See "Heat Rate" in Glossary.

<sup>b</sup> Through 2000, heat rates are for fossil-fueled steam-electric plants at electric utilities. Beginning in 2001, heat rates are for all fossil-fueled plants at electric utilities and electricity-only independent power producers.

<sup>c</sup> Includes anthracite, bituminous coal, subbituminous coal, lignite, and, beginning in 2002, waste coal and coal synfuel.

<sup>d</sup> Includes distillate fuel oil, residual fuel oil, jet fuel, kerosene, petroleum coke, and waste oil.

<sup>e</sup> Includes natural gas and supplemental gaseous fuels.

<sup>f</sup> Includes coal, petroleum, natural gas, and, beginning in 2001, other gases (blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels).

<sup>g</sup> The fossil-fuels heat rate is used as the thermal conversion factor for electricity net generation from noncombustible renewable energy (hydro, geothermal, solar thermal, photovoltaic, and wind) to approximate the quantity of fossil fuels replaced by these sources. Through 2000, also used as the thermal conversion factor for wood and waste electricity net generation at electric utilities; beginning in 2001, Btu data for wood and waste at electric utilities are available from surveys.

<sup>h</sup> Used as the thermal conversion factor for nuclear electricity net generation.

<sup>i</sup> Technology-based geothermal heat rates are no longer used in Btu calculations in this report. For technology-based geothermal heat rates for 1960–2010, see the *Annual Energy Review 2010*, Table A6.

<sup>j</sup> See "Heat Content" in Glossary.

<sup>k</sup> The value of 3,412 Btu per kilowatthour is a constant. It is used as the thermal conversion factor for electricity retail sales, and electricity imports and exports.

<sup>E</sup>=Estimate. NA=Not available. -- =Not applicable.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: See "Thermal Conversion Factor Source Documentation," which follows this table.

## Approximate Heat Content of Petroleum and Natural Gas Liquids

**Asphalt.** The U.S. Energy Information Administration (EIA) adopted the thermal conversion factor of 6.636 million British thermal units (Btu) per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

**Aviation Gasoline Blending Components.** Assumed by EIA to be 5.048 million Btu per barrel or equal to the thermal conversion factor for **Aviation Gasoline (Finished)**.

**Aviation Gasoline (Finished).** EIA adopted the thermal conversion factor of 5.048 million Btu per barrel as adopted by the Bureau of Mines from the Texas Eastern Transmission Corporation publication *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics.

**Butylene.** EIA estimated the thermal conversion factor to be 4.377 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook, NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Crude Oil Exports.** • 1949–2014: Assumed by EIA to be 5.800 million Btu per barrel or equal to the thermal conversion factor for crude oil produced in the United States. See **Crude Oil Production**. • 2015 forward: Calculated annually by EIA based on conversion of American Petroleum Institute (API) gravity ranges of crude oil exports as reported in trade data from the U.S. Census Bureau. Specific gravity (SG) =  $141.5 / (131.5 + \text{API gravity})$ . The higher heating value (HHV) in million Btu per barrel =  $\text{SG} * (7.801796 - 1.3213 * \text{SG}^2)$ .

**Crude Oil Imports.** Calculated annually by EIA as the average of the thermal conversion factors for each type of crude oil imported weighted by the quantities imported. Thermal conversion factors for each type were calculated on a foreign country basis, by determining the average American Petroleum Institute (API) gravity of crude oil imported from each foreign country from Form ERA-60 in 1977 and converting average API gravity to average Btu content by using National Bureau of Standards, Miscellaneous Publication No. 97, *Thermal Properties of Petroleum Products*, 1933.

**Crude Oil Production.** • 1949–2014: EIA adopted the thermal conversion factor of 5.800 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.” • 2015 forward: Calculated annually by EIA based on conversion of American Petroleum Institute (API) gravity ranges of crude oil production as reported on Form EIA-914, “Monthly Crude Oil, Lease Condensate, and Natural Gas Production Report.” Specific gravity (SG) =  $141.5 / (131.5 + \text{API gravity})$ . The higher heating value (HHV) in million Btu per barrel =  $\text{SG} * (7.801796 - 1.3213 * \text{SG}^2)$ .

**Distillate Fuel Oil Consumption.** • 1949–1993: EIA adopted the Bureau of Mines thermal conversion factor of 5.825 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.” • 1994 forward: Calculated by EIA as the annual quantity-weighted average of the conversion factors for **Distillate Fuel Oil, 15 ppm Sulfur and Under** (5.770 million Btu per barrel), **Distillate Fuel Oil, Greater Than 15 ppm to 500 ppm Sulfur** (5.817 million Btu per barrel), and **Distillate Fuel Oil, Greater Than 500 ppm Sulfur** (5.825 million Btu per barrel).

**Distillate Fuel Oil, 15 ppm Sulfur and Under.** EIA adopted the thermal conversion factor of 5.770 million Btu per barrel (137,380 Btu per gallon) for U.S. conventional diesel from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Distillate Fuel Oil, Greater Than 15 ppm to 500 ppm Sulfur.** EIA adopted the thermal conversion factor of 5.817 million Btu per barrel (138,490 Btu per gallon) for low-sulfur diesel from U.S. Department of Energy, Argonne Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Distillate Fuel Oil, Greater Than 500 ppm Sulfur.** EIA adopted the Bureau of Mines thermal conversion factor of 5.825 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.”

**Ethane.** EIA estimated the thermal conversion factor to be 2.783 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook, NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Ethylene.** EIA adopted the thermal conversion factor of 2.436 million Btu per barrel (0.058 million Btu per gallon) as published in the Federal Register EPA; 40 CFR part 98; e-CRF; Table C1; April 5, 2019. The ethylene higher heating value is determined at 41 degrees Fahrenheit at saturation pressure.

**Hydrocarbon Gas Liquids.** • 1949–1966: EIA used the 1967 factor. • 1967 forward: Calculated annually by EIA as the average of the thermal conversion factors for all hydrocarbon gas liquids consumed (see Table A1) weighted by the quantities consumed. The component products of hydrocarbon gas liquids are ethane, propane, normal butane, isobutane, natural gasoline (pentanes plus), and refinery olefins (ethylene, propylene, butylene, and isobutylene). For 1967–1980, quantities consumed are from EIA, Energy Data Reports, “Petroleum Statement, Annual.” For 1981 forward, quantities consumed are from EIA, *Petroleum Supply Annual*.

**Hydrogen.** EIA estimated a thermal conversion factor of 323.6 Btu per standard cubic foot (at 60 degrees Fahrenheit and 1 atmosphere), based on data published by the National Research Council and National Academy of Engineering, in Appendix H of *The Hydrogen Economy: Opportunities, Costs, Barriers, and R&D Needs*, 2004. EIA also assumed a thermal conversion factor of 6.287 million Btu per residual fuel oil equivalent barrel or equal to the thermal conversion factor for **Residual Fuel Oil**.

**Isobutane.** EIA estimated the thermal conversion factor to be 4.183 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook, NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Isobutylene.** EIA estimated the thermal conversion factor to be 4.355 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook, NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Jet Fuel, Kerosene-Type.** EIA adopted the Bureau of Mines thermal conversion factor of 5.670 million Btu per barrel for “Jet Fuel, Commercial” as published by the Texas Eastern Transmission Corporation in the report *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics.

**Jet Fuel, Naphtha-Type.** EIA adopted the Bureau of Mines thermal conversion factor of 5.355 million Btu per barrel for “Jet Fuel, Military” as published by the Texas Eastern Transmission Corporation in the report *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics.

**Kerosene.** EIA adopted the Bureau of Mines thermal conversion factor of 5.670 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.”

**Lubricants.** EIA adopted the thermal conversion factor of 6.065 million Btu per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

**Miscellaneous Products.** EIA adopted the thermal conversion factor of 5.796 million Btu per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

**Motor Gasoline Blending Components.** • 1949–2006: EIA adopted the Bureau of Mines thermal conversion factor of 5.253 million Btu per barrel for “Gasoline, Motor Fuel” as published by the Texas Eastern Transmission Corporation in Appendix V of *Competition and Growth in American Markets 1947–1985*, a 1968 release of historical and projected statistics. • 2007 forward: EIA adopted the thermal conversion factor of 5.222 million Btu per barrel (124,340 Btu per gallon) for gasoline blendstock from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Motor Gasoline Exports.** • 1949–2005: EIA adopted the Bureau of Mines thermal conversion factor of 5.253 million Btu per barrel for “Gasoline, Motor Fuel” as published by the Texas Eastern Transmission Corporation in Appendix V of *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics. • 2006 forward: Calculated by EIA as the annual quantity-weighted average of the conversion factors for gasoline blendstock and the methyl tertiary butyl ether (MTBE) blended into motor gasoline exports. The factor for gasoline

blendstock is 5.253 million Btu per barrel in 2006 and 5.222 million Btu per barrel beginning in 2007 (see **Motor Gasoline Blending Components**). For MTBE, EIA adopted the thermal conversion factor of 4.247 million Btu per barrel (101,130 Btu per gallon) from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Motor Gasoline (Finished) Consumption.** • 1949–1992: EIA adopted the Bureau of Mines thermal conversion factor of 5.253 million Btu per barrel for “Gasoline, Motor Fuel” as published by the Texas Eastern Transmission Corporation in Appendix V of *Competition and Growth in American Markets 1947-1985*, a 1968 release of historical and projected statistics. • 1993–2006: Calculated by EIA as the annual quantity-weighted average of the conversion factors for gasoline blendstock and the oxygenates blended into motor gasoline. The factor for gasoline blendstock is 5.253 million Btu per barrel (the motor gasoline factor used for previous years). The factors for fuel ethanol are shown in Table A3 (see **Fuel Ethanol, Denatured**). The following factors for other oxygenates are from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013—methyl tertiary butyl ether (MTBE): 4.247 million Btu per barrel (101,130 Btu per gallon); tertiary amyl methyl ether (TAME): 4.560 million Btu per barrel (108,570 Btu per gallon); ethyl tertiary butyl ether (ETBE): 4.390 million Btu per barrel (104,530 Btu per gallon); methanol: 2.738 million Btu per barrel (65,200 Btu per gallon); and butanol: 4.555 million Btu per barrel (108,458 Btu per gallon). • 2007 forward: Calculated by EIA as the annual quantity-weighted average of the conversion factors for gasoline blendstock and fuel ethanol blended into motor gasoline. The factor for gasoline blendstock is 5.222 million Btu per barrel (124,340 Btu per gallon), which is from the GREET model (see above). The factors for fuel ethanol are shown in Table A3 (see **Fuel Ethanol, Denatured**).

**Motor Gasoline Imports.** • 1949–2006: EIA adopted the Bureau of Mines thermal conversion factor of 5.253 million Btu per barrel for “Gasoline, Motor Fuel” as published by the Texas Eastern Transmission Corporation in Appendix V of *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics. • 2007 forward: EIA adopted the thermal conversion factor of 5.222 million Btu per barrel (124,340 Btu per gallon) for gasoline blendstock from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Natural Gas Plant Liquids Production.** Calculated annually by EIA as the average of the thermal conversion factors for each natural gas plant liquid produced weighted by the quantities produced.

**Natural Gasoline.** EIA estimated the thermal conversion factor to be 4.638 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook*, *NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute. EIA assumes a natural gasoline ratio of 29% isopentane, 29% neopentane, 20% normal pentane, 13% normal hexane, 4% cyclohexane, 3% benzene, and 2% toluene in these calculations.

**Normal Butane.** EIA estimated the thermal conversion factor to be 4.353 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook*, *NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Other Hydrocarbons.** Assumed by EIA to be 5.825 million Btu per barrel or equal to the thermal conversion factor for **Unfinished Oils**.

**Oxygenates (Excluding Fuel Ethanol).** EIA adopted the thermal conversion factor of 4.247 million Btu per barrel (101,130 Btu per gallon) for methyl tertiary butyl ether (MTBE) from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Petrochemical Feedstocks, Naphtha Less Than 401 Degrees Fahrenheit.** Assumed by EIA to be 5.248 million Btu per barrel or equal to the thermal conversion factor for **Special Naphthas**.

**Petrochemical Feedstocks, Other Oils Equal to or Greater Than 401 Degrees Fahrenheit.** Assumed by EIA to be 5.825 million Btu per barrel or equal to the thermal conversion factor for **Distillate Fuel Oil**.

**Petrochemical Feedstocks, Still Gas.** Assumed by EIA to be equal to the thermal conversion factor for **Still Gas**.

**Petroleum Coke, Catalyst.** Assumed by EIA to be 6.287 million Btu per barrel or equal to the thermal conversion factor for **Residual Fuel Oil**.

**Petroleum Coke, Marketable.** EIA adopted the thermal conversion factor of 5.719 million Btu per barrel, calculated by dividing 28,595,925 Btu per short ton for petroleum coke (from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_October 2013) by 5.0 barrels per short ton (as given in the Bureau of Mines Form 6-1300-M and successor EIA forms).

**Petroleum Coke, Total.** • 1949–2003: EIA adopted the thermal conversion factor of 6.024 million Btu per barrel as reported in Btu per short ton in the Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.” The Bureau of Mines calculated this factor by dividing 30.120 million Btu per short ton, as given in the referenced Bureau of Mines internal memorandum, by 5.0 barrels per short ton, as given in the Bureau of Mines Form 6-1300-M and successor EIA forms. • 2004 forward: Calculated by EIA as the annual quantity-weighted average of the conversion factors for **Petroleum Coke, Catalyst** (6.287 million Btu per barrel) and **Petroleum Coke, Marketable** (5.719 million Btu per barrel).

**Petroleum Consumption, Commercial Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the commercial sector weighted by the estimated quantities consumed by the commercial sector. The quantities of petroleum products consumed by the commercial sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_petrol.pdf).

**Petroleum Consumption, Electric Power Sector.** Calculated annually by EIA as the average of the thermal conversion factors for distillate fuel oil, petroleum coke, and residual fuel oil consumed by the electric power sector weighted by the quantities consumed by the electric power sector. Data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

**Petroleum Consumption, Industrial Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the industrial sector weighted by the estimated quantities consumed by the industrial sector. The quantities of petroleum products consumed by the industrial sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_petrol.pdf).

**Petroleum Consumption, Residential Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the residential sector weighted by the estimated quantities consumed by the residential sector. The quantities of petroleum products consumed by the residential sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_petrol.pdf).

**Petroleum Consumption, Total.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed weighted by the quantities consumed.

**Petroleum Consumption, Transportation Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the transportation sector weighted by the estimated quantities consumed by the transportation sector. The quantities of petroleum products consumed by the transportation sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/state/seds/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/state/seds/sep_use/notes/use_petrol.pdf).

**Petroleum Products Exports.** Calculated annually by EIA as the average of the thermal conversion factors for each petroleum product exported weighted by the quantities exported.

**Petroleum Products Imports.** Calculated annually by EIA as the average of the thermal conversion factors for each petroleum product imported weighted by the quantities imported.

**Plant Condensate.** • 1973–1983: Estimated to be 5.418 million Btu per barrel by EIA from data provided by McClanahan Consultants, Inc., Houston, Texas.

**Propane.** EIA estimated the thermal conversion factor to be 3.841 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook*, *NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Propylene.** EIA estimated the thermal conversion factor to be 3.835 million Btu per barrel, based on data for enthalpy of combustion from the National Institute of Standards and Technology, *NIST Chemistry WebBook*, *NIST Standard Reference Database Number 69*, 2018; and data for density of liquids at 60 degrees Fahrenheit and equilibrium pressure from the American Petroleum Institute.

**Renewable Fuels Except Fuel Ethanol.** For “Biomass-Based Diesel Fuel” and “Other Renewable Fuels,” EIA assumed the thermal conversion factor to be 5.359 million Btu per barrel or equal to the thermal conversion factor for **Biodiesel**. For “Other Renewable Diesel Fuel,” EIA adopted the thermal conversion factor of 5.494 million Btu per barrel (130,817 Btu per gallon) for renewable diesel II (UOP-HDO) from U.S. Department of Energy, Argonne National Laboratory, “The Greenhouse Gases, Regulated Emissions, and Energy Use in Transportation Model” (GREET), version GREET1\_2013, October 2013.

**Residual Fuel Oil.** EIA adopted the thermal conversion factor of 6.287 million Btu per barrel as reported in the Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.”

**Road Oil.** EIA adopted the Bureau of Mines thermal conversion factor of 6.636 million Btu per barrel, which was assumed to be equal to that of **Asphalt** and was first published by the Bureau of Mines in the *Petroleum Statement, Annual, 1970*.

**Special Naphthas.** EIA adopted the Bureau of Mines thermal conversion factor of 5.248 million Btu per barrel, which was assumed to be equal to that of the total gasoline (aviation and motor) factor and was first published in the *Petroleum Statement, Annual, 1970*.

**Still Gas.** • 1949–2015: EIA adopted the Bureau of Mines estimated thermal conversion factor of 6.000 million Btu per barrel, first published in the *Petroleum Statement, Annual, 1970*. • 2016 forward: Assumed by EIA to be 6.287 million Btu per barrel or equal to the thermal conversion factor for **Residual Fuel Oil**.

**Total Petroleum Exports.** Calculated annually by EIA as the average of the thermal conversion factors for crude oil and each petroleum product exported weighted by the quantities exported. See **Crude Oil Exports** and **Petroleum Products Exports**.

**Total Petroleum Imports.** Calculated annually by EIA as the average of the thermal conversion factors for each type of crude oil and petroleum product imported weighted by the quantities imported. See **Crude Oil Imports** and **Petroleum Products Imports**.

**Unfinished Oils.** EIA assumed the thermal conversion factor to be 5.825 million Btu per barrel, the average of all natural gas or equal to that for **Distillate Fuel Oil** and first published it in EIA’s *Annual Report to Congress, Volume 3, 1977*.

**Unfractionated Stream.** • 1979–1982: EIA assumed the thermal conversion factor to be 3.800 million Btu per barrel, the average of all natural gas plant liquids calculated on their contribution to total barrels produced.

**Waxes.** EIA adopted the thermal conversion factor of 5.537 million Btu per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

## Approximate Heat Content of Biofuels

**Biodiesel.** EIA estimated the thermal conversion factor for biodiesel to be 5.359 million Btu per barrel, or 17,253 Btu per pound.

**Biodiesel Feedstock.** EIA used soybean oil input to the production of biodiesel (million Btu soybean oil per barrel biodiesel) as the factor to estimate total biomass inputs to the production of biodiesel. EIA assumed that 7.65 pounds of soybean oil are needed to produce one gallon of biodiesel, and 5.433 million Btu of soybean oil are needed to produce one barrel of biodiesel. EIA also assumed that soybean oil has a gross heat content of 16,909 Btu per pound, or 5.483 million Btu per barrel.

**Ethanol (Undenatured).** EIA adopted the thermal conversion factor of 3.539 million Btu per barrel published in “Oxygenate Flexibility for Future Fuels,” a paper presented by William J. Piel of the ARCO Chemical Company at the National Conference on Reformulated Gasolines and Clean Air Act Implementation, Washington, DC, October 1991.

**Fuel Ethanol (Denatured).** • 1981–2008: EIA used the 2009 factor. • 2009 forward: Calculated by EIA as the annual quantity-weighted average of the thermal conversion factors for undenatured ethanol (3.539 million Btu per barrel), natural gasoline used as denaturant (4.638 million Btu per barrel), and conventional motor gasoline and motor gasoline blending components used as denaturant (5.253 million Btu per barrel). The quantity of ethanol consumed is from EIA’s *Petroleum Supply Annual* (PSA) and *Petroleum Supply Monthly* (PSM), Table 1, data for renewable fuels and oxygenate plant net production of fuel ethanol. The quantity of natural gasoline used as denaturant is from PSA/PSM, Table 1, data for renewable fuels and oxygenate plant net production of natural gasoline, multiplied by -1. The

quantity of conventional motor gasoline and motor gasoline blending components used as denaturant is from PSA/PSM, Table 1, data for renewable fuels and oxygenate plant net production of conventional motor gasoline and motor gasoline blending components, multiplied by -1.

**Fuel Ethanol Feedstock.** EIA used corn input to the production of undenatured ethanol (million Btu corn per barrel undenatured ethanol) as the annual factor to estimate total biomass inputs to the production of undenatured ethanol. EIA used the following observed ethanol yields (in gallons undenatured ethanol per bushel of corn) from U.S. Department of Agriculture: 2.5 in 1980, 2.666 in 1998, 2.68 in 2002; and from University of Illinois at Chicago, Energy Resources Center, “2012 Corn Ethanol: Emerging Plant Energy and Environmental Technologies”: 2.78 in 2008, and 2.82 in 2012. EIA estimated the ethanol yields in other years. EIA also assumed that corn has a gross heat content of 0.392 million Btu per bushel.

## Approximate Heat Content of Natural Gas

**Natural Gas Consumption, Electric Power Sector.** Calculated annually by EIA by dividing the heat content of natural gas consumed by the electric power sector by the quantity consumed. Data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

**Natural Gas Consumption, End-Use Sectors.** Calculated annually by EIA by dividing the heat content of natural gas consumed by the end-use sectors (residential, commercial, industrial, and transportation) by the quantity consumed. The heat content of natural gas consumed by the end-use sectors is calculated as the total heat content of natural gas consumed minus the heat content of natural gas consumed by the electric power sector. The quantity of natural gas consumed by the end-use sectors is calculated as the total quantity of natural gas consumed minus the quantity of natural gas consumed by the electric power sector. Data are from Form EIA-176, “Annual Report of Natural and Supplemental Gas Supply and Disposition”; and Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

**Natural Gas Consumption, Total.** • 1949–1962: EIA adopted the thermal conversion factor of 1,035 Btu per cubic foot as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*. • 1963–1979: EIA adopted the thermal conversion factor calculated annually by the American Gas Association (AGA) and published in *Gas Facts*, an AGA annual publication. • 1980 forward: Calculated annually by EIA by dividing the total heat content of natural gas consumed by the total quantity consumed.

**Natural Gas Exports.** • 1949–1972: Assumed by EIA to be equal to the thermal conversion factor for dry natural gas consumed (see **Natural Gas Consumption, Total**). • 1973 forward: Calculated annually by EIA by dividing the heat content of natural gas exported by the quantity exported. For 1973–1995, data are from Form FPC-14, “Annual Report for Importers and Exporters of Natural Gas.” Beginning in 1996, data are from U.S. Department of Energy, Office of Fossil Energy, *Natural Gas Imports and Exports*.

**Natural Gas Imports.** • 1949–1972: Assumed by EIA to be equal to the thermal conversion factor for dry natural gas consumed (see **Natural Gas Consumption, Total**). • 1973 forward: Calculated annually by EIA by dividing the heat content of natural gas imported by the quantity imported. For 1973–1995, data are from Form FPC-14, “Annual Report for Importers and Exporters of Natural Gas.” Beginning in 1996, data are from U.S. Department of Energy, Office of Fossil Energy, *Natural Gas Imports and Exports*.

**Natural Gas Production, Dry.** Assumed by EIA to be equal to the thermal conversion factor for dry natural gas consumed. See **Natural Gas Consumption, Total**.

**Natural Gas Production, Marketed.** Calculated annually by EIA by dividing the heat content of dry natural gas produced (see **Natural Gas Production, Dry**) and natural gas liquids produced (see **Natural Gas Liquids Production**) by the total quantity of marketed natural gas produced.

## Approximate Heat Content of Coal and Coal Coke

**Coal Coke Imports and Exports.** EIA adopted the Bureau of Mines estimate of 24,800 million Btu per short ton.

**Coal Consumption, Electric Power Sector.** Calculated annually by EIA by dividing the heat content of coal consumed by the electric power sector by the quantity consumed. Data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms.



**Coal Consumption, Industrial Sector, Coke Plants.** • 1949–2011: Calculated annually by EIA based on the reported volatility (low, medium, or high) of coal received by coke plants. (For 2011, EIA used the following volatility factors, in million Btu per short ton: low volatile—26.680; medium volatile—27.506; and high volatile—25.652.) Data are from Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants,” and predecessor forms. • 2012 forward: Calculated annually by EIA by dividing the heat content of coal received by coke plants by the quantity received. Through June 2014, data are from Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants”; beginning in July 2014, data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”).

**Coal Consumption, Industrial Sector, Other.** • 1949–2007: Calculated annually by EIA by dividing the heat content of coal received by manufacturing plants by the quantity received. Data are from Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants,” and predecessor forms. • 2008 forward: Calculated annually by EIA by dividing the heat content of coal received by manufacturing, gasification, and liquefaction plants by the quantity received. Data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”).

**Coal Consumption, Residential and Commercial Sectors.** • 1949–1999: Calculated annually by EIA by dividing the heat content of coal received by the residential and commercial sectors by the quantity received. Data are from Form EIA-6, “Coal Distribution Report,” and predecessor forms. • 2000–2007: Calculated annually by EIA by dividing the heat content of coal consumed by commercial combined-heat-and-power (CHP) plants by the quantity consumed. Data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms. • 2008 forward: Calculated annually by EIA by dividing the heat content of coal received by commercial and institutional users by the quantity received. Data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”).

**Coal Consumption, Total.** Calculated annually by EIA by dividing the total heat content of coal consumed by all sectors by the total quantity consumed.

**Coal Exports.** • 1949–2011: Calculated annually by EIA by dividing the heat content of steam coal and metallurgical coal exported by the quantity exported. Data are from U.S. Department of Commerce, U.S. Census Bureau, “Monthly Report EM 545,” and predecessor forms. • 2012 forward: Calculated annually by EIA by dividing the heat content of steam coal and metallurgical coal exported by the quantity exported. The average heat content of steam coal is derived from receipts data from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”), and Form EIA-923, “Power Plant Operations Report.” Through June 2014, the average heat content of metallurgical coal is derived from receipts data from Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants”; beginning in July 2014, the average heat content of metallurgical coal is derived from receipts data from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”). Data for export quantities are from U.S. Department of Commerce, U.S. Census Bureau, “Monthly Report EM 545.”

**Coal Imports.** • 1949–1963: Calculated annually by EIA by dividing the heat content of coal imported by the quantity imported. Data are from U.S. Department of Commerce, U.S. Census Bureau, “Monthly Report IM 145,” and predecessor forms. • 1964–2011: Assumed by EIA to be 25.000 million Btu per short ton. • 2012 forward: Calculated annually by EIA by dividing the heat content of coal imported (received) by the quantity imported (received). Data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”); Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants” (data through June 2014); and Form EIA-923, “Power Plant Operations Report.”

**Coal Production.** • 1949–2011: Calculated annually by EIA by dividing the heat content of domestic coal (excluding waste coal) received by the quantity received. Data are from Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing and Transformation/Processing Coal Plants and Commercial and Institutional Users”; Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants”; Form EIA-923, “Power Plant Operations Report”; and predecessor forms. • 2012 forward: Calculated annually by EIA by dividing the heat content of domestic coal (excluding waste coal) received and exported by the quantity received and exported. Data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”); Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants” (data through June 2014); Form EIA-



923, “Power Plant Operations Report”; U.S. Department of Commerce, U.S. Census Bureau, “Monthly Report EM 545”; and predecessor forms.

**Waste Coal Supplied.** • 1989–2000: Calculated annually by EIA by dividing the heat content of waste coal consumed by the quantity consumed. Data are from Form EIA-860B, “Annual Electric Generator Report—Nonutility,” and predecessor form. • 2001 forward: Calculated by EIA by dividing the heat content of waste coal received (or consumed) by the quantity received (or consumed). Receipts data are from Form EIA-3, “Quarterly Survey of Industrial, Commercial, and Institutional Coal Users” (formerly called “Quarterly Survey of Non-Electric Sector Coal Data”), and predecessor forms. Consumption data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

## Approximate Heat Rates for Electricity

**Electricity Net Generation, Coal.** • 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for all electric utilities and electricity-only independent power producers using anthracite, bituminous coal, subbituminous coal, lignite, and beginning in 2002, waste coal and coal synfuel.

**Electricity Net Generation, Natural Gas.** • 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for all electric utilities and electricity-only independent power producers using natural gas and supplemental gaseous fuels.

**Electricity Net Generation, Noncombustible Renewable Energy.** There is no generally accepted practice for measuring the thermal conversion rates for power plants that generate electricity from hydro, geothermal, solar thermal, photovoltaic, and wind energy sources. Therefore, EIA calculates a rate factor that is equal to the annual average heat rate factor for fossil-fueled power plants in the United States (see “Electricity Net Generation, Total Fossil Fuels”). By using that factor it is possible to evaluate fossil fuel requirements for replacing those sources during periods of interruption, such as droughts. See Appendix E for more information.

**Electricity Net Generation, Nuclear.** • 1957–1984: Calculated annually by dividing the total heat content consumed in nuclear generating units by the total (net) electricity generated by nuclear generating units. The heat content and electricity generation were reported on Form FERC-1, “Annual Report of Major Electric Utilities, Licensees, and Others”; Form EIA-412, “Annual Report of Public Electric Utilities”; and predecessor forms. For 1982, the factors were published in EIA, *Historical Plant Cost and Annual Production Expenses for Selected Electric Plants 1982*, page 215. For 1983 and 1984, the factors were published in EIA, *Electric Plant Cost and Power Production Expenses 1991*, Table 13. • 1985 forward: Calculated annually by EIA by using the heat rate data reported on Form EIA-860, “Annual Electric Generator Report,” and predecessor forms.

**Electricity Net Generation, Petroleum.** • 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for all electric utilities and electricity-only independent power producers using distillate fuel oil, residual fuel oil, jet fuel, kerosene, petroleum coke, and waste oil.

**Electricity Net Generation, Total Fossil Fuels.** • 1949–1955: The weighted annual average heat rate for fossil-fueled steam-electric power plants in the United States, as published by EIA in *Thermal-Electric Plant Construction Cost and Annual Production Expenses—1981* and *Steam-Electric Plant Construction Cost and Annual Production Expenses—1978*. • 1956–1988: The weighted annual average heat rate for fossil-fueled steam-electric power plants in the United States, as published in EIA, *Electric Plant Cost and Power Production Expenses 1991*, Table 9. • 1989–2000: Calculated annually by EIA by using heat rate data reported on Form EIA-860, “Annual Electric Generator Report,” and predecessor forms; and net generation data reported on Form EIA-759, “Monthly Power Plant Report.” The computation includes data for all electric utility steam-electric plants using fossil fuels. • 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for all electric utilities and electricity-only independent power producers using coal, petroleum, natural gas, and other gases (blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels).

THIS PAGE INTENTIONALLY LEFT BLANK

# Appendix B

## Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors

---

## Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors

---

Data presented in the *Monthly Energy Review* and in other U.S. Energy Information Administration publications are expressed predominately in units that historically have been used in the United States, such as British thermal units, barrels, cubic feet, and short tons. The metric conversion factors presented in Table B1 can be used to calculate the metric-unit equivalents of values expressed in U.S. Customary units. For example, 500 short tons are the equivalent of 453.6 metric tons (500 short tons x 0.9071847 metric tons/short ton = 453.6 metric tons).

In the metric system of weights and measures, the names of multiples and subdivisions of any unit may be derived by combining the name of the unit with prefixes, such as deka, hecto, and kilo, meaning, respectively, 10, 100, 1,000, and deci, centi, and milli, meaning, respectively, one-tenth, one-hundredth, and one-thousandth. Common metric prefixes can be found in Table B2.

The conversion factors presented in Table B3 can be used to calculate equivalents in various physical units commonly used in energy analyses. For example, 10 barrels are the equivalent of 420 U.S. gallons (10 barrels x 42 gallons/barrel = 420 gallons).

**Table B1. Metric Conversion Factors**

Type of Unit	U.S. Unit		Equivalent in	Metric Units
<b>Mass</b>	1 short ton (2,000 lb)	=	0.907 184 7	metric tons (t)
	1 long ton	=	1.016 047	metric tons (t)
	1 pound (lb)	=	0.453 592 37 <sup>a</sup>	kilograms (kg)
	1 pound uranium oxide (lb U <sub>3</sub> O <sub>8</sub> )	=	0.384 647 <sup>b</sup>	kilograms uranium (kgU)
	1 ounce, avoirdupois (avdp oz)	=	28.349 52	grams (g)
<b>Volume</b>	1 barrel of oil (bbl)	=	0.158 987 3	cubic meters (m <sup>3</sup> )
	1 cubic yard (yd <sup>3</sup> )	=	0.764 555	cubic meters (m <sup>3</sup> )
	1 cubic foot (ft <sup>3</sup> )	=	0.028 316 85	cubic meters (m <sup>3</sup> )
	1 U.S. gallon (gal)	=	3.785 412	liters (L)
	1 ounce, fluid (fl oz)	=	29.573 53	milliliters (mL)
	1 cubic inch (in <sup>3</sup> )	=	16.387 06	milliliters (mL)
<b>Length</b>	1 mile (mi)	=	1.609 344 <sup>a</sup>	kilometers (km)
	1 yard (yd)	=	0.914 4 <sup>a</sup>	meters (m)
	1 foot (ft)	=	0.304 8 <sup>a</sup>	meters (m)
	1 inch (in)	=	2.54 <sup>a</sup>	centimeters (cm)
<b>Area</b>	1 acre	=	0.404 69	hectares (ha)
	1 square mile (mi <sup>2</sup> )	=	2.589 988	square kilometers (km <sup>2</sup> )
	1 square yard (yd <sup>2</sup> )	=	0.836 127 4	square meters (m <sup>2</sup> )
	1 square foot (ft <sup>2</sup> )	=	0.092 903 04 <sup>a</sup>	square meters (m <sup>2</sup> )
	1 square inch (in <sup>2</sup> )	=	6.451 6 <sup>a</sup>	square centimeters (cm <sup>2</sup> )
<b>Energy</b>	1 British thermal unit (Btu) <sup>c</sup>	=	1,055.055 852 62 <sup>a</sup>	joules (J)
	1 calorie (cal)	=	4.186 8 <sup>a</sup>	joules (J)
	1 kilowatthour (kWh)	=	3.6 <sup>a</sup>	megajoules (MJ)
<b>Temperature<sup>d</sup></b>	32 degrees Fahrenheit (°F)	=	0 <sup>a</sup>	degrees Celsius (°C)
	212 degrees Fahrenheit (°F)	=	100 <sup>a</sup>	degrees Celsius (°C)

[a] Exact conversion.

[b] Calculated by the U.S. Energy Information Administration.

[c] The Btu used in this table is the International Table Btu adopted by the Fifth International Conference on Properties of Steam, London, 1956.

[d] To convert degrees Fahrenheit (°F) to degrees Celsius (°C) exactly, subtract 32, then multiply by 5/9.

Notes: • Spaces have been inserted after every third digit to the right of the decimal for ease of reading. • Most metric units belong to the International System of Units (SI), and the liter, hectare, and metric ton are accepted for use with the SI units. For more information about the SI units, see <http://physics.nist.gov/cuu/Units/index.html>.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: • General Services Administration, Federal Standard 376B, *Preferred Metric Units for General Use by the Federal Government* (Washington, DC, January 1993), pp. 9–11, 13, and 16. • U.S. Department of Commerce, National Institute of Standards and Technology, *Special Publications 330, 811, and 814*. • American National Standards Institute/Institute of Electrical and Electronic Engineers, ANSI/IEEE Std268-1992, pp. 28 and 29.

**Table B2. Metric Prefixes**

Unit Multiple	Prefix	Symbol	Unit Subdivision	Prefix	Symbol
10 <sup>1</sup>	deka	da	10 <sup>-1</sup>	deci	d
10 <sup>2</sup>	hecto	h	10 <sup>-2</sup>	centi	c
10 <sup>3</sup>	kilo	k	10 <sup>-3</sup>	milli	m
10 <sup>6</sup>	mega	M	10 <sup>-6</sup>	micro	μ
10 <sup>9</sup>	giga	G	10 <sup>-9</sup>	nano	n
10 <sup>12</sup>	tera	T	10 <sup>-12</sup>	pico	p
10 <sup>15</sup>	peta	P	10 <sup>-15</sup>	femto	f
10 <sup>18</sup>	exa	E	10 <sup>-18</sup>	atto	a
10 <sup>21</sup>	zetta	Z	10 <sup>-21</sup>	zepto	z
10 <sup>24</sup>	yotta	Y	10 <sup>-24</sup>	yocto	y

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: U.S. Department of Commerce, National Institute of Standards and Technology, *The International System of Units (SI)*, NIST Special Publication 330, 1991 Edition (Washington, DC, August 1991), p.10.

**Table B3. Other Physical Conversion Factors**

Energy Source	Original Unit		Equivalent in Final Units
<b>Petroleum</b>	1 barrel (bbl)	=	42 <sup>a</sup> U.S. gallons (gal)
<b>Coal</b>	1 short ton	=	2,000 <sup>a</sup> pounds (lb)
	1 long ton	=	2,240 <sup>a</sup> pounds (lb)
	1 metric ton (t)	=	1,000 <sup>a</sup> kilograms (kg)
<b>Wood</b>	1 cord (cd)	=	1.25 <sup>b</sup> shorts tons
	1 cord (cd)	=	128 <sup>a</sup> cubic feet (ft <sup>3</sup> )

[a] Exact conversion.

[b] Calculated by the U.S. Energy Information Administration.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: U.S. Department of Commerce, National Institute of Standards and Technology, *Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices*, NIST Handbook 44, 1994 Edition (Washington, DC, October 1993), pp. B-10, C-17, and C-21.

# Appendix C

**Population, U.S. Gross Domestic Product, and U.S. Gross Output**

---

# Population, U.S. Gross Domestic Product, and U.S. Gross Output

**Table C1. Population, U.S. Gross Domestic Product, and U.S. Gross Output**

	Population			U.S. Gross Domestic Product			U.S. Gross Output <sup>a</sup>
	United States <sup>b</sup>	World	United States as Share of World	Billion Nominal Dollars <sup>d</sup>	Billion Chained (2012) Dollars <sup>e</sup>	Implicit Price Deflator <sup>c</sup> (2012 = 1.00000)	Billion Nominal Dollars <sup>d</sup>
	Million People		Percent				
1950 .....	152.3	2,557.6	6.0	299.8	2,289.5	0.13095	577.8
1955 .....	165.9	2,782.1	6.0	425.5	2,871.2	.14819	802.6
1960 .....	180.7	3,043.0	5.9	542.4	3,260.0	.16638	1,006.0
1965 .....	194.3	3,350.8	5.8	742.3	4,170.8	.17798	1,356.0
1970 .....	205.1	3,713.5	5.5	1,073.3	4,951.3	.21677	1,903.0
1975 .....	216.0	4,089.0	5.3	1,684.9	5,644.8	.29849	3,055.3
1980 .....	227.2	4,445.0	5.1	2,857.3	6,759.2	.42273	5,462.0
1981 .....	229.5	4,526.3	5.1	3,207.0	6,930.7	.46273	6,033.5
1982 .....	231.7	4,606.5	5.0	3,343.8	6,805.8	.49132	6,175.0
1983 .....	233.8	4,687.7	5.0	3,634.0	7,117.7	.51056	6,631.0
1984 .....	235.8	4,766.5	4.9	4,037.6	7,632.8	.52898	7,313.8
1985 .....	237.9	4,848.4	4.9	4,339.0	7,951.1	.54571	7,775.7
1986 .....	240.1	4,932.4	4.9	4,579.6	8,226.4	.55670	8,031.0
1987 .....	242.3	5,019.0	4.8	4,855.2	8,511.0	.57046	8,707.5
1988 .....	244.5	5,106.4	4.8	5,236.4	8,866.5	.59059	9,434.2
1989 .....	246.8	5,193.4	4.8	5,641.6	9,192.1	.61374	10,069.8
1990 .....	249.6	5,282.0	4.7	5,963.1	9,365.5	.63671	10,624.6
1991 .....	253.0	5,365.3	4.7	6,158.1	9,355.4	.65825	10,808.0
1992 .....	256.5	5,449.4	4.7	6,520.3	9,684.9	.67325	11,381.0
1993 .....	259.9	5,530.9	4.7	6,858.6	9,951.5	.68920	12,024.4
1994 .....	263.1	5,610.7	4.7	7,287.2	10,352.4	.70392	12,826.8
1995 .....	266.3	5,691.8	4.7	7,639.7	10,630.3	.71868	13,653.2
1996 .....	269.4	5,772.0	4.7	8,073.1	11,031.4	.73183	14,463.4
1997 .....	272.6	5,850.7	4.7	8,577.6	11,521.9	.74445	15,393.3
1998 .....	275.9	5,928.2	4.7	9,062.8	12,038.3	.75283	16,216.8
1999 .....	279.0	6,005.1	4.6	9,630.7	12,610.5	.76370	17,272.3
2000 .....	282.2	6,081.9	4.6	10,252.3	13,131.0	.78078	18,623.9
2001 .....	285.0	6,159.1	4.6	10,581.8	13,262.1	.79790	18,888.3
2002 .....	287.6	6,236.7	4.6	10,936.4	13,493.1	.81052	19,178.3
2003 .....	290.1	6,314.7	4.6	11,458.2	13,879.1	.82557	20,141.2
2004 .....	292.8	6,393.1	4.6	12,213.7	14,406.4	.84780	21,690.2
2005 .....	295.5	6,471.5	4.6	13,036.6	14,912.5	.87421	23,512.9
2006 .....	298.4	6,551.9	4.6	13,814.6	15,338.3	.90066	24,931.4
2007 .....	301.2	6,634.4	4.5	14,451.9	15,626.0	.92486	26,238.5
2008 .....	304.1	6,718.3	4.5	14,712.8	15,604.7	.94285	26,989.2
2009 .....	306.8	6,801.8	4.5	14,448.9	15,208.8	.95004	24,919.5
2010 .....	309.3	6,884.0	4.5	14,992.1	15,598.8	.96111	26,422.4
2011 .....	311.6	6,965.9	4.5	15,542.6	15,840.7	.98118	27,999.5
2012 .....	313.9	7,047.8	4.5	16,197.0	16,197.0	1.00000	29,186.8
2013 .....	316.1	7,130.5	4.4	16,784.9	16,495.4	1.01755	30,291.3
2014 .....	318.4	7,212.9	4.4	17,527.3	16,912.0	1.03638	31,740.0
2015 .....	320.7	7,294.3	4.4	18,238.3	17,432.2	1.04624	32,222.3
2016 .....	323.1	7,375.3	4.4	18,745.1	17,730.5	1.05722	32,882.2
2017 .....	325.1	7,455.1	4.4	19,543.0	18,144.1	1.07710	34,474.7
2018 .....	326.8	7,533.7	4.3	20,611.9	18,687.8	1.10296	36,603.4
2019 .....	328.3	7,612.1	4.3	21,433.2	19,091.7	1.12265	37,817.0
2020 .....	329.5	7,693.3	4.3	20,932.8	18,422.6	1.13626	36,737.4

<sup>a</sup> Gross output is the value of gross domestic product (GDP) plus the value of intermediate inputs used to produce GDP.

<sup>b</sup> Resident population of the 50 states and the District of Columbia estimated for July 1 of each year.

<sup>c</sup> The gross domestic product implicit price deflator is used to convert nominal dollars to chained (2012) dollars.

<sup>d</sup> See "Nominal Dollars" in Glossary.

<sup>e</sup> See "Chained Dollars" in Glossary.

Notes: • Data are estimates. • U.S. geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **United States Population: 1949–1989**—U.S. Department of Commerce (DOC), U.S. Census Bureau, Current Population Reports Series P-25

(June 2000). **1990–1999**—DOC, U.S. Census Bureau, "Time Series of Intercensal State Population Estimates" (April 2002). **2000–2009**—DOC, U.S. Census Bureau, "Intercensal Estimates of the Resident Population for the United States, Regions, States, and Puerto Rico" (September 2011). **2010 forward**—DOC, U.S. Census Bureau, "Annual Estimates of the Resident Population for the United States, Regions, States, and Puerto Rico" (December 2020). • **World Population: 1950 forward**—DOC, U.S. Census Bureau, International Database (December 2020). • **United States as Share of World Population:** Calculated as U.S. population divided by world population. • **U.S. Gross Domestic Product: 1949 forward**—DOC, Bureau of Economic Analysis (BEA), National Income and Product Accounts (August 2020), Tables 1.1.5, 1.1.6, and 1.1.9. • **U.S. Gross Output: 1949–1996**—DOC, BEA, GDP by industry (Historical) data (October 2019). **1997 forward**—DOC, BEA, GDP by Industry data (March 2021).



# Appendix D

Estimated Primary Energy Consumption in the  
United States, Selected Years, 1635-1945

---

# Estimated Primary Energy Consumption in the United States, Selected Years, 1635-1945

**Table D1. Estimated Primary Energy Consumption in the United States, Selected Years, 1635–1945** (Quadrillion Btu)

	Fossil Fuels				Renewable Energy			Electricity Net Imports <sup>b</sup>	Total
	Coal	Natural Gas	Petroleum	Total	Conventional Hydroelectric Power	Biomass	Total		
						Wood <sup>a</sup>			
1635 .....	NA	--	--	NA	--	(s)	(s)	--	(s)
1645 .....	NA	--	--	NA	--	0.001	0.001	--	0.001
1655 .....	NA	--	--	NA	--	.002	.002	--	.002
1665 .....	NA	--	--	NA	--	.005	.005	--	.005
1675 .....	NA	--	--	NA	--	.007	.007	--	.007
1685 .....	NA	--	--	NA	--	.009	.009	--	.009
1695 .....	NA	--	--	NA	--	.014	.014	--	.014
1705 .....	NA	--	--	NA	--	.022	.022	--	.022
1715 .....	NA	--	--	NA	--	.037	.037	--	.037
1725 .....	NA	--	--	NA	--	.056	.056	--	.056
1735 .....	NA	--	--	NA	--	.080	.080	--	.080
1745 .....	NA	--	--	NA	--	.112	.112	--	.112
1755 .....	NA	--	--	NA	--	.155	.155	--	.155
1765 .....	NA	--	--	NA	--	.200	.200	--	.200
1775 .....	NA	--	--	NA	--	.249	.249	--	.249
1785 .....	NA	--	--	NA	--	.310	.310	--	.310
1795 .....	NA	--	--	NA	--	.402	.402	--	.402
1805 .....	NA	--	--	NA	--	.537	.537	--	.537
1815 .....	NA	--	--	NA	--	.714	.714	--	.714
1825 .....	NA	--	--	NA	--	.960	.960	--	.960
1835 .....	NA	--	--	NA	--	1.305	1.305	--	1.305
1845 .....	NA	--	--	NA	--	1.757	1.757	--	1.757
1850 .....	0.219	--	--	0.219	--	2.138	2.138	--	2.357
1855 .....	.421	--	--	.421	--	2.389	2.389	--	2.810
1860 .....	.518	--	0.003	.521	--	2.641	2.641	--	3.162
1865 .....	.632	--	.010	.642	--	2.767	2.767	--	3.409
1870 .....	1.048	--	.011	1.059	--	2.893	2.893	--	3.952
1875 .....	1.440	--	.011	1.451	--	2.872	2.872	--	4.323
1880 .....	2.054	--	.096	2.150	--	2.851	2.851	--	5.001
1885 .....	2.840	0.082	.040	2.962	--	2.683	2.683	--	5.645
1890 .....	4.062	.257	.156	4.475	0.022	2.515	2.537	--	7.012
1895 .....	4.950	.147	.168	5.265	.090	2.306	2.396	--	7.661
1900 .....	6.841	.252	.229	7.322	.250	2.015	2.265	--	9.587
1905 .....	10.001	.372	.610	10.983	.386	1.843	2.229	--	13.212
1910 .....	12.714	.540	1.007	14.261	.539	1.765	2.304	--	16.565
1915 .....	13.294	.673	1.418	15.385	.659	1.688	2.347	0.002	17.734
1920 .....	15.504	.813	2.676	18.993	.738	1.610	2.348	.003	21.344
1925 .....	14.706	1.191	4.280	20.177	.668	1.533	2.201	.004	22.382
1930 .....	13.639	1.932	5.897	21.468	.752	1.455	2.207	.005	23.680
1935 .....	10.634	1.919	5.675	18.228	.806	1.397	2.203	.005	20.436
1940 .....	12.535	2.665	7.760	22.960	.880	1.358	2.238	.007	25.205
1945 .....	15.972	3.871	10.110	29.953	1.442	<sup>a</sup> 1.261	2.703	.009	32.665

<sup>a</sup> There is a discontinuity in the "Wood" time series between 1945 (in this table) and 1949 (in Table 10.1). Through 1945, data are for fuelwood only; beginning in 1949, data are for wood and wood-derived fuels.

<sup>b</sup> Electricity transmitted across U.S. borders. Net imports equal imports minus exports.

NA=Not available. -- =Not applicable. (s)=Less than 0.5 trillion Btu.

Notes: • For years not shown, data are not available. • See Tables 1.3 and 10.1 for continuation of these data series beginning in 1949. • See Note, "Geographic Coverage of Statistics for 1635–1945," at end of section.

Sources: • **Fossil Fuels:** *Energy in the American Economy, 1850–1975*, Table VII. • **Conventional Hydroelectric Power:** *Energy in the American Economy, 1850–1975*, Table II. • **Wood:** 1635–1845—U.S. Department of Agriculture,

Circular No. 641, *Fuel Wood Used in the United States 1630–1930*, February 1942. This source estimates fuelwood consumption in cords per decade, which were converted to Btu using the conversion factor of 20 million Btu per cord. The annual average value for each decade was assigned to the fifth year of the decade on the assumption that annual use was likely to increase during any given decade and the average annual value was more likely to reflect mid-decade yearly consumption than use at either the beginning or end of the decade. Values thus begin in 1635 and are plotted at 10-year intervals. **1850–1945—Energy in the American Economy, 1850–1975, Table VII. • **Electricity Net Imports:** *Energy in the American Economy, 1850–1975*, Tables I and VI. Electricity net imports are assumed to equal hydroelectric consumption minus hydroelectric production (data are converted to Btu by multiplying by 3,412 Btu per kilowatthour).**

**Note. Geographic Coverage of Statistics for 1635–1945.**

Table D1 presents estimates of U.S. energy consumption by energy source for a period that begins a century and a half before the original 13 colonies formed a political union and continues through the decades during which the United States was still expanding territorially. The question thus arises, what exactly is meant by “U.S. consumption” of an energy source for those years when the United States did not formally exist or consisted of less territory than is now encompassed by the 50 states and the District of Columbia?

The documents used to assemble the estimates, and (as far as possible) the sources of those documents, were reviewed carefully for clues to geographic coverage. For most energy sources, the extent of coverage expanded more rapidly than the nation, defined as all the official states and the District of Columbia. Estimates or measurements of consumption of each energy source generally appear to follow settlement patterns. That is, they were made for areas of the continent that were settled enough to have economically significant consumption even though those areas were not to become states for years. The wood data series, for example, begins in 1635 and includes 12 of the original colonies (excepting Georgia), as well as Maine, Vermont, and the area that would become the District of Columbia. By the time the series reaches 1810, the rest of the continental states are all included, although the last of the 48 states to achieve statehood did not do so until 1912. Likewise, the coal data series begins in 1850 but includes consumption in areas, such as Utah and Washington (state), which were significant coal producing regions but had not yet attained statehood. (Note: No data were available on state-level historical coal consumption. The coal data shown in Table D1 through 1945 describe *apparent* consumption, i.e., production plus imports minus exports. The geographic coverage for coal was therefore based on a tally of coal-*producing* states listed in various historical issues of *Minerals Yearbook*. It is likely that coal was consumed in states where it was not mined in significant quantities.)

By energy source, the extent of coverage can be summarized as follows:

- Coal—35 coal-producing states by 1885.
- Natural Gas—All 48 contiguous states, the District of Columbia, and Alaska by 1885.
- Petroleum—All 48 contiguous states, the District of Columbia, and Alaska by 1885.
- Conventional Hydroelectric Power—Coverage for 1890 and 1895 is uncertain, but probably the 48 contiguous states and the District of Columbia. Coverage for 1900–1945 is the 48 contiguous states, and the District of Columbia.
- Wood—All 48 contiguous states and the District of Columbia by 1810.

THIS PAGE INTENTIONALLY LEFT BLANK

# Appendix E

## Alternative Approaches for Deriving Energy Contents of Noncombustible Renewables

---

# Alternative Approaches for Deriving Energy Contents of Noncombustible Renewables

EIA compiles data on most energy sources in physical units, such as barrels and cubic feet, in order to calculate total primary energy consumption. To sum data for different energy sources, EIA converts the data to the common unit of British thermal units (Btu), a measure that is based on the thermal conversion of energy resources to heat and power.

Noncombustible renewables are resources from which energy is extracted without burning or combusting fuel. They include hydroelectric, geothermal, solar, and wind energy. When noncombustible renewables are used to generate electricity, there is no fuel combustion and, therefore, no set Btu conversion factors for the energy sources.<sup>1</sup> However, there are several possible approaches for converting that electricity to Btu. Three of these approaches are described below.

## *Fossil Fuel Equivalency Approach*

In Sections 1, 2, and 10 of the *Monthly Energy Review*, EIA calculates total primary energy consumption for noncombustible renewable electricity in Btu by applying a fossil fuel equivalency factor. Under that approach, the primary energy consumption of noncombustible renewable electricity can be viewed as the sum of captured energy "transformed into electricity" and an "adjustment for fossil fuel equivalency."

The adjustment for fossil fuel equivalency is equal to the difference between total primary consumption of noncombustible renewables for electricity generation in Btu (calculated using the fossil fuels heat rate in Table A6) and the captured energy of that electricity (calculated using the constant conversion factor of 3,412 Btu per kWh). The fossil fuels heat rate is equal to the thermal efficiency across fossil fuel-fired generating stations based on net generation. The fossil fuel equivalency adjustment represents the energy that would have been consumed if electricity had been generated by fossil fuels. By using that factor, it is possible, for example, to evaluate fossil fuel requirements for replacing electricity generation during periods of interruptions, such as droughts.

## *Captured Energy Approach*

Captured energy (Tables E1a and E1b) reflects the primary energy captured for economic use and does not include losses. Thus, it is the net energy available for direct consumption after transformation of a noncombustible renewable into electricity. In other words, captured energy is the energy measured as the "output" of a generating unit, such as electricity from a wind turbine or solar plant. The captured energy approach is often used to show the economically significant energy transformations in the United States. There is no market for the resource-specific energy apart from its immediate, site-specific energy conversion, and there is no substantive opportunity cost to its continued exploitation.<sup>2</sup>

## *Incident Energy Approach*

Incident energy is the mechanical, radiation, or thermal energy that is measurable as the "input" of the device. EIA defines "incident energy" for noncombustible renewables as the gross energy that first strikes an energy conversion device:

- For hydroelectric, the energy contained in the water passing through the penstock (a closed conduit for carrying water to the turbines)
- For geothermal, the energy contained in the hot fluid at the surface of the wellbore
- For wind, the energy contained in the wind that passes through the rotor disc
- For solar, the energy contained in the sunlight that strikes the panel or collector mirror

The incident energy approach to converting noncombustible renewable electricity to Btu could, in theory, be used to account for “losses” that are due to the inability to convert 100% of incident energy to a useful form of energy. EIA does not publish total primary energy consumption estimates based on the incident energy approach because it would be difficult to obtain accurate estimates of input energy without creating undue burden on survey respondents. Few renewable electricity power plants track cumulative input energy due to its lack of economic significance or other purpose. In addition, estimated energy efficiencies of renewable conversion technologies vary significantly across technologies, site-specific configurations, and environmental factors.<sup>3</sup>

---

<sup>1</sup>Direct use of noncombustible renewables in the form of heat (e.g., solar thermal heating) is estimated separately and is measured in Btu.

<sup>2</sup>There is an initial opportunity cost when a facility is first built: water behind a dam might flood land that could have been used for other purposes, or a solar panel might shade an area that could have used the sunlight. But that is a “fixed” opportunity cost that does not change during the operation of the plant.

<sup>3</sup>Based on EIA research conducted in 2016, engineering estimates of conversion efficiencies for noncombustible renewables range from less than 20% for solar photovoltaics and geothermal to 90% for large-scale hydroelectricity plants. Those estimates are notional indications of the energy output as a percent of energy input at each technology based on typical equipment operating within the normal operating range for that technology.

**Table E1a. Noncombustible Renewable Primary Energy Consumption: Conventional Hydroelectric Power, Geothermal, and Wind** (Trillion Btu)

	Conventional Hydroelectric Power <sup>a</sup>			Geothermal <sup>b</sup>				Wind <sup>c</sup>		
	Trans- formed Into Electricity <sup>d,e</sup>	Adjustment for Fossil Fuel Equivalence <sup>f</sup>	Total Primary Energy <sup>g</sup>	Direct Consump- tion <sup>h</sup>	Trans- formed Into Electricity <sup>d,i</sup>	Adjustment for Fossil Fuel Equivalence <sup>f</sup>	Total Primary Energy <sup>j</sup>	Trans- formed Into Electricity <sup>d,i</sup>	Adjustment for Fossil Fuel Equivalence <sup>f</sup>	Total Primary Energy <sup>g</sup>
1950 .....	344	1,071	1,415	NA	NA	NA	NA	NA	NA	NA
1955 .....	397	963	1,360	NA	NA	NA	NA	NA	NA	NA
1960 .....	510	1,098	1,608	NA	(s)	(s)	(s)	NA	NA	NA
1965 .....	672	1,387	2,059	NA	1	1	2	NA	NA	NA
1970 .....	856	1,777	2,634	NA	2	4	6	NA	NA	NA
1975 .....	1,034	2,120	3,155	NA	11	23	34	NA	NA	NA
1980 .....	953	1,948	2,900	NA	17	35	53	NA	NA	NA
1981 .....	900	1,858	2,758	NA	19	40	59	NA	NA	NA
1982 .....	1,066	2,200	3,266	NA	17	34	51	NA	NA	NA
1983 .....	1,144	2,383	3,527	NA	21	43	64	(s)	(s)	(s)
1984 .....	1,107	2,279	3,386	NA	26	54	81	(s)	(s)	(s)
1985 .....	970	2,000	2,970	NA	32	66	97	(s)	(s)	(s)
1986 .....	1,003	2,068	3,071	NA	35	73	108	(s)	(s)	(s)
1987 .....	863	1,772	2,635	NA	37	76	112	(s)	(s)	(s)
1988 .....	771	1,563	2,334	NA	35	71	106	(s)	(s)	(s)
1989 .....	<sup>e</sup> 928	1,909	2,837	9	<sup>i</sup> 50	102	162	<sup>j</sup> 7	15	22
1990 .....	999	2,047	3,046	10	53	108	171	10	19	29
1991 .....	986	2,030	3,016	11	54	112	178	10	21	31
1992 .....	864	1,754	2,617	12	55	112	179	10	20	30
1993 .....	957	1,935	2,892	13	57	116	186	10	21	31
1994 .....	888	1,796	2,683	13	53	107	173	12	24	36
1995 .....	1,061	2,145	3,205	14	46	92	152	11	22	33
1996 .....	1,185	2,405	3,590	15	49	99	163	11	22	33
1997 .....	1,216	2,424	3,640	16	50	100	167	11	22	34
1998 .....	1,103	2,194	3,297	18	50	100	168	10	21	31
1999 .....	1,090	2,177	3,268	19	51	101	171	15	31	46
2000 .....	940	1,871	2,811	21	48	96	164	19	38	57
2001 .....	740	1,502	2,242	22	47	95	164	23	47	70
2002 .....	902	1,787	2,689	24	49	98	171	35	70	105
2003 .....	941	1,851	2,793	27	49	97	173	38	75	113
2004 .....	916	1,773	2,688	30	51	98	178	48	93	142
2005 .....	922	1,781	2,703	34	50	97	181	61	117	178
2006 .....	987	1,882	2,869	37	50	95	181	91	173	264
2007 .....	845	1,602	2,446	41	50	95	186	118	223	341
2008 .....	869	1,642	2,511	46	51	96	192	189	357	546
2009 .....	933	1,736	2,669	54	51	95	200	252	469	721
2010 .....	888	1,651	2,539	60	52	97	208	323	600	923
2011 .....	1,090	2,013	3,103	64	52	97	212	410	758	1,168
2012 .....	943	1,686	2,629	64	53	95	212	480	860	1,340
2013 .....	916	1,646	2,562	64	54	97	214	573	1,029	1,601
2014 .....	885	1,582	2,467	64	54	97	214	620	1,108	1,728
2015 .....	850	1,471	2,321	64	54	94	212	651	1,127	1,777
2016 .....	914	1,559	2,472	64	54	92	210	774	1,321	2,096
2017 .....	1,025	1,742	2,767	64	54	92	210	868	1,475	2,343
2018 .....	998	1,665	2,663	64	54	91	209	930	1,552	2,482
2019 .....	982	1,581	2,564	64	53	85	201	1,010	1,625	2,635
2020 .....	993	1,599	2,592	64	58	93	214	1,152	1,854	3,006

<sup>a</sup> Conventional hydroelectricity net generation. Through 1989, also includes hydroelectric pumped storage.

<sup>b</sup> Geothermal heat pump and direct use energy; and geothermal electricity net generation.

<sup>c</sup> Wind electricity net generation.

<sup>d</sup> Electricity net generation in kilowatthours (kWh) multiplied by 3,412 Btu/kWh, the heat content of electricity (see Table A6).

<sup>e</sup> Through 1988, data are for electric utilities and industrial plants. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

<sup>f</sup> Equals the difference between the fossil-fuel equivalent value of electricity and the captured energy consumed as electricity. The fossil-fuel equivalent value of electricity equals electricity net generation in kilowatthours multiplied by the total fossil fuels heat rate factors (see Table A6). The captured energy consumed as electricity equals electricity net generation in kilowatthours multiplied by 3,412 Btu/kWh, the heat content of electricity (see Table A6).

<sup>g</sup> Electricity net generation in kilowatthours multiplied by the total fossil fuels

heat rate factors (see Table A6).

<sup>h</sup> Geothermal heat pump and direct use energy.

<sup>i</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

<sup>j</sup> Direct consumption of energy; and energy used to generate electricity, calculated as electricity net generation in kilowatthours multiplied by the total fossil fuels heat rate factors (see Table A6).

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Geothermal direct consumption data are estimates. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **Conventional Hydroelectric Power** and **Wind**: Tables 7.2a, 10.1, and A6. • **Geothermal**: Tables 7.2a, 10.1, 10.2a, 10.2b, and A6.



**Table E1b. Noncombustible Renewable Primary Energy Consumption: Solar and Total**  
(Trillion Btu)

	Solar <sup>a</sup>						Total <sup>b</sup>		
	Distributed <sup>c</sup>			Utility-Scale <sup>d</sup>		Total Primary Energy <sup>i</sup>	Captured Energy <sup>j</sup>	Adjustment for Fossil Fuel Equivalence <sup>g</sup>	Total Primary Energy <sup>i</sup>
	Direct Consumption <sup>e</sup>	Transformed Into Electricity <sup>f</sup>	Adjustment for Fossil Fuel Equivalence <sup>g</sup>	Transformed Into Electricity <sup>f,h</sup>	Adjustment for Fossil Fuel Equivalence <sup>g</sup>				
1950 .....	NA	NA	NA	NA	NA	NA	344	1,071	1,415
1955 .....	NA	NA	NA	NA	NA	NA	397	963	1,360
1960 .....	NA	NA	NA	NA	NA	NA	510	1,098	1,608
1965 .....	NA	NA	NA	NA	NA	NA	673	1,388	2,061
1970 .....	NA	NA	NA	NA	NA	NA	858	1,781	2,639
1975 .....	NA	NA	NA	NA	NA	NA	1,045	2,143	3,188
1980 .....	NA	NA	NA	NA	NA	NA	970	1,983	2,953
1981 .....	NA	NA	NA	NA	NA	NA	920	1,898	2,817
1982 .....	NA	NA	NA	NA	NA	NA	1,082	2,234	3,316
1983 .....	NA	NA	NA	NA	NA	NA	1,165	2,426	3,591
1984 .....	NA	NA	NA	(s)	(s)	(s)	1,133	2,334	3,467
1985 .....	NA	NA	NA	(s)	(s)	(s)	1,002	2,066	3,068
1986 .....	NA	NA	NA	(s)	(s)	(s)	1,038	2,141	3,179
1987 .....	NA	NA	NA	(s)	(s)	(s)	900	1,847	2,747
1988 .....	NA	NA	NA	(s)	(s)	(s)	807	1,634	2,441
1989 .....	52	(s)	(s)	<sup>h</sup> 1	2	54	1,047	2,029	3,075
1990 .....	55	(s)	(s)	1	3	59	1,128	2,177	3,305
1991 .....	56	(s)	(s)	2	3	62	1,120	2,166	3,286
1992 .....	58	(s)	(s)	1	3	63	1,000	1,889	2,889
1993 .....	60	(s)	(s)	2	3	65	1,099	2,075	3,173
1994 .....	62	(s)	(s)	2	3	67	1,029	1,931	2,960
1995 .....	63	(s)	(s)	2	3	68	1,196	2,263	3,458
1996 .....	63	(s)	(s)	2	4	69	1,325	2,531	3,856
1997 .....	62	(s)	1	2	3	68	1,358	2,551	3,909
1998 .....	61	(s)	1	2	3	67	1,245	2,319	3,564
1999 .....	60	(s)	1	2	3	66	1,237	2,313	3,550
2000 .....	57	(s)	1	2	3	63	1,087	2,009	3,096
2001 .....	55	(s)	1	2	4	62	890	1,648	2,538
2002 .....	53	1	1	2	4	60	1,066	1,960	3,025
2003 .....	51	1	1	2	4	58	1,109	2,028	3,138
2004 .....	50	1	2	2	4	58	1,097	1,969	3,067
2005 .....	49	1	2	2	4	58	1,119	2,001	3,120
2006 .....	51	2	3	2	3	61	1,218	2,157	3,375
2007 .....	53	2	5	2	4	66	1,110	1,928	3,038
2008 .....	54	4	7	3	6	74	1,217	2,107	3,323
2009 .....	55	5	10	3	6	78	1,353	2,315	3,668
2010 .....	56	8	15	4	8	91	1,390	2,371	3,761
2011 .....	58	13	24	6	11	112	1,692	2,903	4,595
2012 .....	59	21	38	15	26	159	1,635	2,705	4,339
2013 .....	61	28	50	31	55	225	1,726	2,877	4,602
2014 .....	62	38	68	60	108	337	1,783	2,963	4,746
2015 .....	63	48	84	85	147	427	1,815	2,922	4,737
2016 .....	64	64	109	123	210	570	2,057	3,291	5,348
2017 .....	65	82	139	182	309	777	2,339	3,758	6,097
2018 .....	65	101	168	218	363	915	2,430	3,839	6,269
2019 .....	65	119	192	245	395	1,017	2,538	3,879	6,417
2020 .....	65	142	229	310	499	1,246	2,783	4,275	7,058

<sup>a</sup> Solar thermal direct use energy; and solar photovoltaic (PV) and solar thermal electricity net generation.

<sup>b</sup> Conventional hydroelectricity net generation; geothermal heat pump and direct use energy; geothermal electricity net generation; wind electricity net generation; solar thermal direct use energy; and solar photovoltaic (PV) and solar thermal electricity net generation.

<sup>c</sup> Distributed (small-scale) facilities (electric generators have a combined generator nameplate capacity of less than 1 megawatt).

<sup>d</sup> Utility-scale facilities (combined generator nameplate capacity of 1 megawatt or more).

<sup>e</sup> Solar thermal direct use energy.

<sup>f</sup> Electricity net generation in kilowatthours (kWh) multiplied by 3,412 Btu/kWh, the heat content of electricity (see Table A6).

<sup>g</sup> Equals the difference between the fossil-fuel equivalent value of electricity and the captured energy consumed as electricity. The fossil-fuel equivalent value of electricity equals electricity net generation in kilowatthours multiplied by the total fossil fuels heat rate factors (see Table A6). The captured energy consumed as electricity equals electricity net generation in kilowatthours multiplied by 3,412 Btu/kWh, the heat content of electricity (see Table A6).

<sup>h</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

<sup>i</sup> Direct consumption of energy; and energy used to generate electricity, calculated as electricity net generation in kilowatthours multiplied by the total fossil fuels heat rate factors (see Table A6).

<sup>j</sup> Direct consumption of energy plus captured energy consumed as electricity, which is calculated as electricity net generation in kilowatthours (kWh) multiplied by 3,412 Btu/kWh, the heat content of electricity (see Table A6).

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Beginning in 1989, data for distributed solar and total captured energy are estimates. For the current year, data for utility-scale solar are estimates.

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 states and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#appendices> (Excel and CSV files) for all available annual data beginning in 1949.

Sources: • **Solar:** Tables 10.5, 10.6, and A6. • **Total:** Tables 7.2a, 10.1, 10.2a, 10.2b, 10.5, 10.6, and A6.

THIS PAGE INTENTIONALLY LEFT BLANK

# Glossary

---

**Alcohol:** The family name of a group of organic chemical compounds composed of carbon, hydrogen, and oxygen. The series of molecules vary in chain length and are composed of a **hydrocarbon** plus a hydroxyl group;  $\text{CH}_3\text{-(CH}_2\text{)}_n\text{-OH}$  (e.g., **methanol**, **ethanol**, and tertiary butyl alcohol). See **Fuel ethanol**.

**Alternative fuel:** Alternative fuels, for transportation applications, include the following: **methanol**; denatured **ethanol**, and other **alcohols**; fuel mixtures containing 85 percent or more by volume of methanol, denatured ethanol, and other alcohols with **motor gasoline** or other fuels; **natural gas**; **liquefied petroleum gas (propane)**; **hydrogen**; **coal-derived liquid fuels**; fuels (other than alcohol) derived from biological materials (**biofuels** such as soy **diesel fuel**); **electricity** (including electricity from **solar energy**); and "... any other fuel the Secretary determines, by rule, is substantially not **petroleum** and would yield substantial energy security benefits and substantial environmental benefits." The term "alternative fuel" does not include alcohol or other blended portions of primarily petroleum-based fuels used as **oxygenates** or extenders, i.e., **MTBE**, **ETBE**, other ethers, and the 10-percent ethanol portion of **gasohol**.

**Alternative-fuel vehicle (AFV):** A vehicle designed to operate on an **alternative fuel** (e.g., compressed **natural gas**, **methane** blend, or **electricity**). The vehicle could be either a dedicated vehicle designed to operate exclusively on alternative fuel or a nondedicated vehicle designed to operate on alternative fuel and/or a traditional fuel.

**Anthracite:** The highest rank of **coal**; used primarily for residential and commercial space heating. It is a hard, brittle, and black lustrous coal, often referred to as hard coal, containing a high percentage of fixed carbon and a low percentage of volatile matter. The moisture content of fresh-mined anthracite generally is less than 15 percent. The heat content of anthracite ranges from 22 to 28 million **Btu** per **short ton** on a moist, mineral-matter-free basis. The heat content of anthracite coal consumed in the United States averages 25 million Btu per short ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter). **Note:** Since the 1980's, anthracite refuse or mine waste has been used for steam-electric power generation. This fuel typically has a heat content of 15 million Btu per ton or less.

**Anthropogenic:** Made or generated by a human or caused by human activity. The term is used in the context of global **climate change** to refer to gaseous emissions that are the result of human activities, as well as other potentially climate-altering activities, such as deforestation.

**Asphalt:** A dark brown-to-black cement-like material obtained by **petroleum** processing and containing bitumens as the predominant component; used primarily for road construction. It includes crude asphalt as well as the following finished products: cements, fluxes, the asphalt content of emulsions (exclusive of water), and petroleum distillates blended with asphalt to make cutback asphalts. **Note:** The conversion factor for asphalt is 5.5 barrels per short ton.

**ASTM:** The American Society for Testing and Materials.

**Aviation gasoline blending components:** **Naphthas** that will be used for blending or compounding into finished aviation gasoline (e.g., straight run gasoline, alkylate, reformate, benzene, toluene, and xylene). Excludes **oxygenates (alcohols, ethers)**, **butane**, and **natural gasoline**. Oxygenates are reported as **other hydrocarbons**, **hydrogen**, and oxygenates. See **Aviation gasoline, finished**.

**Aviation gasoline, finished:** A complex mixture of relatively volatile hydrocarbons with or without small quantities of additives, blended to form a fuel suitable for use in aviation reciprocating engines. Fuel specifications are provided in ASTM Specification D 910 and Military Specification MIL-G-5572. **Note:** Data on blending components are not counted in data on finished aviation gasoline.

**Barrel (petroleum):** A unit of volume equal to 42 U.S. Gallons.

**Base gas:** The quantity of **natural gas** needed to maintain adequate reservoir pressures and deliverability rates throughout the withdrawal season. Base gas usually is not withdrawn and remains in the reservoir. All natural gas native to a depleted reservoir is included in the base gas volume.

**Biodiesel:** A fuel typically made from soybean, canola, or other vegetable oils; animal fats; and recycled grease. It can serve as a substitute for **petroleum-derived diesel fuel** or **distillate fuel oil**. For U.S. Energy Information Administration

reporting, it is a fuel composed of mono-alkyl esters of long chain fatty acids derived from vegetable oils or animal fats, designated B100, and meeting the requirements of ASTM (American Society for Testing & Materials) D 6751.

**Biofuels:** Liquid fuels and blending components produced from **biomass** (plant) feedstocks, used primarily for transportation. See **Biodiesel** and **Fuel ethanol, Renewable diesel fuel (other)**, and **Renewable fuels (other)**.

**Biogenic:** Produced by biological processes of living organisms. **Note:** EIA uses the term “biogenic” to refer only to organic nonfossil material of biological origin.

**Biomass:** Organic nonfossil material of biological origin constituting a renewable energy source. See **Biodiesel, Biofuels, Biomass waste, Densified biomass, Fuel ethanol**, and **Wood and wood-derived fuels**.

**Biomass-based diesel fuel:** Biodiesel and other renewable **diesel fuel** or diesel fuel blending components derived from **biomass**, but excluding renewable diesel fuel coprocessed with petroleum feedstocks. See **Renewable diesel fuel (other)**.

**Biomass waste:** Organic non-fossil material of biological origin that is a byproduct or a discarded product. “Biomass waste” includes municipal solid waste from **biogenic** sources, landfill gas, sludge waste, agricultural crop byproducts, straw, and other **biomass** solids, liquids, and gases; but excludes **wood and wood-derived fuels** (including **black liquor**), **biofuels** feedstock, **biodiesel**, and **fuel ethanol**. **Note:** EIA “biomass waste” data also include energy crops grown specifically for energy production, which would not normally constitute waste.

**Bituminous coal:** A dense **coal**, usually black, sometimes dark brown, often with well-defined bands of bright and dull material, used primarily as fuel in steam-electric power generation, with substantial quantities also used for heat and power applications in manufacturing and to make **coke**. Bituminous coal is the most abundant coal in active U.S. mining regions. Its moisture content usually is less than 20 percent. The heat content of bituminous coal ranges from 21 to 30 million **Btu** per **short ton** on a moist, mineral-matter-free basis. The heat content of bituminous coal consumed in the United States averages 24 million Btu per short ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter).

**Black liquor:** A byproduct of the paper production process, alkaline spent liquor that can be used as a source of energy. Alkaline spent liquor is removed from the digesters in the process of chemically pulping wood. After evaporation, the residual “black” liquor is burned as a fuel in a recovery furnace that permits the recovery of certain basic chemicals.

**British thermal unit (Btu):** The quantity of heat required to raise the temperature of 1 pound of liquid water by 1 degree Fahrenheit at the temperature at which water has its greatest density (approximately 39 degrees Fahrenheit). See **Heat content**.

**Btu:** See **British thermal unit**.

**Btu conversion factor:** A factor for converting **energy** data between one unit of measurement and **British thermal units (Btu)**. Btu conversion factors are generally used to convert energy data from physical units of measure (such as **barrels, cubic feet, or short tons**) into the energy-equivalent measure of Btu. (See <http://www.eia.gov/totalenergy/data/monthly/#appendices> for further information on Btu conversion factors.)

**Butane (C<sub>4</sub>H<sub>10</sub>):** A straight-chain or branch-chain **hydrocarbon** extracted from **natural gas** or **refinery gas** streams, which is gaseous at standard temperature and pressure. It includes **isobutane** and **normal butane** and is designated in ASTM Specification D1835 and Gas Processors Association specifications for commercial butane.

**Butylene (C<sub>4</sub>H<sub>8</sub>):** An olefinic **hydrocarbon** recovered from refinery or petrochemical processes, which is gaseous at standard temperature and pressure. Butylene is used in the production of gasoline and various petrochemical products. See **Olefinic hydrocarbons (olefins)**.

**Capacity factor:** The ratio of the electrical energy produced by a generating unit for a given period of time to the electrical energy that could have been produced at continuous full-power operation during the same period.

**Carbon dioxide (CO<sub>2</sub>):** A colorless, odorless, non-poisonous gas that is a normal part of Earth's atmosphere. Carbon dioxide is a product of **fossil-fuel** combustion as well as other processes. It is considered a **greenhouse gas** as it traps

heat (infrared energy) radiated by the Earth into the atmosphere and thereby contributes to the potential for **global warming**. The **global warming potential** (GWP) of other greenhouse gases is measured in relation to that of carbon dioxide, which by international scientific convention is assigned a value of one (1).

**Chained dollars:** A measure used to express **real prices**. Real prices are those that have been adjusted to remove the effect of changes in the purchasing power of the dollar; they usually reflect buying power relative to a reference year. Prior to 1996, real prices were expressed in constant dollars, a measure based on the weights of goods and services in a single year, usually a recent year. In 1996, the U.S. Department of Commerce introduced the chained-dollar measure. The new measure is based on the average weights of goods and services in successive pairs of years. It is “chained” because the second year in each pair, with its weights, becomes the first year of the next pair. The advantage of using the chained-dollar measure is that it is more closely related to any given period and is therefore subject to less distortion over time.

**CIF:** See **Cost, insurance, freight**.

**Citygate:** A point or measuring station at which a distribution gas utility receives gas from a **natural gas** pipeline company or transmission system.

**Climate change:** A term used to refer to all forms of climatic inconsistency, but especially to significant change from one prevailing climatic condition to another. In some cases, “climate change” has been used synonymously with the term “**global warming**”; scientists, however, tend to use the term in a wider sense inclusive of natural changes in climate, including climatic cooling.

**Coal:** A readily combustible black or brownish-black rock whose composition, including inherent moisture, consists of more than 50 percent by weight and more than 70 percent by volume of carbonaceous material. It is formed from plant remains that have been compacted, hardened, chemically altered, and metamorphosed by heat and pressure over geologic time. See **Anthracite, Bituminous coal, Lignite, Subbituminous coal, Waste coal, and Coal synfuel**.

**Coal coke:** A solid carbonaceous residue derived from low-ash, low-sulfur **bituminous coal** from which the volatile constituents are driven off by baking in an oven at temperatures as high as 2,000 degrees Fahrenheit so that the fixed carbon and residual ash are fused together. Coke is used as a fuel and as a reducing agent in smelting iron ore in a blast furnace. Coke from coal is grey, hard, and porous and has a heating value of 24.8 million Btu per ton.

**Coal stocks:** Coal quantities that are held in storage for future use and disposition. **Note:** When coal data are collected for a particular reporting period (month, quarter, or year), coal stocks are commonly measured as of the last day of the period.

**Coal synfuel:** Coal-based solid fuel that has been processed by a **coal synfuel plant**; and coal-based fuels such as briquettes, pellets, or extrusions, which are formed from fresh or recycled coal and binding materials.

**Coal synfuel plant:** A plant engaged in the chemical transformation of **coal** into **coal synfuel**.

**Coke:** See **Coal coke** and **Petroleum coke**.

**Coking coal:** Bituminous coal suitable for making coke. See **Coal coke**.

**Combined heat and power (CHP) plant:** A plant designed to produce both heat and electricity from a single heat source. **Note:** This term is being used in place of the term “cogenerator” that was used by EIA in the past. CHP better describes the facilities because some of the plants included do not produce heat and power in a sequential fashion and, as a result, do not meet the legal definition of cogeneration specified in the Public Utility Regulatory Policies Act (PURPA).

**Commercial sector:** An energy-consuming sector that consists of service-providing facilities and equipment of: businesses; federal, state, and local governments; and other private and public organizations, such as religious, social, or fraternal groups. The commercial sector includes institutional living quarters. It also includes sewage treatment facilities. Common uses of energy associated with this sector include space heating, water heating, air conditioning, lighting, refrigeration, cooking, and running a wide variety of other equipment. **Note:** This sector includes generators that produce electricity and/or useful thermal output primarily to support the activities of the above-mentioned commercial establishments. See **End-use sectors** and **Energy-use sectors**.

**Completion:** The installation of permanent equipment for the production of oil or gas. If a well is equipped to produce only oil or gas from one zone or reservoir, the definition of a well (classified as an oil well or gas well) and the definition of a completion are identical. However, if a well is equipped to produce oil and/or gas separately from more than one reservoir, a well is not synonymous with a completion.

**Conventional hydroelectric power:** Hydroelectric power generated from flowing water that is not created by hydroelectric pumped storage.

**Conventional motor gasoline:** See **Motor gasoline conventional**.

**Conversion factor:** A factor for converting data between one unit of measurement and another (such as between **short tons** and **British thermal units**, or between **barrels** and gallons).  
(See <http://www.eia.gov/totalenergy/data/monthly/#appendices>. See **Btu conversion factor** and **Thermal conversion factor**.)

**Cost, insurance, freight (CIF):** A sales transaction in which the seller pays for the transportation and insurance of the goods to the port of destination specified by the buyer.

**Crude oil:** A mixture of hydrocarbons that exists in liquid phase in natural underground reservoirs and remains liquid at atmospheric pressure after passing through surface separating facilities. Depending upon the characteristics of the crude stream, it may also include: (1) small amounts of hydrocarbons that exist in gaseous phase in natural underground reservoirs but are liquid at atmospheric pressure after being recovered from oil well (casing head) gas in lease separators and are subsequently commingled with the crude stream without being separately measured. Lease condensate recovered as a liquid from natural gas wells in lease or field separation facilities and later mixed into the crude stream is also included; (2) small amounts of nonhydrocarbons produced with the oil, such as sulfur and various metals; and (3) drip gases, and liquid hydrocarbons produced from tar sands, oil sands, gilsonite, and oil shale. Liquids produced at natural gas processing plants are excluded. Crude oil is refined to produce a wide array of petroleum products, including heating oils; gasoline, diesel and jet fuels; lubricants; asphalt; ethane, propane, and butane; and many other products used for their energy or chemical content.

**Crude oil f.o.b. price:** The crude oil price actually charged at the oil-producing country's port of loading. Includes deductions for any rebates and discounts or additions of premiums, where applicable. It is the actual price paid with no adjustment for credit terms.

**Crude oil (including lease condensate):** A mixture of hydrocarbons that exists in liquid phase in underground reservoirs and remains liquid at atmospheric pressure after passing through surface separating facilities. Included are lease condensate and liquid hydrocarbons produced from tar sands, gilsonite, and oil shale. Drip gases are also included, but topped crude oil (residual oil) and other unfinished oils are excluded. Where identifiable, liquids produced at natural gas processing plants and mixed with crude oil are likewise excluded.

**Crude oil landed cost:** The price of crude oil at the port of discharge, including charges associated with the purchase, transporting, and insuring of a cargo from the purchase point to the port of discharge. The cost does not include charges incurred at the discharge port (e.g., import tariffs or fees, wharfage charges, and demurrage).

**Crude oil refinery input:** The total crude oil put into processing units at refineries.

**Crude oil stocks:** Stocks of crude oil and lease condensate held at refineries, in pipelines, at pipeline terminals, and on leases.

**Crude oil used directly:** Crude oil consumed as fuel by crude oil pipelines and on crude oil leases.

**Crude oil well:** A well completed for the production of crude oil from one or more oil zones or reservoirs. Wells producing both crude oil and natural gas are classified as oil wells.

**Cubic foot (natural gas):** The amount of **natural gas** contained at standard temperature and pressure (60 degrees Fahrenheit and 14.73 pounds standard per square inch) in a cube whose edges are one foot long.

**Degree Day Normals:** Simple arithmetic averages of monthly or annual degree days over a long period of time (usually the 30-year period 1961–1990). The averages may be simple degree day normals or population-weighted degree day normals.

**Degree Days, Cooling (CDD):** A measure of how warm a location is over a period of time relative to a base temperature, most commonly specified as 65 degrees Fahrenheit. The measure is computed for each day by subtracting the base temperature (65 degrees) from the average of the day's high and low temperatures, with negative values set equal to zero. Each day's cooling degree days are summed to create a cooling degree day measure for a specified reference period. Cooling degree days are used in energy analysis as an indicator of air conditioning energy requirements or use.

**Degree Days, Heating (HDD):** A measure of how cold a location is over a period of time relative to a base temperature, most commonly specified as 65 degrees Fahrenheit. The measure is computed for each day by subtracting the average of the day's high and low temperatures from the base temperature (65 degrees), with negative values set equal to zero. Each day's heating degree days are summed to create a heating degree day measure for a specified reference period. Heating degree days are used in energy analysis as an indicator of space heating energy requirements or use.

**Degree Days, Population-weighted:** Heating or cooling degree days weighted by the population of the area in which the degree days are recorded. To compute state population-weighted degree days, each state is divided into from one to nine climatically homogeneous divisions, which are assigned weights based on the ratio of the population of the division to the total population of the state. Degree day readings for each division are multiplied by the corresponding population weight for each division and those products are then summed to arrive at the state population-weighted degree day figure. To compute national population-weighted degree days, the nation is divided into nine Census regions, each comprising from three to eight states, which are assigned weights based on the ratio of the population of the region to the total population of the nation. Degree day readings for each region are multiplied by the corresponding population weight for each region and those products are then summed to arrive at the national population-weighted degree day figure.

**Denaturant:** Petroleum, typically **natural gasoline** or **conventional motor gasoline**, added to **fuel ethanol** to make it unfit for human consumption. Fuel ethanol is denatured, usually prior to transport from the ethanol production facility, by adding 2 to 5 volume percent denaturant. See **Fuel ethanol** and **Fuel ethanol minus denaturant**.

**Densified biomass fuel:** Raw biomass, primarily wood, that has been condensed into a homogenously sized, energy-dense product, such as wood pellets, intended for use as fuel. It is mainly used for residential and commercial space heating and electricity generation.

**Design electrical rating, net:** The nominal net electrical output of a nuclear unit as specified by the electric utility for the purpose of plant design.

**Development well:** A well drilled within the proved area of an oil or gas reservoir to the depth of a stratigraphic horizon known to be productive.

**Diesel fuel:** A fuel composed of **distillate fuel oils** obtained in petroleum refining operation or blends of such distillate fuel oils with **residual fuel oil** used in motor vehicles. The boiling point and specific gravity are higher for diesel fuels than for gasoline.

**Direct use:** Use of electricity that (1) is self-generated, (2) is produced by either the same entity that consumes the power or an affiliate, and (3) is used in direct support of a service or industrial process located within the same facility or group of facilities that house the generating equipment. Direct use is exclusive of **station use**.

**Distillate fuel oil:** A general classification for one of the **petroleum** fractions produced in conventional distillation operations. It includes **diesel fuels** and fuel oils. Products known as No. 1, No. 2, and No. 4 diesel fuel are used in on-highway diesel engines, such as those in trucks and automobiles, as well as off-highway engines, such as those in railroad locomotives and agricultural machinery. Products known as No. 1, No. 2, and No. 4 fuel oils are used primarily for space heating and **electricity generation**.



**Dry hole:** An exploratory or development well found to be incapable of producing either oil or gas in sufficient quantities to justify completion as an oil or gas well.

**Dry natural gas production:** See **Natural gas (dry) production**.

**E85:** A fuel containing a mixture of 85 percent **ethanol** and 15 percent **motor gasoline**.

**Electric power plant:** A station containing prime movers, electric generators, and auxiliary equipment for converting mechanical, chemical, and/or fission energy into electric energy.

**Electric power sector:** An energy-consuming sector that consists of electricity-only and combined-heat-and-power (CHP) plants whose primary business is to sell electricity, or electricity and heat, to the public-i.e., North American Industry Classification System 22 plants. See also **Combined heat and power (CHP) plant**, **Electricity-only plant**, **Electric utility**, and **Independent power producer**.

**Electric utility:** Any entity that generates, transmits, or distributes **electricity** and recovers the cost of its generation, transmission or distribution assets and operations, either directly or indirectly, through cost-based rates set by a separate regulatory authority (e.g., State Public Service Commission), or is owned by a governmental unit or the consumers that the entity serves. Examples of these entities include: investor-owned entities, public power districts, public utility districts, municipalities, rural electric cooperatives, and state and federal agencies. Electric utilities may have Federal Energy Regulatory Commission approval for interconnection agreements and wholesale trade tariffs covering either cost-of-service and/or market-based rates under the authority of the Federal Power Act. See **Electric power sector**.

**Electrical system energy losses:** The amount of energy lost during generation, transmission, and distribution of electricity, including plant and unaccounted-for uses.

**Electricity:** A form of energy characterized by the presence and motion of elementary charged particles generated by friction, induction, or chemical change.

**Electricity generation:** The process of producing electric energy, or the amount of electric energy produced by transforming other forms of energy, commonly expressed in **kilowatthours** (kWh) or megawatthours (MWh).

**Electricity generation, gross:** The total amount of electric energy produced by generating units and measured at the generating terminal in **kilowatthours** (kWh) or megawatthours (MWh).

**Electricity generation, net:** The amount of **gross electricity generation** less **station use** (the **electric energy** consumed at the generating station(s) for station service or auxiliaries). **Note:** Electricity required for pumping at **hydroelectric pumped-storage** plants is regarded as electricity for station service and is deducted from gross generation.

**Electricity only plant:** A plant designed to produce electricity only. See also **Combined heat and power (CHP) plant**.

**Electricity retail sales:** The amount of electricity sold to customers purchasing electricity for their own use and not for resale.

**End use sectors:** The **residential**, **commercial**, **industrial**, and **transportation** sectors of the economy.

**Energy:** The capacity for doing work as measured by the capability of doing work (potential energy) or the conversion of this capability to motion (kinetic energy). Energy has several forms, some of which are easily convertible and can be changed to another form useful for work. Most of the world's convertible energy comes from fossil fuels that are burned to produce heat that is then used as a transfer medium to mechanical or other means in order to accomplish tasks. Electrical energy is usually measured in kilowatthours, while heat energy is usually measured in British thermal units.

**Energy consumption:** The use of energy as a source of heat or power or as an input in the manufacturing process.

**Energy service provider:** An energy entity that provides service to a retail or end-use customer.

**Energy use sectors:** A group of major energy-consuming components of U.S. society developed to measure and analyze energy use. The sectors most commonly referred to in EIA are: **residential**, **commercial**, **industrial**, **transportation**, and **electric power**.

**Ethane (C<sub>2</sub>H<sub>6</sub>):** A straight-chain saturated (paraffinic) **hydrocarbon** extracted predominantly from the natural gas stream, which is gaseous at standard temperature and pressure. It is a colorless gas that boils at a temperature of -127 degrees Fahrenheit. See **Paraffinic hydrocarbons**.

**Ethanol (C<sub>2</sub>H<sub>5</sub>OH):** A clear, colorless, flammable **alcohol**. Ethanol is typically produced biologically from **biomass** feedstocks such as agricultural crops and cellulosic residues from agricultural crops or wood. Ethanol can also be produced chemically from **ethylene**. See **Biomass**, **Fuel ethanol**, and **Fuel ethanol minus denaturant**.

**Ether:** A generic term applied to a group of organic chemical compounds composed of carbon, **hydrogen**, and oxygen, characterized by an oxygen atom attached to two carbon atoms (e.g., **methyl tertiary butyl ether**).

**Ethylene (C<sub>2</sub>H<sub>4</sub>):** An olefinic **hydrocarbon** recovered from refinery or petrochemical processes, which is gaseous at standard temperature and pressure. Ethylene is used as a petrochemical feedstock for many chemical applications and the production of consumer goods. See **Olefinic hydrocarbons (olefins)**.

**Exploratory well:** A well drilled to find and produce oil or gas in an area previously considered an unproductive area, to find a new reservoir in a known field (i.e., one previously found to be producing oil or gas in another reservoir), or to extend the limit of a known oil or gas reservoir.

**Exports:** Shipments of goods from within the 50 states and the District of Columbia to U.S. possessions and territories or to foreign countries.

**Federal Energy Administration (FEA):** A predecessor of the U.S. Energy Information Administration.

**Federal Energy Regulatory Commission (FERC):** The Federal agency with jurisdiction over interstate electricity sales, wholesale electric rates, hydroelectric licensing, natural gas pricing, oil pipeline rates, and gas pipeline certification. FERC is an independent regulatory agency within the U.S. Department of Energy and is the successor to the Federal Power Commission.

**Federal Power Commission (FPC):** The predecessor agency of the Federal Energy Regulatory Commission. The Federal Power Commission was created by an Act of Congress under the Federal Water Power Act on June 10, 1920. It was charged originally with regulating the electric power and natural gas industries. It was abolished on September 30, 1977, when the U.S. Department of Energy was created. Its functions were divided between the U.S. Department of Energy and the Federal Energy Regulatory Commission, an independent regulatory agency.

**First purchase price:** The price for domestic crude oil reported by the company that owns the crude oil the first time it is removed from the lease boundary.

**Flared natural gas:** Natural gas burned in flares on the base site or at gas processing plants.

**F.O.B. (free on board):** A sales transaction in which the seller makes the product available for pick up at a specified port or terminal at a specified price and the buyer pays for the subsequent transportation and insurance.

**Footage drilled:** Total footage for wells in various categories, as reported for any specified period, includes (1) the deepest total depth (length of well bores) of all wells drilled from the surface, (2) the total of all bypassed footage drilled in connection with reported wells, and (3) all new footage drilled for directional sidetrack wells. Footage reported for directional sidetrack wells does not include footage in the common bore, which is reported as footage for the original well. In the case of old wells drilled deeper, the reported footage is that which was drilled below the total depth of the old well.

**Former U.S.S.R.:** See **Union of Soviet Socialist Republics (U.S.S.R.)**.

**Fossil fuel:** An energy source formed in the Earth's crust from decayed organic material, such as **petroleum**, **coal**, and **natural gas**.

**Fossil fueled steam electric power plant:** An electricity generation plant in which the prime mover is a turbine rotated by high-pressure steam produced in a boiler by heat from burning fossil fuels.

**Fuel ethanol:** Ethanol intended for fuel use. Fuel ethanol in the United States must be anhydrous (less than 1 percent water). Fuel ethanol is denatured (made unfit for human consumption), usually prior to transport from the ethanol production facility, by adding 2 to 5 volume percent petroleum, typically **natural gasoline** or **conventional motor gasoline**. Fuel ethanol is used principally for blending in low concentrations with **motor gasoline** as an **oxygenate** or octane enhancer. In high concentrations, it is used to fuel **alternative-fuel vehicles** specially designed for its use. See **Alternative-fuel vehicle, Denaturant, E85, Ethanol, Fuel ethanol minus denaturant, and Oxygenates**.

**Fuel ethanol minus denaturant:** An unobserved quantity of anhydrous, **biomass**-derived, undenatured **ethanol** for fuel use. The quantity is obtained by subtracting the estimated **denaturant** volume from **fuel ethanol** volume. Fuel ethanol minus denaturant is counted as **renewable energy**, while denaturant is counted as **nonrenewable fuel**. See **Denaturant, Ethanol, Fuel ethanol, Nonrenewable fuels, Oxygenates, and Renewable energy**.

**Full power operation:** Operation of a nuclear generating unit at 100 percent of its design capacity. Full-power operation precedes commercial operation.

**Gasohol:** A blend of finished motor gasoline containing alcohol (generally ethanol but sometimes methanol) at a concentration between 5.7 percent and 10 percent by volume. See **Motor gasoline, oxygenated**.

**Gas well:** A well completed for production of natural gas from one or more gas zones or reservoirs. Such wells contain no completions for the production of crude oil.

**Geothermal energy:** Hot water or steam extracted from geothermal reservoirs in the earth's crust and used for geothermal heat pumps, water heating, or electricity generation.

**Global warming:** An increase in the near-surface temperature of the Earth. Global warming has occurred in the distant past as the result of natural influences, but the term is today most often used to refer to the warming some scientists predict will occur as a result of increased anthropogenic emissions of **greenhouse gases**. See **Climate change**.

**Global warming potential (GWP):** An index used to compare the relative radiative forcing of different gases without directly calculating the changes in atmospheric concentrations. GWPs are calculated as the ratio of the radiative forcing that would result from the emission of one kilogram of a **greenhouse gas** to that from the emission of one kilogram of **carbon dioxide** over a fixed period of time, such as 100 years.

**Greenhouse gases:** Those gases, such as water vapor, **carbon dioxide**, nitrous oxide, **methane**, hydrofluorocarbons (HFCs), perfluorocarbons (PFCs) and sulfur hexafluoride, that are transparent to solar (short-wave) radiation but opaque to long-wave (infrared) radiation, thus preventing long-wave radiant energy from leaving Earth's atmosphere. The net effect is a trapping of absorbed radiation and a tendency to warm the planet's surface.

**Gross domestic product (GDP):** The total value of goods and services produced by labor and property located in the United States. As long as the labor and property are located in the United States, the supplier (that is, the workers and, for property, the owners) may be either U.S. residents or residents of foreign countries.

**GT/IC:** Gas turbine and internal combustion plants.

**Heat content:** The amount of heat energy available to be released by the transformation or use of a specified physical unit of an energy form (e.g., a ton of coal, a barrel of oil, a kilowatthour of electricity, a cubic foot of natural gas, or a pound of steam). The amount of heat energy is commonly expressed in **British thermal units (Btu)**. **Note:** Heat content of combustible energy forms can be expressed in terms of either gross heat content (higher or upper heating value) or net heat content (lower heating value), depending upon whether or not the available heat energy includes or excludes the energy used to vaporize water (contained in the original energy form or created during the combustion process). The U.S. Energy Information Administration typically uses gross heat content values.

**Heat rate:** A measure of generating station thermal efficiency commonly stated as **Btu per kilowatthour**. **Note:** Heat rates can be expressed as either gross or net heat rates, depending whether the electricity output is gross or net generation. Heat rates are typically expressed as net heat rates.

**Hydrocarbon:** An organic chemical compound of **hydrogen** and carbon in the gaseous, liquid, or solid phase. The molecular structure of hydrocarbon compounds varies from the simplest (methane, the primary constituent of **natural gas**) to the very heavy and very complex.

**Hydrocarbon gas liquids (HGL):** A group of **hydrocarbons** including **ethane, propane, normal butane, isobutane**, and **natural gasoline**, and their associated **olefins**, including **ethylene, propylene, butylene**, and **isobutylene**. As marketed products, HGL represents all **natural gas liquids** (NGL) and olefins. EIA reports production of HGL from refineries (**liquefied refinery gases**, or LRG) and natural gas plants (**natural gas plant liquids**, or NGPL). Excludes liquefied natural gas (LNG). See **Olefinic hydrocarbons (olefins)**.

**Hydroelectric power:** The production of electricity from the kinetic energy of falling water.

**Hydroelectric power plant:** A plant in which the turbine generators are driven by falling water.

**Hydroelectric pumped storage:** Hydroelectricity that is generated during peak load periods by using water previously pumped into an elevated storage reservoir during off-peak periods when excess generating capacity is available to do so. When additional generating capacity is needed, the water can be released from the reservoir through a conduit to turbine generators located in a power plant at a lower level.

**Hydrogen (H):** The lightest of all gases, hydrogen occurs chiefly in combination with oxygen in water. It also exists in acids, bases, **alcohols, petroleum**, and **other hydrocarbons**.

**Imports:** Receipts of goods into the 50 states and the District of Columbia from U.S. possessions and territories or from foreign countries.

**Independent power producer:** A corporation, person, agency, authority, or other legal entity or instrumentality that owns or operates facilities for the generation of electricity for use primarily by the public, and that is not an **electric utility**.

**Industrial sector:** An **energy**-consuming sector that consists of all facilities and equipment used for producing, processing, or assembling goods. The industrial sector encompasses the following types of activity: manufacturing (**NAICS** codes 31-33); agriculture, forestry, fishing and hunting (NAICS code 11); mining, including oil and gas extraction (NAICS code 21); and construction (NAICS code 23). Overall energy use in this sector is largely for process heat and cooling and powering machinery, with lesser amounts used for facility heating, air conditioning, and lighting. Fossil fuels are also used as raw material inputs to manufactured products. **Note:** This sector includes **generators** that produce **electricity** and/or **useful thermal output** primarily to support the above-mentioned industrial activities. See **End use sectors** and **Energy use sectors**.

**Injections (natural gas):** **Natural gas** injected into storage reservoirs.

**Isobutane (C<sub>4</sub>H<sub>10</sub>):** A branch-chain saturated (paraffinic) **hydrocarbon** extracted from both **natural gas** and **refinery gas** streams, which is gaseous at standard temperature and pressure. It is a colorless gas that boils at a temperature of 11 degrees Fahrenheit. See **Paraffinic hydrocarbons**.

**Isobutylene (C<sub>4</sub>H<sub>8</sub>):** A branch-chain olefinic **hydrocarbon** recovered from refinery or petrochemical processes, which is gaseous at standard temperature and pressure. Isobutylene is used in the production of gasoline and various petrochemical products. See **Olefinic hydrocarbons (olefins)**.

**Isopentane (C<sub>5</sub>H<sub>12</sub>):** A saturated branched-chain **hydrocarbon** obtained by fractionation of **natural gasoline** or isomerization of normal pentane.

**Jet fuel:** A refined **petroleum** product used in jet aircraft engines. See **Jet fuel, Kerosene-type**, and **Jet fuel, Naphtha-type**.

**Jet fuel, kerosene-type:** A **kerosene**-based product having a maximum distillation temperature of 400 degrees Fahrenheit at the 10-percent recovery point and a final maximum boiling point of 572 degrees Fahrenheit and meeting ASTM Specification D 1655 and Military Specifications MIL-T-5624P and MIL-T-83133D (Grades JP-5 and JP-8). It is used for commercial and military turbo jet and turbo prop aircraft engines.

**Jet fuel, naphtha-type:** A fuel in the heavy **naphtha** boiling range having an average gravity of 52.8 degrees API, 20% to 90% distillation temperatures of 290 degrees to 470 degrees Fahrenheit, and meeting Military Specification MIL-T-5624L (Grade JP-4). It is used primarily for military turbojet and turboprop aircraft engines because it has a lower freeze point than other aviation fuels and meets engine requirements at high altitudes and speeds.

**Kerosene:** A light **petroleum** distillate that is used in space heaters, cook stoves, and water heaters and is suitable for use as a light source when burned in wick-fed lamps. Kerosene has a maximum distillation temperature of 400 degrees Fahrenheit at the 10-percent recovery point, a final boiling point of 572 degrees Fahrenheit, and a minimum flash point of 100 degrees Fahrenheit. Included are No. 1-K and No. 2-K, the two grades recognized by ASTM Specification D 3699 as well as all other grades of kerosene called range or stove oil, which have properties similar to those of No. 1 fuel oil. See **Jet fuel, kerosene-type**.

**Kilowatt:** A unit of electrical power equal to 1,000 **watts**.

**Kilowatthour (kWh):** A measure of electricity defined as a unit of work or energy, measured as 1 **kilowatt** (1,000 watts) of power expended for 1 hour. One kilowatthour is equivalent to 3,412 Btu. See **Watthour**.

**Landed costs:** The dollar-per-barrel price of crude oil at the port of discharge. Included are the charges associated with the purchase, transporting, and insuring of a cargo from the purchase point to the port of discharge. Not included are charges incurred at the discharge port (e.g., import tariffs or fees, wharfage charges, and demurrage charges).

**Lease and plant fuel:** **Natural gas** used in well, field, and lease operations (such as gas used in drilling operations, heaters, dehydrators, and field compressors) and used as fuel in natural gas processing plants.

**Lease condensate:** Light liquid **hydrocarbons** recovered from lease separators or field facilities at associated and non-associated **natural gas** wells. Mostly pentanes and heavier hydrocarbons. Normally enters the **crude oil** stream after production.

**Lignite:** The lowest rank of coal, often referred to as brown **coal**, used almost exclusively as fuel for steam-electric power generation. It is brownish-black and has a high inherent moisture content, sometimes as high as 45 percent. The heat content of lignite ranges from 9 to 17 million **Btu** per **short ton** on a moist, mineral-matter-free basis. The heat content of lignite consumed in the United States averages 13 million Btu per short ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter).

**Liquefied natural gas (LNG):** **Natural gas** (primarily methane) that has been liquefied by reducing its temperature to -260 degrees Fahrenheit at atmospheric pressure.

**Liquefied petroleum gases (LPG):** A group of **hydrocarbon** gases, primarily **propane**, **normal butane**, and **isobutane**, derived from crude oil refining or **natural gas** processing. These gases may be marketed individually or mixed. They can be liquefied through pressurization (without requiring cryogenic refrigeration) for convenience of transportation or storage. Excludes **ethane** and **olefins**. **Note:** In some EIA publications, LPG includes ethane and marketed refinery olefin streams, in accordance with definitions used prior to January 2014.

**Liquefied refinery gases (LRG):** **Hydrocarbon gas liquids** produced in refineries from processing of **crude oil** and **unfinished oils**. They are retained in the liquid state through pressurization and/or refrigeration. The reported categories include **ethane**, **propane**, **normal butane**, **isobutane**, and refinery **olefins (ethylene, propylene, butylene, and isobutylene)**.

**Low power testing:** The period of time between a nuclear generating unit's initial fuel loading date and the issuance of its operating (full-power) license. The maximum level of operation during that period is 5 percent of the unit's design thermal rating.

**Lubricants:** Substances used to reduce friction between bearing surfaces or as process materials either incorporated into other materials used as processing aids in the manufacturing of other products or as carriers of other materials. Petroleum lubricants may be produced either from distillates or residues. Other substances may be added to impart or improve certain required properties. Excluded are byproducts of lubricating oil refining, such as aromatic extracts derived from solvent extraction or tars derived from deasphalting. Included are all grades of lubricating oils from spindle oil to cylinder oil and those used in greases. Lubricant categories are paraffinic and naphthenic.

**Marketed production (natural gas):** See **Natural gas marketed production**.

**Methane (CH<sub>4</sub>):** A colorless, flammable, odorless **hydrocarbon** gas which is the major component of **natural gas**. It is also an important source of hydrogen in various industrial processes. Methane is a greenhouse gas. See **Greenhouse gases**.

**Methanol (CH<sub>3</sub>OH):** A light, volatile alcohol eligible for gasoline blending. See **Motor gasoline blending** and **Oxygenates**.

**Methyl tertiary butyl ether (MTBE) ((CH<sub>3</sub>)<sub>3</sub>COCH<sub>3</sub>):** An **ether** intended for gasoline blending. See **Motor gasoline blending** and **Oxygenates**.

**Miscellaneous petroleum products:** All finished petroleum products not classified elsewhere—for example, petrolatum, lube refining byproducts (aromatic extracts and tars), absorption oils, ram-jet fuel, petroleum rocket fuels, synthetic natural gas feedstocks, and specialty oils.

**Motor gasoline blending components:** Naphtha (e.g., straight-run gasoline, alkylate, reformate, benzene, toluene, xylene) used for blending or compounding into finished motor gasoline. These components include reformulated gasoline blendstock (RBOB) but exclude oxygenates (alcohols, ethers), butane, and natural gasoline. **Note:** Oxygenates are reported as individual components and are included in the total for other hydrocarbons, hydrogens, and oxygenates.

**Motor gasoline, conventional:** **Finished motor gasoline** not included in the **oxygenated** or **reformulated** motor gasoline categories. **Note:** This category excludes reformulated gasoline blendstock for oxygenate blending (RBOB) as well as other blendstock. Conventional motor gasoline can be leaded or unleaded; regular, midgrade, or premium. See **Motor gasoline grades**.

**Motor gasoline (finished):** A complex mixture of relatively volatile **hydrocarbons** with or without small quantities of additives, blended to form a fuel suitable for use in spark-ignition engines. Motor gasoline, as defined in ASTM Specification D 4814 or Federal Specification VV-G-1690C, is characterized as having a boiling range of 122 to 158 degrees Fahrenheit at the 10 percent recovery point to 365 to 374 degrees Fahrenheit at the 90 percent recovery point. Motor gasoline includes conventional gasoline; all types of oxygenated gasoline, including **gasohol**; and reformulated gasoline, but excludes aviation gasoline. **Note:** Volumetric data on blending components, such as **oxygenates**, are not counted in data on finished motor gasoline until the blending components are blended into the gasoline. See **Motor gasoline, conventional**; **Motor gasoline, oxygenated**; and **Motor gasoline, reformulated**.

**Motor gasoline grades:** The classification of gasoline by octane ratings. Each type of gasoline (conventional, oxygenated, and reformulated) is classified by three grades: regular, midgrade, and premium. **Note:** Gasoline sales are reported by grade in accordance with their classification at the time of sale. In general, automotive octane requirements are lower at high altitudes. Therefore, in some areas of the United States, such as the Rocky Mountain States, the octane ratings for the gasoline grades may be 2 or more octane points lower.

**Regular Gasoline:** Gasoline having an antiknock index, i.e., octane rating, greater than or equal to 85 and less than **88**. **Note:** Octane requirements may vary by altitude. See **Motor gasoline grades**.

**Midgrade Gasoline:** Gasoline having an antiknock index, i.e., octane rating, greater than or equal to **88** and less than or equal to 90. **Note:** Octane requirements may vary by altitude. See **Motor gasoline grades**.

**Premium Gasoline:** Gasoline having an antiknock index, i.e., octane rating, greater than 90. **Note:** Octane requirements may vary by altitude. See **Motor gasoline grades**.

**Motor gasoline, oxygenated:** Finished motor gasoline, other than reformulated gasoline, having an oxygen content of 2.7 percent or higher by weight and required by the U.S. Environmental Protection Agency (EPA) to be sold in areas designated by EPA as carbon monoxide (CO) nonattainment areas. **Note:** Oxygenated gasoline excludes oxygenated fuels program reformulated gasoline (OPRG) and reformulated gasoline blendstock for oxygenate blending (RBOB). Data on gasohol that has at least 2.7 percent oxygen, by weight, and is intended for sale inside CO nonattainment areas are included in data on oxygenated gasoline. Other data on gasohol are included in data on conventional gasoline.

**Motor gasoline, reformulated:** Finished motor gasoline formulated for use in motor vehicles, the composition and properties of which meet the requirements of the reformulated gasoline regulations promulgated by the U.S. Environmental Protection Agency under Section 211(k) of the Clean Air Act. **Note:** This category includes oxygenated fuels program reformulated gasoline (OPRG) but excludes reformulated gasoline blendstock for oxygenate blending (RBOB).

**Motor gasoline retail prices:** Motor gasoline prices calculated each month by the Bureau of Labor Statistics (BLS) in conjunction with the construction of the Consumer Price Index (CPI). Those prices are collected in 85 urban areas selected to represent all urban consumers-about 80 percent of the total U.S. population. The service stations are selected initially, and on a replacement basis, in such a way that they represent the purchasing habits of the CPI population. Service stations in the current sample include those providing all types of service (i.e., full-, mini-, and self-service).

**Motor gasoline (total):** For stock level data, a sum including finished motor gasoline stocks plus stocks of motor gasoline blending components but excluding stocks of oxygenates.

**MTBE:** See **Methyl tertiary butyl ether**.

**NAICS (North American Industry Classification System):** A coding system developed jointly by the United States, Canada, and Mexico to classify businesses and industries according to the type of economic activity in which they are engaged. NAICS replaces the Standard Industrial Classification (SIC) codes. For additional information on NAICS, go to <http://www.census.gov/eos/www/naics/>.

**Naphtha:** A generic term applied to a refined or partially refined **petroleum** fraction with an approximate boiling range between 122 degrees and 400 degrees Fahrenheit.

**Natural Gas:** A gaseous mixture of **hydrocarbon** compounds, primarily **methane**, used as a fuel for **electricity generation** and in a variety of ways in buildings, and as raw material input and fuel for industrial processes.

**Natural gas, dry:** **Natural gas** which remains after: (1) the liquefiable **hydrocarbon** portion has been removed from the gas stream (i.e., gas after lease, field, and/or plant separation); and (2) any volumes of **nonhydrocarbon gases** have been removed where they occur in sufficient quantity to render the gas unmarketable. **Note:** Dry natural gas is also known as consumer-grade natural gas. The parameters for measurement are cubic feet at 60 degrees Fahrenheit and 14.73 pounds per square inch absolute.

**Natural gas (dry) production:** The process of producing consumer-grade **natural gas**. Natural gas withdrawn from reservoirs is reduced by volumes used at the production (lease) site and by processing losses. Volumes used at the production site include (1) the volume returned to reservoirs in cycling, **repressuring** of oil reservoirs, and conservation operations; and (2) **vented natural gas** and **flared natural gas**. Processing losses include (1) **nonhydrocarbon gases** (e.g., water vapor, carbon dioxide, helium, hydrogen sulfide, and nitrogen) removed from the gas stream; and (2) gas converted to liquid form, such as **lease condensate** and **natural gas plant liquids**. Volumes of dry gas withdrawn from gas storage reservoirs are not considered part of production. Dry natural gas production equals **natural gas marketed production** less **natural gas plant liquids** production.

**Natural gas liquids (NGL):** A group of **hydrocarbons** including **ethane**, **propane**, **normal butane**, **isobutane**, and **natural gasoline**. Generally include **natural gas plant liquids** and all **liquefied refinery gases** except **olefins**. See **Paraffinic hydrocarbons**.

**Natural gas marketed production:** Gross withdrawals of **natural gas** from production reservoirs, less gas used for reservoir **repressuring**; **nonhydrocarbon gases** removed in treating and processing operations; and quantities of **vented natural gas** and **flared natural gas**.

**Natural gas plant liquids (NGPL):** Those **hydrocarbons** in **natural gas** that are separated as liquids at natural gas processing, fractionating, and cycling plants. Products obtained include **ethane**, **liquefied petroleum gases** (**propane**, **normal butane** and **isobutane**), and **natural gasoline**. Component products may be fractionated or mixed. **Lease condensate** and **plant condensate** are excluded. **Note:** Some EIA publications categorize NGPL production as field production, in accordance with definitions used prior to January 2014.

**Natural gas wellhead price:** The **wellhead price** of **natural gas** is calculated by dividing the total reported value at the wellhead by the total quantity produced as reported by the appropriate agencies of individual producing states and the U.S. Minerals Management Service. The price includes all costs prior to shipment from the lease, including gathering and compression costs, in addition to state production, severance, and similar charges.

**Natural gasoline:** A commodity product commonly traded in **natural gas liquids** (NGL) markets that comprises liquid **hydrocarbons** (mostly pentanes and hexanes) and generally remains liquid at ambient temperatures and atmospheric pressure. Natural gasoline is equivalent to **pentanes plus**.

**Net summer capacity:** The maximum output, commonly expressed in **kilowatts** (kW) or megawatts (MW), that generating equipment can supply to system load, as demonstrated by a multi-hour test, at the time of summer peak demand (period of June 1 through September 30). This output reflects a reduction in capacity due to electricity use for station service or auxiliaries.

**Neutral zone:** A 6,200 square-mile area shared equally between Kuwait and Saudi Arabia under a 1992 agreement. The Neutral zone contains an estimated 5 billion barrels of oil and 8 trillion cubic feet of natural gas.

**Nominal dollars:** A measure used to express **nominal price**.

**Nominal price:** The price paid for a product or service at the time of the transaction. Nominal prices are those that have not been adjusted to remove the effect of changes in the purchasing power of the dollar; they reflect buying power in the year in which the transaction occurred.

**Non-biomass waste:** Material of non-biological origin that is a byproduct or a discarded product. "Non-biomass waste" includes municipal solid waste from non-biogenic sources, such as plastics, and tire-derived fuels.

**Non-combustion use:** Fossil fuels (coal, natural gas, and petroleum products) that are not burned to release energy and instead used directly as construction materials, chemical, feedstocks, lubricants, solvents, waxes, and other products.

**Nonhydrocarbon gases:** Typical nonhydrocarbon gases that may be present in reservoir **natural gas** are **carbon dioxide**, helium, hydrogen sulfide, and nitrogen.

**Nonrenewable fuels:** Fuels that cannot be easily made or "renewed," such as **crude oil**, **natural gas**, and **coal**.

**Normal butane (C<sub>4</sub>H<sub>10</sub>):** A straight-chain saturated (paraffinic) **hydrocarbon** extracted from both **natural gas** and **refinery gas** streams, which is gaseous at standard temperature and pressure. It is a colorless gas that boils at a temperature of 31 degrees Fahrenheit. See **Paraffinic hydrocarbons**.

**Nuclear electric power (nuclear power):** Electricity generated by the use of the thermal energy released from the fission of nuclear fuel in a reactor.

**Nuclear electric power plant:** A single-unit or multiunit facility in which heat produced in one or more reactors by the fissioning of nuclear fuel is used to drive one or more steam turbines.

**Nuclear reactor:** An apparatus in which a nuclear fission chain reaction can be initiated, controlled, and sustained at a specific rate. A reactor includes fuel (fissionable material), moderating material to control the rate of fission, a heavy-walled pressure vessel to house reactor components, shielding to protect personnel, a system to conduct heat away from the reactor, and instrumentation for monitoring and controlling the reactor's systems.

**OECD:** See **Organization for Economic Cooperation and Development**.

**Offshore:** That geographic area that lies seaward of the coastline. In general, the coastline is the line of ordinary low water along with that portion of the coast that is in direct contact with the open sea or the line marking the seaward limit of inland water.

**Oil:** See **Crude oil**.

**Olefinic hydrocarbons (olefins):** Unsaturated **hydrocarbon** compounds with the general formula C<sub>n</sub>H<sub>2n</sub> containing at least one carbon-to-carbon double-bond. Olefins are produced at crude oil refineries and petrochemical plants and are



not naturally occurring constituents of oil and natural gas. Sometimes referred to as alkenes or unsaturated hydrocarbons. Excludes aromatics.

**Olefins:** See **Olefinic hydrocarbons (olefins)**.

**OPEC:** See **Organization of the Petroleum Exporting Countries**.

**Operable unit (nuclear):** In the United States, a nuclear generating unit that has completed low-power testing and been issued a full-power operating license by the Nuclear Regulatory Commission, or equivalent permission to operate.

**Organization for Economic Cooperation and Development (OECD):** An international organization helping governments tackle the economic, social and governance challenges of a globalized economy. Its membership comprises about 30 member countries. With active relationships with some 70 other countries, non-governmental organizations (NGOs) and civil society, it has a global reach. For details about the organization, see <http://www.oecd.org>.

**Organization of the Petroleum Exporting Countries (OPEC):** An intergovernmental organization whose stated objective is to "coordinate and unify the petroleum policies of member countries." It was created at the Baghdad Conference on September 10–14, 1960. Current and former members (with years of membership) include Algeria (1969 forward), Angola (2007 forward), Congo-Brazzaville (2018 forward), Ecuador (1973–1992 and 2007–2019), Equatorial Guinea (2017 forward), Gabon (1974–1994 and 2016 forward), Indonesia (1962–2008 and 2016), Iran (1960 forward), Iraq (1960 forward), Kuwait (1960 forward), Libya (1962 forward), Nigeria (1971 forward), Qatar (1961–2018), Saudi Arabia (1960 forward), United Arab Emirates (1967 forward), and Venezuela (1960 forward).

**Other energy losses:** Energy losses throughout the energy system as they are consumed, usually in the form of heat, that are not separately identified by U.S. Energy Information Administration. Examples include heat lost in the process of burning motor gasoline to move vehicles or in electricity used to power a lightbulb.

**Other hydrocarbons:** Materials received by a refinery and consumed as a raw material. Includes hydrogen, coal tar derivatives, gilsonite. Excludes **natural gas** used for fuel or **hydrogen** feedstock.

**Oxygenates:** Substances which, when added to gasoline, increase the amount of oxygen in that gasoline blend. **Ethanol**, **Methyl Tertiary Butyl Ether (MTBE)**, Ethyl Tertiary Butyl Ether (ETBE), and methanol are common oxygenates.

**PAD Districts or PADD:** Petroleum Administration for Defense Districts. Geographic aggregations of the 50 states and the District of Columbia into five districts for the Petroleum Administration for Defense in 1950. The districts were originally instituted for economic and geographic reasons as Petroleum Administration for War (PAW) Districts, which were established in 1942.

**Petroleum Administration for Defense District (PADD):** The 50 U.S. states and the District of Columbia are divided into five districts, with PADD 1 further split into three subdistricts. PADDs 6 and 7 encompass U.S. territories. The PADDs include the states and territories listed below:

**PADD 1 (East Coast).**

**PADD 1A (New England):** Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, and Vermont.

**PADD 1B (Central Atlantic):** Delaware, District of Columbia, Maryland, New Jersey, New York, and Pennsylvania.

**PADD 1C (Lower Atlantic):** Florida, Georgia, North Carolina, South Carolina, Virginia, and West Virginia.

**PADD 2 (Midwest):** Illinois, Indiana, Iowa, Kansas, Kentucky, Michigan, Minnesota, Missouri, Nebraska, North Dakota, Ohio, Oklahoma, South Dakota, Tennessee, and Wisconsin.

**PADD 3 (Gulf Coast):** Alabama, Arkansas, Louisiana, Mississippi, New Mexico, and Texas.

**PADD 4 (Rocky Mountain):** Colorado, Idaho, Montana, Utah, and Wyoming.

**PADD 5 (West Coast):** Alaska, Arizona, California, Hawaii, Nevada, Oregon, and Washington.

**PADD 6:** U.S. Virgin Islands and Puerto Rico.

**PADD 7:** Guam, American Samoa and the Northern Mariana Islands Territory.

**Paraffinic hydrocarbons:** Saturated **hydrocarbon** compounds with the general formula  $C_nH_{2n+2}$  containing only single bonds. Sometimes referred to as alkanes or **natural gas liquids**.

**Pentanes plus:** A mixture of liquid **hydrocarbons**, mostly pentanes and heavier, extracted from **natural gas** in a gas processing plant. Pentanes plus is equivalent to **natural gasoline**.

**Petrochemical feedstocks:** Chemical feedstocks derived from refined or partially refined **petroleum** fractions, principally for use in the manufacturing of chemicals, synthetic rubber, and a variety of plastics.

**Petroleum:** A broadly defined class of liquid hydrocarbon mixtures. Included are crude oil, lease condensate, unfinished oils, refined products obtained from the processing of crude oil, and natural gas plant liquids. **Note:** Volumes of finished petroleum products include nonhydrocarbon compounds, such as additives and detergents, after they have been blended into the products.

**Petroleum coke:** A residue high in carbon content and low in **hydrogen** that is the final product of thermal decomposition in the condensation process in cracking. This product is reported as marketable coke or catalyst coke. The conversion is 5 barrels (of 42 U.S. gallons each) per short ton. See **Petroleum coke, Catalyst** and **Petroleum coke, marketable**.

**Petroleum coke, catalyst:** The carbonaceous residue that is deposited on the catalyst used in many catalytic operations (e.g., catalytic cracking). Carbon is deposited on the catalyst, thus deactivating the catalyst. The catalyst is reactivated by burning off the carbon producing heat and **carbon dioxide (CO<sub>2</sub>)**. The carbonaceous residue is not recoverable as a product. See **Petroleum coke**.

**Petroleum coke, marketable:** Those grades of coke produced in delayed or fluid cokers that may be recovered as relatively pure carbon. Marketable petroleum coke may be sold as is or further purified by calcining. See **Petroleum coke**.

**Petroleum consumption:** See **Products supplied (petroleum)**.

**Petroleum imports:** Imports of petroleum into the 50 states and the District of Columbia from foreign countries and from Puerto Rico, the Virgin Islands, and other U.S. territories and possessions. Included are imports for the Strategic Petroleum Reserve and withdrawals from bonded warehouses for onshore consumption, offshore bunker use, and military use. Excluded are receipts of foreign petroleum into bonded warehouses and into U.S. territories and U.S. Foreign Trade Zones.

**Petroleum products:** Products obtained from the processing of crude oil (including lease condensate), natural gas, and other hydrocarbon compounds. Petroleum products include unfinished oils, hydrocarbon gas liquids, aviation gasoline, motor gasoline, naphtha-type jet fuel, kerosene-type jet fuel, kerosene, distillate fuel oil, residual fuel oil, petrochemical feedstocks, special naphthas, lubricants, waxes, petroleum coke, asphalt, road oil, still gas, and miscellaneous products.

**Petroleum stocks, primary:** For individual products, quantities that are held at refineries, in pipelines, and at bulk terminals that have a capacity of 50,000 barrels or more, or that are in transit thereto. Stocks held by product retailers and resellers, as well as tertiary stocks held at the point of consumption, are excluded. Stocks of individual products held at gas processing plants are excluded from individual product estimates but are included in other oils estimates and total.

**Pipeline fuel:** Gas consumed in the operation of pipelines, primarily in compressors.

**Plant condensate:** Liquid **hydrocarbons** recovered at inlet separators or scrubbers in **natural gas** processing plants at atmospheric pressure and ambient temperatures. Mostly pentanes and heavier hydrocarbons.

**Primary energy:** **Energy** in the form that it is first accounted for in a statistical energy balance, before any transformation to secondary or tertiary forms of energy. For example, **coal** can be converted to synthetic gas, which can be converted to **electricity**; in this example, coal is primary energy, synthetic gas is secondary energy, and electricity is tertiary energy. See **Primary energy production** and **Primary energy consumption**.

**Primary energy consumption:** Consumption of **primary energy**. The U.S. Energy Information Administration includes the following in U.S. primary energy consumption: coal consumption; coal coke net imports; **petroleum consumption (petroleum products supplied)**; **dry natural gas**—excluding **supplemental gaseous fuels**—consumption; **nuclear electricity net generation** (converted to Btu using the nuclear plants **heat rate**); **conventional hydroelectricity** net generation (converted to Btu using the average heat rate of fossil-fuel fired plants); **geothermal** electricity net generation (converted to Btu using the average annual heat rate of fossil-fueled fired plants ), geothermal heat pump energy and geothermal direct-use energy; **solar thermal** and **photovoltaic** electricity net generation (converted to Btu

using the average annual heat rate of fossil-fueled fired plants), and solar thermal direct-use energy; wind electricity net generation (converted to Btu using the average annual heat rate of fossil-fueled fired plants); **wood and wood-derived fuels** consumption; **biomass waste** consumption; **fuel ethanol** and **biodiesel** consumption; losses and co-products from the production of fuel ethanol and biodiesel; and electricity net imports (converted to Btu using the electricity heat content of 3,412 Btu per kilowatthour). Primary energy consumption includes all non-combustion use of fossil fuels. Primary energy consumption also includes **other energy losses** throughout the energy system. See **Total energy consumption**. Energy sources produced from other energy sources—e.g. Coal coke from coal—are included in primary energy consumption only if their energy content has not already been included as part of the original energy source. As a result, U.S. primary energy consumption does include net imports of coal coke, but it does not include the coal coke produced from domestic coal.

**Primary energy production:** Production of **primary energy**. The U.S. Energy Information Administration includes the following in U.S. primary energy production: **coal** production, **waste coal** supplied, and coal refuse recovery; **crude oil** and **lease condensate** production; **natural gas plant liquids** production; **dry natural gas**—excluding **supplemental gaseous fuels**— production; **nuclear electricity net generation** (converted to **Btu** using the nuclear plants **heat rate**); **conventional hydroelectricity** net generation (converted to Btu using the fossil-fueled plants heat rate); **geothermal** electricity net generation (converted to Btu using the fossil-fueled plants heat rate), and geothermal heat pump energy and geothermal direct use energy; **solar thermal** and **photovoltaic** electricity net generation (converted to Btu using the fossil-fueled plants heat rate), and solar thermal direct use energy; **wind** electricity net generation (converted to Btu using the fossil-fueled plants heat rate); **wood and wood-derived fuels** production; **biomass waste** consumption; and **biofuels** feedstock.

**Prime mover:** The engine, turbine, water wheel, or similar machine that drives an electric generator; or, for reporting purposes, a device that converts energy to electricity directly.

**Product supplied (petroleum):** Approximately represents consumption of petroleum products because it measures the disappearance of these products from primary sources, i.e., refineries, natural gas-processing plants, blending plants, pipelines, and bulk terminals. In general, product supplied of each product in any given period is computed as follows: field production, plus refinery production, plus imports, plus unaccounted-for crude oil (plus net receipts when calculated on a PAD District basis) minus stock change, minus crude oil losses, minus refinery inputs, and minus exports.

**Propane (C<sub>3</sub>H<sub>8</sub>):** A straight-chain saturated (paraffinic) **hydrocarbon** extracted from **natural gas** or **refinery gas** streams, which is gaseous at standard temperature and pressure. It is a colorless gas that boils at a temperature of -44 degrees Fahrenheit. It includes all products designated in ASTM Specification D1835 and Gas Processors Association specifications for commercial (HD-5) propane. See **Paraffinic hydrocarbons**.

**Propylene (C<sub>3</sub>H<sub>6</sub>):** An olefinic **hydrocarbon** recovered from refinery or petrochemical processes, which is gaseous at standard temperature and pressure. Propylene is an important petrochemical feedstock. See **Olefinic hydrocarbons (olefins)**.

**Real dollars:** These are dollars that have been adjusted for inflation.

**Real price:** A price that has been adjusted to remove the effect of changes in the purchasing power of the dollar. Real prices, which are expressed in constant dollars, usually reflect buying power relative to a base year.

**Refiner acquisition cost of crude oil:** The cost of crude oil to the refiner, including transportation and fees. The composite cost is the weighted average of domestic and imported crude oil costs.

**Refinery and blender net inputs:** Raw materials, **unfinished oils**, and blending components processed at refineries, or blended at refineries or petroleum storage terminals to produce finished **petroleum products**. Included are gross inputs of **crude oil**, **natural gas liquids**, other **hydrocarbon** raw materials, **hydrogen**, **oxygenates** (excluding **fuel ethanol**), and renewable fuels (including fuel ethanol). Also included are net inputs of unfinished oils, **motor gasoline blending components**, and **aviation gasoline blending components**. Net inputs are calculated as gross inputs minus gross production. Negative net inputs indicate gross inputs are less than gross production. Examples of negative net inputs include reformulated gasoline blendstock for oxygenate blending (RBOB) produced at refineries for shipment to

blending terminals, and unfinished oils produced and added to inventory in advance of scheduled maintenance of a refinery crude oil distillation unit.

**Refinery and blender net production:** Liquefied refinery gases, and finished **petroleum products** produced at a **refinery** or petroleum storage terminal blending facility. Net production equals gross production minus gross inputs. Negative net production indicates gross production is less than gross inputs for a finished petroleum product. Examples of negative net production include reclassification of one finished product to another finished product, or reclassification of a finished product to **unfinished oils** or blending components.

**Refinery gas:** **Still gas** consumed as refinery fuel.

**Refinery (petroleum):** An installation that manufactures finished petroleum products from crude oil, unfinished oils, natural gas liquids, other hydrocarbons, and alcohol.

**Refuse mine:** A surface site where **coal** is recovered from previously mined coal. It may also be known as a silt bank, culm bank, refuse bank, slurry dam, or dredge operation.

**Refuse recovery:** The recapture of **coal** from a **refuse mine** or the coal recaptured by that process. The resulting product has been cleaned to reduce the concentration of noncombustible materials.

**Renewable diesel fuel:** See **Biomass-based diesel fuel** and **Renewable diesel fuel (other)**.

**Renewable diesel fuel (other):** **Diesel fuel** and diesel fuel blending components produced from renewable sources that are coprocessed with **petroleum** feedstocks and meet requirements of advanced biofuels. **Note:** This category "other" pertains to the petroleum supply data system. See **Biomass-based diesel fuel**.

**Renewable energy:** Energy obtained from sources that are essentially inexhaustible (unlike, for example, the **fossil fuels**, of which there is a finite supply). Renewable sources of energy include **conventional hydroelectric power**, **biomass**, **geothermal**, **solar**, and **wind**.

**Renewable fuels except fuel ethanol:** See **Biomass-based diesel fuel**, **Renewable diesel fuel (other)**, and **Renewable fuels (other)**.

**Renewable fuels (other):** Fuels and fuel blending components, except **biomass-based diesel fuel**, **renewable diesel fuel (other)**, and **fuel ethanol**, produced from renewable biomass. **Note:** This category "other" pertains to the petroleum supply data system.

**Repressuring:** The injection of a pressurized fluid (such as air, gas, or water) into oil and gas reservoir formations to effect greater ultimate recovery.

**Residential sector:** An energy-consuming sector that consists of living quarters for private households. Common uses of energy associated with this sector include space heating, water heating, air conditioning, and lighting, refrigeration, cooking, and running a variety of other appliances. The residential sector excludes institutional living quarters. See **End-use sectors** and **Energy-use sectors**.

**Residual fuel oil:** A general classification for the heavier oils, known as No. 5 and No. 6 fuel oils, that remain after the **distillate fuel oils** and lighter **hydrocarbons** are distilled away in refinery operations. It conforms to ASTM Specifications D 396 and D 975 and Federal Specification VV-F-815C. No. 5, a residual fuel oil of medium viscosity, is also known as Navy Special and is defined in Military Specification MIL-F-859E, including Amendment 2 (NATO Symbol F-770). It is used in steam-powered vessels in government service and inshore power plants. No. 6 fuel oil includes Bunker C fuel oil and is used for the production of electric power, space heating, vessel bunkering, and various industrial purposes.

**Road oil:** Any heavy petroleum oil, including residual asphaltic oil used as a dust palliative and surface treatment on roads and highways. It is generally produced in six grades, from 0, the most liquid, to 5, the most viscous.

**Rotary rig:** A machine used for drilling wells that employs a rotating tube attached to a bit for boring holes through rock.

**Short ton (coal):** A unit of weight equal to 2,000 pounds.

**SIC (Standard Industrial Classification):** A set of codes developed by the U.S. Office of Management and Budget which categorizes industries into groups with similar economic activities. Replaced by **NAICS (North American Industry Classification System)**.

**Small-scale:** Generators at a site that has a total generating nameplate capacity of less than 1 megawatt (MW).

**Solar energy:** See **Solar photovoltaic (PV) energy** and **Solar thermal energy**.

**Solar photovoltaic (PV) energy:** **Energy**, radiated by the sun that is converted into direct-current electricity by solar photovoltaic cells. Examples of solar PV technologies include solar panels on residential and commercial rooftops (generally small-scale solar PV energy) and mirrors or dishes that concentrate solar rays onto solar PV panels (concentrating PV or CPV). Utility-scale solar PV electric generation typically relies on installations of solar PV panels on or near the ground (solar farms).

**Solar thermal energy:** Energy, radiated by the sun that is converted into electricity or heat by means of solar concentrating collectors. Examples of solar thermal energy technologies include pool heaters, dark water bladders, or thermal panels (generally small-scale solar thermal energy). Utility-scale solar thermal electric generation typically relies on a large array of mirrors to heat fluids and turn a turbine, which generates electricity.

**Special naphthas:** All finished products within the naphtha boiling range that are used as paint thinners, cleaners, or solvents. These products are refined to a specified flash point. Special naphthas include all commercial hexane and cleaning solvents conforming to ASTM Specification D1836 and D484, respectively. Naphthas to be blended or marketed as motor gasoline or aviation gasoline, or that are to be used as petrochemical and synthetic natural gas (SNG) feedstocks are excluded.

**Station use:** Energy that is used to operate an **electric power plant**. It includes energy consumed for plant lighting, power, and auxiliary facilities, regardless of whether the energy is produced at the plant or comes from another source.

**Steam coal:** All nonmetallurgical coal.

**Steam-electric power plant:** A plant in which the prime mover is a steam turbine. The steam used to drive the turbine is produced in a boiler where fossil fuels are burned.

**Still gas:** Any form or mixture of gases produced in refineries by distillation, cracking, reforming, and other processes. The principal constituents are **methane** and **ethane**. May contain **hydrogen** and small/trace amounts of other gases. Still gas is typically consumed as refinery fuel or used as petrochemical feedstock. Still gas burned for refinery fuel may differ in composition from marketed still gas sold to other users. See **Refinery gas**.

**Stocks:** See **Coal stocks**, **Crude oil stocks**, or **Petroleum stocks, primary**.

**Strategic Petroleum Reserve (SPR):** Petroleum stocks maintained by the federal Government for use during periods of major supply interruption.

**Subbituminous coal:** A **coal** whose properties range from those of **lignite** to those of **bituminous coal** and used primarily as fuel for steam-electric power generation. It may be dull, dark brown to black, soft and crumbly, at the lower end of the range, to bright, jet black, hard, and relatively strong, at the upper end. Subbituminous coal contains 20 to 30 percent inherent moisture by weight. The heat content of subbituminous coal ranges from 17 to 24 million **Btu** per **short ton** on a moist, mineral-matter-free basis. The heat content of subbituminous coal consumed in the United States averages 17 to 18 million Btu per ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter).

**Supplemental gaseous fuels:** Synthetic **natural gas**, **propane**-air, coke oven gas, **still gas (refinery gas)**, **biomass** gas, air injected for Btu stabilization, and manufactured gas commingled and distributed with natural gas.

**Synthetic natural gas (SNG):** (Also referred to as substitute natural gas) A manufactured product, chemically similar in most respects to **natural gas**, resulting from the conversion or reforming of **hydrocarbons** that may easily be substituted for or interchanged with pipeline-quality natural gas.

**Thermal conversion factor:** A factor for converting data between physical units of measure (such as **barrels**, **cubic feet**, or **short tons**) and thermal units of measure (such as **British thermal units**, calories, or joules); or for converting data between different thermal units of measure. See **Btu conversion factor**.

**Total energy consumption:** **Primary energy consumption** in the **end-use sectors**, plus **electricity retail sales** and **electrical system energy losses**. Also includes **other energy losses** throughout the energy system.

**Transportation sector:** An energy-consuming sector that consists of all vehicles whose primary purpose is transporting people and/or goods from one physical location to another. Included are automobiles; trucks; buses; motorcycles; trains, subways, and other rail vehicles; aircraft; and ships, barges, and other waterborne vehicles. Vehicles whose primary purpose is not transportation (e.g., construction cranes and bulldozers, farming vehicles, and warehouse tractors and forklifts) are classified in the sector of their primary use. See **End-use sectors** and **Energy-use sectors**.

**Underground storage:** The storage of **natural gas** in underground reservoirs at a different location from which it was produced.

**Unfinished oils:** All oils requiring further processing, except those requiring only mechanical blending. Unfinished oils are produced by partial refining of **crude oil** and include **naphthas** and lighter oils, **kerosene** and light gas oils, heavy gas oils, and residuum.

**Unfractionated streams:** Mixtures of unsegregated **natural gas liquids** components, excluding those in **plant condensate**. This product is extracted from **natural gas**.

**Union of Soviet Socialist Republics (U.S.S.R.):** A political entity that consisted of 15 constituent republics: Armenia, Azerbaijan, Belarus, Estonia, Georgia, Kazakhstan, Kyrgyzstan, Latvia, Lithuania, Moldova, Russia, Tajikistan, Turkmenistan, Ukraine, and Uzbekistan. The U.S.S.R. ceased to exist as of December 31, 1991.

**United States:** The 50 states and the District of Columbia. **Note:** The United States has varying degrees of jurisdiction over a number of territories and other political entities outside the 50 states and the District of Columbia, including Puerto Rico, the U.S. Virgin Islands, Guam, American Samoa, Johnston Atoll, Midway Islands, Wake Island, and the Northern Mariana Islands. EIA data programs may include data from some or all of these areas in U.S. totals. For these programs, data products will contain notes explaining the extent of geographic coverage included under the term "United States."

**Uranium:** A heavy, naturally radioactive, metallic element (atomic number 92). Its two principally occurring isotopes are uranium-235 and uranium-238. Uranium-235 is indispensable to the nuclear industry because it is the only isotope existing in nature, to any appreciable extent, that is fissionable by thermal neutrons. Uranium-238 is also important because it absorbs neutrons to produce a radioactive isotope that subsequently decays to the isotope plutonium-239, which also is fissionable by thermal neutrons.

**Uranium concentrate:** A yellow or brown powder obtained by the milling of uranium ore, processing of in situ leach mining solutions, or as a byproduct of phosphoric acid production. See **Uranium oxide**.

**Uranium ore:** Rock containing uranium mineralization in concentrations that can be mined economically, typically one to four pounds of uranium oxide (U<sub>3</sub>O<sub>8</sub>) per ton or 0.05 percent to 0.2 percent U<sub>3</sub>O<sub>8</sub>.

**Uranium oxide (U<sub>3</sub>O<sub>8</sub>):** **Uranium concentrate** or **yellowcake**.

**Useful thermal output:** The thermal energy made available in a combined-heat-and-power system for use in any industrial or commercial process, heating or cooling application, or delivered to other end users, i.e., total thermal energy made available for processes and applications other than electrical generation.

**U.S.S.R.:** See **Union of Soviet Socialist Republics (U.S.S.R.)**.

**Utility-scale:** Generators at a site that has a total generating nameplate capacity of 1 megawatt (MW) or more.

**Vented natural gas:** **Natural gas** released into the air on the production site or at processing plants.

**Vessel bunkering:** Includes sales for the fueling of commercial or private boats, such as pleasure craft, fishing boats, tugboats, and ocean-going vessels, including vessels operated by oil companies. Excluded are volumes sold to the U.S. Armed Forces.

**Waste:** See **Biomass waste** and **Non-biomass waste**.

**Waste coal:** Usable material that is a byproduct of previous **coal** processing operations. Waste coal is usually composed of mixed coal, soil, and rock (mine waste). Most waste coal is burned as-is in unconventional fluidized-bed combustors. For some uses, waste coal may be partially cleaned by removing some extraneous noncombustible constituents. Examples of waste coal include fine coal, coal obtained from a refuse bank or slurry dam, anthracite culm, bituminous gob, and lignite waste.

**Watt (W):** The unit of electrical power equal to one ampere under a pressure of one volt. A watt is equal to 1/746 horsepower.

**Watthour (Wh):** The electrical energy unit of measure equal to one watt of power supplied to, or taken from, an electric circuit steadily for one hour.

**Wax:** A solid or semi-solid material consisting of a mixture of **hydrocarbons** obtained or derived from **petroleum** fractions, or through a Fischer-Tropsch type process, in which the straight-chained paraffin series predominates. This includes all marketable wax, whether crude or refined, with a congealing point (ASTM D 938) between 100 and 200 degrees Fahrenheit and a maximum oil content (ASTM D 3235) of 50 weight percent.

**Wellhead price:** The value of **crude oil** or **natural gas** at the mouth of the well.

**Wind energy:** Kinetic energy present in wind motion that can be converted to mechanical energy for driving pumps, mills, and electric power generators.

**Wood and wood-derived fuels:** Wood and products derived from wood that are used as fuel, including round wood (cord wood), limb wood, wood chips, bark, sawdust, forest residues, charcoal, paper pellets, railroad ties, utility poles, **black liquor**, red liquor, sludge wood, spent sulfite liquor, **densified biomass** (including wood pellets), and other wood-based solids and liquids.

**Working gas:** The quantity of **natural gas** in the reservoir that is in addition to the cushion or **base gas**. It may or may not be completely withdrawn during any particular withdrawal season. Conditions permitting, the total working capacity could be used more than once during any season. Volumes of working gas are reported in thousand cubic feet at standard temperature and pressure.

THIS PAGE INTENTIONALLY LEFT BLANK